

# **Electricity Industry Participation Code**

## **2010**

---

### **Contents**

#### **Part 1**

Preliminary provisions

#### **Part 2**

Availability of Code information

#### **Part 3**

Market operation service providers

#### **Part 4**

Force majeure provisions relating to ancillary service agents

#### **Part 5**

Regime for dealing with undesirable trading situations

#### **Part 6**

Connection of distributed generation

#### **Part 7**

System operator

**Part 8**  
Common quality

**Part 9**  
Security of supply

**Part 10**  
Metering

**Part 11**  
Registry information management

**Part 12**  
Transport

**Part 12A**  
Distributor use-of-system agreements and distributor tariffs

**Part 13**  
Trading arrangements

**Part 14**  
Clearing and settlement

**Part 14A**  
Prudential requirements

**Part 15**  
Reconciliation

**Part 16**  
Special provisions relating to Rio Tinto agreements [*Revoked*]

**Part 16A**  
Audits

**Part 17**  
Transitional provisions

---

**Code**

**1 Title**

This Code is the Electricity Industry Participation Code 2010.

**2 Commencement**

In accordance with section 36(1) of the Act, this Code comes into force on  
1 November 2010.

# Electricity Industry Participation Code 2010

## Part 1 Preliminary provisions

### Contents

- 1.1 Interpretation
- 1.2 General principles of construction
- 1.3 Special definition of “related”
- 1.4 Special definition of “independent”
- 1.5 Special definition of “purchaser” and “participant”
- 1.5A Application of Code to distributors
- 1.6 Contents tables
- 1.7 Defined terms appear in bold

#### Schedule 1.1

**Notice of assumption of rights and obligations under Parts 8, 13, 14, and 14A of the Electricity Industry Participation Code 2010**

#### Schedule 1.2

**Revocation of notice of assumption of rights and obligations under Parts 8, 13, 14, and 14A of the Electricity Industry Participation Code 2010**

---

### 1.1 Interpretation

- (1) In this Code, unless the context otherwise requires,—

**Act** means the Electricity Industry Act 2010

**active energy** means the integration over time of the product of voltage, current and the cosine of the phase angle between them, and which is normally measured in kilowatt hours (kWh)

**active meter** means a **meter** used for the measurement of **active energy**

**active power** means the product of voltage, current and the cosine of the phase angle between them, and which is normally measured in kilowatts (kW)

**additional customer compensation scheme** means a scheme operated by a **retailer** under clause 9.26, in addition to the **retailer’s default customer compensation scheme**  
Clause 1.1(1) **additional customer compensation scheme**: inserted, on 1 April 2011, by clause 4(1) of the Electricity Industry Participation (Customer Compensation Schemes) Code Amendment 2011.

**adjustment** means, for the purposes of the definitions of **error compensation**, **loss compensation**, and Part 10, an operation or process intended to reduce the differences between the values indicated by an instrument and the values realised by a **reference standard** or **working standard** to within a predetermined tolerance, and **adjust** and **adjusted** have corresponding meanings

Clause 1.1(1) **adjustment**: amended, on 29 August 2013, by clause 4(1) of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2013.

**adjustment clause** means a clause in a **contract for differences** or a **fixed-price physical supply contract** under which the price or prices of a specified volume of **electricity** may be adjusted, including an adjustment relating to the Consumer Price Index, the Producers Price Index or any other index

**administrative cost** means, in relation to an **ancillary service**, the significant costs that are incurred by the **system operator** in relation to the development of **ancillary service** provision, that are specifically attributable to an **ancillary service**, and that have been agreed to by the **Authority** and the **system operator**

**allocable cost** has the meaning set out in clauses 8.55 to 8.58

**alternative ancillary service arrangement** means an arrangement between a **participant** and another **participant** or other person, or an arrangement involving only a **participant**, which is authorised by the **system operator** in accordance with clause 8.48

**ancillary service** means **black start, over frequency reserve, frequency keeping, instantaneous reserve or voltage support**

**ancillary service agent** means a person who provides an **ancillary service**

**ancillary service arrangement** means a contract between the **system operator** and an **ancillary service agent** for the procurement of **ancillary services** in accordance with clause 8.45

**annual consumption list** means the list **published** by the **reconciliation manager** in accordance with clause 13.188

Clause 1.1(1) **annual consumption list**: amended, on 5 October 2017, by clause 4(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

**applications layer** means a part of a **metering installation** used for a function that is not performed by the **metrology layer**

Clause 1.1(1) **applications layer**: inserted, on 29 August 2013, by clause 4(1) of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011.

**approved calibration laboratory** means the Measurement Standards Laboratory of New Zealand, or a calibration laboratory that has been accredited under the Testing Laboratory Registration Act 1972 to ISO 17025, or an international laboratory that has been recognised by the Chief Metrologist for the specific **calibration** required

**approved investment** means—

- (a) an investment approved by the Electricity Commission under section III of part F of the **rules** before this Code came into force; or
- (b) an investment approved by the Commerce Commission under section 54R of the Commerce Act 1986; or
- (c) an investment that is permitted under an input methodology determined by the Commerce Commission under section 54S of the Commerce Act 1986

**approved system** means the system or systems required to convey information between persons in accordance with this Code, as may be approved from time to time by the **Authority**

Clause 1.1(1) **approved system**: inserted, on 5 October 2017, by clause 4(61) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

**approved test house** means a facility that has been approved by the **Authority** in accordance with Part 10 to do one or more of the following:

- (a) **calibrate metering installations or metering components**
- (b) **certify metering installations or metering components**

Clause 1.1(1) **approved test house**: amended, on 29 August 2013, by clause 4(2)(a) of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011.

Clause 1.1(1) **approved test house**: amended, on 19 December 2014, by clause 4(1) of the Electricity Industry Participation Code Amendment (Minor Code Amendments) (No 3) 2014.

Clause 1.1(1) **approved test house**: substituted, on 1 February 2016, by clause 4(1)(a) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

**approved test laboratory** means a test laboratory that has been accredited under the Standards and Accreditation Act 2015 to ISO 17025 for the specific test required

Clause 1.1(1) **approved test laboratory**: amended, on 5 October 2017, by clause 4(3) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

**asset** means equipment or plant that is connected to or forms part of the **grid** and, in the case of Part 8, includes equipment or plant that is intended to become connected to the **grid** and equipment or plant of an **embedded generator**

Clause 1.1(1) **asset**: amended, on 23 February 2015, by clause 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 1.1(1) **asset**: amended, on 5 October 2017, by clause 4(4) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

**asset capability statement** means a statement of capability and operational limitations that applies to specific **assets** during the normal and abnormal conditions that may arise on the **grid**, provided to the **system operator** in accordance with clause 2(5) of **Technical Code A** of Schedule 8.3

**asset owner** means a **participant** who owns an **asset** used for the generation or conveyance of **electricity** and a person who operates such **asset** and, in the case of Part 8, includes a **consumer** with a **point of connection** to the **grid**

**asset owner performance obligations** and **AOPO** means a performance obligation specified in subpart 2 of Part 8 that an **asset owner** must comply with so that the **system operator** can plan to comply and comply with its **principal performance obligations**

**associated equipment**, for the purposes of the definition of **distribution network** and Part 6, means any equipment that is used, or designed or intended for use, in relation to any works or **consumer installation**, if such use is for **construction**, maintenance, or safety purposes and not for purposes that relate directly to the generation, conversion, transformation, conveyance, or use of **electricity**

Clause 1.1(1) **associated equipment**: amended, on 23 February 2015, by clause 4(1) of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 1.1(1) **associated equipment**: amended, on 5 October 2017, by clause 4(5) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

**assumed co-efficient of variation** [*Revoked*]

Clause 1.1(1) **assumed co-efficient of variation**: revoked, on 5 October 2017, by clause 4(60) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

**at risk HVDC transfer** means the quantity of **MWh** for each **trading period** calculated in accordance with Tables 1 and 2, where—

$INJ_{HVDCHAYt}$  is the **electricity** injected from the **HVDC link** into the North Island **grid assets** at the North Island **HVDC injection point** in **trading period t**; and

$INJ_{HVDCBENt}$  is the **electricity** injected from the **HVDC link** into the South Island **grid assets** at the South Island **HVDC injection point** in **trading period t**; and

$INJ_{Pole2HAYt}$  is the **electricity** injected from Pole 2 of the **HVDC link** into the North Island **grid assets** at the North Island **HVDC injection point** in **trading period t**

**Table 1:** HVDC northward transfer – if **electricity** is injected at the North Island **HVDC injection point** in the relevant **trading period**

HVDC configuration at the beginning of trading period t	At risk HVDC transfer north in trading period t (expressed in MWh)
Pole 1 one half pole only	$INJ_{HVDCHAYt}$
Pole 2 only	$INJ_{HVDCHAYt}$
Pole 3 only	$INJ_{HVDCHAYt}$
Pole 2 and Pole 1 one half pole	$INJ_{Pole2HAYt}$
Pole 3 and Pole 2 bipole <b>round power</b>	$INJ_{HVDCHAYt}$
Pole 3 and Pole 2 bipole not <b>round power</b>	$\max(0, INJ_{HVDCHAYt} - 263)$

**Table 2:** HVDC southward transfer – if **electricity** is injected at the South Island **HVDC injection point** in the relevant **trading period**

HVDC configuration at the beginning of trading period t	At risk HVDC transfer south in trading period t (expressed in MWh)
Pole 2 only	$INJ_{HVDCBENt}$
Pole 3 only	$INJ_{HVDCBENt}$
Pole 3 and Pole 2 bipole <b>round power</b>	$INJ_{HVDCBENt}$
Pole 3 and Pole 2 bipole not <b>round power</b>	$\max(0, INJ_{HVDCBENt} - 263)$

Clause 1.1(1) **at risk HVDC transfer**: substituted, on 1 July 2012, by clause 4(1) of the Electricity Industry Participation (HVDC Pole 3 Minor Amendments) Code Amendment 2012.

**ATH** means a person who is approved under Schedule 10.3 to operate an **approved test house**

Clause 1.1(1) **ATH**: inserted, on 29 August 2013, by clause 4(1) of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011.

**auction** means a must-run dispatch auction conducted by the **clearing manager** under subpart 3 of Part 13

**auction bid** means a bid made for an **auction** under clauses 13.117 to 13.130

**auction revenue** means, for a **generator**, the amount owing by the **generator** in accordance with clause 13.112(2) and, for a **purchaser**, the amount owing to the **purchaser** in accordance with clause 13.111

Clause 1.1(1) **auction revenue**: amended, on 24 March 2015, by clause 4(1)(a) of the Electricity Industry Participation (Settlement and Prudential Security) Code Amendment 2013.

**auction right** means the right (but not the obligation) to offer for sale a specified quantity of **electricity** to the **clearing manager** at 0 price in accordance with clause 13.116(1)

**audit** means a process of inspection of the facilities, processes, procedures, and other relevant items, to confirm compliance with this Code, and **audited** has a corresponding meaning

**auditor** means,—

- (a) for the purposes of Parts 10, 11, 15 and 16A, a person—
  - (i) approved or appointed by the **Authority** to carry out an **audit**; or
  - (ii) the **Authority**, if the **Authority** carries out an **audit** itself; and
- (b) for all other Parts of this Code, a person carrying out an **audit**

Clause 1.1(1) **auditor**: replaced, on 1 June 2017, by clause 4(1) of the Electricity Industry Participation Code Amendment (Requirements and Processes for Audits) 2016.

**Authority** has the meaning given to it by section 5 of the **Act**

**automatic control plant** means any hydro **generating plant** that has a pre-programmed generation profile and an automatic override if uncontrollable water inflows change

**automatic under-frequency load shedding** means a form of **extended reserve** in which electrical load is automatically shed when frequency falls below a preset frequency, or falls at a rate, specified by the **system operator** in the relevant **extended reserve provider's statement of extended reserve obligations**

Clause 1.1(1) **automatic under-frequency load shedding**: amended, on 7 August 2014, by clause 4(1) of the Electricity Industry Participation Code Amendment (Extended Reserve) 2014.

**availability cost** means a cost (other than an **administrative cost**), incurred by the **system operator** in purchasing **instantaneous reserve** and providing that **instantaneous reserve** for a **trading period**, and includes—

- (a) payments made by the **system operator** for that **trading period** under contracts that secure the availability of **instantaneous reserves**; and
- (b) the annual and variable costs (including any constrained-on costs) incurred by the **system operator** under any other contracts allocated by the **system operator** to that **trading period**; less
- (c) the costs of **instantaneous reserves** procured as a direct result of a **generator** being granted a **dispensation** under clause 8.31(1); and
- (d) **instantaneous reserve constrained on compensation** calculated in accordance with clause 13.212(6)

**back office** means a part of an **interrogation** system—

- (a) that sends or receives information to or from a **metering installation**; and
- (b) stores the information in a form that can be made available at the **services access interface** to another person



Clause 1.1(1) **back office**: inserted, on 29 August 2013, by clause 4(1) of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011.

**back-up metering information** means **half-hour metering information** from any alternative **metering installation** that measures the same flow of **electricity** at the relevant **grid exit points** and **grid injection points** as would have been given under clause 13.166(1)(b)

**back up protection system** means a protection system—

- (a) that **electrically disconnects** faulted **assets** from the **grid** because a **main protection system** or a **circuit breaker** has failed to **electrically disconnect** a faulted **asset** from the **grid** in the allocated time; and
- (b) that may **electrically disconnect** non-faulted **assets** as well as a faulted **asset**

Clause 1.1(1) **back up protection system**: amended, on 5 October 2017, by clause 4(6)(a) and (b) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

**balancing area** means, in relation to any particular **ICP**,—

- (a) the **embedded network**; or
- (b) that part of the relevant **local network** owned by 1 **network owner**—  
having 1 or more **NSPs**, to which that **ICP** is **electrically connected** from time to time under normal circumstances

Clause 1.1(1) **balancing area**: amended, on 23 February 2015, by clause 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 1.1(1) **balancing area**: amended, on 5 October 2017, by clause 4(7) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

**bank** means a registered bank within the meaning of the Reserve Bank of New Zealand Act 1989 that is carrying on in New Zealand the business of banking

**bank bill bid rate** means the rate per annum (rounded upwards to 2 decimal places) displayed at or about 10.45am on the Reuters Screen on page BKBM (or its successor or equivalent page) on the relevant date as the bank bill “settlement” bid rate for bank bills having a tenor of 1 month, provided that if such a rate is not available, **bank bill bid rate** means the rate determined by the **clearing manager** to be the nearest practicable equivalent

**base case** means a base case **published** by the **Authority** under clause 13.236D

Clause 1.1(1) **base case**: inserted, on 1 December 2011, by clause 4 of the Electricity Industry Participation Code (Spot Price Risk Disclosure) Amendment 2011.

Clause 1.1(1) **base case**: amended, on 5 October 2017, by clause 4(8) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

**benchmark agreement** means the agreement for the connection to and/or use of the **grid**, that is incorporated by reference in this Code under clause 12.34

Clause 1.1(1) **benchmark agreement**: amended, on 23 February 2015, by clause 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 1.1(1) **benchmark agreement**: amended, on 5 October 2017, by clause 4(9) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

**benefit to the public** means public benefit net of any costs and detriments, including those detriments associated with a lessening of competition as those concepts are applied under the Commerce Act 1986

**bid**,—

- (a) means—

- (i) a **nominated bid**;
- (ii) a **difference bid**; and
- (b) includes a **bid** revised in accordance with clause 13.19A or 13.19B

(c) *[Revoked]*

Clause 1.1(1) **bid**: substituted, on 28 June 2012, by clause 4(b) of the Electricity Industry Participation (Demand-side Bidding and Forecasting) Code Amendment 2011.

Clause 1.1(1) **bid** paragraph (b): amended, on 29 June 2017, by clause 4(1)(a) of the Electricity Industry Participation Code Amendment (Shortened Gate Closure and Revised Bid and Offer Provisions) 2017.

Clause 1.1(1) **bid** paragraph (c): revoked, on 29 June 2017, by clause 4(1)(b) of the Electricity Industry Participation Code Amendment (Shortened Gate Closure and Revised Bid and Offer Provisions) 2017.

**binding constraint** means a **constraint** that is likely to cause a significant difference between the price at 1 **node** and the price at another **node**

**billing period** means a period of 1 calendar month

**black start** means an **ancillary service** required to enable a **generating unit** isolated from the **grid** to be—

- (a) made live, as defined in the Electricity (Safety) Regulations 2010; and
- (b) **electrically connected to the grid**

Clause 1.1(1) **black start**: amended, on 23 February 2015, by clause 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 1.1(1) **black start**: replaced, on 5 October 2017, by clause 4(1)(a) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

**block dispatch group** means a group of **generating stations** on 1 continuous water course, which is the subject of an agreement between the **system operator** and a **generator** under clause 13.60

**block security constraint** means any of the following:

- (a) a constraint applied by the **system operator** to a **generating unit** or **generating station** to provide **voltage support** or **frequency keeping** as determined in accordance with Part 8
- (b) a limitation in the offered capacity of a **grid owner's network** to convey **electricity** between **generating stations** constituting a **block dispatch group**
- (c) a limitation in the offered capacity of a **grid owner's network** to convey **electricity** between **generating stations** constituting a **block dispatch group** and a **grid owner's network**—

and, in paragraphs (b) and (c), such a limitation in the offered capacity being the offered capacity of a **grid owner's network** or a **grid system security constraint** as determined by the **system operator** in accordance with Part 8

**bona fide physical reason** includes,—

- (a) in relation to a **generator**, or a **purchaser**, or an **ancillary service agent** or a **grid owner**, a situation where personnel or plant safety is at risk; and
- (b) in relation to a **generator** or an **ancillary service agent** providing **partly loaded spinning reserve**, **tail water depressed reserve** or **frequency keeping**,—
  - (i) a reasonably unforeseeable change in generating capability, reserve capability, or **frequency keeping** capability (as the case may be) from an item of **generating plant** that is the subject of an existing **offer**, **reserve**

- offer**, or offer to provide **frequency keeping** by that **generator** or **ancillary service agent**; or
- (ii) a reasonably unforeseeable change in the level of expected uncontrollable water inflows into the head pond of a hydro station that is the subject of an existing **offer**, **reserve offer**, or offer to provide **frequency keeping** by that **generator** or **ancillary service agent**; or
  - (iii) a reasonably unforeseeable change in circumstances such that the **generator** or **ancillary service agent** will breach any consent held by it under the Resource Management Act 1991; or
  - (iv) a reasonably unforeseeable physical infeasibility that arises from a **price-responsive schedule**, a **non-response schedule**, or a **dispatch schedule**; and
- (c) in relation to a **purchaser**, or an **ancillary service agent** providing **interruptible load**,—
- (i) a reasonably unforeseeable full or partial loss of demand or reserve capability (as the case may be) at a **grid exit point** that is the subject of an existing **bid** or **reserve offer** by the **purchaser** or the **ancillary service agent**; or
  - (ii) a reasonably unforeseeable change in circumstances such that the **purchaser** or **ancillary service agent** will breach any consent held by it under the Resource Management Act 1991; or
  - (iii) a reasonably unforeseeable full or partial loss of generating capability from an item of **generating plant** owned by, or the subject of a supply contract with, that **purchaser** during the relevant **trading periods**; and
- (d) in relation to a **grid owner**, a reasonably unforeseeable loss of full or partial capacity on transmission plant forming part of the **grid**

Clause 1.1(1) **bona fide physical reason** paragraph(b)(iv): substituted, on 28 June 2012, by clause 4(c)(i) of the Electricity Industry Participation (Demand-side Bidding and Forecasting) Code Amendment 2011.

Clause 1.1(1) **bona fide physical reason** paragraph(c)and(c)(i): amended, on 28 June 2012, by clause 4(c)(ii)and(iii) of the Electricity Industry Participation (Demand-side Bidding and Forecasting) Code Amendment 2011.

**bound**, in relation to a **transmission security constraint**, means that the flow of **electricity** through 1 or more transmission **lines** or transformers is equal to or greater than the **transmission security constraint** applied to those transmission **lines** or transformers, and **bind** has a corresponding meaning

Clause 1.1(1) **bound**: amended, on 1 February 2016, by clause 4(3) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

**branch** means an electrical link between—

- (a) 2 or more **nodes**; or
- (b) a **node** and a **point of connection to the grid**

**business** means the business carried out as a **participant**

**business day** means,—

- (a) for the purposes of Part 6, any day of the week other than Saturday, Sunday, or a public holiday within the meaning of the Holidays Act 2003; and
- (b) for the rest of the Code, any day of the week except Saturdays, Sundays, **national**

**holidays** and any other day from time to time declared by the **Authority** not to be a **business day** by notice to each **registered participant**

Clause 1.1(1) **business day**: amended, on 21 September 2012, by clause 4(1) of the Electricity Industry Participation (Minor Amendments) Code Amendment 2012.

Clause 1.1(1) **business day**: amended, on 5 October 2017, by clause 4(10) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

**buyer**, for the purposes of subpart 5 of Part 13, means—

- (a) in respect of a **contract for differences**, the fixed-price payer, being the **party** obliged to make payments at a fixed price from time to time during the **term** of the contract; or
- (b) in respect of a **fixed-price physical supply contract**, the purchaser of **electricity**; or
- (c) in respect of an **options contract**, either—
  - (i) the **party** paying the **premium**; or
  - (ii) if there is no **premium**, the **party** who agrees to be the **buyer** for the purposes of subpart 5 of Part 13; or
  - (iii) if neither **party** agrees to be the **buyer**, the **party** whose name is the first alphabetically

**calibration** means the set of operations that establishes, under specified conditions, the relationship between the values indicated by the measuring system and the corresponding values of a quantity realised by a **reference standard** or **working standard**, and **calibrate** and **calibrated** have corresponding meanings

**calibration report** means a report that contains the results of all **calibration** tests carried out on—

- (a) a **metering installation**; or
- (b) a **metering component** in a **metering installation**; or
- (c) a **working standard**

Clause 1.1(1) **calibration report**: substituted, on 29 August 2013, by clause 4(2)(b) of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011.

**call** [*Revoked*]

Clause 1.1(1) **call**: revoked, on 24 March 2015, by clause 4(1)(b) of the Electricity Industry Participation (Settlement and Prudential Security) Code Amendment 2013.

**capacity** [*Revoked*]

Clause 1.1(1) **capacity**: revoked, on 23 February 2015, by clause 4(11) of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

**capacity reserve** means—

- (a) demand that can be decreased for the purpose of adjusting a **constraint**; or
- (b) generation that can be increased or decreased for the purpose of adjusting a **constraint**

**cash deposit** means the cash deposited in **cleared funds** by a **participant** in accordance with clause 2 of Schedule 14A.1, and includes any interest under clause 14A.14 that has not been paid out

Clause 1.1(1) **cash deposit**: amended, on 24 March 2015, by clause 4(1)(c) of the Electricity Industry Participation (Settlement and Prudential Security) Code Amendment 2013.

**cash deposit accounts** means the trust accounts established by the **clearing manager** in accordance with clause 14A.11

Clause 1.1(1) **cash deposit accounts**: amended, on 24 March 2015, by clause 4(1)(d) of the Electricity Industry Participation (Settlement and Prudential Security) Code Amendment 2013.

**cash interest rate** *[Revoked]*

Clause 1.1(1) **cash interest rate**: revoked, on 24 March 2015, by clause 4(1)(e) of the Electricity Industry Participation (Settlement and Prudential Security) Code Amendment 2013.

**category 1 metering installation** means a **metering installation** that has the required defining characteristics for a **metering installation** of that category in Table 1 of Schedule 10.1

Clause 1.1(1) **category 1 metering installation**: inserted, on 1 December 2011, by clause 4(a) of the Electricity Industry Participation Code (Distributor Use-of-System Agreements and Distributor Tariffs) Amendment 2011.

Clause 1.1(1) **category 1 metering installation**: substituted, on 29 August 2013, by clause 4(2)(c) of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011.

**category 2 metering installation** means a **metering installation** that has the required defining characteristics for a **metering installation** of that category in Table 1 of Schedule 10.1

Clause 1.1(1) **category 2 metering installation**: inserted, on 1 December 2011, by clause 4(a) of the Electricity Industry Participation Code (Distributor Use-of-System Agreements and Distributor Tariffs) Amendment 2011.

Clause 1.1(1) **category 2 metering installation**: substituted, on 29 August 2013, by clause 4(2)(d) of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011.

**causer**, in relation to an **under-frequency event**, means—

- (a) if the **under-frequency event** is caused by an interruption or reduction of **electricity** from a single **generator's** or **grid owner's asset** or **assets**, the **generator** or **grid owner**; unless—
  - (i) the **under-frequency event** is caused by an interruption or reduction of **electricity** from a single **generator's asset** or **assets** but another **generator's** or a **grid owner's act** or omission or property causes the interruption or reduction of **electricity**, in which case the other **generator** or the **grid owner** is the **causer**; or
  - (ii) the **under-frequency event** is caused by an interruption or reduction of **electricity** from a single **grid owner's asset** or **assets** but a **generator's** or another **grid owner's act** or omission or property causes the interruption or reduction of **electricity**, in which case the **generator** or other **grid owner** is the **causer**; or
- (b) if the **under-frequency event** is caused by more than 1 interruption or reduction of **electricity**, the **generator** or **grid owner** who, in accordance with paragraph (a), would be the **causer** of the **under-frequency event** if it had been caused by the first in time of the interruption or reduction of **electricity**; but
- (c) if an interruption or reduction of **electricity** occurs in order to comply with this Code, the interruption or reduction of **electricity** must be disregarded for the purposes of determining the **causer** of the **under-frequency event**

**centralised data set** *[Revoked]*

Clause 1.1(1) **centralised data set**: revoked, on 1 February 2016, by clause 4(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

**certification** means—

- (a) if applied to a **metering installation**, confirmation that the **metering installation** meets the requirements of this Code; and
- (b) if applied to a **metering component**, confirmation that the **metering component** meets the requirements of this Code; and
- (c) if applied to a **reconciliation participant**, confirmation that that **reconciliation participant** has met the requirements of Schedule 15.1

Clause 1.1(1) **certification**: amended, on 29 August 2013, by clause 4(2)(e) of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011.

**certification report** means a report that contains—

- (a) the **calibration report** or **calibration reports**;
- (b) all other information relevant to the **certification** of a **metering installation** or a **metering component** required under Part 10

Clause 1.1(1) **certification report**: substituted, on 29 August 2013, by clause 4(2)(f) of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011.

**certification sticker** means a sticker that is valid for a specific period and that is attached—

- (a) to a **metering installation**, confirming that the **metering installation** has been **certified** by an **ATH** under Schedule 10.7; or
- (b) to a **metering component**, confirming that the **metering component** has been **certified** by an **ATH** under Schedule 10.8

Clause 1.1(1) **certification sticker**: substituted, on 29 August 2013, by clause 4(2)(g) of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011.

**certified** means having achieved **certification**

**certify** means to carry out a **certification**

**chargeable capacity** means the capacity that the **distributor** may charge for, but that may not be the actual installed capacity at the relevant **ICP**

**check metering information** means **half-hour metering information** from a **meter**, located at the **grid exit point** or **grid injection point** that gives equivalent information, but not necessarily of the same accuracy, as the relevant **grid exit point** or **grid injection point meter**

**circuit branch** means a **branch** that is not a **transformer branch** or the **HVDC link**

**circuit breaker** means a switching device capable of making, carrying and breaking currents under normal circuit conditions, and capable of making, carrying for a specified time and breaking currents under specified abnormal conditions (such as a short circuit)

**circuit breaker failure protection system** means a protection system that—

- (a) operates because a **circuit breaker** has failed to **electrically disconnect** a faulted **asset** from the **grid** in the allocated time; and
- (b) may **electrically disconnect** non-faulted **assets** from the **grid** as well as a faulted **asset**

Clause 1.1(1) **circuit breaker failure protection system**: amended, on 5 October 2017, by clause 4(11) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

**class A approved test house** [*Revoked*]

Clause 1.1(1) **class A approved test house**: revoked, on 29 August 2013, by clause 4(3) of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011.

**class A ATH** means an **ATH** who is approved under clause 3 of Schedule 10.3

Clause 1.1(1) **class A ATH**: inserted, on 29 August 2013, by clause 4(1) of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011.

**class B approved test house** *[Revoked]*

Clause 1.1(1) **class B approved test house**: revoked, on 29 August 2013, by clause 4(3) of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011.

**class B ATH** means an **ATH** who is approved under clause 4 of Schedule 10.3

Clause 1.1(1) **class B ATH**: inserted, on 29 August 2013, by clause 4(1) of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011.

**cleared funds**, in relation to a **business day**, means funds that are immediately available for disbursement on that day

**clearing auction price** means the lowest successful price bid at an **auction** in dollars per **MW** per **half hour**

**clearing manager** has the meaning given to it in section 5 of the **Act**

**Code information** means all information that is supplied by 1 **participant** to another **participant**, or group of **participants**, under this Code (other than **excluded Code information** and information that is supplied under Parts 2 to 6 and 9 of this Code)

Clause 1.1(1) **Code information**: amended, on 16 December 2013, by clause 4(1) of the Electricity Industry Participation (Revocation of Part 16) Code Amendment 2013.

**code of practice** means a code of practice issued under this Code

Clause 1.1(1) **code of practice**: amended, on 29 August 2013, by clause 4(2)(h) of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011.

**co-efficient of variation** means the ratio of the standard deviation to the mean of the distribution for the random variable under consideration

**co-generator** *[Revoked]*

Clause 1.1(1) **co-generator**: revoked, on 27 May 2015, by clause 4(1) of the Electricity Industry Participation Code Amendment (Industrial Co-generation Dispatch Arrangements) 2015.

**commissioning** means to verify the correct operation of—

- (a) an **asset**; or
- (b) a **point of connection**; or
- (c) metering equipment installed in a **metering installation**,—

and **commissioned** has a corresponding meaning

Clause 1.1(1) **commissioning**: amended, on 29 August 2013, by clause 4(2) of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2013.

Clause 1.1(1) **commissioning**: replaced, on 5 October 2017, by clause 4(1)(b) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

**commissioning report** *[Revoked]*

Clause 1.1(1) **commissioning report**: revoked, on 29 August 2013, by clause 4(3) of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011.

**committed projects** means transmission augmentation projects and **non-transmission projects** that are reasonably likely to proceed in a similar timeframe for which the assessment of costs and benefits under a net benefits test set out in Part 12 is undertaken, and in relation to which either—

- (a) all of the following are satisfied:
  - (i) the proponent has obtained all required planning consents, construction approvals, and licences, and fulfilled any other regulatory requirement that must be met before commencing construction:
  - (ii) construction has commenced or a firm commencement date for construction has been set:
  - (iii) the proponent has acquired or executed an agreement to acquire land (or commenced legal proceedings to acquire land), or has executed an agreement for the leasing of land, for the purposes of construction:
  - (iv) contracts for supply and construction of the major components of the plant and equipment (including any **generating units**, turbines, boilers, transmission towers, conductors, termination station equipment) have been executed (i.e. all the necessary formal legal requirements have been observed to make the contract valid and complete):
  - (v) contracts for the financing of the project, including any debt plans, have been executed (i.e. all the necessary formal legal requirements have been observed to make the contract valid and complete); or
- (b) in the case of transmission augmentation projects, the project is an **approved investment**

**common quality** means those elements of quality of **electricity** conveyed across the **grid** that cannot be technically or commercially isolated to an identifiable person or group of persons

**communication** means, for the purposes of Part 10, the electronic transfer of information, or instructions, to or from a **metering installation**

Clause 1.1(1) **communication**: inserted, on 29 August 2013, by clause 4(1) of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011.

**communication equipment** means a device, used for **communication**, in—

- (a) a **metering installation**; or
- (b) a **back office**

Clause 1.1(1) **communication equipment**: inserted, on 29 August 2013, by clause 4(1) of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011.

**comparative recertification** means **recertification** of a **category 2 metering installation** under clause 12(3) of Schedule 10.7

Clause 1.1(1) **comparative recertification**: inserted, on 29 August 2013, by clause 4(1) of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011.

**compensation factor** means 1 of the following factors used to compensate for errors, losses, or ratios within a **metering installation**, to produce accurate **volume information**:

- (a) **error compensation**:
- (b) **loss compensation**:
- (c) **ratio compensation**

Clause 1.1(1) **compensation factor**: inserted, on 29 August 2013, by clause 4(1) of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011.

**complete** [*Revoked*]



Clause 1.1(1) **complete**: revoked, on 16 December 2013, by clause 4(2)(a) of the Electricity Industry Participation (Revocation of Part 16) Code Amendment 2013.

**confidential information**, for the purposes of Schedule 6.2, means all data and other information of a confidential nature provided by 1 party (A) to another party (B) under the **regulated terms**, but excludes—

- (a) information known to B before the date it was provided by B to A and that was not obtained directly or indirectly from A; and
- (b) information obtained bona fide from another person who is in lawful possession of the information and who did not acquire the information directly or indirectly from A under an obligation of confidence

**configuration**, in relation to the **HVDC link**, means the following modes of operation of the **HVDC link**:

- (a) Pole 1 one half pole only:
- (b) Pole 2 only:
- (c) Pole 3 only:
- (d) Pole 2 and Pole 1 one half pole:
- (e) Pole 3 and Pole 2 bipole **round power**:
- (f) Pole 3 and Pole 2 bipole not **round power**

Clause 1.1 **configuration**: substituted, on 1 July 2012, by clause 4(2) of the Electricity Industry Participation (HVDC Pole 3 Minor Amendments) Code Amendment 2012.

**conforming GXP** means a **GXP** that—

- (a) has been determined by the **Authority** to be a **conforming GXP** under clause 13.27A or 13.27B(4); or
- (b) is deemed to be a **conforming GXP** under clause 13.27F

Clause 1.1(1) **conforming GXP**: inserted, on 28 March 2012, by clause 4(a) of the Electricity Industry Participation (Demand-side Bidding and Forecasting) Code Amendment 2011.

**congestion management policy** means the policies, clauses, or conditions referred to in clause 6.3(2)(d)

**connect***[Revoked]*

Clause 1.1(1) **connect**: amended, on 23 February 2015, by clause 4(2) of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 1.1(1) **connect**: revoked, on 5 October 2017, by clause 4(60) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

**connected asset owner** means a **direct consumer**, or a **distributor** in its capacity as the owner or operator of a **local network**

Clause 1.1(1) **connected asset owner**: inserted, on 1 February 2016, by clause 4(19) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

**connection and operation standards**, in relation to a **distributor** or **distributed generation**,—

- (a) means requirements, as amended from time to time by the **distributor**, that—
  - (i) are set out in written policies and standards of the **distributor**; and
  - (ii) relate to connecting **distributed generation** to a **distribution network** or to a **consumer installation** that is connected to a **distribution network**, and the operation of the **distribution network**, including requirements relating to the planning, design, construction, testing, inspection, and operation of **distributed generation** that is, or is proposed to be, connected; and

- (iii) are made publicly available in accordance with clause 6.3; and
- (iv) reflect, or are consistent with, **reasonable and prudent operating practice**; and
- (b) includes the following, as amended from time to time by the **distributor**:
  - (i) the **distributor's congestion management policy**, as referred to in clause 6.3(2)(d); and
  - (ii) the **distributor's** emergency response policies; and
  - (iii) the **distributor's** safety standards

Clause 1.1(1) **connection and operation standards**: amended, on 23 February 2015, by clause 4(3) of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 1.1(1) **connection and operation standards**: amended, on 23 February 2015, by clause 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 1.1(1) **connection and operation standards**, paragraph (a)(ii): replaced, on 5 October 2017, by clause 4(12) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

**connection asset**, for the purposes of subparts 2, 6 and 7 of Part 12, has the meaning set out in the **transmission pricing methodology**

**Connection Code** means the Connection Code that is incorporated by reference in this Code under clause 12.26

**connection location** means a substation or other location at which **lines**, equipment and plant owned or managed by a **designated transmission customer** that are directly related to a **point of connection**, and that are used for the consumption, conveyance, or generation of **electricity**, are directly connected to the **grid**

Clause 1.1(1) **connection location**: amended, on 23 February 2015, by clause 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 1.1(1) **connection location**: amended, on 1 February 2016, by clause 4(4) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

Clause 1.1(1) **connection location**: amended, on 5 October 2017, by clause 4(13) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

**constrained off amounts** means the amounts calculated by the **clearing manager** under clauses 13.194 to 13.196

**constrained off compensation** means either—

- (a) **constrained off amounts** owing to a **dispatched purchaser** under clause 13.201A; or
- (b) **constrained off amounts** owing to the **clearing manager** under clause 13.201A by **purchasers**

Clause 1.1(1) **constrained off compensation**: inserted, on 15 May 2014, by clause 5(1) of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

Clause 1.1(1) **constrained off compensation**: amended, on 24 March 2015, by clause 4(1)(g) of the Electricity Industry Participation (Settlement and Prudential Security) Code Amendment 2013.

**constrained off situation** means a situation as defined in clause 13.192

**constrained on amounts** means the amounts calculated by the **clearing manager** under clauses 13.204 and 13.205

**constrained on compensation** means, as the case may be,—

- (a) the **constrained on amounts** owing to—
  - (i) a **generator** under clause 13.212(1)(a); or
  - (ii) an **ancillary service agent** under clause 13.212(1)(a); or
  - (iii) a **dispatched purchaser** under clause 13.212(1)(b); or

- (b) the **constrained on amounts** owing by—  
(i) the **system operator** under clause 13.212(2); or  
(ii) a **purchaser** under clause 13.212(5)

Clause 1.1(1) **constrained on compensation**: substituted, on 15 May 2014, by clause 5(2) of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

Clause 1.1(1) **constrained on compensation**: amended, on 24 March 2015, by clause 4(1)(f) of the Electricity Industry Participation (Settlement and Prudential Security) Code Amendment 2013.

**constrained on situation** means a situation as defined in clause 13.202

**constraint** means a limitation in the capacity of the **grid** to convey electricity caused by limitations in capability of available **assets** forming the **grid** or limitations in the performance of the integrated power system

**constraint price**, in relation to a transmission security constraint, means the amount in dollars and cents per **MW** per hour by which the objective function described in clause 8 of schedule 13.3 is increased by relaxing the transmission security constraint by a very small amount

Clause 1.1(1) **constraint price**: amended, on 15 May 2014, by clause 4(1) of the Electricity Industry Participation (Minor Code Amendments) Code Amendment 2014.

**construct**, for the purposes of the definition of **associated equipment** and Part 6, includes to erect, to lay, and to place, and **construction** has a corresponding meaning  
Clause 1.1(1) **construct**: amended, on 21 September 2012, by clause 4(2) of the Electricity Industry Participation (Minor Amendments) Code Amendment 2012.

**consumer** means a person who is supplied **electricity** for consumption, and includes a **distributor**, a **retailer** or a **generator** if the **distributor**, or the **retailer** or the **generator** is supplied with **electricity** for its own consumption

**consumer installation**, for the purposes of the definition of **associated equipment** and Part 6, means—

- (a) all fittings that are part of a system for conveying **electricity** from a **consumer's point of supply** to any point from which **electricity** conveyed through that system may be consumed; and  
(b) includes any fittings that are used, or designed or intended for use, by any person in, or in relation to, the generation of **electricity**—  
(i) for that person's use and not for supply to any other person; or  
(ii) so that **electricity** can be injected into a **distribution network**; but  
(c) does not include any appliance that uses, or is designed or intended to use, **electricity**, whether or not it also uses, or is designed or intended to use, any other form of energy

Clause 1.1(1) **consumer installation**: substituted, on 23 February 2015, by clause 4(4)(a) of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 1.1(1) **consumer installation**: amended, on 5 October 2017, by clause 4(14) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

**consumption information** means the information describing the quantity of **electricity** conveyed during the period for which the information is required, which may be directly measured or calculated from information obtained from a **metering installation**, or calculated in accordance with this Code

**consumption pattern** means, for the purposes of this Part and Schedule 15.5, the shape of the half **hourly** consumption

**consumption period** means a calendar month during which **electricity** is supplied to **consumers** (and conversely produced by **generators**)

**contract for differences**, for the purposes of subpart 5 of Part 13, means a financial derivative contract—

- (a) under which 1 or both **parties** makes or may make a payment to the other **party**; and
- (b) in which the payment to be made depends on, or is derived from, the price of a specified **quantity** of **electricity** at a particular time; and
- (c) that may provide a means for the risk to 1 or both **parties** of an increase or decrease in the price of **electricity** to be reduced or eliminated; and
- (d) that either—
  - (i) relates to a quantity of **electricity** that equals or exceeds 0.25 **MW** of **electricity**; or
  - (ii) is entered into through a derivatives exchange, being a market in which **parties** trade standardised financial derivative contracts, and contracts containing the right to buy or sell standardised financial derivative contracts, with a central counterparty

Clause 1.1(1) **contract for differences**: amended, on 15 January 2016, by clause 4(5) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

**contract price** means, in respect of a **risk management contract**, a single price that has, in accordance with clause 13.220, been calculated, time weighted, adjusted to a location factor for the relevant **grid zone area**, and corrected for losses, for the purposes of subpart 5 of Part 13

**contract price schedule** means, in respect of a **risk management contract**, a price or series of prices to be paid under that contract in respect of specified times or amounts and at a single location

**contract specifications** means specifications prescribing the specific terms of, and terms of trading in, each class of contract that may from time to time be traded on a market under this Code

**control device** means a device in a **metering installation** that controls either or both of the following:

- (a) **electricity**—
  - (i) conveyed through the **metering installation**; and
  - (ii) used to satisfy controllable load:
- (b) a **meter** register in the **metering installation**

Clause 1.1(1) **control device**: inserted, on 29 August 2013, by clause 4(1) of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011.

**controller** means,—

- (a) in relation to a company,—
  - (i) any person in accordance with whose directions and instructions the

- persons occupying the position of directors of the company are accustomed to act (but disregarding advice given in a professional capacity); or
- (ii) any person who is entitled to exercise, or control the exercise of, 50% or more of the voting power at any general meeting of the company or of another company of which the company is a **subsidiary**; and
- (b) in relation to an unincorporated body of persons,—
- (i) any person in accordance with whose directions and instructions the officers of the body are accustomed to act (but disregarding advice given in a professional capacity); or
  - (ii) any person who is entitled to exercise, or control the exercise of, 50% or more of the voting power on any resolution of the body;
- (c) in relation to any person, any person who has the power to appoint or remove a majority of the participants of the governing body of that person or otherwise controls or has the power to control the affairs or policies of that person,—
- and **control** and **controlled** have corresponding meanings

**control room** means the location at which **asset owners** have facilities to receive operational instructions from the **system operator** and to act on those instructions

**control system** means equipment that adjusts the output voltage, frequency, **MW** or **reactive power** (as the case may be) of an **asset** in response to certain aspects of **common quality** such as voltage, frequency, **MW** or **reactive power**, including speed governors and exciters

**core grid** means the **assets** that form part of the **core grid** as specified in the **core grid determination**

**core grid determination** means the determination specifying the **assets** forming part of the **core grid**, developed in accordance with clauses 12.63 to 12.69, including variations

**customer** means a person who purchases, or has agreed to purchase, **electricity** from a **retailer** at a specific **ICP**

**customer compensation scheme** means a **default customer compensation scheme** or an **additional customer compensation scheme**

Clause 1.1(1) **customer compensation scheme**: inserted, on 1 April 2011, by clause 4(1) of the Electricity Industry Participation (Customer Compensation Schemes) Code Amendment 2011.

**data logger** *[Revoked]*

Clause 1.1(1) **data logger**: revoked, on 15 May 2014, by clause 4(2) of the Electricity Industry Participation (Minor Code Amendments) Code Amendment 2014.

**data storage device** means a device in a **metering installation**, whether or not integral to the **meter**, that—

- (a) electronically stores data and **event logs** used to provide information for the purposes of Part 15; and
- (b) makes the data and **event logs** available during an **interrogation**

Clause 1.1(1) **data storage device**: inserted, on 29 August 2013, by clause 4(1) of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011.

**declaration date** means the date, nominated by the **profile applicant**, on which the **Authority** must, for a particular **profile**, give written notice to every **registered participant** of the information set out in clause 13 of Schedule 15.5 for that **profile**

Clause 1.1(1) **declaration date**: amended, on 5 October 2017, by clause 4(15) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

**decommissioning** means—

- (a) the permanent removal from service of—
  - (i) an **asset**; or
  - (ii) a **point of connection**; or
  - (iii) a **metering installation** associated with a **point of connection**; or
- (b) for the purposes of Parts 11 and 15, the permanent removal of a **point of connection** by—
  - (i) permanently removing an **electrical installation** associated with the **point of connection**; or
  - (ii) changing the allocation of electrical loads between **points of connection** with the effect of making the **point of connection** obsolete; or
  - (iii) in the case of a **distributor-only ICP** for an **embedded network**, the **embedded network** ceasing to exist

and **decommission** and **decommissioned** have corresponding meanings

Clause 1.1(1) **decommissioning**: inserted, on 29 August 2013, by clause 4(1) of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011.

Clause 1.1(1) **decommissioning**, paragraph (a): replaced, on 5 October 2017, by clause 4(16) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

**de-energisation** *[Revoked]*

Clause 1.1(1) **de-energisation**: amended, on 29 August 2013, by clause 4(2)(i) of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011.

Clause 1.1(1) **de-energisation**: amended, on 1 February 2016, by clause 4(6) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

Clause 1.1(1) **de-energisation**: revoked, on 5 October 2017, by clause 4(60) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

**de-energise** *[Revoked]*

Clause 1.1(1) **de-energise**: inserted, on 29 August 2013, by clause 4(3) of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2013.

Clause 1.1(1) **de-energise**: revoked, on 1 February 2016, by clause 4(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

**default customer compensation scheme** means a scheme that complies with clause 9.24

Clause 1.1(1) **default customer compensation scheme**: inserted, on 1 April 2011, by clause 4(1) of the Electricity Industry Participation (Customer Compensation Schemes) Code Amendment 2011.

**default interest rate** means the **bank bill bid rate** plus 5% per annum

**demand** means the rate of consumption of electrical energy

**designated transmission customers** means **participants** who are required to enter into **transmission agreements** with **Transpower** under subpart 2 of Part 12

**difference bid** means the information that a **purchaser** submits to the **system operator** under clause 13.7AA to indicate a reasonable estimate of an increase or decrease in the **purchaser's** usual **non-dispatch-capable load** purchased at a **conforming GXP**

Clause 1.1(1) **difference bid**: inserted, on 28 June 2012, by clause 4(a) of the Electricity Industry Participation (Demand-side Bidding and Forecasting) Code Amendment 2011.

Clause 1.1(1) **difference bid**: substituted, on 15 May 2014, by clause 5(2) of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

Clause 1.1(1) **difference bid**: amended, on 29 June 2017, by clause 4(2) of the Electricity Industry Participation Code Amendment (Shortened Gate Closure and Revised Bid and Offer Provisions) 2017.

**direct consumer** means a **consumer** with a **point of connection** to the **grid**

**direct purchaser** means a **consumer** who purchases, or agrees to purchase, **electricity** directly from the **clearing manager** for its own consumption at a **point of connection**

**disclosed** [*Revoked*]

Clause 1.1(1) **disclosed**: revoked, on 16 December 2013, by clause 4(2)(b) of the Electricity Industry Participation (Revocation of Part 16) Code Amendment 2013.

**disclosing participant** means any of the following:

- (a) a person who consumes **electricity** that is conveyed to the person directly from the national **grid**;
- (b) a person who buys **electricity** from the **clearing manager**

Clause 1.1(1) **disclosing participant**: inserted, on 1 December 2011, by clause 4 of the Electricity Industry Participation Code (Spot Price Risk Disclosure) Amendment 2011.

**disclosure information**, in relation to a **participant**, means information that—

- (a) is about the **participant**; and
- (b) is held by the **participant**; and
- (c) the **participant** expects, or ought reasonably to expect, if made available to the public, will have a material impact on prices in the **wholesale market**

Clause 1.1(1) **disclosure information**: inserted, on 1 October 2013, by clause 4(1) of the Electricity Industry Participation (Disclosure Obligations) Code Amendment 2013.

Clause 1.1(1) **disclosure information**: amended, on 5 October 2017, by clause 4(17) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

**disconnected** [*Revoked*]

Clause 1.1(1) **disconnected**: amended, on 23 February 2015, by clause 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 1.1(1) **disconnected**: revoked, on 5 October 2017, by clause 4(60) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

**dispatch** means the process of—

- (a) pre-dispatch scheduling, to match expected **supply** with expected **demand**, and to allocate **ancillary service offers** and transmission **offers** to match expected **grid** conditions; and
- (b) rescheduling to meet forecast **demand**; and
- (c) issuing instructions based on the **dispatch schedule** and the real-time conditions to manage resources to meet the actual **demand**,—

and **dispatching** has a corresponding meaning

Clause 1.1(1) **dispatch** paragraphs (a) and (c): amended, on 28 June 2012, by clause 4(d) of the Electricity Industry Participation (Demand-side Bidding and Forecasting) Code Amendment 2011.

**dispatch arc flows** [*Revoked*]

Clause 1.1(1) **dispatch arc flows**: revoked, on 28 June 2012, by clause 4(i) of the Electricity Industry Participation (Demand-side Bidding and Forecasting) Code Amendment 2011.

**dispatch group constraint arc flows** [*Revoked*]

Clause 1.1(1) **dispatch group constraint arc flows**: revoked, on 28 June 2012, by clause 4(i) of the Electricity Industry Participation (Demand-side Bidding and Forecasting) Code Amendment 2011.

**dispatch instruction** means an instruction issued by the **system operator** under clause 13.72(1)

Clause 1.1(1) **dispatch instruction**: substituted, on 15 May 2014, by clause 5(2) of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

**dispatch objective** means the objective defined in clause 13.57

**dispatch prices** *[Revoked]*

Clause 1.1(1) **dispatch prices**: revoked, on 28 June 2012, by clause 4(i) of the Electricity Industry Participation (Demand-side Bidding and Forecasting) Code Amendment 2011.

**dispatch quantities** *[Revoked]*

Clause 1.1(1) **dispatch quantities**: revoked, on 28 June 2012, by clause 4(i) of the Electricity Industry Participation (Demand-side Bidding and Forecasting) Code Amendment 2011.

**dispatch schedule** means the schedule produced by the **system operator** under clause 13.69A

Clause 1.1(1) **dispatch schedule**: substituted, on 15 May 2014, by clause 5(2) of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

**dispatchable load information** means the **volume information**—

- (a) of each **dispatch-capable load station** for each **trading period** in a **consumption period**; and
- (b) that is—
  - (i) prepared under clause 15.5A or 15.5B; and
  - (ii) aggregated and rounded in accordance with clause 15.5C

Clause 1.1(1) **dispatchable load information**: inserted, on 15 May 2014, by clause 5(1) of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

**dispatchable load purchaser** means a **purchaser** that purchases **electricity** for a **dispatch-capable load station**

Clause 1.1(1) **dispatchable load purchaser**: inserted, on 15 May 2014, by clause 5(1) of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

**dispatch-capable load station** means a device or a group of devices approved as a **dispatch-capable load station** under clause 13.3A

Clause 1.1(1) **dispatch-capable load station**: inserted, on 15 May 2014, by clause 5(1) of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

**dispatch-capable load station identifier** means a unique code—

- (a) assigned to a **dispatch-capable load station** under clause 6(2) of Schedule 13.8; and
- (b) that is used to identify the **dispatch-capable load station**

Clause 1.1(1) **dispatch-capable load station identifier**: inserted, on 15 May 2014, by clause 5(1) of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

**dispatched purchaser** means a **dispatchable load purchaser**,—

- (a) issued with a **dispatch instruction** under clause 13.72(1)(b) for 1 or more **dispatch-capable load stations**; or
- (b) issued with a **dispatch instruction** in accordance with backup procedures under clause 13.81(2) for 1 or more **dispatch-capable load stations**

Clause 1.1(1) **dispatched purchaser**: inserted, on 15 May 2014, by clause 5(1) of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

**dispensation** means an exclusion from compliance with an **AOPO** or **technical code** granted by the **system operator** in accordance with the process set out in clauses 8.29 to 8.31



**distributed generation** means **generating plant** that is connected, or that a **distributed generator** proposes to connect, to a **distribution network** or to a **consumer installation** that is connected to a **distribution network**, but does not include—

- (a) **generating plant** that is connected, or that a **participant** proposes to connect, to a **distribution network** and that is operated by a **distributor** for the purpose of maintaining or restoring the provision of **electricity** to part or all of the **distributor's distribution network**—
  - (i) as a result of a planned **distribution network** outage; or
  - (ii) as a result of an unplanned **distribution network** outage; or
  - (iii) during a period when the **distribution network capacity** would otherwise be exceeded on part or all of the **distribution network**; or
- (b) **generating plant** that is only momentarily **synchronised**, or that a **participant** proposes only to momentarily **synchronise**, with the **distribution network** for the purpose of switching operations to start or stop the **generating plant**

Clause 1.1(1) **distributed generation**: substituted, on 23 February 2015, by clause 4(4)(b) of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 1.1(1) **distributed generation**: replaced, on 5 October 2017, by clause 4(1)(c) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

**distributed generator**, for the purposes of Part 6, means a person who owns or operates, or intends to own or operate, **distributed generation**

Clause 1.1(1) **distributed generator**: amended, on 23 February 2015, by clause 4(5) of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

**distributed unmetered load** means **unmetered load** with a single **profile** supplied to a single **customer** across more than 1 **point of connection**

**distribution** has the meaning given to it by section 5 of the **Act**

Clause 1.1(1) **distribution**: inserted, on 1 February 2016, by clause 4(19) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

**distribution network** means the **electricity lines**, and **associated equipment**, owned or operated by a **distributor**

Clause 1.1(1) **distributed network**: amended, on 23 February 2015, by clause 4(6) of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

**distribution network capacity** means the capacity of a **distribution network** to convey **electricity** under a range of load and **generation** conditions in accordance with **reasonable and prudent operating practice**

Clause 1.1(1) **distribution network capacity**: inserted, on 23 February 2015, by clause 4(12) of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

**distributor** has the meaning given to it by section 5 of the **Act**

Clause 1.1(1) **distributor**: amended, on 21 September 2012, by clause 4(3) of the Electricity Industry Participation (Minor Amendments) Code Amendment 2012.

Clause 1.1(1) **distributor**: amended, on 23 February 2015, by clause 4(7) of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 1.1(1) **distributor**: amended, on 24 March 2015, by clause 4(1)(h) of the Electricity Industry Participation (Settlement and Prudential Security) Code Amendment 2013.

Clause 1.1(1) **distributor**: substituted, on 1 February 2016, by clause 4(1)(b) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

**distributor installation details** means any information, additional to **price category** and **chargeable capacity**, that may be used to calculate line charges applicable to an **ICP**

**distributor kvar reference node** means a notional node that represents a group of **grid exit points** within a **zone** for which a **distributor** nominates peak demand in kvar, and for which the individual kvar quantities measured at the individual **grid exit points** within the group are aggregated for **voltage support** charging purposes, as approved by the **system operator** (such approval not to be unreasonably withheld)

**document**, for the purposes of paragraph (b) of the definition of **publish**, and Parts 2 and 6, has the meaning given to it in section 2(1) of the Official Information Act 1982  
Clause 1.1(1) **document**: amended, on 16 December 2013, by clause 4(3)(a) and (b) of the Electricity Industry Participation (Revocation of Part 16) Code Amendment 2013.

**domestic consumer** means a person who acquires **electricity** for personal, domestic or household use or consumption and does not acquire **electricity** or hold himself or herself out as acquiring **electricity** for the purpose of resupplying it in trade or consuming it in the course of production or manufacture

**draft policy statement** means a document provided for in clause 8.10A(2), 8.11A(1), or 8.12A(1)

Clause 1.1(1) **draft policy statement**: amended, on 10 January 2013, by clause 4(1) of the Electricity Industry Participation (Policy Statement and Procurement Plan Review Process) Code Amendment 2012.

**draft procurement plan** means a document provided for in clause 8.42A(2), 8.43A(1), or 8.44A(1)

Clause 1.1(1) **draft procurement plan**: amended, on 10 January 2013, by clause 4(2) of the Electricity Industry Participation (Policy Statement and Procurement Plan Review Process) Code Amendment 2012.

**effective date**, for the purposes of subpart 5 of Part 13, means the date of the first **trading period** to which a **risk management contract** applies

**EIEP** means an electricity information exchange protocol that sets out standard formats for the exchange or provision of information

Clause 1.1(1) **EIEP**: inserted, on 16 December 2013, by clause 4(a) of the Electricity Industry Participation (Electricity Information Exchange Protocols) Code Amendment 2013.

Clause 1.1(1) **EIEP**: amended, on 1 February 2016, by clause 4(7) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

**EIEP12 [Revoked]**

Clause 1.1(1) **EIEP12**: inserted, on 1 December 2011, by clause 4(a) of the Electricity Industry Participation Code (Distributor Use-of-System Agreements and Distributor Tariffs) Amendment 2011.

Clause 1.1(1) **EIEP12**: revoked, on 16 December 2013, by clause 4(b) of the Electricity Industry Participation (Electricity Information Exchange Protocols) Amendment 2013.

**electrical installation** means,—

- (a) *[revoked]*
- (b) all fittings that form part of a system for conveying **electricity** at any point from an **ICP** to any point from which **electricity** conveyed through that system may be consumed (including any fittings that are used or designed or intended for use by any person in, or in relation to, the generation of **electricity** for that person's use and not for supply to any other person), but does not include any electrical appliance

Clause 1.1(1) **electrical installation paragraph (a)**: revoked, on 23 February 2015, by clause 4(8)(a) of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 1.1(1) **electrical installation paragraph (b)**: amended, on 23 February 2015, by clause 4(8)(b) of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 1.1(1) **electrical installation paragraph (b)**: amended, on 5 October 2017, by clause 4(18) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

**electrically connect** means to operate a device so that **electricity** is able to flow, including through a **point of connection**, and **electrically connected**, **electrically connecting**, **electrical connection**, and similar phrases have corresponding meanings

Clause 1.1(1) **electrically connect**: inserted, on 5 October 2017, by clause 4(61) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

**electrically connecting** *[Revoked]*

Clause 1.1(1) **electrically connecting**: inserted, on 29 August 2013, by clause 4(2) of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011, Amendment 2013 (No 2).

Clause 1.1(1) **electrically connecting**: amended, on 23 February 2015, by clause 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 1.1(1) **electrically connecting**: revoked, on 5 October 2017, by clause 4(60) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

**electrically disconnect** means to operate a device so that **electricity** is unable to flow, including through a **point of connection**, and **electrically disconnected**, **electrically disconnecting**, **electrical disconnection**, and similar phrases have corresponding meanings

Clause 1.1(1) **electrically disconnect**: inserted, on 5 October 2017, by clause 4(61) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

**electricity** means electrical energy measured in kilowatt-hours (kWh)

**electricity supplied** means, for any particular period, the information relating to the quantities of **electricity** supplied by **retailers** across **points of connection** to **consumers**, sourced directly from the **retailer's** financial records, including quantities—

- (a) that are metered or unmetered; and
- (b) supplied through normal **customer** supply and billing arrangements; and
- (c) supplied under sponsorship arrangements; and
- (d) supplied under any other arrangement

**embedded generating station** means 1 or more **generating units** that are directly connected to a **local network** or an **embedded network** and that injects into a **local network** or an **embedded network** at a single point of **injection**

Clause 1.1(1) **embedded generating station**: amended, on 23 February 2015, by clause 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 1.1(1) **embedded generating station**: amended, on 5 October 2017, by clause 4(19) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

**embedded generator** means a **generator** who owns or operates 1 or more **embedded generating stations**

**embedded network** means a system of **lines**, substations, and other **works**, used primarily for the conveyance of **electricity**, that—

- (a) is indirectly connected to the **grid** through 1 or more other **networks**; and
- (b) has 1 or more **ICP identifiers** recorded in the **registry** as being connected to it

Clause 1.1(1) **embedded network**: amended, on 1 February 2016, by clause 4(1)(c) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

Clause 1.1(1) **embedded network**: replaced, on 5 October 2017, by clause 4(20) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

**emergency management policy** means the emergency management policy that is incorporated by reference in this Code under clause 7.4

**EMP departure situation** means any situation in which the **system operator** believes on reasonable grounds that complying with the **emergency management policy** will not—

- (a) adequately mitigate an emergency situation; or
- (b) minimise risk to public safety or significant damage to **assets**

Clause 1.1(1) **EMP departure situation**: inserted, on 21 September 2012, by clause 4(4) of the Electricity Industry Participation (Minor Amendments) Code Amendment 2012.

**end date**, for the purposes of subpart 5 of Part 13, means the date of the final **trading period** to which the **risk management contract** applies

**energisation** *[Revoked]*

Clause 1.1(1) **energisation**: inserted, on 29 August 2013, by clause 4(1) of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011.

Clause 1.1(1) **energisation**: substituted, on 29 August 2013, by clause 4(1) of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011, Amendment 2013 (No 2).

Clause 1.1(1) **energisation** paragraph (b): revoked, on 1 February 2016, by clause 4(8) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

Clause 1.1(1) **energisation**: revoked, on 5 October 2017, by clause 4(60) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

**equivalence arrangement** means an arrangement put in place in accordance with the process set out in clauses 8.29 and 8.30

**equivalent day** means the day of a previous week corresponding to the day for which an **initial estimate** or **final estimate** is required to be made. However, if the day is a **national holiday**, the **equivalent day** will be deemed to be the previous Sunday. If the day for which an **initial estimate** is required to be made is a **business day**, but the corresponding day of the previous week is a **national holiday**, the **equivalent day** is deemed to be the next earlier corresponding day that is not a **national holiday**

**error claimant** means a person who—

- (a) considers that prices contain a **pricing error**; and
- (b) claims, in accordance with subpart 4 of Part 13, that a **pricing error** has occurred

**error compensation** means the application of a predetermined **adjustment** or process to the data within or obtained from, a **metering component** or **metering installation** in order to correct such data for known errors in any **metering component**

Clause 1.1(1) **error compensation**: amended, on 29 August 2013, by clause 4(2)(j) of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011.

**estimated reading** means a value, used in the place of a **meter reading**, that is—

- (a) created using an estimation algorithm; and
- (b) not a **validated meter reading**

**event charge** means the amount calculated under clause 8.64

**event date**, in relation to an **ICP**, means the earlier of the following dates:

- (a) the date on which the gaining **trader** commences trading **electricity** at the **ICP** under clauses 1(1), 8(1) or 13(1) of Schedule 11.3:
- (b) the date on which the gaining **trader** otherwise assumes responsibility under clause 11.18(1) for the **ICP**

Clause 1.1(1) **event date**: substituted, on 1 February 2016, by clause 4(1)(d) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

**event log** means an automatically generated record of activity in a **data storage device**, that can be extracted or manually read as part of an **interrogation**

Clause 1.1(1) **event log**: inserted, on 29 August 2013, by clause 4(1) of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011.

**event of default** means any event listed in clause 14.41

Clause 1.1(1) **event of default**: amended, on 24 March 2015, by clause 4(1)(i) of the Electricity Industry Participation (Settlement and Prudential Security) Code Amendment 2013.

**exceptional circumstances** means, for the purposes of Part 15, circumstances in which access to the relevant **meter** is not achieved despite the **reconciliation participant's** best endeavours

**excluded Code information** means information—

- (a) that relates to **bids, offers, reserve offers**, or any **asset capability statement**; or
- (b) that is provided to the **Authority**, any investigator, or the **Rulings Panel** and that is required to be kept confidential under this Code or the **Act**; or
- (c) in relation to which the **Rulings Panel** has prohibited publication or communication

Clause 1.1(1) **excluded Code information** paragraph (a): substituted, on 1 October 2013, by clause 4(2) of the Electricity Industry Participation (Disclosure Obligations) Code Amendment 2013.

**excluded generating station** has the meaning set out in clause 8.21(1)

**existing assets** means transmission **assets** and **non-transmission projects** that have been **commissioned** before, and are in operation at the time of, application of a net benefits tests set out in Part 12. To avoid doubt, an investment in the expansion of generating capacity of an existing **generating unit** is not an **existing asset** or part of an **existing asset**, unless the additional generating capacity associated with the investment has been **commissioned** before, and is in operation at the time of, the application of the relevant net benefits test

Clause 1.1(1) **existing assets**: amended, on 5 October 2017, by clause 4(21) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

**expected interruption costs** *[Revoked]*

Clause 1.1(1) **expected interruption costs**: revoked, on 7 August 2014, by clause 4(2) of the Electricity Industry Participation Code Amendment (Extended Reserve) 2014.

**expected near-constraint arc flows** means the scheduled quantity of energy flow on a transmission line or a transformer, if the energy flow is equal to or greater than 95% of the maximum energy flow limit (in **MW**) of the transmission line or transformer as set by the **system operator** in accordance with Schedule 13.3

Clause 1.1(1) **expected near-constraint arc flows**: inserted, on 28 June 2012, by clause 4(a) of the Electricity Industry Participation (Demand-side Bidding and Forecasting) Code Amendment 2011.

**expected near-group-constraint arc flows** means the scheduled quantity of energy flow on a group of transmission **lines** or a group of transformers or a group of

transmission **lines** and transformers, calculated according to a group constraint formula covering the group, if the scheduled quantity of energy flow is equal to or above 95% of the maximum energy flow limit (in **MW**) for the group as set by the **system operator** in accordance with Schedule 13.3

Clause 1.1(1) **expected near-group-constraint arc flows**: inserted, on 28 June 2012, by clause 4(a) of the Electricity Industry Participation (Demand-side Bidding and Forecasting) Code Amendment 2011.

Clause 1.1(1) **expected near-group-constraint arc flows**: amended, on 1 February 2016, by clause 4(9) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

**expected unserved energy** means a forecast of the aggregate amount by which the **demand** for electricity exceeds the **supply** of electricity at each **grid exit point** as a result of likely planned or unplanned outages of **primary transmission equipment**

**extended emergency situation** [*Revoked*]

Clause 1.1(1) **extended emergency situation**: revoked, on 21 September 2012, by clause 4(4) of the Electricity Industry Participation (Minor Amendments) Code Amendment 2012.

**export congestion** means a situation in which a **distribution network** is unable to accept **electricity** exported from **distributed generation** because the injection of an additional unit of **electricity** into the **distribution network** would—

- (a) directly cause a component in the **network** to operate beyond the component's rated maximum capacity; or
- (b) give rise to an unacceptably high level of voltage at the **point of connection** between the **distribution network** and the **distributed generation**

Clause 1.1(1) **export congestion**: inserted, on 23 February 2015, by clause 4(12) of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 1.1(1) **export congestion**: amended, on 5 October 2017, by clause 4(22) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

**extended reserve** means services provided to restore frequency to the **normal band** after disturbances of a magnitude that make it impracticable or uneconomic to restore frequency using **ancillary services**

Clause 1.1(1) **extended reserve**: inserted, on 7 August 2014, by clause 4(3) of the Electricity Industry Participation Code Amendment (Extended Reserve) 2014.

**extended reserve manager** means the **market operation service provider** that is for the time being appointed as the **extended reserve manager** under this Code, or if no regulations have been made establishing the **extended reserve manager** as a **market operation service provider**, the **Authority**

Clause 1.1(1) **extended reserve manager**: inserted, on 7 August 2014, by clause 4(3) of the Electricity Industry Participation Code Amendment (Extended Reserve) 2014.

Clause 1.1(1) **extended reserve manager**: amended, on 5 October 2017, by clause 4(23) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

**extended reserve procurement notice** means the notice given to an **asset owner** by the **extended reserve manager** under clause 8.54L

Clause 1.1(1) **extended reserve procurement notice**: inserted, on 7 August 2014, by clause 4(3) of the Electricity Industry Participation Code Amendment (Extended Reserve) 2014.

**extended reserve procurement schedule** means the schedule **published** by the **extended reserve manager** under clause 8.54J

Clause 1.1(1) **extended reserve procurement schedule**: inserted, on 7 August 2014, by clause 4(3) of the Electricity Industry Participation Code Amendment (Extended Reserve) 2014.

**extended reserve provider** means an **asset owner** required to provide **extended reserve** under Schedule 8.3, **Technical Code B**, clause 7

Clause 1.1(1) **extended reserve provider**: inserted, on 7 August 2014, by clause 4(3) of the Electricity Industry Participation Code Amendment (Extended Reserve) 2014.

**extended reserve schedule** means the schedule **published** by the **system operator** under clause 8.54O

Clause 1.1(1) **extended reserve schedule**: inserted, on 7 August 2014, by clause 4(3) of the Electricity Industry Participation Code Amendment (Extended Reserve) 2014.

**extended reserve selection methodology** means the methodology **published** by the **extended reserve manager** under clause 8.54G

Clause 1.1(1) **extended reserve selection methodology**: inserted, on 7 August 2014, by clause 4(3) of the Electricity Industry Participation Code Amendment (Extended Reserve) 2014.

**extended reserve technical requirements report** means the report **published** by the **system operator** under clause 8.54D

Clause 1.1(1) **extended reserve technical requirements report**: inserted, on 7 August 2014, by clause 4(3) of the Electricity Industry Participation Code Amendment (Extended Reserve) 2014.

**extended reserve technical requirements schedule** means the schedule of requirements **published** by the **system operator** under clause 8.54D

Clause 1.1(1) **extended reserve technical requirements schedule**: inserted, on 7 August 2014, by clause 4(3) of the Electricity Industry Participation Code Amendment (Extended Reserve) 2014.

**fast instantaneous reserve** means—

- (a) for providers of **partly loaded spinning reserve** and **tail water depressed reserve**, the additional capacity (in **MW**) provided 6 seconds after a “Contingent Event” (as defined in the **policy statement**) that is sustained for a period of at least 60 seconds; and
- (b) for providers of **interruptible load**, the drop in load (in **MW**) that occurs within 1 second of the **grid** system frequency falling to or below 49.2 Hertz that is sustained for a period of at least 60 seconds

**final application**, for the purposes of Part 6, means an application made under clause 15 of Schedule 6.1

**final estimate** means the mean of the metering data for each of the previous 4 **equivalent days** for the relevant **trading period** weighted in accordance with the quantity of **electricity** sold in the relevant **trading period** on the **equivalent days** in the relevant **island** as determined in accordance with the following formula:

$$\frac{Eday_4 + Eday_3 + Eday_2 + Eday_1}{4} \times \left\{ \frac{(IslandLoad_0)}{\left( \frac{IslandLoad_4 + IslandLoad_3 + IslandLoad_2 + IslandLoad_1}{4} \right)} \right\}$$

where

$Eday_1$  is the quantity of **electricity** measured at the relevant **metering installation** in kWh for the **trading period** of the **equivalent day** 1 week before the **trading day** for which the estimate is required

$Eday_2$  is the quantity of **electricity** measured at the relevant **metering installation** in kWh for the **trading period** of the **equivalent day** 2

- Eday<sub>3</sub>* weeks before the **trading day** for which the estimate is required is the quantity of **electricity** measured at the relevant **metering installation** in kWh for the **trading period** of the **equivalent day** 3 weeks before the **trading day** for which the estimate is required
- Eday<sub>4</sub>* is the quantity of **electricity** measured at the relevant **metering installation** in kWh for the **trading period** of the **equivalent day** 4 weeks before the **trading day** for which the estimate is required
- Island Load<sub>0</sub>* means the quantity of **electricity**, measured in kWh, for the relevant **trading period** (as measured before the commencement of the calculation of this estimate) supplied in the **island** in which the relevant **metering installation** is located, less any measurement taken at any **metering installation** for which an estimate is being obtained for the same **trading period** and **island**
- Island Load<sub>1</sub>* means the quantity of **electricity**, measured in kWh, for the **trading period** of the **equivalent day** 1 week before the **trading day** for which the estimate is required (as measured before the commencement of the calculation of this estimate) supplied in the **island** in which the relevant **metering installation** is located, less any measurement taken at any **metering installation** for which an estimate is being obtained for the same **trading period** and **island**
- Island Load<sub>2</sub>* means the quantity of **electricity**, measured in kWh, for the **trading period** of the **equivalent day** 2 weeks before the **trading day** for which the estimate is required (as measured before the commencement of the calculation of this estimate) supplied in the **island** in which the relevant **metering installation** is located, less any measurement taken at any **metering installation** for which an estimate is being obtained for the same **trading period** and **island**
- Island Load<sub>3</sub>* means the quantity of **electricity**, measured in kWh, for the **trading period** of the **equivalent day** 3 weeks before the **trading day** for which the estimate is required (as measured before the commencement of the calculation of this estimate) supplied in the **island** in which the relevant **metering installation** is located, less any measurement taken at any **metering installation** for which an estimate is being obtained for the same **trading period** and **island**
- Island Load<sub>4</sub>* means the quantity of **electricity**, measured in kWh, for the **trading period** of the **equivalent day** 4 weeks before the **trading day** for which the estimate is required (as measured before the commencement of the calculation of this estimate) supplied in the **island** in which the relevant **metering installation** is located, less any measurement taken at any **metering installation** for which an estimate is being obtained for the same **trading period** and **island**
- final marginal location factor** means the factor that is determined by dividing the **final price** at any **grid exit point** or **grid injection point** by the **final price** at the relevant **reference point**



**final price** means a price in dollars and cents for each **grid injection point**, each **grid exit point** and each **reference point** determined in accordance with the methodology specified by clause 13.135

**final reserve price** means the price calculated in dollars and cents for **fast instantaneous reserve** and **sustained instantaneous reserve** determined in each **island** in accordance with the methodology specified by clause 13.135

**financial year** *[Revoked]*

Clause 1.1(1) **financial year**: revoked, on 5 October 2017, by clause 4(60) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

**fittings** *[Revoked]*

Clause 1.1(1) **fittings**: revoked, on 23 February 2015, by clause 4(11) of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

**fixed-price physical supply contract** means a contract that provides for the physical supply of **electricity**, if—

- (a) the **buyer** is reasonably expected to purchase 1 **MW** or more of **electricity** on average during the **term** of the contract (for the purposes of determining whether a contract meets this 1 **MW** threshold, the total purchases under the contract should be used despite clause 13.219(6)); and
- (b) the contract allows the **buyer** to purchase either—
  - (i) variable amounts of **electricity** linked to actual consumption of **electricity** at a fixed price or prices; or
  - (ii) a fixed amount of **electricity** at a fixed price or prices; and
- (c) excludes a contract for the physical supply of **electricity**, that is generated by an **embedded generating station**, directly to a **consumer**

**floating-price payer** means the **party** obliged to make 1 or more payments, from time to time during the **term** of a **contract for differences**, of a floating amount for a **quantity** of **electricity**

**force majeure clause**, for the purposes of subpart 5 of Part 13, means a clause in a **risk management contract** under which some or all obligations may be suspended and/or the **risk management contract** may terminate due to 1 or more events (not being events specified in a **suspension clause**) beyond the control of the **party** and that could not reasonably have been foreseen, including—

- (a) any event or circumstance occasioned by, or in consequence of, any act of God (being an event or circumstance—
  - (i) due to natural causes, directly or indirectly and exclusively without human intervention; and
  - (ii) that could not reasonably have been foreseen or if foreseen, could not reasonably have been resisted); or
- (b) strikes, lockouts, other industrial disturbances, acts of public enemy, wars, blockades, insurrections, riots, epidemics, or civil disturbances; or
- (c) the binding order of any court, government or a local authority beyond the control of the **party**

**force majeure event**, for the purposes of Parts 3 and 4,—

- (a) means an event or circumstance beyond the reasonable control of a **market operation service provider** or **ancillary service agent** that results in, or causes, the **market operation service provider** or **ancillary service agent** to be unable to perform any of its obligations under this Code or the Electricity Industry (Enforcement) Regulations 2010; and
- (b) includes (without limitation)—
  - (i) fire, flood, storm, earthquake, landslide, volcanic eruption, or other act of God; and
  - (ii) explosion or nuclear, biological, or chemical contamination; and
  - (iii) sabotage, terrorism, or act of war (whether declared or not); and
- (c) includes an act or omission by a party to an agreement with a **market operation service provider** (not being the **Authority**) or an **ancillary service agent** only if—
  - (i) the act or omission is a breach of an obligation under the agreement; and
  - (ii) the obligation is in all material respects the same as an obligation in the **market operation service provider agreement**, or the **ancillary service agent's agreement** with the **system operator**; and
  - (iii) the act or omission would have been a **force majeure event** if it had been an act or omission of the **market operation service provider** or **ancillary service agent** and not an act or omission of the party; and
- (d) does not include that a **market operation service provider**, **ancillary service agent**, or other person—
  - (i) is unable or unwilling to pay any amount necessary to meet the obligations under this Code or the Electricity Industry (Enforcement) Regulations 2010; or
  - (ii) is unable to pay its debts; or
  - (iii) calls a meeting for the purpose of Part 14 of the Companies Act 1993; or
  - (iv) is adjudicated bankrupt; or
  - (v) in the case of a company, society, or partnership, has a receiver or statutory manager or similar person appointed in respect of it or of all or any of its assets; or
  - (vi) is put into liquidation; and
- (e) does not include an event that could have been prevented by the **market operation service provider** or **ancillary service agent** by the exercise of a reasonable standard of care

Clause 1.1(1) **force majeure event**: substituted, on 1 November 2012, by clause 4 of the Electricity Industry Participation (Force Majeure) Code Amendment 2012.

**forecast marginal location factor** means the factor that is determined by dividing the **forecast price** at any **grid exit point** or **grid injection point** by the **forecast price** at the relevant **reference point**

**forecast prices** means the prices for **electricity** at all **grid exit points**, **grid injection points**, and **reference points** scheduled in the **price-responsive schedule** or the **non-response schedule** (whichever is the case) in dollars and cents

Clause 1.1(1) **forecast prices**: substituted, on 28 June 2012, by clause 4(e) of the Electricity Industry Participation (Demand-side Bidding and Forecasting) Code Amendment 2011.

**forecast reserve prices** means the prices for **fast instantaneous** and **sustained instantaneous reserve** for each **island** scheduled in the **price-responsive schedule** or the **non-response schedule** (whichever is relevant) in dollars and cents

Clause 1.1(1) **forecast reserve prices**: substituted, on 28 June 2012, by clause 4(f) of the Electricity Industry Participation (Demand-side Bidding and Forecasting) Code Amendment 2011.

**formal notice** means a notice issued by the **system operator** in accordance with clause 5 of **Technical Code B** of Schedule 8.3

Clause 1.1(1) **formal notice**: amended, on 1 June 2013, by clause 4(b) of the Electricity Industry Participation (Scarcity Pricing) Code Amendment 2011.

**forward estimate** means, in relation to non **half hour** metered **ICPs**, any **volume information** (in kWh) submitted for a part or full **consumption period** that is not an **historical estimate**

**frequency fluctuation** means a deviation in frequency outside the **normal band**

Clause 1.1(1) **frequency fluctuation**: inserted, on 19 May 2016, by clause 4(2) of the Electricity Industry Participation Code Amendment (System Operator and Alignment with Statutory Objective) 2016.

**frequency keeping** means an **ancillary service** that maintains the system frequency within the **normal band**

**frequency keeping unit** means any equipment that provides **frequency keeping services**

Clause 1.1(1) **frequency keeping unit**: inserted, on 3 October 2013, by clause 4 of the Electricity Industry Participation (Technology Neutral Language in Frequency Keeping) Code Amendment 2013.

**frequency time error** *[Revoked]*

Clause 1.1(1) **frequency time error**: revoked, on 19 May 2016, by clause 4(1) of the Electricity Industry Participation Code Amendment (System Operator and Alignment with Statutory Objective) 2016.

**FTR** means a financial transmission right created under subpart 6 of Part 13

Clause 1.1(1) **FTR**: inserted, on 1 October 2011, by clause 4(1) of the Electricity Industry Participation (Financial Transmission Rights) Code Amendment 2011.

**FTR account** *[Revoked]*

Clause 1.1(1) **FTR account**: inserted, on 1 October 2011, by clause 4(1) of the Electricity Industry Participation (Financial Transmission Rights) Code Amendment 2011.

Clause 1.1(1) **FTR account**: revoked, on 24 March 2015, by clause 4(1)(j) of the Electricity Industry Participation (Settlement and Prudential Security) Code Amendment 2013.

**FTR acquisition cost** means—

- (a) the amount a **participant** owes or is owed in respect of the acquisition of an **FTR** in an **FTR auction**; or
- (b) if an **FTR** has been assigned by the first holder of the **FTR**, the amount that becomes owing under clause 13.249(3); or
- (c) an amount described in paragraph (a) or (b) that is adjusted under clause 13.242A

Clause 1.1(1) **FTR payment**: inserted, on 1 October 2011, by clause 4(1) of the Electricity Industry Participation (Financial Transmission Rights) Code Amendment 2011.

Clause 1.1(1) **FTR payment**: amended to **FTR acquisition cost**, on 1 November 2012, by clause 4(2) of the Electricity Industry Participation (Financial Transmission Rights) Code Amendment 2012.

Clause 1.1(1) **FTR acquisition cost**: amended, on 1 November 2014, by clause 4(2) of the Electricity Industry Participation (FTR Reconfiguration Auctions) Code Amendment 2014.

Clause 1.1(1) **FTR acquisition cost**: amended, on 24 March 2015, by clause 4(1)(l) of the Electricity Industry Participation (Settlement and Prudential Security) Code Amendment 2013.

**FTR allocation plan** means the FTR allocation plan prepared and **published** by the **FTR manager** under clause 13.238

Clause 1.1(1) **FTR allocation plan**: inserted, on 1 October 2011, by clause 4(1) of the Electricity Industry Participation (Financial Transmission Rights) Code Amendment 2011.

**FTR auction** means an auction conducted by the **FTR manager** in accordance with the **FTR allocation plan** approved under subpart 6 of Part 13

Clause 1.1(1) **FTR auction**: inserted, on 1 October 2011, by clause 4(1) of the Electricity Industry Participation (Financial Transmission Rights) Code Amendment 2011.

**FTR hedge value** means the gross amount that becomes due and owing by the **clearing manager** or the holder of an **FTR** on the settlement of the **FTR** in accordance with the terms of the **FTR** (excluding the **FTR acquisition cost** and any amount owing under clause 13.249(4) or (7))

Clause 1.1(1) **FTR hedge value**: inserted, on 1 November 2012, by clause 4(1) of the Electricity Industry Participation (Financial Transmission Rights) Code Amendment 2012.

Clause 1.1(1) **FTR hedge value**: amended, on 24 March 2015, by clause 4(1)(k) of the Electricity Industry Participation (Settlement and Prudential Security) Code Amendment 2013.

**FTR manager** means the **market operation service provider** who is for the time being appointed as the **FTR manager** under this Code

Clause 1.1(1) **FTR manager**: inserted, on 1 October 2011, by clause 4(1) of the Electricity Industry Participation (Financial Transmission Rights) Code Amendment 2011.

Clause 1.1(1) **FTR payment**: inserted, on 1 October 2011, by clause 4(1) of the Electricity Industry Participation (Financial Transmission Rights) Code Amendment 2011.

Clause 1.1(1) **FTR payment**: amended to **FTR acquisition cost**, on 1 November 2012, by clause 4(2) of the Electricity Industry Participation (Financial Transmission Rights) Code Amendment 2012.

Clause 1.1(1) **FTR manager**: amended, on 5 October 2017, by clause 4(24) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

**FTR period** means a period for which an **FTR** applies

Clause 1.1(1) **FTR period**: inserted, on 1 October 2011, by clause 4(1) of the Electricity Industry Participation (Financial Transmission Rights) Code Amendment 2011.

**FTR reconfiguration amount** means the amount a **participant** that sells a **reconfigured FTR**—

- (a) is entitled to be paid for the **reconfigured FTR**, if the amount is positive; or
- (b) is liable to pay in respect of the **reconfigured FTR**, if the amount is negative

Clause 1.1(1) **FTR reconfiguration amount**: inserted, on 1 November 2014, by clause 4(1) of the Electricity Industry Participation (FTR Reconfiguration Auctions) Code Amendment 2014.

**FTR reconfiguration auction** means an **FTR auction** that allows a holder of an **FTR** to offer for sale a portion of the **FTR** expressed in terms of all or a specified amount of the **electricity** (in MW) to which the **FTR** relates

Clause 1.1(1) **FTR reconfiguration auction**: inserted, on 1 November 2014, by clause 4(1) of the Electricity Industry Participation (FTR Reconfiguration Auctions) Code Amendment 2014.

**FTR register** means the register created and operated by the **FTR manager** under clause 13.247

Clause 1.1(1) **FTR register**: inserted, on 1 October 2011, by clause 4(1) of the Electricity Industry Participation (Financial Transmission Rights) Code Amendment 2011.

**fully calibrated certification** means certification of a metering installation under clause 13(3) of Schedule 10.7

Clause 1.1(1) **fully calibrated certification**: inserted, on 29 August 2013, by clause 4(1) of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011.

**fully certified metering installation** means a certified metering installation other than an interim certified metering installation

Clause 1.1(1) **fully certified metering installation**: inserted, on 29 August 2013, by clause 4(1) of the Electricity

Industry Participation (Metering Arrangements) Code Amendment 2011.

**gaining metering equipment provider** means, for the purposes of Parts 10 and 11,—

- (a) the person who a **trader** records in the **registry** as the **metering equipment provider** for each **metering installation** for a **point of connection**; or
- (b) the person with whom the **participant** responsible for ensuring there is a **metering installation** for a **point of connection** enters into an arrangement to become the **metering equipment provider** for each **metering installation** for the **point of connection**

Clause 1.1(1) **gaining metering equipment provider**: inserted, on 29 August 2013, by clause 4(1) of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011.

Clause 1.1(1) **gaining metering equipment provider**: amended, on 5 October 2017, by clause 4(25) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

**gate closure period**, in relation to a **trading period** for which a **generator** or **ancillary service agent** has submitted an **offer** or **reserve offer**, or for which a **dispatchable load purchaser** has submitted a **nominated dispatch bid**, means—

- (a) the **trading period** immediately preceding the **trading period** to which the **offer** or **reserve offer** relates, for—
  - (i) an **embedded generator**;
  - (ii) an **intermittent generator**;
  - (iii) an **ancillary service agent** that is also an **embedded generator**; and
- (b) the 2 **trading periods** immediately preceding the **trading period** to which the **offer**, **reserve offer**, or **nominated dispatch bid** relates, for—
  - (i) any other **generator**;
  - (ii) any other **ancillary service agent**;
  - (iii) a **dispatchable load purchaser**

Clause 1.1(1) **gate closure period**: inserted, on 29 June 2017, by clause 4(3) of the Electricity Industry Participation Code Amendment (Shortened Gate Closure and Revised Bid and Offer Provisions) 2017.

**generally available retail tariff plan**—

- (a) means a retail tariff plan that a **retailer** will make available to any **consumer** (subject to credit requirements) if the **consumer** satisfies the requirements specified for the retail tariff plan relating to:
  - (i) physical location;
  - (ii) **metering** configuration;
  - (iii) **price category** code; but
- (b) does not include a retail tariff plan made available by a **retailer** only under an agreement reached as a result of the **retailer** directly contacting a **consumer** to offer a retail tariff plan that provides the **consumer** with a financial discount or other benefit when compared with any other of the **retailer's** tariff plans to which paragraph (a) applies that are available to that **consumer**

Clause 1.1(1) **generally available retail tariff plan**: inserted, on 1 February 2016, by clause 4 of the Electricity Industry Participation Code Amendment (Access to Retail Tariff Information) 2015.

**generating plant** means equipment collectively used for generating **electricity**

**generating station** means 1 or more **generating units** that are directly connected to the **grid** or to a **local network** and that inject into the **grid** or a **local network** (as the case may be) at a single point of **injection**

Clause 1.1(1) **generating station**: amended, on 23 February 2015, by clause 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 1.1(1) **generating station**: amended, on 5 October 2017, by clause 4(26) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

**generating unit** means a machine that generates **electricity**

**generating unit gross** means the output of a **generating unit** measured or calculated at its output terminals, inclusive of any **generating unit load** supplied

Clause 1.1(1) **generating unit gross**: inserted, on 1 June 2011, by clause 4(1) of the Electricity Industry Participation (Minor Amendments) Code Amendment 2011.

**generating unit load** means the active and **reactive power** supplied or injected via connections between the **generating unit's** output terminals and its **generating unit circuit breaker**

Clause 1.1(1) **generating unit load**: inserted, on 1 June 2011, by clause 4(1) of the Electricity Industry Participation (Minor Amendments) Code Amendment 2011.

Clause 1.1(1) **generating unit load**: amended, on 23 February 2015, by clause 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 1.1(1) **generating unit load**: amended, on 5 October 2017, by clause 4(27) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

**generating unit net** means the output of a **generating unit** measured or calculated at its **point of connection**, but does not include **generating unit load** or any other active or **reactive power** supplied (including losses) between the **generating unit** and the **point of connection**

Clause 1.1(1) **generating unit net**: inserted, on 1 June 2011, by clause 4(1) of the Electricity Industry Participation (Minor Amendments) Code Amendment 2011.

**generator** means a person who owns **generating units** connected to a **network**, or any person who acts, in respect of Parts 13, 14 and 15, on behalf of any person who owns such **generating units**, and includes **embedded generators**, **intermittent generators**, **type A co-generators**, and **type B co-generators**

Clause 1.1(1) **generator**: amended, on 23 February 2015, by clause 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 1.1(1) **generator**: amended, on 27 May 2015, by clause 4(2) of the Electricity Industry Participation Code Amendment (Industrial Co-generation Dispatch Arrangements) 2015.

Clause 1.1(1) **generator**: amended, on 5 October 2017, by clause 4(28) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

**good electricity industry practice** in relation to transmission, means the exercise of that degree of skill, diligence, prudence, foresight and economic management, as determined by reference to good international practice, which would reasonably be expected from a skilled and experienced **asset** owner engaged in the management of a transmission network under conditions comparable to those applicable to the **grid** consistent with applicable law, safety and environmental protection. The determination is to take into account factors such as the relative size, duty, age and technological status of the relevant transmission network and the applicable law

**grid** means the system of transmission **lines**, substations and other works, including the **HVDC link** used to connect **grid injection points** and **grid exit points** to convey **electricity** throughout the North Island and the South Island of New Zealand

Clause 1.1(1) **grid**: amended, on 23 February 2015, by clause 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 1.1(1) **grid**: amended, on 1 February 2016, by clause 4(10) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

Clause 1.1(1) **grid**: amended, on 5 October 2017, by clause 4(29) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

**grid economic investment report** means the report prepared under clause 12.115, either as part of **Transpower's** annual planning report or in some other form, if the **Authority** so determines

**grid emergency** means a situation where—

- (a) in the reasonable opinion of the **system operator**, 1 or more of the events set out in clause 5(1) of **Technical Code B** of Schedule 8.3 has occurred, or is reasonably expected to occur and urgent action is required of the **system operator** or **participants** to alleviate the situation; or
- (b) independent action (as set out in clause 9 of **Technical Code B** of Schedule 8.3) is required of a **participant** to alleviate the situation

**grid exit point** and **GXP** mean any **point of connection** on the **grid**—

- (a) at which **electricity** predominantly flows out of the **grid**; or
- (b) determined as being such by the **Authority** following an application in accordance with clause 13.28,—

and such **point of connection** may, at any given time, be a **grid exit point** or a **grid injection point**, but may not be both at the same time

**grid injection point** and **GIP** mean any **point of connection** on the **grid** at which **electricity** predominantly flows into the **grid**. A **point of connection** may, at any given time, be a **grid injection point** or a **grid exit point**, but may not be both at the same time

**grid interface** means the **assets** used to make a connection to the **grid** (as the case may be), including associated protection, control and communication systems. The term includes the interface between **assets** forming part of the **grid**

Clause 1.1(1) **grid interface**: amended, on 23 February 2015, by clause 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 1.1(1) **grid interface**: amended, on 5 October 2017, by clause 4(30) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

**grid owner** means a person who owns or operates any part of the **grid**

**grid reliability report** means a report on grid reliability **published** by **Transpower** under clause 12.76(1)

**grid reliability standards** means standards for reliability of the **grid** developed in accordance with clauses 12.55 to 12.58, 12.61 and 12.62

**grid zone area** means a geographical area, which includes many **nodes**, as determined by the **Authority** and **published** under clause 13.221(1)

**group constraint formula** means the mathematical formula applied by the **system operator**, in accordance with Schedule 13.3, to constrain the energy flows on a group of transmission **lines**, transformers or both

Clause 1.1(1) **group constraint formula**: amended, on 1 February 2016, by clause 4(11) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

**GST** means goods and services tax payable under the Goods and Services Tax Act 1985

**half hour** means a thirty minute period ending on any hour or half hour, and **half hourly** has a corresponding meaning

**half-hour metering** means the process of measuring and recording information—

- (a) relating to **electricity** conveyed; and
- (b) during—
  - (i) an interval that is a **trading period**; or
  - (ii) intervals that can be aggregated to 1 **trading period**

Clause 1.1(1) **half-hour metering**: substituted, on 29 August 2013, by clause 4(2)(k) of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011.

**half-hour metering information**—

- (a) means information describing the quantity of **electricity** conveyed in each **trading period** that is—
  - (i) recorded directly by a **metering installation**; or
  - (ii) calculated or estimated using information recorded directly by a **metering installation**; and
- (b) in respect of a **generator** that is selling **electricity** to the **clearing manager** and other persons at the same **grid injection point** in the same **trading period**, includes the file recording the quantity of **electricity** sold to the **clearing manager** during each such **trading period** constructed in accordance with **dispatch instructions** issued by the **system operator** under this Code.

Clause 1.1(1) **half-hour metering information**: substituted, on 19 December 2014, by clause 4(2) of the Electricity Industry Participation Code Amendment (Minor Code Amendments) (No 3) 2014.

**half-hour metering installation** means a **metering installation** used for **half-hour metering**

Clause 1.1(1) **half-hour metering installation**: amended, on 29 August 2013, by clause 4(2)(l) of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011.

**hedge settlement agreement** means an agreement in a form set out in Schedule 14.4 between **participants** that provides for settlement by the **clearing manager** of payments for differences in respect of the price of **electricity**

Clause 1.1(1) **hedge settlement agreement**: amended, on 24 March 2015, by clause 4(1)(m) of the Electricity Industry Participation (Settlement and Prudential Security) Code Amendment 2013.

**high spring washer price relaxation factor** means, in relation to a **high spring washer price situation** in a **trading period**, 1MW

Clause 1.1(1) **high spring washer price relaxation factor**: amended, on 21 September 2012, by clause 4(1) of the Electricity Industry Participation (High Spring Washer Price Situation) Code Amendment 2012.

**high spring washer price situation** means a situation in a **trading period** in which—

- (a) 1 or more **transmission security constraints** bind; and
- (b) the **software** used by the **pricing manager** to calculate provisional prices, interim prices, and final prices (or used by the **system operator** to determine, under clause 13.134(4), whether a **high spring washer price situation** still exists) calculates a price for electricity at any **grid injection point** or **grid exit point**, excluding **grid injection points** and **grid exit points** that are **electrically disconnected**, that is equal to or greater than the product of the **high spring washer price trigger ratio** and the highest unconstrained cleared offer price in that **trading period**



Clause 1.1(1) **high spring washer price situation**: amended, on 21 September 2012, by clause 4(2) of the Electricity Industry Participation (High Spring Washer Price Situation) Code Amendment 2012.

Clause 1.1(1) **high spring washer price situation**: amended, on 5 October 2017, by clause 4(31) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

**high spring washer price situation methodology** means the methodology described in clauses 13.134(2) and 13.134(4)

Clause 1.1(1) **high spring washer price situation methodology**: amended, on 21 September 2012, by clause 4(3) of the Electricity Industry Participation (High Spring Washer Price Situation) Code Amendment 2012.

**high spring washer price trigger ratio** means the ratio in clause 13.133

**high voltage terminal** means the point at which the higher voltage side of a **grid owner's** transformer connects to the **grid**

Clause 1.1(1) **high voltage terminal**: amended, on 23 February 2015, by clause 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 1.1(1) **high voltage terminal**: amended, on 5 October 2017, by clause 4(32) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

**historical annual consumption** means the annual consumption of a **grid exit point** or **grid injection point** for the 12-month period ended 3 months preceding publication of the **annual consumption list**

**historical estimate** means, in relation to non **half hour** metered **ICPs**, **volume information** (in kWh), apportioned to part or full **consumption periods** after having the **seasonal adjustment shape**, or any other **profile** that has, from time to time, been approved by the **Authority** for this purpose, applied, being 1 of the following:

- (a) the difference between 2 **validated** actual **meter readings**:
- (b) the difference between 2 **permanent estimates**:
- (c) any relevant **unmetered load**

**hub** means a **node** or group of **nodes** (and in the case of a group of **nodes**, **nodes** in the group may be given different weightings) identified as either hub A or hub B in an **FTR**

Clause 1.1(1) **hub**: inserted, on 1 October 2011, by clause 4(1) of the Electricity Industry Participation (Financial Transmission Rights) Code Amendment 2011.

**HV**, for the purposes of subparts 2, 6 and 7 of Part 12, means high voltage

**HVDC component flows** means the quantity of energy flow on each component of the **HVDC link** as calculated by the modelling system in accordance with the model formulation set out in the **system operator's market operation service provider agreement** (as amended from time to time)

**HVDC injection point** means the point at which **electricity** is injected into the North Island or the South Island from the **HVDC link**

**HVDC link** means the converter stations at Benmore in the South Island and Haywards in the North Island and the high voltage transmission **lines** and undersea cables linking them (and including all associated equipment)

Clause 1.1(1) **HVDC link**: amended, on 1 February 2016, by clause 4(12) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

**HVDC owner** means the **grid owner** who owns and/or operates the **HVDC link**

**HVDC risk offsets** means the values by which HVDC flows are adjusted by the **system operator** to determine the relevant reserve risk on the **HVDC link**

**ICP** means an installation control point being 1 of the following:

- (a) a **point of connection** at which a **customer** installation is connected to a **network** other than the **grid**;
- (b) a **point of connection** between a **network** and an **embedded network**;
- (c) a **point of connection** between a **network** and **shared unmetered load**

Clause 1.1(1) **ICP**: amended, on 23 February 2015, by clause 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 1.1(1) **ICP**: amended, on 5 October 2017, by clause 4(33) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

**ICP day** means any day when an **ICP** with the **installation type** L or B is recorded on the **registry** as having the status of Active

Clause 1.1(1) **ICP day**: amended, on 5 October 2017, by clause 4(34) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

**ICP identifier** means a unique identifier for an **ICP** created by a **distributor** in accordance with clause 1 of Schedule 11.1

**identification costs** means any reasonable identification and testing costs incurred by the **system operator** in accordance with clause 8.3 that are unable to be recovered from **participants** by the **system operator**

**incremental costs**, for the purpose of Part 6, means the reasonable costs that an efficient **distributor** would incur in providing **electricity** distribution services with connection services to **distributed generation**, less the costs that the efficient **distributor** would incur if it did not provide those connection services

Clause 1.1(1) **incremental costs**: inserted, on 23 February 2015, by clause 4(12) of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 1.1(1) **incremental costs**: amended, on 5 October 2017, by clause 4(35) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

**industrial co-generating station** means a **generating station** that —

- (a) *[Revoked]*
- (b) is reliant on a co-located **industrial process** because—
  - (i) it derives its fuel source from that co-located **industrial process**; or
  - (ii) it provides some or all of the **electricity** that it generates to that co-located **industrial process**; or
  - (iii) it provides some or all of any by-product of generating **electricity** to that co-located **industrial process**; and
- (c) is tightly coupled to an **industrial process**; and
- (d) has been approved by the **Authority** under clause 8(1)(a) of Schedule 13.4

Clause 1.1(1) **industrial co-generating station**: amended, on 23 February 2015, by clause 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 1.1(1) **industrial co-generating station**: amended, on 27 May 2015, by clause 4(3)(a) of the Electricity Industry Participation Code Amendment (Industrial Co-generation Dispatch Arrangements) 2015.

Clause 1.1(1) **industrial co-generating station** paragraph (a): revoked, on 27 May 2015, by clause 4(3)(b) of the Electricity Industry Participation Code Amendment (Industrial Co-generation Dispatch Arrangements) 2015.

Clause 1.1(1) **industrial co-generating station** paragraph (b): amended, on 27 May 2015, by clause 4(3)(c) of the Electricity Industry Participation Code Amendment (Industrial Co-generation Dispatch Arrangements) 2015.

Clause 1.1(1) **industrial co-generating station** paragraph (c): amended, on 27 May 2015, by clause 4(3)(d) of the Electricity Industry Participation Code Amendment (Industrial Co-generation Dispatch Arrangements) 2015.

Clause 1.1(1) **industrial co-generating station** paragraph (d): amended, on 27 May 2015, by clause 4(3)(e) of the Electricity Industry Participation Code Amendment (Industrial Co-generation Dispatch Arrangements) 2015.

**industrial process** means a process that has a primary purpose of producing an output other than **electricity**

**infeasibility situation** means a situation where the **software** used to determine **final prices** and **final reserve prices** calculates a model variable with a value (either positive or negative) as set out in the list given to the **pricing manager** under Schedule 13.2

**information system** *[Revoked]*

Clause 1.1(1) **information system**: revoked, on 5 October 2017, by clause 4(60) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

**inherent characteristics** means the permanent and fundamental characteristics of an **asset** that are outside the reasonable control of the **asset owner** and affect the output or response of that **asset** and includes the effects of water temperature, ambient air temperature and performance during ramping on **asset** performance

**initial application**, for the purposes of Part 6, means an application under clause 11 of Schedule 6.1

**initial estimate** means an estimate of **metering information** to be made by giving the **metering information** of all **participants** of the **equivalent day** of the previous week

**injection** means the flow of **electricity** into a **network**

**input connection contract** means the fixed term input connection and input connection assets contracts between **Transpower** and each of the following: Tuaropaki Power Company Limited, Carter Holt Harvey Limited, Contact Energy Limited, Empower Limited, and Mighty River Power Limited

Clause 1.1(1) **input connection contract**: amended, on 23 February 2015, by clause 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 1.1(1) **input connection contract**: amended, on 5 October 2017, by clause 4(36) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

**input information** means information given to the **pricing manager** in accordance with clause 13.141

**installation type** means a category based on whether an **ICP** consumes **electricity**, generates **electricity**, or both consumes and generates **electricity**

**instantaneous reserve** means an **ancillary service** comprising 1 or more of the following:

- (a) **interruptible load**;
- (b) **partly loaded spinning reserve**;
- (c) **tail water depressed reserve**

**interconnecting transformer** means a transformer (other than a transformer that is required to supply **demand** to **distributors** or **direct consumers**) that allows for the transfer of power within the grid between any of the following voltage levels:

- (a) 220kV;
- (b) 110kV;
- (c) 66kV;
- (d) 50kV

**interconnection asset**, for the purposes of subparts 2, 6 and 7 of Part 12—

- (a) has the meaning set out in the **transmission pricing methodology**; and
- (b) includes the **HVDC link**

**interconnection branch** means an **interconnection circuit branch**, and an **interconnection transformer branch**

**interconnection circuit branch** means a **circuit branch** that comprises or includes **interconnection assets**

**interconnection point** means a **point of connection** between—

- (a) a **local network** and any other **local network**; or
- (b) an **embedded network** that is not a gateway **NSP** and a **local network**; or
- (c) an **embedded network** that is not a gateway **NSP** and any other **embedded network**

Clause 1.1(1) **interconnection point**: substituted, on 29 August 2013, by clause 4(2)(m) of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011.

**interconnection transformer branch** means a **transformer branch** comprising **interconnection assets**

**interim certified metering installation** means a **metering installation** referred to in clause 10.51(3)(a)(i)

Clause 1.1(1) **interim certified metering installation**: inserted, on 29 August 2013, by clause 4(1) of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011.

**interim marginal location factor** means the factor that is determined by dividing the **interim price** at any **grid exit point** or **grid injection point** by the **interim price** at the relevant **reference point**

**interim price** means a price in dollars and cents for each **grid injection point** and each **grid exit point**, determined in accordance with the methodology specified in clause 13.135

**interim reserve price** means a price in dollars and cents for **fast instantaneous reserve** and **sustained instantaneous reserve**, determined in each **island** in accordance with methodology specified in clause 13.135

Clause 1.1(1) **interim reserve price**: amended, on 5 October 2017, by clause 4(37) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

**intermittent generating station** means a **wind generating station**

**intermittent generator** means the owner of an **intermittent generating station**. To avoid doubt, clauses referring to an **intermittent generator** apply only to the **intermittent generating stations** owned by the **intermittent generator**

**interrogation** means the extraction or manual reading of stored data from a **metering installation** and **interrogated** and **interrogating** have corresponding meanings

Clause 1.1(1) **interrogation**: amended, on 29 August 2013, by clause 4(2)(n) of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011.

**interruptible load** means a form of **instantaneous reserve** comprised of energy being consumed that is able to be **electrically disconnected** to balance the **injection supply**

and the **offtake of electricity** following a drop in system frequency to a specified level below 50 Hz

Clause 1.1(1) **interruptible load**: amended, on 5 October 2017, by clause 4(38) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

**interruptible load group GXP** means the **grid exit point**, as approved by the **system operator** (such approval not to be unreasonably withheld), at which a **reserve offer** for **interruptible load** comprises the aggregate quantity of **interruptible load** available at a number of specified **grid exit points** for the purposes of **offer** and **dispatch**

**interruption**, for the purposes of Part 12, means an interruption in the conveyance of **electricity** between **assets** owned or operated by a **designated transmission customer** and the **grid assets** owned by **Transpower** at a **point of connection**, other than an interruption by reason of **Transpower** being directed to **electrically disconnect a point of connection** by the **Authority** or the **Rulings Panel** under the **Act** or this Code or by any other person authorised to do so by this Code

Clause 1.1(1) **interruption**: amended, on 5 October 2017, by clause 4(39) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

**investment contracts** means contracts for investments that are agreed between **Transpower** and a **designated transmission customer**

**island** means the South Island or the North Island of New Zealand (as the case may be)

**island GWAP** means the generation weighted average price for an **island** for a **trading period** calculated in accordance with clause 1(2) of Schedule 13.3A

Clause 1.1(1) **island GWAP**: inserted, on 1 June 2013, by clause 4(a) of the Electricity Industry Participation (Scarcity Pricing) Code Amendment 2011.

**island scarcity pricing situation** means a situation determined to be an island scarcity pricing situation by the **pricing manager** under clause 13.135A(3)

Clause 1.1(1) **island scarcity pricing situation**: inserted, on 1 June 2013, by clause 4(a) of the Electricity Industry Participation (Scarcity Pricing) Code Amendment 2011.

**island shortage situation** means a situation specified in a notice to be an **island** wide shortage by the **system operator** under clause 5(1A) of **Technical Code B** of Schedule 8.3

**island shortage situation**: inserted, on 1 June 2013, by clause 4(a) of the Electricity Industry Participation (Scarcity Pricing) Code Amendment 2011.

**line function services** has the meaning given to it by section 5 of the **Act**

Clause 1.1(1) **line function services**: substituted, on 1 February 2016, by clause 4(1)(e) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

**line owner**, for the purposes of the definition of **specified participant**, means a person who owns **works** that are used or intended to be used for the conveyance of **electricity**

Clause 1.1(1) **line owner**: amended, on 21 September 2012, by clause 4(5) of the Electricity Industry Participation (Minor Amendments) Code Amendment 2012.

**lines** has the meaning given to it by section 5 of the **Act**

Clause 1.1(1) **lines**: amended, on 23 February 2015, by clause 4(9) of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 1.1(1) **lines**: substituted, on 1 February 2016, by clause 4(1)(f) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

**livening** [*Revoked*]

Clause 1.1(1) **livening**: inserted, on 29 August 2013, by clause 4(1) of the Electricity Industry Participation (Metering

Arrangements) Code Amendment 2011.

Clause 1.1(1) **livening**: revoked, on 29 August 2013, by clause 4(2) of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011, Amendment 2013 (No 2).

**local authority**, for the purposes of Part 6, means a territorial authority within the meaning of the Local Government Act 2002

**local losses** means losses applying to the conveyance of **electricity** over a **local network** or an **embedded network**

**local network** means the **lines**, equipment and plant that are used to convey **electricity** between the **grid** and 1 of the following:

- (a) an **embedded generator**;
- (b) an **embedded network**;
- (c) an **ICP**

Clause 1.1(1) **local network**: amended, on 1 February 2016, by clause 4(13) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

**location factor**, for the purposes of subpart 5 of Part 13, means the location factor calculated in accordance with clause 13.221(2)

**losing metering equipment provider** means, for the purposes of Parts 10 and 11, the existing **metering equipment provider** responsible for each **metering installation** for a **point of connection** at which there is a **gaining metering equipment provider**

Clause 1.1(1) **losing metering equipment provider**: inserted, on 29 August 2013, by clause 4(1) of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011.

**loss adjusted demand** means the total demand determined by taking all actual demand **half-hour metering information** given to the **pricing manager** under clause 13.138 and multiplying the total by 1.05

**loss and constraint excess** means the difference between **purchaser** and **generator** payments as defined in clause 14.16

Clause 1.1(1) **loss and constraint excess**: amended, on 24 March 2015, by clause 4(1)(n) of the Electricity Industry Participation (Settlement and Prudential Security) Code Amendment 2013.

**loss category** means the relevant code in the schedule **published** by the **registry manager** that identifies the relevant **loss factors** that apply to **submission information** or **dispatchable load information**

Clause 1.1(1) **loss category**: amended, on 15 May 2014, by clause 5(3) of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

Clause 1.1(1) **loss category**: amended, on 5 October 2017, by clause 4(40) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

**loss compensation** means the application of a predetermined **adjustment** or process to the data within, or obtained from, a **metering component** or **metering installation** in order to correct such data for known **losses** in primary plant (such as power transformers and cables)

Clause 1.1(1) **loss compensation**: amended, on 29 August 2013, by clause 4(2)(o) of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011.

**losses** means the difference between the delivered **electricity** at a **point of connection** and the **electricity** required to be injected into an other **point of connection** in order to supply the delivered **electricity**

**loss factor** means the factor, identified by reference to a **loss category** within the **registry**, to be applied to **submission information** or **dispatchable load information** to obtain adjusted for **losses** information at the relevant **NSP**, which factor is—

- (a) as set out in the report to be provided by the **registry** in accordance with clause 11.26(b); or
- (b) if a report has not been provided by the **registry**, as directed by the **Authority** under clause 15.20B(3) or 15(1) of Schedule 15.4

Clause 1.1(1) **loss factor**: amended, on 15 May 2014, by clause 5(4) of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

**loss of communication** means a sustained disruption of communications between the **system operator** and 1 or more **dispatch customers** such that operation of the **grid** is affected or is likely to be affected

**LV**, for the purposes of subparts 2, 6 and 7 of Part 12, means low voltage

**main protection system** means a protection system that detects 1 or more types of faults and **electrically disconnects** a faulted **asset** from the **grid** with the least possible disruption to the **grid** and non-faulted **assets**

Clause 1.1(1) **main protection system**: amended, on 5 October 2017, by clause 4(41) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

**maintain**, for the purposes of Part 6, includes to repair, and **maintenance** has a corresponding meaning

**manufacturer's specification**, for the purposes of Part 12, means the specifications for an **asset**, as stated by the manufacturer

**market administrator** *[Revoked]*

Clause 1.1(1) **market administrator**: revoked, on 5 October 2017, by clause 4(60) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

**market operation service provider** has the meaning given to it in section 5 of the **Act**

**market operation service provider agreement** means the agreement entered into between the **Authority** and a **market operation service provider** for the provision of services for the purposes of this Code

**maximum continuous rating** means the maximum electrical performance of an **asset** that can be maintained continuously in normal service

**maximum South Island frequency** means the maximum frequency permitted in the South Island, which is 55 Hertz

**measuring transformer** means—

- (a) a current transformer; or
- (b) a voltage transformer; or
- (c) both a current transformer and a voltage transformer

Clause 1.1(1) **measuring transformer**: inserted, on 29 August 2013, by clause 4(1) of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011.

**meter** means a device that measures either or both of the following—

- (a) **active energy**:

**(b) reactive energy**

Clause 1.1(1) **meter**: substituted, on 29 August 2013, by clause 4(2)(p) of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011.

**meter reading** means a **meter** register value or the equivalent, obtained from **raw meter data** or such other reading as detailed in clause 3(1) of Schedule 15.2, which is not an **estimated reading**

**metering** means the process used to measure **electricity** conveyed

Clause 1.1(1) **metering**: inserted, on 29 August 2013, by clause 4(1) of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011.

**metering component** means a component of a **metering installation** including—

- (a) a **measuring transformer**;
- (b) all wiring and intermediate terminals in the **metering installation**;
- (c) a **control device**;
- (d) a **meter**;
- (e) a **data storage device**;
- (f) a **test facility**;
- (g) a **fuse**;
- (h) a **circuit breaker**;
- (i) **communication equipment**;
- (j) an **error compensation device**

Clause 1.1(1) **metering component**: inserted, on 29 August 2013, by clause 4(1) of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011.

**metering data** means, in relation to a **metering installation**,—

- (a) all **metering records** about the **metering installation**; and
- (b) all **raw meter data** obtained from the **metering installation**

Clause 1.1(1) **metering data**: inserted, on 29 August 2013, by clause 4(1) of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011.

**metering equipment owner** means the **participant** who owns any or all of the items of metering equipment installed in a **metering installation**

**metering equipment provider** has the meaning given to it in section 5 of the **Act**

Clause 1.1(1) **metering equipment provider**: inserted, on 29 August 2013, by clause 4(1) of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011.

**metering information** means the quantity of **electricity** measured by a **metering installation** and adjusted for **local losses** (if relevant) to represent the equivalent amount of **electricity** at the **point of connection** with the **grid** and consolidated into a single quantity per **trading period**

**metering infrastructure** means, in relation to a **metering installation**,—

- (a) the **metering installation**;
- (b) if a **back office** process is necessary, the **metering equipment owner's back office** for the **metering installation**;
- (c) a system that collects and sends information to or from the **metering installation**

Clause 1.1(1) **metering infrastructure**: inserted, on 29 August 2013, by clause 4(1) of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011.

**metering installation** means—



- (a) equipment, including all **metering components**, used, or intended to be used, for **metering**;
- (b) in the context of **unmetered load**, the calculation process used to derive the quantity of **unmetered load**;
- (c) in the context of instances of both **metered electricity** quantities and **unmetered load**, both (a) and (b)

Clause 1.1(1) **metering installation**: substituted, on 29 August 2013, by clause 4(2)(q) of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011.

Clause 1.1(1) **metering installation**: inserted, on 1 February 2016, by clause 4(14) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

**metering records** means all specifications for, attributes of, and information relating to or concerning, a **metering installation** (other than **raw meter data**), including—

- (a) the relevant records of the **metering equipment provider** responsible for the **metering installation**;
- (b) the relevant records of each **ATH** who **certified** the **metering installation** or any **metering component** of the **metering installation**;
- (c) all factors applied in a **meter** in the **metering installation** and relating to that data (for example the k factor and m factor);
- (d) the **metering installation's** maintenance and repair history and requirements;
- (e) details of each **metering component** in the **metering installation** including information about its ownership;
- (f) all **certification reports** and supporting documents and records

Clause 1.1(1) **metering records**: inserted, on 29 August 2013, by clause 4(1) of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011.

**metering situation** means a situation in which—

- (a) the **metering information** to be given is incomplete or incorrect or is and remains an **initial estimate** for—
  - (i) a **grid exit point** or **grid injection point** specified on the **annual consumption list** as having **historical annual consumption** greater than 500 GWh; or
  - (ii) any 2 or more **grid exit points** or **grid injection points** specified on the **annual consumption list** as having **historical annual consumption** greater than 300 GWh; or
  - (iii) any 10 or more **grid exit points** or **grid injection points**; or
  - (iv) an **intermittent generating station** with a **point of connection** to the **grid**; or
  - (v) a **type B industrial co-generating station** with a **point of connection** to the **grid**; or
- (b) the **metering information** for a **dispatch-capable load station** given for a **trading period** is incomplete or incorrect or is and remains an **initial estimate** for a **grid exit point** at which a **nominated dispatch bid** has been submitted for the **trading period**

Clause 1.1(1) **metering situation**: substituted, on 15 May 2014, by clause 5(2) of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

Clause 1.1(1) **metering situation** paragraph (a)(v): inserted, on 27 May 2015, by clause 4(4) of the Electricity Industry Participation Code Amendment (Industrial Co-generation Dispatch Arrangements) 2015.

**metering testing requirements** [*Revoked*]

Clause 1.1(1) **metering testing requirements**: revoked, on 29 August 2013, by clause 4(3) of the Electricity Industry

Participation (Metering Arrangements) Code Amendment 2011.

**metering standards** means the **metering** requirements set out in the Schedules to Part 10

Clause 1.1(1) **metering standards**: substituted, on 29 August 2013, by clause 4(2)(r) of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011.

**metrology layer** means a part of a **metering installation** used for either or both of the following:

- (a) measuring and recording **electricity** conveyed; or
- (b) recording **event logs**

Clause 1.1(1) **metrology layer**: inserted, on 29 August 2013, by clause 4(1) of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011.

**minimum South Island frequency** means the minimum frequency permitted in the South Island, which is 45 Hertz

**model formulation** means the model from which **software specifications** have been developed for the **system operator**

**modelled projects** means transmission augmentation projects and **non-transmission projects** that are reasonably expected to occur within the time period for which the assessment of costs and benefits under a net benefits test set out in Part 12 is undertaken

**momentary fluctuations** *[Revoked]*

Clause 1.1(1) **momentary fluctuations**: revoked, on 19 May 2016, by clause 4(1) of the Electricity Industry Participation Code Amendment (System Operator and Alignment with Statutory Objective) 2016.

**MV**, for the purposes of subparts 2, 6 and 7 of Part 12, means medium voltage

**MW** means a megawatt of electrical power

**MWh** means a megawatt hour of electrical energy

**N-1 criterion** means that, with all **assets** that are reasonably expected to be in service, the power system would be in a **secure state**

**nameplate capacity** means the lesser of—

- (a) the full-load continuous rating of **generating plant** under conditions specified by its designer in **MW** or kilowatts; or
- (b) the full-load continuous rating of the **generating plant's** inverter (if any) under conditions specified by its designer in **MW** or kilowatts

Clause 1.1(1) **nameplate capacity**: inserted, on 23 February 2015, by clause 4(12) of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

**national grid** *[Revoked]*

Clause 1.1(1) **national grid**: revoked, on 23 February 2015, by clause 4(11) of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

**national GWAP** means the generation weighted average price for both **islands** for a **trading period** calculated in accordance with clause 2(2) of Schedule 13.3A

Clause 1.1(1) **national GWAP**: inserted, on 1 June 2013, by clause 4(a) of the Electricity Industry Participation (Scarcity Pricing) Code Amendment 2011.

**national holiday** means any day on which any of the following are observed as a statutory holiday:

- (a) Good Friday:

- (b) Easter Monday:
- (c) ANZAC Day:
- (d) Queen's Birthday:
- (e) Labour Day:
- (f) Christmas Day:
- (g) Boxing Day:
- (h) New Year's Day:
- (i) the day after New Year's Day:
- (j) Waitangi Day

**national scarcity pricing situation** means a situation determined to be a national scarcity pricing situation by the **pricing manager** under clause 13.135A(4)  
**national scarcity pricing situation**: inserted, on 1 June 2013, by clause 4(a) of the Electricity Industry Participation (Scarcity Pricing) Code Amendment 2011.

**national shortage situation** means concurrent **island shortage situations** in the North Island and the South Island  
**national shortage situation**: inserted, on 1 June 2013, by clause 4(a) of the Electricity Industry Participation (Scarcity Pricing) Code Amendment 2011.

**negative sequence voltage** means a measure of difference in magnitude and phase angle in each phase

**net grid exit point** means any **grid exit point** or **grid injection point** that is not a **net grid injection point**

**net grid injection point** means a **grid exit point** or **grid injection point** for which the most recent information provided by the **grid owner** under clauses 13.141(1)(b) and 13.166 is less than or equal to 0

**net purchase quantity assessment** means the quantity of an **ancillary service** derived from the following formula:

$$a = b - c$$

where

- a is the net purchase quantity of the **ancillary service** to be procured by the **system operator** in accordance with the **procurement plan**
- b is the gross amount of an **ancillary service** that the **system operator** believes is required in order to meet the **principal performance objectives**;
- c is the amount of the **ancillary service** that is made available to the **system operator** under **alternative ancillary service arrangements**

**network** means the **grid**, a **local network** or an **embedded network**

**new investment agreement contracts** means contracts entered into before 1 April 2008 between **Transpower** and its customers, under which **Transpower** agrees to provide new or upgraded plant and the customer agrees to pay charges based on **Transpower's** cost of providing the new or upgraded plant

**New Zealand daylight time** means New Zealand daylight time declared by Order in Council under section 4 of the Time Act 1974

**New Zealand standard time** has the meaning given to it by section 2 of the Time Act 1974

**node** means—

- (a) a bus; or
- (b) a location at which an electrical link that is not part of or does not contain a **transformer**, diverges or terminates (such as a "tee" point or a deviation); or
- (c) a point at a substation at which 2 or more electrical links join at which there is no bus

**nominal voltage** means the voltage at which particular equipment is designed to operate under normal circumstances

**nominated bid**—

- (a) *[Revoked]*
- (b) *[Revoked]*
- (c) *[Revoked]*
- (d) means the information that a **purchaser** submits to the **system operator** under clause 13.7 to indicate a reasonable estimate of the—
  - (i) **electricity** that the **purchaser** will purchase for a **dispatch-capable load station** at a **GXP**; or
  - (ii) **non-dispatch-capable load** that the **purchaser** will purchase at a **non-conforming GXP**; and
- (e) includes a deemed **nominated bid** under clause 13.8A

Clause 1.1(1) **nominated bid**: inserted, on 28 June 2012, by clause 4(a) of the Electricity Industry Participation (Demand-side Bidding and Forecasting) Code Amendment 2011.

Clause 1.1(1) **nominated bid**: amended, on 15 May 2014, by clause 5(5) of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

Clause 1.1(1) **nominated bid**: amended, on 19 December 2014, by clause 4(3) of the Electricity Industry Participation Code Amendment (Minor Code Amendments) (No 3) 2014.

Clause 1.1(1) **nominated bid** paragraph (d): amended, on 29 June 2017, by clause 4(4) of the Electricity Industry Participation Code Amendment (Shortened Gate Closure and Revised Bid and Offer Provisions) 2017.

**nominated dispatch bid** means a **nominated bid** that a **purchaser** submits to the **system operator** in relation to a **dispatch-capable load station** that the **purchaser** is making available to be **dispatched**

Clause 1.1(1) **nominated dispatch bid**: inserted, on 15 May 2014, by clause 5(1) of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

**nominated non-dispatch bid** means a **nominated bid** that a **purchaser** submits to the **system operator** in relation to—

- (a) **non-dispatch-capable load** at a **non-conforming GXP**; or
- (b) a **dispatch-capable load station** that the **purchaser** is not making available to be dispatched

Clause 1.1(1) **nominated non-dispatch bid**: inserted, on 15 May 2014, by clause 5(1) of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

**non-conforming GXP** means a **GXP** that has been determined by the **Authority** to be a **non-conforming GXP** under clause 13.27A or 13.27B(4)

Clause 1.1(1) **non-conforming GXP**: inserted, on 28 March 2012, by clause 4(a) of the Electricity Industry Participation (Demand-side Bidding and Forecasting) Code Amendment 2011.

**non-dispatch-capable load** means a quantity of **electricity** purchased at a **GXP** that is not purchased for 1 or more **dispatch-capable load stations**.

Clause 1.1(1) **non-dispatch-capable load**: inserted, on 15 May 2014, by clause 5(1) of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

**non half-hour metering** means the process of measuring and recording information—

- (a) relating to **electricity** conveyed; and
- (b) at intervals that are greater than 1 **trading period**

Clause 1.1(1) **non half-hour metering**: inserted, on 29 August 2013, by clause 4(1) of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011.

**non half-hour metering installation** means a **metering installation** used for **non half-hour metering**

Clause 1.1(1) **non half-hour metering installation**: inserted, on 29 August 2013, by clause 4(1) of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011.

**non-response schedule** means the schedule prepared by the **system operator**—

- (a) under clause 13.58(1)(b); and
- (b) for the purpose of assisting **generators, purchasers, consumers, ancillary service agents, and grid owners** to manage their resources

Clause 1.1(1) **non-response schedule**: inserted, on 28 June 2012, by clause 4(a) of the Electricity Industry Participation (Demand-side Bidding and Forecasting) Code Amendment 2011.

**non-transmission projects** includes investments in any of the following:

- (a) generation;
- (b) energy efficiency;
- (c) **demand-side** management;
- (d) **local network** augmentation;
- (e) improvements to the systems and processes of the **system operator**;
- (f) the provision of **ancillary services**

**normal band** means a frequency band between 49.8 Hertz and 50.2 Hertz (both inclusive)

**notified planned outage** means the outage of an **asset** that forms part of, or is connected to, the **grid** or **local network**—

- (a) that is planned by the relevant **asset owner**; and
- (b) for which the **asset owner** has given written notice to the **system operator** in accordance with **Technical Code D** of Schedule 8.3

Clause 1.1(1) **notified planned outages**: amended, on 23 February 2015, by clause 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 1.1(1) **notified planned outages**: replaced, on 5 October 2017, by clause 4(1)(d) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

**notify** [*Revoked*]

Clause 1.1(1) **notify**: revoked, on 5 October 2017, by clause 4(60) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

**notional embedding contracts** means contracts entered into before 1 April 2008 between **Transpower** and its customers, under which a customer's generation assets are treated as if they were physically connected to load in lieu of their existing connection to the **grid**

Clause 1.1(1) **national embedding contracts**: amended, on 23 February 2015, by clause 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 1.1(1) **notional embedding contracts**: amended, on 5 October 2017, by clause 4(43) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

**NSP** means a network supply point that is a **point of connection** between—

- (a) a **local network** and the **grid**; or
- (b) 2 **local networks**; or
- (c) a **local network** and an **embedded network**; or
- (d) 2 **embedded networks**; or
- (e) a **generator** and the **grid**

Clause 1.1(1) **network supply point**: amended, on 5 October 2017, by clause 4(42) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

**NSP identifier** means a unique identifier for an **NSP** created by the **reconciliation manager** in accordance with clause 28 of Schedule 11.1

**obligation FTR** means an **FTR** for which the terms and conditions provide that—

- (a) (excluding the **FTR acquisition cost**) the holder of the **FTR** is entitled to receive a payment when, for the **FTR period**, the difference between the price (calculated in accordance with the terms of the **FTR**) at the **hub** identified as hub B and the price at the **hub** identified as hub A in the **FTR** is positive; and
- (b) (excluding the **FTR acquisition cost**) the holder must make a payment when the difference between those prices is negative

Clause 1.1(1) **obligation FTR**: inserted, on 1 October 2011, by clause 4(1) of the Electricity Industry Participation (Financial Transmission Rights) Code Amendment 2011.

Clause 1.1(1) **obligation FTR**: amended, on 1 November 2012, by clause 4(3) of the Electricity Industry Participation (Financial Transmission Rights) Code Amendment 2012.

**offer** means the information that a **generator** submits to the **system operator** under clause 13.6(1), and includes any revised **offer** that a **generator** submits under clauses 13.17 to 13.19

Clause 1.1(1) **offer**: amended, on 15 May 2014, by clause 4(3) of the Electricity Industry Participation (Minor Code Amendments) Code Amendment 2014.

Clause 1.1(1) **offer**: substituted, on 29 June 2017, by clause 5(a) of the Electricity Industry Participation Code Amendment (Shortened Gate Closure and Revised Bid and Offer Provisions) 2017.

**offer stack** means the stack generated from ranking in price order, from lowest to highest, all **offers** to sell **electricity** as given to the **pricing manager** under clause 13.141(1)(c)

**offered FTR** means an **FTR** that has been offered into an **FTR reconfiguration auction**

Clause 1.1(1) **offered FTR**: inserted, on 1 November 2014, by clause 4(1) of the Electricity Industry Participation (FTR Reconfiguration Auctions) Code Amendment 2014.

**official conservation campaign** is a campaign to encourage **electricity** conservation that—

- (a) is commenced by the **system operator**; and
- (b) lasts for 1 week or more; and
- (c) covers—
  - (i) the South Island; or
  - (ii) all of New Zealand

Clause 1.1(1) **official conservation campaign**: inserted, on 1 April 2011, by clause 4(1) of the Electricity Industry

Participation (Customer Compensation Schemes) Code Amendment 2011.

**offtake** means the flow of **electricity** from the **grid** at a **grid exit point**

**operating account** means the trust account established by the **clearing manager** in accordance with clause 14.66

Clause 1.1(1) **operating account**: amended, on 24 March 2015, by clause 4(1)(o) of the Electricity Industry Participation (Settlement and Prudential Security) Code Amendment 2013.

**option FTR** means an **FTR** for which the terms and conditions provide that—

- (a) (excluding the **FTR acquisition cost**) the holder of the **FTR** is entitled to receive a payment when, for the **FTR period**, the difference between the price (calculated in accordance with the terms of the **FTR**) at the **hub** identified as hub B and the price at the **hub** identified as hub A in the **FTR** is positive; but
- (b) (excluding the **FTR acquisition cost**) the holder is not required to make a payment when the difference between those prices is negative

Clause 1.1(1) **option FTR**: inserted, on 1 October 2011, by clause 4(1) of the Electricity Industry Participation (Financial Transmission Rights) Code Amendment 2011.

Clause 1.1(1) **option FTR**: amended, on 1 November 2012, by clause 4(4) of the Electricity Industry Participation (Financial Transmission Rights) Code Amendment 2012.

**options contract** means a contract containing the right to buy or sell a financial derivative contract

**other party**, for the purposes of subpart 5 of Part 13, means the **party to a risk management contract** who did not submit information under clauses 13.219(1) to (4), 13.223(1), or 13.224, as the case may be

**outage**, for the purposes of Part 12, has the meaning given to it by clause 12.130

**outage constraint** means any **grid injection point** or **grid exit point** that has no load or generation connected to it in the modelling system, and of which the **system operator** gives written notice to the **reconciliation manager** under clause 15.15(a)

Clause 1.1(1) **outage constraint**: replaced, on 5 October 2017, by clause 4(1)(e) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

**outage plan**, for the purposes of Part 12, means the annual outage plan developed under the **Outage Protocol**

**Outage Protocol**, for the purposes of Part 12, means the Outage Protocol that is incorporated by reference in this Code under clause 12.150

**overall accuracy** *[Revoked]*

Clause 1.1(1) **overall accuracy**: revoked, on 29 August 2013, by clause 4(3) of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011.

**over frequency limit** means the maximum frequency of 50.5 Hz

**over frequency reserve** means an **ancillary service** that comprises an automatic reduction in the level of **injection** by a generating set to arrest an unplanned rise in system frequency

**participant** has the meaning given to it in section 5 of the **Act** and, for the purposes of Parts 8, 13, 14, and 14A, has the additional meaning set out in clause 1.5

Clause 1.1(1) **participant**: amended, on 5 October 2017, by clause 4(44) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

**participant identifier** means a unique 4 letter code assigned to a **participant** under clause 15.39 that is used to identify the **participant**, including in the reconciliation and **registry** processes

Clause 1.1(1) **participant identifier**: amended, on 15 May 2014, by clause 4(4) of the Electricity Industry Participation (Minor Code Amendments) Code Amendment 2014.

**participant rolling outage plan** means a plan developed by a **specified participant** under clauses 9.6 to 9.13

**partly loaded spinning reserve** means a form of **instantaneous reserve** consisting of spare capacity, held in reserve on a **generating unit**, generating, but not operating at full output, which is able to provide **fast instantaneous reserve** or **sustained instantaneous reserve** following a drop in system frequency to a specified level below 50 Hz

Clause 1.1(1) **partly loaded spinning reserve**: amended, on 5 October 2017, by clause 4(45) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

**party**, for the purposes of subpart 5 of Part 13, means either the **buyer** or **seller** under a **risk management contract** or both the **buyer** and **seller** under a **risk management contract**, as the case may be

**payee** *[Revoked]*

Clause 1.1(1) **payee**: substituted, on 1 October 2011, by clause 4(2) of the Electricity Industry Participation (Financial Transmission Rights) Code Amendment 2011.

Clause 1.1(1) **payee**: amended, on 15 May 2014, by clause 5(6) of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

Clause 1.1(1) **payee**: revoked, on 24 March 2015, by clause 4(1)(p) of the Electricity Industry Participation (Settlement and Prudential Security) Code Amendment 2013.

**payer** *[Revoked]*

Clause 1.1(1) **payer** paragraph (iv): inserted, on 1 October 2011, by clause 4(3) of the Electricity Industry Participation (Financial Transmission Rights) Code Amendment 2011.

Clause 1.1(1) **payer**: revoked, on 24 March 2015, by clause 4(1)(q) of the Electricity Industry Participation (Settlement and Prudential Security) Code Amendment 2013.

**permanent estimate** means a value sourced from an **estimated reading** that has passed the validation process in clauses 16 and 17 of Schedule 15.2 and has been calculated from **validated meter readings**

**pivotal** means—

- (a) in relation to a **generator**, that the total **demand** in a **trading period** at any 1 or more **nodes** would not have been met if the **generator** had not submitted **offers** for all or any of its **generating plant**; and
- (b) in relation to an **ancillary service agent**, that the total **demand** in a **trading period** for an **ancillary service** supplied by the **ancillary service agent** in an **island** would not have been met if the **ancillary service agent** had not submitted **reserve offers** for all or any of its capacity to provide **instantaneous reserve** in the **island**.

Clause 1.1(1) **pivotal**: inserted, on 17 July 2014, by clause 4(1) of the Electricity Industry Participation Code Amendment (Pivotal Supply) 2014.

**planned interruption**, for the purposes of Part 12, means an **interruption** caused by a **planned outage**



**planned outage**, for the purposes of Part 12, means an **outage** carried out in accordance with the planning requirements set out in the **Outage Protocol**

**point of connection** means a point at which **electricity** may flow into or out of a **network** and, for the purposes of **Technical Code A** of Schedule 8.3, means a **grid injection point** or a **grid exit point**

**point of measurement** *[Revoked]*

Clause 1.1(1) **point of measurement**: revoked, on 29 August 2013, by clause 4(3) of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011.

**point of service** means a normally contiguous electrical busbar of a particular voltage at which **Transpower**, as a **grid owner**, has agreed to provide services to 1 or more **designated transmission customers**

**point of supply**, in relation to any premises, means the point at which fittings, used or intended to be used for the purposes of supplying **electricity** to those premises, enter those premises

**policy statement** means the policy statement that is incorporated by reference in this Code under clause 8.10

**preceding year** *[Revoked]*

Clause 1.1(1) **preceding year**: revoked, on 5 October 2017, by clause 4(60) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

**preceding year day** *[Revoked]*

Clause 1.1(1) **preceding year day**: revoked, on 5 October 2017, by clause 4(60) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

**pre-dispatch schedule** *[Revoked]*

Clause 1.1(1) **pre-dispatch schedule**: revoked, on 28 June 2012, by clause 4(i) of the Electricity Industry Participation (Demand-side Bidding and Forecasting) Code Amendment 2011.

**preliminary sample** means the statistical sample that is required in order to establish parameter estimates to determine the appropriate size of the **profile sample**

**preliminary sample size** means the required size of the **preliminary sample**

**premium**, in relation to an **options contract**, means the dollar amount paid by the **buyer** of the **options contract** to the **seller**

**prescribed form** means a form prescribed from time to time by the **Authority**

**price**, for the purposes of Part 5, includes—

- (a) valuable consideration in any form, whether direct or indirect; and
- (b) any consideration that in effect relates to the acquisition of goods or services or the acquisition or disposition of any interest in land, although ostensibly relating to any other matter or thing

**price category** means the relevant code in the schedule **published** by a **distributor** that is used to unambiguously define the line charges for an **ICP**

**price-responsive schedule** means the schedule prepared by the **system operator**—

- (a) under clause 13.58(1)(a); and

- (b) for the purpose of assisting **generators, purchasers, consumers, ancillary service agents, and grid owners** to manage their resources

Clause 1.1(1) **price-responsive schedule**: inserted, on 28 June 2012, by clause 4(a) of the Electricity Industry Participation (Demand-side Bidding and Forecasting) Code Amendment 2011.

**pricing error** means an **interim price** or **interim reserve price** is incorrect or is likely to be incorrect, as the result of—

- (a) an incorrect input being used in calculating the **interim price** or **interim reserve price**; or  
(b) the **pricing manager** having followed an incorrect process in calculating that **interim price** or **interim reserve price**, in contravention of this Code

**pricing manager** means the **market operation service provider** who is for the time being appointed as pricing manager under this Code

**primary transmission equipment** means any plant or equipment forming part of the **grid** that enables the bulk transfer of **electricity**, including without limitation transmission circuits, busbars and switchgear

**principal performance obligation** and **PPO** mean a **system operator** obligation set out in any of clauses 7.2A to 7.2D

Clause 1.1(1) **principal performance obligations** and **PPOs**: amended, on 19 May 2016, by clause 4(3) of the Electricity Industry Participation Code Amendment (System Operator and Alignment with Statutory Objective) 2016.

**procurement plan** means the procurement plan that is incorporated by reference in this Code under clause 8.42

**profile** means a fixed or variable **electricity consumption pattern** assigned to a particular group of **meter** registers or **unmetered loads**

**profile acceptance limit** means the maximum value allowed for the sample **co-efficient of variation** calculated from the **preliminary sample**

**profile applicant** means the **participant** who submitted an application to the **Authority** to approve a new **profile** or a change to an existing **profile**, and may be a joint entity with more than 1 **participant** or an independent commercial entity acting on behalf of 1 or more **participants**

Clause 1.1(1) **profile applicant**: amended, on 5 October 2017, by clause 4(46) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

**profile class** means the grouping of 1 or more individual **profiles** that are applied to **metering installations** and loads with similar generic descriptions

**profile owner** means the legal entity that introduced the approved **profile** or is nominated as the **profile owner** in accordance with Schedule 15.5

**profile population** means all **ICP identifiers** included in a **profile**

**profile sample** means the statistical sample used to generate consumption data that is to be used to represent the load patterns of all **ICP identifiers** included in the **profile**

**profile sample size** means the required size of the **profile sample**

**provisional marginal location factor** means the factor that is determined by dividing the **provisional price** at a **grid exit point** or **grid injection point** by the **provisional price** at the relevant **reference point**

**provisional price** means a price in dollars and cents that has been **published** based on data relating to a **provisional price situation**. When a **provisional price** is **published**, the **provisional price** applies to all **trading periods** on the relevant **trading day**

**provisional price situation** means a **metering situation**, or a **SCADA situation**, or an **infeasibility situation**, or a **high spring washer price situation**

**provisional reserve price** means a price calculated in dollars and cents that has been **published** based on data relating to a **provisional price situation**

**public conservation period** means—

- (a) any period during which an **official conservation campaign** is running;
- (b) any period during which a **supply shortage declaration** is in force for 1 week or more

Clause 1.1(1) **public conservation period**: inserted, on 1 April 2011, by clause 4(1) of the Electricity Industry Participation (Customer Compensation Schemes) Code Amendment 2011.

**publicise** *[Revoked]*

Clause 1.1(1) **publicise**: revoked, on 5 October 2017, by clause 4(60) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

**publish** means—

- (a) in respect of information that the **Authority** is required to **publish** under this Code, to make the information available to the public, at no cost, on a website maintained by, or on behalf of, the **Authority**; or
- (b) in respect of information that a **participant** is required to **publish** under this Code, to make the information available to the public, at no cost, on a website maintained by, or on behalf of, the **participant**,—

and **published**, **publishes**, **publication**, and **publishing** have corresponding meanings

Clause 1.1(1) **publish**: replaced, on 5 October 2017, by clause 4(1)(f) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

**purchaser** means a person who buys **electricity** from the **clearing manager** and, for the purposes of Parts 8, 13, 14, and 14A, has the additional meaning set out in clause 1.5

Clause 1.1(1) **purchaser**: amended, on 5 October 2017, by clause 4(47) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

**qualifying customer** has the meaning set out in clause 9.21

Clause 1.1(1) **qualifying customer**: inserted, on 1 April 2011, by clause 4(1) of the Electricity Industry Participation (Customer Compensation Schemes) Code Amendment 2011.

**qualifying date** *[Revoked]*

Clause 1.1(1) **qualifying date**: inserted, on 1 April 2011, by clause 4(1) of the Electricity Industry Participation (Customer Compensation Schemes) Code Amendment 2011.

Clause 1.1(1) **qualifying date**: revoked, on 5 October 2017, by clause 4(60) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

**quantity**, for the purposes of subpart 5 of Part 13, means—

- (a) for a **contract for differences** or **options contract** the total volume in **MWh** of **electricity** to which the contract relates; or

- (b) for a **fixed-price physical supply contract**, the volume in **MWh** of **electricity** reasonably likely to be supplied under the contract

**ratio compensation** means a multiplier, used to convert **raw meter data** into **volume information**, that is developed from—

- (a) the connected ratio of **measuring transformers**; and  
(b) the number of **metering** elements; and  
(c) the resolution of the **meter**

Clause 1.1(1) **ratio compensation**: inserted, on 29 August 2013, by clause 4(1) of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011.

Clause 1.1(1) **ratio compensation**: amended, on 23 February 2015, by clause 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 1.1(1) **ratio compensation**: amended, on 5 October 2017, by clause 4(48) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

**raw meter data** means—

- (a) for the purposes of Part 10, information obtained by the **interrogation** of a **metering installation**; or  
(b) for the purposes of Part 15, information obtained from a **metering installation** by 1 of the following **interrogation** methods:  
(i) locally by way of a handheld computer or recording device (in which case it must take the form of a downloaded file); or  
(ii) locally by way of any other manual record (in which case it must take the form of the first entry in a database system); or  
(iii) remotely (in which case it must take the form of database records), but excluding data transmission between **meters** and data concentrators that are relaying information into the **back office**

Clause 1.1(1) **raw meter data**: substituted, on 29 August 2013, by clause 4(2)(s) of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011.

**reactive** means that component of the impedance at which the current and voltage are 90 degrees out of phase

**reactive capability** means the **reactive power** injection or absorption capability of **generating units** and other **reactive power** resources such as Static Var Compensators, capacitors and synchronous condensers, and includes **reactive power** capability of a **generating unit** during the normal course of the **generating unit** operations

**reactive current** means the component of electrical current on a **line** 90 degrees out of phase with the voltage on the **line**

Clause 1.1(1) **reactive current**: inserted, on 24 November 2016, by clause 4 of the Electricity Industry Participation Code Amendment (Generation Fault Ride Through) 2016.

**reactive energy** means the integration over time of the product of voltage and current and the sine of the phase angle between them, normally measured in kilovar hours (kvarh)

Clause 1.1(1) **reactive energy**: inserted, on 29 August 2013, by clause 4(1) of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011.

**reactive meter** means a **meter** used for the measurement of **reactive power**

**reactive power** means the product of voltage and current and the sine of the phase angle between them, and which is normally measured in kiloVolt-Amps reactive (kVAr)

**real time price** means a price for **electricity** at a **grid exit point** or a **grid injection point**, and the price for **instantaneous reserve** in dollars and cents for the **real time pricing period** determined in accordance with clause 13.88

Clause 1.1(1) **real time price**: amended, on 21 September 2012, by clause 4(6) of the Electricity Industry Participation (Minor Amendments) Code Amendment 2012.

**real time pricing period** means a period of 5 minutes starting on the hour or any multiple of 5 minutes past the hour on any **trading day**

**reasonable and prudent operating practice**, in relation to **distributed generation**, includes—

- (a) the industry operating standards; and
- (b) measures to avoid the injection of **electricity** from **distributed generation** that—
  - (i) exceeds the **distribution network capacity** at the point of injection; or
  - (ii) results in a significant adverse effect on voltage levels; or
  - (iii) results in a significant adverse effect on the quality and reliability of **electricity** conveyed to other users of the **distribution network**; and
- (c) the use or proposed use of reasonable and prudent measures to enable the connection of **distributed generation**

Clause 1.1(1) **reasonable and prudent operating practice**: amended, on 23 February 2015, by clause 4(10) of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 1.1(1) **reasonable and prudent operating practice**: amended, on 23 February 2015, by clause 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 1.1(1) **reasonable and prudent operating practice**: amended, on 5 October 2017, by clause 4(49) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

**reasonable and prudent system operator** [*Revoked*]

Clause 1.1(1) **reasonable and prudent system operator**: revoked, on 19 May 2016, by clause 4(1) of the Electricity Industry Participation Code Amendment (System Operator and Alignment with Statutory Objective) 2016.

**recalibration** means to repeat a **calibration** because a previous **calibration** has expired or become suspect, and **recalibrate** has a corresponding meaning

**recertification** means to repeat a **certification** because a previous **certification** has expired or been cancelled, and **recertified** and **recertify** have corresponding meanings

**reconciled quantity** means a quantity of **electricity** that has been reconciled by the **reconciliation manager**

**reconciliation information** means information specifying the amount of **electricity** sold to or purchased from the **clearing manager** in each **half hour** of a **reconciliation period** (or such other period as has been agreed to), calculated from and reconciled with **submission information** and the relevant **losses**, and after the process of balancing in accordance with clause 22 of Schedule 15.4

**reconciliation manager** means the **market operation service provider** who is for the time being appointed as reconciliation manager under this Code

**reconciliation participant** means a **participant** (excluding the **Authority** (even if the **Authority** acts as a **market operation service provider**) and the **Rulings Panel**) who is any of the following:

- (a) a **retailer** when purchasing **electricity** from, or selling **electricity** to, the **clearing manager**;
- (b) a **generator**;
- (c) a **network** owner;
- (d) a **distributor**;
- (e) a person who purchases **electricity** from or sells **electricity** to the **clearing manager**

**reconciliation period** means a calendar month, subsequent to a **consumption period**, during which the reconciliation process is performed in respect of the **electricity** conveyed during 1 or more **consumption periods**

Clause 1.1(1) **reconciliation period**: amended, on 1 June 2011, by clause 4(2) of the Electricity Industry Participation (Minor Amendments) Code Amendment 2011.

**reconciliation type** means a code that identifies the type of processing to be performed during reconciliation

**reconfigured FTR** means the portion of an **FTR** that was sold at an **FTR reconfiguration auction**

Clause 1.1(1) **reconfigured FTR**: inserted, on 1 November 2014, by clause 4(1) of the Electricity Industry Participation (FTR Reconfiguration Auctions) Code Amendment 2014.

**reference point** means,—

- (a) for the North Island,—
  - (i) the Haywards 220 kV bus to which the HVDC Pole 2 or Pole 3 **injection** or **offtake** is **electrically connected**; or
  - (ii) if there is no Pole 2 or Pole 3 **injection** or **offtake** that is **electrically connected** to a Haywards 220kV bus, the first indexed Haywards 220 kV **node**;
- (b) for the South Island,—
  - (i) the Benmore 220 kV bus to which the HVDC Pole 2 or Pole 3 **injection** or **offtake** is **electrically connected**; or
  - (ii) if there is no Pole 2 or Pole 3 **injection** or **offtake** that is **electrically connected** to a Benmore 220kV bus, the first indexed Benmore 220 kV **node**

Clause 1.1(1) **reference point**: substituted, on 1 July 2012, by clause 4(3) of the Electricity Industry Participation (HVDC Pole 3 Minor Amendments) Code Amendment 2012.

Clause 1.1(1) **reference point**: amended, on 23 February 2015, by clause 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 1.1(1) **reference point**: amended, on 5 October 2017, by clause 4(50) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

**reference standard** means a measuring instrument that has been **calibrated** by an **approved calibration laboratory** and is not used as a **working standard**

**register** means the register of **participants** maintained by the **Authority** under section 16 of the **Act**

**registered**, in relation to a **participant**, means that details of the **participant** are kept in the **register**

**registry** means the database maintained by the **Authority** to record information about **ICPs**

Clause 1.1(1) **registry** and **registry manager**: replaced, on 5 October 2017, by clause 4(1)(g) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

**registry manager** means the **market operation service provider** for the time being appointed as registry manager under this Code

Clause 1.1(1) **registry manager**: inserted, on 5 October 2017, by clause 4(61) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

**registry metering records** means the **metering records** set out in Table 1 of clause 7 of Schedule 11.4

Clause 1.1(1) **registry metering records**: inserted, on 29 August 2013, by clause 4(1) of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011.

**regulated terms** means the terms set out in Schedule 6.2

**relative standard error** means the error expressed as a percentage of the estimated parameter

**relevant contracts** *[Revoked]*

Clause 1.1(1) **relevant contracts**: revoked, on 24 March 2015, by clause 4(1)(r) of the Electricity Industry Participation (Settlement and Prudential Security) Code Amendment 2013.

**relevant information** *[Revoked]*

Clause 1.1(1) **relevant information**: amended, on 21 September 2012, by clause 4(7) of the Electricity Industry Participation (Minor Amendments) Code Amendment 2012.

Clause 1.1(1) **relevant information**: revoked, on 1 October 2013, by clause 4(3) of the Electricity Industry Participation (Disclosure Obligations) Code Amendment 2013.

**relevant local reconciliation contracts** means the contracts for the sale and/or the purchase of **electricity** within a **local network**

**relevant participant** *[Revoked]*

Clause 1.1(1) **relevant participant**: inserted, on 29 August 2013, by clause 4(1) of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011.

Clause 1.1(1) **relevant participant**: revoked, on 1 June 2017, by clause 4(2) of the Electricity Industry Participation Code Amendment (Requirements and Processes for Audits) 2016.

**relevant registration factor** means the mean difference over time between **metering installation** readings and **check metering information** readings at the relevant **grid exit point**

**republish** *[Revoked]*

Clause 1.1(1) **republish**: revoked, on 5 October 2017, by clause 4(60) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

**reserve offer** means the information that an **ancillary service agent** submits to the **system operator** under clauses 13.37 to 13.54 specifying the **instantaneous reserve** the **ancillary service agent** is willing and able to provide

Clause 1.1(1) **reserve offer**: substituted, on 28 June 2012, by clause 4(g) of the Electricity Industry Participation (Demand-side Bidding and Forecasting) Code Amendment 2011.

Clause 1.1(1) **reserve offer**: substituted, on 29 June 2017, by clause 5(b) of the Electricity Industry Participation Code Amendment (Shortened Gate Closure and Revised Bid and Offer Provisions) 2017.

**residual loss and constraint excess** means, in respect of a **billing period**, an amount available for the settlement of **FTRs** that is not required to settle **FTRs** for the **billing period**, but does not include any amount that is retained for the settlement of **FTRs** in a future **billing period** in accordance with clause 13.249(6)

Clause 1.1(1) **residual loss and constraint excess**: inserted, on 1 October 2011, by clause 4(1) of the Electricity Industry Participation (Financial Transmission Rights) Code Amendment 2011.

Clause 1.1(1) **residual loss and constraint excess**: amended, on 24 March 2015, by clause 4(1)(s) of the Electricity Industry Participation (Settlement and Prudential Security) Code Amendment 2013.

**resistive** means that component of the impedance that is where the current and voltage are in phase

**responsible party** means the person responsible for the installation, maintenance, operation and **interrogation** of a **metering installation** and the supply of **submission information** to the **reconciliation manager**

**retailer** means as follows:

- (a) except as provided in paragraphs (b) and (c), a **participant** who supplies **electricity** to another person for any purpose other than for resupply by the other person;
- (b) in Parts 1 (except for the definition of specified participant), 8, 10, and 12 to 15, a **participant** who supplies **electricity** to a **consumer** or to another **retailer**;
- (c) in subpart 4 of Part 9, the **retailer** defined in paragraph (a) who is recorded in the **registry** as being responsible for the **ICP** described in clause 9.21(1)(b)

Clause 1.1(1) **retailer**: substituted, on 1 April 2011, by clause 4(2) of the Electricity Industry Participation (Customer Compensation Schemes) Code Amendment 2011.

Clause 1.1(1) **retailer** para (b): amended, on 28 February 2015, by clause 4 of the Electricity Industry Participation Code Amendment (Trader Default) 2014.

Clause 1.1(1) **retailer**: amended, on 5 October 2017, by clause 4(51) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

#### **Rio Tinto agreement** *[Revoked]*

Clause 1.1(1) **Rio Tinto agreement**: revoked, on 16 December 2013, by clause 4(2)(c) of the Electricity Industry Participation (Revocation of Part 16) Code Amendment 2013.

#### **Rio Tinto party** *[Revoked]*

Clause 1.1(1) **Rio Tinto party**: revoked, on 16 December 2013, by clause 4(2)(d) of the Electricity Industry Participation (Revocation of Part 16) Code Amendment 2013.

**risk management contract**, for the purposes of subpart 5 of Part 13, means—

- (a) a **contract for differences**; or
- (b) a **fixed-price physical supply contract**; or
- (c) an **options contract**; but
- (d) does not include an **FTR**

Clause 1.1(1) **risk management contract**: amended, on 15 May 2014, by clause 4(5) of the Electricity Industry Participation (Minor Code Amendments) Code Amendment 2014.

**round power** means a mode of operation of the **HVDC link** where power is transferred in opposite directions on Pole 2 and Pole 3

Clause 1.1(1) **round power**: inserted, on 1 July 2012, by clause 4(4) of the Electricity Industry Participation (HVDC Pole 3 Minor Amendments) Code Amendment 2012.

**rules** means the Electricity Governance Rules 2003

**Rulings Panel** has the meaning given to it in section 5 of the **Act**



**sample date** means the most recent date when the **profile sample** was drawn or updated

**satisfactory state** means that none of the following occur on the power system:

- (a) insufficient **supply of electricity** to satisfy **demand for electricity** at any **grid exit point**;
- (b) **unacceptable overloading** of any **primary transmission equipment**;
- (c) **unacceptable voltage conditions**;
- (d) **system instability**

**SCADA** means the monitoring and remote control of equipment from a central location using computing technologies

**SCADA situation** means a situation where the **input information** to be given under clause 13.141(1)(a) is incorrect or incomplete, except when a reasonable estimate has been made by the **grid owner** under clause 13.141(1)(a)(ii)

Clause 1.1(1) **SCADA situation**: amended, on 15 May 2014, by clause 5(7) of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

**scaling factor**, for the purpose of Appendix A of Technical Code C of Schedule 8.3, means a factor applied to a measurement at 1 point to calculate a corresponding measurement at another point

Clause 1.1(1) **scaling factor**: inserted, on 1 June 2011, by clause 4(1) of the Electricity Industry Participation (Minor Amendments) Code Amendment 2011.

**schedule of dispatch prices, dispatch quantities, dispatch arc flows, dispatch group constraint arc flows, group constraint formulas and HVDC component flows**

*[Revoked]*

Clause 1.1(1) **schedule of dispatch prices, dispatch quantities, dispatch arc flows, dispatch group constraint arc flows, group constraint formulas and HVDC component flows**: revoked, on 28 June 2012, by clause 4(i) of the Electricity Industry Participation (Demand-side Bidding and Forecasting) Code Amendment 2011.

**scarcity pricing situation** means an **island scarcity pricing situation** or a **national scarcity pricing situation**

Clause 1.1(1) **scarcity pricing situation**: inserted, on 1 June 2013, by clause 4(a) of the Electricity Industry Participation (Scarcity Pricing) Code Amendment 2011.

**schedule length period** means,—

- (a) in relation to a **price-responsive schedule** or a **non-response schedule** prepared under clause 13.62(1)(a), the current **trading period** and the following 71 **trading periods**; and
- (b) in relation to a **price-responsive schedule** or a **non-response schedule** prepared under clause 13.62(1)(b), the current **trading period** and the following 7 **trading periods**

Clause 1.1(1) **schedule length period**: inserted, on 28 June 2012, by clause 4(a) of the Electricity Industry Participation (Demand-side Bidding and Forecasting) Code Amendment 2011.

**schedule period** means the current **trading period** and the following 71 **trading periods**

Clause 1.1(1) **schedule period**: substituted, on 28 June 2012, by clause 4(h) of the Electricity Industry Participation (Demand-side Bidding and Forecasting) Code Amendment 2011.

**scheduled quantity**, for the purposes of clauses 13.194 and 13.204(1)(a) and (b), means the sum of all the **offer quantities** at the relevant **grid injection point** at which the **final**

**price** is equal to or greater than the **offer** price for each of those **offer** quantities in the relevant **trading period**. For the **grid injection points** that form part of a **block dispatch group**, **scheduled quantity** is the sum of all the **offer** quantities of the individual **grid injection points** that form that **block dispatch group** at which the **final price** is equal to or greater than the **offer** price for each of those **offer** quantities in the relevant **trading period**

**scorecard rating** means the numerical value, pursuant to clauses 17 and 18 of Schedule 15.4, to rate the quality of each **retailer's** processes for the production of **submission information**

**seasonal adjustment shape** means the total energy consumption (expressed as daily kWh values) for all **NSP** derived **profiles** for all **retailers** in each **balancing area**

**secure state** means that the power system—

- (a) would be in a **satisfactory state**; and
- (b) would remain in a **satisfactory state** during and following a **single credible contingency event** occurring on the **grid**

**security of supply forecasting and information policy** means the security of supply forecasting and information policy that is incorporated by reference in this Code under clause 7.4

**selected component certification** means **certification** of a **metering installation** under clause 11(3) of Schedule 10.7

Clause 1.1(1) **selected component certification**: inserted, on 29 August 2013, by clause 4(1) of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011.

**seller**, for the purposes of subpart 5 of Part 13, means—

- (a) in respect of a **contract for differences**, the **floating-price payer**; or
- (b) in respect of a **fixed-price physical supply contract**, the **party** selling the **electricity**; or
- (c) in respect of an **options contract**, either—
  - (i) the **party** receiving the **premium**; or
  - (ii) if there is no **premium** under the **options contract**, the **party** who agrees to be the **seller** for the purposes of subpart 5 of Part 13; or
  - (iii) if neither **party** agrees to be the **seller**, the **party** whose name is the second alphabetically

**series**, for the purposes of determining the level of impedance of **branches** under Part 12, means an arrangement of **assets** where the **assets** comprising a **branch** have the same current flowing through them

**serious financial breach**—

- (a) means a failure by a **retailer**—
  - (i) to pay to a **distributor** an amount due and owing that exceeds the greater of \$100,000 or 20% of the actual charges payable by the **retailer** for the previous month, unless the amount is genuinely disputed by the **retailer**; or
  - (ii) to comply with the prudential requirements under a **use-of-system agreement** between the **retailer** and a **distributor**; but

- (b) does not include a failure by a **retailer** to comply with prudential requirements to the extent that the prudential requirements exceed what is permitted under clauses 12A.4 and 12A.5.

Clause 1.1(1) **serious financial breach**: inserted, on 16 December 2013, by clause 4 of the Electricity Industry Participation (Managing Retailer Default Situations) Code Amendment 2013.

**services access interface** means the point, at which access may be gained to the services available from a **metering installation**, that is—

- (a) recorded in the **certification report** by the **certifying ATH** for the **metering installation**; and
- (b) where information received from the **metering installation** can be made available to another person; and
- (c) where signals for services such as remote control of load (but not ripple control) can be injected

Clause 1.1(1) **services access interface**: inserted, on 29 August 2013, by clause 4(1) of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2013.

**settlement default** means failure of a **participant** to pay any amount payable when it becomes due under Part 14

Clause 1.1(1) **settlement default**: inserted, on 24 March 2015, by clause 4(1)(t) of the Electricity Industry Participation (Settlement and Prudential Security) Code Amendment 2013.

**shared unmetered load** means **unmetered load** at a single **point of connection** that is distributed across more than 1 **ICP**

**shortage situation** means an **island shortage situation** or a **national shortage situation**

Clause 1.1(1) **shortage situation**: inserted, on 1 June 2013, by clause 4(a) of the Electricity Industry Participation (Scarcity Pricing) Code Amendment 2011.

**shunt**, for the purposes of determining the level of impedance of **branches** under Part 12, means an arrangement of **assets** where the **assets** comprising a **branch** have the same voltage across the terminals

**shunt asset**, for the purposes of Part 12, means a shunt connected **asset** that is an **interconnection asset**

Clause 1.1(1) **shunt asset**: amended, on 23 February 2015, by clause 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 1.1(1) **shunt asset**: amended, on 5 October 2017, by clause 4(52) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

**simple random sampling without replacement** means the general procedure of drawing **consumers** from a **profile population** to form a sample. Each **consumer** in the **profile population** must have an equal probability of being drawn and may only be drawn once

**single credible contingency event** means an individual credible contingency event comprising any of the following:

- (a) a single transmission circuit interruption;
- (b) the failure or removal from operational service of a single **generating unit**;
- (c) an **HVDC link** single pole interruption;
- (d) the failure or removal from service of a single bus section;
- (e) a single inter-connecting transformer interruption;

- (f) the failure or removal from service of a single shunt connected reactive component

Clause 1.1(1) **single credible contingency event**: amended, on 23 February 2015, by clause 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 1.1(1) **single credible contingency event**: amended, on 5 October 2017, by clause 4(53) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

**single-line diagram** means a schematic diagram of a **network** interface

**software** means, other than in Parts 10 and 15, any software—

- (a) developed by or on behalf of a **market operation service provider** that is used by that **market operation service provider** to perform its obligations under this Code or its **market operation service provider agreement**; or
- (b) used by a **market operation service provider** exclusively for the purposes of performing its obligations under this Code or its **market operation service provider agreement**

Clause 1.1(1) **software**: amended, on 29 August 2013, by clause 4(2)(t) of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011.

**software specification** means the user requirements and other information describing the **software** in respect of the **market operation service providers**

**special credit clause** means a clause in a **contract for differences** that specifies that, if a **party** defaults during the **term** of the contract, the **party** that is not in default will be paid a specified amount or that on execution of the contract, the **party** that is not in default, is provided with a guarantee that payment will be made when the settlement amount reaches a certain threshold

**special protection scheme** means a protection scheme that takes predetermined action, including reconfiguration of the **grid**, changes of **demand**, or changes of generation, to counteract a particular condition once that condition is detected. **Special protection schemes** allow a power system to be operated to a higher pre-event capacity limit while still in a **secure state**. **Automatic under frequency load shedding** systems and **instantaneous reserves** are excluded from the requirements for **special protection schemes**

Clause 1.1(1) **special protection scheme**: inserted, on 1 June 2011, by clause 4(1) of the Electricity Industry Participation (Minor Amendments) Code Amendment 2011.

Clause 1.1(1) **special protection scheme**: amended, on 15 May 2014, by clause 4(6) of the Electricity Industry Participation (Minor Code Amendments) Code Amendment 2014.

Clause 1.1(1) **special protection scheme**: amended, on 1 February 2016, by clause 4(15) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

**specified participant** for the purposes of Part 9,—

- (a) means any of the following:
- (i) **distributor**;
  - (ii) **retailer**;
  - (iii) a **line owner**; and
- (b) includes a person who uses **electricity** that is conveyed to the person directly from the **grid**

**spot price risk disclosure statement** means a spot price risk disclosure statement prepared and submitted under clause 13.236A

Clause 1.1(1) **spot price risk disclosure statement**: inserted, on 1 December 2011, by clause 4 of the Electricity Industry Participation Code (Spot Price Risk Disclosure) Amendment 2011.

**statement of extended reserve obligations**, in relation to an **asset owner**, means the latest statement of obligation given to the **asset owner** by the **system operator** under clause 8.54P

Clause 1.1(1) **statement of extended reserve obligations**: inserted, on 7 August 2014, by clause 4(3) of the Electricity Industry Participation Code Amendment (Extended Reserve) 2014.

**statement of proposal**, in relation to a proposal, means a statement that contains—

- (a) a detailed statement of the proposal; and
- (b) a statement of the reasons for the proposal; and
- (c) an assessment of the reasonably practicable options, including the proposal; and
- (d) any other information relevant to considering the proposal.

**station dispatch group** means—

- (a) 1 or more **generating units** that inject into a single **grid injection point**; or
- (b) 1 or more **generating units** that are the subject of an agreement between the **system operator** and a **generator**,—

and is not a **block dispatch group**

**station net** means the sum of all **generating unit net** outputs for **generating units** at a single **generating station**, measured or calculated at its **point of connection**, but excludes **generating unit load** and any other active or **reactive power** (including losses) supplied between the **generating station** and the **point of connection**

Clause 1.1(1) **station net**: inserted, on 1 June 2011, by clause 4(1) of the Electricity Industry Participation (Minor Amendments) Code Amendment 2011.

**station security constraint** means any of the following:

- (a) a constraint applied by the **system operator** to a **generating unit** to provide **voltage support** or frequency reserve capacity as determined in accordance with Part 8;
- (b) a limitation in the offered capacity of a **grid owner's network** to convey **electricity** between **generating units** constituting a **station dispatch group**;
- (c) a limitation in the offered capacity of a **grid owner's network** to convey **electricity** between **generating units** constituting a **station dispatch group** and a **grid owner's network**—

and, if in paragraphs (b) and (c) above, the limitation in the offered capacity is either the offered capacity of a **grid owner's network** or a **grid system security limit**, as determined by the **system operator** in accordance with Part 8

**stress test** means a stress test **published** by the **Authority** under clause 13.236D

Clause 1.1(1) **stress test**: inserted, on 1 December 2011, by clause 4 of the Electricity Industry Participation Code (Spot Price Risk Disclosure) Amendment 2011.

Clause 1.1(1) **stress test**: amended, on 5 October 2017, by clause 4(54) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

**sub-block dispatch groups** means that grouping of **generating stations** or **generating units** within a **block dispatch group** into subgroups to take account of any **block security constraints** notified by the **system operator** in accordance with clauses 13.61(1) and 13.73(1)(j)

Clause 1.1(1) **sub-block dispatch groups**: amended, on 21 September 2012, by clause 4(8) of the Electricity Industry

Participation (Minor Amendments) Code Amendment 2012.

Clause 1.1(1) **sub-block dispatch groups**: amended, on 15 May 2014, by clause 5(8) of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

**sub-station dispatch group** means a grouping of **generating units** or **generating stations** within a **station dispatch group** into subgroups to take account of any **station security constraints** notified by the **system operator** in accordance with clauses 13.65(1) and 13.75(1)(g)

Clause 1.1(1) **sub-station dispatch groups**: amended, on 15 May 2014, by clause 5(9) of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

Clause 1.1(1) **sub-station dispatch groups**: amended, on 1 February 2016, by clause 4(16) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

**submission expiry date** means—

- (a) in the case of a submission on a **draft policy statement**, the date notified by the **Authority** in accordance with clause 8.12(2); and
- (b) in the case of a submission on a **draft procurement plan**, the date notified by the **Authority** in accordance with clause 8.44(2); and
- (c) in the case of a submission on the **transmission agreement** structure, the date notified by the **Authority** in accordance with clause 12.6(3); and
- (d) in the case of a submission on the draft **benchmark agreement**, the date notified by the **Authority** in accordance with clause 12.32(2); and
- (e) in the case of a submission on the draft **grid reliability standards**, the date notified by the **Authority** in accordance with clause 12.61(3); and
- (f) in the case of a submission on the issues paper, the date notified by the **Authority** in accordance with clause 12.82(1); and
- (g) in the case of a submission on the proposed **transmission pricing methodology**, the date notified by the **Authority** in accordance with clause 12.92(2)

Clause 1.1(1) **submission expiry date**: amended, on 19 December 2014, by clause 4(4) of the Electricity Industry Participation Code Amendment (Minor Code Amendments) (No 3) 2014.

**submission information** means **volume information** aggregated in accordance with clause 8 of Schedule 15.3 (and includes, if relevant, any **profile** shape or control times associated with a **profile**)

**subsidiary** means a subsidiary as defined in section 5 of the Companies Act 1993

**supply** means a measure of the rate of production of electrical energy

**supply shortage declaration** means a declaration made under clause 9.14

**suspension clause** means a clause in a **risk management contract** under which some or all of the obligations may be suspended due to an event directly relating to the **supply** (including transmission) or generation of **electricity** or the price at which **electricity** is supplied, including an inability to inject **electricity** into the **grid** as a result of an **outage** of or damage to the **grid** or a **grid injection point** or the price of **electricity** exceeding a level specified in the contract

**sustained instantaneous reserve** means—

- (a) for providers of **partly loaded spinning reserve** and **tail water depressed reserve**, the average additional output (in **MW**) provided during the first 60 seconds after a Contingent Event (as defined in the **policy statement**) that is

- sustained for at least 15 minutes after the Contingent Event (unless a new **dispatch instruction** is given before the expiry of that 15 minute period); and
- (b) for providers of **interruptible load**, the average drop in load (in **MW**) that occurs over the first 60 seconds after the **grid** system frequency falls to or below 49.2 Hz that is sustained until instructed by the **system operator**

**switch event meter reading**, in relation to a **meter** or **data storage device** that is located at an **ICP** that is being switched under Schedule 11.3, means—

- (a) a **validated meter reading**, if one is available; or
- (b) a reasonable estimate of the **meter reading** based on the **meter reading** contained in the final information provided in the switch file that the losing **trader** received when it gained the **ICP** if—
- (i) a **validated meter reading** is not available; and
- (ii) the losing **trader** has been recorded in the **registry** as being responsible for the **ICP** for a period of less than 3 months; or
- (c) in every other case, a **permanent estimate**

Clause 1.1(1) **switch event meter reading**: amended, on 9 October 2015, by clause 4 of the Electricity Industry Participation Code Amendment (ICP Switching) 2014.

**synchronised** means the condition whereby a synchronous machine is **electrically connected** to a **network** and the electrical angular velocity of the machine corresponds with the **network** frequency and **synchronise**, **de-synchronise**, **synchronising**, **synchronism** and **synchronisation** have corresponding meanings. Asynchronous **intermittent generating stations** must be treated as being **synchronised** for the purposes of subpart 2 of Part 8

Clause 1.1(1) **synchronised**: amended, on 23 February 2015, by clause 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 1.1(1) **synchronised**: amended, on 5 October 2017, by clause 4(55) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

**system instability** means operating conditions under which it is reasonably likely that 1 or more **generating units** may cease to be **synchronised** with the **grid**

**system number** means a coded number assigned to **assets** referred to in clause 2(1)(a) of **Technical Code A** of Schedule 8.3 for the purposes of the operation of the **grid** and the management of the **assets** that, when used in conjunction with a locality name, uniquely identifies the **assets**

**system operator** has the meaning given to it in section 5 of the **Act**

**system operator register** means the register kept by the **system operator** for recording **equivalence arrangements**, **dispensations**, and **alternative ancillary service arrangements** in accordance with clause 8 of Schedule 8.1 and clause 4 of Schedule 8.2. The **system operator** must maintain an up to date copy of the **system operator register** and **publish** it and keep it **published**

Clause 1.1(1) **system operator register**: amended, on 5 October 2017, by clause 4(56) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

**system operator rolling outage plan** means the system operating rolling outage plan that is incorporated by reference in this Code under clause 9.3

**system security** means the security and quality objectives set out in Part 8

**system security forecast** means the forecast prepared by the **system operator** under clause 8.15

**system security situation** means any situation that the **system operator** believes on reasonable grounds is not adequately mitigated by the current **policy statement** and 1 of the following exists:

- (a) the **system operator** reasonably considers that its ability to comply with the **principal performance obligations** is at risk:
- (b) there is a risk of significant damage to **assets**:
- (c) public safety is at risk

**system test** means a test conducted on an **asset**, with the **asset electrically connected** to the **grid**, to assess the interaction of the **asset** with the **grid**

Clause 1.1(1) **system test**: amended, on 23 February 2015, by clause 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 1.1(1) **system test**: amended, on 5 October 2017, by clause 4(57) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

**tail water depressed reserve** means a form of **instantaneous reserve** comprising a generating capacity on a motoring hydro generation set with no water flowing through the turbine that is available following a drop in system frequency

**technical codes** means the technical codes contained in Schedule 8.3

**temporary energisation** *[Revoked]*

Clause 1.1(1) **temporary energisation**: inserted, on 29 August 2013, by clause 4(1) of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011.

Clause 1.1(1) **temporary energisation**: revoked, on 5 October 2017, by clause 4(60) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

**term**, for the purposes of subpart 5 of Part 13, means the term of a **risk management contract**, being the period between the **effective date** and the **end date**

**test facility** means a device that permits access to voltage and current circuits for testing purposes while the **metering installation** is in normal service

**time block** means a block of **trading periods** either from 1 to 16 (inclusive) or from 17 to 48 (inclusive) in each **trading day**. On the day on which **New Zealand daylight time** begins **time block** means a block of **trading periods** either from 1 to 14 (inclusive) or from 15 to 46 (inclusive). On the day on which **New Zealand daylight time** ends, **time block** means a block of **trading periods** either from 1 to 18 (inclusive) or from 19 to 50 (inclusive)

**total auction revenue** means, for each **auction**, the aggregate of all amounts owing by all **generators** in the relevant **time block**

Clause 1.1(1) **total auction revenue**: amended, on 24 March 2015, by clause 4(1)(u) of the Electricity Industry Participation (Settlement and Prudential Security) Code Amendment 2013.

**traceable** means having the property of **traceability**

**traceability** is the property of the result of a measurement whereby it can be related to the SI units of measurement through an unbroken chain of comparisons, each with a stated **uncertainty**



**trade date**, for the purposes of subpart 5 of Part 13, means the date on which legally binding rights and obligations are created between the **parties** to a **risk management contract**

**trader** means a **retailer** or a **generator** or a **purchaser** who—

- (a) buys **electricity** from the **clearing manager**; or
- (b) sells **electricity** to the **clearing manager**; or
- (c) enters into an arrangement with another **retailer** or **generator** or **purchaser** to buy or sell contracts (or parts of contracts) for **electricity** for the purposes of this Code

Clause 1.1(1) **trader**: amended, on 29 August 2013, by clause 4(2)(u) of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011.

**trading day** means the period from 0000 hours until 2400 hours on any day

**trading period** means a period of 30 minutes ending on each hour or 30 minutes past each hour on any **trading day**

**trading rights** means, in relation to a **generator** or a **purchaser**, the rights conferred on the **generator** or **purchaser** by this Code in relation to the trading of **electricity**

**transfer** means transfer, sell, assign or otherwise dispose of an ownership interest

**transformer branch** means a **branch** that contains a transformer

**transmission alternative** *[Revoked]*

Clause 1.1(1) **transmission alternative**: amended, on 21 September 2012, by clause 4(9) of the Electricity Industry Participation (Minor Amendments) Code Amendment 2012.

Clause 1.1(1) **transmission alternative**: revoked, on 15 May 2014, by clause 4(7)(a) of the Electricity Industry Participation (Minor Code Amendments) Code Amendment 2014.

**transmission agreement** means an agreement for connection and/or use of the **grid** under subpart 2 of Part 12 (including, if relevant, an agreement for investment in the **grid**)

Clause 1.1(1) **transmission agreement**: amended, on 23 February 2015, by clause 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 1.1(1) **transmission agreement**: amended, on 5 October 2017, by clause 4(58) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

**transmission alternative** means an alternative to investment in the **grid**, including investment in local generation, energy efficiency, demand-side management and **distribution network** augmentation set out in Part 12

Clause 1.1(1) **transmission alternative**: inserted, on 15 May 2014, by clause 4(7)(b) of the Electricity Industry Participation (Minor Code Amendments) Code Amendment 2014.

**transmission pricing methodology** means the pricing methodology developed in accordance with subpart 4 of Part 12

**transmission security constraint** means a flow limit covered by clause 15(d)(i) or (iii) of Schedule 13.3, including any adjustments that have been made in accordance with clause 13(2)(d) and (f) of Schedule 13.3, but excluding a flow limit set in relation to the **HVDC link**

**Transpower** means Transpower New Zealand Limited

**type A co-generator** means the owner of a **type A industrial co-generating station**, in its capacity as owner of that **industrial co-generating station**

Clause 1.1(1) **type A co-generator**: inserted, on 27 May 2015, by clause 4(5) of the Electricity Industry Participation Code Amendment (Industrial Co-generation Dispatch Arrangements) 2015.

**type A industrial co-generating station** means an **industrial co-generating station** approved by the **Authority** under clause 8(1)(a)(i) of Schedule 13.4

Clause 1.1(1) **type A industrial co-generating station**: inserted, on 27 May 2015, by clause 4(5) of the Electricity Industry Participation Code Amendment (Industrial Co-generation Dispatch Arrangements) 2015.

**type B co-generator** means the owner of a **type B industrial co-generating station**, in its capacity as owner of that **industrial co-generating station**

Clause 1.1(1) **type B co-generator**: inserted, on 27 May 2015, by clause 4(5) of the Electricity Industry Participation Code Amendment (Industrial Co-generation Dispatch Arrangements) 2015.

**type B industrial co-generating station** means an **industrial co-generating station** approved by the **Authority** under clause 8(1)(a)(ii) of Schedule 13.4

Clause 1.1(1) **type B industrial co-generating station**: inserted, on 27 May 2015, by clause 4(5) of the Electricity Industry Participation Code Amendment (Industrial Co-generation Dispatch Arrangements) 2015.

**type-testing** means subjecting a sample or samples of a device to testing by an **approved test laboratory** accredited for the appropriate form of **type-testing** to verify compliance of that device with a prescribed standard or defined requirements, and **type-test** and **type-tested** have corresponding meaning

**unacceptable overloading** means that 1 or more **grid assets** exceed their stated capability, as set out in the **asset capability statements** for those **grid assets**, for the prevailing conditions, including without limitation ambient and seasonal temperature, pre-fault loading and time dependent loading cycles

**unaccounted for electricity** and **UFE** mean, for any **balancing area**, the quantity of **electricity**, as calculated per **trading period** by the **reconciliation manager** under clause 16 of Schedule 15.4.

**unacceptable voltage conditions** means voltages on the **grid** outside the limits specified in Part 8 of this Code

**uncertainty** means a parameter associated with the result of a measurement that characterises the dispersion of the values that could reasonably be attributed to the quantity being measured, and must be determined to a confidence level of 95% or greater unless otherwise specifically stated

**unconstrained cleared offer price** means the highest amount in dollars and cents per **MWh** specified for a **grid injection point** or a **grid exit point** in an **offer** that is—

- (a) provided to the **pricing manager** in accordance with clause 13.63; and
- (b) less than or equal to the price for **electricity** at that **grid injection point** or **grid exit point** calculated by the **software** used by the **pricing manager** to calculate **provisional prices** and **final prices**

**under-frequency event** means—

- (a) an interruption or reduction of **electricity** injected into the **grid**; or

- (b) an interruption or reduction of **electricity** injected from the **HVDC link** into the South Island **HVDC injection point** or the North Island **HVDC injection point**—

if there is, within any 60 second period, an aggregate loss of **injection of electricity** in excess of 60 MW (being the aggregate of the net reductions in the **injection of electricity** (expressed in MW) experienced at **grid injection points** and **HVDC injection points** by reason of paragraph (a) or (b)), and such loss causes the frequency on the **grid** (or any part of the **grid**) to fall below 49.25 Hz (as determined by **system operator** frequency logging)

**under-frequency limit** means the minimum frequency of 48hz for a contingent event

**undesirable trading situation** means any situation—

- (a) that threatens, or may threaten, confidence in, or the integrity of, the **wholesale market**; and
- (b) that, in the reasonable opinion of the **Authority**, cannot satisfactorily be resolved by any other mechanism available under this Code (but for the purposes of this paragraph a proceeding for a breach of clause 13.5A is not to be regarded as another mechanism for satisfactory resolution of a situation)

Clause 1.1(1) **undesirable trading situation**: substituted, on 18 July 2013, by clause 4(1) of the Electricity Industry Participation (Undesirable Trading Situation) Code Amendment 2013.

Clause 1.1(1) **undesirable trading situation**: amended, on 17 July 2014, by clause 4(2) of the Electricity Industry Participation Code Amendment (Pivotal Supply) 2014.

**unit cost** means the quantity calculated by dividing the product of the **consumer's half hour** consumption and the corresponding **half hour** prices over a defined time period by the sum of the **consumer's half hour** consumption over the same period of time (note that the **half hour** prices are based on the prices for trading at the **grid exit point** supplying energy to the **consumer**)

**unmetered load** means **electricity** consumed that is not directly recorded using a **meter**, but is calculated or estimated in accordance with this Code, and includes **shared unmetered load** and **distributed unmetered load**

**unoffered generation** means **electricity** supplied from a **generating** station for which an **offer** has not been made in accordance with clause 13.25, but which is purchased by the **clearing manager**

**unplanned interruption**, for the purposes of Part 12, means an **interruption** caused by an **unplanned outage**

**unplanned outage**, for the purposes of Part 12, means an **outage** not planned in accordance with the planning requirements set out in the **Outage Protocol**

**use-of-system agreement** means an agreement between a **distributor** and a **trader** that allows the **trader** to trade on the **distributor's local network** or **embedded network**

Clause 1.1(1) **use-of-system agreement**: inserted, on 1 December 2011, by clause 4(a) of the Electricity Industry Participation Code (Distributor Use-of-System Agreements and Distributor Tariffs) Amendment 2011.

Clause 1.1(1) **use-of-system agreement**: amended, on 1 February 2016, by clause 4(17) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

**validated meter reading** means a **meter reading** that has passed a **reconciliation participant's** validation process in accordance with clauses 16 and 17 of Schedule 15.2

**value of expected unserved energy** means the value of any **expected unserved energy** that applies under clause 4 of Schedule 12.2 or clause 12.39

Clause 1.1(1) **value of expected unserved energy**: amended, on 1 February 2016, by clause 4(18) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

**verification notice**, for the purposes of subpart 5 of Part 13, means the notice provided by the **other party** in accordance with clause 13.226(2)(b) or (c)

**voltage support** means an **ancillary service** comprising **reactive power injection** to the power system to boost voltage at the point of injection

**volume information** means the information describing the quantity of **electricity** generated, conveyed, or consumed that is calculated or estimated from **raw meter data** and supporting data, and in the case of **unmetered load**, calculated in accordance with this Code

**washup** means the correction procedure followed as set out in subpart 6 of Part 14 if incorrect information, including **volume information**, has been used in calculating an amount owing under Part 14

Clause 1.1(1) **washup**: amended, on 24 March 2015, by clause 4(1)(v) of the Electricity Industry Participation (Settlement and Prudential Security) Code Amendment 2013.

**wholesale market** means—

- (a) the spot market for **electricity**, including the processes for setting—
  - (i) **real time prices**:
  - (ii) **forecast prices** and **forecast reserve prices**:
  - (iii) **provisional prices** and **provisional reserve prices**:
  - (iv) **interim prices** and **interim reserve prices**:
  - (v) **final prices** and **final reserve prices**:

- (b) markets for **ancillary services**:

- (c) the hedge market for **electricity**, including the market for **FTRs**

Clause 1.1(1) **wholesale market**: substituted, on 18 July 2013, by clause 4(2) of the Electricity Industry Participation (Undesirable Trading Situation) Code Amendment 2013.

**wind generating station** means 1 or more **generating units** that are connected to the **grid** or to a **local network** and that inject into the **grid** or a **local network** (as the case may be) at a single point of **injection**, and for which wind is the primary power source

Clause 1.1(1) **wind generating station**: amended, on 23 February 2015, by clause 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 1.1(1) **wind generating station**: amended, on 5 October 2017, by clause 4(59) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

**winter capacity margin** means the difference between a measure of the expected capacity and expected demand from 1 April to 31 October between 7am and 10pm, expressed as a MW margin over demand

**winter energy margin** means the difference between the expected amount of energy that can be supplied and expected demand during the period 1 April to 30 September, expressed as a percentage of expected demand

**WITS** means the system operated by the **WITS manager**

Clause 1.1(1) **WITS**: inserted, on 5 October 2017, by clause 4(61) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

**WITS manager** means the **market operation service provider** for the time being appointed as wholesale information trading system provider under this Code

Clause 1.1(1) **WITS manager**: inserted, on 5 October 2017, by clause 4(61) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

**working day** *[Revoked]*

Clause 1.1(1) **working day**: revoked, on 5 October 2017, by clause 4(60) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

**working standard** means a measuring instrument that has been **calibrated** by an **approved calibration laboratory** or an **ATH**, that is used routinely for the **calibration of metering installations and metering components**

Clause 1.1(1) **working standard**: amended, on 29 August 2013, by clause 4(2)(v) of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011.

**works** has the meaning given to it in section 5 of the **Act**

**year** *[Revoked]*

Clause 1.1(1) **year**: revoked, on 5 October 2017, by clause 4(60) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

**zone** means the following **points of connection**:

- (a) zone 1: all **points of connection** to the **grid** in the North Island on circuits north of Huntly (excluding the Thames Valley spur):
  - (b) zone 2: all **points of connection** to the **grid** in the North Island not in zone 1:
  - (c) zone 3: all **points of connection** to the **grid** in the South Island on circuits north of (and not including) Islington, Coleridge, Hororata and Papanui:
  - (d) zone 4: all **points of connection** to the **grid** in the South Island not in zone 3
- (2) Any term that is defined in the **Act** and used, but not defined in this Code, has the same meaning as in the **Act**.

Compare: Electricity Governance Rules 2003 rule 1 part A

## 1.2 General principles of construction

In this Code—

- (a) a **participant** who carries on the functions or **business** of a **generator**, a **purchaser**, a **distributor**, a **grid owner** or a **market operation service provider** is, for the purpose of this Code, to be treated as a separate person for each such function or **business**, notwithstanding that at law all or any of the functions or **businesses** may be carried on by the same person; and
- (b) for the purpose of the arrangements expressed in this Code as to the supply and conveyance of **electricity** by a **generator** or a **purchaser** to another **generator** or **purchaser**, the supply and conveyance is deemed to have been made, notwithstanding that the physical flow of **electricity** from **generators** to **consumers** will not necessarily correspond with the contractual supply of **electricity** from **generators** to **purchasers**.

Compare: Electricity Governance Rules 2003 rule 2 part A

### 1.3 Special definition of “related”

For the purposes of this Code a person (the “first person”) is deemed to be related to another person (the “second person”) if the first person is related to the second person by reason of any domestic or **business** relationship (other than because the second person is a **customer** of the first person), such that the first person can reasonably be expected to have influence over the second person’s judgment in trading or investment matters, or to be consulted by the second person before any such judgment is formed, and if the first person is deemed to be so connected, the second person is also deemed to be related to the first person. No person is deemed to be related to any other person if either person is a shareholding minister as that term is defined in section 2 of the State-Owned Enterprises Act 1986 or any other New Zealand legislation, provided that person is acting in his or her capacity as a shareholding minister.

Compare: Electricity Governance Rules 2003 rule 3 part A

### 1.4 Special definition of “independent”

A person is deemed to be independent for the purposes of this Code, unless the person—

- (a) is a director or employee of a **participant**; or
- (b) has a direct or indirect financial interest, whether legal or beneficial, and whether as a shareholder, a partner or another equity holder in a **participant**, other than an interest not greater than 0.1% of the equity capital or funds of the relevant entity or, if that entity is a **subsidiary** of another entity, of the other entity; or
- (c) is a director or employee of a shareholder, a partner or another equity holder referred to in paragraph (b); or
- (d) is a person who regularly or from time to time trades, directly or indirectly, under this Code.

Compare: Electricity Governance Rules 2003 rule 4 part A

### 1.5 Special definition of “purchaser” and “participant”

- (1) For any matter that relates to a **trading period** during which a notice given under subclause (2) is in effect, a reference in Parts 8, 13, 14, or 14A of this Code to a **purchaser** or a **participant** that incurs financial obligations under this Code or owes an amount to the **clearing manager**, if it refers to a **participant** who is described as participant B in the notice, must be read as a reference to the **participant** who is described as participant A in the notice.
- (2) A **participant** (participant A) may, by notice in the form set out in Schedule 1.1, give notice to the **Authority** that, from a date specified in the notice, participant A will assume all rights and obligations under Parts 8, 13, 14, and 14A of this Code of another **participant** named in the notice (participant B) in participant B’s capacity as a **purchaser** and a **participant** that incurs financial obligations under this Code or owes an amount to the **clearing manager**.
- (3) A notice given under subclause (2) takes effect from the first **trading period** on the date specified in the notice. That date must be at least 30 **business days** after the date that the notice is given to the **Authority**.

- (4) A notice given under subclause (2) does not take effect unless the **Authority** approves it by notice to the **clearing manager**, participant A, and participant B.
- (5) Participant A or participant B may revoke a notice given under subclause (2) by giving notice to the **Authority** in the form set out in Schedule 1.2.
- (6) A revocation takes effect from the first **trading period** on the date specified in the notice. That date must be at least 15 **business days** after the date that the notice is given to the **Authority**.
- (7) A notice given under subclauses (2) or (5) must be signed by both participant A and participant B.
- (8) The **Authority** must **publish** notice of—
  - (a) each approval given by the **Authority** under subclause (4); and
  - (b) each revocation under subclause (5).
- (9) If, but for this clause, a provision in Parts 8, 13, 14, or 14A of this Code would confer a right or impose an obligation on participant B in participant B's capacity as a **purchaser** or a **participant** that incurs financial obligations under this Code or owes an amount to the **clearing manager**, that provision must be read as conferring the right or imposing the obligation on participant A in respect of every **trading period** during which a notice under subclause (2) is in effect.
- (10) Participant A is able to comply with any obligation that arises from the operation of subclause (9) by complying in aggregate with its own obligations under this Code and obligations that arise from the operation of subclause (9).
- (11) To avoid doubt, for any **trading period** during which a notice under subclause (2) is in effect, participant A is deemed to be the person who buys **electricity** from the **clearing manager** for participant B.

Compare: Electricity Governance Rules 2003 rule 5 part A

Heading of clause 1.5: amended, on 24 March 2015, by clause 4(2)(a) of the Electricity Industry Participation (Settlement and Prudential Security) Code Amendment 2013.

Clause 1.5(1): amended, on 24 March 2015, by clause 4(2)(b) of the Electricity Industry Participation (Settlement and Prudential Security) Code Amendment 2013.

Clause 1.5(2): amended, on 24 March 2015, by clause 4(2)(c) of the Electricity Industry Participation (Settlement and Prudential Security) Code Amendment 2013.

Clause 1.5(9): amended, on 24 March 2015, by clause 4(2)(d) of the Electricity Industry Participation (Settlement and Prudential Security) Code Amendment 2013.

### 1.5A Application of Code to distributors

Except in Parts 6, 9, and 12A, nothing in this Code applies to a **distributor** in respect of its **distribution** activities that are not conducted on a **network** that is—

- (a) directly connected to the **grid**; or
- (b) indirectly connected to the **grid** through 1 or more other **networks**.

Clause 1.5A: inserted, on 1 February 2016, by clause 5 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

Clause 1.5A: amended, on 5 October 2017, by clause 5 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### 1.6 Contents tables

The contents tables that appear at the beginning of this Code, and at the beginning of each Part, are included only to assist in reading this Code, and do not form part of it.

**1.7 Defined terms appear in bold**

Words and phrases appear in bold in this Code only to alert the reader to the fact that they are defined in this Part.



## Schedule 1.1

cl 1.5(2)

### Notice of assumption of rights and obligations under Parts 8, 13, 14, and 14A of the Electricity Industry Participation Code 2010

Heading: amended, on 24 March 2015, by clause 5(1) of the Electricity Industry Participation (Settlement and Prudential Security) Code Amendment 2013.

1. \_\_\_\_\_ (participant A) gives notice to the Electricity Authority under clause 1.5(2) of the Electricity Industry Participation Code 2010 that it will assume all rights and obligations of \_\_\_\_\_ (participant B) under Parts 8, 13, 14, and 14A of the Electricity Industry Participation Code 2010 in participant B's capacity as a purchaser and as a participant that incurs financial obligations under that Code or owes an amount to the clearing manager.
2. The notice given under clause 1 will, if approved by the Electricity Authority under clause 1.5(4) of the Electricity Industry Participation Code 2010, take effect from the first trading period on \_\_\_\_\_ and will continue until it is revoked by participant A or participant B under clause 1.5(5) of the Electricity Industry Participation Code 2010.

**SIGNED** for and on behalf of \_\_\_\_\_ )  
\_\_\_\_\_ by \_\_\_\_\_ )  
(participant A)

\_\_\_\_\_  
[insert name]

\_\_\_\_\_  
[insert occupation]

\_\_\_\_\_  
[insert date]

**SIGNED** for and on behalf of \_\_\_\_\_ )  
\_\_\_\_\_ by \_\_\_\_\_ )  
(participant B)

\_\_\_\_\_  
[insert name]

\_\_\_\_\_  
[insert occupation]

\_\_\_\_\_  
[insert date]

Compare: Electricity Governance Rules 2003 schedule A1 part A  
Schedule 1.1: amended, on 24 March 2015, by clause 5(2) of the Electricity Industry Participation (Settlement and Prudential Security) Code Amendment 2013.

**Electricity Industry Participation Code 2010**  
**Schedule 1.1**

---

Schedule 1.1: amended, on 5 October 2017, by clause 6 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

## Schedule 1.2

cl 1.5(5)

### Revocation of notice of assumption of rights and obligations under Parts 8, 13, 14, and 14A of the Electricity Industry Participation Code 2010

Heading: amended, on 24 March 2015, by clause 6(1) of the Electricity Industry Participation (Settlement and Prudential Security) Code Amendment 2013.

1. \_\_\_\_\_ gives notice to the Electricity Authority that the notice given to the Authority under clause 1.5(2) of the Electricity Industry Participation Code 2010 by \_\_\_\_\_ (participant A) on \_\_\_\_\_ that it would assume all rights and obligations under Parts 8, 13, 14, and 14A of the Electricity Industry Participation Code 2010 of \_\_\_\_\_ (participant B) in participant B's capacity as a purchaser and as a participant that incurs financial obligations under that Code or owes an amount to the clearing manager is revoked.
2. The revocation under clause 1 will take effect from the first trading period on \_\_\_\_\_.

**SIGNED** for and on behalf of \_\_\_\_\_ )  
\_\_\_\_\_ by \_\_\_\_\_ )  
(participant A)

\_\_\_\_\_  
[insert name]

\_\_\_\_\_  
[insert occupation]

\_\_\_\_\_  
[insert date]

**SIGNED** for and on behalf of \_\_\_\_\_ )  
\_\_\_\_\_ by \_\_\_\_\_ )  
(participant B)

\_\_\_\_\_  
[insert name]

\_\_\_\_\_  
[insert occupation]

\_\_\_\_\_  
[insert date]

Compare: Electricity Governance Rules 2003 schedule A2 part A  
Schedule 1.2: amended, on 24 March 2015, by clause 6(2) of the Electricity Industry Participation (Settlement and Prudential Security) Code Amendment 2013.

**Electricity Industry Participation Code 2010**  
**Schedule 1.1**

---

Schedule 1.2: amended, on 5 October 2017, by clause 7 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

# Electricity Industry Participation Code 2010

## Part 2 Availability of Code information

### Contents

	<i>Power to request Code information</i>
2.1	Requests for Code information
	<i>Information held by Authority</i>
2.2	Information held by Authority
	<i>Information held by other participants</i>
2.3	Information not held by Authority
2.4	Authority must contact participant believed to hold requested information
2.5	Participant must consider request
2.6	Code information should be made available to all participants unless good reason
2.7	Other reasons
2.8	Transfer of requests
2.9	Participants must not enter contracts that prejudice supply of Code information
2.10	Decision about supplying information
2.11	Process if participant agrees to supply information
2.12	Charges payable
2.13	Documents may include deletions
2.14	Process if participant refuses to supply information
2.15	Appeal

---

### *Power to request Code information*

#### **2.1 Requests for Code information**

- (1) A **participant** may request the **Authority** to make available to the **participant** (the requesting **participant**) any **Code information** held by the **Authority** or by any other **participant**.
- (2) The request must specify, with as much particularity as possible, the nature of the information sought and the name of the **participant** who is believed to hold the information.

Compare: SR 2003/374 r 15

### *Information held by Authority*

#### **2.2 Information held by Authority**

If the **Authority** receives a request for the supply of **Code information** that the **Authority** holds, the **Authority** must—

- (a) consider and process the request in accordance with the Official Information Act 1982; and
- (b) if the **Authority** proposes to provide the information to the requester, give prior written notice to the **participant** that supplied the information to the **Authority**.

Compare: SR 2003/374 r 16  
Clause 2.2(b): replaced, on 5 October 2017, by clause 8 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

*Information held by other participants*

**2.3 Information not held by Authority**

The rest of this Part applies if the **Authority** receives a request for the supply of **Code information** that the **Authority** does not hold.

Compare: SR 2003/374 r 17

**2.4 Authority must contact participant believed to hold requested information**

The **Authority** must, as soon as practicable after receiving a request for **Code information** that it does not hold, send a written notice to the **participant** who the **Authority** believes holds the relevant **Code information**—

- (a) giving the **participant** written notice of the request made to the **Authority**, and the name and address of the requesting **participant**; and
- (b) requesting the **participant** to either—
  - (i) supply the information, together with a note of the **participant's** charges (if any) in relation to the supply of information; or
  - (ii) supply reasons for refusing to supply the information.

Compare: SR 2003/374 r 18

Clause 2.4: amended, on 5 October 2017, by clause 9(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 2.4(a): amended, on 5 October 2017, by clause 9(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

**2.5 Participant must consider request**

A **participant** who receives a request under clause 2.4(b) must consider that request in accordance with clauses 2.6 to 2.8.

Compare: SR 2003/374 r 19

**2.6 Code information should be made available to all participants unless good reason**

- (1) The general principle to be followed by **participants** in relation to **Code information** is that **Code information** should be made available to all **participants** unless there is good reason for refusing to supply it.
- (2) A **participant** has good reason for refusing to supply **Code information** if the supply of the information would be likely to—
  - (a) breach a legislative, regulatory, or other legal requirement; or
  - (b) prejudice the maintenance and supervision of this Code, including the prevention, investigation, and detection of Code breaches and the right to a fair hearing before the **Rulings Panel**; or
  - (c) result in a disclosing **participant** breaching an obligation of confidentiality; or
  - (d) interfere with the privacy of natural persons; or
  - (e) create an improper gain or improper advantage for the requesting **participant** or any other **participant** or person; or

- (f) commercially disadvantage the disclosing **participant** or any other **participant** or person, in a material manner; or
- (g) prejudice the future supply of information that is required by a **market operation service provider** to perform any obligation under this Code.

Compare: SR 2003/374 r 20

## 2.7 Other reasons

A **participant** may also refuse to supply **Code information** if—

- (a) the information requested is, or will soon be, made available to the public; or
- (b) the information requested does not exist or cannot be found; or
- (c) the information requested cannot be made available without substantial collation or research and the **Authority** agrees that it is unreasonable to undertake the collation or research; or
- (d) the request is frivolous or vexatious or the information requested is trivial.

Compare: SR 2003/374 r 21

Clause 2.7(a): amended, on 5 October 2017, by clause 10 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

## 2.8 Transfer of requests

- (1) This clause applies if—

- (a) a notice is sent to a **participant** under clause 2.4(b); and
- (b) the information to which the request relates—
  - (i) is not held by the **participant** but is believed by the person dealing with the notice to be held by another **participant**; or
  - (ii) is believed by the person dealing with the notice to be more closely related to the activities of another **participant**.

- (2) The **participant** to which the notice was sent must promptly, and in any case not later than 10 **business days** after the day on which the notice is received, transfer the notice to the other **participant**, and inform the **Authority** accordingly.

Compare: SR 2003/374 r 22

Clause 2.8(1)(b)(ii): amended, on 5 October 2017, by clause 11(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 2.8(2): amended, on 5 October 2017, by clause 11(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

## 2.9 Participants must not enter contracts that prejudice supply of Code information

A **participant** must, so far as is reasonably practicable without materially affecting its business or its ability to meet its obligations under this Code, avoid entering into an obligation with a person that would have the effect of prejudicing that **participant's** ability to comply freely with the provisions of this Part.

Compare: SR 2003/374 r 23

## 2.10 Decision about supplying information

A **participant** must, as soon as practicable after considering a request, inform the **Authority** and the requesting **participant** of whether it agrees or refuses to supply all or part of the **Code information** requested.

Compare: SR 2003/374 r 24

### 2.11 Process if participant agrees to supply information

- (1) If a **participant** agrees to supply all or part of the **Code information** requested, the **participant** must, as soon as practicable,—
  - (a) inform the **Authority** and the requesting **participant** of the information that will be supplied, and the amount of any charges to be paid for the supply of that information under clause 2.12; and
  - (b) supply that information, with any deletions authorised by clause 2.13, to the **Authority**.
- (2) The **Authority** must, as soon as practicable after receiving the information, and any charges required to be paid in respect of it by the requesting **participant**, send the information to the requesting **participant**.

Compare: SR 2003/374 r 25

### 2.12 Charges payable

- (1) A **participant** that supplies **Code information** may charge the requesting **participant** for—
  - (a) the reasonable cost of labour and materials involved in supplying the information to the requesting **participant**; and
  - (b) any additional costs incurred as a result of a request for urgent availability.
- (2) The **participant** that supplies the **Code information**, or the **Authority**, may require the whole or any part of the charge to be paid in advance by the requesting **participant**.

Compare: SR 2003/374 r 26

### 2.13 Documents may include deletions

If the **Code information** requested is contained in a **document**, and there are good reasons for refusing to supply some of the information contained in the **document**, the **participant** supplying the information may supply a copy of the **document** with any deletions or alterations that are necessary.

Compare: SR 2003/374 r 27

### 2.14 Process if participant refuses to supply information

- (1) If the **participant** refuses to supply all or any of the **Code information** requested, the **participant** must, as soon as practicable, give written notice to the **Authority** and the requesting **participant** of both the refusal and of the reasons for the refusal.
- (2) The **Authority** must, as soon as practicable after receiving the notice, advise the requesting **participant** of its rights to appeal under clause 2.15.

Compare: SR 2003/374 r 28

Clause 2.14(1): amended, on 5 October 2017, by clause 12(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 2.14(2): amended, on 5 October 2017, by clause 12(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.



## 2.15 Appeal

A requesting **participant** who receives written notice under clause 2.14 that another **participant** refuses to supply any **Code information** may appeal that refusal by notice of appeal to the **Rulings Panel**.

Compare: SR 2003/374 r 29

Clause 2.15: amended, on 5 October 2017, by clause 13 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

# Electricity Industry Participation Code 2010

## Part 3 Market operation service providers

### Contents

3.1	Appointment of market operation service providers
3.2	Functions, rights, powers, and obligations of market operation service providers
3.2A	Market operation service providers to assist Authority to give effect to Authority's statutory objective
3.3	Term of appointment of market operation service provider
3.4	Terms of market operation service provider agreements
3.5	Publication of market operation service provider agreements
3.6	Insurance cover
	<i>Force majeure provisions relating to market operation service providers</i>
3.7	Relief of obligation because of force majeure
3.8	Effect of relief
3.9	Authority may contract elsewhere during force majeure event
3.10	Authority may terminate market operation service provider agreements
	<i>Disclosure to Authority</i>
3.11	Disclosure to Authority
	<i>Performance standards</i>
3.12	Performance standards to be agreed
	<i>Accountability of market operation service providers via self-review</i>
3.13	Self-review must be carried out by market operation service providers
3.14	Market operation service providers must report to Authority
	<i>Review of market operation service providers by Authority</i>
3.15	Review of market operation service providers
	<i>Market operation service provider software</i>
3.16	Software specifications for market operation service providers
3.17	Market operation service provider must arrange audit of software
3.18	Requirements for using software

---

### 3.1 Appointment of market operation service providers

- (1) The **Authority** must appoint a person or persons to perform each of the following **market operation service provider** roles:
- (a) **registry manager:**
  - (b) **reconciliation manager:**
  - (c) **pricing manager:**
  - (d) **clearing manager:**
  - (e) **FTR manager:**
  - (f) **WITS manager:**
  - (g) **extended reserve manager:**

- (h) any other role identified in regulations as a **market operation service provider** role and for which market operation services are provided under this Code.
- (2) *[Revoked]*.
- (3) The **system operator** is also a **market operation service provider**, but clauses 3.3, 3.10 and 3.15 do not apply to the **system operator**.
- (4) The **Authority** may also appoint a person or persons to act as an industry service provider in providing any service under this Code.

Compare: SR 2003/374 r 30

Clause 3.1(3): amended, on 19 May 2016, by clause 5 of the Electricity Industry Participation Code Amendment (System Operator and Alignment with Statutory Objective) 2016.

Clause 3.1(1): substituted, on 5 October 2017, by clause 14(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 3.1(2): revoked, on 5 October 2017, by clause 14(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### 3.2 Functions, rights, powers, and obligations of market operation service providers

A **market operation service provider** has the functions, rights, powers, and obligations set out in relation to that **market operation service provider** under this Code and Part 2 and Subpart 1 of Part 4 of the **Act**.

Compare: SR 2003/374 r 31

Clause 3.2: amended, on 5 October 2017, by clause 15 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

#### 3.2A Market operation service providers to assist Authority to give effect to Authority's statutory objective

- (1) Each **market operation service provider** must perform its obligations under this Code in a way that assists the **Authority** to give effect to the **Authority's** statutory objective.
- (2) The **system operator** must progressively increase the extent to which it assists the **Authority** to give effect to the **Authority's** statutory objective.
- (3) The **system operator** is not required to comply with subclause (1) when exercising discretion in real time in performing its functions.
- (4) This clause does not permit a **market operation service provider** to contravene any other provision of this Code.

Clause 3.2A: inserted, on 19 May 2016, by clause 6 of the Electricity Industry Participation Code Amendment (System Operator and Alignment with Statutory Objective) 2016.

### 3.3 Term of appointment of market operation service provider

- (1) A **market operation service provider's** term of appointment, and the date on which the term begins, is as agreed between the **Authority** and the **market operation service provider**.
- (2) The **Authority** may at any time terminate, re-appoint, or change the appointment of a person as a **market operation service provider**, subject to the terms of any agreement between that **market operation service provider** and the **Authority**.

Compare: SR 2003/374 r 32(1) and (2)

### 3.4 Terms of market operation service provider agreements

- (1) The remuneration of a **market operation service provider** is as agreed between the **Authority** and the **market operation service provider**.
- (2) The **Authority** and the **market operation service provider** may agree on any other terms and conditions, not inconsistent with the functions, rights, powers, and obligations of that **market operation service provider** under this Code and Part 2 and Subpart 1 of Part 4 of the **Act**.

Compare: SR 2003/374 r 33

Clause 3.4(2): amended, on 19 December 2014, by clause 5 of the Electricity Industry Participation Code Amendment (Minor Code Amendments) (No 3) 2014.

Clause 3.4(2): amended, on 5 October 2017, by clause 16 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### 3.5 Publication of market operation service provider agreements

The **Authority** must **publish** each **market operation service provider agreement**.

Compare: SR 2003/374 r 34

Clause 3.5: amended, on 5 October 2017, by clause 17 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### 3.6 Insurance cover

Each **market operation service provider** must at all times maintain any insurance cover that is required by the **Authority**, on terms and in respect of risks approved by the **Authority**, with an insurer approved by the **Authority**.

Compare: SR 2003/374 r 36

*Force majeure provisions relating to market operation service providers*

### 3.7 Relief of obligation because of force majeure

- (1) A **market operation service provider** is relieved of an obligation under this Code and under the Electricity Industry (Enforcement) Regulations 2010 to the extent that, and for so long as, it is unable to perform the obligation as a result of a **force majeure event**.
- (2) Subclause (1) applies only—
  - (a) if the **market operation service provider** promptly advises the **Authority** of—
    - (i) the details of the **force majeure event**; and
    - (ii) the obligation that cannot be performed; and
    - (iii) the likely duration of the inability to perform the obligation; and
  - (b) for so long as the **market operation service provider** uses its reasonable endeavours to overcome the inability to perform the obligation from which it seeks relief and to remove or mitigate the effect of the **force majeure event**; and
  - (c) if the **market operation service provider** provides the **Authority** with reports in accordance with subclauses (3) and (4).
- (3) As soon as practicable, but in any event no later than by the end of the month following the month in which the **market operation service provider** advises the **Authority** of a **force majeure event** under subclause (2)(a), the **market operation service provider** must provide the **Authority** with a written report that sets out—
  - (a) the full details of the **force majeure event**; and

- (b) the actions the **market operation service provider** is taking or intends to take to comply with subclause (2)(b); and
- (c) the proposed timeline for completing the actions.
- (4) By the end of each following month (unless the **Authority** advises that reports may be provided less frequently or are not required) the **market operation service provider** must provide the **Authority** with a written report that updates the information previously provided and includes any other matters related to the **force majeure event** that the **Authority** requests.
- (5) The **Authority** must **publish** the information provided under subclause (2)(a) and the reports provided under subclauses (3) and (4) as soon as practicable after receiving the information.
- (6) Despite subclause (5), the **Authority** must not **publish** or otherwise make available to the public any information or any part of a report if the **market operation service provider** advises the **Authority** (with reasons) that the **market operation service provider** considers that it would have good reason to refuse to supply the information or the part under clause 2.6 or clause 2.7.

Compare: SR 2003/374 r 38

Clause 3.7: substituted, on 1 November 2012, by clause 5 of the Electricity Industry Participation (Force Majeure) Code Amendment 2012.

Clause 3.7(5): amended, on 5 October 2017, by clause 18(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 3.7(6): amended, on 5 October 2017, by clause 18(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### 3.8 Effect of relief

If a **market operation service provider** is relieved of an obligation under clause 3.7,—

- (a) the **market operation service provider** is not liable for a breach of this Code or with the Electricity Industry (Enforcement) Regulations 2010 in respect of that obligation during the period for which the relief applies under that clause; and
- (b) any costs arising from the relief from the obligation lie where they fall, except that the **Authority** and the **market operation service provider** may agree to adjust the remuneration of the **market operation service provider**.

Compare: SR 2003/374 r 39

Clause 3.8(a): amended, on 1 November 2012, by clause 6 of the Electricity Industry Participation (Force Majeure) Code Amendment 2012.

### 3.9 Authority may contract elsewhere during force majeure event

For the duration of a **force majeure event**, the **Authority** may contract with others for the performance of an obligation that the **market operation service provider** fails to perform in accordance with this Code or with the Electricity Industry (Enforcement) Regulations 2010, or the relevant **market operation service provider agreement**.

Compare: SR 2003/374 r 40

Clause 3.9: amended, on 1 November 2012, by clause 7 of the Electricity Industry Participation (Force Majeure) Code Amendment 2012.

### 3.10 Authority may terminate market operation service provider agreements

If a **force majeure event** results in a **market operation service provider** being relieved of a material obligation for more than 30 continuous days, the **Authority** may terminate

the relevant **market operation service provider agreement** by written notice with immediate effect.

Compare: SR 2003/374 r 41(1)

#### *Disclosure to Authority*

### **3.11 Disclosure to Authority**

Each **market operation service provider** is entitled to disclose to the **Authority** all information received by it from any person as part of its provision of services under this Code and Part 2 and Subpart 1 of Part 4 of the **Act**.

Compare: SR 2003/374 r 42

Clause 3.11: amended, on 5 October 2017, by clause 19 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

#### *Performance standards*

### **3.12 Performance standards to be agreed**

The **Authority** and the relevant **market operation service provider** must, at the beginning of each year ending 30 June, seek to agree on a set of performance standards against which the **market operation service provider's** actual performance must be reported and measured at the end of the **financial year**.

Compare: SR 2003/374 r 43

Clause 3.12: amended, on 5 October 2017, by clause 20 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

#### *Accountability of market operation service providers via self-review*

### **3.13 Self-review must be carried out by market operation service providers**

- (1) Each **market operation service provider** must conduct, on a monthly basis, a self-review of its performance.
- (2) The review must concentrate on the **market operation service provider's** compliance with—
  - (a) its obligations under this Code and Part 2 and Subpart 1 of Part 4 of the **Act**; and
  - (b) the operation of this Code and Part 2 and Subpart 1 of Part 4 of the **Act**; and
  - (c) any performance standards agreed between the **market operation service provider** and the **Authority**; and
  - (d) the provisions of the **market operation service provider agreement**.

Compare: SR 2003/374 r 44

Clause 3.13(2)(a) and (b): amended, on 5 October 2017, by clause 21 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### **3.14 Market operation service providers must report to Authority**

- (1) Each **market operation service provider** must prepare a written report for the **Authority** on the results of the review carried out under clause 3.13.
- (1A) A **market operation service provider** must provide the report prepared under subclause (1) to the **Authority**—

- (a) within 10 **business days** after the end of each calendar month except after the month of December;
- (b) within 20 **business days** after the end of the month of December.
- (2) The report must contain details of—
  - (a) any circumstances identified by the **market operation service provider** in which it has failed, or may have failed, to comply with its obligations under this Code and Part 2 and Subpart 1 of Part 4 of the **Act**; and
  - (b) any event or series of events that, in the **market operation service provider's** view, highlight an area where a change to this Code may need to be considered; and
  - (c) any other matters that the **Authority**, in its reasonable discretion, considers appropriate and asks the **market operation service provider**, in writing within a reasonable time before the report is provided, to report on.

Compare: SR 2003/374 r 45

Clause 3.14(1): replaced, on 5 October 2017, by clause 22(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 3.14(1A): inserted, on 5 October 2017, by clause 22(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 3.14(2)(a): amended, on 5 October 2017, by clause 22(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

#### *Review of market operation service providers by Authority*

### **3.15 Review of market operation service providers**

- (1) At the end of each year ending 30 June, the **Authority** may review the manner in which each **market operation service provider** has performed its duties and obligations under this Code and Part 2 and Subpart 1 of Part 4 of the **Act**.
- (2) The review must concentrate on the **market operation service provider's** compliance with—
  - (a) its obligations under this Code and Part 2 and Subpart 1 of Part 4 of the **Act**; and
  - (b) the operation of this Code and Part 2 and Subpart 1 of Part 4 of the **Act**; and
  - (c) any performance standards agreed between the **market operation service provider** and the **Authority**; and
  - (d) the provisions of the **market operation service provider agreement**.

Compare: SR 2003/374 r 46

Clause 3.15: amended, on 5 October 2017, by clause 23 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

#### *Market operation service provider software*

### **3.16 Software specifications for market operation service providers**

- (1) This clause and clauses 3.17 and 3.18, apply only to **software** that the **market operation service provider agreement** requires the **market operation service provider** to use.
- (2) Unless otherwise agreed by the **Authority** in writing, the **software specification** for all **software** to be used by a **market operation service provider** must be set out or

described in the **market operation service provider agreement** for that **market operation service provider**.

- (3) Each **market operation service provider** must ensure that its **software** performs in accordance with the relevant **software specification** and this Code.

Compare: SR 2003/374 r 51(1AA) to (2)

### **3.17 Market operation service provider must arrange audit of software**

- (1) Unless otherwise agreed by the **Authority** in writing, each **market operation service provider** must arrange and pay for a suitably qualified independent person approved by the **Authority** to carry out—
- (a) before any **software** is first used by the **market operation service provider** in relation to this Code and Part 2 and Subpart 1 of Part 4 of the **Act**, an **audit** of all **software** and **software specifications** to be used by the **market operation service provider**; and
  - (b) an annual **audit** of all **software** used by the **market operation service provider**, within 1 month after 1 March in each year; and
  - (c) an **audit** of any changes to the **software** or the **software specification**, before it is used by the **market operation service provider**.
- (2) A **market operation service provider** must ensure that the person carrying out an **audit** under subclause (1) provides a report to the **Authority** as to—
- (a) the performance (including likely future performance) of all of the **software** in accordance with the relevant **software specification**; and
  - (b) any other matters that the **Authority** requires.

Compare: SR 2003/374 r 52

Clause 3.17(2): amended, on 1 February 2016, by clause 6 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

Clause 3.17(1)(a): amended, on 5 October 2017, by clause 24 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### **3.18 Requirements for using software**

A **market operation service provider** may not use any **software** unless—

- (a) the **market operation service provider** has provided to the **Authority**, in respect of that **software**, an **auditor's** report issued in accordance with clause 3.17(2); or
- (b) the **Authority** has agreed that no **audit** is required under clause 3.17(1).

Compare: SR 2003/374 r 53



# Electricity Industry Participation Code 2010

## Part 4

### Force majeure provisions relating to ancillary service agents

#### Contents

- 4.1 Relief of obligation because of force majeure
  - 4.2 Effect of relief
- 

#### 4.1 Relief of obligation because of force majeure

- (1) An **ancillary service agent** is relieved of an obligation under this Code and under the Electricity Industry (Enforcement) Regulations 2010 to the extent that, and for so long as, it is unable to perform the obligation as a result of a **force majeure event**.
- (2) Subclause (1) applies only—
  - (a) if the **ancillary service agent** advises the **system operator**, immediately after becoming aware of the existence of a **force majeure event**, of—
    - (i) the details of the **force majeure event**; and
    - (ii) the obligation that cannot be performed; and
    - (iii) the likely duration of the inability to perform the obligation; and
  - (b) for so long as the **ancillary service agent** uses its reasonable endeavours to overcome the inability to perform the obligation from which it seeks relief and to remove or mitigate the effect of the **force majeure event**; and
  - (c) if the **ancillary service agent** provides the **Authority** with reports in accordance with subclauses (4) and (5).
- (3) To avoid doubt, the relief in subclause (1) applies only if an **ancillary service agent** is acting in its capacity as an **ancillary service agent** under an **ancillary service arrangement**.
- (4) As soon as practicable, but in any event no later than by the end of the month following the month in which the **ancillary service agent** advises the **system operator** of a **force majeure event** under subclause (2)(a), the **ancillary service agent** must provide the **Authority** with a written report that sets out—
  - (a) the full details of the **force majeure event**; and
  - (b) the actions the **ancillary service agent** is taking or intends to take to comply with subclause (2)(b); and
  - (c) the proposed timeline for completing the actions.
- (5) By the end of each following month (unless the **Authority** advises that reports may be provided less frequently or are not required) the **ancillary service agent** must provide the **Authority** with a written report that updates the information previously provided and includes any other matters related to the **force majeure event** that the **Authority** requests.
- (6) The **Authority** must **publish** the information provided under subclause (2)(a) and the reports provided under subclauses (4) and (5) as soon as practicable after receiving the information.

- (7) Despite subclause (6), the **Authority** must not **publish** or otherwise make available to the public any information or any part of a report if the **ancillary service agent** advises the **Authority** (with reasons) that the **ancillary service agent** considers that it would have good reason to refuse to supply the information or the part under clause 2.6 or clause 2.7.

Compare: SR 2003/374 r 53B

Clause 4.1: substituted, on 1 November 2012, by clause 8 of the Electricity Industry Participation (Force Majeure) Code Amendment 2012.

Clause 4.1(6): amended, on 5 October 2017, by clause 25(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 4.1(7): amended, on 5 October 2017, by clause 25(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

## 4.2 Effect of relief

If an **ancillary service agent** is relieved of an obligation under clause 4.1,—

- (a) the **ancillary service agent** is not liable for a breach of this Code or of the Electricity Industry (Enforcement) Regulations 2010 in respect of that obligation during the period for which the relief applies under that clause; and
- (b) any costs arising from the relief from the obligation lie where they fall, except that the **system operator** and the **ancillary service agent** may agree to adjust the remuneration of the **ancillary service agent**.

Compare: SR 2003/374 r 53C

Clause 4.2(a): amended, on 21 September 2012, by clause 5 of the Electricity Industry Participation (Minor Amendments) Code Amendment 2012.

Clause 4.2(a): amended, on 1 November 2012, by clause 9 of the Electricity Industry Participation (Force Majeure) Code Amendment 2012.

# Electricity Industry Participation Code 2010

## Part 5

### Regime for dealing with undesirable trading situations

#### Contents

- 5.1 Occurrence of undesirable trading situation
  - 5.1A Time limit for investigating undesirable trading situation
  - 5.2 Actions Authority may take to correct undesirable trading situation
  - 5.3 Authority must consult with system operator
  - 5.4 Authority must consult with participants
  - 5.5 Authority must attempt to correct and restore normal operation as soon as possible
- 

#### 5.1 Occurrence of undesirable trading situation

- (1) If the **Authority** suspects or anticipates the development, or possible development, of an **undesirable trading situation**, the **Authority** may investigate the matter.
- (2) The following are examples of what the **Authority** may consider to constitute an **undesirable trading situation**:
  - (a) manipulative or attempted manipulative trading activity;
  - (b) conduct in relation to trading that is misleading or deceptive, or is likely to mislead or deceive;
  - (c) unwarranted speculation or an undesirable practice;
  - (d) material breach of any law;
  - (e) a situation that threatens orderly trading or proper settlement;
  - (f) any exceptional or unforeseen circumstance that is contrary to the public interest.
- (3) To avoid doubt,—
  - (a) the list of examples in subclause (2) is not an exhaustive list, and does not prevent the **Authority** from finding that an **undesirable trading situation** is developing or has developed in other circumstances; and
  - (b) an example listed in subclause (2) does not constitute an **undesirable trading situation** unless the example comes within the definition of that term in Part 1.

Compare: SR 2003/374 r 54

Clause 5.1(2) and (3): inserted, on 18 July 2013, by clause 5 of the Electricity Industry Participation (Undesirable Trading Situation) Code Amendment 2013.

#### 5.1A Time limit for investigating undesirable trading situation

Despite clause 5.1(1), the **Authority** must not commence an investigation if more than 10 **business days** have passed since the situation, which the **Authority** suspects or anticipates may be an **undesirable trading situation**, occurred.

Clause 5.1A: inserted, on 18 July 2013, by clause 6 of the Electricity Industry Participation (Undesirable Trading Situation) Code Amendment 2013.

Clause 5.1A: amended, on 15 May 2014, by clause 5 of the Electricity Industry Participation (Minor Code Amendments) Code Amendment 2014.

## 5.2 Actions Authority may take to correct undesirable trading situation

- (1) If the **Authority** finds that an **undesirable trading situation** is developing or has developed, it may take any action that—
  - (a) the **Authority** considers is necessary to correct the **undesirable trading situation**; and
  - (b) relates to an aspect of the **electricity** industry that the **Authority** could regulate in this Code under section 32 of the **Act**.
- (2) The actions that the **Authority** may take under subclause (1) include any 1 or more of the following:
  - (a) directing that an activity be suspended, limited, or stopped, either generally or for a specified period;
  - (b) directing that completion of trades be deferred for a specified period;
  - (c) directing that any trades be closed out or settled at a specified price;
  - (d) directing a **participant** to take any actions that will, in the **Authority's** opinion, correct or assist in overcoming the **undesirable trading situation**.
- (2A) A direction given to a **participant** under subclause (2)(d)—
  - (a) may be inconsistent with this Code; but
  - (b) must not be inconsistent with the **Act**, or any other law.
- (3) The **participant** must comply promptly with a direction given to it in writing.
- (4) A **participant** is not liable to any other **participant** in relation to the taking of an action, or an omission, that is reasonably necessary for compliance with an **Authority** direction under this clause.
- (5) A **participant** does not breach this Code if it acts in accordance with a direction given under subclause (2)(d).

Compare: SR 2003/374 r 56

Clause 5.2(1): substituted, on 18 July 2013, by clause 7(1) of the Electricity Industry Participation (Undesirable Trading Situation) Code Amendment 2013.

Clause 5.2(2): substituted, on 18 July 2013, by clause 7(2) of the Electricity Industry Participation (Undesirable Trading Situation) Code Amendment 2013.

Clause 5.2(2A): inserted, on 18 July 2013, by clause 7(2) of the Electricity Industry Participation (Undesirable Trading Situation) Code Amendment 2013.

Clause 5.2(4): amended, on 18 July 2013, by clause 7(3) of the Electricity Industry Participation (Undesirable Trading Situation) Code Amendment 2013.

Clause 5.2(5): inserted, on 18 July 2013, by clause 7(4) of the Electricity Industry Participation (Undesirable Trading Situation) Code Amendment 2013.

## 5.3 Authority must consult with system operator

- (1) The **Authority** must consult with the **system operator** if—
  - (a) the **Authority** is considering taking an action under clause 5.2 to correct an **undesirable trading situation**; and
  - (b) it is possible that the action may have an effect on **system security**.
- (2) The **system operator** must maintain procedures that are necessary to enable it to respond immediately to the **Authority**, and provide information as soon as reasonably practicable, if the **Authority** consults the **system operator** under this clause.

Compare: SR 2003/374 r 58

**5.4 Authority must consult with participants**

If the **Authority** finds that an **undesirable trading situation** is developing or has developed, the **Authority** must—

- (a) immediately advise all **registered participants** of its findings and of any actions that the **Authority** intends to take, or has taken, to correct the **undesirable trading situation**; and
- (b) unless the **Authority** considers that it is impractical to do so, consult with affected **participants** before taking the action.

Compare: SR 2003/374 r 59

**5.5 Authority must attempt to correct and restore normal operation as soon as possible**

The **Authority** must attempt to correct every **undesirable trading situation** and, consistently with section 15 of the **Act**, restore the normal operation of the **wholesale market** as soon as possible.

Compare: SR 2003/374 r 60

# Electricity Industry Participation Code 2010

## Part 6 Connection of distributed generation

### Contents

- 6.1 Contents of this Part
- 6.2 Purpose
- 6.2A Application of Part to distributors in respect of embedded networks
- 6.2B Application of Part to distributors in respect of systems of lines not directly or indirectly connected to grid
- 6.3 Distributors must make information publicly available
- 6.4 Process for obtaining approval
- 6.4A Distributor and distributed generator may agree to simpler process for existing connection
- 6.5 Connection contract
- 6.6 Connection on regulated terms
- 6.7 Extra terms
- 6.8 Dispute resolution
- 6.9 Pricing principles
- 6.10 *[Revoked]*
- 6.11 Distributors must act at arm's length
- 6.12 This Part does not affect rights and obligations under Code
- Transitional provisions*
- 6.13 This Part does not apply to earlier connections

### Schedule 6.1

#### Process for obtaining approval

##### *Preliminary provisions*

##### *Part 1*

##### *Applications for distributed generation 10 kW or less in total*

##### *Application process*

##### *Post-approval process*

##### *Part 1A*

##### *Part 2*

##### *Applications for distributed generation above 10 kW in total*

##### *Initial application process*

##### *Final application process*

##### *Post-approval process*

##### *Part 3*

##### *General provisions*

##### *Confidentiality*

##### *Annual reporting and record keeping*

##### *Costs*

### Schedule 6.2

#### Regulated terms for distributed generation

*General*

*Meters*

*Access*

*Interruptions and disconnections*

*Confidentiality*

*Pricing*

*Liability*

**Schedule 6.3**

**Default dispute resolution process**

**Schedule 6.4**

**Pricing principles**

*Share of generation-driven costs*

*Repayment of previously funded investment*

*Non-firm connection service*

**Schedule 6.5**

**Prescribed maximum fees**

---

**6.1 Contents of this Part**

This Part specifies—

- (a) a framework to enable the connection and continued connection of **distributed generation** if consistent with **connection and operation standards**; and
- (b) in Schedule 6.1, processes (including time frames) under which **distributed generators** may—
  - (i) connect **distributed generation**; or
  - (ii) continue an existing connection of **distributed generation** if the connection contract for the **distributed generation**—
    - (A) is in force and the **distributed generator** wishes to extend the term of the connection contract; or
    - (B) has expired; or
  - (iii) continue an existing connection of **distributed generation** that is connected without a connection contract if the **regulated terms** do not apply; or
  - (iv) change the **nameplate capacity** or fuel type of connected **distributed generation**; and
- (c) in Schedule 6.2, the **regulated terms** that apply to the connection of **distributed generation** in the absence of contractually agreed terms; and
- (d) in Schedule 6.3, a default dispute resolution process for disputes related to this Part; and
- (e) in Schedule 6.4, the pricing principles to be applied for the purposes of this Part; and
- (f) in Schedule 6.5, prescribed maximum fees.

Compare: SR 2007/219 r 4

Clause 6.1(a) and (b): substituted, on 23 February 2015, by clause 5 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 6.1(a): amended, on 5 October 2017, by clause 26(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 6.1(b): amended, on 5 October 2017, by clause 26(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 6.1(c): amended, on 23 February 2015, by clause 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 6.1(c): amended, on 5 October 2017, by clause 26(3) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

## 6.2 Purpose

The purpose of this Part is to enable **distributed generation** to be connected to a **distribution network** or to a **consumer installation** that is connected to a **distribution network**, if being connected is consistent with **connection and operation standards**. .

Compare: SR 2007/219 r 3

Clause 6.2: amended, on 23 February 2015, by clauses 6 and 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 6.2: replaced, on 5 October 2017, by clause 27 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### 6.2A Application of Part to distributors in respect of embedded networks

Nothing in this Part applies to—

- (a) a **distributor** in respect of the **distributor's** ownership or operation of an **embedded network** that conveys less than 5 GWh of **electricity** per annum; or
- (b) a **distributed generator** when the **distributed generator** wishes to connect or has **distributed generation** connected to such an **embedded network**.

Clause 6.2A: inserted, on 1 February 2016, by clause 7 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

Clause 6.2A(b): amended, on 5 October 2017, by clause 28 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### 6.2B Application of Part to distributors in respect of systems of lines not directly or indirectly connected to grid

Nothing in this Part applies to—

- (a) a **distributor** in respect of the **distributor's** ownership or operation of a system of **lines** that is used for providing **line function services** only to the **distributor**; or
- (b) a **distributor** in respect of the **distributor's** ownership or operation of a system of **lines**—
  - (i) that conveys less than 5 GWh of **electricity** per annum; and
  - (ii) that is not—
    - (A) directly connected to the **grid**; or
    - (B) indirectly connected to the **grid** through 1 or more other **networks**; or
- (c) a **distributed generator** when the **distributed generator** wishes to connect or has **distributed generation** connected to a system of **lines** described in paragraph (b).

Heading: amended, on 5 October 2017, by clause 29(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 6.2B: inserted, on 1 February 2016, by clause 7 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

Clause 6.2B(b)(ii)(A) and (B): amended, on 5 October 2017, by clause 29(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 6.2B(c): amended, on 5 October 2017, by clause 29(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.



### 6.3 Distributors must make information publicly available

- (1) The purpose of this clause is to require each **distributor** to make certain information publicly available to enable the approval of **distributed generation** under Schedule 6.1.
- (2) Each **distributor** must make publicly available, free of charge, from its office and Internet site,—
  - (a) forms for applications under Schedule 6.1; and
  - (b) the **distributor's connection and operation standards**; and
  - (c) a copy of the **regulated terms**, together with an explanation of how the **regulated terms** will apply if—
    - (i) approval is granted under Schedule 6.1; and
    - (ii) the **distributor** and the **distributed generator** do not enter into a connection contract; and
  - (d) a statement of the circumstances in which **distributed generation** will be, or may be, curtailed or interrupted from time to time in order to ensure that the **distributor's other connection and operation standards** are met; and
  - (da) a list of all locations on its **distribution network** that the **distributor**—
    - (i) knows to be subject to **export congestion**; or
    - (ii) expects to become subject to **export congestion** within the next 12 months; and
  - (e) a list of any fees that the **distributor** charges under Schedule 6.1, which must not exceed the relevant maximum fees prescribed in Schedule 6.5; and
  - (f) a list of the makes and models of inverters that the **distributor** has approved for connection to its **distribution network**; and
  - (g) the **distributor's** contact information for any enquiries relating to the connection of **distributed generation** to its **distribution network**.
- (3) The application forms referred to in subclause (2)(a) must specify the information, including any supporting documents, that must be provided with an application under Schedule 6.1.

Compare: SR 2007/219 r 6

Clause 6.3(1): substituted, on 23 February 2015, by clause 7(1) of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 6.3(2)(a) – (c): substituted, on 23 February 2015, by clause 7(2) of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 6.3(2)(c)(ii), (f) and (g): amended, on 5 October 2017, by clause 30(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 6.3(2)(d): amended, on 23 February 2015, by clause 7(3) of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 6.3(2)(d): amended, on 5 October 2017, by clause 30(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 6.3(2)(da): inserted, on 23 February 2015, by clause 7(4) of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 6.3(2)(e): substituted, on 23 February 2015, by clause 7(5) of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 6.3(2)(f) and (g): inserted, on 23 February 2015, by clause 7(5) of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 6.3(3): substituted, on 23 February 2015, by clause 7(6) of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

### 6.4 Process for obtaining approval

- (1) Schedule 6.1 applies if a **distributed generator** wishes to—

- (a) connect **distributed generation**, whether on the **regulated terms** or on other terms; or
  - (b) continue an existing connection of **distributed generation** if the connection contract for the **distributed generation**—
    - (i) is in force and the **distributed generator** wishes to extend the term of the connection contract; or
    - (ii) has expired; or
  - (c) continue an existing connection of **distributed generation** that is connected without a connection contract if the **regulated terms** do not apply; or
  - (d) change the **nameplate capacity** or fuel type of connected **distributed generation**.
- (2) A **distributor** must approve an application submitted under Schedule 6.1 if the application complies with the requirements of that Schedule.
- (3) Except as provided in clause 6.4A, a **distributor** cannot contract out of the provisions of Schedule 6.1 with a **distributed generator**.

Compare: SR 2007/219 r 7

Clause 6.4: substituted, on 23 February 2015, by clause 8 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 6.4(1): amended, on 5 October 2017, by clause 31 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

#### **6.4A Distributor and distributed generator may agree to simpler process for existing connection**

A **distributor** and a **distributed generator** may agree a simpler process for the continued connection of **distributed generation** to the **distributor's distribution network** than the relevant process set out in Schedule 6.1 if—

- (a) a connection contract for the **distributed generation**—
  - (i) is in force and the **distributed generator** wishes to extend the term of the connection contract; or
  - (ii) has expired; or
- (b) the **distributed generation** is connected without a connection contract; or
- (c) there is a change in the **nameplate capacity** or fuel type of the **distributed generation**.

Clause 6.4A: inserted, on 23 February 2015, by clause 8 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 6.4A: amended, on 5 October 2017, by clause 32 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

#### **6.5 Connection contract**

If a **distributor** and a **distributed generator** enter into a contract for the connection of **distributed generation**,—

- (a) their rights and obligations in respect of the connection of the **distributed generation** are governed by that contract, and accordingly the **regulated terms** do not apply; and
- (b) a breach of the terms of that contract is not a breach of this Code.

Compare: SR 2007/219 r 8

Heading: amended, on 23 February 2015, by clause 9 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 6.5: amended, on 23 February 2015, by clauses 9 and 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 6.5: amended, on 5 October 2017, by clause 33 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

## 6.6 Connection on regulated terms

- (1) Schedule 6.2 sets out the **regulated terms** for the connection of **distributed generation**.
- (2) The **regulated terms** apply in the following circumstances:
  - (a) if a **distributor** and a **distributed generator** do not enter into a connection contract by the expiry of the period for negotiating a connection contract under clauses 9 or 24 of Schedule 6.1:
  - (b) in accordance with clause 9G of Schedule 6.1.
- (3) If the **regulated terms** apply,—
  - (a) the parties' rights and obligations in respect of the connection of the **distributed generation** are governed by the **regulated terms**; and
  - (b) a breach of the **regulated terms** is not a breach of contract.
- (4) Despite this clause, a **distributor** and a **distributed generator** may at any time, by agreement, enter into a connection contract that will apply instead of the **regulated terms**.

Compare: SR 2007/219 r 9

Clause 6.6: amended, on 5 October 2017, by clause 34 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 6.6(1): amended, on 23 February 2015, by clause 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 6.6(2) and (4): substituted, on 23 February 2015, by clause 10 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 6.6(3): amended, on 23 February 2015, by clause 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

## 6.7 Extra terms

- (1) The parties' rights and obligations in respect of a connection on the **regulated terms** are also governed by any other terms and conditions that—
  - (a) were made publicly available under clause 6.3(2)(d) in a statement of the terms and conditions that would apply to **distributed generation** if there is congestion on the **distribution network**; or
  - (b) cover any other incidental matters (for example, invoicing procedures) if—
    - (i) the matters are not covered by the **regulated terms**; and
    - (ii) the other matters are reasonable terms and conditions that either were proposed by the **distributor** during the 30 **business day** negotiation period as part of a connection contract or are terms that would be implied by law if the connection was under a connection contract; and
    - (iii) the other terms and conditions do not contradict any of the **regulated terms**.
- (2) In this Part, if the parties have agreed to change all or any part of 1 or more of the **regulated terms** as part of a binding contract, the resulting contract is, in total, a connection contract on terms that apply instead of the **regulated terms** for the purposes of this Part.

Compare: SR 2007/219 r 10

Clause 6.7: amended, on 23 February 2015, by clauses 11 and 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 6.7: amended, on 5 October 2017, by clause 35 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

## 6.8 Dispute resolution

- (1) Subject to subclause (2), Schedule 6.3 applies to a dispute between a **distributed generator** that is a **participant** and a **distributor** arising from any one of the following—
- (a) an allegation that a party has breached any of the **regulated terms** that apply under clause 6.6(2); and
  - (aa) an allegation that conditions specified by the **distributor** under clause 18 of Schedule 6.1 are not reasonably required; and
  - (ab) an allegation that a party has not attempted to negotiate in good faith under clause 6 or clause 21 of Schedule 6.1; and
  - (b) an allegation that a party has breached any of the other provisions of this Part.
- (2) However, Schedule 6.3 does not apply to disputes between a **distributed generator** and a **distributor**—
- (a) arising from an allegation that a party has breached any of the terms of a connection contract; or
  - (b) arising from an allegation that a party has breached any of the extra terms referred to in clause 6.7(1); or
  - (c) that the **distributed generator** and the **distributor** have agreed should be determined by any other agreed method (for example, under any dispute resolution scheme under section 95 of the **Act**).

Compare: SR 2007/219 r 11

Clause 6.8: amended, on 5 October 2017, by clause 36 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 6.8(1) and (1)(a): amended, on 23 February 2015, by clause 12(1) and (2) of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 6.8(1)(aa) and (ab): inserted, on 23 February 2015, by clause 12(3) of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 6.8(1)(b): substituted, on 23 February 2015, by clause 12(4) of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 6.8(2)(a): amended, on 23 February 2015, by clauses 12(5) and 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

## 6.9 Pricing principles

Schedule 6.4 applies in accordance with—

- (a) clause 19 of Schedule 6.2; and
- (b) clause 4 of Schedule 6.3.

Compare: SR 2007/219 r 12

Clause 6.9(a): amended, on 23 February 2015, by clause 13 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

## 6.10 *[Revoked]*

Compare: SR 2007/219 r 13

Clause 6.10: revoked, on 23 February 2015, by clause 14 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

## 6.11 Distributors must act at arm's length

A **distributor** must use, in respect of all **distributed generators**, the same reasonable efforts in processing and considering applications and notices under Schedule 6.1, regardless of—

- (a) whether the **distributor** has an ownership interest or a beneficial interest in the **distributed generator**; or
- (b) who the **distributed generator** is.

Compare: SR 2007/219 r 14

Heading: amended, on 23 February 2015, by clause 15(1) of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 6.11 and 6.11(a): amended, on 23 February 2015, by clause 15(2) of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 6.11(b): substituted, on 23 February 2015, by clause 15(3) of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

## **6.12 This Part does not affect rights and obligations under Code**

This Part does not affect any rights or obligations of a **distributor** or a **distributed generator** under any other clause in this Code.

Compare: SR 2007/219 r 15

### *Transitional provisions*

## **6.13 This Part does not apply to earlier connections**

This Part does not apply in relation to, or affect, any **distributed generation** that was connected under a contract entered into before 30 August 2007, except for the purpose of renewing or extending the term of the contract.

Compare: SR 2007/219 r 17

Clause 6.13: substituted, on 23 February 2015, by clause 16 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 6.13: amended, on 5 October 2017, by clause 37 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

## Schedule 6.1

### Process for obtaining approval

cl 6.4

Heading: amended, on 23 February 2015, by clause 17 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

#### Contents

##### *Preliminary provisions*

- 1A Contents of this Schedule
- 1B Distributed generator must apply
- 1C How Parts apply to applications
- 1D When application may be made under Part 1A

#### **Part 1**

Applications for distributed generation 10 kW or less in total

- 1 Contents of this Part

##### *Application process*

- 2 Applications under this Part of this Schedule
- 3 Distributor's decision on application
- 4 Extension of time by mutual agreement for distributor to process application
- 5 Distributed generator must give notice of intention to negotiate

##### *Post-approval process*

- 6 30 business days to negotiate connection contract if distributed generator notifies intention to proceed
- 7 Testing and inspection
- 8 Connection of distributed generation if connection contract negotiated
- 9 Connection of distributed generation on regulated terms if connection contract not negotiated

#### **Part 1A**

Applications for distributed generation of 10 kW or less in total in specified circumstances

- 9A Contents of this Part
- 9B Application for distributed generation of 10 kW or less in total in specified circumstances
- 9C Distributor may inspect distributed generation
- 9D Export congestion
- 9E Non-compliance or incomplete information
- 9F Notice of final approval
- 9G Regulated terms apply
- 9H When distributed generator may connect to distribution network

#### **Part 2**

Applications for distributed generation above 10 kW in total

- 10 Contents of this Part

##### *Initial application process*

- 11 Distributed generator must make initial application and give information
- 12 Distributor must give information to distributed generator

- 13 Other matters to assist with decision making  
14 Distributor and distributed generator must make reasonable endeavours regarding new information

*Final application process*

- 15 Distributed generator must make final application  
16 Notice to third parties  
17 Priority of final applications  
18 Distributor's decision on application  
19 Time within which distributor must decide final applications  
20 Distributed generator must give notice of intention to proceed

*Post-approval process*

- 21 30 business days to negotiate connection contract if distributed generator notifies intention to proceed  
22 Testing and inspection  
23 Connection of distributed generation if connection contract negotiated  
24 Connection of distributed generation on regulated terms if connection contract not negotiated

**Part 3**

General provisions

*Confidentiality*

- 25 Confidentiality of information provided

*Annual reporting and record keeping*

- 26 *[Revoked]*  
27 *[Revoked]*  
28 Distributors must keep records

*Costs*

- 29 *Responsibility for costs under this Schedule*
- 

*Preliminary provisions*

**1A Contents of this Schedule**

This Schedule specifies the procedures for processing applications from **distributed generators** for the connection or continued connection of **distributed generation**.

Clause 1A: amended, on 5 October 2017, by clause 38 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

**1B Distributed generator must apply**

Subject to clause 6.4A and clause 1D, a **distributed generator** that owns or operates **distributed generation** must apply to a **distributor** if it wishes to—

- (a) connect the **distributed generation** to the **distributor's distribution network**; or  
(b) continue an existing connection of the **distributed generation** to the **distributor's distribution network** if a connection contract for the **distributed generation**—  
(i) is in force and the **distributed generator** wishes to extend the term of the connection contract; or

- (ii) has expired; or
- (c) continue an existing connection of the **distributed generation** to the **distributor's distribution network** that is connected without a connection contract if the **regulated terms** do not apply; or
- (d) change the **nameplate capacity** or fuel type of the **distributed generation** connected to the **distributor's distribution network**.

Clause 1B: amended, on 5 October 2017, by clause 39 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

## 1C How Parts apply to applications

This Schedule applies to applications made under clause 1B as follows:

- (a) Part 1 applies to applications in respect of **distributed generation** that has a **nameplate capacity** of 10 kW or less in total, unless the **distributed generator** has elected, under clause 1D, to apply under Part 1A:
- (b) Part 1A applies to applications in respect of **distributed generation** that has a **nameplate capacity** of 10 kW or less in total, if the **distributed generator** has elected, under clause 1D, to apply under Part 1A:
- (c) Part 2 applies to applications in respect of **distributed generation** that has a **nameplate capacity** of more than 10 kW in total.

## 1D When application may be made under Part 1A

A **distributed generator** may elect to apply to a **distributor** under Part 1A instead of Part 1 if the **distributed generation** to which the application relates—

- (a) is designed and installed in accordance with AS 4777.1; and
- (b) incorporates an inverter that has been tested and issued a Declaration of Conformity with AS/NZS 4777.2 by a laboratory with accreditation issued or recognised by International Accreditation New Zealand; and
- (c) has protection settings that meet the **distributor's connection and operation standards**.

Cross heading and clauses 1A to 1D: inserted, on 23 February 2015, by clause 18 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 1D(b): amended, on 20 October 2016, by clause 4 of the Electricity Industry Participation Code Amendment (Inverter Standard for Distributed Generation) 2016.

# Part 1

## Applications for distributed generation 10 kW or less in total

Heading: amended, on 23 February 2015, by clause 19 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

## 1 Contents of this Part

- (1) This Part applies to applications relating to **distributed generation** that has a **nameplate capacity** of 10 kW or less in total, unless the **distributed generator** that owns or operates the **distributed generation** has elected, under clause 1D, to apply under Part 1A.
- (2) This Part of this Schedule provides for a 1-stage application process.

Compare: SR 2007/219 clause 1 Schedule 1

Clause 1(1): substituted, on 23 February 2015, by clause 20 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.



*Application process*

**2 Applications under this Part of this Schedule**

(1) *[Revoked]*

(2) A **distributed generator** must apply to a **distributor** by—

- (a) using the application form provided by the **distributor** that is publicly available under clause 6.3(2)(a); and
- (b) providing any information in respect of the **distributed generation** to which the application relates that is—
  - (i) referred to in subclause (3); and
  - (ii) specified by the **distributor** under clause 6.3(3) as being required to be provided with the application; and
- (c) paying the application fee (if any) specified by the **distributor** in accordance with clause 6.3(2)(e).

(3) The information may include the following:

- (a) the full name and address of the **distributed generator** and the contact details of a person that the **distributor** may contact regarding the **distributed generation**:
- (aa) whether the application is to—
  - (i) connect **distributed generation**; or
  - (ii) continue an existing connection of **distributed generation** that is connected in accordance with a connection contract if the connection contract—
    - (A) is in force and the **distributed generator** wishes to extend the term of the connection contract; or
    - (B) has expired; or
  - (iii) continue an existing connection of **distributed generation** that is connected without a connection contract; or
  - (iv) change the **nameplate capacity** or fuel type of connected **distributed generation**:
- (b) evidence of the **nameplate capacity** that the **distributed generation** will have, or other suitable evidence that the **distributed generation** is or will only be capable of generating **electricity** at a rate of 10 kW or less:
- (ba) if the application is to change the **nameplate capacity** or fuel type of connected **distributed generation**—
  - (i) the **nameplate capacity** that the **distributed generation** will have after the change; and
  - (ii) the aggregate **nameplate capacity** that all **distributed generation** that is connected at the **point of connection** at which the **distributed generation** is connected will have after the change; and
  - (iii) the fuel type that the **distributed generation** will have after the change:
- (c) details of the fuel type of the **distributed generation** (for example, solar, wind, or liquid fuel):
- (d) a brief description of the physical location at the address at which the **distributed generation** is or will be connected:
- (da) if the application is to connect **distributed generation**, when the **distributed generator** expects the **distributed generation** to be connected:

- (e) technical specifications of the **distributed generation** and **associated equipment**, including the following:
    - (i) technical specifications of equipment that allows the **distributed generation** to be **electrically disconnected** from the **distribution network** on loss of mains voltage:
    - (ii) manufacturer's rating of equipment:
    - (iii) number of phases:
    - (iv) proposed or current **point of connection** to the **distribution network** (for example, the **ICP identifier** and street address):
    - (v) details of either or both of any inverter and battery storage:
    - (vi) details of any load at the proposed or current **point of connection**:
    - (vii) details of the voltage (for example, 415 V or 11 kV) when it is **electrically connected**:
  - (f) information showing how the **distributed generation** complies with the **distributor's connection and operation standards**:
  - (g) any additional information or documents that are reasonably required by the **distributor**.
- (4) *[Revoked]*
- (5) The **distributor** must, within 5 **business days** of receiving an application, give written notice to the applicant advising whether or not the application is complete.

Compare: SR 2007/219 clause 2 Schedule 1

Heading: amended, on 23 February 2015, by clause 21(1) of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 2: amended, on 5 October 2017, by clause 40(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 2(1): revoked, on 23 February 2015, by clause 21(2) of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 2(2): substituted, on 23 February 2015, by clause 21(3) of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 2(3)(a): amended, on 23 February 2015, by clause 21(4) of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 2(3)(aa): inserted, on 23 February 2015, by clause 21(5) of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 2(3)(aa): amended, on 5 October 2017, by clause 40(3) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 2(3)(aa), (3)(ba) and (3)(d): amended, on 5 October 2017, by clause 40(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 2(3)(b): substituted, on 23 February 2015, by clause 21(6) of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 2(3)(ba): inserted, on 23 February 2015, by clause 21(7) of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 2(3)(ba)(ii): amended, on 23 February 2015, by clause 6(1) of the Electricity Industry Participation Code Amendment (Minor Code Amendments) (No 3) 2014.

Clause 2(3)(ba)(iii): inserted, on 23 February 2015, by clause 6(2) of the Electricity Industry Participation Code Amendment (Minor Code Amendments) (No 3) 2014.

Clause 2(3)(c) and (d): substituted, on 23 February 2015, by clause 21(8) of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 2(3)(da): inserted, on 23 February 2015, by clause 21(9) of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 2(3)(da): amended, on 5 October 2017, by clause 40(4) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 2(3)(e): substituted, on 23 February 2015, by clause 21(10) of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 2(3)(e)(i): amended, on 5 October 2017, by clause 40(5) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 2(3)(e)(vii): amended, on 5 October 2017, by clause 40(6) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 2(3)(g): amended, on 23 February 2015, by clause 21(11) of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 2(4): revoked, on 23 February 2015, by clause 21(12) of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

### **3 Distributor's decision on application**

- (1) A **distributor** must, within 30 **business days** after the date of receipt of a completed application made in accordance with clause 2, give notice in writing to the applicant stating whether the application is approved or declined.
- (2) A **distributor** must approve an application if—
  - (a) the application has been properly made in accordance with Part 6 of this Code; and
  - (b) the information provided in the application would reasonably support an assessment by the **distributor** that—
    - (i) the **distributed generator** will comply at all times with the requirements of the Health and Safety at Work Act 2015; and
    - (ii) the **distributed generator** will ensure that the **distributed generation** complies at all times with the **Act**, and this Code; and
    - (iii) the **distributed generation** meets the **distributor's connection and operation standards**.
- (3) A notice stating that an application is declined must be accompanied by the following information:
  - (a) detailed reasons of why the application has been declined and the steps that the applicant can take to achieve approval if it makes a new application;
  - (b) information about the default process under Schedule 6.3 for the resolution of disputes between **participants** about an alleged breach of the **regulated terms** or any other provision of Part 6 of this Code;
  - (c) that if the **distributed generator** is not a **participant**, the **distributed generator** may report to the **Authority** under the Electricity Industry (Enforcement) Regulations 2010 if it considers that the **distributor** has breached any requirement in Part 6 of this Code.

Compare: SR 2007/219 clause 3 Schedule 1

Clause 3(2): amended, on 23 February 2015, by clause 22(1) of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 3(2)(b)(i): amended, on 5 October 2017, by clause 41 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 3(2)(b)(ii) and (iii): substituted, on 23 February 2015, by clause 22(2) of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 3(3)(a) and (b): amended, on 23 February 2015, by clause 22(3) and (4) of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 3(3)(c): inserted, on 23 February 2015, by clause 22(5) of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

### **4 Extension of time by mutual agreement for distributor to process application**

- (1) A **distributor** may seek an extension of the time specified in clause 3(1) by which the **distributor** must give notice in writing stating whether an application is approved or declined.
- (2) The **distributor** must do this by notice in writing to the **distributed generator** specifying the reasons for the extension.

- (3) The **distributed generator** that made the application—
- (a) may grant an extension which must not exceed 20 **business days**; and
  - (b) must not unreasonably withhold consent to an extension.
- Compare: SR 2007/219 clause 4 Schedule 1  
Clause 4(1): amended, on 23 February 2015, by clause 23(1) of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.  
Clause 4(3): substituted, on 23 February 2015, by clause 23(2) of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

## **5 Distributed generator must give notice of intention to negotiate**

- (1) If a **distributor** advises a **distributed generator** that its application is approved, the **distributed generator** must give written notice to the **distributor** confirming whether the **distributed generator** intends to negotiate a connection contract under clause 6 and, if so, confirming the details of the **distributed generation** to which the application relates.
- (2) The **distributed generator** must give the notice within 10 **business days** after the **distributor** gives notice of approval, or such later date as is agreed by the **distributor** and the **distributed generator**.
- (3) The **distributor's** duties under Part 6 of this Code arising from the application no longer apply if the **distributed generator** fails to give notice to the **distributor** within the time limit specified in subclause (2).
- (4) Subclause (3) does not prevent the **distributed generator** from making a new application under Part 6 of this Code.

Compare: SR 2007/219 clause 5 Schedule 1  
Heading: amended, on 5 October 2017, by clause 42(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.  
Clause 5(1): substituted, on 23 February 2015, by clause 24(1) of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.  
Clause 5(1): amended, on 5 October 2017, by clause 42(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.  
Clause 5(2): amended, on 23 February 2015, by clause 24(2) of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.  
Clause 5(3) and (4): amended, on 23 February 2015, by clause 24(3) and (4) of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

### *Post-approval process*

Cross heading: amended, on 23 February 2015, by clause 25 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

## **6 30 business days to negotiate connection contract if distributed generator notifies intention to proceed**

- (1) If a **distributed generator** whose application under clause 2 is approved gives notice to a **distributor** under clause 5, the **distributor** and the **distributed generator** have 30 **business days**, starting on the date on which the **distributor** receives the notice, during which they must, in good faith, attempt to negotiate a connection contract.
- (2) The **distributor** and the **distributed generator** may, by agreement, extend the time specified in subclause (1) for negotiating a connection contract.

Compare: SR 2007/219 clause 6 Schedule 1  
Clause 6: amended, on 23 February 2015, by clauses 26 and 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.  
Clause 6: amended, on 5 October 2017, by clause 43 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

## **7 Testing and inspection**

- (1) Subject to subclause (1A), a **distributed generator** whose application under clause 2 is approved by a **distributor** must test and inspect the **distributed generation** to which the application relates within a reasonable time frame specified by the **distributor**.
- (1A) The **distributor** may waive the requirement that the **distributed generator** test and inspect if the **distributor** is satisfied that the **distributed generation** complies with the **distributor's connection and operation standards**.
- (2) The **distributed generator** must give adequate notice of the testing and inspection to the **distributor**.
- (3) The **distributor** may send qualified personnel to the site to observe the testing and inspection.
- (4) The **distributed generator** must give the **distributor** with a written test report when testing and inspection is complete, including suitable evidence that the **distributed generation** complies with the **distributor's connection and operation standards**.
- (5) The **distributed generator** must pay any fee specified by the **distributor** in accordance with clause 6.3(2)(e) for observing the testing and inspection.

Compare: SR 2007/219 clause 7 Schedule 1

Clause 7(1): substituted, on 23 February 2015, by clause 27(1) of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 7(1A): inserted, on 23 February 2015, by clause 27(2) of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 7(4) and (5): amended, on 23 February 2015, by clause 27(3) and (4) of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

## **8 Connection of distributed generation if connection contract negotiated**

- (1) This clause applies if a **distributor** and a **distributed generator** whose application under this Part of this Schedule is approved enter into a connection contract before the period for negotiating a connection contract under this Part of this Schedule expires.
- (2) If the application is to connect **distributed generation** under clause 1B(a), the **distributor** must allow the **distributed generator** to connect the **distributed generation** in accordance with the contract as soon as practicable.
- (3) If the application is to continue an existing connection of **distributed generation** under clause 1B(b), the **distributor** must use its best endeavours to ensure that the new terms under which the **distributed generator's** existing connection continues apply—
  - (a) as soon as practicable, if the previous connection contract has expired; or
  - (b) no later than the expiry of the previous connection contract, if the contract is in force.
- (4) If the application is to continue an existing connection for which there is no connection contract under clause 1B(c), the **distributor** must use its best endeavours to ensure that the new terms under which the **distributed generator's** existing connection continues apply as soon as practicable.
- (5) If the application is to change the **nameplate capacity** or fuel type of connected **distributed generation** under clause 1B(d), the **distributor** must use its best endeavours to ensure that the new terms under which the **distributed generator's** existing connection continues apply as soon as practicable.

Compare: SR 2007/219 clause 8 Schedule 1

Clause 8: substituted, on 23 February 2015, by clause 28 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 8: amended, on 5 October 2017, by clause 44 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

**9 Connection of distributed generation on regulated terms if connection contract not negotiated**

- (1) This clause applies if a **distributor** and a **distributed generator** whose application under this Part of this Schedule is approved do not enter into a connection contract before the period for negotiating a connection contract under this Part of this Schedule expires.
- (2) If the application is to connect **distributed generation** under clause 1B(a), the **distributor** must allow the **distributed generator** to connect the **distributed generation** on the **regulated terms** as soon as practicable after the expiry of the period.
- (3) If the application is to continue an existing connection of **distributed generation** under clause 1B(b), the **regulated terms** apply to the **distributed generator's** existing connection as follows:
  - (a) if the previous connection contract has expired, the **regulated terms** apply from the day after the date on which the period for negotiating a connection contract under this Part of this Schedule expires;
  - (b) if the previous connection contract is still in force, the **regulated terms** apply from the day after the date on which the contract expired.
- (4) If the application is to continue an existing connection for which there is no connection contract under clause 1B(c), the **regulated terms** apply from the day after the date that the period for negotiating a connection contract under this Part of this Schedule expires.
- (5) If the application is to change the **nameplate capacity** or fuel type of connected **distributed generation** under clause 1B(d), the **regulated terms** apply from the day after the date that the period for negotiating a connection contract under this Part of this Schedule expires.

Compare: SR 2007/219 clause 9 Schedule 1

Clause 9: substituted, on 23 February 2015, by clause 28 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 9: amended, on 5 October 2017, by clause 45(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 9(2): amended, on 5 October 2017, by clause 45(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 9(5): amended, on 5 October 2017, by clause 45(3) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

## Part 1A

Applications for distributed generation of 10 kW or less in total in specified circumstances

### 9A Contents of this Part

- (1) This Part applies to applications relating to **distributed generation** that has a **nameplate capacity** of 10 kW or less in total if the **distributed generator** that owns or operates the **distributed generation** has elected, under clause 1D, to apply under this Part of this Schedule.
- (2) This Part of this Schedule provides for a simplified 1-stage application process.

### 9B Application for distributed generation of 10 kW or less in total in specified circumstances

- (1) A **distributed generator's** application to a **distributor** must specify which of the following circumstances applies:
  - (a) the **distributed generator** wishes to connect **distributed generation**:
  - (b) the **distributed generator** wishes to continue an existing connection of **distributed generation** that is connected in accordance with a connection contract that—
    - (i) is in force and the **distributed generator** wishes to extend the term of the connection contract; or
    - (ii) has expired:
  - (c) the **distributed generator** wishes to continue an existing connection of **distributed generation** that is connected without a connection contract:
  - (d) the **distributed generator** wishes to change the **nameplate capacity** or fuel type of connected **distributed generation**.
- (2) An application must include the following:
  - (a) the name, contact, and address details of the **distributed generator** and, if applicable, the **distributed generator's** agent:
  - (b) a brief description of the physical location at the address at which the **distributed generation** is or will be connected:
  - (c) any application fee specified by the **distributor** in accordance with clause 6.3(2)(e):
  - (d) details of the make and model of the inverter:
  - (e) confirmation as to whether the inverter—
    - (i) is included on the **distributor's** list of approved inverters made publicly available under clause 6.3(2)(f); or
    - (ii) conforms with the protection settings specified in the **distributor's connection and operation standards**:
  - (f) if the inverter is not included on the **distributor's** list of approved inverters, a copy of the AS/NZS 4777.2 Declaration of Conformity certificate for the inverter:
  - (g) details of—
    - (i) the **nameplate capacity** of the **distributed generation**; and
    - (ii) the fuel type of the **distributed generation** (for example, solar, wind, or liquid fuel).
- (3) The **distributed generator** must also give the **distributor** the following information as soon as it is available, but no later than 10 **business days** after the approval of the application:

- (a) a copy of the Certificate of Compliance issued under the Electricity (Safety) Regulations 2010 that relates to the **distributed generation**;
  - (b) the **ICP identifier** of the **ICP** at which the **distributed generation** is connected or is proposed to be connected, if one exists.
- (4) A **distributor** must, no later than 2 **business days** after receiving an application from a **distributed generator**, acknowledge receipt of the application.
- Clause 9B: amended, on 5 October 2017, by clause 46(3) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.
- Clause 9B(1)(a): amended, on 5 October 2017, by clause 46(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.
- Clause 9B(1): amended, on 5 October 2017, by clause 46(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.
- Clause 9B(2)(f): amended, on 20 October 2016, by clause 5 of the Electricity Industry Participation Code Amendment (Inverter Standard for Distributed Generation) 2016.

#### **9C Distributor may inspect distributed generation**

- (1) A **distributor** may inspect **distributed generation** that is connected or is proposed to be connected to its **distribution network** for the purpose of—
- (a) verifying that the **distributed generation** meets, or continues to meet, the requirements specified in clause 1D; or
  - (b) verifying the information contained in an application made under this Part of this Schedule.
- (2) If a **distributor** wishes to inspect **distributed generation**, the **distributor** must give the **distributed generator** at least 2 **business days**’ notice of the time and date on which the inspection will take place.
- (3) Following receipt of a notice, the **distributed generator** must—
- (a) pay the fee specified by the **distributor** in accordance with clause 6.3(2)(e) for the inspection (if any); and
  - (b) provide or arrange for the **distributor** to have reasonable access to the **distributed generation**.

Clause 9C(1): amended, on 5 October 2017, by clause 47 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

#### **9D Export congestion**

- (1) This clause applies if a **distributed generator** applies to a **distributor** under this Part of this Schedule to connect **distributed generation** or continue an existing connection of **distributed generation** to a location on the **distributor's distribution network** that is included in the list made publicly available in accordance with clause 6.3(2)(da).
- (2) The **distributor** may advise the **distributed generator** that the **distributed generation** may be subject to **export congestion** as set out in the **distributor's congestion management policy**.
- (3) If a **distributor** has advised a **distributed generator** under subclause (2), the **distributor** must take reasonable steps to work with the **distributed generator** to assess whether solutions exist to mitigate the **export congestion**.

Clause 9D(1): amended, on 5 October 2017, by clause 48 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

#### **9E Non-compliance or incomplete information**

- (1) This clause applies if a **distributor** considers that an application made to it by a **distributed generator** under this Part of this Schedule has 1 or more of the following deficiencies:



- (a) the **distributed generation** to which the application relates does not meet the requirements specified in clause 1D;
  - (b) the **distributed generation** to which the application relates is not as described in the information given under clause 9B(2);
  - (c) the **distributed generator** has not complied with clause 9B(2).
- (2) If this clause applies, the **distributor** must advise the **distributed generator** of the deficiency or deficiencies.
- (3) If the **distributed generator** is advised of a deficiency or deficiencies, it must remedy each deficiency to the satisfaction of the **distributor** no later than 10 **business days** after being advised of the deficiency.
- (4) If the **distributed generator** is required to remedy a deficiency it must pay the relevant fee specified by the **distributor** in accordance with clause 6.3(2)(e).
- (5) If the **distributed generator** does not remedy each deficiency of which it is advised within the time frame specified in subclause (3)—
- (a) if the **distributed generation** to which the application relates is **electrically connected** to the **distributor's distribution network** at the time the **distributor** advises the **distributed generator** under subclause (2), the **distributor** may, by notice to the **distributed generator**, require the **distributed generator** to—
    - (i) **electrically disconnect** the **distributed generation** within a reasonable time frame specified by the **distributor** (if applicable); and
    - (ii) keep the **distributed generation electrically disconnected** until each deficiency is remedied to the **distributor's** satisfaction; or
  - (b) if the **distributed generation** is not connected to the **distributor's distribution network** at the time of being advised under subclause (2), the **distributor** may, by notice to the **distributed generator**, prohibit the **distributed generator** from connecting the **distributed generation** to the **distributor's distribution network** until each deficiency is remedied to the **distributor's** satisfaction.
- (6) The **distributor** must approve connection of the **distributed generation** as soon as is reasonable in the circumstances if—
- (a) the **distributed generator** complies with a notice given under subclause (5)(a) (if applicable); and
  - (b) the **distributed generator** remedies each deficiency advised under subclause (2)—
    - (i) to the satisfaction of the **distributor**; and
    - (ii) no later than 12 months after the date of the notice given under subclause (5) or such later date as is agreed by the **distributor** and the **distributed generator**.
- (7) If the **distributor** approves the connection of **distributed generation**, it must give a notice of final approval to the **distributed generator** under clause 9F.

Clause 9E(5)(a): replaced, on 5 October 2017, by clause 49(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 9E(5)(b): amended, on 5 October 2017, by clause 49(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 9E(6): amended, on 5 October 2017, by clause 49(3) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 9E(7): amended, on 5 October 2017, by clause 49(4) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

**9F Notice of final approval**

- (1) A **distributor** must give a notice of final approval of **distributed generation** to a **distributed generator** that has made an application to the **distributor** under this Part of this Schedule if the **distributor** is satisfied that—
  - (a) the **distributed generation** meets the requirements specified in clause 1D; and
  - (b) the information given by the **distributed generator** under clause 9B(2) is complete and accurate.
- (2) The **distributor** must give the notice no later than 10 **business days** after the date on which the application was submitted.
- (3) If the **distributed generator** does not receive a notice by the date specified in subclause (2), the **distributor** is deemed to have given notice of final approval.

**9G Regulated terms apply**

- (1) If a **distributor** gives a notice of final approval to a **distributed generator** under clause 9F, the **regulated terms** apply.
- (2) Despite subclause (1), and in accordance with clause 6.6(4), the **distributor** and **distributed generator** may at any time enter into a connection contract on terms that apply instead of the **regulated terms**.

Clause 9G(2): amended, on 5 October 2017, by clause 50 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

**9H When distributed generator may connect to distribution network**

- (1) A **distributed generator** that has submitted an application to a **distributor** under clause 1D may connect the **distributed generation** to which the application relates to the **distributor's distribution network** if the **distributed generator** receives a notice of final approval under clause 9F(1), or is deemed to have received a notice of final approval under clause 9F(3).
- (2) Despite subclause (1) a **distributor** may prohibit a **distributed generator** from connecting if—
  - (a) the **distributor** has advised the **distributed generator** of a deficiency under clause 9E(2) and the deficiency has not been remedied in accordance with clause 9E(3); or
  - (b) the **distributor** gave notice that it wished to inspect the **distributed generation** under clause 9C(2), but the **distributed generator** has not provided or arranged for the **distributor** to have reasonable access to the **distributed generation** under clause 9C(3)(b).

Part 1A: inserted, on 23 February 2015, by clause 29 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 9H(1) and (2): amended, on 5 October 2017, by clause 51 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Part 2  
Applications for distributed generation  
above 10 kW in total

Heading: amended, on 23 February 2015, by clause 30 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

**10 Contents of this Part**

- (1) This Part of this Schedule applies to applications relating to **distributed generation** that has a **nameplate capacity** of more than 10 kW in total.

- (2) This Part of this Schedule provides for a 2-stage application process.

Compare: SR 2007/219 clause 10 Schedule 1

Clause 10(1): substituted, on 23 February 2015, by clause 31 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

*Initial application process*

**11 Distributed generator must make initial application and give information**

- (1) *[Revoked]*

- (2) A **distributed generator** must apply to a **distributor** ("initial application") by—

- (a) using the application form provided by the **distributor** that is publicly available under clause 6.3(2)(a); and
- (b) providing any information in respect of the **distributed generation** to which the application relates that is—
  - (i) referred to in subclause (3); and
  - (ii) specified by the **distributor** under clause 6.3(3) as being required to be provided with the application; and
- (c) paying the application fee (if any) specified by the **distributor** in accordance with clause 6.3(2)(e).

- (3) The information may include the following:

- (a) the full name and address of the **distributed generator** and the contact details of a person whom the **distributor** may contact regarding the **distributed generation**:
- (aa) whether the application is to—
  - (i) connect **distributed generation**; or
  - (ii) continue an existing connection of **distributed generation** that is connected in accordance with a connection contract if the connection contract—
    - (A) is in force and the **distributed generator** wishes to extend the term of the connection contract; or
    - (B) has expired; or
  - (iii) continue an existing connection of **distributed generation** that is connected without a connection contract; or
  - (iv) change the **nameplate capacity** or fuel type of connected **distributed generation**:
- (b) evidence of the **nameplate capacity** that the **distributed generation** will have:
- (ba) if the application is to change the **nameplate capacity** or fuel type of connected **distributed generation**,—

- (i) the **nameplate capacity** that the **distributed generation** will have after the change; and
  - (ii) the aggregate **nameplate capacity** that all **distributed generation** that is connected at the **point of connection** at which the **distributed generation** is connected will have after the change; and
  - (iii) the fuel type that the **distributed generation** will have after the change;
  - (c) details of the fuel type of the **distributed generation** (for example, solar, wind, or liquid fuel):
  - (d) a brief description of the physical location at the address at which the **distributed generation** is or will be connected:
  - (da) if the application is to **connect distributed generation**, when the **distributed generator** expects the **distributed generation** to be connected:
  - (e) technical specifications of the **distributed generation** and **associated equipment**, including the following:
    - (i) technical specifications of equipment that allows the **distributed generation** to be **electrically disconnected** from the **distribution network** on loss of mains voltage:
    - (ii) manufacturer's rating of equipment:
    - (iii) number of phases:
    - (iv) proposed or current **point of connection** to the **distribution network** (for example, the **ICP identifier** and street address):
    - (v) details of either or both of any inverter and battery storage:
    - (vi) details of any load at the proposed or current **point of connection**:
    - (vii) details of the voltage (for example, 415 V or 11 kV) when **electrically connected**:
  - (f) information showing how the **distributed generation** complies with the **distributor's connection and operation standards**:
  - (g) the maximum **active power** injected (**MW max**):
  - (h) the **reactive power** requirements (**MVAr**s) (if any):
  - (i) resistance and reactance details of the **distributed generation**:
  - (j) fault level contribution (**kA**):
  - (k) method of voltage control:
  - (l) single line diagram of proposed connection:
  - (m) means of **synchronising** with, **electrically connecting** to, and **electrically disconnecting** from, the **distribution network**, including the type and ratings of the proposed **circuit breaker**:
  - (n) details of compliance with frequency and voltage support requirements as specified in this Code (if applicable):
  - (o) proposed periods and amounts of **electricity injections** into, and **offtakes** from, the **distribution network** (if known):
  - (p) any other information that is required by the **system operator**:
  - (q) any additional information or **documents** that are reasonably required by the **distributor**.
- (4) *[Revoked]*

- (5) The **distributor** must, within 5 **business days** of receiving an **initial application**, give written notice to the applicant advising whether or not the application is complete.

Compare: SR 2007/219 clause 11 Schedule 1

Heading: amended, on 23 February 2015, by clause 32(1) of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 11: amended, on 5 October 2017, by clause 52(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 11(1): revoked, on 23 February 2015, by clause 32(2) of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 11(2): substituted, on 23 February 2015, by clause 32(3) of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 11(3)(a): amended, on 23 February 2015, by clause 32(4) of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 11(3)(aa): inserted, on 23 February 2015, by clause 32(5) of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 11(3)(aa): amended, on 5 October 2017, by clause 52(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 11(3)(aa), (ba) and (d): amended, on 5 October 2017, by clause 52(3) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 11(3)(b): substituted, on 23 February 2015, by clause 32(6) of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 11(3)(ba): inserted, on 23 February 2015, by clause 32(7) of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 2(3)(ba)(ii): amended, on 23 February 2015, by clause 7(1) of the Electricity Industry Participation Code Amendment (Minor Code Amendments) (No 3) 2014.

Clause 2(3)(ba)(iii): inserted, on 23 February 2015, by clause 7(2) of the Electricity Industry Participation Code Amendment (Minor Code Amendments) (No 3) 2014.

Clause 11(3)(c) and (d): substituted, on 23 February 2015, by clause 32(8) of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 11(3)(da): inserted, on 23 February 2015, by clause 32(9) of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 11(3)(da): amended, on 5 October 2017, by clause 52(4) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 11(3)(e): substituted, on 23 February 2015, by clause 32(10) of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 11(3)(e)(i): amended, on 5 October 2017, by clause 52(5) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 11(3)(e)(vii): amended, on 5 October 2017, by clause 52(6) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 11(3)(i): amended, on 23 February 2015, by clause 32(11) of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 11(3)(l): amended, on 23 February 2015, by clause 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 11(3)(l): amended, on 5 October 2017, by clause 52(7) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 11(3)(m): amended, on 23 February 2015, by clauses 32(12) and 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 11(3)(m): replaced, on 5 October 2017, by clause 52(8) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 11(3)(q): amended, on 23 February 2015, by clause 32(13) of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 11(4): revoked, on 23 February 2015, by clause 32(14) of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

## **12 Distributor must give information to distributed generator**

A **distributor** must give a **distributed generator** that makes an **initial application** the following within 30 **business days** of receiving the completed **initial application**:

- (a) information about the **capacity** of the **distribution network**, including both the design **capacity** (including fault levels) and actual operating levels:

- (b) information about the extent to which connection and operation of the **distributed generation** may result in a breach of the relevant standards for safety, voltage, power quality, and reliability of **electricity** conveyed to **points of connection** on the **distribution network**:
- (c) information about any measures or conditions (including modifications to the design and operation of the **distribution network** or to the operation of the **distributed generation**) that may be necessary to address the matters referred to in paragraphs (a) and (b):
- (d) the approximate costs of any **distribution network** related measures or conditions identified under paragraph (c) and an estimate of time constraints or restrictions that may delay connecting the **distributed generation**:
- (e) information about any further detailed investigative studies that the **distributor** reasonably considers are necessary to identify any potential adverse effects the **distributed generation** may have on the system, together with an indication of—
  - (i) whether the **distributor** agrees to the **distributed generator**, or a suitably qualified agent of the **distributed generator**, undertaking those studies; or
  - (ii) if not, whether the **distributor** could undertake those studies and, if so, the reasonable estimated cost of the studies that the **distributed generator** would be charged:
- (f) information about any obligations to other parties that may be imposed on the **distributor** and that could affect the **distributed generation** (for example, obligations to **Transpower**, in respect of other **networks**, or under this Code):
- (g) any additional information or documents that the **distributor** considers would assist the **distributed generator's** application:
- (h) information about the extent to which planned and **unplanned outages** may adversely affect the operation of the **distributed generation**.

Compare: SR 2007/219 clause 12 Schedule 1

Heading: amended, on 23 February 2015, by clause 33(1) of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 12: amended, on 23 February 2015, by clause 33(2) of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 12(b): amended, on 23 February 2015, by clauses 33(3) and 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 12(b): amended, on 5 October 2017, by clause 53(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 12(d): amended, on 23 February 2015, by clauses 33(4) and 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 12(d): amended, on 5 October 2017, by clause 53(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 12(e): amended, on 23 February 2015, by clause 33(5) of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

### 13 Other matters to assist with decision making

- (1) A **distributor** must provide, if requested by a **distributed generator** making an **initial application**, further information that is reasonably necessary to enable the **distributed generator** to consider and act on the information given by the **distributor** under clause 12.
- (2) The information that the **distributor** must provide under subclause (1) may include single line diagrams, equipment ratings, normal switch configurations (including fault

levels), and protection system details relevant to the current or proposed **point of connection** of the **distributed generation** to the **distribution network**.

- (3) The **distributor** must provide the further information under this clause within 10 **business days** of the request being received.

Compare: SR 2007/219 clause 13 Schedule 1

Clause 13(2): amended, on 23 February 2015, by clause 34 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

#### **14 Distributor and distributed generator must make reasonable endeavours regarding new information**

If a **distributor** or a **distributed generator** has given information under this Part of this Schedule and subsequently becomes aware of new information that is relevant to the application, the party that becomes aware of the new information must use reasonable endeavours to provide the other party with the new information.

Compare: SR 2007/219 clause 14 Schedule 1

Clause 14: amended, on 23 February 2015, by clause 35 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

#### *Final application process*

#### **15 Distributed generator must make final application**

- (1) A **distributed generator** that makes an **initial application** to a **distributor** must make a **final application**, no later than 12 months after receiving information under clauses 12 and 13, if the **distributed generator** wishes to proceed with the application, unless—
- (a) the **distributor** and the **distributed generator** agree that a **final application** is not required; and
  - (b) there are no persons to whom notification is required under clause 16 at the time that the **distributor** and **distributed generator** agree that a **final application** is not required.
- (1A) If a **final application** is not required—
- (a) subclause (2) does not apply; and
  - (b) the **distributed generator's initial application** must be treated as a **final application** for the purposes of clauses 16 to 24.
- (2) The **distributed generator** must make the **final application** by—
- (a) using the **final application** form provided by the **distributor** that is publicly available under clause 6.3(2)(a); and
  - (b) providing the results of any investigative studies that were identified by the **distributor** under clause 12(e)(i) as to be undertaken by the **distributed generator** or the **distributed generator's agent**.

Compare: SR 2007/219 clause 15 Schedule 1

Clause 15(1): substituted, on 23 February 2015, by clause 36(1) of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 15(1A): inserted, on 23 February 2015, by clause 36(2) of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

#### **16 Notice to third parties**

A **distributor** that receives a **final application** must give written notice to the following persons no later than 10 **business days** after receiving the **final application**:

- (a) all persons that have made an **initial application** relating to a particular part of the **distribution network** that the **distributor** considers would be affected by the approval of the **final application**; and
- (b) all **distributed generators** that have **distributed generation** with a **nameplate capacity** of 10 kW or more in total connected on the **regulated terms** to the particular part of the **distribution network** that the **distributor** considers would be affected by the approval of the **final application**.

Compare: SR 2007/219 clause 16 Schedule 1

Clause 16: substituted, on 23 February 2015, by clause 37 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 16(b): amended, on 5 October 2017, by clause 54 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

## 17 Priority of final applications

- (1) Subclause (2) applies if—

- (a) a **distributor** receives a **final application** (the **first application**); and
- (b) the **distributor** receives another **final application**, within 20 **business days** after receiving the **first application**, relating to a particular part of the **distribution network** that the **distributor** considers would be affected by the approval of the **first application**.

- (2) If this subclause applies, the **distributor**—

- (a) may consider the **final applications** together as if they were competitive bids to use the same part of the **distribution network**; and
- (b) must consider the **final applications** in light of the purpose of Part 6 of this Code.

- (3) In any other case in which a **distributor** receives more than 1 **final application** relating to a similar part of the **distribution network**, the **distributor** must consider an earlier **final application** in priority to other **final applications**.

- (4) Subclause (3) does not limit clause 19.

Compare: SR 2007/219 clause 17 Schedule 1

Clause 17(1) and (2): substituted, on 23 February 2015, by clause 38(1) of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 17(3): amended, on 23 February 2015, by clause 38(2) of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

## 18 Distributor's decision on application

- (1) A **distributor** must, within the time limit specified in clause 19, give notice in writing to the applicant stating whether the **final application** is approved or declined.

- (2) A **distributor** must approve a **final application**, subject to any conditions specified by the **distributor** that are reasonably required, if—

- (a) the application has been properly made in accordance with Part 6 of this Code; and
- (b) the information provided in the application would reasonably support an assessment by the **distributor** that—
  - (i) the **distributed generator** will comply at all times with the requirements of the Health and Safety at Work Act 2015; and
  - (ii) the **distributed generator** will ensure that the **distributed generation** complies at all times with the **Act** and this Code; and



- (iii) the **distributed generation** meets the **distributor's connection and operation standards** (assuming that the **distributed generator** meets the conditions (if any) referred to in subclause (3)).
- (3) A notice stating that an application is approved must be accompanied by the following information:
  - (a) a detailed description of any conditions (or other measures) that are conditions of the approval under subclause (2), and what the **distributed generator** must do to comply with them;
  - (b) detailed reasons for those conditions (or other measures);
  - (c) a detailed description of any charges payable by the **distributed generator** to the **distributor** or by the **distributor** to the **distributed generator**, and an explanation of how the charges have been, or will be, calculated;
  - (d) the default process for resolving disputes under Schedule 6.3, if the **distributed generator** disputes all or any of the conditions (or other measures) or charges payable.
- (4) A notice stating that an application is declined must be accompanied by the following information:
  - (a) detailed reasons as to why the application has been declined and what the applicant must do to get approval if it makes a new application;
  - (aa) if the application is one to which clause 17(2) applies, the criteria used in making a decision under clause 17(2)(a) and clause 17(2)(b);
  - (b) the default process for resolving disputes between **participants** under Schedule 6.3;
  - (c) that if the **distributed generator** is not a **participant**, the **distributed generator** may report to the **Authority** under the Electricity Industry (Enforcement) Regulations 2010 if it considers that the **distributor** has breached any requirement in Part 6 of this Code.

Compare: SR 2007/219 clause 18 Schedule 1

Clause 18(2): amended, on 23 February 2015, by clause 39(1) of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 18(2)(b)(i): amended, on 5 October 2017, by clause 55 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 18(3): substituted, on 23 February 2015, by clause 39(2) of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 18(4)(a): substituted, on 23 February 2015, by clause 39(3) of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 18(4)(aa): inserted, on 23 February 2015, by clause 39(4) of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 18(4)(b): substituted, on 23 February 2015, by clause 39(5) of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 18(4)(c): inserted, on 23 February 2015, by clause 39(5) of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

## 19 Time within which distributor must decide final applications

- (1) A notice required by clause 18 must be given by a **distributor** to a **distributed generator** no later than—
  - (a) 45 **business days** after the date of receipt of the **final application**, in the case of **distributed generation** that will have a **nameplate capacity** of less than 1 MW;or

- (b) 60 **business days** after the date of receipt of the **final application**, in the case of **distributed generation** that will have a **nameplate capacity** of 1 **MW** or more but less than 5 **MW**; or
- (c) 80 **business days** after the date of receipt of the **final application**, in the case of **distributed generation** that will have a **nameplate capacity** of 5 **MW** or more.
- (2) The **distributor** may seek 1 or more extensions of the time specified in subclause (1).
- (3) The **distributor** must do this by notice in writing to the **distributed generator** specifying the reasons for the extension.
- (4) A **distributed generator** that receives a notice seeking an extension—
  - (a) may grant an extension which must not exceed 40 **business days**; and
  - (b) must not unreasonably withhold consent to an extension.

Compare: SR 2007/219 clause 19 Schedule 1

Clause 19(1): substituted, on 23 February 2015, by clause 40(1) of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 19(4): substituted, on 23 February 2015, by clause 40(2) of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

## **20 Distributed generator must give notice of intention to proceed**

- (1) If a **distributor** advises a **distributed generator** that the **distributed generator's final application** is approved, the **distributed generator** must give written notice to the **distributor** confirming whether or not the **distributed generator** intends to proceed to negotiate a connection contract under clause 21(1) and, if so, confirming—
  - (a) the details of the **distributed generation**; and
  - (b) that the **distributed generator** accepts all of the conditions (or other measures) that have been specified by the **distributor** under clause 18.
- (2) The **distributed generator** must give the notice no later than 30 **business days** after the day on which the **distributor** gives notice of approval under clause 18, or such later date as is agreed by the **distributor** and the **distributed generator**.
- (3) If the **distributed generator** is a **participant** and does not accept 1 or more of the conditions specified by the **distributor** under clause 18(2) (if any), but intends to proceed to negotiate a connection contract under clause 21(1), the **distributed generator** must—
  - (a) give notice of the dispute in accordance with clause 2 of Schedule 6.3 within 30 **business days** after the day on which the **distributor** gives notice of approval under clause 18; and
  - (b) give a notice under subclause (1) within 30 **business days** after the dispute is resolved.
- (4) The **distributor's** duties under Part 6 of this Code arising from the application no longer apply if the **distributed generator** fails to give notice to the **distributor** of an intention to proceed to negotiate a connection contract under clause 21(1) within the time limits specified in this clause.
- (5) Subclause (4) does not prevent the **distributed generator** from making a new application under Part 6 of this Code.

Compare: SR 2007/219 clause 20 Schedule 1

Clause 20: substituted, on 23 February 2015, by clause 41 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 20: amended, on 5 October 2017, by clause 56 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

*Post-approval process*

Cross heading: amended, on 23 February 2015, by clause 42 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

**21 30 business days to negotiate connection contract if distributed generator notifies intention to proceed**

- (1) If a **distributed generator** whose **final application** is approved gives notice to a **distributor** under clause 20(1), the **distributor** and the **distributed generator** have 30 **business days**, starting on the date on which the **distributor** receives the notice, during which they must, in good faith, attempt to negotiate a connection contract.
- (2) The **distributor** and the **distributed generator** may, by agreement, extend the time specified in subclause (1) for negotiating a connection contract.

Compare: SR 2007/219 clause 21 Schedule 1

Clause 21: amended, on 23 February 2015, by clauses 43 and 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 21: amended, on 5 October 2017, by clause 57 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

**22 Testing and inspection**

- (1) A **distributed generator** whose **final application** is approved by a **distributor** must test and inspect the **distributed generation** to which the **final application** relates within a reasonable time frame specified by the **distributor**.
- (1A) The **distributor** may waive the requirement that the **distributed generator** test and inspect if the **distributor** is satisfied that the **distributed generation** complies with the **distributor's connection and operation standards**.
- (2) The **distributed generator** must give adequate notice of the testing and inspection to the **distributor**.
- (3) The **distributor** may send qualified personnel to the site to observe the testing and inspection.
- (4) The **distributed generator** must give the **distributor** with a written test report when testing and inspection is complete, including suitable evidence that the **distributed generation** complies with the **distributor's connection and operation standards**.
- (5) The **distributed generator** must pay any fee specified by the **distributor** in accordance with clause 6.3(2)(e) for observing the testing and inspection.

Compare: SR 2007/219 clause 22 Schedule 1

Clause 22(1): substituted, on 23 February 2015, by clause 44(1) of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 22(1A): inserted, on 23 February 2015, by clause 44(2) of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 22(4): amended, on 23 February 2015, by clause 44(3) of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 22(5): amended, on 23 February 2015, by clause 44(4) of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

**23 Connection of distributed generation if connection contract negotiated**

- (1) This clause applies if a **distributor** and a **distributed generator** whose **final application** is approved enter into a connection contract before the period for negotiating a connection contract under this Part of this Schedule expires.

- (2) If the application is to connect **distributed generation** under clause 1B(a), the **distributor** must allow the **distributed generator** to connect the **distributed generation** in accordance with the contract as soon as practicable.
- (3) If the application is to continue an existing connection of **distributed generation** under clause 1B(b), the **distributor** must use its best endeavours to ensure that the new terms under which the **distributed generator's** existing connection continues apply—
  - (a) as soon as practicable, if the previous connection contract has expired; or
  - (b) no later than the expiry of the previous connection contract, if the contract is in force.
- (4) If the application is to continue an existing connection for which there is no connection contract under clause 1B(c), the **distributor** must use its best endeavours to ensure that the new terms under which the **distributed generator's** existing connection continues apply as soon as practicable.
- (5) If the application is to change the **nameplate capacity** or fuel type of connected **distributed generation** under clause 1B(d), the **distributor** must use its best endeavours to ensure that the new terms under which the **distributed generator's** existing connection continues apply as soon as practicable.

Compare: SR 2007/219 clause 23 Schedule 1

Clause 23: substituted, on 23 February 2015, by clause 45 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 23: amended, on 5 October 2017, by clause 58(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 23(2): amended, on 5 October 2017, by clause 58(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 23(5): amended, on 5 October 2017, by clause 58(3) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

## **24 Connection of distributed generation on regulated terms if connection contract not negotiated**

- (1) This clause applies if a **distributor** and a **distributed generator** whose **final application** is approved do not enter into a connection contract before the period for negotiating a connection contract under this Part of this Schedule expires.
- (2) If the application is to connect **distributed generation** under clause 1B(a), the **distributor** must allow the **distributed generator** to connect the **distributed generation** on the **regulated terms** as soon as practicable after the later of the following:
  - (a) the expiry of the period for negotiating a connection contract under this Part of this Schedule;
  - (b) the date on which the **distributed generator** has fully complied with any conditions (or other measures) that were specified by the **distributor** under clause 18 as conditions of the connection.
- (3) If the application is to continue an existing connection of **distributed generation** under clause 1B(b), the **regulated terms** apply to the **distributed generator's** existing connection from the later of the following:
  - (a) the expiry of the period for negotiating a connection contract under this Part of this Schedule;
  - (b) the expiry of the existing connection contract;
  - (c) the date on which the **distributed generator** has fully complied with any conditions (or other measures) that were specified by the **distributor** under clause 18 as conditions of the connection.

- (4) If the application is to continue an existing connection for which there is no connection contract under clause 1B(c), the **regulated terms** apply from the later of the following:
- (a) the expiry of the period for negotiating a connection contract under this Part of this Schedule;
  - (b) the date on which the **distributed generator** has fully complied with any conditions (or other measures) that were specified by the **distributor** under clause 18 as conditions of the connection.
- (5) If the application is to change the **nameplate capacity** or fuel type of connected **distributed generation** under clause 1B(d), the **regulated terms** apply from the later of the following:
- (a) the expiry of the period for negotiating a connection contract under this Part of this Schedule;
  - (b) the date on which the **distributed generator** has fully complied with any conditions (or other measures) that were specified by the **distributor** under clause 18 as conditions of the connection.

Compare: SR 2007/219 clause 24 Schedule 1

Clause 24: substituted, on 23 February 2015, by clause 45 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 24: amended, on 5 October 2017, by clause 59(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 24(2): amended, on 5 October 2017, by clause 59(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 24(5): amended, on 23 February 2015, by clause 8 of the Electricity Industry Participation Code Amendment (Minor Code Amendments) (No 3) 2014.

Clause 24(5): amended, on 5 October 2017, by clause 59(3) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

## Part 3 General provisions

### *Confidentiality*

#### **25 Confidentiality of information provided**

- (1) All information given with, or relating to, an application made under this Schedule to a **distributor** must be kept confidential by the **distributor** except as agreed otherwise by the person that gave the information.
- (1A) A **distributor** may require a **distributed generator** to keep confidential information that—
- (a) is given to the **distributed generator** by the **distributor** for the purpose of an application under this Schedule; and
  - (b) the **distributor** reasonably identifies as being confidential.
- (1B) A **distributor** is excused from processing an application made by a **distributed generator** under this Schedule if the **distributed generator** does not agree to comply with a requirement to keep information confidential imposed under subclause (1A).
- (2) Despite subclause (1), the **distributor**—
- (a) may, in response to an application under this Schedule, disclose to the applicant that another **distributed generator** has made an application under this Schedule (without identifying who the other **distributed generator** is); and

- (b) may, in the case of an application under Part 1 of this Schedule, generally indicate the location or proposed location of the **distributed generation** that is the subject of the other application; and
  - (c) may, in the case of an application under Part 2 of this Schedule, disclose the **nameplate capacity** and proposed location of the **distributed generation** that is the subject of the other application.
- (3) The obligation to keep information confidential set out in subclause (1) includes—
- (a) an obligation not to use the information for any purpose other than considering the application under this Schedule and enabling the connection or continued connection of the **distributed generation**; and
  - (b) an obligation to destroy the information as soon as is reasonably practicable after the later of—
    - (i) the date on which the information is no longer required for the purposes in paragraph (a); and
    - (ii) 60 months after receiving the information.

Compare: SR 2007/219 clause 25 Schedule 1

Heading: amended, on 23 February 2015, by clause 46(1) of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 25(1): substituted, on 23 February 2015, by clause 46(2) of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 25(1A) and (1B): inserted, on 23 February 2015, by clause 46(3) of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 25(2) and (3): substituted, on 23 February 2015, by clause 46(4) of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 25(3)(a): amended, on 5 October 2017, by clause 60 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### *Record keeping*

Heading: amended, on 29 August 2013, by clause 4(1) of the Electricity Industry Participation (Additional Registry Fields) Code Amendment 2012

## **26 [Revoked]**

Compare: SR 2007/219 clause 26 Schedule 1

Clause 26: revoked, on 29 August 2013, by clause 4(2) of the Electricity Industry Participation (Additional Registry Fields) Code Amendment 2012

## **27 [Revoked]**

Compare: SR 2007/219 clause 27 Schedule 1

Clause 27: amended, on 21 September 2012, by clause 6 of the Electricity Industry Participation (Minor Amendments) Code Amendment 2012

Clause 27: revoked, on 29 August 2013, by clause 4(2) of the Electricity Industry Participation (Additional Registry Fields) Code Amendment 2012

## **28 Distributors must keep records**

A **distributor** must maintain records of each application and notification received under this Schedule and the resulting outcomes, including records of how long it took to approve or decline the application, and justification for these outcomes, for a minimum of 60 months after the day on which the application was approved or declined.

Compare: SR 2007/219 clause 28 Schedule 1

Clause 28: substituted, on 23 February 2015, by clause 47 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

*Costs*

**29 Responsibility for costs under this Schedule**

A **distributor** and **distributed generator** must pay their respective costs (including legal costs) incurred under this Schedule.

Cross heading and clause 29: inserted, on 23 February 2015, by clause 48 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

## Schedule 6.2

cl 6.6

### Regulated terms for distributed generation

Heading: amended, on 23 February 2015, by clause 49 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

#### Contents

##### *General*

- 1 Contents of this Schedule
- 2 Interpretation
- 3 General obligations

##### *Meters*

- 4 Installation of meters and access to metering information

##### *Access*

- 5 Right of distributor to access distributed generator's premises
- 6 Process if distributor wants to access distributed generator's premises
- 7 Distributor must not interfere with distributed generator's equipment
- 8 Distributed generator must not interfere with, and must protect, distributor's equipment
- 9 Obligation to advise if interference with distributor's equipment or theft of electricity is discovered

##### *Interruptions and disconnections*

- 10 General obligations relating to interruptions
- 11 Circumstances allowing distributor to temporarily electrically disconnect distributed generation
- 12 Obligations if distributed generation temporarily electrically disconnected by distributor
- 13 Adverse operating effects
- 14 Interruptions by distributed generator
- 15 Disconnecting distributed generation

##### *Time frame for construction*

- 15A Distributed generator must construct distributed generation within 18 months of approval

##### *Confidentiality*

- 16 General obligations relating to confidentiality
- 17 When confidential information can be disclosed
- 18 Disclosures by employees, agents, etc

##### *Pricing*

- 19 Pricing principles

##### *Liability*

- 20 General obligations relating to liability
- 21 Exceptions to general obligations relating to liability
- 22 Limits on liability
- 23 Liability clauses do not apply to fraud, wilful breach, and breach of confidentiality
- 24 *[Revoked]*



*General*

**1 Contents of this Schedule**

This Schedule sets out the **regulated terms** that apply to a **distributor** and a **distributed generator** in respect of **distributed generation** that is connected in accordance with clause 6.6 of Part 6 of this Code and Schedule 6.1.

Compare: SR 2007/219 clause 1 Schedule 2

Clause 1: amended, on 23 February 2015, by clauses 50 and 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 1: amended, on 5 October 2017, by clause 61 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

**2 Interpretation**

These **regulated terms** must be interpreted—

- (a) in light of the purpose of Part 6 of this Code; and
- (b) so as to give business efficacy to the relationship between the **distributor** and the **distributed generator** created by Part 6 of this Code.

Compare: SR 2007/219 clause 2 Schedule 2

**3 General obligations**

- (1) The **distributor** and the **distributed generator** must perform all obligations under these **regulated terms** in accordance with **connection and operation standards** (where applicable).
- (2) The **distributor** and the **distributed generator** must each **construct**, connect, operate, test, and **maintain** their respective equipment in accordance with—
  - (a) these **regulated terms**; and
  - (b) **connection and operation standards** (where applicable); and
  - (c) this Code.
- (3) The **distributed generator** must, subject to subclause (2), **construct**, connect, operate, test, and **maintain** its **distributed generation** in accordance with—
  - (a) **reasonable and prudent operating practice**; and
  - (b) the applicable manufacturer's instructions and recommendations.
- (4) The **distributor** and **distributed generator** must each be fully responsible for the respective facilities they own or operate.
- (5) The **distributor** and **distributed generator** must each ensure that their respective facilities adequately protect each other's equipment, personnel, and other persons and their property, from damage and injury.
- (6) The **distributed generator** must comply with any conditions specified by the **distributor** under clause 18 of Schedule 6.1 (or, to the extent that those conditions were the subject of a dispute under clause 20(3) of that Schedule, or of negotiation during the period for negotiation of the connection contract, the conditions or other measures as finally resolved or negotiated).

Compare: SR 2007/219 clause 3 Schedule 2

Clause 3(1): amended, on 23 February 2015, by clause 51(1) of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 3(2) and (3): amended, on 5 October 2017, by clause 62(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 3(6): amended, on 23 February 2015, by clauses 51(2) and 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 3(6): amended, on 5 October 2017, by clause 62(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### *Meters*

#### **4 Installation of meters and access to metering information**

(1) *[Revoked]*

(2) The **distributed generator** must give the **distributor**, at the **distributor's** request, the interval data and cumulative data recorded by the **metering installations** at the **point of connection** at which the **distributed generation** is connected or is proposed to be connected.

(3) The **distributed generator** must provide **reactive** metering if—

(a) the **meter** for the **distributed generation** is part of a **category 2 metering installation**, or a higher category of **metering installation**; and

(b) the **distributed generator** is required to do so by the **distributor**.

(4) The **distributor's** requirements in respect of metering measurement and accuracy must be the same as set out in Part 10 of this Code.

Compare: SR 2007/219 clause 4 Schedule 2

Clause 4(1): revoked, on 23 February 2015, by clause 52(1) of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014. Clause 4(2): amended, on 5 October 2017, by clause 63 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 4(3): substituted, on 1 December 2011, by clause 5 of the Electricity Industry Participation Code (Distributor Use-of-System Agreements and Distributor Tariffs) Amendment 2011.

Clause 4(2) to (4): substituted, on 23 February 2015, by clause 52(2) of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

### *Access*

#### **5 Right of distributor to access distributed generator's premises**

(1) The **distributed generator** must provide the **distributor**, or a person appointed by the **distributor**, with safe and unobstructed access onto the **distributed generator's** premises at all reasonable times—

(a) for the purpose of installing, testing, inspecting, maintaining, repairing, replacing, operating, reading, or removing any of the **distributor's** equipment and for any other purpose related to these **regulated terms**; and

(b) for the purpose of verifying **metering information**; and

(c) for the purpose of ascertaining the cause of any interference to the quality of delivery services being provided by the **distributor** to the **distributed generator**; and

(d) for the purpose of protecting, or preventing danger or damage to, persons or property; and

(e) for the purposes of **electrically connecting** or **electrically disconnecting** the **distributed generation**; and

(f) for any other purpose relevant to either or both of—

- (i) the **distributor** connecting **distributed generation** in accordance with **connection and operation standards**; and
  - (ii) maintaining the integrity of the **distribution network**.
- (2) The rights of access conferred by these **regulated terms** are in addition to any right of access the **distributor** may have under a statute or regulation or contract.

Compare: SR 2007/219 clause 5 Schedule 2

Clause 5(1)(e): amended, on 5 October 2017, by clause 64(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 5(1)(f)(i): amended, on 23 February 2015, by clause 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 5(1)(f)(i): amended, on 5 October 2017, by clause 64(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

## **6 Process if distributor wants to access distributed generator's premises**

- (1) The **distributor** must exercise its right of access under clause 5 by,—
  - (a) wherever practicable, giving to the **distributed generator** reasonable notice of its intention and of the purpose for which it will exercise its right of access; and
  - (b) causing as little inconvenience as practicable to the **distributed generator** in carrying out its work; and
  - (c) observing **reasonable and prudent operating practice** at all times; and
  - (d) observing any reasonable security or site safety requirements that are made known to the **distributor** by the **distributed generator**.
- (2) However, the **distributor** may take all reasonable steps to gain immediate access where it reasonably believes there is immediate danger to persons or property.

Compare: SR 2007/219 clause 6 Schedule 2

## **7 Distributor must not interfere with distributed generator's equipment**

- (1) The **distributor** must not interfere with the **distributed generator's** equipment without the prior written consent of the **distributed generator**.
- (2) However, if emergency action has to be taken to protect the health and safety of persons, or to prevent damage to property, the **distributor**—
  - (a) may interfere with the **distributed generator's** equipment without prior written consent; and
  - (b) must, as soon as practicable, inform the **distributed generator** of the occurrence and circumstances involved.

Compare: SR 2007/219 clause 7 Schedule 2

## **8 Distributed generator must not interfere with, and must protect, distributor's equipment**

- (1) The **distributed generator** must not interfere with the **distributor's** equipment without the prior written consent of the **distributor**.
- (2) However, if emergency action has to be taken to protect the health and safety of persons, or to prevent damage to property, the **distributed generator**—
  - (a) may interfere with the **distributor's** equipment without prior written consent; and
  - (b) must, as soon as practicable, inform the **distributor** of the occurrence and circumstances involved.

- (3) The **distributed generator** must protect the **distributor's** equipment against interference and damage.  
Compare: SR 2007/219 clause 8 Schedule 2  
Clause 8(1): amended, on 23 February 2015, by clause 53 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

**9 Obligation to advise if interference with distributor's equipment or theft of electricity is discovered**

- (1) If the **distributor** or the **distributed generator** discovers evidence of interference with the **distributor's** equipment, or evidence of theft of **electricity**, the party discovering the interference or evidence must advise the other party within 24 hours.
- (2) If interference with the **distributor's** equipment at the **distributed generator's** installation is suspected, the **distributor** may itself carry out an investigation and present the findings to the **distributed generator** within a reasonable period.
- (3) The cost of the investigation—
- (a) must be borne by the **distributed generator** if it is discovered that interference by the **distributed generator**, or by its subcontractors, agents, or invitees, has occurred, or if the interference has been by a third party, and the **distributed generator** has failed to provide reasonable protection against interference to the **distributor's** equipment; and
- (b) must be borne by the **distributor** in any other case.

Compare: SR 2007/219 clause 9 Schedule 2

Heading: amended, on 23 February 2015, by clause 54(1) of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 9(1): amended, on 23 February 2015, by clause 54(2) of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

*Interruptions and disconnections*

**10 General obligation relating to interruptions**

The **distributor** must make reasonable endeavours to ensure that the connection of the **distributed generation** is not interrupted.

Compare: SR 2007/219 clause 10 Schedule 2

Clause 10: amended, on 23 February 2015, by clause 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 10: amended, on 5 October 2017, by clause 65 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

**11 Circumstances allowing distributor to temporarily electrically disconnect distributed generation**

Despite clause 10, the **distributor** may interrupt the connection service, or curtail either the operation or output of the generation, or both, and may temporarily **electrically disconnect** the **distributed generation** in any of the following cases:

- (a) in accordance with the **distributor's congestion management policy**;
- (b) if reasonably necessary for planned **maintenance, construction**, and repairs on the **distribution network**;
- (c) for the purpose of protecting, or preventing danger or damage to, persons or property;

- (d) if the **distributed generator** fails to allow the **distributor** access as required by clause 5;
- (e) *[Revoked]*
- (f) in accordance with clause 13 (adverse operating effects):
- (g) if the **distributed generator** fails to comply with the **distributor's**—
  - (i) **connection and operation standards**; or
  - (ii) **safety requirements**.

Compare: SR 2007/219 clause 11 Schedule 2

Heading: amended, on 5 October 2017, by clause 66(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 11: amended, on 23 February 2015, by clauses 55(1) and 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 11: amended, on 5 October 2017, by clause 66(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 11(e): revoked, on 23 February 2015, by clause 55(2) of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 11(g): inserted, on 23 February 2015, by clause 55(3) of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

## 12 **Obligations if distributed generation temporarily electrically disconnected by distributor**

- (1) The **distributor** must make reasonable endeavours to—
  - (a) advise the **distributed generator** before an interruption under clause 11; and
  - (b) co-ordinate with the **distributed generator** to minimise the impact of the interruption.
- (2) The **distributor** and the **distributed generator** must co-operate to restore the **distribution network** and the **distributed generation** to a normal operating state as soon as is reasonably practicable following the **distributed generation** being temporarily **electrically disconnected**.
- (3) In the case of a forced outage, the **distributor** must, subject to the need to restore the **distribution network**, make reasonable endeavours to—
  - (a) restore service to the **distributed generator**; and
  - (b) advise the **distributed generator** of the expected duration of the outage.

Compare: SR 2007/219 clause 12 Schedule 2

Heading: amended, on 5 October 2017, by clause 67(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 12(1)(a): amended, on 23 February 2015, by clause 56(1) of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 12(2): amended, on 5 October 2017, by clause 67(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 12(3): amended, on 23 February 2015, by clause 56(2) of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

## 13 **Adverse operating effects**

- (1) The **distributor** must advise the **distributed generator** as soon as is reasonably practicable if it reasonably considers that operation of the **distributed generation** may—
  - (a) adversely affect the service provided to other **distribution network** customers; or
  - (b) cause damage to the **distribution network** or other facilities; or
  - (c) present a hazard to a person.

- (2) If, after receiving that advice, the **distributed generator** fails to remedy the adverse operating effect within a reasonable time, the **distributor** may **electrically disconnect the distributed generation** by giving reasonable notice (or without notice when reasonably necessary in the event of an emergency or hazardous situation).

Compare: SR 2007/219 clause 13 Schedule 2

Clause 13(1): amended, on 23 February 2015, by clause 57(1) of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 13(2): amended, on 23 February 2015, by clause 57(2) of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 13(2): amended, on 5 October 2017, by clause 68 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

#### 14 Interruptions by distributed generator

- (1) This clause applies to any connected **distributed generation** above 10 kW in total.
- (2) The **distributed generator** must advise the **distributor** of any **planned outages** and must make reasonable endeavours to advise the **distributor** of an event that affects **distribution network** operations.
- (3) The **distributed generator** must make reasonable endeavours to advise the **distributor** of the interruption and to co-ordinate with the **distributor** to minimise the impact of the interruption.

Compare: SR 2007/219 clause 14 Schedule 2

Clause 14: amended, on 23 February 2015, by clauses 58 and 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 14(1): amended, on 5 October 2017, by clause 69 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

#### 15 Disconnecting distributed generation

- (1) Despite clause 10, the **distributor** may disconnect **distributed generation** in the following circumstances:
- (a) on receipt of a request from a **distributed generator**:
  - (b) without notice, if a **distributed generator** has been temporarily **electrically disconnected** under clause 11(g) and—
    - (i) the **distributed generator** fails to remedy the non-compliance within a reasonable period of time; and
    - (ii) there is an ongoing risk to persons or property:
  - (c) without notice, if the **trader** that is recorded in the **registry** as being responsible for the **ICP** to which the **distributed generation** is connected to the **distribution network** has **electrically disconnected the ICP** and updated the **ICP's** status in the **registry** to "inactive" with the reason of "electrically disconnected – ready for decommissioning":
  - (d) on at least 10 **business days'** notice of intention to disconnect, if—
    - (i) the **distributed generator** has not injected **electricity** into the **distribution network** at any time in the preceding 12 months; and
    - (ii) the **distributed generator** has not given written notice to the **distributor** of the reasons for the non-injection; and
    - (iii) the **distributor** has reasonable grounds for believing that the **distributed generator** has ceased to operate the **distributed generation**.
- (2) *[Revoked]*

- (3) If a **distributor** disconnects **distributed generation** under subclause (1) and the **point of connection** is to be **decommissioned**, the **distributor** must—
- (a) remove all electrical conductors between the **distributed generation** and the **distributor's lines**;
  - (b) advise the **distributed generator** within 2 **business days** of the completion of the work referred to in paragraph (a).

(4) *[Revoked]*

(5) *[Revoked]*

Compare: SR 2007/219 clause 15 Schedule 2

Heading: replaced, on 5 October 2017, by clause 70(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 15(1): amended, on 5 October 2017, by clause 70(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 15(1)(b): amended, on 5 October 2017, by clause 70(3) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 15(1)(b) and (c): substituted, on 23 February 2015, by clause 59(1) of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 15(1)(c): amended, on 5 October 2017, by clause 70(4) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 15(1)(d)(i): amended, on 23 February 2015, by clause 59(2) of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 15(1)(d)(ii): replaced, on 5 October 2017, by clause 70(5) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 15(2): revoked, on 23 February 2015, by clause 59(3) of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 15(3): amended, on 23 February 2015, by clause 59(4) of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 15(3): replaced, on 5 October 2017, by clause 70(6) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 15(4) and (5): revoked, on 23 February 2015, by clause 59(5) of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

### *Time frame for construction*

#### **15A Distributed generator must construct distributed generation within 18 months of approval**

- (1) This clause applies if the **distributor** approves the **distributed generator's** application to connect **distributed generation** under Part 1, Part 1A, or Part 2 of Schedule 6.1.
- (2) The **regulated terms** cease to apply if the **distributed generator** does not **construct the distributed generation** within—
  - (a) 18 months from the date on which approval was granted; or
  - (b) such later date as is agreed by the **distributor** and **distributed generator**.
- (3) The **distributed generator** must reapply under Schedule 6.1 if—
  - (a) the **regulated terms** no longer apply in accordance with subclause (1); and
  - (b) the **distributed generator** wishes to connect **distributed generation** to the **distributor's distribution network**.

Cross heading and clause 15A: inserted, on 23 February 2015, by clause 60 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 15A: amended, on 5 October 2017, by clause 71 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

*Confidentiality*

**16 General obligations relating to confidentiality**

- (1) Each party must preserve the confidentiality of **confidential information**, and must not directly or indirectly reveal, report, publish, transfer, or disclose the existence of any **confidential information**, except as permitted in subclause (2).
- (2) Each party must only use **confidential information** for the purposes expressly permitted by these **regulated terms**.

Compare: SR 2007/219 clause 17 Schedule 2

**17 When confidential information can be disclosed**

Either party may disclose **confidential information** in any of the following circumstances:

- (a) if the **distributed generator** and **distributor** agree in writing to the disclosure of information;
- (b) if disclosure is expressly provided for under these **regulated terms**;
- (c) if, at the time of receipt by the party, the **confidential information** is in the public domain or if, after the time of receipt by either party, the **confidential information** enters the public domain (except where it does so as a result of a breach by either party of its obligations under this clause or a breach by any other person of that person's obligation of confidence);
- (d) if either party is required to disclose **confidential information** by—
  - (i) a statutory or regulatory obligation, body, or authority; or
  - (ii) a judicial or arbitration process; or
  - (iii) the regulations of a stock exchange upon which the share capital of either party is from time to time listed or dealt in; or
  - (iv) this Code;
- (e) if the **confidential information** is released to the officers, employees, directors, agents, or advisors of the party, provided that—
  - (i) the information is disseminated only on a need-to-know basis; and
  - (ii) recipients of the **confidential information** have been made fully aware of the party's obligations of confidence in relation to the information; and
  - (iii) any copies of the information clearly identify it as **confidential information**;
- (f) if the **confidential information** is released to a bona fide potential purchaser of the business or any part of the business of a party, subject to that bona fide potential purchaser having signed a confidentiality agreement enforceable by the other party in a form approved by that other party, and that approval may not be unreasonably withheld.

Compare: SR 2007/219 clause 18 Schedule 2



## 18 Disclosures by employees, agents, etc

To avoid doubt, a party is responsible for any unauthorised disclosure of **confidential information** made by that party's officers, employees, directors, agents, or advisors.

Compare: SR 2007/219 clause 19 Schedule 2

### *Pricing*

## 19 Pricing principles

Charges that are payable by the **distributed generator** or the **distributor** must be determined in accordance with the pricing principles set out in Schedule 6.4.

Compare: SR 2007/219 clause 20 Schedule 2

Clause 19: amended, on 23 February 2015, by clause 61 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

### *Liability*

## 20 General obligations relating to liability

- (1) If the **distributor** or the **distributed generator** breaches any of the **regulated terms** (whether by act or omission), that party is liable to the other.
- (2) The **distributed generator's** and the **distributor's** liability to each other is limited to damages for any direct loss caused by that breach.
- (3) This clause and clauses 21 to 25 do not limit the liability of either party to pay all charges and other amounts due under Part 6 of this Code or the **regulated terms**.

Compare: SR 2007/219 clause 21 Schedule 2

Clause 20(1) and (3): amended, on 23 February 2015, by clause 62 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

## 21 Exceptions to obligations relating to liability

- (1) Neither the **distributor** nor the **distributed generator**, nor any of its officers, employees, directors, agents, or advisors, are in any circumstances liable to the other party for—
  - (a) any indirect loss, consequential loss (including, but not limited to, incidental or special damages), loss of profit, loss of revenue (except any liability under clause 20(3)), loss of use, loss of opportunity, loss of contract, or loss of goodwill; or
  - (b) any loss resulting from the liability of the other party to another person; or
  - (c) any loss or damage incurred by the other party if, and to the extent that, this results from any breach of the **regulated terms** or any negligent action.
- (2) The **distributor** is not liable, except to the extent caused or contributed to by the **distributor** in circumstances where the **distributor** was not acting in accordance with Part 6 of this Code (including these **regulated terms**), for—
  - (a) any momentary fluctuations in the voltage or frequency of **electricity** conveyed to or from the **distributed generation's point of connection** or nonconformity with harmonic voltage and current levels; or
  - (b) any failure to convey **electricity** to the extent that—
    - (i) the failure arises from any act or omission of the **distributed generator** or other person, excluding the **distributor** and its officers, employees, directors, agents, or advisors; or

- (ii) the failure arises from a reduced **injection** of **electricity** into the **distribution network**; or
  - (iia) the failure arises from an interruption in the conveyance of **electricity** in the **distribution network**, if the interruption was at the request of the **system operator** or under a nationally or regionally co-ordinated response to an **electricity** shortage; or
  - (iii) the failure arises from any defect or abnormal conditions in or about the **distributed generator's** premises; or
  - (iv) the **distributor** was taking any action in accordance with Part 6 of this Code or the **regulated terms**; or
  - (v) the **distributor** was prevented from making necessary repairs (for example, by police at an accident scene).
- (3) The **distributed generator** is not liable for—
- (a) a failure to perform an obligation under these **regulated terms** caused by the **distributor's** failure to comply with the obligation; or
  - (b) a failure to perform an obligation under these **regulated terms** arising from any defect or abnormal conditions in the **distribution network**.

Compare: SR 2007/219 clause 22 Schedule 2

Clause 21(1): amended, on 23 February 2015, by clause 63(1) of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 21(2)(b)(ii): substituted, on 23 February 2015, by clause 63(2) of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 21(2)(b)(iia): inserted, on 23 February 2015, by clause 63(3) of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

## 22 Limits on liability

The maximum total liability of each party, as a result of a breach of the **regulated terms**, must not in any circumstances exceed, in respect of a single event or series of events arising from the same event or circumstance, the lesser of—

- (a) the direct damage suffered or the maximum total liability that the party bringing the claim against the other party has at the time that the event (or, in the case of a series of related events, the first of such events) giving rise to the liability occurred; or
- (b) \$1,000 per kW of **nameplate capacity** up to a maximum of \$5 million.

Compare: SR 2007/219 clause 23 Schedule 2

Clause 22(b): amended, on 23 February 2015, by clause 64 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

## 23 Liability clauses do not apply to fraud, wilful breach, and breach of confidentiality

The exceptions in clause 21, and the limits on liability in clause 22, do not apply—

- (a) if the **distributor** or the **distributed generator**, or any of its officers, employees, directors, agents, or advisors, has acted fraudulently or wilfully in breach of these **regulated terms**; or
- (b) to a breach of confidentiality under clause 16 by either party.

Compare: SR 2007/219 clause 24 Schedule 2

Clause 23(a): amended, on 23 February 2015, by clause 65 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

**24** *[Revoked]*

Compare: SR 2007/219 clause 25 Schedule 2

Clause 24: revoked, on 23 February 2015, by clause 66 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

**25 Force majeure**

- (1) A failure by either party to comply with or observe any provisions of these **regulated terms** (other than payment of any amount due) does not give rise to any cause of action or liability based on default of the provision if—
- (a) the failure is caused by—
- (i) an event or circumstance occasioned by, or in consequence of, an act of God, being an event or circumstance—
    - (A) due to natural causes, directly or indirectly and exclusively without human intervention; and
    - (B) that could not reasonably have been foreseen or, if foreseen, could not reasonably have been resisted; or
  - (ii) a strike, lockout, other industrial disturbance, act of public enemy, war, blockade, insurrection, riot, epidemic, aircraft, or civil disturbance; or
  - (iii) the binding order or requirement of a Court, government, **local authority**, the **Rulings Panel**, or the **Authority**, and the failure is not within the reasonable control of the affected party; or
  - (iv) the partial or entire failure of the **injection of electricity** into the **distribution network**; or
  - (v) any other event or circumstance beyond the control of the party invoking this clause; and
- (b) the party could not have prevented such failure by the exercise of the degree of skill, diligence, prudence, and foresight that would reasonably and ordinarily be expected from a skilled and experienced **distributor** or **distributed generator** engaged in the same type of undertaking under the same or similar circumstances in New Zealand at the time.
- (2) If a party becomes aware of a prospect of a forthcoming **force majeure event**, it must advise the other party as soon as is reasonably practicable of the particulars of which it is aware.
- (3) If a party invokes this clause, it must as soon as is reasonably practicable advise the other party that it is invoking this clause and of the full particulars of the **force majeure event** relied on.
- (4) The party invoking this clause must—
- (a) use all reasonable endeavours to overcome or avoid the **force majeure event**; and
  - (b) use all reasonable endeavours to mitigate the effects or the consequences of the **force majeure event**; and
  - (c) consult with the other party on the performance of the obligations referred to in paragraphs (a) and (b).
- (5) Nothing in subclause (4) requires a party to settle a strike, lockout, or other industrial disturbance by acceding, against its judgement, to the demands of opposing parties.

Compare: SR 2007/219 clause 26 Schedule 2

**Electricity Industry Participation Code 2010**  
**Schedule 6.2**

---

Clause 25(1)(a)(iv): substituted, on 23 February 2015, by clause 67(1) of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 25(2) and (3): amended, on 23 February 2015, by clause 67(2) of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

## Schedule 6.3 Default dispute resolution process

cl 6.8

### Contents

- 1 Application of this schedule
  - 2 Notice of dispute
  - 3 Complaints
  - 4 Application of pricing principles to disputes
  - 5 Orders that Rulings Panel can make
- 

#### 1 Application of this Schedule

This Schedule applies in accordance with clause 6.8.

Compare: SR 2007/219 clause 1 Schedule 3

Clause 1: substituted, on 23 February 2015, by clause 68 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

#### 2 Notice of dispute

- (1) A party must give written notice to the other party of the dispute.
- (2) The parties must attempt to resolve the dispute with each other in good faith.
- (3) If the parties are unable to resolve the dispute, either party may complain in writing to the **Authority**.

Compare: SR 2007/219 clause 2 Schedule 3

#### 3 Complaints

- (1) A complaint made under clause 2(3) must be treated as if it were a notification given under regulations made under section 112 of the **Act**.
- (2) The following provisions apply to the complaint:
  - (a) sections 53-62 of the **Act**; and
  - (b) the Electricity Industry (Enforcement) Regulations 2010 except regulations 5, 6, 7, 9, 17, 51 to 75, and subpart 2 of Part 3.
- (3) Those provisions apply—
  - (a) to the dispute that is the subject of the complaint in the same way as those provisions apply to a notification of an alleged breach of this Code; and
  - (b) as if references to a **participant** in those provisions were references to a party under Part 6 of this Code; and
  - (c) with any further modifications that the **Authority** or the **Rulings Panel**, as the case may be, considers necessary or desirable for the purpose of applying those provisions to the complaint.

Compare: SR 2007/219 clause 3 Schedule 3

#### 4 Application of pricing principles to disputes

- (1) The **Authority** and the **Rulings Panel** must apply the pricing principles set out in Schedule 6.4 to determine any connection charges payable.
- (2) Subclause (1) applies if—

- (a) there is a dispute under Part 6 of this Code; and
- (b) in the opinion of the **Authority** or the **Rulings Panel** it is necessary or desirable to apply subclause (1) in order to resolve the dispute.

Compare: SR 2007/219 clause 4 Schedule 3

Clause 4(1): amended, on 23 February 2015, by clause 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 4(1): amended, on 5 October 2017, by clause 72 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

## **5 Orders that Rulings Panel can make**

If a complaint is referred to it, the **Rulings Panel** may make any order, or take any action, that it is able to make or take in accordance with section 54 of the **Act**.

Compare: SR 2007/219 clause 5 Schedule 3

## Schedule 6.4 Pricing principles

cl 6.9

- 1 This Schedule sets out the pricing principles to be applied for the purposes of Part 6 of this Code in accordance with clause 6.9 (which relates to clause 19 of Schedule 6.2 and clause 4 of Schedule 6.3).

Compare: SR 2007/219 clause 1 Schedule 4

Clause 1: amended, on 23 February 2015, by clause 69 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

- 2 The pricing principles are as follows:

*Charges to be based on recovery of reasonable costs incurred by distributor to connect the distributed generator and to comply with connection and operation standards within the distribution network, and must include consideration of any identifiable avoided or avoidable costs*

- (a) subject to paragraph (i), connection charges in respect of **distributed generation** must not exceed the **incremental costs** of providing connection services to the **distributed generation**. To avoid doubt, **incremental cost** is net of—
  - (i) if the **distributed generation** is included in a list **published** by the **Authority** under clause 2C(1), transmission costs that an efficient **distributor** would be able to avoid as a result of the **electrical connection** of the **distributed generation** at the **nameplate capacity** specified for that **distributed generation** in the list; and
  - (ii) **distribution** costs that an efficient **distributor** would be able to avoid as a result of the **electrical connection** of the **distributed generation**:
- (b) costs that cannot be calculated (eg, avoidable costs) must be estimated with reference to reasonable estimates of how the **distributor's** capital investment decisions and operating costs would differ, in the future, with and without the generation:
- (c) estimated costs may be adjusted ex post. Ex-post adjustment involves calculating, at the end of a period, what the actual costs incurred by the **distributor** as a result of the **distributed generation** being **electrically connected** to the **distribution network** were, and deducting the costs that would have been incurred had the generation not been **electrically connected**. In this case, if the costs differ from the costs charged to the **distributed generator**, the **distributor** must advise the **distributed generator** and recover or refund those costs after they are incurred (unless the **distributor** and the **distributed generator** agree otherwise):

*Capital and operating expenses*

- (d) if costs include distinct capital expenditure, such as costs for a significant **asset** replacement or upgrade, the connection charge attributable to the **distributed generator's** actions or proposals is payable by the **distributed generator** before

the **distributor** has committed to incurring those costs. When making reasonable endeavours to facilitate connection, the **distributor** is not obliged to incur those costs until that payment has been received:

- (e) if **incremental costs** are negative, the **distributed generator** is deemed to be providing network support services to the **distributor**, and may invoice the **distributor** for this service and, in that case, the **distributed generator** must comply with all relevant obligations (for example, obligations under Part 6 of this Code and in respect of tax):
- (f) if costs relate to ongoing or periodic operating expenses, such as costs for routine **maintenance**, the connection charge attributable to the **distributed generator's** actions or proposals may take the form of a periodic charge:
- (g) *[Revoked]*
- (h) after the connection of the **distributed generation**, the **distributor** may review the connection charges payable by a **distributed generator** not more than once in any 12-month period. Following a review, the **distributor** must advise the **distributed generator** in writing of any change in the connection charges payable, and the reasons for any change, not less than 3 months before the date the change is to take effect:

*Share of generation-driven costs*

- (i) if multiple **distributed generators** are sharing an investment, the portion of costs payable by any 1 **distributed generator**—
  - (i) must be calculated so that the charges paid or payable by each **distributed generator** take into account the relative expected peak of each **distributed generator's** injected generation; and
  - (ii) may also have regard to the percentage of **assets** that will be used by each **distributed generator**, the percentage of **distribution network capacity** used by each **distributed generator**, the relative share of expected maximum combined peak output, and whether the combined peak generation is coincident with the peak load on the **distribution network**:
- (j) in order to facilitate the calculation of equitable connection charges under paragraph (i), the **distributor** must make and retain adequate records of investments for a period of 60 months, provide the rationale for the investment in terms of facilitating **distributed generation**, and indicate the extent to which the associated costs have been or are to be recovered through generation connection charges:

*Repayment of previously funded investment*

- (k) if a **distributed generator** has paid connection charges that include (in part) the cost of an investment that is subsequently shared by other **distributed generators**, the **distributor** must refund to the **distributed generator** all connection charges paid to the **distributor** under paragraph (i) by other **distributed generators** in respect of that investment:



- (l) if there are multiple prior **distributed generators**, a refund to each **distributed generator** referred to in paragraph (k) must be provided in accordance with the expected peak of that **distributed generator's** injected generation over a period of time agreed between the **distributed generator** and the **distributor**. The refund—
- (i) must take into account the relative expected peak of each **distributed generator's** injected generation; and
  - (ii) may also have regard to the percentage of **assets** that will be used by each **distributed generator**, the percentage of **distribution network capacity** used by each **distributed generator**, the relative share of expected maximum combined peak output, and whether the combined peak generation is coincident with the peak load on the **distribution network**:
- (m) no refund of previous payments from the **distributed generator** referred to in paragraph (k) is required after a period of 36 months from the initial connection of that **distributed generator**:

*Non-firm connection service*

- (n) to avoid doubt, nothing in Part 6 of this Code creates any **distribution network capacity** or property rights in any part of the **distribution network** unless these are specifically contracted for. **Distributors** must **maintain** connection and **lines** services to **distributed generators** in accordance with their **connection and operation standards**.

Compare: SR 2007/219 clause 2 Schedule 4

Heading: amended, on 23 February 2015, by clause 70(1) of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 2: amended, on 23 February 2015, by clause 70(2) of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 2(a): amended, on 23 February 2015, by clauses 70(3) and 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 2(a): replaced, on 9 January 2017, by clause 4 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2016.

Clause 2(a): amended, on 5 October 2017, by clause 73(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 2(c): amended, on 23 February 2015, by clauses 70(4) and 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 2(c): amended, on 5 October 2017, by clause 73(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 2(d): amended, on 23 February 2015, by clause 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 2(d), (f), (h), (j), (k), and (m): amended, on 5 October 2017, by clause 73(3) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 2(f): amended, on 23 February 2015, by clauses 70(5) and 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 2(g): revoked, on 23 February 2015, by clause 70(6) of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 2(h): amended, on 23 February 2015, by clauses 70(7) and 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 2(i)(ii): amended, on 23 February 2015, by clause 70(8) of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 2(j): amended, on 23 February 2015, by clauses 70(9) and 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 2(k): amended, on 23 February 2015, by clause 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 2(l)(ii): amended, on 23 February 2015, by clause 70(10) of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 2(m): amended, on 23 February 2015, by clauses 70(11) and 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 2(n): amended, on 23 February 2015, by clauses 70(2) and 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 2(n): amended, on 5 October 2017, by clause 73(4) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

**2A Transpower to provide reports to Authority in relation to distributed generation**

- (1) **Transpower** must, by 15 March 2017 (or such later date as the **Authority** may allow), provide a report to the **Authority** that identifies which (if any) **distributed generation** located in the Lower South Island is required for **Transpower** to meet the **grid reliability standards** in the period from 1 April 2017 to 31 March 2020.
- (2) **Transpower** must, by 30 August 2017, provide a report to the **Authority** that identifies which (if any) **distributed generation** located in the Lower North Island is required for **Transpower** to meet the **grid reliability standards** in the period from 1 April 2017 to 31 March 2020.
- (3) **Transpower** must, by 31 January 2018, provide a report to the **Authority** that identifies which (if any) **distributed generation** located in the Upper North Island is required for **Transpower** to meet the **grid reliability standards** in the period from 1 April 2017 to 31 March 2020.
- (4) **Transpower** must, by 31 January 2018, provide a report to the **Authority** that identifies which (if any) **distributed generation** located in the Upper South Island is required for **Transpower** to meet the **grid reliability standards** in the period from 1 April 2017 to 31 March 2020.
- (5) In this clause and clause 4,—
  - (a) Upper North Island is that part of the North Island situated on, or north and west of, a line—
    - (i) commencing at 38°02'S and 174°42'E; then
    - (ii) proceeding in a generally north-easterly direction directly to 37°36'S and 175°27'E; then
    - (iii) proceeding north along the 175°27'E line of longitude; and
  - (b) Lower North Island is that part of the North Island not referred to in subclause (a); and
  - (c) Upper South Island is that part of the South Island situated on, or north of, a line passing through 43°30'S and 169°30'E, and 44°40'S and 171°12'E; and
  - (d) Lower South Island is that part of the South Island not referred to in subclause (c).

Clause 2A: inserted, on 9 January 2017, by clause 5 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2016.

Clause 2A(5): amended, on 5 October 2017, by clause 74 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

**2B Authority to review Transpower's reports in relation to distributed generation**

- (1) The **Authority** must, as soon as practicable after receiving a report from **Transpower** under clause 2A,—
  - (a) approve the report; or
  - (b) decline to approve the report.
- (2) If the **Authority** declines to approve the report,—
  - (a) the **Authority** must, as soon as practicable,—
    - (i) advise **Transpower** of its reasons for declining to approve the report; and

- (ii) direct **Transpower** as to how it should amend the report before resubmitting it; and
  - (b) **Transpower** must amend the report in accordance with the **Authority's** direction, and resubmit the report to the **Authority**,—
    - (i) for the report provided under clause 2A(1), within 10 **business days**; and
    - (ii) for reports provided under clauses 2A(2), (3), or (4), within 20 **business days**.
  - (3) The **Authority** must, as soon as practicable after receiving a resubmitted report from **Transpower**,—
    - (a) approve the report; or
    - (b) decline to approve the report.
  - (4) Subclause (2) applies to the resubmitted report as if it were the report originally provided under clause 2A.
- Clause 2B: inserted, on 9 January 2017, by clause 5 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2016.

## **2C Authority to publish list of distributed generation**

- (1) The **Authority** must, after approving a report provided by **Transpower** under clause 2A, **publish** a list of **distributed generation** for the relevant region for the purposes of clause 2(a)(i).
  - (2) A list **published** under subclause (1) must include—
    - (a) only **distributed generation** that is connected as at 6 December 2016; and
    - (b) the **nameplate capacity** of the **distributed generation** as at 6 December 2016.
- Clause 2C: inserted, on 9 January 2017, by clause 5 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2016.
- Clause 2C(2)(a): amended, on 5 October 2017, by clause 75 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

## **3 [Revoked]**

Compare: SR 2007/219 clause 3 Schedule 4

Clause 3: revoked, on 23 February 2015, by clause 71 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

## **4 Delayed application of Electricity Industry Participation Code Amendment (Distributed Generation) 2016**

- (1) Despite clause 2 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2016,—
  - (a) until the close of 31 March 2018, Part 6 of this Code applies to the Lower South Island as if the Electricity Industry Participation Code Amendment (Distributed Generation) 2016 had not been made; and
  - (b) until the close of 30 September 2018, Part 6 of this Code applies to the Lower North Island as if the Electricity Industry Participation Code Amendment (Distributed Generation) 2016 had not been made; and
  - (c) until the close of 31 March 2019, Part 6 of this Code applies to the Upper North Island as if the Electricity Industry Participation Code Amendment (Distributed Generation) 2016 had not been made; and
  - (d) until the close of 30 September 2019, Part 6 of this Code applies to the Upper South Island as if the Electricity Industry Participation Code Amendment (Distributed Generation) 2016 had not been made.

- (2) In this clause, Upper North Island, Lower North Island, Upper South Island, and Lower South Island have the meanings set out in clause 2A(5).

Clause 4: inserted, on 5 October 2017, by clause 76 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

## Schedule 6.5 cls 2(4), 7(5), 11(4), and 22(5) of Sch 6.1 Prescribed maximum fees

1 *[Revoked]*

Clause 1: revoked, on 23 February 2015, by clause 72 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

- 2 A **distributor** may require the payment of fees for any of the following activities prescribed under Part 6 of this Code to the maximum fee specified in the column opposite that activity:

Description of fee	\$ (exclusive of GST)
<b>Part 1 of Schedule 6.1 application</b>	
Application fee under clause 2(2)(c)	200
Fee for observation of testing and inspection under clause 7(5)	60
<b>Part 1A of Schedule 6.1 application</b>	
Application fee under clause 9B(2)(c)	100
Fee for inspection under clause 9C(3)	60
Deficiency fee under clause 9E(4)	80
<b>Part 2 of Schedule 6.1 application</b>	
Application fee for <b>distributed generation</b> with <b>nameplate capacity</b> of more than 10 kW but less than 100 kW under clause 11(2)(c)	500
Application fee for <b>distributed generation</b> with <b>nameplate capacity</b> of 100 kW or more in total but less than 1 MW under clause 11(2)(c)	1,000
Application fee for <b>distributed generation</b> with <b>nameplate capacity</b> of 1 MW or more under clause 11(2)(c)	5,000
Fee for observation of testing and inspection of <b>distributed generation</b> with	120

**Electricity Industry Participation Code 2010**  
**Schedule 6.5**

---

<b>nameplate capacity</b> of more than 10 kW but less than 100 kW under clause 22(5)	
Fee for observation of testing and inspection of <b>distributed generation</b> with <b>nameplate capacity</b> of 100 kW or more under clause 22(5)	1,200

Compare: SR 2007/219 Schedule 5

Clause 2: substituted, on 23 February 2015, by clause 73 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

# Electricity Industry Participation Code 2010

## Part 7 System operator

### Contents

7.1	Contents of this Part
7.1A	Reasonable and prudent system operator standard
7.2	Principal performance obligations of the system operator in relation to common quality and dispatch
7.2A	System operator to maintain frequency
7.2B	System operator to restore frequency if frequency fluctuation occurs
7.2C	System operator to manage frequency time error
7.2D	System operator to identify and resolve problems
7.2E	System operator to report on frequency fluctuations
7.3	Functions of system operator in relation to security of supply and emergency management
7.4	Incorporation of security of supply forecasting and information policy and emergency management policy by reference
7.5	Approval of draft security of supply forecasting and information policy and emergency management policy
7.6	Variations to security of supply forecasting and information policy and emergency management policy
7.7	System operator and Authority joint development programme
7.8	Review of system operator
7.9	Additional matters to be taken into account in system operator review
7.10	Separation of Transpower roles
7.11	Review of performance of the system operator
7.12	Authority must publish system operator reports

---

### 7.1 Contents of this Part

This Part provides for—

- (aa) a reasonable and prudent **system operator** standard; and
- (a) high level, output focussed performance obligations of the **system operator** in relation to the real time co-ordination and delivery of **common quality** and **dispatch**; and
- (b) the functions of the **system operator** in relation to **demand** and supply forecasting, security of supply, and supply emergencies; and
- (c) review of the **system operator's** performance under the **Act**, this Code, and the relevant **market operation service provider agreement**.

Clause 7.1(aa): inserted, on 19 May 2016, by clause 7(1) of the Electricity Industry Participation Code Amendment (System Operator and Alignment with Statutory Objective) 2016.

Clause 7.1(a): amended, on 19 May 2016, by clause 7(2) of the Electricity Industry Participation Code Amendment (System Operator and Alignment with Statutory Objective) 2016.

Clause 7.1(b): amended, on 19 May 2016, by clause 7(3) of the Electricity Industry Participation Code Amendment (System Operator and Alignment with Statutory Objective) 2016.

Clause 7.1(c): amended, on 19 May 2016, by clause 7(4) of the Electricity Industry Participation Code Amendment (System Operator and Alignment with Statutory Objective) 2016.

### 7.1A Reasonable and prudent system operator standard

- (1) The **system operator** must carry out its obligations under this Code with skill, diligence, prudence, foresight, good economic management, and in accordance with recognised international good practice, taking into account—
  - (a) the circumstances in New Zealand; and
  - (b) the fact that real-time co-ordination of the power system involves complex judgements and inter-related events.
- (2) The **system operator** does not breach a **principal performance obligation** or clause 8.5 of this Code if the **system operator** complies with subclause (1).

Clause 7.1A: inserted, on 19 May 2016, by clause 8 of the Electricity Industry Participation Code Amendment (System Operator and Alignment with Statutory Objective) 2016.

### 7.2 Principal performance obligations of the system operator in relation to common quality and dispatch

The obligations in clauses 7.2A to 7.2D are **principal performance obligations**.

Clause 7.2: amended, on 19 May 2016, by clause 9 of the Electricity Industry Participation Code Amendment (System Operator and Alignment with Statutory Objective) 2016.

#### 7.2A System operator to maintain frequency

- (1) The **system operator** must **dispatch assets** made available in a manner that avoids cascade failure of **assets** resulting in a loss of **electricity** to **consumers** arising from—
  - (a) a frequency or voltage excursion; or
  - (b) a **supply** and **demand** imbalance.
- (2) Except as provided in this clause and clause 7.2B, the **system operator** must maintain frequency in the **normal band**.
- (3) The **system operator** must ensure that the scheduling, pricing, and dispatch tool has the information necessary to schedule a minimum quantity of **instantaneous reserve**.
- (4) Subject to the availability of **offers** or **reserve offers**, the **system operator** must schedule sufficient **instantaneous reserve** to meet the **system operator's** obligations in subclauses (5) to (7).
- (5) During a contingent event, the **system operator** must ensure that, for the **island** in which the contingent event takes place—
  - (a) frequency remains at or above 48 Hertz; and
  - (b) frequency returns to or above 49.25 Hertz within 60 seconds after the contingent event.
- (6) During an extended contingent event in the North Island, the **system operator** must ensure that, for that **island**—
  - (a) frequency remains at or above 47 Hertz; and
  - (b) frequency does not drop to or below 47.1 Hertz for longer than 5 seconds; and
  - (c) frequency does not drop to or below 47.3 Hertz for longer than 20 seconds; and
  - (d) frequency returns to or above 49.25 Hertz within 60 seconds after the extended contingent event.



- (7) During an extended contingent event in the South Island, the **system operator** must ensure that, for that **island**—
- (a) frequency remains at or above 45 Hertz; and
  - (b) frequency returns to or above 49.25 Hertz within 60 seconds after the extended contingent event.

#### 7.2B System operator to restore frequency if frequency fluctuation occurs

If a **frequency fluctuation** occurs, the **system operator** must ensure that frequency is restored to the **normal band** as soon as reasonably practicable having regard to all circumstances surrounding the **frequency fluctuation**.

#### 7.2C System operator to manage frequency time error

- (1) The **system operator** must ensure that any deviations from **New Zealand standard time** in the power system, caused by variations in system frequency, do not exceed 5 seconds.
- (2) At least once in each day, the **system operator** must eliminate from the power system any deviations from **New Zealand standard time** caused by variations in system frequency.

#### 7.2D System operator to identify and resolve problems

- (1) A **participant** may request that the **system operator** investigate and resolve a security of supply or reliability problem arising from non-compliance with a standard in clause 4.7, 4.8, or 4.9 of the **Connection Code**, at any **point of connection** to the **grid**.
- (2) If the **system operator** receives a reasonable request under subclause (1), the **system operator** must, given the **assets** made available to it at the relevant time—
  - (a) identify whether there is a security of supply or reliability problem arising from non-compliance with a standard in clause 4.7, 4.8, or 4.9 of the **Connection Code**, at any **point of connection** to the **grid**; and
  - (b) if there is such a problem—
    - (i) identify the cause of the problem; and
    - (ii) resolve the problem to the extent reasonable and practical.

#### 7.2E System operator to report on frequency fluctuations

- (1) By the 10<sup>th</sup> **business day** of each month (except by the 20<sup>th</sup> **business day** in the month of January), the **system operator** must report to the **Authority** the number of **frequency fluctuations** in each of the following frequency bands, in each **island** in the previous month:

Frequency band (Hertz) (where "x" is the maximum or minimum frequency during a <b>frequency fluctuation</b> )				
52.00	>	x	≥	51.25
51.25	>	x	≥	50.50

49.50	>	x	≥	48.75
48.75	>	x	≥	48.00
48.00	>	x	≥	47.00

- (2) By the 10<sup>th</sup> **business day** of each month (except by the 20<sup>th</sup> **business day** in the month of January), the **system operator** must report to the **Authority** the number of **frequency fluctuations** in each of the following frequency bands, in the South Island in the previous month:

Frequency band (Hertz) (where "x" is the maximum or minimum frequency during a <b>frequency fluctuation</b> )				
55.00	>	x	≥	53.75
53.75	>	x	≥	52.00
47.00	>	x	≥	45.00

Compare: Electricity Governance Rules 2003 rules 2 and 3 section II part C

Clauses 7.2A-E: inserted, on 19 May 2016, by clause 10 of the Electricity Industry Participation Code Amendment (System Operator and Alignment with Statutory Objective) 2016.

Clause 7.2E: amended, on 5 October 2017, by clause 77 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### 7.3 Functions of system operator in relation to security of supply and emergency management

- (1) The **system operator** must—
- (a) prepare and **publish** a **security of supply forecasting and information policy** that includes a requirement that the **system operator**—
    - (i) prepare and **publish** at least annually a security of supply assessment that contains detailed supply and demand forecasts for at least 5 years, which assists interested parties to assess whether the energy security of supply standard and the capacity security of supply standard set out in subclause (2) are likely to be met; and
    - (ii) consult with persons that the **system operator** thinks are representative of the interests of persons likely to be substantially affected by a security of supply assessment prepared under subparagraph (i) before **publishing** such an assessment; and
    - (iii) prepare and **publish** information that assists interested parties to monitor how hydro and thermal generating capacity, transmission assets, primary fuel, and **ancillary services** are being utilised to manage risks of shortage, including extended dry periods; and
    - (iv) **publish**, in relation to the information **published** under subparagraphs (i) and (iii), sufficient details of the modelling data, assumptions, and

- methodologies that the **system operator** has used to prepare that information as to allow interested parties to recreate that information (but without **publishing** information that is confidential to any **participant**); and
- (b) implement and comply with the **security of supply forecasting and information policy** prepared and **published** in accordance with paragraph (a).
- (2) For the purposes of subclause (1)(a)(i)—
- (a) the energy security of supply standard is a **winter energy margin** of 14-16% for New Zealand and a **winter energy margin** of 25.5-30% for the South Island; and
- (b) the capacity security of supply standard is a **winter capacity margin** of 630-780 MW for the North Island.
- (2A) The **Authority** may **publish** a security standards assumptions document.
- (2B) Subject to subclauses (2C) and (2D), if the **Authority** has **published** a security standards assumptions document under subclause (2A), the **system operator** must use the assumptions set out in that document in preparing a security of supply assessment under the **security of supply forecasting and information policy**.
- (2C) The **system operator** may use different assumptions from those in a security standards assumptions document to prepare a security of supply assessment if—
- (a) the **system operator** considers that there are good reasons to use different assumptions; and
- (b) the **system operator** includes in the security of supply assessment—
- (i) a detailed explanation of the assumptions used to prepare the security of supply assessment; and
- (ii) a statement of reasons for using those assumptions instead of the assumptions **published** by the **Authority**; and
- (iii) a description of how the security of supply assessment prepared using those assumptions differs from a security of supply assessment prepared using the assumptions set out in the security standards assumptions document.
- (2D) Despite subclause (2C), the **system operator** is not required to include the information referred to in subclause (2C)(b) in a security of supply assessment if the **system operator** considers that it would have good reason to refuse to supply the information under clause 2.6.
- (3) The **system operator** must —
- (a) prepare and **publish** an **emergency management policy** that sets out the steps that the **system operator** must take, and must encourage **participants** to take, at various stages during an extended emergency such as an extended dry sequence or an extended period of capacity inadequacy; and
- (b) include in the **emergency management policy** the steps that, at various stages in anticipation of and during a gas transmission failure or gas supply failure to **generators**, the **system operator** must—
- (i) take as the **system operator**; and
- (ii) encourage **participants** to take, including, if appropriate, steps for relevant **participants** to take in conjunction with gas industry entities; and
- (iii) encourage relevant gas industry entities to take; and
- (c) implement and comply with the **emergency management policy** .

- (4) The **emergency management policy** is not required to include information that is already set out in—
- (a) the **system operator rolling outage plan** prepared under subpart 1 of Part 9; or
  - (b) the **policy statement**; or
  - (c) **Technical Code B** of Schedule 8.3.
- (5) The **system operator** may depart from the policies set out in an **emergency management policy** if an **EMP departure situation** arises and such departure is required to enable the **system operator** to comply with clause 7.1A(1).
- (6) If the **system operator** makes a departure under subclause (5), the **system operator** must provide a report to the **Authority** setting out the circumstances of the **EMP departure situation** and the actions taken to deal with it. The **Authority** must **publish** the report within a reasonable time of its receipt.

Heading: amended, on 5 October 2017, by clause 78(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 7.3(1): amended, on 19 May 2016, by clause 11(1) of the Electricity Industry Participation Code Amendment (System Operator and Alignment with Statutory Objective) 2016.

Clause 7.3(1)(a): amended, on 19 May 2016, by clause 11(2) of the Electricity Industry Participation Code Amendment (System Operator and Alignment with Statutory Objective) 2016.

Clause 7.3(1)(a)(iv): amended, on 5 October 2017, by clause 78(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 7.3(1)(b): amended, on 19 May 2016, by clause 11(3) of the Electricity Industry Participation Code Amendment (System Operator and Alignment with Statutory Objective) 2016.

Clause 7.3(2)(a): amended, on 3 January 2013, by clause 4(1) of the Electricity Industry Participation (Supply Standards) Code Amendment 2012.

Clause 7.3(2)(b): amended, on 3 January 2013, by clause 4(2) of the Electricity Industry Participation (Supply Standards) Code Amendment 2012.

Clause 7.3(2A), (2B), (2C) and (2D): inserted, on 3 January 2013, by clause 4(3) of the Electricity Industry Participation (Supply Standards) Code Amendment 2012.

Clause 7.3(2A): amended, on 5 October 2017, by clause 78(3) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 7.3(2B): amended, on 19 May 2016, by clause 11(4) of the Electricity Industry Participation Code Amendment (System Operator and Alignment with Statutory Objective) 2016.

Clause 7.3(2B): amended, on 5 October 2017, by clause 78(4) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 7.3(2C)(b)(ii): amended, on 5 October 2017, by clause 78(5) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 7.3(3): amended, on 19 May 2016, by clause 11(5) of the Electricity Industry Participation Code Amendment (System Operator and Alignment with Statutory Objective) 2016.

Clause 7.3(3)(a): amended, on 19 May 2016, by clause 11(6)(a) and (b) of the Electricity Industry Participation Code Amendment (System Operator and Alignment with Statutory Objective) 2016.

Clause 7.3(3)(b): amended, on 19 May 2016, by clause 11(7) of the Electricity Industry Participation Code Amendment (System Operator and Alignment with Statutory Objective) 2016.

Clause 7.3(3)(b)(i): amended, on 19 May 2016, by clause 11(8) of the Electricity Industry Participation Code Amendment (System Operator and Alignment with Statutory Objective) 2016.

Clause 7.3(3)(b)(ii): amended, on 19 May 2016, by clause 11(9) of the Electricity Industry Participation Code Amendment (System Operator and Alignment with Statutory Objective) 2016.

Clause 7.3(3)(c): amended, on 19 May 2016, by clause 11(10) of the Electricity Industry Participation Code Amendment (System Operator and Alignment with Statutory Objective) 2016.

Clause 7.3(4)(b): amended, on 10 January 2013, by clause 5 of the Electricity Industry Participation (Policy Statement and Procurement Plan Review Process) Code Amendment 2012.

Clause 7.3(5): amended, on 21 September 2012, by clause 7(1) of the Electricity Industry Participation (Minor Amendments) Code Amendment 2012.

Clause 7.3(5): amended, on 19 May 2016, by clause 11(11) of the Electricity Industry Participation Code Amendment (System Operator and Alignment with Statutory Objective) 2016.

Clause 7.3(6): amended, on 21 September 2012, by clause 7(2) of the Electricity Industry Participation (Minor Amendments) Code Amendment 2012.

Clause 7.3(6): amended, on 19 May 2016, by clause 11(12) of the Electricity Industry Participation Code Amendment (System Operator and Alignment with Statutory Objective) 2016.

#### **7.4 Incorporation of security of supply forecasting and information policy and emergency management policy by reference**

- (1) The **security of supply forecasting and information policy** and the **emergency management policy** are incorporated by reference in this Code in accordance with section 32 of the **Act**.
- (2) Subclause (1) is subject to Schedule 1 of the **Act**, which includes a requirement that the **Authority** must give notice in the *Gazette* before an amended or substituted **security of supply forecasting and information policy** or **emergency management policy** becomes incorporated by reference in this Code.

Clause 7.4(1): amended, on 5 October 2017, by clause 79 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

#### **7.5 Approval of draft security of supply forecasting and information policy and emergency management policy**

- (1) The **system operator** may submit to the **Authority** for approval a draft **security of supply forecasting and information policy** or a draft **emergency management policy** to replace an existing **security of supply forecasting and information policy** or **emergency management policy** as the case may be.
- (2) *[Revoked]*
- (3) In preparing the draft **security of supply forecasting and information policy** or the draft **emergency management policy**, the **system operator** must—
  - (a) consult with persons that the **system operator** thinks are representative of the interests of persons likely to be substantially affected by the policies; and
  - (b) consider submissions made on the policies.
- (4) The **system operator** must provide a copy of each submission received under subclause (3) to the **Authority**.
- (5) The **Authority** must, as soon as practicable after receiving the draft **security of supply forecasting and information policy** or the draft **emergency management policy**, by notice in writing to the **system operator**,—
  - (a) approve the relevant policy; or
  - (b) decline to approve the relevant policy.
- (6) If the **Authority** declines to approve the draft **security of supply forecasting and information policy** or the draft **emergency management policy**, the **Authority** must **publish** the changes that the **Authority** wishes the **system operator** to make to the relevant draft policy.
- (7) When the **Authority publishes** the changes that the **Authority** wishes the **system operator** to make to the relevant draft policy under subclause (6), the **Authority** must notify the **system operator** and interested parties of the date by which submissions on the changes must be received by the **Authority**.
- (8) Each submission on the changes to the draft policy must be made in writing to the **Authority** and be received on or before the date specified by the **Authority** under subclause (7). The **Authority** must provide a copy of each submission received to the **system operator** and must **publish** the submissions.
- (9) The **system operator** may make its own submission on the changes to the draft policy and the submissions received in relation to the changes. The **Authority** must **publish**

the **system operator's** submission when it is received.

- (10) The **Authority** must consider the submissions made to it on the changes to the draft policy.
- (11) Following the consultation required by subclauses (7) to (10), the **Authority** may approve the draft policy subject to the changes that the **Authority** considers appropriate being made by the **system operator**.

Clause 7.5(2): revoked, on 19 May 2016, by clause 12 of the Electricity Industry Participation Code Amendment (System Operator and Alignment with Statutory Objective) 2016.

## **7.6 Variations to security of supply forecasting and information policy and emergency management policy**

- (1) A **participant** or the **Authority** may submit a proposal for a variation to the **security of supply forecasting and information policy** or the **emergency management policy** to the **system operator**.
- (2) The **system operator** must consider a proposed variation to the **security of supply forecasting and information policy** or the **emergency management policy** submitted under subclause (1).
- (3) The **system operator** may submit a request for a variation to the **security of supply forecasting and information policy** or the **emergency management policy** to the **Authority**.
- (4) Clause 7.5(3) to (11) apply to a request for a variation submitted under subclause (3) as if references to a draft policy were a reference to the requested variation.
- (5) The **Authority** may approve a variation requested under subclause (3) without complying with subclause (4) if—
  - (a) the **Authority** considers that it is necessary or desirable in the public interest that the requested variation be made urgently; and
  - (b) the **Authority publishes** a notice of the variation and a statement of the reasons why the urgent variation is needed.
- (6) Every variation made under subclause (5) expires on the date that is 9 months after the date on which the variation is made.

## **7.7 System operator and Authority joint development programme**

- (1) At least annually, the **system operator** and the **Authority** must agree a development programme that coordinates and prioritises—
  - (a) those items in the **Authority's** industry development work plan on which the **Authority** intends to liaise with the **system operator**; and
  - (b) the **system operator's** capital expenditure plan provided to the **Authority** under the **system operator market operation service provider agreement**.
- (2) The **Authority** must **publish** the programme agreed under subclause (1).

## **7.8 Review of system operator**

- (1) The **Authority** must review the performance of the **system operator** at least once in each year ending 30 June, after the **system operator** submits its self-review under clause 7.11.
- (2) The review must concentrate on the **system operator's** compliance with—

- (a) its obligations under this Code and the **Act**; and
  - (b) the operation of this Code and the **Act**; and
  - (c) any performance standards agreed between the **system operator** and the **Authority**; and
  - (d) the provisions of the **system operator's market operation service provider agreement**.
- (3) The **Authority** must **publish** a report on the performance of the **system operator** no later than 10 **business days** after the **Authority** completes its review.

Compare: SR 2003/374 r 47

Clause 7.8(1): amended, on 19 May 2016, by clause 13(1) of the Electricity Industry Participation Code Amendment (System Operator and Alignment with Statutory Objective) 2016.

Clause 7.8(1): amended, on 5 October 2017, by clause 80(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 7.8(3): inserted, on 19 May 2016, by clause 13(2) of the Electricity Industry Participation Code Amendment (System Operator and Alignment with Statutory Objective) 2016.

Clause 7.8(3): amended, on 5 October 2017, by clause 80(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

## 7.9 Additional matters to be taken into account in system operator review

The **Authority** must take into account the following matters when conducting a review under clause 7.8:

- (a) the terms of the **system operator's market operation service provider agreement**:
- (b) reports from the **system operator** to the **Authority**, including the **system operator's** self-review under clause 7.11:
- (c) the performance of the **system operator** over time in relation to this Part and Part 8:
- (d) the extent to which the acts or omissions of other persons have impacted on the performance of the **system operator** and the nature of the task being monitored:
- (e) reports or complaints from any person, and any responses by the **system operator** to such reports or complaints:
- (f) the fact that the real time co-ordination of the power system involves a number of complex judgments and inter-related incidents:
- (g) any disparity of information between the **Authority** and the **system operator**:
- (h) any other matter the **Authority** considers relevant to assess the **system operator's** performance.

Compare: SR 2003/374 r 48

Clause 7.9(b): amended, on 19 May 2016, by clause 14(1) of the Electricity Industry Participation Code Amendment (System Operator and Alignment with Statutory Objective) 2016.

Clause 7.9(e): amended, on 19 May 2016, by clause 14(2) of the Electricity Industry Participation Code Amendment (System Operator and Alignment with Statutory Objective) 2016.

## 7.10 Separation of Transpower roles

- (1) **Transpower's** role as **system operator** under this Code and the **Act** is distinct and separate from any other role or capacity that **Transpower** may have under this Code and the **Act**, including as a **grid owner** or transmission provider.
- (2) For this purpose, when assessing an aspect of the performance, or non-performance, of the **system operator**,—

- (a) the assessment must be made on the basis that the **system operator** had no other role or capacity; and
- (b) the **system operator** must be treated as if it did not have any knowledge or information that may be received or held by **Transpower** unless **Transpower** receives or holds that information or knowledge in its capacity as **system operator**.
- (3) Subclause (2) applies, with necessary modifications, to an assessment of an aspect of the performance, or non-performance, of **Transpower** in any other role or capacity under this Code or the **Act**.
- (4) **Transpower** must report, in each self-review report provided under this Code, on the extent to which its role as **system operator** under this Code and the **Act** has, despite subclauses (1) to (3), been materially affected by—
  - (a) any other role or capacity that **Transpower** has under this Code or the **Act**; or
  - (b) an agreement.

Compare: SR 2003/374 r 50

#### **7.11 Review of performance of the system operator**

- (1) No later than 31 August in each year, the **system operator** must submit to the **Authority** a review and assessment of its performance in the previous 12 month period ending 30 June.
- (2) The self-review must contain such information as the **Authority** may reasonably require from time to time to enable the **Authority** to review the **system operator's** performance during the period in relation to the following:
  - (a) the **policy statement**;
  - (b) the **security of supply forecasting and information policy**;
  - (c) the **emergency management policy**;
  - (d) the joint development programme prepared under clause 7.7(1);
  - (e) the work programmes agreed with the **Authority** under the **system operator's market operation service provider agreement**;
  - (f) the **system operator's** engagement with **participants**;
  - (g) delivery of the **system operator's** capital and business plans;
  - (h) the financial and operational performance of the **system operator**.
- (3) *[Revoked]*
- (4) *[Revoked]*

Compare: Electricity Governance Rules rule 14 section II part C

Clause 7.11(1): amended, on 19 May 2016, by clause 15(1)(a) and (b) of the Electricity Industry Participation Code Amendment (System Operator and Alignment with Statutory Objective) 2016.

Clause 7.11(2): amended, on 19 May 2016, by clause 15(2) of the Electricity Industry Participation Code Amendment (System Operator and Alignment with Statutory Objective) 2016.

Clause 7.11(3) and (4): revoked, on 19 May 2016, by clause 15(3) of the Electricity Industry Participation Code Amendment (System Operator and Alignment with Statutory Objective) 2016.

Clause 7.11(4): amended, on 15 May 2014, by clause 6 of the Electricity Industry Participation (Minor Code Amendments) Code Amendment 2014.

#### **7.12 Authority must publish system operator reports**

- (1) The **Authority** must **publish** all self-review reports that are received from the **system operator** and that are required to be provided by the **system operator** to the **Authority**



under this Code.

- (2) The **Authority** must **publish** each report within 5 **business days** after receiving the report.

Compare: SR 2003/374 r 49

Clause 7.12: amended, on 5 October 2017, by clause 81 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

# Electricity Industry Participation Code 2010

## Part 8 Common quality

### Contents

- 8.1 Contents of this Part
- 8.1A Requirement to provide complete and accurate information
  - Subpart 1—Performance obligations of the system operator
- 8.2 Contents of this subpart
- 8.3 Recovery of costs from causers of voltage non-compliance
- 8.4 System operator may rely on information provided
- 8.5 Restoration
- 8.6 System operator may contract for higher levels of common quality
- 8.7 System operator must not contract contrary to this arrangement
- Policy statement*
- 8.8 System operator to comply with policy statement
- 8.9 *[Revoked]*
- 8.10 Incorporation of policy statement by reference
- 8.10A Review of policy statement
- 8.10B System operator decides not to propose change to the policy statement
- 8.10C Authority may require system operator to reconsider
- 8.11 Content of draft policy statement
- 8.11A Changes and variations
- 8.12 Consultation on draft policy statement
- 8.12A Technical and non-controversial changes
- 8.12B Authority adopts new policy statement
- 8.13 *[Revoked]*
- 8.14 Departure from policy statement
- System security forecast*
- 8.15 System operator to prepare and review system security forecast
  - Subpart 2—Asset owner performance obligations and technical standards
- 8.16 Contents of this subpart
  - Asset owner performance obligations and technical standards concerning frequency*
  - 8.17 Contribution by injections to overall frequency management
  - 8.18 Contributions by purchasers to overall frequency management
  - 8.19 Contributions to frequency support in under-frequency events
  - 8.20 Contributions by grid owners to frequency support
  - 8.21 Excluded generating stations
  - Asset owner performance obligations and technical standards concerning voltage*
  - 8.22 Voltage range AOPOs
  - 8.23 Voltage support AOPOs
  - 8.24 Load shedding obligations to support voltage
  - 8.25 Other asset owner performance obligations and technical standards
  - 8.25A Fault ride through
  - 8.25B Reactive current and active power output

- 8.25C Use of additional equipment
- 8.25D Application
- 8.26 Asset owners must co-operate

*Compliance*

- 8.27 System operator to monitor compliance
- 8.28 Responsibility for compliance

*Equivalence arrangements and dispensations*

- 8.29 Right to apply for approval of equivalence arrangement or grant of dispensation
- 8.30 Approval of equivalence arrangements
- 8.31 Grant of dispensations
- 8.32 Liability of asset owner pending decision
- 8.33 Modification of equivalence arrangement or dispensation
- 8.34 Cancellation of equivalence arrangement or dispensation
- 8.35 Revocation of equivalence arrangement and revocation or variation of dispensation
- 8.36 Appeal against decisions
- 8.37 Other provisions relating to equivalence arrangements and dispensations
- 8.38 Authority may require excluded generating stations to comply with certain clauses

Subpart 3—Arrangements concerning ancillary services

- 8.39 Contents of this subpart

*Procurement plan*

- 8.40 System operator to use reasonable endeavours to implement and comply with procurement plan
- 8.41 *[Revoked]*
- 8.42 Incorporation of procurement plan by reference
- 8.42A Review of procurement plan
- 8.42B System operator decides not to amend the procurement plan
- 8.42C Authority may require system operator to reconsider
- 8.43 Content of draft procurement plan
- 8.43A Changes and variations
- 8.44 Consultation on draft procurement plan
- 8.44A Technical and non-controversial amendments
- 8.44B Authority adopts new procurement plan
- 8.45 Contracts with ancillary service agents
- 8.45A Methodology to assess net purchase quantity
- 8.46 *[Revoked]*
- 8.47 Departure from procurement plan

*Alternative ancillary service arrangements*

- 8.48 Alternative ancillary service arrangements
- 8.49 Suspension of alternative ancillary service arrangement
- 8.50 Modification of alternative ancillary service arrangement
- 8.51 Cancellation of alternative ancillary service arrangement
- 8.52 Revocation of alternative ancillary service arrangements
- 8.53 Appeal of system operator decisions
- 8.54 Other provisions relating to alternative ancillary service arrangements

Subpart 4—Interruptible load

- 8.54A Contents of this subpart

- 8.54B Ancillary service agents to provide information about interruptible load  
Subpart 5—Extended reserve
- 8.54C Contents of this subpart
- 8.54D System operator to review extended reserve
- 8.54E Review of extended reserve technical requirements schedule
- 8.54F Authority may require system operator to reconsider
- 8.54G Preparation and publication of extended reserve selection methodology
- 8.54H Principles for extended reserve selection methodology
- 8.54I Review of extended reserve selection methodology
- 8.54J Extended reserve manager to undertake extended reserve selection process
- 8.54K Information required for extended reserve selection process
- 8.54L Extended reserve manager to issue extended reserve procurement notices
- 8.54M Asset owners to prepare implementation plans
- 8.54N Terms and conditions applying to the provision of extended reserve
- 8.54O System operator to publish and maintain extended reserve schedule
- 8.54P System operator to issue statements of extended reserve obligations
- 8.54Q System operator to give written notice of dates
- 8.54R System operator to report to Authority
- 8.54S New connected asset owners and new grid owners to provide information
- 8.54T Assignment of extended reserve obligations
- 8.54TA Extended reserve manager may rely on information provided
- 8.54TB Extended reserve manager to consider new or revised information
- 8.54TC Extended reserve manager to produce periodic performance report
- Information required for transitional purposes*
- 8.54TD Information required for transition
- Transitional provisions—extended reserve*
- 8.54TE Transitional provisions for extended reserve
- 8.54TF Transitional provisions for change to frequency limit in South Island
- Subpart 6—Allocating costs
- 8.54U Contents of this subpart
- Allocating costs for ancillary services and extended reserve*
- 8.55 Identifying costs associated with ancillary services and extended reserve
- 8.56 Black start costs allocated the grid owner
- 8.57 Over frequency reserve costs allocated to HVDC owner
- 8.58 Frequency keeping costs are allocated to purchasers
- 8.59 Availability costs allocated to generators and HVDC owner
- 8.60 System operator must investigate causer of under-frequency event
- 8.61 Authority to determine causer of under-frequency event
- 8.62 Disputes regarding Authority determinations
- 8.63 Decision of the Rulings Panel
- 8.64 Event costs allocated to event causers
- 8.65 Rebates paid for under-frequency events
- 8.66 Payments and rebates
- 8.67 Voltage support costs allocated in 3 parts – nominated peak, monthly peak and residual charges
- 8.67A Extended reserve costs allocated to connected asset owners

- 8.68 Clearing manager to determine amounts owing
- 8.69 Clearing manager to determine wash up amounts payable and receivable
- 8.70 System operator pays ancillary service agents

**Schedule 8.1**

**Approval of equivalence arrangement or grant of dispensation**

**Schedule 8.2**

**Approval of alternative ancillary service arrangement**

**Schedule 8.3**

**Technical codes**

*Technical Code A – Assets*

*Appendix A: Main protection system requirements*

*Appendix B: Routine testing of assets and automatic under-frequency load shedding systems*

*Technical Code B – Emergencies*

*Technical Code C – Operational communications*

*Appendix A: Indications and Measurements*

*Technical Code D – Co-ordination of outages affecting common quality*

**Schedule 8.4**

**[Revoked]**

**Schedule 8.5**

**Consultation and approval requirements for extended reserve procurement documents**

*Part 1*

*Consultation on extended reserve technical requirements schedule*

*Part 2*

*Consultation on extended reserve selection methodology*

*Part 3*

*Consultation on extended reserve procurement schedule*

---

**8.1 Contents of this Part**

This Part relates to **common quality**. In particular, this Part concerns the performance obligations of the **system operator**, the performance obligations of **asset owners**, arrangements concerning **ancillary services**, **extended reserve**, and **technical codes**.

Compare: Electricity Governance Rules 2003 rule 1 section I part C

Clause 8.1: amended, on 7 August 2014, by clause 5 of the Electricity Industry Participation Code Amendment (Extended Reserve) 2014.

**8.1A Requirement to provide complete and accurate information**

- (1) A **participant** must take all practicable steps to ensure that information that it provides to the **extended reserve manager** under this Part is—
  - (a) complete and accurate; and
  - (b) not misleading or deceptive; and
  - (c) not likely to mislead or deceive.
- (2) If a **participant** provides information to the **extended reserve manager** under this Part, and subsequently becomes aware that the information is incomplete, inaccurate,

misleading or deceptive, or likely to mislead or deceive, the **participant** must provide revised information as soon as practicable.

- (3) For the purpose of this clause, information provided by an **asset owner** to the **extended reserve manager** is deemed to be accurate if it complies with a data specification **published by the extended reserve manager**.

Clause 8.1A: inserted, on 19 January 2017, by clause 4 of the Electricity Industry Participation Code Amendment (Extended Reserve) 2016.

## Subpart 1—Performance obligations of the system operator

### 8.2 Contents of this subpart

This subpart provides for—

- (a) general performance obligations of the **system operator**
- (b) a **policy statement** relating to the **principal performance obligations** of the **system operator**; and
- (c) the review of the **policy statement**.

Compare: Electricity Governance Rules 2003 rule 1 section II part C

### 8.3 Recovery of costs from causers of harmonic and voltage non-compliance

- (1) If the **system operator** is able to establish who is causing any departure from the standards referred to in clause 7.2(D), the **system operator** must endeavour to recover its reasonable identification and testing costs from that person. If the causer is a **participant**, the **participant** must pay those costs to the **system operator**.
- (2) If the **system operator** is unable to recover its reasonable identification and testing costs, or the causer is not able to be identified, then those costs will form part of the **system operator's identification costs**.

Compare: Electricity Governance Rules 2003 rule 2.3.2 section II part C

Clause 8.3 Heading: amended, on 19 May 2016, by clause 16(1) of the Electricity Industry Participation Code Amendment (System Operator and Alignment with Statutory Objective) 2016.

Clause 8.3(1): amended, on 19 May 2016, by clause 16(2) of the Electricity Industry Participation Code Amendment (System Operator and Alignment with Statutory Objective) 2016.

### 8.4 System operator may rely on information provided

For the purposes of this Code, the **system operator** may—

- (a) rely on the **assets** and information about the **assets** made available to the **system operator** by **asset owners**; and
- (b) assume that **asset owners** are complying with the **asset owner performance obligations** and the **technical codes**, or complying with a valid **dispensation** or **equivalence arrangement**; and
- (c) rely on information provided to the **system operator** by the **extended reserve manager**.

Compare: Electricity Governance Rules 2003 rule 4 section II part C

Clause 8.4: replaced, on 19 January 2017, by clause 5 of the Electricity Industry Participation Code Amendment (Extended Reserve) 2016.

## 8.5 Restoration

- (1) If an event disrupts the **system operator's** ability to comply with the **principal performance obligations**, the **system operator** must re-establish normal operation of the power system as soon as possible, given—
  - (a) the capability of **generation, ancillary services, and extended reserve**; and
  - (b) the configuration and capacity of the **grid**; and
  - (c) the information made available by **asset owners**.
- (2) When re-establishing normal operation of the power system under subclause (1), the **system operator** must have regard to the following priorities:
  - (a) first, the safety of natural persons;
  - (b) second, the avoidance of damage to **assets**;
  - (c) third, the restoration of **offtake**;
  - (d) fourth, conformance with the **principal performance obligations**;
  - (e) fifth, full conformance with the **dispatch objective**.

Compare: Electricity Governance Rules 2003 rule 5 section II part C

Clause 8.5(1): amended, on 19 May 2016, by clause 17 of the Electricity Industry Participation Code Amendment (System Operator and Alignment with Statutory Objective) 2016.

Clause 8.5(1)(a): amended, on 7 August 2014, by clause 6 of the Electricity Industry Participation Code Amendment (Extended Reserve) 2014.

## 8.6 System operator may contract for higher levels of common quality

Subject to clause 17.29, nothing in this Code prevents the **system operator** from entering into contracts or arrangements in which levels of quality more stringent than those specified in the **principal performance obligations** are agreed, if the **system operator** can identify the incremental costs of those more stringent levels, and can ensure that those incremental costs are paid to the **system operator** by the persons wishing to enter into that contract or arrangement with the **system operator**.

Compare: Electricity Governance Rules 2003 rule 6 section II part C

## 8.7 System operator must not contract contrary to this arrangement

Subject to clauses 8.6 and 17.29, the **system operator** must not enter into a contract with another person that is inconsistent with the **system operator's** obligations under this Code and the **technical codes**.

Compare: Electricity Governance Rules 2003 rule 7 section II part C

### *Policy statement*

## 8.8 System operator to comply with policy statement

Subject to clause 8.14, the **system operator** must comply with the **policy statement**.

Compare: Electricity Governance Rules 2003 rule 8 section II part C

Clause 8.8: amended, on 19 May 2016, by clause 18 of the Electricity Industry Participation Code Amendment (System Operator and Alignment with Statutory Objective) 2016.

## 8.9 [Revoked]

Clause 8.9: revoked, on 10 January 2013, by clause 6 of the Electricity Industry Participation (Policy Statement and Procurement Plan Review Process) Code Amendment 2012.

### 8.10 Incorporation of policy statement by reference

- (1) The **policy statement** is incorporated by reference in this Code in accordance with section 32 of the **Act**.
- (2) Subclause (1) is subject to Schedule 1 of the **Act**, which includes a requirement that the **Authority** must give notice in the *Gazette* before an amended or substituted **policy statement** becomes incorporated by reference in this Code.

Compare: Electricity Governance Rules 2003 rule 9 section II part C

Clause 8.10(1): amended, on 10 January 2013, by clause 7 of the Electricity Industry Participation (Policy Statement and Procurement Plan Review Process) Code Amendment 2012.

### 8.10A Review of policy statement

- (1) At least once every 2 years the **system operator** must—
  - (a) review the **policy statement**; and
  - (b) as soon as practicable after completing a review, decide whether or not to propose a change to the **policy statement**; and
  - (c) advise the **Authority** of its decision.
- (2) If the **system operator** decides to propose a change to the **policy statement**, the **system operator** must submit a **draft policy statement** to the **Authority** together with the following information:
  - (a) an explanation of the proposed change and a statement of the objectives of the proposed change;
  - (b) an evaluation of alternative means of achieving the objectives of the proposed change;
  - (c) an evaluation of the costs and benefits of the proposed change;
  - (d) a list of the persons consulted and a summary of the submissions received.
- (3) As part of a review conducted under this clause, the **system operator** must invite comments from **participants**.

Clause 8.10A: inserted, on 10 January 2013, by clause 8 of the Electricity Industry Participation (Policy Statement and Procurement Plan Review Process) Code Amendment 2012.

Clause 8.10A(1): amended, on 5 October 2017, by clause 82 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### 8.10B System operator decides not to propose change to the policy statement

If the **system operator** advises the **Authority** under clause 8.10A(1)(c) that the **system operator** does not intend to propose a change to the **policy statement** the **system operator** must provide the **Authority** with the following information:

- (a) the findings of the review of the **policy statement** conducted by the **system operator**;
- (b) details of any request to amend the **policy statement** received from a **participant** or the **Authority** since the last review;
- (c) the **system operator's** decision on each such request including, if the **system operator** declined a requested change, the reasons for declining.

Clause 8.10B: inserted, on 10 January 2013, by clause 8 of the Electricity Industry Participation (Policy Statement and Procurement Plan Review Process) Code Amendment 2012.



### 8.10C Authority may require system operator to reconsider

- (1) The **Authority** may require the **system operator** to reconsider a decision made under clause 8.10A(1)(b) not to propose a change to the **policy statement**.
- (2) If the **Authority** requires the **system operator** to reconsider a decision made under subclause 8.10A(1)(b), the **Authority** must advise the **system operator** of—
  - (a) the **Authority's** reasons for requiring the **system operator** to reconsider; and
  - (b) the date, determined after consulting with the **system operator**, by which the **system operator** must either confirm its decision or submit a **draft policy statement**.
- (3) The **Authority** must as soon as practicable **publish** the advice received from the **system operator** under clause 8.10A(1)(c) and the advice given by the **Authority** to the **system operator** under subclause (2).

Clause 8.10C: inserted, on 10 January 2013, by clause 8 of the Electricity Industry Participation (Policy Statement and Procurement Plan Review Process) Code Amendment 2012.

Clause 8.10C(3): amended, on 5 October 2017, by clause 83 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### 8.11 Content of draft policy statement

- (1) *[Revoked]*
- (2) *[Revoked]*
- (3) The **draft policy statement** must include—
  - (a) the policies and means that the **system operator** considers appropriate for the **system operator** to observe in complying with its **principal performance obligations**; and
  - (b) the policies and means by which scheduling and **dispatch** are adjusted to meet the **dispatch objective**, and must include the provision of a **dispatch** process statement. The **dispatch** process statement must contain the details of the processes that enable the **system operator** to meet the **dispatch objective**, including the methodologies to be used by the **system operator** for planning to meet the **dispatch objective** during the period leading up to real time and meeting the **dispatch objective** in real time; and
  - (c) a policy setting out how the **system operator** will manage any conflict of interest that arises in the performance of its obligations under this Code; and
  - (d) a statement of the reasons for adopting the policies and means set out in the **policy statement** (which statement must be regarded as an explanatory note only and does not form part of the policies itself); and
  - (e) a statement of how future policies and means might be formulated and implemented.

Compare: Electricity Governance Rules 2003 rule 10 section II part C

Clause 8.11 Heading: substituted, on 10 January 2013, by clause 9(a) of the Electricity Industry Participation (Policy Statement and Procurement Plan Review Process) Code Amendment 2012.

Clause 8.11(1): revoked, on 10 January 2013, by clause 9(b) of the Electricity Industry Participation (Policy Statement and Procurement Plan Review Process) Code Amendment 2012.

Clause 8.11(2): revoked, on 10 January 2013, by clause 9(c) of the Electricity Industry Participation (Policy Statement and Procurement Plan Review Process) Code Amendment 2012.

Clause 8.11(3): amended, on 10 January 2013, by clause 9(d) of the Electricity Industry Participation (Policy Statement and Procurement Plan Review Process) Code Amendment 2012.

Clause 8.11(3): amended, on 19 May 2016, by clause 19(1) of the Electricity Industry Participation Code Amendment (System Operator and Alignment with Statutory Objective) 2016.

Clause 8.11(3)(c): amended, on 19 May 2016, by clause 19(2) of the Electricity Industry Participation Code Amendment (System Operator and Alignment with Statutory Objective) 2016.

### 8.11A Changes and variations

- (1) The **system operator** may at any time propose a change to the **policy statement** by submitting a **draft policy statement** to the **Authority** together with the following information:
  - (a) an explanation of the proposed change and a statement of the objectives of the proposed change;
  - (b) an evaluation of alternative means of achieving the proposed change;
  - (c) an evaluation of the costs and benefits of the proposed change.
- (2) The **Authority** or a **participant** may at any time request that the **system operator** propose a change to the **policy statement** under subclause (1).
- (3) If the **system operator** receives a request under subclause (2), it must as soon as practicable—
  - (a) decide whether to decline the request, defer the request until the next **review date**, or submit a **draft policy statement** to the **Authority**; and
  - (b) **publish** the decision.
- (4) If the **system operator** declines a request under subclause (3), the **Authority** may require the **system operator** to reconsider its decision, giving reasons.

Clause 8.11A: inserted, on 10 January 2013, by clause 10 of the Electricity Industry Participation (Policy Statement and Procurement Plan Review Process) Code Amendment 2012.

Clause 8.11A(3)(b): amended, on 5 October 2017, by clause 84 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### 8.12 Consultation on draft policy statement

- (1) The **Authority** must **publish** the following information as soon as practicable after it receives it:
  - (a) a **draft policy statement** submitted under clause 8.10A and the information required under clause 8.10A(2);
  - (b) a **draft policy statement** submitted under clause 8.11A and the information required under clauses 8.11A(1)(a) to (c).
- (2) When the **Authority publishes** a **draft policy statement** and information under subclause (1), the **Authority** must advise **participants** of the date (which must not be earlier than 10 **business days** after the date that the **Authority publishes** the **draft policy statement**) by which submissions on the changes proposed in the **draft policy statement** must be received by the **Authority**.
- (3) Each submission on changes proposed in a **draft policy statement** must be made in writing to the **Authority** and received on or before the **submission expiry date**.
- (4) The **Authority** must provide a copy of each submission received to the **system operator** at the close of business on the **submission expiry date** and must **publish** the submissions as soon as practicable.
- (5) The **system operator** may make its own submission on the **draft policy statement** and the submissions received in relation to it no later than 10 **business days** after the **submission expiry date**.

- (6) The **Authority** must **publish** the **system operator's** submission as soon as practicable after it is received.
- (7) Following the consultation process required by subclauses (1) to (6), the **Authority** may approve the **draft policy statement** subject to the **system operator** making any changes that the **Authority** considers appropriate.

Compare: Electricity Governance Rules 2003 rule 11 section II part C

Clause 8.12: substituted, on 10 January 2013, by clause 11 of the Electricity Industry Participation (Policy Statement and Procurement Plan Review Process) Code Amendment 2012.

Clause 8.12(1), (2), (4) and (6): amended, on 5 October 2017, by clause 85(1) and (2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

#### 8.12A Technical and non-controversial changes

- (1) The **system operator** may at any time propose a change to the **policy statement** that it considers is technical and non-controversial by submitting a **draft policy statement** to the **Authority** together with an explanation of the proposed change.
- (2) If the **system operator** submits a **draft policy statement** under subclause (1) the **system operator** is not required to provide a statement of the objectives of the proposed change, an evaluation of alternative means of achieving the objectives of the proposed change or an evaluation of costs and benefits of the proposed change.
- (3) The **Authority** must, as soon as practicable after receiving a **draft policy statement** and the information required under subclause (1), by notice in writing to the **system operator**—
  - (a) approve the **draft policy statement** to be incorporated by reference into this Code; or
  - (b) decline to approve the **draft policy statement**, giving reasons.
- (4) If the **Authority** approves the **draft policy statement** it must as soon as practicable—
  - (a) **publish** notice of its intention to incorporate the **draft policy statement** by reference into this Code; and
  - (b) include in the notice the **Authority's** reasons for considering that the changes proposed in the **draft policy statement** are technical and non-controversial; and
  - (c) invite comment from **participants** on the reasons given in the notice.
- (5) After considering any comments made under subclause 4(c) the **Authority** must advise the **system operator** by notice in writing of its decision as to whether to confirm or revoke its approval of the **draft policy statement**, and give reasons for its decision.
- (6) The **Authority** must **publish** its decision and reasons as soon as practicable.

Clause 8.12A: inserted, on 10 January 2013, by clause 12 of the Electricity Industry Participation (Policy Statement and Procurement Plan Review Process) Code Amendment 2012.

Clause 8.12A(4)(a) and (6): amended, on 5 October 2017, by clause 86 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

#### 8.12B Authority adopts new policy statement

If the **Authority** approves a **draft policy statement** under clause 8.12 or confirms its approval of a **draft policy statement** under clause 8.12A it must—

- (a) incorporate the new **policy statement** by reference into this Code in accordance with Schedule 1 of the **Act**; and
- (b) **publish** the new **policy statement** and the date on which it takes legal effect.

Clause 8.12B: inserted, on 10 January 2013, by clause 12 of the Electricity Industry Participation (Policy Statement and Procurement Plan Review Process) Code Amendment 2012.

Clause 8.12B(b): amended, on 5 October 2017, by clause 87 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### 8.13 *[Revoked]*

Compare: Electricity Governance Rules 2003 rule 12 section II part C

Clause 8.13: revoked, on 10 January 2013, by clause 13 of the Electricity Industry Participation (Policy Statement and Procurement Plan Review Process) Code Amendment 2012.

### 8.14 **Departure from policy statement**

- (1) The **system operator** may depart from the policies set out in a **policy statement** when a **system security situation** arises and such departure is required for the **system operator** to comply with clause 7.1A(1).
- (2) If the **system operator** departs from a **policy statement** under subclause (1), the **system operator** must provide a report to the **Authority** setting out the circumstances of the **system security situation** and the actions taken to deal with it.
- (3) The **Authority** must **publish** the report within a reasonable time after receiving it.

Compare: Electricity Governance Rules 2003 rule 13 section II part C

Clause 8.14(1): amended, on 19 May 2016, by clause 20(1) of the Electricity Industry Participation Code Amendment (System Operator and Alignment with Statutory Objective) 2016.

Clause 8.14(2): amended, on 19 May 2016, by clause 20(2) of the Electricity Industry Participation Code Amendment (System Operator and Alignment with Statutory Objective) 2016.

Clause 8.14(3): substituted, on 10 January 2013, by clause 14 of the Electricity Industry Participation (Policy Statement and Procurement Plan Review Process) Code Amendment 2012.

Clause 8.14(3): amended, on 5 October 2017, by clause 88 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### *System security forecast*

### 8.15 **System operator to prepare and review system security forecast**

- (1) Every 2 years, the **system operator** must prepare, **publish**, and provide to the **Authority** a **system security forecast**.
- (1A) The **system security forecast** must—
  - (a) identify risks to the **system operator's** ability to meet the **principal performance obligations** over the ensuing period of not less than 36 months, and indicate how those risks can be managed; and
  - (b) take into account the capabilities of the **grid** and connected **assets** based on information known to, and able to be disclosed by, the **system operator**.
- (2) The date by which the **system operator** must **publish** the **system security forecast** and provide it to the **Authority** in each year in which the **system operator** is required to do so, is the date established for that purpose under rule 15 of section II of part C of the **rules**.
- (3) The **system operator** must review the most recent **system security forecast** prepared in accordance with subclause (1) at 6 monthly intervals until a new forecast or update is prepared. If, in the reasonable opinion of the **system operator**, a change has been made to the power system that would materially affect the most recent forecast or update, the **system operator** must amend the **system security forecast**, **publish** it and provide it to the **Authority**.

Compare: Electricity Governance Rules 2003 rule 15 section II part C

Clause 8.15(1): substituted, on 21 September 2012, by clause 8 of the Electricity Industry Participation (Minor Amendments) Code Amendment 2012.

Clause 8.15(1A): inserted, on 21 September 2012, by clause 8 of the Electricity Industry Participation (Minor Amendments) Code Amendment 2012.

Clause 8.15(1A)(b): amended, on 23 February 2015, by clause 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 8.15(1A)(b): amended, on 5 October 2017, by clause 89 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

## Subpart 2—Asset owner performance obligations and technical standards

### 8.16 Contents of this subpart

This subpart provides for—

- (a) the establishment of performance obligations and technical standards for **asset owners** to assist the **system operator** in complying with the **principal performance obligations**; and
- (b) **asset owners** to obtain an assessment of their **assets** from the **system operator**; and
- (c) a process for the **system operator** to approve applications for **equivalence arrangements** and **dispensations** (if necessary).

Compare: Electricity Governance Rules 2003 rule 1 section III part C

*Asset owner performance obligations and technical standards concerning frequency*

### 8.17 Contribution by injections to overall frequency management

Each **generator** (while **synchronised**) and the **HVDC owner** must at all times ensure that its **assets**, other than any **generating units** within an **excluded generating station**, make the maximum possible **injection** contribution to maintain frequency within the **normal band** (and to restore frequency to the **normal band**). Any such contribution must be assessed against the **technical codes**.

Compare: Electricity Governance Rules 2003 rule 2.1 section III part C

### 8.18 Contributions by purchasers to overall frequency management

Each **purchaser** must limit the magnitude of any instantaneous change in the **offtake of electricity** and net rate of change in **offtake** to the levels the **system operator** reasonably requires. In setting those requirements, the **system operator** must have regard to the impact of the **offtake** on the **system operator's** ability to comply with the **principal performance obligations** concerning frequency (as set out in clause 7.2A to 7.2C) and the **dispatch objective**.

Compare: Electricity Governance Rules 2003 rule 2.2 section III part C

Clause 8.18: amended, on 19 May 2016, by clause 21 of the Electricity Industry Participation Code Amendment (System Operator and Alignment with Statutory Objective) 2016.

### 8.19 Contributions to frequency support in under-frequency events

- (1) Subject to subclause (3), each **generator** must at all times ensure that, while **electrically connected**, its **assets**, other than any **excluded generating stations**, contribute to supporting frequency by remaining **synchronised**, ensuring that each of its **generating units** can and does, at a minimum, sustain pre-event output—

- (a) at all times when the frequency is above 47.5 Hertz; and
  - (b) for at least 120 seconds when the frequency is 47.5 Hertz; and
  - (c) for at least 20 seconds when the frequency is 47.3 Hertz; and
  - (d) for at least 5 seconds when the frequency is 47.1 Hertz; and
  - (e) for at least 0.1 seconds when the frequency is 47.0 Hertz; and
  - (f) at any frequencies between those specified in paragraphs (b) to (e) for times derived by linear interpolation.
- (2) If the **inherent characteristics** and design of a **generator's generating unit** are such that it is reasonably able to operate beyond the above requirements, the **generator** must declare such capabilities in accordance with clause 2(5) of **Technical Code A** of Schedule 8.3.
- (3) Each South Island **generator** must ensure that each of its **assets**, other than excluded **generating units**, remains **synchronised**, and can and do, at a minimum, sustain pre-event output—
- (a) at all times when the frequency is above 47 Hertz; and
  - (b) for 30 seconds if the frequency falls below 47 Hertz but not below 45 Hertz.
- (4) The **HVDC owner** must at all times ensure that, while **electrically connected**, its **assets** contribute to supporting frequency during an **under-frequency event** in either **island** by—
- (a) remaining **electrically connected** to those **assets** making up the **grid** in the North Island and South Island while the frequency in both **islands** remains above 48 Hertz; and
  - (b) remaining **electrically connected** to those **assets** making up the **grid** in the North Island and South Island while the frequency in both **islands** remains below 48 Hertz and above 47 Hertz for 90 seconds; and
  - (c) remaining **electrically connected** to those **assets** making up the **grid** in the North Island and South Island while the frequency in both **islands** remains above 45 Hertz for 35 seconds, unless the frequency in either **island** is less than 46.5 Hertz and the frequency is falling at a rate of 7 Hertz per second or greater; and
  - (d) subject to the level of transfer and the **HVDC link** configuration at the beginning of the **under-frequency event**, if the **HVDC link** itself is not the cause of the **under-frequency event**, modifying the instantaneous transfer on the **HVDC link** by up to 250 MW with the objective of limiting the difference between the North Island and South Island frequencies to no greater than 0.2 Hertz.
- (5) Each **extended reserve provider** must provide **extended reserve** in accordance with Schedule 8.3, Technical Code B.

Compare: Electricity Governance Rules 2003 rule 2.3 section III part C

Clause 8.19(5): substituted, on 7 August 2014, by clause 7 of the Electricity Industry Participation Code Amendment (Extended Reserve) 2014.

Clause 8.19(1) and (4): amended, on 23 February 2015, by clause 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 8.19(1) and (4): amended, on 5 October 2017, by clause 90 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

## 8.20 Contributions by grid owners to frequency support

Each **grid owner** must ensure that its **assets** are capable of being operated, and operate,

within the frequency targets set out in clause 7.2A.

Compare: Electricity Governance Rules 2003 rule 2.4 section III part C

Clause 8.20: amended, on 19 May 2016, by clause 22 of the Electricity Industry Participation Code Amendment (System Operator and Alignment with Statutory Objective) 2016.

### 8.21 Excluded generating stations

- (1) For the purposes of clauses 8.17, 8.19, 8.25D, and the provisions in **Technical Code A** of Schedule 8.3 relating to the obligations of **asset owners** in respect of frequency, an **excluded generating station** means a **generating station** that exports less than 30 MW to a **local network** or the **grid**, unless the **Authority** has issued a direction under clause 8.38 that the **generating station** must comply with clauses 8.17, 8.19, 8.25A, and 8.25B and the relevant provisions in **Technical Code A** of Schedule 8.3.
- (2) Whether likely to be an **excluded generation station** or not, a **generator** who is planning to connect to the **grid** or a **local network** a **generating unit** with rated net maximum capacity equal to or greater than 1 MW must provide the **system operator** with written advice of its intention to connect together with other information relating to that **generating unit** in accordance with clause 8.25(4).

Compare: Electricity Governance Rules 2003 rules 2.5 and 2.6 section III part C

Clause 8.21(1): amended, on 24 November 2016, by clause 5(1) and (2) of the Electricity Industry Participation Code Amendment (Generation Fault Ride Through) 2016.

Clause 8.21(2): amended, on 23 February 2015, by clause 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 8.21(2): amended, on 5 October 2017, by clause 91 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

*Asset owner performance obligations and technical standards concerning voltage*

### 8.22 Voltage range AOPOs

- (1) Each **grid owner** must ensure that its **assets** at and in between—
  - (a) the **high voltage terminals** of the **grid owner's** transformers at each **grid injection point** and **grid exit point**; or
  - (b) if no transformer exists, the relevant **grid injection point** or **grid exit point**—are capable of being operated within the following range of voltages:

Nominal <b>grid</b> voltage (kV)	Voltage limits			
	Minimum (kV)		Maximum (kV)	
220	198	-10.0%	242	10.0%
110	99	-10.0%	121	10.0%
66	62.7	-5.0%	69.3	5.0%
50	47.5	-5.0%	52.5	5.0%

- (2) Each **generator** with a **point of connection** to the **grid** must at all times ensure that its **assets** are capable of being operated, and do operate, when the **grid** is operated within the range of voltages set out in subclause (1).
- (3) Each **connected asset owner** must ensure that its **local network** is capable of being operated, and does operate, when the **grid** is operated over the range of voltages set out in subclause (1).

Compare: Electricity Governance Rules 2003 rule 3.1 section III part C  
Clause 8.22(3): amended, on 1 February 2016, by clause 8 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

### 8.23 Voltage support AOPOs

Each **generator** with a **point of connection** to the **grid** must at all times ensure that its **assets**—

- (a) when the voltage at its **grid injection point** is within the applicable range of nominal voltage, are capable of exporting (over excited) when **synchronised** and made available for **dispatch** by the **system operator**, a minimum net **reactive power** which is 50% of the maximum continuous **MW** output power as measured at the following **generating unit** terminals:

Nominal <b>grid</b> voltage (kV)	Voltage range for which <b>reactive power</b> is required			
	Minimum (kV)		Maximum (kV)	
220	198	-10.0%	242	10.0%
110	99	-10.0%	121	10.0%
66	62.7	-5.0%	69.3	5.0%
50	47.5	-5.0%	52.5	5.0%
33	31.35	-5.0%	34.65	5.0%
22	21.45	-2.5%	22.55	2.5%
11	10.725	-2.5%	11.275	2.5%

- (b) when the voltage at its **grid injection point** is within the applicable range of nominal voltage, are capable of importing (under excited) when **synchronised** and made available for **dispatch** by the **system operator**, a minimum net **reactive power** which is 33% of the maximum continuous **MW** output power as measured at the **generating unit** terminals as set out below:

Nominal <b>grid</b> voltage (kV)	Voltage range for which <b>reactive power</b> is required			
	Minimum (kV)		Maximum (kV)	
220	209	-5.0%	242	10.0%
110	104.5	-5.0%	121	10.0%
66	62.7	-5.0%	69.3	5.0%
50	47.5	-5.0%	52.5	5.0%
33	31.35	-5.0%	34.65	5.0%
22	21.45	-2.5%	22.55	2.5%
11	10.725	-2.5%	11.275	2.5%

- (c) when **synchronised**, continuously operate in a manner that supports voltage and voltage stability on the **grid** in compliance with the **technical codes**.

Compare: Electricity Governance Rules 2003 rule 3.2 section III part C  
Clause 8.23: amended, on 21 September 2012, by clause 9 of the Electricity Industry Participation (Minor Amendments) Code Amendment 2012.



#### 8.24 Load shedding obligations to support voltage

- (1) If it is not possible for a **connected asset owner** to comply with subclause (2), the **grid owner** must, if possible, establish load shedding in block sizes and at voltage levels (and, if automatic systems are established, with relay settings) set out in the **technical codes** or otherwise as the **system operator** reasonably requires.
- (2) In order to prevent the collapse of the **network** voltage, each **connected asset owner** must ensure that, if possible, it has established load shedding in block sizes and at voltage levels (and, if automatic systems are established, with relay settings) in accordance with the **technical codes** or otherwise as the **system operator** reasonably requires.

Compare: Electricity Governance Rules 2003 rule 3.3 section III part C

Clause 8.24(1): amended, on 1 February 2016, by clause 9 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

Clause 8.24(2): amended, on 1 May 2016, by clause 4 of the Electricity Industry Participation Code Amendment (Minor Code Amendments) 2016.

#### 8.25 Other asset owner performance obligations and technical standards

- (1) Each **grid owner** must ensure that the design and configuration of its **assets** (including its connections to other persons) and associated protection arrangements are consistent with the **technical codes** and, in the reasonable opinion of the **system operator**, with maintaining the **system operator's** ability to comply with the **principal performance obligations**. In reaching this opinion, the **system operator** must have regard to the potential impact of the design or configuration of those **assets** or associated protection arrangements on its compliance with the **principal performance obligations** and achievement of the **dispatch objective**.
- (2) Each **grid owner** and each **connected asset owner** must use reasonable endeavours to ensure that a **generator** who meets the following criteria provides the **system operator** with written advice of the existence of its **generating unit** and the **generator's** name and address:
  - (a) the **generator** is directly connected to the **grid owner's grid** or directly or indirectly connected to the **local network** (as the case may be):
  - (b) the **generator** has a **generating unit** with a rated net maximum capacity equal to or greater than 1 MW.
- (3) Each **asset owner** and each **purchaser** must provide communication facilities that comply with the **technical codes** or otherwise, as the **system operator** reasonably requires, which must assist the **system operator** in planning to comply, and complying, with its **principal performance obligations** and achieving the **dispatch objective**.
- (4) Each **asset owner** and each **purchaser** must provide information that complies with the **technical codes** or otherwise as the **system operator** reasonably requests, to assist the **system operator** in planning to comply, and complying, with its **principal performance obligations** and achieving the **dispatch objective**.
- (5) If the **system operator** reasonably considers it necessary to assist the **system operator** in planning to comply, and complying, with the **principal performance obligations** and achieving the **dispatch objective**, the **system operator**—
  - (a) may require that an **embedded generator** provide information regarding the

intended output of each **embedded generating station** greater than 10 MW in capacity, that must be either—

- (i) submitted as an **offer** in accordance with subpart 1 of Part 13; or
  - (ii) provided in a form and manner agreed between the **system operator** and the **embedded generator**; and
- (b) must notify the **embedded generator** of its requirement at least 20 **business days** in advance of the requirement coming into effect.
- (6) If the **system operator** reasonably considers it necessary to assist it in planning to comply, and complying, with the **principal performance obligations** and achieving the **dispatch objective**, the **system operator** may apply to the **Authority** to require an **embedded generator** to provide information regarding the intended output of a group of **embedded generating stations** that total greater than 10 MW in capacity and that are connected to the same **grid exit point**. If the **Authority** approves the **system operator's** request, the information must be provided to the **system operator** by the relevant **embedded generator** in a form and manner determined by the **Authority**.

Compare: Electricity Governance Rules 2003 rule 4.1 to 4.6 section III part C

Clause 8.25(1), (2) and (6): amended, on 23 February 2015, by clause 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 8.25(1), (2) and (6): amended, on 5 October 2017, by clause 92(1) and (2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 8.25(2): amended, on 1 February 2016, by clause 10 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.


Clause 8.25(5) (b): amended, on 5 October 2017, by clause 92(3) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### 8.25A Fault ride through


- (1) Each **generator** must ensure that each of its **assets**, when **electrically connected** to a **network**, is capable of remaining stable and **electrically connected** when the **grid's** lowest **line-to-line** voltage is within the no-trip zone shaded and marked "No-trip zone" in Figure 8.1 (for an **asset** in the North Island) or Figure 8.2 (for an **asset** in the South Island) for the period of 6 seconds immediately following the commencement of a zero impedance three-phase short circuit fault, or an unbalanced short circuit fault, on any part of the **grid** at 110 kV or 220 kV in the **island** in which the **asset** is connected.
- (2) Each **generator** must ensure that each of its **assets**, when **electrically connected** to a **network**, is capable of remaining stable and **electrically connected** when the highest **line-to-line** voltage at Haywards 220 kV bus (for an **asset** in the North Island) or Benmore 220 kV bus (for an **asset** in the South Island) is within the no-trip zone shaded and marked "No-trip zone" in Figure 8.3 for the period of 1 second immediately following the commencement of a trip of the **HVDC link**.
- (3) Whether a **generator** is complying with subclause (2) must be determined using power system analysis that uses—
  - (a) study cases provided by the relevant **grid owner**; and
  - (b) relevant system assumptions provided by the **system operator**.
- (4) A **generator** is not required to comply with subclause (1) in respect of an **asset** in the event of a fault of a type described in subclause (1) if the **asset** becomes isolated from the **grid** as a result of the fault.
- (5) A **generating unit** need not comply with subclause (1) to the extent that it is complying with a **special protection scheme** approved by the **system operator**.

- (6) The absolute **grid** voltage (per unit) shown on the Y axis of Figure 8.1 and Figure 8.2 is the ratio of **grid** lowest **line-to-line** voltage on a **line** to the nominal operating voltage of the **line** (that is, 110 kV or 220 kV).


**Figure 8.1: North Island no-trip zone during 110 kV or 220 kV faults**



**Figure 8.2: South Island no-trip zone during 110 kV or 220 kV faults**



**Figure 8.3: Haywards and Benmore no-trip zone during permanent loss of the HVDC link**



Clause 8.25A Figure 8.1, Figure 8.2 and Figure 8.3: inserted, on 24 November 2016, by clause 6 of the Electricity Industry Participation Code Amendment (Generation Fault Ride Through) 2016.

Clause 8.25A(1): amended, on 5 October 2017, by clause 93(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 8.25A(2): amended, on 5 October 2017, by clause 93(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### 8.25B Reactive current and active power output

- (1) Each **generator** must ensure that each of its **generating units** generates **reactive current** to oppose the change in its terminal voltage without exceeding the maximum transient **reactive current** specified in the **generator's asset capability statement** for the period of 6 seconds immediately following the commencement of a fault on the **grid** of a type described in clause 8.25A(1).
- (2) Each **generator** must ensure that each of its **generating units** provides **active power** output relative to pre-fault **active power** output at least in proportion to the **grid** voltage at the **grid injection point** for the period of 6 seconds immediately following the clearance of a fault on the **grid** of a type described in clause 8.25A(1).
- (3) Subclause (2) does not apply to a **wind generating station** if there has been a reduction in the intermittent wind power source during the 6 seconds following the commencement of the fault.

Clause 8.25B: inserted, on 24 November 2016, by clause 6 of the Electricity Industry Participation Code Amendment (Generation Fault Ride Through) 2016.

### 8.25C Use of additional equipment

A **generator** may comply with clause 8.25A in relation to a **generating station** by—

- (a) ensuring that the performance of **generating units** that comprise the **generating station** comply; or
- (b) installing additional equipment within the **generating station**; or
- (c) a combination of the methods described in paragraphs (a) and (b).

Clause 8.25C: inserted, on 24 November 2016, by clause 6 of the Electricity Industry Participation Code Amendment (Generation Fault Ride Through) 2016.

### 8.25D Application

Clauses 8.25A and 8.25B do not apply—

- (a) to a **wind generating station** when it operates at less than 5% of rated **MW**; or
- (b) to any **asset** at an **excluded generating station**.

Clause 8.25D: inserted, on 24 November 2016, by clause 6 of the Electricity Industry Participation Code Amendment (Generation Fault Ride Through) 2016.

### 8.26 Asset owners must co-operate

Each **asset owner** and each **purchaser** must co-operate with the **system operator** as may reasonably be required by the **system operator** in carrying out its functions.

Compare: Electricity Governance Rules 2003 rule 4.7 section III part C

## *Compliance*

### 8.27 System operator to monitor compliance

- (1) To the extent possible, given the information made available by **asset owners**, the **system operator** must monitor, in the manner set out in the **policy statement**, the ongoing compliance of **asset owners** with the **asset owner performance obligations** and the **technical codes**. To avoid doubt, the **system operator** has no monitoring obligations under this subpart other than those set out in the **policy statement**.
- (2) The **system operator** has a discretion to not **dispatch** an **asset** or configuration of **assets**, if it is not satisfied that the **assets** or configuration of **assets** comply with the relevant **asset owner performance obligations** or provisions of the **technical codes**, or that the **asset owner** has and is complying with a valid **equivalence arrangement** or **dispensation** from the relevant **asset owner performance obligations** or provisions of the **technical codes**.
- (3) The **system operator** must immediately advise an **asset owner** if the **system operator** has reasonable grounds to believe that the **asset owner** is not complying with an **asset owner performance obligation**, **equivalence arrangement** or **dispensation**, and that the **asset owner**—
  - (a) does not have a valid **equivalence arrangement** or **dispensation** from the relevant **asset owner performance obligations** or provisions of the **technical codes**; or
  - (b) is not complying with a valid **equivalence arrangement** or **dispensation** from the relevant **asset owner performance obligations** or provisions of the **technical codes**.

Compare: Electricity Governance Rules 2003 rule 5 section III part C

Clause 8.27(2): amended, on 19 May 2016, by clause 23 of the Electricity Industry Participation Code Amendment (System Operator and Alignment with Statutory Objective) 2016.

### 8.28 Responsibility for compliance

- (1) Each **asset owner** must comply with the **asset owner performance obligations** and **technical codes** at all times and must satisfy the **system operator**, whenever requested by the **system operator** acting reasonably, that each of its **assets** or configuration of **assets** complies with the **asset owner performance obligations** and **technical codes** that apply to that **asset** or configuration of **assets**.
- (2) If an **asset owner** receives notification under clause 8.27(3), it must co-operate with the **system operator** and use reasonable endeavours to restore compliance as soon as practicable.
- (3) During a period of **commissioning** or testing of **assets**, the **asset owner performance obligations** and **technical codes** do not apply to the **asset owner** in respect of the **assets**, if—
  - (a) the obligations that do not apply to the **asset owner** are specified in the agreed **commissioning** plan or testing plan; and
  - (b) during the period of non-compliance the **asset owner** complies with a **commissioning** plan or testing plan (as appropriate) agreed with the **system operator**; and
  - (c) the period of non-compliance is no longer than the agreed **commissioning** plan or testing plan; and
  - (d) subject to subclause (4), if an **asset owner** during a period of non-compliance meets the requirements of paragraphs (a) to (c), neither the **asset owner** nor the **system operator** is liable under this Code in relation to the non-compliance, except that the **asset owner** is not relieved of liability in the case of a negligent act or omission by the **asset owner**.
- (4) During any period of non-compliance, the non-compliant **asset owner** must pay the readily identifiable and quantifiable costs associated with its non-compliance, including the costs of the **system operator** purchasing additional **ancillary services** required as a consequence of its non-compliance.

Compare: Electricity Governance Rules 2003 rule 6 section III part C  
Clause 8.28(3): amended, on 5 October 2017, by clause 94 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### *Equivalence arrangements and dispensations*

### 8.29 Right to apply for approval of equivalence arrangement or grant of dispensation

- (1) Subject to subclause (2), if an **asset owner** cannot comply with an **AOPO** or a **technical code** obligation in respect of a particular **asset** or configuration of **assets**, being an existing, new or proposed **asset**, the **asset owner** may apply for an **equivalence arrangement** to be approved or **dispensation** to be granted in accordance with Schedule 8.1.
- (2) The **system operator** may not grant a dispensation in relation to an obligation to provide **extended reserve** under clause 8.19(5) or Schedule 8.3, Technical Code B, clause 7.

Compare: Electricity Governance Rules 2003 rule 7.1 section III part C

Clause 8.29(1): amended, on 7 August 2014, by clause 8(1) of the Electricity Industry Participation Code Amendment (Extended Reserve) 2014.

Clause 8.29(2): inserted, on 7 August 2014, by clause 8(2) of the Electricity Industry Participation Code Amendment (Extended Reserve) 2014.

### 8.30 Approval of equivalence arrangements

The **system operator** must approve an **equivalence arrangement** if it has received satisfactory evidence that the **asset owner** will put in place on the agreed date technical or commercial arrangements that will, in the reasonable opinion of the **system operator**, achieve compliance with the **AOPO** or **technical code** for which the **equivalence arrangement** is sought, even if the **assets** or configuration of **assets** do not strictly comply.

Compare: Electricity Governance Rules 2003 rule 7.2 section III part C

### 8.31 Grant of dispensations

- (1) Subject to subclause (1A), the **system operator** must grant a **dispensation** to an **asset owner** who has or will have **assets** or a configuration of **assets** that do not comply with either an **AOPO** or **technical code** if the **system operator** has a reasonable expectation that it can continue to operate the existing system and meet its **principal performance obligations** and if the **system operator** can readily quantify the costs on other persons of that **dispensation**, despite the non-compliance of the **assets**, but—
- (a) if the approval of a **dispensation** could impose readily identifiable and quantifiable costs on other persons, a condition of the **dispensation** must be that the **asset owner** is liable to pay the **system operator** for those costs, including the costs of the **system operator** purchasing any other **ancillary services** required as a consequence of its **dispensation**; and
  - (b) the **asset owner** must acknowledge that the granting of a **dispensation** does not guarantee that the **system operator** will **dispatch** that **asset** for which the **dispensation** was granted, as **dispatch** will only occur in accordance with the **dispatch objective**; and
  - (c) if the **dispensation** is a **generating unit dispensation** from clause 8.19(1) or (3), the **generator** must be allocated the following costs in a relevant **trading period** with respect to paragraph (a) for each of **fast instantaneous reserves** or **sustained instantaneous reserves**:

$$\text{DispCost}_{\text{GENxt}} = 0.5 * Q_{\text{GENxt}} * P_{\text{IRt}}$$

where

**DispCost<sub>GENxt</sub>** is the cost payable by a **generator** for **generating unit x** in any **trading period t** in which a class of **instantaneous reserves** is procured as a direct result of that **generating unit's dispensation** to ensure that the frequency does not fall below 47 Hertz or, in the South Island, below the **minimum South Island frequency**

**Q<sub>GENxt</sub>** is the **MW** amount by which **generating unit x** is unable to

sustain pre-event output in **trading period t** with reference to clause 8.19(1) or (3) (as the case may be) as determined from the capabilities specified in that **generating unit's dispensation** (different amounts may be specified with respect to each class of **instantaneous reserves**)

$P_{IRt}$  is the **final reserve price for fast instantaneous reserves or sustained instantaneous reserves** (as the case may be) in **trading period t** in the relevant **island**.

- (1A) If the **system operator** grants a **dispensation** from clause 8.25A or clause 8.25B to an **asset owner** under subclause (1), and the granting of the **dispensation** could impose readily identifiable and quantifiable costs on any other person, the **system operator** must not impose a condition on the **asset owner** in accordance with subclause (1)(a) that has effect earlier than 24 November 2018.
- (2) The **system operator** may impose other reasonable conditions on the grant of a **dispensation** under subclause (1), including conditions as to duration of the **dispensation**.

Compare: Electricity Governance Rules 2003 rules 7.3 and 7.4 section III part C

Clause 8.31(1): amended, on 15 May 2014, by clause 7 of the Electricity Industry Participation (Minor Code Amendments) Code Amendment 2014.

Clause 8.31(1): amended, on 24 November 2016, by clause 7(1) of the Electricity Industry Participation Code Amendment (Generation Fault Ride Through) 2016.

Clause 8.31(1)(c): amended, on 19 May 2016, by clause 24 of the Electricity Industry Participation Code Amendment (System Operator and Alignment with Statutory Objective) 2016.

Clause 8.31(1A): inserted, on 24 November 2016, by clause 7(2) of the Electricity Industry Participation Code Amendment (Generation Fault Ride Through) 2016.

### 8.32 Liability of asset owner pending decision

Pending determination of an **asset owner's** application for a **dispensation** or an **equivalence arrangement**, if the **asset** does not comply with the **AOPOs** or the **technical codes**, the **asset owner** is liable for the non-compliance and is responsible for additional costs incurred by the **system operator** or **asset owners** as a result of the non-compliance, including the costs of the **system operator** purchasing other **ancillary services** as a consequence of the non-compliance.

Compare: Electricity Governance Rules 2003 rule 8 section III part C

Clause 8.32: amended, on 15 May 2014, by clause 8 of the Electricity Industry Participation (Minor Code Amendments) Code Amendment 2014.

### 8.33 Modification of equivalence arrangement or dispensation

An **asset owner** may apply to the **system operator** for a modification to an **equivalence arrangement** or **dispensation**, in which case clauses 8.34 to 8.36 and Schedule 8.1 apply.

Compare: Electricity Governance Rules 2003 rule 8.1 section III part C

### 8.34 Cancellation of equivalence arrangement or dispensation

- (1) An **asset owner** may at any time give written notice to the **system operator** for an **equivalence arrangement** or a **dispensation** to be cancelled on the grounds that the



**asset** or configuration of **assets** subject to the **equivalence arrangement** or **dispensation** complies with **APOs** or **technical codes**.

- (2) A cancellation takes effect on the date specified in the notice as being the date the **system operator** accepted the cancellation.
- (3) The **system operator** must record the cancellation in the **system operator register** no later than 5 days after receiving the notice.

Compare: Electricity Governance Rules 2003 rule 8.2 section III part C

### 8.35 Revocation of equivalence arrangement and revocation or variation of dispensation

- (1) The **system operator** may revoke approval of an **equivalence arrangement** or revoke or vary the grant of a **dispensation** as the **system operator** reasonably considers appropriate if, at any time after the **system operator** has approved an **equivalence arrangement** or granted a **dispensation**, the **system operator** is satisfied that 1 or more of the following apply:
  - (a) the **dispensation** or **equivalence arrangement** was approved on information that was false or materially misleading;
  - (b) a prerequisite of the **dispensation** or **equivalence arrangement** has changed;
  - (c) a condition on which the **dispensation** or **equivalence arrangement** was approved has not been complied with;
  - (d) withdrawal is **provided** for under the terms of the **dispensation** granted;
  - (e) a change to this Code has occurred that affects the **dispensation** or **equivalence arrangement**;
  - (f) a decision has been reconsidered at the direction of the **Rulings Panel** under clause 8.36(4).
- (2) The **system operator** must not revoke or amend a **dispensation** or grant a further **dispensation** or revoke its approval of an **equivalence arrangement** under subclause (1), unless—
  - (a) the **asset owner** to whom the **dispensation** was granted, or for whom an **equivalence arrangement** was approved, and any other person who in the opinion of the **system operator** is likely to have an interest in the matter, is given reasonable notice of the **system operator's** intentions and a reasonable opportunity to make submissions to the **system operator** on the issue; and
  - (b) the **system operator** has had regard to the submissions.

Compare: Electricity Governance Rules 2003 rule 8.3 section III part C

### 8.36 Appeal against decisions

- (1) A **participant** may **appeal** a decision of the **system operator** or an **asset owner** in relation to an application for **dispensation** or **equivalence arrangements** on the grounds set out in subclause (3).
- (2) An appeal must be made to the **Rulings Panel** by giving written notice to the **Authority** specifying the grounds of appeal. A notice must be given no later than 10 **business days** after publication of the relevant decision in the **system operator register** under clause 8 of Schedule 8.1.

- (3) For the purposes of subclause (2), an appeal may be made on the grounds that—
  - (a) the **system operator** made an error of fact or failed to take into account all relevant information or took into account irrelevant information and such error, failure or irrelevancy was material to the decision; or
  - (b) the conditions imposed on the **dispensation** or **equivalence arrangement** are unjustifiably onerous, unnecessary or impose extra costs if appropriate alternatives exist.
- (4) The **Rulings Panel**, in determining an appeal, must approve the decision of the **system operator** or direct the **system operator** to reconsider the decision in full or by reference to specified matters.
- (5) Pending the outcome of an appeal, the decision of the **system operator** in relation to the grant of a **dispensation** or approval of an **equivalence arrangement** remains valid and may be relied upon by the relevant **asset owner**.

Compare: Electricity Governance Rules 2003 rule 8.4 section III part C

### 8.37 Other provisions relating to equivalence arrangements and dispensations

- (1) An **asset owner** who obtains approval for an **equivalence arrangement** must comply with its obligations under that arrangement.
- (1A) An **asset owner** who is granted a **dispensation** must comply with its obligations under that **dispensation**.
- (2) An **equivalence arrangement** and a **dispensation** are specific to an **asset owner**, and no approval of an **equivalence arrangement** or granting of a **dispensation** creates a precedent for the approval of other **equivalence arrangements** or **dispensations**.
- (3) The owner or operator of an **asset** or configuration of **assets** must advise the **system operator** if the owner or operator believes that it is in breach of a condition of its **dispensation** or **equivalence arrangement** or that the **asset** or configuration of **assets**, including any **equivalence arrangement**, does not, or is likely not to, comply with the **asset owner performance obligations** and **technical codes**.
- (4) If an **asset owner** fails to put in place, maintain and meet all requirements of an approved **equivalence arrangement** or **dispensation**, the **asset owner** is in breach of this Code.

Compare: Electricity Governance Rules 2003 rule 9 section III part C

Clause 8.37(1A): inserted, on 15 May 2014, by clause 9 of the Electricity Industry Participation (Minor Code Amendments) Code Amendment 2014.

### 8.38 Authority may require excluded generating stations to comply with certain clauses

- (1) Despite clauses 8.17, 8.19, and 8.25D, the **system operator** may, at any time, apply to the **Authority** for the **Authority** to issue a directive that an **excluded generating station asset** must comply with clauses 8.17, 8.19, 8.25A, and 8.25B, and the provisions of the **technical codes** (or parts thereof).
- (2) The **Authority** must issue the directive referred to in subclause (1) if the **Authority** is satisfied that there is a **benefit to the public** in obtaining compliance.

- (3) If a directive is issued under subclause (2), the owner of the **excluded generating station asset** must comply with the directive with effect from the date specified in the directive.

Compare: Electricity Governance Rules 2003 rule 10 section III part C

Clause 8.38(1): amended, on 24 November 2016, by clause 8(1) and (2) of the Electricity Industry Participation Code Amendment (Generation Fault Ride Through) 2016.

### Subpart 3—Arrangements concerning ancillary services

#### 8.39 Contents of this subpart

This subpart provides for—

- (a) a **procurement plan** that the **system operator** must use reasonable endeavours to implement and comply with; and
- (b) the review of the **procurement plan**; and
- (c) **alternative ancillary service arrangements**; and
- (d) how **ancillary services** are to be priced and measured; and
- (e) identifying the **allocable costs** for **ancillary services** and the regime by which those costs are allocated to affected parties.

Compare: Electricity Governance Rules 2003 rule 1 section IV part C

#### *Procurement plan*

#### 8.40 System operator to use reasonable endeavours to implement and comply with procurement plan

The **system operator** must use reasonable endeavours to both implement and comply with the **procurement plan**.

Compare: Electricity Governance Rules 2003 rule 2 section IV part C

#### 8.41 *[Revoked]*

Clause 8.41: revoked, on 10 January 2013, by clause 15 of the Electricity Industry Participation (Policy Statement and Procurement Plan Review Process) Code Amendment 2012.

#### 8.42 Incorporation of procurement plan by reference

- (1) The **procurement plan** is incorporated by reference in this Code in accordance with section 32 of the **Act**.
- (2) Subclause (1) is subject to Schedule 1 of the **Act**, which includes a requirement that the **Authority** must give notice in the *Gazette* before an amended or substituted **procurement plan** becomes incorporated by reference in this Code.

Compare: Electricity Governance Rules 2003 rule 3 section IV part C

Clause 8.42(1): amended, on 10 January 2013, by clause 16 of the Electricity Industry Participation (Policy Statement and Procurement Plan Review Process) Code Amendment 2012.

#### 8.42A Review of procurement plan

- (1) At least once every 2 years the **system operator** must—
  - (a) review the **procurement plan**; and
  - (b) as soon as practicable after completing the review, decide whether or not to propose a change to the **procurement plan**; and

- (c) advise the **Authority** of its decision.
- (2) If the **system operator** decides to propose a change to the **procurement plan**, the **system operator** must submit a **draft procurement plan** to the **Authority** together with the following information:
  - (a) an explanation of the proposed change and a statement of the objectives of the proposed change;
  - (b) an evaluation of the costs and benefits of the proposed change;
  - (c) an evaluation of alternative means of achieving the objectives of the proposed change;
  - (d) a list of the persons consulted and a summary of the submissions received.
- (3) As part of a review conducted under this clause, the **system operator** must invite comments from **participants**.

Clause 8.42A: inserted, on 10 January 2013, by clause 17 of the Electricity Industry Participation (Policy Statement and Procurement Plan Review Process) Code Amendment 2012.

Clause 8.42A(1): amended, on 5 October 2017, by clause 95 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

#### **8.42B System operator decides not to amend the procurement plan**

If the **system operator** advises the **Authority** under clause 8.42A(1)(c) that the **system operator** does not intend to propose a change to the **procurement plan** the **system operator** must provide the **Authority** with the following information:

- (a) the findings of the review of the **procurement plan** conducted by the **system operator**;
- (b) details of any request to amend the **procurement plan** received from a **participant** or the **Authority** since the last review;
- (c) the **system operator's** decision on each such request including, if the **system operator** declined a requested change, the reason for declining.

Clause 8.42B: inserted, on 10 January 2013, by clause 17 of the Electricity Industry Participation (Policy Statement and Procurement Plan Review Process) Code Amendment 2012.

#### **8.42C Authority may require system operator to reconsider**

- (1) The **Authority** may require the **system operator** to reconsider a decision made under clause 8.42A(1)(b) not to propose a change to the **procurement plan**.
- (2) If the **Authority** requires the **system operator** to reconsider a decision made under subclause 8.42A(1)(b) the **Authority** must advise the **system operator** of—
  - (a) the **Authority's** reasons for requiring the **system operator** to reconsider; and
  - (b) the date, determined after consulting the **system operator**, by which the **system operator** must either confirm its decision or submit a **draft procurement plan**.
- (3) The **Authority** must as soon as practicable **publish** the advice received from the **system operator** under clause 8.42A(1)(c) and the advice given by the **Authority** to the **system operator** under subclause (2).

Clause 8.42C: inserted, on 10 January 2013, by clause 17 of the Electricity Industry Participation (Policy Statement and Procurement Plan Review Process) Code Amendment 2012.

Clause 8.42C(3): amended, on 5 October 2017, by clause 96 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### 8.43 Content of draft procurement plan

The **draft procurement plan** must, for each **ancillary service**—

- (a) specify the principles that the **system operator** must apply in making a **net purchase quantity assessment**, which must include—
  - (i) determining the requirements for complying with the **principal performance obligations**; and
  - (ii) determining the requirements for achieving the **dispatch objective**; and
  - (iii) assessing the contribution that compliance by **asset owners** with the **asset owner performance obligations** will make towards the **system operator's** compliance with the **principal performance obligations**; and
  - (iv) assessing the impact that **dispensations** and **alternative ancillary services arrangements** held by **asset owners** will have on the quantity of **ancillary services** required to enable the **system operator** to comply with the **principal performance obligations**; and
- (b) contain a methodology for conducting a **net purchase quantity assessment** for each relevant **ancillary service**; and
- (c) outline the process that the **system operator** must use to procure that **ancillary service**, taking into account that the **system operator** must use—
  - (i) market mechanisms to procure **ancillary services** wherever technology and transaction costs make this practicable and efficient; and
  - (ii) transparent processes that encourage all potential providers to compete to supply **ancillary services** required to meet **common quality** standards at the best economic cost; and
- (d) specify the **administrative costs** for that **ancillary service** as proposed in the **draft procurement plan**; and
- (e) outline the **system operator's** technical requirements and key contract terms to support the **procurement plan**; and
- (f) outline the rights and obligations of the **system operator** in relation to procurement of that **ancillary service** in circumstances not anticipated by the **draft procurement plan**, and if the assumptions made by the **system operator** in the **procurement plan** cannot be met; and
- (g) outline how the **system operator** will report on progress in implementing the **procurement plan**.

Compare: Electricity Governance Rules 2003 rule 4 section IV part C

Clause 8.43: substituted, on 10 January 2013, by clause 18 of the Electricity Industry Participation (Policy Statement and Procurement Plan Review Process) Code Amendment 2012.

Clause 8.43: amended, on 19 December 2014, by clause 9 of the Electricity Industry Participation Code Amendment (Minor Code Amendments) (No 3) 2014.

### 8.43A Changes and variations

- (1) The **system operator** may at any time propose a change to the **procurement plan** by submitting a **draft procurement plan** to the **Authority** together with the following information:
  - (a) an explanation of the proposed change and a statement of the objectives of the proposed change:

- (b) an evaluation of alternative means of achieving the objectives of the proposed change:
  - (c) an evaluation of the costs and benefits of the proposed change.
- (2) The **Authority** or a **participant** may at any time request that the **system operator** propose a change to the **procurement plan** under subclause (1).
- (3) If the **system operator** receives a request under subclause (2), it must as soon as practicable—
  - (a) decide whether to decline the request, defer the request until the next **review date**, or submit a **draft procurement plan** to the **Authority**; and
  - (b) **publish** the decision.
- (4) If the **system operator** declines a request under subclause (3) the **Authority** may require the **system operator** to reconsider its decision, giving reasons.

Clause 8.43A: inserted, on 10 January 2013, by clause 19 of the Electricity Industry Participation (Policy Statement and Procurement Plan Review Process) Code Amendment 2012.

Clause 8.43A(3)(b): amended, on 5 October 2017, by clause 97 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

#### 8.44 Consultation on draft procurement plan

- (1) The **Authority** must **publish** the following information as soon as practicable after it receives it:
  - (a) a **draft procurement plan** submitted under clause 8.42A and the information required under clause 8.42A(2):
  - (b) a **draft procurement plan** submitted under clause 8.43A and the information required under clause 8.43A(1)(a) to (c).
- (2) When the **Authority publishes** a **draft procurement plan** and information under subclause (1) the **Authority** must advise **participants** of the date (which must not be earlier than 10 **business days** after the date that the **Authority publishes** the **draft procurement plan**) by which submissions on the changes proposed in the **draft procurement plan** must be received by the **Authority**.
- (3) Each submission on changes proposed in a **draft procurement plan** must be made in writing to the **Authority** and received on or before the **submission expiry date**.
- (4) The **Authority** must provide a copy of each submission received to the **system operator** at the close of business on the **submission expiry date** and must **publish** the submissions as soon as practicable.
- (5) The **system operator** may make its own submission on the **draft procurement plan** and the submissions received in relation to it no later than 10 **business days** after the **submission expiry date**.
- (6) The **Authority** must **publish** the **system operator's** submission as soon as practicable after it is received.
- (7) Following the consultation process required by subclauses (1) to (6), the **Authority** may approve the **draft procurement plan** subject to the **system operator** making any changes that the **Authority** considers appropriate.

Compare: Electricity Governance Rules 2003 rule 5 section IV part C

Clause 8.44: substituted, on 10 January 2013, by clause 20 of the Electricity Industry Participation (Policy Statement and Procurement Plan Review Process) Code Amendment 2012.

Clause 8.44(1), (4) and (6): amended, on 5 October 2017, by clause 98(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 8.44(2): amended, on 5 October 2017, by clause 98(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

#### 8.44A Technical and non-controversial amendments

- (1) The **system operator** may at any time propose a change to the **procurement plan** that it considers is technical and non-controversial by submitting a **draft procurement plan** to the **Authority** together with an explanation of the proposed change.
- (2) If the **system operator** submits a **draft procurement plan** under subclause (1) it is not required to provide a statement of the objectives of the proposed change, an evaluation of alternative means of achieving the objectives of the proposed change or an evaluation of the costs and benefits of the proposed change.
- (3) The **Authority** must, as soon as practicable after receiving a **draft procurement plan** and the information required under subclause (1), by notice in writing to the **system operator**—
  - (a) approve the **draft procurement plan** to be incorporated by reference into this Code; or
  - (b) decline to approve the **draft procurement plan**, giving reasons.
- (4) If the **Authority** approves the **draft procurement plan** it must as soon as practicable—
  - (a) **publish** notice of its intention to incorporate the **draft procurement plan** by reference into this Code; and
  - (b) include in the notice the **Authority's** reasons for considering that the changes proposed in the **draft procurement plan** are technical and non-controversial; and
  - (c) invite comment from **participants** on the reasons given in the notice.
- (5) After considering any comments made under subclause 4(c) the **Authority** must advise the **system operator** by notice in writing of its decision as to whether to confirm or revoke its approval of the **draft procurement plan**, and give reasons for its decision.
- (6) The **Authority** must **publish** its decision and reasons as soon as practicable.

Clause 8.44A: inserted, on 10 January 2013, by clause 21 of the Electricity Industry Participation (Policy Statement and Procurement Plan Review Process) Code Amendment 2012.

Clause 8.44A(4)(a) and (6): amended, on 5 October 2017, by clause 99 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

#### 8.44B Authority adopts new procurement plan

If the **Authority** approves a **draft procurement plan** under clause 8.44 or confirms its approval of a **draft procurement plan** under clause 8.44A it must—

- (a) incorporate the new **procurement plan** by reference into this Code in accordance with Schedule 1 of the **Act**; and
- (b) **publish** the new **procurement plan** and the date on which it takes legal effect.

Clause 8.44B: inserted, on 10 January 2013, by clause 21 of the Electricity Industry Participation (Policy Statement and Procurement Plan Review Process) Code Amendment 2012.

Clause 8.44B(b): amended, on 5 October 2017, by clause 100 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

#### 8.45 Contracts with ancillary service agents

- (1) The **system operator** must use reasonable endeavours to implement the **procurement plan** for each **ancillary service** by entering into contracts with the **ancillary service agents** in the manner specified in the **procurement plan**.
- (2) The **system operator** is the principal in any contract it enters into with an **ancillary**

**service agent.**

- (3) If the **system operator** has entered into a contract, the **system operator** must use reasonable endeavours to ensure that the **ancillary service agent** complies with its contractual obligations, but the **system operator** is not otherwise liable in respect of any failure by an **ancillary service agent** to comply with such obligations.

Compare: Electricity Governance Rules 2003 rule 6 section IV part C

#### **8.45A Methodology to assess net purchase quantity**

The **system operator** must make the **net purchase quantity assessment** for each relevant **ancillary service** using the methodology in the **procurement plan** and **publish** the results of the assessment as soon as practicable.

Clause 8.45A: inserted, on 10 January 2013, by clause 22 of the Electricity Industry Participation (Policy Statement and Procurement Plan Review Process) Code Amendment 2012.

Clause 8.45A: amended, on 5 October 2017, by clause 101 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

#### **8.46 [Revoked]**

Compare: Electricity Governance Rules 2003 rule 7 section IV part C

Clause 8.46: revoked, on 10 January 2013, by clause 23 of the Electricity Industry Participation (Policy Statement and Procurement Plan Review Process) Code Amendment 2012.

#### **8.47 Departure from procurement plan**

- (1) The **system operator** may depart from the processes and arrangements set out in the **procurement plan** if the **system operator** reasonably considers it necessary to do so to comply with the **principal performance obligations**.
- (2) When the **system operator** makes a departure under subclause (1), the **system operator** must provide a report to the **Authority** setting out the circumstances of the departure and the actions taken to deal with it.
- (3) The **Authority** must **publish** the report within a reasonable time after receiving it.

Compare: Electricity Governance Rules 2003 rule 8 section IV part C

Clause 8.47(2): amended, on 10 January 2013, by clause 24(a) of the Electricity Industry Participation (Policy Statement and Procurement Plan Review Process) Code Amendment 2012.

Clause 8.47(3): inserted, on 10 January 2013, by clause 24(b) of the Electricity Industry Participation (Policy Statement and Procurement Plan Review Process) Code Amendment 2012.

Clause 8.47(3): amended, on 5 October 2017, by clause 102 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

#### *Alternative ancillary service arrangements*

#### **8.48 Alternative ancillary service arrangements**

- (1) If an **asset owner** wishes to have an **alternative ancillary service arrangement** authorised by the **system operator**, that **asset owner** (or, if more than 1 **asset owner** wishes to have an authorisation, those **asset owners** jointly) may apply to the **system operator** to have that arrangement authorised as an **alternative ancillary service arrangement** using the process set out in Schedule 8.2.
- (2) The **system operator** must authorise the arrangement as an **alternative ancillary service arrangement** if—
- (a) the proposed arrangement complies with the technical requirements for that **ancillary service** as set out in the current **procurement plan**; and



- (b) the implementation of the proposed arrangement will make the **ancillary service** available for **dispatch** by the **system operator** in substantially the same manner as if the **ancillary service** had been procured in accordance with the **procurement plan**.
- (3) As a condition of authorising an **alternative ancillary service arrangement** under subclause (2), the **system operator** may do 1 or more of the following:
  - (a) require the **asset owner** to enter into arrangements with the **system operator** to ensure that the **system operator** can continue to meet the **principal performance obligations**;
  - (b) specify the date on which the **alternative ancillary service arrangement** commences;
  - (c) impose any other condition it reasonably believes is necessary, including conditions necessary for the **system operator** to meet its **principal performance obligations** and conditions necessary for the orderly reconciliation and settlement of **ancillary services**.

Compare: Electricity Governance Rules 2003 rules 9.1 to 9.3 section IV part C

#### **8.49 Suspension of alternative ancillary service arrangement**

- (1) An **asset owner** may at any time give written reasonable notice to the **system operator** of suspension of the **alternative ancillary service arrangement** for a period specified in the notice.
- (2) The **system operator** may suspend an **alternative ancillary service arrangement** in a **system security situation**.

Compare: Electricity Governance Rules 2003 rule 9.4 section IV part C

#### **8.50 Modification of alternative ancillary service arrangement**

An **asset owner** may apply to the **system operator** for a modification to an **alternative ancillary service arrangement** in which case clauses 8.51 to 8.53 and Schedule 8.2 apply.

Compare: Electricity Governance Rules 2003 rule 9.5 section IV part C

#### **8.51 Cancellation of alternative ancillary service arrangement**

An **asset owner** may at any time give reasonable notice in writing to the **system operator** of cancellation of the **alternative ancillary service arrangement**, which comes into effect on the date specified in the notice.

Compare: Electricity Governance Rules 2003 rule 9.6 section IV part C

#### **8.52 Revocation of alternative ancillary service arrangements**

- (1) The **system operator** may revoke authorisation of the **alternative ancillary service arrangement** as the **system operator** reasonably considers appropriate, if at any time after the **system operator** has authorised an **alternative ancillary service arrangement**, the **system operator** is satisfied that 1 or more of the following factors apply:
  - (a) the **alternative ancillary service arrangement** was authorised on information that was false or materially misleading;

- (b) a prerequisite of the **alternative ancillary service arrangement** has changed;
  - (c) a condition upon which the authorisation was granted has not been complied with;
  - (d) such revocation is provided for under the terms of the authorisation.
- (2) Subject to clause 8.49(2), the **system operator** must not revoke or amend an **alternative ancillary service arrangement** unless—
- (a) the person to whom the authorisation was granted and any other person who, in the opinion of the **system operator**, is likely to have an interest in the matter, is given reasonable notice of the **system operator's** intentions and a reasonable opportunity to make submissions to the **system operator**; and
  - (b) the **system operator** has had regard to those submissions.

Compare: Electricity Governance Rules 2003 rule 9.7 section IV part C

### 8.53 Appeal of system operator decisions

- (1) An applicant may appeal any decision of the **system operator** in relation to any **alternative ancillary service arrangement**.
- (2) A **participant** may appeal any decision of the **system operator** in relation to an **alternative ancillary service arrangement** on the grounds set out in subclause (4).
- (3) An appeal must be commenced with the **Rulings Panel** by giving written notice to the **Authority**, specifying the grounds of appeal. A notice must be given within 10 **business days** of **publication** of the decision in the **system operator register** under clause 4 of Schedule 8.2.
- (4) For the purpose of subclause (2), an appeal may be made on the grounds that—
  - (a) the **system operator** made an error of fact, or failed to take properly into account all relevant information or took into account irrelevant information, and such error, failure or irrelevancy was material to the decision; or
  - (b) the conditions imposed on the **alternative ancillary service arrangement** are onerous, unnecessary or impose extra costs if appropriate alternatives exist.
- (5) The **Rulings Panel**, in determining an appeal, must either approve the decision of the **system operator** or direct the **system operator** to reconsider the decision in full or by reference to specified matters.
- (6) Pending the outcome of an appeal, the decision of the **system operator** in relation to the authorisation of an **alternative ancillary service arrangement** remains valid and can be acted upon by the relevant **asset owner**.

Compare: Electricity Governance Rules 2003 rule 9.8 section IV part C

### 8.54 Other provisions relating to alternative ancillary service arrangements

- (1) The **system operator** must monitor the performance of **alternative ancillary service arrangements** in accordance with the **procurement plan** and the monitoring regimes specified in the respective **alternative ancillary service arrangements**. If the **system operator** considers, on reasonable grounds, that an **alternative ancillary service arrangement** is not being, or likely not to be, complied with, the **system operator** must immediately advise the **asset owner**.
- (2) An **asset owner** who obtains an authorisation of an **alternative ancillary service arrangement** must comply with its obligations under the arrangement. If an **asset**

**owner** receives notification under subclause (1), it must co-operate with the **system operator** and must immediately use reasonable endeavours to restore compliance as soon as possible.

- (3) An **asset owner** who holds an **alternative ancillary service arrangement** is relieved of an obligation to pay costs for **ancillary service** in the manner provided for in clauses 8.55 to 8.59 and 8.64 to 8.70 to the extent provided for in the **alternative ancillary service arrangement**.
- (4) The holder of an **alternative ancillary service arrangement** breaches this Code if **ancillary services** are not made available to the **system operator** in accordance with the **alternative ancillary service arrangement**, or if an **alternative ancillary service arrangement** fails. From the date a breach of an **alternative ancillary service arrangement** becomes known, the holder of the **alternative ancillary service arrangement** must meet its share of the ancillary costs as if the **alternative ancillary service arrangement** had not been authorised.

Compare: Electricity Governance Rules 2003 rule 10 section IV part C

## Subpart 4—Interruptible load

Heading: inserted, on 7 August 2014, by clause 9 of the Electricity Industry Participation Code Amendment (Extended Reserve) 2014.

### 8.54A Contents of this subpart

This subpart provides for the provision of information relating to **interruptible load**.

Clause 8.54A: inserted, on 7 August 2014, by clause 9 of the Electricity Industry Participation Code Amendment (Extended Reserve) 2014.

### 8.54B Ancillary service agents to provide information about interruptible load

- (1) Each **ancillary service agent** that contracts for **interruptible load** in a **network** must, within 10 **business days** of entering into the contract, give the following **participants** the information in subclause (2):
  - (a) if the **interruptible load** is contracted on a **local network**, the **connected asset owner** that operates the **local network**;
  - (b) if the **interruptible load** is contracted on an **embedded network**, the **connected asset owner** that operates the **local network** to which the **embedded network** is **connected**;
  - (c) if the **interruptible load** is contracted on the **grid**, the **grid owner** that owns or operates the part of the **grid** on which the **interruptible load** is contracted.
- (2) The information required is—
  - (a) a list of the **ICPs** to which the contract relates; and
  - (b) the maximum **MW** that can be interrupted under the contract; and
  - (c) the commencement and expiry dates of the contract.
- (3) If an **ancillary service agent** has given a **connected asset owner** or **grid owner** information under subclause (1), the **connected asset owner** or **grid owner** may require the **ancillary service agent** to provide further information about the **interruptible load** to which the contract relates.
- (4) An **ancillary service agent** must comply with a requirement under subclause (3).

Clause 8.54B: inserted, on 7 August 2014, by clause 9 of the Electricity Industry Participation Code Amendment (Extended Reserve) 2014.

Clause 8.54B(1)(b): amended, on 23 February 2015, by clause 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 8.54B(1) and (3): amended, on 1 February 2016, by clause 11 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

## Subpart 5—Extended reserve

Heading: inserted, on 7 August 2014, by clause 9 of the Electricity Industry Participation Code Amendment (Extended Reserve) 2014.

### 8.54C Contents of this subpart

This subpart provides for the procurement of **extended reserve**.

Clause 8.54C: inserted, on 7 August 2014, by clause 9 of the Electricity Industry Participation Code Amendment (Extended Reserve) 2014.

### 8.54D System operator to review extended reserve

- (1) The **system operator** must review the technical requirements for **extended reserve** in accordance with this clause.
- (2) The **Authority** may, at any time, give the **system operator** principles outlining the **Authority's** expectations for the objectives of the review.
- (3) As part of the review, the **system operator** must consider any principles given to the **system operator** by the **Authority** under subclause (2).
- (4) On the basis of the review, the **system operator** must prepare and **publish**—
  - (a) an **extended reserve technical requirements report**; and
  - (b) an **extended reserve technical requirements schedule**.
- (5) The **extended reserve technical requirements report** must reflect the **system operator's** analysis of the technical requirements for **extended reserve** on which the **extended reserve technical requirements schedule** is based.
- (6) The **extended reserve technical requirements schedule** must—
  - (a) specify the technical specifications for **extended reserve** that the **system operator** requires in order to be able to comply with the **principal performance obligations**; and
  - (b) specify requirements for periodic testing that each **extended reserve provider** will be required to carry out in relation to the relevant **assets**.
- (7) The consultation requirements in Part 1 of Schedule 8.5 apply to the preparation and **publication** of the **extended reserve technical requirements schedule**.

Clause 8.54D: inserted, on 7 August 2014, by clause 9 of the Electricity Industry Participation Code Amendment (Extended Reserve) 2014.

### 8.54E Review of extended reserve technical requirements schedule

- (1) The **system operator** must—
  - (a) review the **extended reserve technical requirements schedule** under this clause; and
  - (b) as soon as practicable after completing the review, decide whether to propose a change to the schedule; and
  - (c) advise the **Authority** of its decision.

- (2) The review must be conducted so that the **system operator** advises the **Authority** of its decision no later than 60 months after the date on which the **system operator** advised the **Authority** of its decision on the previous review.
- (3) The **Authority** may direct the **system operator** to review the **extended reserve technical requirements schedule** at a time that is sooner than required under subclause (2).
- (4) If the **system operator** decides to propose a change to the **extended reserve technical requirements schedule** as a result of a review, the **system operator** must—
  - (a) prepare and **publish**—
    - (i) an **extended reserve technical requirements report**; and
    - (ii) an **extended reserve technical requirements schedule**; and
  - (b) provide the following additional information when giving a draft of the revised schedule to the **Authority** under clause 2(2) of Schedule 8.5:
    - (i) an explanation of the proposed change and a statement of the objectives of the proposed change;
    - (ii) an evaluation of the costs and benefits of the proposed change;
    - (iii) an evaluation of alternative means of achieving the objectives of the proposed change.
- (5) Clause 8.54D(2), (3) and (5) to (7) applies to each review of the **extended reserve technical requirements schedule**.
- (6) If the **system operator** advises the **Authority** that it does not intend to propose a change to the **extended reserve technical requirements schedule**, the **system operator** must give the **Authority** the findings of its review of the schedule.

Clause 8.54E: inserted, on 7 August 2014, by clause 9 of the Electricity Industry Participation Code Amendment (Extended Reserve) 2014.

Clause 8.54E(2): amended, on 19 December 2014, by clause 10 of the Electricity Industry Participation Code Amendment (Minor Code Amendments) (No 3) 2014.

#### **8.54F Authority may require system operator to reconsider**

- (1) The **Authority** may require the **system operator** to reconsider a decision made under clause 8.54E(1)(c) not to propose a change to the **extended reserve technical requirements schedule**.
- (2) If the **Authority** requires the **system operator** to reconsider, the **Authority** must advise the **system operator** of—
  - (a) the **Authority's** reasons for requiring the **system operator** to reconsider; and
  - (b) the date, determined after consulting with the **system operator**, by which the **system operator** must—
    - (i) confirm its decision under clause 8.54E(1)(c); or
    - (ii) provide a draft of the revised schedule to the **Authority** under clause 2(2) of Schedule 8.5.
- (3) The **Authority** must as soon as practicable **publish** the advice received from the **system operator** under clause 8.54E(1)(c) and any advice given by the **Authority** to the **system operator** under subclause (2).

Clause 8.54F: inserted, on 7 August 2014, by clause 9 of the Electricity Industry Participation Code Amendment (Extended Reserve) 2014.

Clause 8.54F(3): amended, on 5 October 2017, by clause 103 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

#### **8.54G Preparation and publication of extended reserve selection methodology**

- (1) The **extended reserve manager** must prepare and **publish** an **extended reserve selection methodology**.
- (2) The methodology must specify how the **extended reserve manager** will procure **extended reserve** according to the **extended reserve technical requirements schedule**.
- (3) The methodology must—
  - (a) be based on the principles specified in clause 8.54H; and
  - (b) specify how the methodology applies to each **island**, including, if appropriate, specifying that the methodology does not apply to an **island**; and
  - (c) identify the **asset owners** that are required to provide information during an **extended reserve** selection process; and
  - (d) specify the information that the **asset owners** are required to provide; and
  - (e) specify the time frame within which **asset owners** are required to provide the information; and
  - (f) specify the basis on which the **extended reserve manager** selects **asset owners** to be **extended reserve providers**; and
  - (g) include default terms and conditions specifying the basis on which **extended reserve** must be provided, including requirements for periodic testing of **assets**.
- (3A) If the **extended reserve manager** decides that **asset owners** will receive payment for providing **extended reserve**, the methodology must specify how payments are set.
- (4) The consultation and approval requirements in Part 2 of Schedule 8.5 apply to the preparation and **publication** of the **extended reserve selection methodology**.

Clause 8.54G: inserted, on 7 August 2014, by clause 9 of the Electricity Industry Participation Code Amendment (Extended Reserve) 2014.

Clause 8.54G(3)(g): amended, on 5 October 2017, by clause 104(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 8.54G(3)(h): revoked, on 5 October 2017, by clause 104(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 8.54G(3A): inserted, on 5 October 2017, by clause 104(3) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

#### **8.54H Principles for extended reserve selection methodology**

- (1) The **extended reserve selection methodology** must give effect to the principles specified in subclause (2).
- (2) The **extended reserve selection methodology** must—
  - (a) reflect a balance of interests between potential **extended reserve providers**, and between such providers and the **system operator**; and
  - (b) enable **extended reserve** to be procured cost-effectively, by setting out how to evaluate—
    - (i) the expected cost of providing the **extended reserve** (including capital and operating costs); and
    - (ii) in the case of **extended reserve** that involves the interruption of load, the expected cost of an interruption during an event that calls on **extended reserve**, taking into account opportunity cost and the performance

- characteristics of the relevant load; and
- (iii) the likely transaction costs associated with administering **extended reserve** and in providing **extended reserve**; and
- (c) seek an appropriate balance between certainty in the provision of **extended reserve** products and flexibility to accommodate changes in circumstances and technologies.

Clause 8.54H: inserted, on 7 August 2014, by clause 9 of the Electricity Industry Participation Code Amendment (Extended Reserve) 2014.

#### **8.54I Review of extended reserve selection methodology**

- (1) The **Authority** may direct the **extended reserve manager** to review the **extended reserve selection methodology**.
- (2) Clause 8.54G applies to each review of the **extended reserve selection methodology**, except that the **extended reserve manager** must give a draft of the revised methodology to the **Authority** and the **system operator** under clause 5(2) of Schedule 8.5 no later than 40 **business days** after the date of the direction under subclause (1).

Clause 8.54I: inserted, on 7 August 2014, by clause 9 of the Electricity Industry Participation Code Amendment (Extended Reserve) 2014.

#### **8.54J Extended reserve manager to undertake extended reserve selection process**

- (1) The **extended reserve manager** must undertake an **extended reserve** selection process in accordance with the **extended reserve selection methodology** when directed to do so by the **Authority**.
- (2) The **Authority** must make a direction under subclause (1) no later than 60 months after the **publication** of the current **extended reserve procurement schedule**.
- (3) The **Authority** may direct the **extended reserve manager** as to the scope of a selection process.
- (4) If the **Authority** directs the **extended reserve manager** to undertake a limited selection process under subclause (3), the **Authority** must give reasons for the direction.
- (5) After completing a selection process, the **extended reserve manager** must prepare and **publish** an **extended reserve procurement schedule**.
- (6) Subclause (5) does not require the **extended reserve manager** to **publish** any information the **publication** of which would be likely unreasonably to prejudice the commercial position of the person who supplied or who is the subject of the information.
- (7) The **extended reserve procurement schedule** must—
  - (a) set out the results of the selection process; and
  - (b) identify the **asset owners** that are required to be **extended reserve providers**; and
  - (c) specify the **extended reserve** to be provided; and
  - (d) include information as to how the amounts payable (if any) to each **extended reserve provider** will be calculated; and
  - (e) identify **asset owners** that have not been selected to be **extended reserve providers**.
- (8) The consultation and approval requirements in Part 3 of Schedule 8.5 apply to the preparation and **publication** of the **extended reserve procurement schedule**.

- (9) The **extended reserve manager** may undertake consultation additional to that required by Part 3 of Schedule 8.5 if the **extended reserve manager** considers it necessary to do so.
- (10) As soon as practicable after receiving a direction from the **Authority** under subclause (2), the **extended reserve manager** must **publish** an indicative time frame within which the **extended reserve manager** expects to complete the selection process.
- (11) The **publication** of an **extended reserve procurement schedule** relating to the provision of **extended reserve** for only part of an **island** must be disregarded for the purposes of determining the date by which the **Authority** must give a direction under subclause (2).
- (12) Despite subclause (6), the **extended reserve manager** must, within 2 **business days** after **publishing** the **extended reserve procurement schedule** under subclause (5), provide a copy of the **extended reserve procurement schedule** to the **clearing manager**.

Clause 8.54J: inserted, on 7 August 2014, by clause 9 of the Electricity Industry Participation Code Amendment (Extended Reserve) 2014.

Clause 8.54J(2): amended, on 19 December 2014, by clause 11 of the Electricity Industry Participation Code Amendment (Minor Code Amendments) (No 3) 2014.

Clause 8.54J(12): inserted, on 19 January 2017, by clause 6 of the Electricity Industry Participation Code Amendment (Extended Reserve) 2016.

#### **8.54K Information required for extended reserve selection process**

- (1) During an **extended reserve** selection process, each **asset owner** identified in the **extended reserve selection methodology**, other than a **generator** that is directly **connected** to the **grid**, must comply with a request from the **extended reserve manager** to provide any information described in the methodology.
- (2) Each **asset owner** required to give information to the **extended reserve manager**, must do so—
  - (a) within the time frame specified in the **extended reserve selection methodology**; and
  - (b) in accordance with the **extended reserve selection methodology**, data specification and **extended reserve manager** calendar **published** by the **extended reserve manager**.
- (3) If the **extended reserve manager** considers that any information provided by an **asset owner** is incomplete or insufficient, the **extended reserve manager** may require that the **asset owner** provide further information.
- (4) An **asset owner** must comply with a requirement under subclause (3) within the time frame specified by the **extended reserve manager**.

Clause 8.54K: inserted, on 7 August 2014, by clause 9 of the Electricity Industry Participation Code Amendment (Extended Reserve) 2014.

Clause 8.54K(1): amended, on 19 January 2017, by clause 7(1) of the Electricity Industry Participation Code Amendment (Extended Reserve) 2016.

Clause 8.54K(2): replaced, on 19 January 2017, by clause 7(2) of the Electricity Industry Participation Code Amendment (Extended Reserve) 2016.

#### **8.54L Extended reserve manager to issue extended reserve procurement notices**

- (1) The **extended reserve manager** must issue an **extended reserve procurement notice** to each **asset owner** specified in the **extended reserve procurement schedule**.



- (2) Each **extended reserve procurement notice** must—
  - (a) specify the information in the **extended reserve procurement schedule** relating to the **asset owner**; and
  - (b) if an **asset owner** has been selected to be an **extended reserve provider**,—
    - (i) specify the default terms and conditions (as specified in the **extended reserve selection methodology**) that apply to the provision of **extended reserve** by the **asset owner**; and
    - (ii) include information as to how the amounts payable (if any) to each **extended reserve provider** will be calculated.
- (3) The **extended reserve manager** must give each **asset owner** its **extended reserve procurement notice** no later than 5 **business days** after **publishing** the **extended reserve procurement schedule**.

Clause 8.54L: inserted, on 7 August 2014, by clause 9 of the Electricity Industry Participation Code Amendment (Extended Reserve) 2014.

#### **8.54M Asset owners to prepare implementation plans**

- (1) Each **asset owner** identified in an **extended reserve procurement schedule** must prepare an implementation plan specifying how the **asset owner** will implement the obligations allocated to it.
- (2) Each **asset owner** must give its implementation plan to the **system operator** for approval no later than 40 **business days** after receiving its **extended reserve procurement notice**, or by such later date as may be agreed between the **asset owner** and the **system operator**.
- (3) Each implementation plan must specify how the **asset owner** will implement the transition to complying with its obligations (if any) under its most recent **extended reserve procurement notice** from complying with its obligations (if any) under its previous **extended reserve procurement notice**.
- (4) Each implementation plan must specify 1 or more dates on which payments (if any) to the **asset owner** will commence or cease for all or part of the provision of **extended reserve** under the **asset owner's extended reserve procurement notice**.
- (5) Each date specified in an implementation plan under subclause (4) must be the date on which provision of the **extended reserve** to which the payment (if any) relates will commence or cease, as the case may be.
- (6) An **asset owner** may amend an implementation plan after giving it to the **system operator** under subclause (2) with the agreement of the **system operator**.
- (7) If the **system operator** requires that an **asset owner** make changes to an implementation plan given to the **system operator** under subclause (2), the **asset owner** must comply with the requirement.
- (8) The **system operator** must approve an implementation plan given to it by an **asset owner** under subclause (2) if the plan meets the requirements of this clause.

Clause 8.54M: inserted, on 7 August 2014, by clause 9 of the Electricity Industry Participation Code Amendment (Extended Reserve) 2014.

#### **8.54N Terms and conditions applying to the provision of extended reserve**

In the case of an **asset owner** that has been selected to be an **extended reserve provider**, the default terms and conditions in the **asset owner's extended reserve procurement notice** apply to the provision of **extended reserve** by the **asset owner** but may be amended by agreement in writing between the **asset owner** and the **system operator**.

Clause 8.54N: inserted, on 7 August 2014, by clause 9 of the Electricity Industry Participation Code Amendment (Extended Reserve) 2014.

Clause 8.54N: amended, on 19 January 2017, by clause 8 of the Electricity Industry Participation Code Amendment (Extended Reserve) 2016.

#### **8.54O System operator to publish and maintain extended reserve schedule**

- (1) The **system operator** must **publish** an **extended reserve schedule**.
- (2) Subclause (1) does not require the **system operator** to **publish** any information the **publication** of which would be likely unreasonably to prejudice the commercial position of the person who supplied or who is the subject of the information.
- (3) The **extended reserve schedule** must specify the obligations of each **asset owner** identified in the **extended reserve procurement schedule**, based on information from—
  - (a) the latest **extended reserve procurement schedule**; and
  - (b) each approved implementation plan; and
  - (c) any amendment to default terms and conditions applying to an **extended reserve provider** agreed under clause 8.54N; and
  - (d) any other information held by the **system operator** that describes the obligations of an **extended reserve provider** to provide **extended reserve**.
- (4) The **system operator** must amend the **extended reserve schedule** to reflect any change to any information described in subclause (3), so that the schedule is kept up to date.
- (5) Despite subclause (2), the **system operator** must, within 2 **business days** of **publishing** the **extended reserve schedule** under subclause (1), provide a copy of the **extended reserve schedule** to the **extended reserve manager**.

Clause 8.54O: inserted, on 7 August 2014, by clause 9 of the Electricity Industry Participation Code Amendment (Extended Reserve) 2014.

Clause 8.54O(3)(c): amended, on 19 January 2017, by clause 9(1) of the Electricity Industry Participation Code Amendment (Extended Reserve) 2016.

Clause 8.54O(5): inserted, on 19 January 2017, by clause 9(2) of the Electricity Industry Participation Code Amendment (Extended Reserve) 2016.

#### **8.54P System operator to issue statements of extended reserve obligations**

- (1) The **system operator** must issue to each **asset owner** identified in the **extended reserve schedule** a **statement of extended reserve obligations** under this clause.
- (2) Each **statement of extended reserve obligations** must specify the obligations of the **asset owner** to which it relates, as specified in the **extended reserve schedule** as at the date on which it is issued.
- (3) The **system operator** must issue a **statement of extended reserve obligations** to an **asset owner** at each of the following times:
  - (a) as soon as practicable after the **asset owner's** implementation plan is approved under clause 8.54M:

- (b) as soon as practicable after it makes an amendment to the schedule under clause 8.54O(4) that relates to the **asset owner's** obligations under this subpart:
- (c) as soon as practicable after the **system operator** becomes aware of any other information to which clause 8.54O(3)(d) applies that relates to the obligations of the **asset owner**.

Clause 8.54P: inserted, on 7 August 2014, by clause 9 of the Electricity Industry Participation Code Amendment (Extended Reserve) 2014.

#### **8.54Q System operator to give written notice of dates**

- (1) The **system operator** must give written notice to the **Authority**, the **extended reserve manager**, and the **clearing manager** of all dates on which **extended reserve providers** will provide, or cease to provide, **extended reserve**, as set out in the **extended reserve schedule**.
- (2) If an amendment to an implementation plan made under clause 8.54M(6) or (7) results in an **extended reserve provider** providing, or ceasing to provide, any **extended reserve** on a date that is different from the relevant date specified in the implementation plan, in each case the **system operator** must—
  - (a) update the **extended reserve schedule** with the new date; and
  - (b) give written notice to the **Authority**, the **extended reserve manager**, and the **clearing manager** of the new date.

Clause 8.54Q: inserted, on 7 August 2014, by clause 9 of the Electricity Industry Participation Code Amendment (Extended Reserve) 2014.

Clause 8.54Q heading: amended, on 19 December 2014, by clause 12(1) of the Electricity Industry Participation Code Amendment (Minor Code Amendments) (No 3) 2014.

Clause 8.54Q heading: amended, on 19 January 2017, by clause 10(1) of the Electricity Industry Participation Code Amendment (Extended Reserve) 2016.

Clause 8.54Q heading: amended, on 5 October 2017, by clause 105(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 8.54Q(1) and (2)(b): amended, on 19 December 2014, by clause 12(2) of the Electricity Industry Participation Code Amendment (Minor Code Amendments) (No 3) 2014.

Clause 8.54Q(1) and (2)(b): amended, on 19 January 2017, by clause 10(2) of the Electricity Industry Participation Code Amendment (Extended Reserve) 2016.

Clause 8.54Q(1) and (2)(b): amended, on 5 October 2017, by clause 105(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

#### **8.54R System operator to report to Authority**

In its monthly report given to the **Authority** under clause 3.14, the **system operator** must include information about any use of **extended reserve**.

Clause 8.54R: inserted, on 7 August 2014, by clause 9 of the Electricity Industry Participation Code Amendment (Extended Reserve) 2014.

Clause 8.54R heading: amended, on 19 December 2014, by clause 13 of the Electricity Industry Participation Code Amendment (Minor Code Amendments) (No 3) 2014.

#### **8.54S New connected asset owners and new grid owners to provide information**

- (1) The purpose of this clause is to require new **connected asset owners** and new **grid owners** to provide information so that their obligations under this subpart can be determined.
- (2) No later than 20 **business days** after a **connected asset owner** commences taking **electricity** from the **grid**, it must give the **Authority** either—

- (a) historical records of the quantity of **electricity** consumed in the **connected asset owner's network** or by the **connected asset owner**; or
  - (b) if the **Authority** advises the **connected asset owner** that it is not satisfied with the records given under paragraph (a), or if there are no such records, a bona fide **business** plan that permits a realistic estimate to be made of the amount of **electricity** to be consumed in the **connected asset owner's network** or by the **connected asset owner**.
- (3) No later than 20 **business days** after a **grid owner** starts to convey **electricity** on the **grid**, it must give the **Authority** either—
- (a) historical records of the quantity of **electricity** conveyed by the **grid owner** on the **grid**; or
  - (b) if the **Authority** advises the **grid owner** that it is not satisfied with the records given under paragraph (a), or if there are no such records, a bona fide **business** plan that permits the **Authority** to make a realistic estimate of the amount of **electricity** to be conveyed by the **grid owner** on the **grid**.

Clause 8.54S: inserted, on 7 August 2014, by clause 9 of the Electricity Industry Participation Code Amendment (Extended Reserve) 2014.

Clause 8.54S Heading: amended, on 1 February 2016, by clause 12(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

Clause 8.54S(1) & (2): amended, on 1 February 2016, by clause 12(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

#### **8.54T Assignment of extended reserve obligations**

- (1) An **extended reserve provider** that proposes to assign **assets** that it uses to provide **extended reserve** may apply to the **Authority** by notice in writing for approval to assign its obligations to provide **extended reserve** that relate to those **assets**.
- (2) The **Authority** may, on receiving an application under subclause (1),—
  - (a) approve the assignment; or
  - (b) approve the assignment with conditions; or
  - (c) decline to approve the assignment.
- (3) Before giving an **extended reserve provider** approval to assign its obligations under subclause (2), the **Authority** must consult with the **system operator**.
- (4) If the **Authority** gives an **extended reserve provider** approval to assign its obligations under subclause (2), the **Authority** must give written notice to the **system operator**.
- (5) An assignment of an **extended reserve provider's** obligations is not effective except as approved by the **Authority** under subclause (2).

Clause 8.54T: inserted, on 7 August 2014, by clause 9 of the Electricity Industry Participation Code Amendment (Extended Reserve) 2014.

Clause 8.54T(4): amended, on 19 December 2014, by clause 14 of the Electricity Industry Participation Code Amendment (Minor Code Amendments) (No 3) 2014.

Clause 8.54T(4): amended, on 5 October 2017, by clause 106 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

#### **8.54TA Extended reserve manager may rely on information provided**

For the purposes of this Code, the **extended reserve manager** may rely on the information provided to the **extended reserve manager** by an **asset owner**.

Clause 8.54TA: inserted, on 19 January 2017, by clause 11 of the Electricity Industry Participation Code Amendment (Extended Reserve) 2016.

#### **8.54TB Extended reserve manager to consider new or revised information**

- (1) If the **extended reserve manager** receives new or revised information from an **asset owner**, it must provide that information to the **Authority** if it considers that the information would change the outcome of the processes specified in clauses 8.54J, 8.54K, or 8.54L.
- (2) If the **extended reserve manager** provides the information to the **Authority** under subclause (1), the **Authority** may direct the **extended reserve manager** to undertake the **extended reserve** selection process under clause 8.54J again.

Clause 8.54TB: inserted, on 19 January 2017, by clause 11 of the Electricity Industry Participation Code Amendment (Extended Reserve) 2016.

#### **8.54TC Extended reserve manager to produce periodic performance report**

- (1) The **extended reserve manager** must—
  - (a) monitor the performance of **extended reserve**; and
  - (b) produce a periodic performance report that reports on the outcome of its monitoring of the performance of **extended reserve**.
- (2) The time period to be covered in the periodic performance report must be agreed between the **extended reserve manager** and the **Authority**.
- (3) The **extended reserve manager** must provide the periodic performance report to the **Authority** and the **system operator** no later than 30 **business days** after the end of each periodic performance reporting period.
- (4) The **extended reserve manager** must, no later than 5 **business days** after finalising the periodic performance report, **publish** a copy of the report that excludes any information that, if **published**, would be likely unreasonably to prejudice the commercial position of the person who supplied, or who is the subject of, the information.

Clause 8.54TC: inserted, on 19 January 2017, by clause 11 of the Electricity Industry Participation Code Amendment (Extended Reserve) 2016.

#### *Information required for transitional purposes*

Cross heading: inserted, on 19 January 2017, by clause 11 of the Electricity Industry Participation Code Amendment (Extended Reserve) 2016.

#### **8.54TD Information required for transition**

- (1) The **extended reserve manager** and the **system operator** may request an **asset owner**, other than a **generator** directly **connected** to the **grid**, to provide any information that the **extended reserve manager** or the **system operator** (as the case may be) considers is necessary to transition from the obligations that existed immediately prior to the Electricity Industry Participation Code Amendment (Extended Reserve) 2014 coming into effect, to the obligations specified in that Code amendment.
- (2) An **asset owner** that receives a request under subclause (1) must comply with that request.
- (3) If the **extended reserve manager** or the **system operator** (as the case may be) considers that information provided by an **asset owner** in accordance with subclause (2) is incomplete or insufficient, the **extended reserve manager** or the **system operator** (as the case may be) may require that the **asset owner** provide further information.

- (4) Each **asset owner** required to provide information under this clause must do so within the time frame specified in the request.
- (5) The **extended reserve manager** and the **system operator** may provide the information received from an **asset owner** under subclause (2) or (3) to each other.

Clause 8.54TD: inserted, on 19 January 2017, by clause 11 of the Electricity Industry Participation Code Amendment (Extended Reserve) 2016.

*Transitional provisions—extended reserve*

Cross heading: inserted, on 5 October 2017, by clause 107 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

**8.54TE Transitional provisions for extended reserve**

- (1) If the **system operator** took any action before clause 8.54D came into force that, if that clause had been in force at the time of the action, would have contributed to complying with that clause, the action is deemed to have been taken when that clause was in force.
- (2) The first implementation plan that an **asset owner** gives the **system operator** under clause 8.54M(2) must specify how the **asset owner** will implement the transition from complying with its obligations (if any) under Schedule 8.3, Technical Code B, clause 7 as it applied before clause 8.54M(2) came into force, to complying with its **extended reserve procurement notice**.
- (3) The first **statement of extended reserve obligations** that the **system operator** issues to each **asset owner** under clause 8.54P must specify the date on which it comes into force.
- (4) Despite the revocation of Schedule 8.3, **Technical Code A**, Appendix B, clause 6, and the replacement of Schedule 8.3, **Technical Code B**, clause 7 by the Electricity Industry Participation Code Amendment (Extended Reserve) 2014, each North Island **distributor** that was required to comply with those clauses before 7 August 2014 must continue to comply with those clauses as if the Electricity Industry Participation Code Amendment (Extended Reserve) 2014 had not been made until the earlier of—
  - (a) 7 August 2024; or
  - (b) the date on which the first **statement of extended reserve obligations** issued under clause 8.54P comes into force in respect of the **distributor**.
- (5) Despite the revocation of Schedule 8.3, **Technical Code A**, Appendix B, clause 7, and the replacement of Schedule 8.3, **Technical Code B**, clause 7 by the Electricity Industry Participation Code Amendment (Extended Reserve) 2014, each South Island **grid owner** that was required to comply with those clauses before 7 August 2014 must continue to comply with those clauses as if the Electricity Industry Participation Code Amendment (Extended Reserve) 2014 had not been made until the earlier of—
  - (a) 7 August 2024; or
  - (b) the date on which the first **statement of extended reserve obligations** issued under clause 8.54P comes into force in respect of the **grid owner**.
- (6) However, subclause (5) applies as if Schedule 8.3, **Technical Code B**, clause 7(6)(d)(ii) was amended from 7 May 2015 by replacing "45.5 Hertz" with "46.5 Hertz".
- (7) Clause 8.29(2) does not apply in respect of an application for a dispensation from a South Island **grid owner** until 7 August 2024.

Clause 8.54TE: inserted, on 5 October 2017, by clause 107 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

#### **8.54TF Transitional provisions for change to frequency limit in South Island**

- (1) No later than 7 February 2015, each South Island **grid owner** must prepare and give the **system operator** a plan for complying with Schedule 8.3, **Technical Code B**, clause 7(6)(d)(ii), as modified by clause 8.54T(6).
- (2) The **system operator** must approve a plan received under subclause (1) subject to any changes that the **system operator** considers necessary.
- (3) A South Island **grid owner** does not breach Schedule 8.3, **Technical Code B**, clause 7(6)(d)(ii) if the **grid owner** complies with a plan approved by the **system operator** under subclause (2).

Clause 8.54TF: inserted, on 5 October 2017, by clause 107 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### **Subpart 6—Allocating costs**

Heading: inserted, on 24 March 2015, by clause 10 of the Electricity Industry Participation Code Amendment (Extended Reserve) 2014.

#### **8.54U Contents of this subpart**

This subpart provides for the allocation of costs relating to **ancillary services** and **extended reserve**.

Clause 8.54U: inserted, on 24 March 2015, by clause 10 of the Electricity Industry Participation Code Amendment (Extended Reserve) 2014.

#### *Allocating costs for ancillary services and extended reserve*

Cross heading: amended, on 24 March 2015, by clause 11 of the Electricity Industry Participation Code Amendment (Extended Reserve) 2014.

#### **8.55 Identifying costs associated with ancillary services and extended reserve**

- (1) The **allocable costs** for each **ancillary service** are—
  - (a) the actual amounts that the **ancillary service agents** are entitled to receive for that **ancillary service** under contracts entered into by the **system operator** in implementing the **procurement plan**; plus
  - (b) the actual **administrative costs** of the **system operator** (as approved by the **Authority**) incurred in administering the **procurement plan** in respect of that **ancillary service**; less
  - (c) any readily identifiable and quantifiable costs to be paid by **asset owners** in respect of that **ancillary service** as a condition of any **dispensations** stipulated in accordance with clause 8.31(1)(a); less
  - (d) any identifiable costs to be paid by any person in respect of that **ancillary service**, as a condition of any agreement reached by the **system operator**, in accordance with clause 8.6.
- (2) The **allocable costs** for **extended reserve** are the actual amounts (if any) that **extended reserve providers** are entitled to receive for providing **extended reserve** under the current **extended reserve procurement schedule**.

Compare: Electricity Governance Rules 2003 rule 11.1 section IV part C

Clause 8.55 heading: amended, on 24 March 2015, by clause 12(1) of the Electricity Industry Participation Code Amendment (Extended Reserve) 2014.

Clause 8.55(2): inserted, on 24 March 2015, by clause 12(2) of the Electricity Industry Participation Code Amendment (Extended Reserve) 2014.

#### 8.56 Black start costs allocated to grid owner

The **allocable cost** of **black start** must be paid by the **registered participants** who are **grid owners** to the **system operator** in accordance with the process described in clause 8.68. If there are multiple **grid owners**, those costs must be allocated between them in proportion to their respective ODV valuations.

Compare: Electricity Governance Rules 2003 rule 11.2 section IV part C

#### 8.57 Over frequency reserve costs allocated to HVDC owner

The **allocable cost** of **over frequency reserve** must be paid by the **HVDC owner** to the **system operator** in accordance with the process described in clause 8.68.

Compare: Electricity Governance Rules 2003 rule 11.3 section IV part C

#### 8.58 Frequency keeping costs are allocated to purchasers

The **allocable cost** of **frequency keeping** must be paid by **purchasers** to the **system operator** in accordance with the process in clause 8.68. Those costs must be calculated in accordance with the following formula:

$$\text{Share}_{\text{PURx}} = \text{Fc} * \frac{\max(0, \sum_t (\text{Offtake}_{\text{PURxt}} - E_{\text{PURxt}}^{\text{FK}}))}{\sum_x \max(0, \sum_t (\text{Offtake}_{\text{PURxt}} - E_{\text{PURxt}}^{\text{FK}}))}$$

where

$\text{Share}_{\text{PURx}}$  is **purchaser x's share of allocable cost** in relation to **frequency keeping**

$\text{Fc}$  is the **allocable cost** of **frequency keeping** services in the **billing period**

$\text{Offtake}_{\text{PURxt}}$  is the total **reconciled quantity** in **kWh** for **purchaser x** across all **grid exit points** in **trading period t** in the **billing period**

$E_{\text{PURxt}}^{\text{FK}}$  is the quantity of any **frequency keeping** provided under any alternative **ancillary service arrangement** for **frequency keeping** authorised by the **system operator** for **purchaser x** in **trading period t**.

Compare: Electricity Governance Rules 2003 rule 11.4 section IV part C

#### 8.59 Availability costs allocated to generators and HVDC owner

The **availability costs** in a **billing period** must be allocated separately to persons in the North Island and South Island in accordance with the following formula:

$$\text{Share}_t = \frac{\text{Ac}_t * m_t}{M_t}$$

where



---

$Share_t$	is the <b>availability cost</b> allocated to a <b>generator</b> who owns <b>generating unit</b> x or to the <b>HVDC link</b> for <b>trading period</b> t for the North Island or South Island as appropriate
$Ac_t$	is the <b>availability cost</b> for the North Island or South Island as appropriate incurred in respect of <b>trading period</b> t
$m_t$	$\begin{cases} \text{is } \max(0, INJ_{GENxt} - (h * INJ_D) - E_{GENxt}^{IR}) = m_{xt} \text{ for any } \mathbf{generating\ unit} \\ \text{is } \max(0, HVDC_{Riskt} - (h * INJ_D) - E_{HVDCt}^{IR}) = m_{ht} \text{ for the } \mathbf{HVDC\ link} \end{cases}$
$M_t$	is $\sum_x m_{xt} + m_{ht}$
$h$	is 0.5 MWh/MW
$INJ_{GENxt}$	is the <b>electricity injected</b> (expressed in MWh) by <b>generating unit</b> x in <b>trading period</b> t into the North Island or South Island as appropriate
$E_{GENxt}^{IR}$	is the quantity of any <b>instantaneous reserve</b> provided under any <b>alternative ancillary service arrangements</b> for <b>instantaneous reserve</b> authorised by the <b>system operator</b> for <b>generating unit</b> x in <b>trading period</b> t
$HVDC_{Riskt}$	is the <b>at risk HVDC transfer</b> (expressed in MWh) in <b>trading period</b> t into the North Island or South Island as appropriate
$E_{HVDCt}^{IR}$	is the quantity of any <b>instantaneous reserve</b> provided under any <b>alternative ancillary service arrangement</b> for <b>instantaneous reserve</b> authorised by the <b>system operator</b> for <b>at risk HVDC transfer</b> in <b>trading period</b> t
$INJ_D$	is 60 MW.

Compare: Electricity Governance Rules 2003 rule 11.5.1 section IV part C

## 8.60 System operator must investigate causer of under-frequency event

- (1) The **system operator** must promptly notify the **Authority**, every **generator**, **grid owner** and any other **participant** substantially affected by an **under-frequency event**, that an **under-frequency event** has occurred.
- (2) The **system operator** may, by notice in writing to a **participant**, require a **participant** to provide information required by the **system operator** for the purposes of this clause.
- (3) A notice given under subclause (2) must specify the information required by the **system operator** and the date by which the information must be provided (which must not be earlier than 20 **business days** after the notice is given).
- (4) A **participant** who has received a notice under subclause (2) must provide the information required by the **system operator** by the date specified by the **system operator** in the notice.
- (5) Within 40 **business days** of receiving the information, or such longer period as may be agreed by the **Authority**, the **system operator** must provide a report to the **Authority** that includes the following:

- (a) whether, in the **system operator's** view, the **under-frequency event** was caused by a **generator** or **grid owner**, and if so, the identity of the **causer**;
- (b) the reasons for the **system operator's** view;
- (c) all of the information the **system operator** considered in reaching its view.

Compare: Electricity Governance Rules 2003 rule 11.5.1A section IV part C

Clause 8.60 Heading: amended, on 19 May 2016, by clause 25(1) of the Electricity Industry Participation Code Amendment (System Operator and Alignment with Statutory Objective) 2016.

Clause 8.60(1): amended, on 19 May 2016, by clause 25(2) of the Electricity Industry Participation Code Amendment (System Operator and Alignment with Statutory Objective) 2016.

Clause 8.60(2): amended, on 19 May 2016, by clause 25(3)(a), (b) and (c) of the Electricity Industry Participation Code Amendment (System Operator and Alignment with Statutory Objective) 2016.

Clause 8.60(3): amended, on 19 May 2016, by clause 25(4)(a) and (b) of the Electricity Industry Participation Code Amendment (System Operator and Alignment with Statutory Objective) 2016.

Clause 8.60(5): inserted, on 19 May 2016, by clause 25(5) of the Electricity Industry Participation Code Amendment (System Operator and Alignment with Statutory Objective) 2016.

#### **8.61 Authority to determine causer of under-frequency event**

- (1) The **Authority** must determine whether an **under-frequency event** has been caused by a **generator** or **grid owner** and, if so, the identity of the **causer**.
- (2) The **Authority** must **publish** a draft determination that states whether the **under-frequency event** was caused by a **generator** or **grid owner** and, if so, the identity of the **causer**.
- (3) The **Authority** must give reasons for its findings in the draft determination.
- (4) The **Authority** must consult every **generator**, **grid owner** and other **participant** substantially affected by an **under-frequency event** in relation to the draft determination.
- (5) When the **Authority publishes** the draft determination under subclause (2), the **Authority** must give notice to **generators**, **grid owners**, and other **participants** substantially affected by the **under-frequency event** of the closing date for submissions on the draft determination.
- (6) The date referred to in subclause (5) must be no earlier than 10 **business days** after the date of **publication** of the draft determination.
- (7) The **Authority** must **publish** submissions received under subclause (4) unless there is good reason for withholding information in a submission.
- (8) For the purposes of subclause (7), good reason for withholding information exists if there is good reason for withholding the information under the Official Information Act 1982.
- (9) Following the consultation under subclause (4), the **Authority** must **publish** a final determination.

Compare: Electricity Governance Rules 2003 rule 11.5.1B section IV part C

Clause 8.61 Heading: amended, on 19 May 2016, by clause 26(1) of the Electricity Industry Participation Code Amendment (System Operator and Alignment with Statutory Objective) 2016.

Clause 8.61: amended, on 19 May 2016, by clause 26(2) of the Electricity Industry Participation Code Amendment (System Operator and Alignment with Statutory Objective) 2016.

Clause 8.61(1): amended, on 19 May 2016, by clause 26(3) of the Electricity Industry Participation Code Amendment (System Operator and Alignment with Statutory Objective) 2016.

Clause 8.61(5): amended, on 19 May 2016, by clause 26(4)(a) and (b) of the Electricity Industry Participation Code Amendment (System Operator and Alignment with Statutory Objective) 2016.

### 8.62 Disputes regarding Authority determinations

- (1) A **participant** who is substantially affected by a determination may dispute the determination by referring the matter to the **Rulings Panel**.
- (2) A dispute is commenced by giving written notice to the **Rulings Panel** specifying the grounds of the dispute.
- (3) A notice under subclause (2) must be given within 10 **business days** after the determination is **published**.
- (4) The **Authority's** determination is suspended if a dispute is referred to the **Rulings Panel** within that time.
- (5) If a dispute is not referred to the **Rulings Panel** within that time, the determination is final.
- (6) If a dispute is referred to the **Rulings Panel**, the **Authority** must provide the **Rulings Panel** with all information considered by the **Authority** in making the determination.

Compare: Electricity Governance Rules 2003 rule 11.5.1C section IV part C

Clause 8.62 Heading: amended, on 19 May 2016, by clause 27(1) of the Electricity Industry Participation Code Amendment (System Operator and Alignment with Statutory Objective) 2016.

Clause 8.62(1): amended, on 19 May 2016, by clause 27(2) of the Electricity Industry Participation Code Amendment (System Operator and Alignment with Statutory Objective) 2016.

Clause 8.62(3): amended, on 5 October 2017, by clause 108 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 8.62 (4): amended, on 19 May 2016, by clause 27(3) of the Electricity Industry Participation Code Amendment (System Operator and Alignment with Statutory Objective) 2016.

Clause 8.62(6): amended, on 19 May 2016, by clause 27(4) of the Electricity Industry Participation Code Amendment (System Operator and Alignment with Statutory Objective) 2016.

### 8.63 Decision of the Rulings Panel

- (1) The **Rulings Panel** may—
  - (a) confirm the determination; or
  - (b) amend the determination; or
  - (c) substitute its own determination; or
  - (d) refer the determination back to the **Authority** with directions as to the particular matters that require reconsideration or amendment.
- (2) The **Authority's** determination has effect as confirmed, amended, or substituted by the **Rulings Panel** from the date of the **Rulings Panel's** decision.
- (3) The **Rulings Panel** must give a copy of its decision to the **Authority** as soon as reasonably practicable.
- (4) The **Authority** must **publish** the **Rulings Panel's** decision as soon as reasonably practicable.
- (5) If the **Rulings Panel** refers the matter back to the **Authority**, the **Authority** must have regard to the **Rulings Panel's** directions under subclause (1)(d).

Compare: Electricity Governance Rules 2003 rule 11.5.1D section IV part C

Clause 8.63: amended, on 19 May 2016, by clause 28(1) of the Electricity Industry Participation Code Amendment (System Operator and Alignment with Statutory Objective) 2016.

Clause 8.63(3): amended, on 19 May 2016, by clause 28(2) of the Electricity Industry Participation Code Amendment (System Operator and Alignment with Statutory Objective) 2016.

### 8.64 Event costs allocated to event causers

The **event charge** payable by the **causer** of an **under-frequency event** (referred to as “Event e” below) must be calculated in accordance with the following formula:

$$EC = ECR * (\sum_y (INT_{ye} \text{ for all } y) - INJ_D)$$

where

EC is the **event charge** payable by the **causer**

ECR is \$1,250 per **MW**

INJ<sub>D</sub> is 60 **MW**

INT<sub>ye</sub> is the electric power (expressed in **MW**) lost at point y by reason of Event e (being the net reduction in the **injection of electricity** (expressed in **MW**) experienced at point y by reason of Event e) excluding any loss at point y by reason of secondary Event e

y is a **point of connection** or the **HVDC injection point** at which the **injection of electricity** was interrupted or reduced by reason of Event e.

Compare: Electricity Governance Rules 2003 rule 11.5.2 section IV part C  
Clause 8.64: amended, on 21 September 2012, by clause 10 of the Electricity Industry Participation (Minor Amendments) Code Amendment 2012.

### 8.65 Rebates paid for under-frequency events

An **event charge** that has been paid for an **under-frequency event** (referred to as “Event e”) under clause 8.64 must be rebated in accordance with the following formula to persons who are allocated **availability costs** in accordance with clause 8.59:

$$\text{Rebate}_{xe} = EC_e * Z_{xe}/Z_{tote}$$

where

Rebate<sub>xe</sub> is the rebate of the **event charge** paid for Event e to person “x”, who has been allocated **availability costs** in accordance with clause 8.59

EC<sub>e</sub> is the **event charge** paid for Event e

Z<sub>xe</sub> is the sum of all **availability costs** paid by x during the **billing period** in which Event e occurred and the 2 preceding **billing periods**

Z<sub>tote</sub> is the sum of all **availability costs** paid for all **trading periods** during the **billing period** in which Event e occurred and the two preceding **billing periods**.

Compare: Electricity Governance Rules 2003 rule 11.5.3 section IV part C

### 8.66 Payments and rebates

All costs calculated in accordance with clauses 8.59 and 8.64 are payable by the relevant **participants** to the **system operator**, and all **event charge** rebates calculated in accordance with clause 8.65 are payable by the **system operator** to the relevant **participants**, in accordance with clause 8.69.

Compare: Electricity Governance Rules 2003 rule 11.5.4 section IV part C

**8.67 Voltage support costs allocated in 3 parts – nominated peak, monthly peak and residual charges**

- (1) Each **connected asset owner** must pay the **allocable cost** of **voltage support** in each **zone** to the **system operator** in accordance with clause 8.68. The costs must be calculated in accordance with this clause.
- (2) Each **connected asset owner** must pay a nominated peak kvar charge calculated in accordance with the following formula:

$$\text{NomCharge}_{xz} = \text{PeakRate}_z * \sum_j Q_{xjz}$$

where

$\text{NomCharge}_{xz}$  is the total nominated peak charges for **connected asset owner x** in **zone z**

$\text{Peak Rate}_z$  is the fixed \$/kvar set annually in advance by **system operator** for **zone z**

$Q_{xjz}$  is  $\text{Nom Peak}_{\text{LINES}_{xjz}}$ , which is the peak demand in kvar (in **zone z**) nominated to the **system operator** in advance of, and having effect from, 1 March each year by **connected asset owner x** at its **connected asset owner kvar reference node j**

$\sum_j$  is the sum across all **connected asset owner kvar reference nodes j** of **connected asset owner x** in **zone z**

- (3) Each **connected asset owner** must pay a monthly peak penalty charge calculated in accordance with the following formula:

$$\text{PeakPenaltyCharge}_{\text{LINE}_{xz}} = \text{PenaltyRate}_z * \sum_j \text{PenaltyQuantity}_{\text{LINE}_{xjz}}$$

where

$\text{PeakPenaltyCharge}_{\text{LINE}_{xz}}$  is the total peak penalty charges for **connected asset owner x** across all **connected asset owner kvar reference nodes j** for **connected asset owner x** in **zone z**

$\text{PenaltyRate}_z$  is the fixed \$/kvar penalty charge for “kvar above nominated kvar” set annually in advance by the **system operator** in **zone z**

$\sum_j$  is the sum across all **connected asset owner kvar reference nodes j** of **connected asset owner x** in **zone z**

$\text{PenaltyQuantity}_{\text{LINE}_{xjz}}$  is the “kvar above nominated kvar” quantity for **connected asset owner x** at its **connected asset owner kvar reference node j** in **zone z**

- (4) For the purpose of calculating the “kvar above nominated kvar” quantity, the kvar taken by the **connected asset owner**—
- (a) includes only kvar demands on weekdays (Monday to Friday but excluding **national holidays**) between the hours of 0700 to 2100 inclusive; and
  - (b) includes no more than 2 kvar peaks in any 1 day; and
  - (c) is the average of the 6 largest kvar peaks for the **connected asset owner** in each month measured at the **connected asset owner kvar reference node j** within the **zone z**,—
- and “kvar above nominated kvar” is the difference between the kvar taken by the **connected asset owners** as determined in accordance with paragraphs (a) to (c) and the nominated kvar specified by the **connected asset owner**.
- (5) Each **connected asset owner** must pay a residual charge or receive a residual payment calculated in accordance with the following formulae:

$$\text{Residual}_{\text{ALL}z} = \text{Vcost}_z - \text{Nom Charge}_{\text{ALL}z} - \text{PeakPenaltyCharge}_{\text{ALL}z}$$

$$\text{Residual}_{\text{LINEall}z} = \text{Residual}_{\text{ALL}z} * (\sum_{xj} \text{NomPeak}_{\text{LINE}xjz} / \sum_{xj} Q_{xjz})$$

$$\text{Residual}_{\text{LINE}xz} = \text{Residual}_{\text{LINEall}z} * (\text{BillingPeriodOfftake}_{\text{LINE}xz} / \text{BillingPeriodOfftake}_{\text{ALL}z})$$

where

$\text{Vcost}_z$  is the total **allocable costs** for **voltage support** in **zone z** in the **billing period**

$\text{Nom Charge}_{\text{ALL}z}$  is the sum of all  $\text{Nom Charge}_{xz}$  for **zone z**

$\text{PeakPenaltyCharge}_{\text{ALL}z}$  is the sum of all **connected asset owners’**  $\text{PeakPenaltyCharge}_{\text{LINE}xz}$  for **zone z**

$\text{Residual}_{\text{ALL}z}$  is the total residual to be recovered from or paid to **connected asset owners** in **zone z**

$\text{Residual}_{\text{LINEall}z}$  is the portion of  $\text{Residual}_{\text{ALL}z}$  to be recovered from or paid to **connected asset owners** in **zone z**

$\text{Residual}_{\text{LINE}xz}$  is the portion of  $\text{Residual}_{\text{LINEall}z}$  to be recovered from or paid to **connected asset owner x** in **zone z**

$\text{BillingPeriodOfftake}_{\text{LINE}xz}$  is the sum of **metering information** for **connected asset owner x** across all **connected asset owner kvar reference nodes** in **zone z** for the **billing period** for all **trading periods**

$\text{BillingPeriodOfftake}_{\text{ALL}z}$  is the sum of **metering information** for all **connected asset owners** across all **connected asset owner kvar reference**

**nodes in zone z for the billing period for all trading periods**

$\Sigma_{xj}$  is the sum across all **connected asset owner kvar reference nodes j** for all **connected asset owners x** in **zone z**

$\Sigma_j$  is the sum across all **connected asset owner kvar reference nodes j** of **connected asset owner x** in **zone z**

$Q_{xjz}$  is Nom PeakLINES $_{xjz}$ , which is the peak demand in kvar (in **zone z**) nominated to the **system operator** in advance of, and having effect from, 1 March each year by **connected asset owner x** at its **connected asset owner kvar reference node j**

- (6) For the purposes of this clause, a **connected asset owner** does not include a **generator** who is supplied **electricity** for consumption at a **point of connection** with the **grid**.

Compare: Electricity Governance Rules 2003 rule 11.6 section IV part C

Clause 8.67: amended, on 1 February 2016, by clause 13 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

Clause 8.67(5): amended, on 15 May 2014, by clause 10 of the Electricity Industry Participation (Minor Code Amendments) Code Amendment 2014.

#### 8.67A Extended reserve costs allocated to connected asset owners

If there are **allocable costs** for **extended reserve** in a **billing period**, each **connected asset owner**, other than a **generator** that is directly **connected** to the **grid**, must pay a charge for **extended reserve** for the **billing period** in accordance with the following formula:

$$\text{Extended reserve charge}_D = \left( \text{TERAC}_{NI} \times \frac{L_{NI, D}}{L_{NI, TOT}} \right) + \left( \text{TERAC}_{SI} \times \frac{L_{SI, D}}{L_{SI, TOT}} \right)$$

where

Extended reserve charge $_D$  is the **extended reserve** charge owing by the **connected asset owner** for the **billing period**

TERAC $_{NI}$  is the sum of all payments for **extended reserve** provided in the North Island for the **billing period**

L $_{NI, D}$  is the **connected asset owner's** total **offtake** (in **MWh**) at **grid exit points** in the North Island in the **billing period**

L $_{NI, TOT}$  is the total **offtake** (in **MWh**) by all **connected asset owners** at **grid exit points** in the North Island in the **billing period**

TERAC $_{SI}$  is the sum of all payments for **extended reserve** provided in the South Island for the **billing period**

$L_{SI, D}$  is the **connected asset owner's total offtake** (in **MWh**) at **grid exit points** in the South Island in the **billing period**

$L_{SI, TOT}$  is the total **offtake** (in **MWh**) by all **connected asset owners** at **grid exit points** in the South Island in the **billing period**.

Clause 8.67A: inserted, on 24 March 2015, by clause 13 of the Electricity Industry Participation Code Amendment (Extended Reserve) 2014.

Clause 8.67A Heading: amended, on 1 February 2016, by clause 14(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

Clause 8.67A: amended, on 1 February 2016, by clause 14(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

Clause 8.67A: amended, on 19 January 2017, by clause 12 of the Electricity Industry Participation Code Amendment (Extended Reserve) 2016.

#### **8.68 Clearing manager to determine amounts owing**

- (1) The **clearing manager** must determine the amount owing to the **system operator** by each **grid owner, purchaser, generator** and **connected asset owner** for **ancillary services** under clauses 8.55 to 8.67. On behalf of the **system operator**, the **clearing manager** must collect those amounts, and any amounts advised by the **system operator** as owing to it under clauses 8.6 and 8.31(1)(a), by including the relevant amounts in the amounts advised by the **clearing manager** as owing under Part 14.
- (2) To enable the **clearing manager** to determine those amounts, the **system operator** must provide to the **clearing manager** the total **allocable cost** for each **ancillary service** and any additional information required to carry out the calculations under clauses 8.55 to 8.67 that is not otherwise provided by the **reconciliation manager** or the **pricing manager** under Part 13.
- (3) The **clearing manager** must determine the amount owing by each **connected asset owner**, other than a **generator** that is directly **connected** to the **grid**, for **extended reserve** in accordance with clause 8.67A.
- (4) The **clearing manager** must determine the amount owing to each **extended reserve provider** for the provision of **extended reserve** in accordance with—
  - (a) the **extended reserve schedule**; and
  - (b) any relevant notice received from the **system operator** under clause 8.54Q(2).
- (5) The **clearing manager** must collect the amounts determined under subclause (3) and pay the amounts determined under subclause (4) by including the relevant amounts in the invoices issued by the **clearing manager** under Part 14.
- (6) All amounts owing under this clause are subject to the priority order of payments set out in clause 14.56.

Compare: Electricity Governance Rules 2003 rule 11.7 section IV part C

Clause 8.68 heading: amended, on 24 March 2015, by clause 7(1) of the Electricity Industry Participation (Settlement and Prudential Security) Code Amendment 2013.

Clause 8.68(1): amended, on 24 March 2015, by clause 7(2) of the Electricity Industry Participation (Settlement and Prudential Security) Code Amendment 2013.

Clause 8.68(1): amended, on 24 March 2015, by clause 14(1) of the Electricity Industry Participation Code Amendment (Extended Reserve) 2014.

Clause 8.68(1): amended, on 1 February 2016, by clause 15 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.



Clause 8.68(3), (4), (5) and (6): inserted, on 24 March 2015, by clause 14(2) of the Electricity Industry Participation Code Amendment (Extended Reserve) 2014.

Clause 8.68(3): amended, on 1 February 2016, by clause 15 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

Clause 8.68(3): amended, on 19 January 2017, by clause 13 of the Electricity Industry Participation Code Amendment (Extended Reserve) 2016.

### **8.69 Clearing manager to determine wash up amounts payable and receivable**

- (1) The **clearing manager** must determine the following amounts owing as a result of **washups** under subpart 6 of Part 14:
  - (a) the amount owing to the **system operator** by each **grid owner, purchaser, generator** and **connected asset owner** for **ancillary services** under clauses 8.55 to 8.67:
  - (b) the amount owing to each **grid owner, purchaser, generator** and **connected asset owner** by the **system operator** for **ancillary services** under clauses 8.55 to 8.67:
  - (c) the amount owing by each **distributor** for **extended reserve** under clause 8.67A:
  - (d) the amount owing to each **extended reserve provider** for **extended reserve** under clause 8.68.
- (2) On behalf of the **system operator** the **clearing manager** must collect or pay the amounts owing for **ancillary services**, and any amounts advised by the **system operator** as payable to it under clauses 8.6 and 8.31(1)(a) by including the relevant amounts advised by the **clearing manager** as owing under Part 14.
- (3) To enable the **clearing manager** to determine the amounts payable for **ancillary services**, the **system operator** must provide to the **clearing manager** the **allocable cost** for each **ancillary service** and any additional information required to carry out the recalculations under clauses 8.55 to 8.67 that is not otherwise provided by the **reconciliation manager** or the **pricing manager** under Part 13.
- (4) All amounts owing under this clause are subject to the priority order of payments set out in clause 14.56.

Compare: Electricity Governance Rules 2003 rule 11.8 section IV part C

Clause 8.69 heading: amended, on 24 March 2015, by clause 8(1) of the Electricity Industry Participation (Settlement and Prudential Security) Code Amendment 2013.

Clause 8.69: substituted, on 24 March 2015, by clause 15 of the Electricity Industry Participation Code Amendment (Extended Reserve) 2014.

Clause 8.69(1): amended, on 24 March 2015, by clause 8(2) of the Electricity Industry Participation (Settlement and Prudential Security) Code Amendment 2013.

Clause 8.69(1)(a) & (b): amended, on 1 February 2016, by clause 16(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

Clause 8.69(4): amended, on 1 February 2016, by clause 16(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

### **8.70 System operator pays ancillary service agents**

- (1) The **system operator** must pay each **ancillary service agent** the amounts that each **ancillary service agent** is entitled to receive for **ancillary services** under contracts entered into by the **system operator** in implementing the **procurement plan**.
- (2) The **system operator** must use the **clearing manager** as its agent to pay **participants**.

Compare: Electricity Governance Rules 2003 rule 11.9 section IV part C

## Schedule 8.1

cls 8.29 and 8.33

### Approval of equivalence arrangement or grant of dispensation

#### 1 Contents of this Schedule

This Schedule sets out the process for an **asset owner** who wishes to apply for—

- (a) approval of an **equivalence arrangement**; or
- (b) the grant of a **dispensation**.

Compare: Electricity Governance Rules 2003 clause 1 schedule C1 part C

#### 2 Application and supporting information

Each application for an **equivalence arrangement** or a **dispensation** must—

- (a) be in writing; and
- (b) specify the **AOPO** or **technical code** from which approval for an **equivalence arrangement** or the grant of **dispensation** is sought; and
- (c) provide supporting information for the application, including sufficient information about the actual capability of the **asset** or configuration of **assets**; and
- (d) describe any remedial action planned to return the **asset** or configuration of **assets** to a compliant state; and
- (e) specify the required term of the **equivalence arrangement** or **dispensation**; and
- (f) indicate any information for which confidentiality is sought on the grounds that it would, if disclosed, unreasonably prejudice the commercial position of the person who supplied the information (or of the person who is the subject of that information), or would disclose a trade secret, or on the ground that it is necessary to protect information which is itself subject to an obligation of confidence, and the duration of the requirement for confidentiality.

Compare: Electricity Governance Rules 2003 clause 2 schedule C1 part C

#### 3 System operator obligations on receipt of application

No later than **5 business days** after receiving the application made in accordance with clause 2, the **system operator** must—

- (a) record the name of the **asset owner** making the application, the date and the subject matter of the application in the **system operator register**; and
- (b) give written notice to the **Authority** of the application; and
- (c) provide the **asset owner** with an estimate of the likely time that it will take to consider the application and the likely costs associated with processing the application.

Compare: Electricity Governance Rules 2003 clause 3 schedule C1 part C

Clause 3(b): amended, on 5 October 2017, by clause 109 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

#### 4 Rights and obligations while processing applications

- (1) The **system operator** must use reasonable endeavours to process an application for approval of an **equivalence arrangement** or grant of a **dispensation** within the timeframe and costs estimated in accordance with clause 3(c).

- (2) If the **system operator** cannot process the application within the timeframe or costs originally estimated, it must give notice of this fact and its amended estimates of timeframe or costs to the **asset owner**, and clause 5 applies in respect of those costs.
- (3) The **system operator** may require the provision of additional information at any stage during the application process and, provided the **system operator's** requirements are reasonable, that information must be provided by the **asset owner** if the application is to be processed.
- (4) The **asset owner** may withdraw an application at any time, provided that it meets all costs incurred by the **system operator** as at the date of the withdrawal of the application. If any costs have been paid in advance, those monies outstanding to the credit of the **asset owner** must immediately be returned to the **asset owner**.
- (5) An applicant may amend an application being considered by the **system operator** at any time. All amendments must be in writing and submitted to the **system operator** and take effect from the date of receipt.

Compare: Electricity Governance Rules 2003 clause 4 schedule C1 part C

## 5 Obligation of asset owner to pay costs

- (1) The **system operator** and the **asset owner** must agree on the costs involved in processing an application for approval of an **equivalence arrangement** or grant of a **dispensation** and the method for payment to the **system operator** by the **asset owner** of those costs—
  - (a) before the **system operator** proceeds with the application; and
  - (b) at any time during the processing of the application when either—
    - (i) the **system operator** gives written notice to the **asset owner** that it considers the estimate of the likely timeframe involved in processing the application will exceed the estimate given under clause 3(c) or any revised estimate given under clause 4; or
    - (ii) an **asset owner** varies its application and the **system operator**, acting reasonably, considers this variation will change the cost of processing the application.
- (2) The **system operator** is entitled not to proceed until agreement on costs is reached at any of these stages.

Compare: Electricity Governance Rules 2003 clause 5 schedule C1 part C

Clause 5(1)(b)(i): amended, on 5 October 2017, by clause 110 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

## 6 Special provisions relating to the grant of dispensations

- (1) Before granting a **dispensation**, the **system operator** must issue a draft decision on the application. The draft decision must be published on the **system operator register** and must include—
  - (a) an assessment by the **system operator** of the technical issues; and
  - (b) advice from the **system operator** about any changes required to **ancillary services** procurement as a result of the proposed **dispensation**.
- (2) If changes are required to the **procurement plan**, the draft decision must be conditional on the **procurement plan** being amended appropriately in accordance with clause 8.44.

- (3) A **participant** may make a submission to the **system operator** on the application that resulted in the publication of the draft decision no later than 10 **business days** after the draft decision is recorded on the **system operator register**.
- (4) The **system operator** must—
  - (a) consider all submissions; and
  - (b) give written notice of its decision on an application to the **participant** who made the application.

Compare: Electricity Governance Rules 2003 clause 6 schedule C1 part C

Clause 6(4): replaced, on 5 October 2017, by clause 111 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

## **7 Decision of the system operator**

The **system operator** must advise all applicants for approval of an **equivalence arrangement** or grant of a **dispensation** of—

- (a) its decision as soon as it is made in writing; and
- (b) the reason for its decision.

Compare: Electricity Governance Rules 2003 clause 7 schedule C1 part C

## **8 Decisions must be recorded**

- (1) An approval of an **equivalence arrangement** or grant of a **dispensation** by the **system operator** must be recorded in the **system operator register**.
- (2) The approval must state the name of the **asset owner**, the date, duration and nature of the **equivalence arrangement** or **dispensation**, including any conditions.
- (3) On request, and at the cost of the person making the request, the **system operator** must supply all background information in relation to its decision to that person, other than information designated as commercially sensitive by the relevant **asset owner**.

Compare: Electricity Governance Rules 2003 clause 8 schedule C1 part C

## Schedule 8.2

cls 8.48 and 8.50

### Approval of alternative ancillary service arrangement

#### 1 Process for approval of alternative ancillary service arrangement

- (1) An application for an **alternative ancillary service arrangement** must—
  - (a) be in writing; and
  - (b) specify the **ancillary service** for which approval for an **alternative ancillary service arrangement** is sought; and
  - (c) provide supporting information for the application, including sufficient information about the actual capability of the **asset** or configuration of **assets**; and
  - (d) describe any remedial action planned to return the **asset** or configuration of **assets** to a compliant state; and
  - (e) specify the required term of the **alternative ancillary service arrangement**; and
  - (f) indicate any information for which confidentiality is sought on the grounds that it would, if disclosed, unreasonably prejudice the commercial position of the person who supplied the information (or the person who is the subject of that information), or would disclose a trade secret, or on the ground that it is necessary to protect information which is itself subject to an obligation of confidence.
- (2) No later than 5 **business days** after receipt of the application under subclause (1), the **system operator** must—
  - (a) record the name of the **asset owner** making the application, the date and the subject matter of the application in the **system operator register**; and
  - (b) give written notice to the **Authority** of the application; and
  - (c) provide the **asset owner** with an estimate of the likely time it will take to consider the application and the likely costs associated with processing the application.
- (3) The **system operator** and the **asset owner** must agree on the costs involved in processing an application for authorisation of an **alternative ancillary service arrangement** and the method for payment to the **system operator** by the **asset owner** of those costs—
  - (a) before the **system operator** proceeds with the application; and
  - (b) at any time during the processing of the application, the **system operator** is entitled not to proceed until agreement is reached if either—
    - (i) the **system operator** gives written notice to the **asset owner** that it considers the estimate of the likely timeframe and costs involved in processing the application will exceed the estimate given under subclause (2)(c); or
    - (ii) an **asset owner** varies its application and the **system operator**, acting reasonably, considers this variation will change the costs in processing the application.

Compare: Electricity Governance Rules 2003 clauses 1.1 to 1.3 schedule C2 part C  
Clause 1(2)(b) and (3)(b)(i): amended, on 5 October 2017, by clause 112(1) and (2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

## 2 Obligations in processing applications

- (1) The **system operator** must use reasonable endeavours to process an application for authorisation of an **alternative ancillary service arrangement** within the timeframe and costs estimated in accordance with clause 1(2)(c).
- (2) If the **system operator** cannot process an application within the timeframe and costs originally estimated, it must give notice of this fact and its amended estimates of timeframe and costs to the **asset owner** and the provisions of clause 1(3) must apply in respect of those costs.
- (3) The **system operator** may require the provision of additional information at any stage during the application process and, provided the **system operator's** requirements are reasonable, that information must be provided by the **asset owner** if the application is to be processed.
- (4) The **asset owner** may withdraw an application at any time provided that it meets all costs incurred by the **system operator** as at the date of withdrawal of the application. If those costs have been paid in advance, those monies outstanding to the credit of the **asset owner** must immediately be returned to the **asset owner**.
- (5) An applicant may amend an application being considered by the **system operator** at any time. All amendments must be in writing and submitted to the **system operator** and must take effect from the date of receipt.

Compare: Electricity Governance Rules 2003 clause 1.4 schedule C2 part C

## 3 Decision of the system operator

The **system operator** must advise all applicants for authorisation of an **alternative ancillary service arrangement** of its decision as soon as it is made in writing, and advise such applicants of the reason for that decision.

Compare: Electricity Governance Rules 2003 clause 1.5 schedule C2 part C

## 4 Decisions must be recorded

An authorisation of an **alternative ancillary service arrangement** by the **system operator** must be recorded in the **system operator register**. Except for information that the **system operator** agreed was commercially sensitive, the authorisation must state the name of the **asset owner**, the date, duration and nature of the **alternative ancillary service arrangement**, including any conditions. On request, and at the cost of the person making the request, the **system operator** must supply all background information in relation to its decision to that person, other than information designated as commercially sensitive by the relevant **asset owner**.

Compare: Electricity Governance Rules 2003 clause 1.6 schedule C2 part C

## Schedule 8.3 Technical codes

cl 1.1

### *Technical Code A – Assets*

#### 1 Purpose

The purpose of this **technical code** is to define obligations for **asset owners** and technical standards for **assets** that are supportive of, or more detailed than, those set out in subpart 2 of Part 8, in order to enable the **system operator** to plan to comply, and to comply, with the **principal performance obligations**.

Compare: Electricity Governance Rules 2003 clause 1 technical code A schedule C3 part C

#### 2 General requirements

- (1) Each **asset owner** must ensure that—
  - (a) its **assets** at **grid exit points** and at **grid injection points**, and, in the case of connected **asset owners**, the **assets** of any **embedded generator** connected to it, are identified and referred to by a **system number**; and
  - (b) its **assets**, both in the manner in which they are designed and operated, are capable of being operated, and operate, within the limits stated in the **asset capability statement** provided by the **asset owner** for that **asset**; and
  - (c) it meets any other reasonable requirements of the **system operator**, identified during planning studies, which are required for the **system operator** to plan to comply, or to comply, with its **principal performance obligations**.
- (2) Each **asset owner** must provide the **system operator** with an **asset capability statement**, and any other information reasonably required by the **system operator**, to allow the **system operator** to assess compliance of its **asset** or any configuration of **assets** with the requirements of the **asset owner performance obligations** and **technical codes** at each of the following times:
  - (a) before the completion of planning for the construction of that **asset** or configuration of **assets**;
  - (b) at, or before, the completion of construction but before the **commissioning** of that **asset** or configuration of **assets**, except that the **asset owner** must put in place a **commissioning** plan in accordance with subclauses (6) to (8) to minimise the impact of **commissioning** tests on the **system operator's** ability to comply with its **principal performance obligations**, and adhere to this plan during **commissioning**, unless otherwise agreed to by the **system operator**.
- (3) On, or before, completion of **commissioning** of an **asset** or configuration of **assets**, the **asset owner** must obtain a final assessment in writing from the **system operator** that the **asset** or configuration of **assets** meets the requirements of the **asset owner performance obligations** and **technical codes**. This final assessment must be based on the information supplied by the **asset owner** and, if necessary, the result of **system tests** at **commissioning**.
- (4) The **system operator** must give the assessment referred to in subclause (2)(b) within a

reasonable time frame of the request and supply the **asset owner** with all information that supports its assessment. Any permission granted by the **system operator** to an **asset owner** to conduct **commissioning** of any **asset** or configuration of **assets** must permit connection of the **asset** (or configuration of **assets**) solely for the purposes of **commissioning**.

- (5) Each **asset owner** must provide the **system operator** with an **asset capability statement** in the form from time to time **published** by the **system operator** for each **asset** that is proposed to be connected, or is connected to, or forms part of the **grid**. The **asset capability statement** must—
- (a) include all information reasonably requested by the **system operator** so as to allow the **system operator** to determine the limitations in the operation of the **asset** that the **system operator** needs to know for the safe and efficient operation of the **grid**; and
  - (b) include any modelling data for the planning studies, as reasonably requested by the **system operator**; and
  - (c) be updated and reissued to the **system operator** as information and design development progresses through the study, design, manufacture, testing and **commissioning** phases; and
  - (d) be complete and up to date before the **commissioning** of the **asset**; and
  - (e) be complete and up to date at all times while the **asset** is connected to, or forms part of, the **grid**.
- (6) Each **asset owner** must provide a **commissioning** plan or test plan in accordance with subclauses (7) or (8) (as the case may be) in the following situations:
- (a) when changes are made to **assets** that alter any of the following at the **grid interface**:
    - (i) the **single-line diagram**;
    - (ii) a protection system, other than a change to a protection system setting;
    - (iii) a **control system**, including a change to a **control system** setting;
    - (iv) any rating of **assets**;
  - (b) when **assets** are to be connected to, or are to form part of, the **grid**;
  - (c) if it is necessary for an **asset owner** to perform a **system test** or other test to ascertain or confirm **asset** capabilities, and if the **commissioning** or testing or connection of those **assets** may affect the **system operator's** ability to plan to comply, or to comply with, its **principal performance obligations**. If an **asset owner** is unsure whether the **commissioning** or connection of an **asset** may impact on the **system operator's** ability to plan to comply, and to comply, with the **principal performance obligations** it must contact the **system operator** for advice.
- (7) The **commissioning** plan prepared by an **asset owner** and agreed by the **system operator** must—
- (a) include a timetable containing the sequence of events necessary to connect the **assets** to the **grid** and conduct any proposed **system test**; and
  - (b) contain the protection and control settings to be applied before the **assets** are made live (where live has the meaning given to it in the Electricity (Safety)



- Regulations 2010); and
- (c) contain the procedures for **commissioning** the plant with minimum risk to personnel and plant and to the ability of the **system operator** to plan to comply and to comply with its **principal performance obligations**.
  - (8) If a test plan is required under subclause (6), it must be prepared by the **asset owner** in consultation with the **system operator**. The test plan must contain sufficient information to enable the **system operator** to plan to comply, and to comply, with the **principal performance obligations**.
  - (9) Once assessed by the **system operator** acting reasonably, the **asset owner** must follow the **commissioning** plan or test plan at all times, unless otherwise agreed with the **system operator** (such agreement must not be unreasonably withheld if compliance with the **commissioning** plan or testing plan is not practicable and non-compliance does not impact on the **system operator's** ability to comply with its **principal performance obligations** or on other **asset owners**).

Compare: Electricity Governance Rules 2003 clause 2 technical code A schedule C3 part C

Clause 2(1)(a): amended, on 1 February 2016, by clause 17 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

Clause 2(1) and (4) – (7): amended, on 23 February 2015, by clause 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 2(1) - (7) and (9): amended, on 5 October 2017, by clause 113 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### 3 Requirements for asset information

- (1) In accordance with clause 8.25(4), the following information is required by the **system operator** to assist it to plan to comply, and to comply, with its **principal performance obligations**:
  - (a) sufficient information must be exchanged between the **system operator** and the **asset owner** to ensure that both fully understand the implications of any changes to the **asset capability statement** or of any proposed connection of the relevant **assets** to the **grid** or to the **local network**. This information must be exchanged in accordance with a timetable agreed to by the **system operator** and the **asset owner**;
  - (b) if reasonably requested by the **system operator**, the **asset owner** must provide sufficient information to the **system operator** to demonstrate the compliance of the **asset owner's assets** with the **asset owner performance obligations** and the **technical codes**.
- (2) **Information** about an **asset**, **supply** or **demand** of other **asset owners** must only be disclosed by the **system operator**—
  - (a) as expressly provided for in this Code; or
  - (b) as reasonably required in a **grid emergency** or to ensure the security of the **grid**;  
or
  - (c) as required by **law**; or
  - (d) otherwise as may be agreed with the relevant **asset owners**.
- (3) Each **asset owner** must provide the **system operator** with—
  - (a) all information reasonably requested by the **system operator** so as to ensure compliance with clause 8.25(4) and to enable the **system operator** to assess the

- grid interface**; and
- (b) details of protection systems, including settings, to ensure that the requirements of clause 8.25(4) are met.
- (4) Each **asset owner** must ensure that all supporting information for the operational control of **assets** is kept up to date.

Compare: Electricity Governance Rules 2003 clause 3 technical code A schedule C3 part C  
Clause 3(1)(a): amended, on 23 February 2015, by clause 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.  
Clause 3(1)(a): amended, on 5 October 2017, by clause 114 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

#### **4 Requirements for grid and grid interface**

- (1) Each **asset owner** and **grid owner** must co-operate with the **system operator** to ensure that protection systems on both sides of a **grid interface**, which include **main protection systems** and **back up protection systems**, are co-ordinated so that a faulted **asset** is **electrically disconnected** by the **main protection system** first and the other **assets** are not prematurely **electrically disconnected**.
- (2) A proposed **grid interface**, including the settings of any associated protection system, must be agreed between the relevant **asset owner** and the **system operator** before being implemented.
- (3) Each **asset owner** must ensure that sufficient **circuit breakers** are provided for its **assets** so that each of its **assets** is able to be **electrically disconnected** from the **grid** whenever a fault occurs within the **asset**.
- (4) Each **asset owner** must ensure that it provides protection systems for its **assets** that are connected to, or form part of, the **grid**. Each **asset owner** must also ensure that as a minimum requirement—
- (a) such protection systems support the **system operator** in planning to comply, and complying, with the **principal performance obligations** and are designed, **commissioned** and maintained, and settings are applied, to achieve the following performance in a reliable manner:
- (i) **electrically disconnect** any faulted **asset** in minimum practical time (taking into account selectivity margins and industry best design practice) and minimum disruption to the operation of the **grid** or other **assets**:
- (ii) be selective when operating, so that the minimum amount of **assets** are **electrically disconnected**:
- (iii) as far as reasonably practicable, preserve power system stability; and
- (b) it provides duplicated **main protection systems** for each of its **assets** at voltages of 220 kV a.c. or above, other than busbars; and
- (c) it provides, for each of its 220 kV a.c. busbars—
- (i) a single **main protection system** and a **back up protection system**; or
- (ii) if the performance of its **back up protection system** does not meet the requirements of paragraph (a), a duplicated **main protection system**; and
- (d) it provides duplicated **main protection systems** for each of its busbars at voltages above 220 kV a.c; and
- (e) it designs, tests and maintains its **main protection systems** at voltages of 220 kV a.c. or above in accordance with the requirements set out in Appendix A; and

- (f) it provides a **circuit breaker failure protection system**, that need not be duplicated, for each **circuit breaker** at voltages of 220 kV a.c. or above. **Circuit breaker** duplication is not required; and
  - (g) protection system design for a connection of **assets** to the **grid** at lower voltages must be similar to existing design practice in adjacent connections of **assets** to ensure coordination of protection systems.
- (5) At a **point of connection**—
- (a) an **asset owner**, other than a **grid owner**, must provide a means of checking **synchronisation** before the switching of **assets** if it is possible that such switching may result in **electrical connection** of parts of the New Zealand electric power system that are not **synchronised**; and
  - (b) a **grid owner** must provide a means of checking **synchronisation** before the switching of **assets** in locations agreed with the **system operator** so that it is not possible for such switching to result in **electrical connection** of parts of the New Zealand electric power system that are not **synchronised**.
- (6) An auto-reclose facility at the **grid interface**, at which power flows into the **grid** can occur, must include an appropriate **synchronising** check facility.

Compare: Electricity Governance Rules 2003 clause 4 technical code A schedule C3 part C

Clause 4 Heading: amended, on 15 May 2014, by clause 11 of the Electricity Industry Participation (Minor Code Amendments) Code Amendment 2014.

Clause 4(1), (3), (4) and (5): amended, on 5 October 2017, by clause 115 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 4(4) and (5): amended, on 23 February 2015, by clause 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

## 5 Specific requirements for generators

- (1) Each **generator** must ensure that—
- (a) each of its **generating units**, and its associated **control systems**,—
    - (i) supports the **system operator** to plan to comply, and to comply, with the **principal performance obligations**; and
    - (ii) is able to **synchronise** at a stable frequency within the frequency range stated in the **asset capability statement** for that **asset**; and
  - (b) the rate of change in the output of any of its **generating units** does not adversely affect the **system operator's** ability to plan to comply, and to comply, with the **principal performance obligations**. The rate of change must be adjustable to allow for changes in **grid** conditions; and
  - (c) each of its **generating units** has a speed governor that—
    - (i) provides stable performance with adequate damping; and
    - (ii) has an adjustable droop over the range of 0% to 7%; and
    - (iii) does not adversely affect the operation of the **grid** because of any of its non-linear characteristics; and
  - (d) appropriate speed governor settings to be applied before commencing **system tests** for a **generating unit** are agreed between the **system operator** and the **generator**. The performance of the **generating unit** is then assessed by measurements from **system tests** and final settings are then applied to the **generating unit** before making it ready for service after those final settings are

- agreed between the **system operator** and the **generator**. An **asset owner** must not change speed governor settings without **system operator** approval.
- (2) Each **generator** with a **generating unit** connected to the **grid** must—
- (a) have an excitation and voltage control system with a voltage set point that is adjustable over the range of voltage set out in clause 8.23 and operates continuously in the voltage control mode when **synchronised**; and
  - (b) in order to meet the **asset owner performance obligations**, ensure that each of its **generating units** is equipped with either—
    - (i) a connection transformer with an appropriate range of taps on each transformer together with an on-load tap-changer; or
    - (ii) **assets** to give a dynamic performance equivalent to those required by subparagraph (i).
- (3) If the output of more than 1 **generating unit** is controlled by a common **control system**, the **generator** must ensure that—
- (a) the common **control system** does not adversely affect the ability of the **system operator** to plan to comply, and to comply, with the **principal performance obligations**; and
  - (b) the combined output from the **generating units** performs as though it were from 1 **generating unit**; and
  - (c) the **control system** does not degrade the individual performance of any one **generating unit**.
- (4) Each **generator** and **grid owner** must ensure that each of its **assets** is capable of operating under the voltage imbalance conditions stated in clause 4.9 of the **Connection Code** and, when operated within the limits stated in its **asset capability statement**, does not—
- (a) contribute unbalanced phase currents into the **grid**; or
  - (b) aggravate any current imbalance that may occur on the **grid**.
- (5) At some **points of connection**, a **generator** must ensure that its **generating units** have both **main protection systems** and **back-up protection systems** for nearby faults on the **grid**, if the necessity for, and the method of providing, such protection systems is agreed between the **system operator** and the **generator**.

Compare: Electricity Governance Rules 2003 clause 5 technical code A schedule C3 part C

Clause 5(2): amended, on 23 February 2015, by clause 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 5(2): amended, on 5 October 2017, by clause 116 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 5(4): amended, on 19 May 2016, by clause 29 of the Electricity Industry Participation Code Amendment (System Operator and Alignment with Statutory Objective) 2016.

## 6 Specific requirements for connected asset owners

Each **connected asset owner** must agree with the **system operator** any temporary or permanent connection of the **connected asset owner's assets** if those **assets** become simultaneously connected to the **grid** at more than 1 **point of connection**.

Compare: Electricity Governance Rules 2003 clause 6 technical code A schedule C3 part C

Clause 6 Heading: amended, on 1 February 2016, by clause 18(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

Clause 6: amended, on 23 February 2015, by clause 75 of the Electricity Industry Participation Code Amendment

(Distributed Generation) 2014.

Clause 6: amended, on 1 February 2016, by clause 18(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

Clause 6: amended, on 5 October 2017, by clause 117 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

## 7 Modifications and changes to assets

- (1) **Assets** that have been modified, or are proposed to be modified, are deemed to be new **assets** for the purposes of this Code and this **Technical Code** and are subject to the requirements for connection to the **grid** and the requirements for **commissioning assets**. For the purposes of this Schedule, the following are considered to be modifications to **assets**, if the new connection or alteration may affect the capacity of the **assets** or may affect **asset owner performance obligations** or **technical code** requirements:
  - (a) a new connection of **assets** to the **grid** or a **local network**;
  - (b) a new connection of **assets** to form part of the **grid**;
  - (c) a new connection of an **embedded generator** to a **local network** other than an **excluded generator** as defined in clause 8.21(1);
  - (d) an alteration to **assets** already connected to the **grid** or, in the case of **embedded generator**, already connected to a **local network**.
- (2) The **asset owner** must give written notice to the **system operator** in a timely manner of any **assets** that have been **decommissioned** if the **assets** affect or could affect the **system operator's** ability to comply with its **principal performance obligations**.

Compare: Electricity Governance Rules 2003 clause 7 technical code A schedule C3 part C

Clause 7(1): amended, on 23 February 2015, by clause 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 7(1) and (2): amended, on 5 October 2017, by clause 118 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

## 8 Records, tests and inspections

- (1) Each **asset owner** must arrange for, and retain, records for each of its **assets** to demonstrate that the **assets** comply with the **asset owner performance obligations** and this **technical code**.
- (2) In addition to the requirements for **commissioning** or testing in clause 2(6) to (8), each **asset owner** must carry out periodic testing—
  - (a) of its **assets** in accordance with Appendix B; and
  - (b) in the case of an **asset owner** that is an **extended reserve provider**, of **assets** specified in its **statement of extended reserve obligations** in accordance with that statement.
- (3) If the **system operator** advises an **asset owner** that it reasonably believes that an **asset** may not comply with an **asset owner performance obligation** or this **technical code**, the **asset owner** must—
  - (a) as soon as practicable, but no later than 30 days after receiving a written request, advise the **system operator** of its remedial or test plan for the **assets**; and
  - (b) as soon as reasonably practicable undertake any remedial action or testing of its **assets** in accordance with its plan advised to the **system operator** in paragraph (a). The **system operator** may require such testing or remedial action to be undertaken in the presence of a **system operator** representative.

- (4) Each **asset owner** must, at the request of the **system operator**, provide access to records of the performance or testing of an **asset** and access to inspect an **asset**.

Compare: Electricity Governance Rules 2003 clause 8 technical code A schedule C3 part C

Clause 8(2): substituted, on 7 August 2014, by clause 16 of the Electricity Industry Participation Code Amendment (Extended Reserve) 2014.

Clause 8(2): amended, on 5 October 2017, by clause 119 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

## **9 Status of system operator approval**

A review and approval by the **system operator** under this Code must not be construed as confirming or endorsing the design or warranting the safety, durability or reliability of an **asset**. Such review or approval does not relieve the **asset owner** from its obligations to continue to meet the requirements of this Code. The **system operator** is not, by reason of any such review or lack of review, responsible for strength, adequacy of design or capacity of an **asset**. In undertaking a review, the **system operator** is not responsible for any consequence of a failure of an **asset** due to inadequate design.

Compare: Electricity Governance Rules 2003 clause 9 technical code A schedule C3 part C

*Appendix A: Main protection system requirements*

**1 General requirements**

An **asset owner** must design, test and maintain all **main protection systems** at voltages of 220 kV a.c. or above to conform to electricity industry standards and practices as they are reasonably and ordinarily applied by a skilled and experienced **asset owner** to current installations at voltages of 220 kV a.c. or above in the New Zealand context.

Compare: Electricity Governance Rules 2003 clause 1 appendix A technical code A schedule C3 part C

**2 Specific requirements for main protection systems**

**Main protection systems** at voltages of 220 kV a.c. or above must meet the requirements set out below:

- (a) either test blocks or both test switches and test terminals must be provided;
- (b) the electrical continuity of fused protection circuits, including d.c. and voltage transformer circuits must be supervised;
- (c) the electrical continuity of **circuit breaker** trip circuits must be supervised.

Compare: Electricity Governance Rules 2003 clause 2 appendix A technical code A schedule C3 part C

**3 Specific requirements for duplicated main protection systems**

Duplicated **main protection systems** (the 2 components of which are referred to in this appendix as main 1 protection and main 2 protection) at voltages of 220 kV a.c. or above must meet the requirements set out below:

- (a) duplicated **main protection systems** must be designed with sufficient coverage and probability of detection that if any or all parts of 1 **main protection system** fail, the other **main protection system electrically disconnects** a faulted **asset** before a **back up protection system** initiates the **electrical disconnection** of other non-faulted **assets**;
- (b) the d.c. supply to duplicated **main protection systems** must consist of 2 independent station batteries, each with its own charger, supervision, and with a capacity and carry over duty to cover charger failure until repair and restoration. Station batteries may only feed a common primary d.c. busbar provided that the busbar is insulated and isolated from earth;
- (c) the d.c. supply to each duplicated **main protection system** must be independently fused at the primary d.c. busbar;
- (d) the manufacturer of main 1 protection must not be the same as the manufacturer of main 2 protection, unless one protection uses different measurement principles from the other;
- (e) the current transformer core (or an equivalent instrument) and the cabling associated with that current transformer core or equivalent instrument (as the case may be) used for main 1 protection must be independent from that used for main 2 protection;
- (f) if a voltage transformer supply is required for main 1 or main 2 protection—
  - (i) the supply must be fused at the voltage transformer; and
  - (ii) the supply for main 1 protection must use an independent fuse and cable

from those used for main 2 protection:

- (g) main 1 protection must use, in each of the **circuit breakers** tripped by that main 1 protection, an independent trip coil from that used for main 2 protection:
- (h) if protection signalling is used, main 1 protection must use a signal channel over an independent bearer on a different route from that used for main 2 protection:
- (i) main 1 protection cabling must be segregated from main 2 protection cabling in a manner that minimises the risk of common mode failure of main 1 and 2 protection and minimises the number of connections in any protection circuit.

Compare: Electricity Governance Rules 2003 clause 3 appendix A technical code A schedule C3 part C  
Clause 3(a) and (i): amended, on 5 October 2017, by clause 120 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.  
Clause 3(i): amended, on 23 February 2015, by clause 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

#### 4 Existing equipment

Despite clauses 1 and 3—

- (a) a current transformer **commissioned** before 31 May 2007 is not required to comply with clause 3(e) until the current transformer is replaced; and
- (b) a **circuit breaker commissioned** before 31 May 2007, if not designed to incorporate a second trip coil, is not required to comply with clause 3(g) until the **circuit breaker** is replaced; and
- (c) cabling **commissioned** before 31 May 2007, if not designed to be segregated, is not required to comply with the segregation requirements of clause 3(i) until the cabling is replaced.

Compare: Electricity Governance Rules 2003 clause 4 appendix A technical code A schedule C3 part C  
Clause 4: amended, on 5 October 2017, by clause 121 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.



*Appendix B: Routine testing of assets*

Cross heading: amended, on 7 August 2014, by clause 17 of the Electricity Industry Participation Code Amendment (Extended Reserve) 2014.

**1 Periodic tests to be carried out**

- (1) This Appendix sets out periodic tests required for the purposes of clause 8(2) of **Technical Code A**.
- (2) Each **asset owner** may be legally required, other than under this Code, to carry out additional tests to ensure that their **assets** are safe and reliable.
- (3) For the purposes of this Appendix, **generating unit** does not include a **generating unit** for which wind is the primary power source.

Compare: Electricity Governance Rules 2003 clause 1 appendix B technical code A schedule C3 part C  
Clause 1: substituted, on 7 August 2014, by clause 18 of the Electricity Industry Participation Code Amendment (Extended Reserve) 2014.

**2 Generating unit frequency response**

Each **generator**, other than **generators** who are owners of **excluded generating stations** that are not subject to a directive issued by the **Authority** under clause 8.38, must—

- (a) test the trip frequencies and trip time delays of each of its **generating units'** analogue over-frequency relays and analogue under-frequency relays at least once every 4 years; and
- (b) test the trip frequencies and trip time delays of each of its **generating units'** non-self monitoring digital over-frequency relays and non-self monitoring digital under-frequency relays at least once every 4 years; and
- (c) test the trip frequencies and trip time delays of each of its **generating units'** self monitoring digital over-frequency relays and self monitoring digital under-frequency relays at least once every 10 years; and
- (d) based on the tests carried out in accordance with paragraphs (a) to (c), provide a verified set of under-frequency trip settings and time delays to the **system operator** in an updated **asset capability statement** within 3 months of the completion date of each such test; and
- (e) based on the tests carried out in accordance with paragraphs (a) to (c), provide a verified set of over-frequency trip settings and time delays to the **system operator** in an updated **asset capability statement** within 3 months of the completion date of each such test.

Compare: Electricity Governance Rules 2003 clause 2 appendix B technical code A schedule C3 part C

**3 Generating unit governor and speed control**

Each **generator**, other than **generators** who are owners of **excluded generating stations** that are not subject to a directive issued by the **Authority** under clause 8.38 must—

- (a) test the governor system response of each of its **generating units'** mechanical or analogue speed governors at least once every 5 years; and
- (b) test the governor system response of each of its **generating units'** digital or

- electro-hydraulic speed governors at least once every 10 years; and
- (c) based on the tests carried out in accordance with paragraphs (a) or (b), provide a verified set of modelling parameters and governor system response data to the **system operator** in an updated **asset capability statement** within 3 months of the completion date of each such test, including—
- (i) a block diagram showing the mathematical representation of the governor; and
  - (ii) a block diagram showing the mathematical representation of the turbine dynamics including non-linearity and the applicable fuel source; and
  - (iii) a parameter list showing gains, time constants and other settings applicable to the block diagrams.

Compare: Electricity Governance Rules 2003 clause 3 appendix B technical code A schedule C3 part C

#### 4 **Generating unit transformer voltage control**

Each **generator** with a **point of connection** to the **grid** must—

- (a) test the operation of each of its **generating unit** transformers' on-load tap changer analogue **control systems** at least once every 4 years; and
- (b) test the operation of each of its **generating unit** transformers' on-load tap changer digital **control systems** at least once every 10 years; and
- (c) based on the tests carried out in accordance with paragraphs (a) or (b), provide a verified set of control parameters including voltage set points, operating dead bands and response times to the **system operator** in an updated **asset capability statement** within 3 months of the completion date of each such test.

Compare: Electricity Governance Rules 2003 clause 4 appendix B technical code A schedule C3 part C

#### 5 **Generating unit voltage response and control**

Each **generator** with a **point of connection** to the **grid** must—

- (a) test the modelling parameters and voltage response of each of its **generating units'** analogue excitation systems at least once every 5 years; and
- (b) test the modelling parameters and voltage response of each of its **generating units'** digital excitation systems at least once every 10 years; and
- (c) based on the tests carried out in accordance with paragraphs (a) or (b), provide a verified set of modelling parameters and voltage response data to the **system operator** in an updated **asset capability statement** within 3 months of the completion date of each such test, including—
  - (i) a block diagram showing the mathematical representation of the automatic voltage regulator; and
  - (ii) a block diagram showing the mathematical representation of the exciter; and
  - (iii) a parameter list showing gains, time constants and other settings applicable to the block diagrams.

Compare: Electricity Governance Rules 2003 clause 5 appendix B technical code A schedule C3 part C

**6**     *[Revoked]*

Compare: Electricity Governance Rules 2003 clause 6 appendix B technical code A schedule C3 part C  
Clause 6: revoked, on 7 August 2014, by clause 19 of the Electricity Industry Participation Code Amendment (Extended Reserve) 2014.

**7**     *[Revoked]*

Compare: Electricity Governance Rules 2003 clause 7 appendix B technical code A schedule C3 part C  
Clause 7: revoked, on 7 August 2014, by clause 19 of the Electricity Industry Participation Code Amendment (Extended Reserve) 2014.

**8**     **Grid owner transformer voltage range**

Each **grid owner** must—

- (a) test the operation of each of its transformers' on-load tap changer analogue **control systems** at least once every 4 years; and
- (b) test the operation of each of its transformers' on-load tap changer digital **control systems** at least once every 10 years; and
- (c) based on the tests carried out in accordance with paragraphs (a) or (b), provide a verified set of control parameters to the **system operator** in an updated **asset capability statement** within 3 months of the completion date of each such test, including voltage set points, operating dead bands and response times.

Compare: Electricity Governance Rules 2003 clause 8 appendix B technical code A schedule C3 part C

**9**     **Grid owner static var compensator transient response and control**

Each **grid owner** must—

- (a) test the transient response, steady state response and a.c. disturbance response of each of its static var compensators at least once every 10 years; and
- (b) test the operation of each of its static var compensators' analogue **control systems** at least once every 4 years; and
- (c) test the operation of each of its static var compensators' digital **control systems** at least once every 10 years; and
- (d) based on the test carried out in accordance with paragraph (a), provide a verified set of modelling parameters, transient response parameters, steady state response parameters, and a.c. disturbance response data to the **system operator** in an updated **asset capability statement** within 3 months of the completion date of each such test including—
  - (i) a block diagram showing the mathematical representation of the static var compensator; and
  - (ii) a parameter list showing gains, time constants, limiters and other settings applicable to the block diagrams; and
  - (iii) a detailed functional description of all of the components of the static var compensator and how they interact in each mode of control; and
  - (iv) step response test results; and
  - (v) a.c. fault recovery disturbance test results; and
- (e) based on tests carried out in accordance with paragraphs (b) or (c), provide a set of **control system** test results to the **system operator** in an updated **asset capability statement** within 3 months of the completion date of each such test.

Compare: Electricity Governance Rules 2003 clause 9 appendix B technical code A schedule C3 part C

## 10 Grid owner capacitors and reactive power control systems

Each **grid owner** must—

- (a) test the capacitance of each of its capacitors at least once every 8 years; and
- (b) test the operation of each of its reactive power control assets' analogue **control systems** at least once every 4 years; and
- (c) test the operation of each of its reactive power control assets' digital **control systems** at least once every 10 years; and
- (d) based on the test carried out in accordance with paragraph (a), provide a set of test results to the **system operator** in an updated **asset capability statement** within 3 months of the completion date of each such test; and
- (e) based on tests carried out in accordance with paragraphs (b) or (c), provide a verified set of **control system** test results including voltage set points, operating dead bands and time delays to the **system operator** in an updated **asset capability statement** within 3 months of the completion date of each such test.

Compare: Electricity Governance Rules 2003 clause 10 appendix B technical code A schedule C3 part C

## 11 Grid owner synchronous compensators

Each **grid owner** must—

- (a) test each of its synchronous compensators' analogue and electromechanical excitation systems at least once every 5 years; and
- (b) test each of its synchronous compensators' digital excitation systems at least once every 10 years; and
- (c) based on the tests carried out in accordance with paragraphs (a) or (b), provide a verified set of modelling parameters and voltage response data to the **system operator** in an updated **asset capability statement** within 3 months of the completion date of each such test including—
  - (i) a block diagram showing the mathematical representation of the automatic voltage regulator; and
  - (ii) a block diagram showing the mathematical representation of the exciter; and
  - (iii) a detailed functional description of the excitation system in all modes of control; and
  - (iv) a parameter list showing gains, time constants, limiters and other settings applicable to the block diagrams.

Compare: Electricity Governance Rules 2003 clause 11 appendix B technical code A schedule C3 part C

## 12 HVDC link frequency control and protection

The **HVDC owner** must—

- (a) test the operation of each of its **HVDC link's** analogue **control systems** at least once every 4 years; and
- (b) test the operation of each of its **HVDC link's** digital **control systems** at least once every 10 years; and
- (c) test the operation of each of its **HVDC link's** analogue protection systems at least

- once every 4 years; and
- (d) test the operation of each of its **HVDC link's** digital protection systems at least once every 10 years; and
- (e) test the modulation functions on its **HVDC link** at least once every 10 years; and
- (f) based on the tests carried out in accordance with paragraphs (a) or (b), provide a set of **control system** test results and verified modelling parameters to the **system operator** in an updated **asset capability statement** within 3 months of the completion date of each such test; and
- (g) based on the tests carried out in accordance with paragraphs (c) or (d), provide a set of protection system test results to the **system operator** in an updated **asset capability statement** within 3 months of the completion date of each such test; and
- (h) based on the tests carried out in accordance with paragraph (e), provide a set of modulation function test results to the **system operator** in an updated **asset capability statement** within 3 months of the completion date of each such test including—
  - (i) a block diagram showing the mathematical representation of the **HVDC link**; and
  - (ii) a parameter list showing gains, time constants, limiters and other settings applicable to the block diagram; and
  - (iii) a detailed functional description of all of the components of the **HVDC link** and how they interact in each mode of control.

Compare: Electricity Governance Rules 2003 clause 12 appendix B technical code A schedule C3 part C

### 13 Asset owner a.c. protection systems

Each **asset owner** must—

- (a) test the operation of the analogue protection systems on its a.c. **assets** at least once every 4 years; and
- (b) test the operation of the non-self monitoring digital protection systems on its a.c. **assets** at least once every 4 years; and
- (c) test the operation of the self monitoring digital protection systems on its a.c. **assets** at least once every 10 years; and
- (d) test the operation of the protection system measuring circuits on its a.c. **assets** by secondary injection at least once every 4 years; and
- (e) test the operation of the protection system trip circuits, including circuit breaker trips, on its a.c. **assets** at least once every 4 years; and
- (f) confirm at least once every 4 years that its protection settings are identified, co-ordinated, applied correctly and meet the requirements of the **AOPOs** and the **technical codes**; and
- (g) based on tests carried out in accordance with paragraphs (a) to (e), provide a verification to the **system operator** in an updated **asset capability statement** that the protection systems meet the requirements of the **AOPOs** and **technical codes** within 3 months of the completion date of each such test; and
- (h) based on the confirmation carried out in accordance with paragraph (f), provide an

updated **asset capability statement** to the **system operator** within 3 months of the completion date of each such confirmation.

Compare: Electricity Governance Rules 2003 clause 13 appendix B technical code A schedule C3 part C

#### **14 Representative testing**

- (1) Subject to clause 8(3) of **Technical Code A**, each **asset owner** may provide the information required under clauses 3(c), 5(c), and 11(c) to the **system operator**, based on representative modelling parameters and response data instead of based on the tests required under clauses 3(a) and (b), 5(a) and (b), and 11(a) and (b), for any group of identical **assets**, if each of those **assets**—
  - (a) was manufactured to the same specification; and
  - (b) is installed at the same location; and
  - (c) is controlled in the same way; and
  - (d) has a similar maintenance history.
- (2) Each **asset owner** providing representative modelling parameters and response data to the **system operator** in accordance with subclause (1) for a group of identical **assets** must—
  - (a) complete a full set of tests in accordance with clauses 3(a) or (b), 5(a) or (b), and 11(a) or (b), as applicable, on an **asset** that is representative of that group to derive a verified set of modelling parameters and response data; and
  - (b) complete sufficient testing on the remaining **assets** in that group of identical **assets** in accordance with clauses 3(a) or (b), 5(a) or (b), and 11(a) or (b), as applicable, to verify that the performance of the remaining **assets** in that group is fully consistent with the modelling parameters and response data derived from the tests carried out on the representative **asset**; and
  - (c) certify to the **system operator**, that to the best of the **asset owner's** information, knowledge and belief, the performance of that group of **assets** is fully consistent with the representative modelling parameters and response data provided to the **system operator** for that group of **assets**.

Compare: Electricity Governance Rules 2003 clause 14 appendix B technical code A schedule C3 part C

#### **15 Transitional provisions**

- (1) Unless a test interval of less than 60 months is specified in this Appendix, each **asset owner** must complete the first of each test required in this Appendix no later than 5 June 2013.
- (2) A test that is required to be carried out in accordance with this Appendix, but that an **asset owner** carried out before 5 June 2008, is deemed to be the first test of that type required in this Appendix, if—
  - (a) the **asset owner** has submitted the relevant written test results to the **system operator**; and
  - (b) the **system operator** has advised the **asset owner** that the specification of the test is acceptable; and
  - (c) the interval between the actual date of the test and the date on which this Code came into force is less than the maximum test interval specified for the

corresponding test in this Appendix.

- (3) If a test has been deemed to be the first test in accordance with subclause (2), the date by which the next such test must be carried out must be calculated using the actual date upon which the first test was carried out, not the date upon which it was deemed to have been carried out.

Compare: Electricity Governance Rules 2003 clause 15 appendix B technical code A schedule C3 part C  
Clause 15(1): amended, on 21 September 2012, by clause 11(1) of the Electricity Industry Participation (Minor Amendments) Code Amendment 2012.

Clause 15(2): amended, on 21 September 2012, by clause 11(2) of the Electricity Industry Participation (Minor Amendments) Code Amendment 2012.

*Technical Code B – Emergencies*

**1 Purpose and application**

The purpose of this **technical code** is to set out the basis on which the **system operator** and **participants** must anticipate and respond to emergency events on the **grid** that affect the **system operator's** ability to plan to comply, and to comply with its **principal performance obligations**.

Compare: Electricity Governance Rules 2003 clause 1.1 technical code B schedule C3 part C

**2 Application**

This **technical code** applies to all **asset owners** except for **excluded generating stations**. If the **system operator** reasonably considers it necessary to assist the **system operator** in planning to comply and complying with the **principal performance obligations**, the **system operator** may require that an **excluded generating station** comply with some or all of the requirements of this **technical code**.

Compare: Electricity Governance Rules 2003 clause 1.2 technical code B schedule C3 part C

**3 Obligations of all parties**

The **system operator** and all **participants** must plan individually and, if appropriate, collectively, for a **grid emergency**, and act quickly and safely during a **grid emergency** in accordance with this **technical code**, so that the actual and potential impacts of any **grid emergency** are minimised.

Compare: Electricity Governance Rules 2003 clause 2 technical code B schedule C3 part C

**4 Obligations of the system operator**

The **system operator** must use reasonable endeavours to ensure that—

- (a) if necessary, each **participant** is advised of any independent action required of it if there is a **grid emergency**; and
- (b) facilities to be put in place by **grid owners** or other **asset owners** to manually **electrically disconnect demand** at each **point of connection** are specified.

Compare: Electricity Governance Rules 2003 clause 3 technical code B schedule C3 part C

Clause 4: amended, on 15 May 2014, by clause 12 of the Electricity Industry Participation (Minor Code Amendments) Code Amendment 2014.

Clause 4(b): amended, on 5 October 2017, by clause 122 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

**5 Formal notices and responses**

- (1) The **system operator** must issue a notice either orally or in writing to relevant **participants** whenever, or as soon as practicable after, any of the following events has occurred:
  - (a) the ability of the **system operator** to plan to comply, and to comply, with the **principal performance obligations** is at risk or is compromised (as set out in the **policy statement**):
  - (b) public safety is at risk:
  - (c) there is a risk of significant damage to **assets**:
  - (d) independent action has been taken in accordance with this **technical code** to



restore the **system operator's principal performance obligations**.

- (1A) The **system operator** must issue a notice in writing to all **participants** whenever, or as soon as practicable after, an **island** wide instruction to **electrically disconnect demand** has been issued, amended, or revoked under clause 6.
- (1B) For the purposes of subclause (1A), an **island** wide instruction is when the electrical or geographical region affected by a notice is all of an **island**.
- (1C) The **system operator** must provide any notice issued under subclause (1A) to the **pricing manager** by 0730 hours on the following **trading day**.
- (2) The **system operator** must ensure that a **formal notice** issued in accordance with subclause (1) or subclause (1A) includes the following:
  - (a) the electrical or geographical region affected by the notice:
  - (b) the potential consequences of the situation:
  - (c) the responses requested of **participants**:
  - (d) the start time and end time of the situation to which the notice applies.
- (3) The **system operator** must record the issue of a **formal notice**, and each **participant** must record receipt of a **formal notice**.
- (4) If the **system operator** issues a request in accordance with this **technical code** to a **participant**, the **participant** must use reasonable endeavours to respond to the request.

Compare: Electricity Governance Rules 2003 clause 4 technical code B schedule C3 part C

Clause 5(1A): inserted, on 1 June 2013, by clause 5(a) of the Electricity Industry Participation (Scarcity Pricing) Code Amendment 2011.

Clause 5(1A): amended, on 5 October 2017, by clause 123 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 5(1B): inserted, on 1 June 2013, by clause 5(a) of the Electricity Industry Participation (Scarcity Pricing) Code Amendment 2011.

Clause 5(1C): inserted, on 1 June 2013, by clause 5(a) of the Electricity Industry Participation (Scarcity Pricing) Code Amendment 2011.

Clause 5(2): amended, on 1 June 2013, by clause 5(b) of the Electricity Industry Participation (Scarcity Pricing) Code Amendment 2011.

Clause 5(2)(d): amended, on 19 January 2017, by clause 4 of the Electricity Industry Participation Code Amendment (Scarcity Pricing) 2016.

## **6 Actions to be taken by the system operator in a grid emergency**

- (1) If insufficient generation and **frequency keeping** gives rise to a **grid emergency**, the **system operator** may, having regard to the priority below, if practicable, and regardless of whether a **formal notice** has been issued, do 1 or more of the following:
  - (a) request that a **generator** varies its **offer** and **dispatch** the **generator** in accordance with that **offer**, to ensure there is sufficient generation and **frequency keeping**:
  - (b) request that a **purchaser** or a **connected asset owner** reduce **demand**:
  - (c) require a **grid owner** to reconfigure the **grid**:
  - (d) require the **electrical disconnection** of **demand** in accordance with clause 7A:
  - (e) take any other reasonable action to alleviate the **grid emergency**.
- (2) If insufficient transmission capacity gives rise to a **grid emergency**, the **system operator** may, having regard to the priority below, if practicable, and regardless of whether a **formal notice** has been issued, do 1 or more of the following:
  - (a) request that a **generator** varies its **offer** and **dispatch** the **generator** in accordance with that **offer**, to ensure that the available transmission capacity

- within the **grid** is sufficient to transmit the remaining level of **demand**:
- (b) request that an **asset owner** restores its **assets** that are not in service:
  - (c) request that a **purchaser** or **connected asset owner** reduces its **demand**:
  - (d) require the **electrical disconnection** of **demand** in accordance with clause 7A:
  - (e) take any other reasonable action to alleviate the **grid emergency**.
- (3) If frequency is outside the **normal band** and all available **injection** has been **dispatched**, the **system operator** may require the **electrical disconnection** of **demand** in accordance with clause 7A in appropriate block sizes until frequency is restored to the **normal band**.
- (4) If any **grid** voltage reaches the minimum voltage limit set out in the table contained in clause 8.22(1), and is sustained at or below that limit, the **system operator** may require the **electrical disconnection** of **demand** in accordance with clause 7A in appropriate block sizes until the voltage is restored to above the minimum voltage limit.
- (5) The **system operator** may, if an unexpected event occurs giving rise to a **grid emergency**, take any reasonable action to alleviate the **grid emergency**.

Compare: Electricity Governance Rules 2003 clause 5 technical code B schedule C3 part C

Clause 6: amended, on 5 October 2017, by clause 124 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 6(1)(b): amended, on 1 February 2016, by clause 19 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

Clause 6(1)(d), amended, on 7 August 2014, by clause 20(1) of the Electricity Industry Participation Code Amendment (Extended Reserve) 2014.

Clause 6(2)(c): amended, on 1 February 2016, by clause 19 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

Clause 6(2)(d): amended, on 7 August 2014, by clause 20(1) of the Electricity Industry Participation Code Amendment (Extended Reserve) 2014.

Clause 6(3): amended, on 7 August 2014, by clause 20(2) of the Electricity Industry Participation Code Amendment (Extended Reserve) 2014.

Clause 6(4): amended, on 7 August 2014, by clause 20(1) of the Electricity Industry Participation Code Amendment (Extended Reserve) 2014.

## **7 Extended reserve providers to provide extended reserve**

- (1) Each **extended reserve provider** must provide **extended reserve** at all times in accordance with its current **statement of extended reserve obligations** issued by the **system operator** under clause 8.54P.
- (2) An **extended reserve provider** must give written notice to the **system operator** as soon as practicable if the **extended reserve provider** is unable to comply with subclause (1).

Compare: Electricity Governance Rules 2003 clause 6 technical code B schedule C3 part C

Clause 7: substituted, on 7 August 2014, by clause 21 of the Electricity Industry Participation Code Amendment (Extended Reserve) 2014.

Clause 7(2): amended, on 19 December 2014, by clause 15 of the Electricity Industry Participation Code Amendment (Minor Code Amendments) (No 3) 2014.

Clause 7(2): amended, on 5 October 2017, by clause 125 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 7(9A) and (9B): inserted, from 3 January 2013 to 2 October 2013, by clause 4(a) of the Electricity Industry Participation (Automatic Under-Frequency Load Shedding Systems) Code Amendment 2012.

Clause 7(9A) and (9B): inserted, on 2 October 2013, by clause 4(a) of the Electricity Industry Participation (Automatic Under-Frequency Load Shedding Systems) Code Amendment 2013.

Clause 7(9A) and (9B): revoked, on 3 April 2014, by clause 5(a) of the Electricity Industry Participation (Automatic Under-Frequency Load Shedding Systems) Code Amendment 2013.

Clause 7(10): revoked, from 3 January 2013 to 2 October 2013, by clause 4(b) of the Electricity Industry Participation (Automatic Under-Frequency Load Shedding Systems) Code Amendment 2012.

Clause 7(10): revoked, on 2 October 2013, by clause 4(b) of the Electricity Industry Participation (Automatic Under-Frequency Load Shedding Systems) Code Amendment 2013.

Clause 7(10): inserted, on 3 April 2014, by clause 5(b) of the Electricity Industry Participation (Automatic Under-Frequency Load Shedding Systems) Code Amendment 2013.

Clause 7(11): amended, from 3 January 2013 to 2 October 2013, by clause 4(c) of the Electricity Industry Participation (Automatic Under-Frequency Load Shedding Systems) Code Amendment 2012.

Clause 7(11): amended, on 2 October 2013, by clause 4(c) of the Electricity Industry Participation (Automatic Under-Frequency Load Shedding Systems) Code Amendment 2013.

Clause 7(11): amended, on 3 April 2014, by clause 5(c) of the Electricity Industry Participation (Automatic Under-Frequency Load Shedding Systems) Code Amendment 2013.

Clause 7(12A) and (12B): inserted, from 3 January 2013 to 2 October 2013, by clause 4(d) of the Electricity Industry Participation (Automatic Under-Frequency Load Shedding Systems) Code Amendment 2012.

Clause 7(12A) and (12B): inserted, on 2 October 2013, by clause 4(d) of the Electricity Industry Participation (Automatic Under-Frequency Load Shedding Systems) Code Amendment 2013.

Clause 7(12A) and (12B): revoked, on 3 April 2014, by clause 5(d) of the Electricity Industry Participation (Automatic Under-Frequency Load Shedding Systems) Code Amendment 2013.

Clause 7(13): amended, from 3 January 2013 to 2 October 2013, by clause 4(e) of the Electricity Industry Participation (Automatic Under-Frequency Load Shedding Systems) Code Amendment 2012.

Clause 7(13): amended, on 2 October 2013, by clause 4(e) of the Electricity Industry Participation (Automatic Under-Frequency Load Shedding Systems) Code Amendment 2013.

Clause 7(13): amended, on 3 April 2014, by clause 5(e) of the Electricity Industry Participation (Automatic Under-Frequency Load Shedding Systems) Code Amendment 2013.

Clause 7(15): amended, from 3 January 2013 to 2 October 2013, by clause 4(f) of the Electricity Industry Participation (Automatic Under-Frequency Load Shedding Systems) Code Amendment 2012.

Clause 7(15): amended, on 2 October 2013, by clause 4(f) of the Electricity Industry Participation (Automatic Under-Frequency Load Shedding Systems) Code Amendment 2013.

Clause 7(15): amended, on 3 April 2014, by clause 5(f) of the Electricity Industry Participation (Automatic Under-Frequency Load Shedding Systems) Code Amendment 2013.

Clause 7(16): substituted, from 3 January 2013 to 2 October 2013, by clause 4(g) of the Electricity Industry Participation (Automatic Under-Frequency Load Shedding Systems) Code Amendment 2012.

Clause 7(16): substituted, on 2 October 2013, by clause 4(g) of the Electricity Industry Participation (Automatic Under-Frequency Load Shedding Systems) Code Amendment 2013.

Clause 7(16): substituted, on 3 April 2014, by clause 5(g) of the Electricity Industry Participation (Automatic Under-Frequency Load Shedding Systems) Code Amendment 2013.

Clause 7(16A) and (16B): inserted, from 3 January 2013 to 2 October 2013, by clause 4(g) of the Electricity Industry Participation (Automatic Under-Frequency Load Shedding Systems) Code Amendment 2012.

Clause 7(16A) and (16B): inserted on 2 October 2013, by clause 4(g) of the Electricity Industry Participation (Automatic Under-Frequency Load Shedding Systems) Code Amendment 2013.

Clause 7(16A) and (16B): revoked on 3 April 2014, by clause 5(g) of the Electricity Industry Participation (Automatic Under-Frequency Load Shedding Systems) Code Amendment 2013.

## **7A Emergency load shedding**

- (1) Each **connected asset owner** must maintain a process for **electrical disconnection of demand** for **points of connection**.
- (2) The process must specify the **participant** that will effect the **electrical disconnection of demand**.
- (3) The **connected asset owner** must obtain agreement for the process from the **system operator** and each **grid owner**.
- (4) Each **connected asset owner** must advise the **system operator** of the agreed process in addition to any changes to a process previously advised.
- (5) If the **system operator** requires the **electrical disconnection of demand** under this **technical code**, the **system operator** must instruct **connected asset owners** and **grid owners** in accordance with the agreed process under subclause (3) to **electrically disconnect demand** for the relevant **point of connection**.
- (6) If the **system operator** and a **connected asset owner** or **grid owner** have not agreed on a process for **electrical disconnection of demand** at a **point of connection**, the **system**

**operator** must instruct **grid owners** to **electrically disconnect demand** directly at the relevant **point of connection**.

- (7) To the extent practicable, the **system operator** must use reasonable endeavours when instructing the **electrical disconnection of demand** to ensure equity between **connected asset owners**.
- (8) Each **connected asset owner** or **grid owner** must act as instructed by the **system operator** operating under clause 6.

Clause 7A: inserted, on 7 August 2014, by clause 21 of the Electricity Industry Participation Code Amendment (Extended Reserve) 2014.

Clause 7A(1), (2), (5), (6) and (7): amended, on 5 October 2017, by clause 126 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 7A(1), (3), (4), (5), (6), (7) and (8): amended, on 1 February 2016, by clause 20 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

#### **7B Obligations of extended reserve providers in relation to automatic under-frequency load shedding**

- (1) On the operation of **extended reserve** that is an **automatic under-frequency load shedding** system, an **extended reserve provider**—
  - (a) must, as soon as practicable, advise the **system operator** of the operation of the **automatic under-frequency load shedding** system and, if reasonably required by the **system operator** to plan to comply, or to comply, with its **principal performance obligations**, a reasonable estimate of the amount of **demand** that has been **electrically disconnected**; and
  - (b) may **electrically connect demand** only when permitted to do so by the **system operator**; and
  - (c) must ensure **demand electrically connected** under paragraph (b) complies with the obligations in its **statement of extended reserve obligations**; and
  - (d) must report to the **system operator** if **demand** is moved between **points of connection**; and
  - (e) may request permission to **electrically connect demand** from the **system operator** if no instruction to **electrically connect demand** is received from the **system operator** within 15 minutes of the frequency returning to the **normal band**; and
  - (f) may cautiously and gradually **electrically connect the demand electrically disconnected** through the **automatic under-frequency load shedding** system if there is a **loss of communication** with the **system operator**, 15 minutes after the **loss of communication** occurred.
- (2) An **extended reserve provider** may **electrically connect demand** only while frequency is within the **normal band** and voltage is within the required range.
- (3) Each **extended reserve provider** must immediately cease the **electrical connection of demand** and, to the extent necessary, **electrically disconnect demand**, if the frequency drops below the **normal band** or the voltage moves outside the required range.
- (4) As soon as practicable after communications are restored, each **extended reserve provider** must report to the **system operator** on the status of **electrical connection** of load and the status of re-arming the **automatic under-frequency load shedding** system.

Clause 7B: inserted, on 7 August 2014, by clause 21 of the Electricity Industry Participation Code Amendment (Extended Reserve) 2014.

Clause 7B: amended, on 5 October 2017, by clause 127 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

## **7C Obligations of extended reserve providers in security of supply situations**

- (1) This clause applies if a direction under clause 9.15 is in force.
- (2) The **system operator** may give notice to 1 or more of the **participants** specified in subclause (5), specifying modifications to the **participant's statement of extended reserve obligations** during any 1 or more periods, or in any 1 or more circumstances, specified in the notice.
- (3) The **system operator** must keep a record of each notice given under subclause (2).
- (4) When a notice under subclause (2) is in force in relation to a **participant**, the requirements of the **participant's statement of extended reserve obligations** are modified for that **participant** to the extent, and during the periods or in the circumstances (as the case may be), specified in the notice.
- (5) The **participants** to whom the **system operator** may issue a notice in accordance with subclause (2) are—
  - (a) **connected asset owners** in the North Island; and
  - (b) **grid owners** in the South Island.
- (6) The **system operator** may amend or revoke a notice, or revoke and substitute a new notice.
- (7) A notice under subclause (2) expires on the earlier of—
  - (a) the date (if any) specified in the notice for its expiry; and
  - (b) the revocation or expiry of the direction referred to in subclause (1).

Clause 7C: inserted, on 7 August 2014, by clause 21 of the Electricity Industry Participation Code Amendment (Extended Reserve) 2014.

Clause 7C(5)(a): amended, on 1 February 2016, by clause 21 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

## **8 Obligations of grid owners**

- (1) A **grid owner** must use reasonable endeavours to ensure that appropriate **assets** are installed for the manual **electrical disconnection of demand at points of connection**.
- (2) A **grid owner** must take independent action as may be required by the **system operator** in accordance with clause 6(4), to **electrically disconnect demand at points of connection** when any **grid** voltage reaches the minimum voltage limit set out in the table contained in clause 8.22(1) and is sustained at or below that level. A **grid owner** must continue to **electrically disconnect demand at points of connection** while the voltage remains below that minimum voltage limit, being guided by any arrangements with **connected asset owners** as advised by the **system operator**.

Compare: Electricity Governance Rules 2003 clause 7 technical code B schedule C3 part C

Clause 8(2): amended, on 1 February 2016, by clause 22 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

Clause 8(1) and (2): amended, on 5 October 2017, by clause 128(1) and (2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

**9 Obligations of generators and ancillary service agents to take independent action**

The following independent action is required of **generators** and **ancillary service agents** during the occurrence of extreme variations of frequency or voltage at the **points of connection** to which their **assets** are connected (such extreme levels of frequency or voltage are deemed to constitute a **grid emergency** and require a fast and independent response from each **generator** and each **ancillary service agent**):

- (a) when the **under-frequency limit** is reached and the frequency continues to fall, each **generator** must use reasonable endeavours to take the following immediate independent action to assist in restoring frequency:
  - (i) increase the energy **injection** from each **generating unit** that is physically capable of increasing such **injection**;
  - (ii) attempt to restore **grid** frequency to the **normal band** by **synchronising** and loading each **generating unit** that is not **electrically connected** but is able to be **electrically connected** and operated in this manner;
  - (iii) **re-synchronise** and load each **generating unit** that has tripped and is able to be **electrically connected** and operated in this manner;
  - (iv) report to the **system operator** as soon as practicable after taking action in accordance with subparagraphs (i) to (iii):
- (b) when the **over frequency limit** is reached and the frequency continues to rise, each **generator** must use reasonable endeavours to take the following immediate independent action to assist in restoring frequency:
  - (i) decrease the energy injection from **electrically connected generating units** if the **generator** is physically capable of decreasing such **injection**;
  - (ii) report to the **system operator** as soon as practicable after taking action in accordance with subparagraph (i):
- (c) when either the minimum voltage limit or the maximum voltage limit set out in the table contained in clause 8.22(1) is exceeded at any **point of connection**, **generators** and **ancillary service agents** must use reasonable endeavours to take immediate independent action to return the voltage to, as close as practicable, within such limits. Each **generator** must use reasonable endeavours to **synchronise** and, as necessary, load and adjust all available **generating units** that can assist in restoring the voltage. **Ancillary service agents** must also use reasonable endeavours to **electrically connect** to the **grid** and, as necessary, load all available **reactive capability** resources, that can assist in restoring the voltage. As soon as practicable after taking such actions, each **generator** and **ancillary service agent** must report to the **system operator** on the action taken to correct voltage:
- (d) for a **loss of communication** with the **system operator**, lasting at least 5 minutes, each **generator** must use reasonable endeavours to—
  - (i) for **synchronised generating units**, take independent action to adjust supply to maintain frequency as close as possible to the **normal band**, and maintain voltage as close as possible either to that previously advised by the **system operator**, or as can be best established by the **generator**; and

- (ii) **synchronise** available **generating units** to the **grid** if the **generating units** currently **electrically connected** do not have the capacity to control the frequency and voltage as required by paragraph (e)(i); and
  - (iii) continue to attempt to maintain the frequency and voltage to meet the requirements of paragraph (e)(i); and
  - (iv) as soon as practicable after communications are restored, report to the **system operator** on the action taken:
- (e) for a **loss of communication** with the **system operator** lasting at least 5 minutes, **ancillary service agents** must use reasonable endeavours to—
  - (i) if on load, take independent action to adjust any real or **reactive power** resources to maintain frequency and voltage as close as possible either to that previously advised by the **system operator** or as can be best established by the **ancillary service agent**; and
  - (ii) **electrically connect** available **reactive capability** resources to the **grid** if the currently **electrically connected reactive power** resources do not have the capacity to control the voltage above the minimum limit set out in the table contained in clause 8.22(1); and
  - (iii) continue to attempt to maintain the voltage above the minimum limit set out in the table contained in clause 8.22(1); and
  - (iv) as soon as practicable after communications are restored, report to the **system operator** on the action taken:
- (f) in the event of a failure at the **system operator's** operational centre that disables the main **dispatch** or communication systems, the **system operator** may temporarily transfer its operational activities to an alternative operational centre, and the **system operator** must arrange for communication facilities to transfer to the new location and must give written notice to **participants** of those arrangements.

Compare: Electricity Governance Rules 2003 clause 8 technical code B schedule C3 part C

Clause 9: amended, on 23 February 2015, by clause 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 9: amended, on 5 October 2017, by clause 129 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

*Technical Code C – Operational communications*

**1 Purpose**

The purpose of this **technical code** is to state the minimum requirements for the communications required under this Code between **asset owners**, except owners of **excluded generating stations**, and the **system operator**, in order to assist the **system operator** to plan to comply, and to comply, with the **principal performance obligations**. Additional requirements may be set out in other clauses. This **technical code** does not deal with the content of communications, which is dealt with in each **technical code** and in Part 13 where relevant.

Compare: Electricity Governance Rules 2003 clause 1.1 technical code C schedule C3 part C

**2 Application**

This **technical code** applies to the **system operator** and to all **asset owners** except owners of **excluded generating stations**. If the **system operator** reasonably considers it necessary to assist the **system operator** in planning to comply, and complying, with the **principal performance obligations**, the **system operator** may require that an **excluded generating station** comply with some or all of the requirements of this **technical code**.

Compare: Electricity Governance Rules 2003 clause 1.2 technical code C schedule C3 part C

**3 General requirements for operational communications**

- (1) Each voice or electronic communication between the **system operator** and an **asset owner** must be logged by the **system operator** and the **asset owner**. Unless otherwise agreed between the **system operator** and the **asset owner**, every voice instruction must be repeated back by the person receiving the instruction and confirmed by the person giving the instruction before the instruction is actioned.
- (2) The **system operator** and each **asset owner** must nominate and advise each other of the preferred points of contact and the alternative points of contact to be used by the **system operator** and the **asset owner**. Each **asset owner** must also nominate and advise the **system operator** of the person to receive instructions and **formal notices** as set out in **Technical Code B**. The preferred points of contact must include those to be used when the **system operator** instructs the **asset owner**, when the **system operator** sends **formal notices** to the **asset owner** and when the **asset owner** contacts the **system operator**. The alternative points of contact must be used only if the preferred points of contact are not available.
- (3) The **grid owner** and each other **asset owner** must nominate and advise each other of the preferred points of contact and the alternative points of contact to be used by the **grid owner** and the other **asset owner** for the purpose of communications regarding the availability of the **grid owner's** data transmission communications. The alternative points of contact must only be used if the preferred points of contact are not available.

Compare: Electricity Governance Rules 2003 clause 2 technical code C schedule C3 part C



#### 4 Specific requirements for voice communication

- (1) Each **asset owner** must have in place a primary means of communicating by voice between the **control room** of the **asset owner** and the **system operator**. The primary means of voice communication must use either—
  - (a) the **grid owner's** speech network; or
  - (b) a widely available public switched telephone network that operates in real time and in full duplex mode.
- (2) Each **asset owner** must have in place a backup means of communicating by voice between the **control room** of the **asset owner** and the **system operator**. The backup means of voice communication—
  - (a) must be approved by the **system operator** (such approval not to be unreasonably withheld); and
  - (b) may include, but is not limited to, satellite phone or cellular phone; and
  - (c) may be used only if the primary means of voice communication described in subclause (1) is unavailable or otherwise with the agreement of the **system operator**.
- (3) An **asset owner** who has a **control room** with, at any time, operational control of more than 299 MW of **injection, offtake**, or power flow must have 2 or more back up means of voice communication between the **control room** of the **asset owner** and the **system operator**, each of which must meet the requirements of subclause (2).

Compare: Electricity Governance Rules 2003 clause 3 technical code C schedule C3 part C

#### 5 Specific requirements for transmitting information

- (1) Each **asset owner** must transmit information between its **control room** and the **system operator** in writing.
- (2) Despite subclause (1), an **asset owner** may request the **system operator** to approve an alternative means of transmitting information (such approval not to be unreasonably withheld).
- (3) Each **asset owner** must have in place a backup means of transmitting information. The backup means of transmitting information—
  - (a) must be approved by the **system operator** (such approval not to be unreasonably withheld); and
  - (b) may include, but is not limited to, voice communication or email; and
  - (c) may only be used if the primary means of transmitting information described in subclause (1) or (2) is unavailable or otherwise with the agreement of the **system operator**.

Compare: Electricity Governance Rules 2003 clause 4 technical code C schedule C3 part C

Heading: amended, on 5 October 2017, by clause 130(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 5(1): replaced, on 5 October 2017, by clause 130(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 5(2) and (3): amended, on 5 October 2017, by clause 130(3) and (4) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

## **6 Specific requirements for data transmission communication**

- (1) Each **asset owner** (other than a **grid owner**) must have in place—
  - (a) a primary means of transmitting data between the **assets** of the **asset owner** and a **SCADA** remote terminal unit of a **grid owner**; or
  - (b) if approved by the **system operator** (such approval not to be unreasonably withheld), a primary means of transmitting data between the **assets** of the **asset owner** and the **system operator**.
- (2) A **grid owner** must have in place a primary means of transmitting data between the **assets** of the **grid owner** and the **system operator**.
- (3) Each **asset owner** must have in place a backup means of transmitting data for each type of indication and measurement specified in Appendix A of this **technical code**. The backup means of data transmission communication—
  - (a) must be approved by the **system operator** (such approval not to be unreasonably withheld); and
  - (b) may include, but is not limited to, use of voice communication or document transmission communication; and
  - (c) may only be used if the primary means of data transmission communication described in subclause (1) or (2) is unavailable or otherwise with the agreement of the **system operator**.

Compare: Electricity Governance Rules 2003 clause 5 technical code C schedule C3 part C

## **7 Availability of primary means of communication**

- (1) Each **asset owner** must use reasonable endeavours to ensure that the primary means of communication described in clauses 4(1), 5(1) or (2), and 6(1) or (2) is available continuously.
- (2) If the primary means of communication described in clauses 4(1), 5(1) or (2), and 6(1) or (2) is unavailable, an **asset owner** must use reasonable endeavours to restore availability of the primary means of communication as soon as practicable.

Compare: Electricity Governance Rules 2003 clause 6 technical code C schedule C3 part C

## **8 Notification of planned outages of primary means of communication**

Each **asset owner** must give written notice to the **system operator** of any planned outage of a primary means of communication described in clauses 4(1), 5(1) or (2), and 6(1) or (2).

Compare: Electricity Governance Rules 2003 clause 7 technical code C schedule C3 part C

Clause 8: amended, on 5 October 2017, by clause 131 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

## **9 Performance requirements for indications and measurements**

- (1) Each **asset owner** must provide the relevant indications and measurements shown in Appendix A to the **system operator**, in accordance with clause 6. The **system operator** may require the **asset owner** to provide additional information if, in the reasonable opinion of the **system operator**, such information is required for the **system operator** to plan to comply, and to comply, with its **principal performance obligations**.
- (2) The **asset owner** must use reasonable endeavours to ensure that the accuracy of the

measurements it provides to the **system operator** in accordance with subclause (1) complies with Appendix A.

- (3) Each indication and measurement provided in accordance with subclause (1) must be updated at the **grid owner's SCADA** remote terminal or the **system operator's** interface unit at least once every 8 seconds when provided by the primary means of data transmission communications.

Compare: Electricity Governance Rules 2003 clause 8 technical code C schedule C3 part C

*Appendix A: Indications and Measurements  
(Clause 9(1)-(3) of Technical Code C)*

**Table A1: Requirements of generators**

Each **generator** must provide the indications and measurements in Table A1. If net (or gross) measurements are required in Table A1, the use of **scaling factors** together with the provision of the relevant gross (or net) values is acceptable with the **system operator's** approval. Each **generator** must provide **scaling factors** to the **grid owner** so that the **grid owner** can apply the adjustment at the **SCADA** server.

Indication or measurement	Values required	Accuracy <sup>3</sup>
Station net MW	Import and export	±2%
Generating unit gross MW <sup>1</sup>	Import and export, for each <b>generating unit</b>	±2%
Station net Mvar	Import and export	±2%
Generating unit gross Mvar <sup>1</sup>	Import and export, for each <b>generating unit</b>	±2%
Generating unit circuit breaker status <sup>1</sup>	Open /closed /in transition/ indication error <sup>2</sup>	N/A
Grid interface circuit breaker status	Open /closed /in transition/ indication error <sup>2</sup>	N/A
Grid interface disconnecter status	Open /closed /in transition/ indication error	N/A
Special protection scheme status	Enabled/disabled/summer/winter	N/A
Maximum output capacity of <b>generating station</b> (for <b>intermittent generators</b> only)	Number of connected <b>generating units</b> × MW capability of each <b>generating unit</b>	N/A

Compare: Electricity Governance Rules 2003 table A1 appendix A technical code C schedule C3 part C

Table A1: amended, on 23 February 2015, by clause 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Table A1: amended, on 5 October 2017, by clause 132 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

**Table A2: Requirements of grid owners:**

Each **grid owner** must provide the indications and measurements shown in Table A2 in respect of **assets** connected to, or forming part of, the **grid**.

Indication or measurement	Values required	Accuracy <sup>3</sup>
Grid interface circuit breaker status	Open /closed /in transition/ indication error <sup>2</sup>	N/A
Grid interface disconnecter status	Open/ closed/ in transition/ closed to earth/ indication error	N/A
Grid interface auto reclose status	Enabled/disabled/ operated/locked out	N/A
Grid interface MW	Import and export	±2%

Indication or measurement	Values required	Accuracy <sup>3</sup>
<b>Grid interface Mvar</b>	Import and export	±2%
Circuit Amps	Current at each termination point of a circuit	N/A
Circuit MW	MW at each termination point of a circuit	N/A
Circuit Mvar	Mvar at each termination point of a circuit	N/A
<b>Special protection scheme status</b>	Enabled/disabled/summer/winter	N/A
Tap positions for <b>interconnecting transformers</b> and supply transformers with on-load tap changers	Tap position for all windings including tapped tertiaries	N/A
Tap positions for <b>interconnecting transformers</b> and supply transformers with off-load tap changers <sup>4</sup>	Tap position for all windings including tapped tertiaries	N/A
Reactive plant (eg RPC equipment, capacitor, reactor, condenser) Mvar	Import and export	±2%
Bus voltage	kV	±2%
<b>Special protection scheme status</b>	Enabled/disabled/summer/winter	N/A
HVDC modulation status	Frequency stabiliser/ spinning reserve sharing/ Haywards frequency control/ AC transient voltage support	N/A

Compare: Electricity Governance Rules 2003 table A2 appendix A technical code C schedule C3 part C

Table A2: amended, on 23 February 2015, by clause 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Table A2: amended, on 5 October 2017, by clause 133 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### Table A3: Requirements of connected asset owners

Each **connected asset owner** must provide the indications and measurements shown in Table A3 in respect of **assets** connected to, or forming part of, the **grid**.

Indication or measurement	Values required	Accuracy <sup>3</sup>
<b>Grid interface circuit breaker status</b>	Open/ closed/ in transition/ indication error <sup>2</sup>	N/A
<b>Grid interface disconnector status</b>	Open/ closed/ in transition/ indication error	N/A
<b>Grid interface auto reclose status</b>	Enabled/disabled/operated/locked out	N/A
<b>Special protection scheme status</b>	Enabled/disabled/summer/winter	N/A
Reactive plant <sup>5</sup> (eg RPC equipment, capacitor, reactor, condenser) Mvar	Import and export	±2%

Table A3 Heading: amended, on 1 February 2016, by clause 23(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

Table A3: amended, on 23 February 2015, by clause 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Table A3: amended, on 1 February 2016, by clause 23(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

Table A3: amended, on 5 October 2017, by clause 134 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

- <sup>1</sup> Required only if a **generating unit** has a maximum continuous rating of greater than 5 MW.
- <sup>2</sup> No intentional time delays should be included for **circuit breaker** indications as these are time tagged by the **system operator** to less than 10 ms.
- <sup>3</sup> If accuracy is measured at the input terminal of the RTU of the **grid owner**, under normal operating conditions at full scale.
- <sup>4</sup> Indication required within 5 minutes of status change.
- <sup>5</sup> Required only if reactive plant has a maximum continuous rating of greater than 5 Mvar.

Compare: Electricity Governance Rules 2003 table A3 appendix A technical code C schedule C3 part C

*Technical Code D – Co-ordination of outages affecting common quality*

**1 Purpose**

The purpose of this **technical code** is to set out the obligations of **asset owners** to give written notice of planned outages of **assets** that affect **common quality**, and to set out the obligations of the **system operator** in relation to outage co-ordination and the provision of timely advice to **asset owners** on the security implications of **notified planned outages**.

Compare: Electricity Governance Rules 2003 clause 1 technical code D schedule C3 part C  
Clause 1: amended, on 5 October 2017, by clause 135 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

**2 Notice of planned outages**

- (1) Each **asset owner** must, in relation to each of its **assets**, give written notice to the **system operator** as soon as practicable of all planned outages of such **assets** if such outages may impact on the **system operator's** ability to plan to comply, and to comply, with the **principal performance obligations**.
- (2) If the **asset owner** is unsure whether an outage of an **asset** may impact on the **system operator's** ability to plan to comply, and to comply, with the **principal performance obligations**, the **asset owner** must contact the **system operator** for advice.
- (3) Each **asset owner** must give written notice to the **system operator** up to 12 months ahead of planned outages and update the **system operator** of changes to the planned outages as and when the **asset owner** becomes aware of them.

Compare: Electricity Governance Rules 2003 clause 2 technical code D schedule C3 part C  
Heading: amended, on 5 October 2017, by clause 136(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.  
Clause 2(1) and (3): amended, on 5 October 2017, by clause 136(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

**3 Assessment of notified planned outages**

The **system operator** must assess all **notified planned outages** and the extent to which they impact on the **system operator's** ability to plan to comply, and to comply with the **principal performance obligations**.

Compare: Electricity Governance Rules 2003 clause 3 technical code D schedule C3 part C

**4 Assets may be requested to remain in service**

The **system operator** may request that an **asset owner** of **assets** that are the subject of a **notified planned outage** keep those **assets** in service until a more suitable time, if such outage would, in the reasonable opinion of the **system operator**, adversely affect the **system operator's** ability to plan to comply, and to comply, with the **principal performance obligations**. The **system operator** may propose a suitable alternative time for the **notified planned outage**.

Compare: Electricity Governance Rules 2003 clause 4 technical code D schedule C3 part C

**5 Asset owners to assist security**

- (1) An **asset owner** must endeavour to programme its **notified planned outage** at a time when there will be no disruption to the **system operator's** ability to plan to comply, and

to comply, with the **principal performance obligations**.

- (2) The **system operator** may advise an **asset owner** when an appropriate time would be.
- (3) If an **asset owner** is able to modify the **notified planned outage** period for an **asset** in the manner suggested by the **system operator** without material cost or disruption, the **asset owner** must endeavour to do so.

Compare: Electricity Governance Rules 2003 clause 5 technical code D schedule C3 part C

## **6 Asset outage programme**

The **system operator** must regularly publish an **asset** outage programme containing all **notified planned outage** information provided by the **asset owners**.

Compare: Electricity Governance Rules 2003 clause 6 technical code D schedule C3 part C

## **7 Assets may be requested to return to service**

The **system operator** may request an **asset owner** to terminate a **notified planned outage** in progress within a pre-arranged period so that **assets** that are the subject of the **notified planned outage** can be returned to service to support the **system operator** in planning to comply, and in complying, with the **principal performance obligations**.

Compare: Electricity Governance Rules 2003 clause 7 technical code D schedule C3 part C



**Schedule 8.4**  
***[Revoked]***

cl 7.2

Compare: Electricity Governance Rules 2003 schedule C6 part C  
Schedule 8.4: revoked, on 19 May 2016, by clause 30 of the Electricity Industry Participation Code Amendment (System Operator and Alignment with Statutory Objective) 2016.

## Schedule 8.5

cl 8.54D(7), 8.54E(4)(b), 8.54F(2)(b)(ii),  
8.54G(4), 8.54I(2), 8.54J(8), (9)

### Consultation and approval requirements for extended reserve procurement documents

#### Part 1

#### Consultation on extended reserve technical requirements schedule

##### 1 Application of this Part

This Part sets out the consultation requirements that apply to the **extended reserve technical requirements schedule**.

##### 2 Publication of extended reserve technical requirements schedule

- (1) The **system operator** must prepare a draft of the **extended reserve technical requirements schedule**.
- (2) The **system operator** must give the draft schedule to the **Authority** for comment, along with the **extended reserve technical requirements report**.
- (3) The **Authority** must provide comments on the draft schedule to the **system operator** as soon as practicable after receiving it.
- (4) The **system operator** must consider the **Authority's** comments.
- (5) After the **system operator** has considered the **Authority's** comments, the **system operator** must—
  - (a) consult with persons that the **system operator** thinks are representative of the interests of persons likely to be substantially affected by the draft schedule; and
  - (b) consider submissions made on the draft schedule.
- (6) The **system operator** must give a copy of each submission made to it and a copy of the draft schedule that the **system operator** proposes to **publish** to the **Authority**.
- (7) The **Authority** must provide comments on the draft schedule as soon as practicable after receiving it.
- (8) The **system operator** must consider the **Authority's** comments.
- (9) Following the consultation required by this clause, the **system operator** must finalise and **publish** the draft schedule.

##### 3 Technical and non-controversial changes

- (1) The **system operator** may at any time make a change to the **extended reserve technical requirements schedule** that it considers is technical and non-controversial.
- (2) If the **system operator** makes a change to the **extended reserve technical requirements schedule** under subclause (1), the **system operator** is not required to comply with clause 2 of this Schedule.
- (3) The **system operator** must give written notice to the **Authority** of any changes to the **extended reserve technical requirements schedule** made under this clause.

Clause 3(3): amended, on 19 December 2014, by clause 16 of the Electricity Industry Participation Code Amendment (Minor Code Amendments) (No 3) 2014.

Clause 3(3): amended, on 5 October 2017, by clause 137 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

## Part 2

### Consultation on extended reserve selection methodology

#### 4 Application of this Part

This Part sets out the consultation and approval requirements that apply to the **extended reserve selection methodology**.

#### 5 Preparation of and consultation on extended reserve selection methodology

- (1) The **extended reserve manager** must prepare a draft of the **extended reserve selection methodology**.
- (2) The **extended reserve manager** must give the draft methodology to the **Authority** and the **system operator** for comment, along with one or more worked examples of an **extended reserve procurement schedule**, created using—
  - (a) the draft **extended reserve selection methodology**; and
  - (b) data specified by the **system operator**.
- (3) The **Authority** and the **system operator** must provide comments on the draft methodology to the **extended reserve manager** as soon as practicable after receiving it.
- (4) The **extended reserve manager** must consider the comments provided by the **Authority** and the **system operator**.
- (5) After the **extended reserve manager** has considered the comments provided by the **Authority** and the **system operator**, the **extended reserve manager** must—
  - (a) consult with persons that the **extended reserve manager** thinks are representative of the interests of persons likely to be substantially affected by the draft methodology; and
  - (b) consider submissions made on the draft methodology.

#### 6 Approval of extended reserve selection methodology

- (1) The **extended reserve manager** must give the **Authority** and the **system operator**—
  - (a) a copy of each submission made on the draft **extended reserve selection methodology**; and
  - (b) a response to each issue raised in each submission; and
  - (c) a copy of the draft methodology that the **extended reserve manager** proposes to **publish**.
- (2) As soon as practicable, but no later than 15 **business days** after receiving a copy of the draft methodology, the **system operator** must—
  - (a) give the **Authority** any comments it wishes to make on the draft methodology; or
  - (b) advise the **Authority** that it does not wish to make any comments.
- (3) As soon as practicable after receiving the **system operator's** comments, or advice that the **system operator** does not wish to make any comments, the **Authority** must, by notice in writing to the **extended reserve manager** and the **system operator**,—
  - (a) approve the draft methodology; or

- (b) decline to approve the draft methodology.
- (4) If the **Authority** declines to approve the draft methodology, the **Authority** must either—
  - (a) **publish** the changes that the **Authority** wishes the **extended reserve manager** to make to the draft methodology; or
  - (b) require the **extended reserve manager** to prepare a new draft methodology.

Clause 6(4)(a): amended, on 5 October 2017, by clause 138 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

## **7 Consultation on proposed changes**

- (1) When the **Authority publishes** changes that the **Authority** wishes the **extended reserve manager** to make to the draft **extended reserve selection methodology** under clause 6(4), the **Authority** must advise the **extended reserve manager** and interested parties of the date by which submissions on the changes must be made to the **Authority**.
- (2) Each submission on the changes to the draft methodology must be made in writing to the **Authority** and be received by the date specified by the **Authority**.
- (3) The **Authority** must—
  - (a) give a copy of each submission made to the **extended reserve manager**; and
  - (b) **publish** the submissions.
- (4) The **extended reserve manager** may make its own submission on the changes to the draft methodology and the submissions made in relation to the changes.
- (5) The **Authority** must **publish** the **extended reserve manager's** submission when it is received.
- (6) The **Authority** must consider the submissions made to it on the changes to the draft methodology and prepare a revised draft methodology incorporating any amendments that the **Authority** proposes be made to the methodology.
- (7) The **Authority** must give the revised draft methodology prepared under subclause (6) to the **system operator**, and clause 6(2) applies as if the revised draft methodology was the draft methodology prepared under clause 5.
- (8) As soon as practicable after receiving the **system operator's** comments, or advice that the **system operator** does not wish to make any comments, the **Authority** must,—
  - (a) by notice in writing to the **extended reserve manager** and the **system operator**,—
    - (i) approve the revised draft methodology; or
    - (ii) amend the revised draft methodology to address any comments received from the **system operator**, and approve it; or
  - (b) **publish** a further revised draft methodology, and advise the **extended reserve manager** and interested parties of the date by which submissions on the changes must be made to the **Authority**.
- (9) If the **Authority publishes** a further revised draft methodology under subclause (8)(b), subclauses (2) to (8) apply as if the further revised draft methodology was the revised draft methodology.

Clause 7(1): amended, on 19 December 2014, by clause 17 of the Electricity Industry Participation Code Amendment (Minor Code Amendments) (No 3) 2014.

Clause 7(1) and (9): amended, on 5 October 2017, by clause 139(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 7(3)(b), (5) and (8)(b): amended, on 5 October 2017, by clause 139(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 7(8)(b): amended, on 19 December 2014, by clause 17 of the Electricity Industry Participation Code Amendment (Minor Code Amendments) (No 3) 2014.

## **8 Technical and non-controversial changes**

- (1) The **extended reserve manager** may at any time propose a change to the **extended reserve selection methodology** that it considers is technical and non-controversial by giving a draft methodology to the **Authority** together with an explanation of the proposed change.
- (2) If the **extended reserve manager** gives a draft methodology to the **Authority** under subclause (1) the **extended reserve manager** is not required to comply with clauses 5 and 6 of this Schedule.
- (3) The **Authority** must give written notice to the **system operator** of any proposed change to the **extended reserve selection methodology** that it receives under subclause (1).
- (4) The **Authority** must, as soon as practicable after receiving a draft methodology and the information required by subclause (1), by notice in writing to the **extended reserve manager** and the **system operator**—
  - (a) approve the draft methodology; or
  - (b) decline to approve the draft methodology, giving reasons.

Clause 8(3): amended, on 19 December 2014, by clause 18 of the Electricity Industry Participation Code Amendment (Minor Code Amendments) (No 3) 2014.

Clause 8(3): amended, on 5 October 2017, by clause 140 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

## **9 Publication of extended reserve selection methodology**

As soon as practicable after the **Authority** approves the **extended reserve selection methodology** under clause 6(3)(a), 7(8)(a), or 8(4)(a), the **extended reserve manager** must **publish** the methodology.

Clause 9: amended, on 5 October 2017, by clause 141 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

## **Part 3**

### **Consultation on extended reserve procurement schedule**

## **10 Application of this Part**

This sets out the consultation and approval requirements that apply to the **extended reserve procurement schedule**.

## **11 Preparation of and consultation on extended reserve procurement schedule**

- (1) The **extended reserve manager** must prepare a draft of the **extended reserve procurement schedule**.
- (2) The **extended reserve manager** must—
  - (a) give the draft to the **Authority** and the **system operator** for comment; and
  - (b) if requested, give the **Authority** or the **system operator** the information used by the **extended reserve manager** to prepare the draft.

- (3) The **Authority** and the **system operator** must provide comments on the draft procurement schedule to the **extended reserve manager** as soon as practicable after receiving it.
- (4) The **extended reserve manager** must consider the comments provided by the **Authority** and the **system operator**.
- (5) After the **extended reserve manager** has considered the comments provided by the **Authority** and the **system operator**, the **extended reserve manager** must—
  - (a) consult with persons that the **extended reserve manager** thinks are representative of the interests of persons likely to be substantially affected by the draft procurement schedule; and
  - (b) consider submissions made on the draft procurement schedule.

## **12 Approval of extended reserve procurement schedule**

- (1) The **extended reserve manager** must give the **Authority** and the **system operator**—
  - (a) a copy of each submission made on the draft **extended reserve procurement schedule**; and
  - (b) a response to each issue raised by each submission; and
  - (c) a copy of the draft procurement schedule that the **extended reserve manager** proposes to **publish**.
- (2) As soon as practicable, but no later than 15 **business days** after receiving a copy of the draft procurement schedule, the **system operator** must—
  - (a) give the **Authority** any comments it wishes to make on the draft procurement schedule; or
  - (b) advise the **Authority** that it does not wish to make any comments.
- (3) As soon as practicable after receiving the **system operator's** comments, or advice that the **system operator** does not wish to make any comments, the **Authority** must, by notice in writing to the **extended reserve manager** and the **system operator**,—
  - (a) approve the draft procurement schedule; or
  - (b) decline to approve the draft procurement schedule.
- (4) If the **Authority** declines to approve the draft procurement schedule, the **Authority** must either—
  - (a) **publish** the changes that the **Authority** wishes the **extended reserve manager** to make to the draft procurement schedule; or
  - (b) require the **extended reserve manager** to prepare a new draft procurement schedule.

Clause 12(4)(a): amended, on 5 October 2017, by clause 142 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

## **13 Consultation on proposed changes**

- (1) When the **Authority publishes** changes that the **Authority** wishes the **extended reserve manager** to make to the draft **extended reserve procurement schedule** under clause 12(4), the **Authority** must advise the **extended reserve manager** and interested parties of the date by which submissions on the changes must be made to the **Authority**.
- (2) Each submission on the changes to the draft procurement schedule must be made in

- writing to the **Authority** and be made by the date advised by the **Authority**.
- (3) The **Authority** must—
- (a) give a copy of each submission made to the **extended reserve manager**; and
  - (b) **publish** the submissions.
- (4) The **extended reserve manager** may make its own submission on the changes to the draft procurement schedule and the submissions made in relation to the changes.
- (5) The **Authority** must **publish** the **extended reserve manager's** submission when it is received.
- (6) The **Authority** must consider the submissions made to it on the changes to the draft procurement schedule and prepare a revised draft procurement schedule incorporating any amendments that the **Authority** proposes be made to the schedule.
- (7) The **Authority** must give the revised draft procurement schedule prepared under subclause (6) to the **system operator**, and clause 12(2) applies as if the revised draft procurement schedule was the draft procurement schedule prepared under clause 11.
- (8) As soon as practicable after receiving the **system operator's** comments, or advice that the **system operator** does not wish to make any comments, the **Authority** must,—
- (a) by notice in writing to the **extended reserve manager** and the **system operator**,—
    - (i) approve the revised draft procurement schedule; or
    - (ii) amend the revised draft procurement schedule to address any comments received from the **system operator**, and approve it; or
  - (b) **publish** a further revised draft procurement schedule, and advise the **extended reserve manager** and interested parties of the date by which submissions on the changes must be made to the **Authority**.
- (9) If the **Authority publishes** a further revised draft procurement schedule under subclause (8)(b), subclauses (2) to (8) apply as if the further revised draft procurement schedule was the revised procurement schedule.

Clause 13(1) and (8)(b): amended, on 19 December 2014, by clause 19(1) of the Electricity Industry Participation Code Amendment (Minor Code Amendments) (No 3) 2014.

Clause 13(2): amended, on 19 December 2014, by clause 19(2) of the Electricity Industry Participation Code Amendment (Minor Code Amendments) (No 3) 2014.

Clause 13(1), (3)(b), (5), (8)(b) and (9): amended, on 5 October 2017, by clause 143 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

## 14 Publication of extended reserve procurement schedule

As soon as practicable after the **Authority** approves the **extended reserve procurement schedule** under clause 12(3)(a) or 13(8)(a), the **extended reserve manager** must **publish** the schedule.

Schedule 8.5: inserted, on 7 August 2014, by clause 22 of the Electricity Industry Participation Code Amendment (Extended Reserve) 2014.

# Electricity Industry Participation Code 2010

## Part 9 Security of supply

### Contents

#### Subpart 1—Planning for shortage of supply situations

##### 9.1 Purpose

##### *System operator rolling outage plan*

##### 9.2 System operator must prepare and publish system operator rolling outage plan

##### 9.3 Incorporation of system operator rolling outage plan by reference

##### 9.4 Contents of system operator rolling outage plan

##### 9.5 Amendments and substitutions of system operator rolling outage plans

##### *Participant rolling outage plans*

##### 9.6 System operator must require specified participants to develop participant rolling outage plans

##### 9.7 Specified participants must develop participant rolling outage plans

##### 9.8 Contents of participant rolling outage plans

##### 9.9 Approval of participant rolling outage plans

##### 9.10 Revision of participant rolling outage plans

##### 9.11 Approval of revised participant rolling outage plans

##### 9.12 Publishing of participant rolling outage plans

##### 9.13 Specified participants must keep participant rolling outage plans up to date

#### Subpart 1A—Urgent temporary grid reconfigurations

##### 9.13A Purpose

##### 9.13B Request for urgent temporary grid reconfiguration

#### Subpart 2—Outages in shortage of supply situation

##### 9.14 Supply shortage declaration

##### 9.15 Power to direct outages in security of supply situation

##### 9.16 Specified participants must comply with direction

##### 9.17 Revocation of supply shortage declaration

#### Subpart 3—Miscellaneous

##### 9.18 Provision of information

#### Subpart 4—Customer compensation schemes

##### 9.19 Contents of this subpart

##### *Requirement for retailers to have customer compensation scheme*

##### 9.20 Retailer must have customer compensation scheme

##### 9.21 Qualifying customers

##### 9.22 Requirement to implement customer compensation schemes

##### *Official conservation campaign*

##### 9.23 System operator commences official conservation campaign

##### *Default customer compensation scheme*

##### 9.24 Requirements of default customer compensation schemes



*Minimum weekly amount of compensation*

- 9.25 Authority must determine minimum weekly amount

*Additional customer compensation schemes*

- 9.26 Retailer may have additional customer compensation schemes  
9.27 Qualifying customer may elect to be covered by additional customer compensation scheme  
9.28 Publishing description of additional customer compensation schemes

*Certificate of compliance*

- 9.29 Each retailer must provide certification

*Audit*

- 9.30 Audit of compliance  
9.31 Retailer must provide information to auditor  
9.32 Auditor must provide audit report  
9.33 Payment of auditor's costs
- 

Subpart 1— Planning for shortage of supply situations

**9.1 Purpose**

The purpose of this subpart and subpart 2 is to provide for the management and co-ordination of planned outages as an emergency measure during energy shortages.

Compare: SR 2008/252 r 3

*System operator rolling outage plan*

**9.2 System operator must prepare and publish system operator rolling outage plan**

- (1) The **system operator** must prepare and **publish** a **system operator rolling outage plan**.  
(2) Before **publishing** a **system operator rolling outage plan** the **system operator** must submit to the **Authority** for approval a draft **system operator rolling outage plan**.  
(3) Clause 7.5(3) to (11) applies to the approval of the **system operator rolling outage plan** by the **Authority** as if references to the **security of supply forecasting and information policy** and the **emergency management policy** were a reference to the **system operator rolling outage plan**.

Compare: SR 2008/252 r 5

**9.3 Incorporation of system operator rolling outage plan by reference**

- (1) The **system operator rolling outage plan** is incorporated by reference in this Code in accordance with section 32 of the **Act**.  
(2) Subclause (1) is subject to Schedule 1 of the **Act**, which includes a requirement that the **Authority** must give notice in the *Gazette* before an amended or substituted **system operator rolling outage plan** becomes incorporated by reference in this Code.

Clause 9.3(1): amended, on 5 October 2017, by clause 144 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

#### 9.4 Contents of system operator rolling outage plan

A **system operator rolling outage plan** must—

- (a) describe events that the **system operator** predicts will be likely to give rise to the need to make a **supply shortage declaration**; and
- (b) set out thresholds that the **system operator** will apply in deciding whether to make a **supply shortage declaration**; and
- (c) specify how the **system operator** intends to determine what directions to give to address the shortage of **electricity** supply or transmission capacity that gives rise to the declaration; and
- (d) identify **specified participants**, or a class or classes of **specified participants**, who are required to develop **participant rolling outage plans** under clauses 9.6 to 9.13; and
- (e) specify criteria, methodologies, and principles to be applied in implementing outages, or taking any other action, to be provided for in **participant rolling outage plans**; and
- (f) specify criteria, methodologies, and principles to be applied by any **specified participant** who does not have an approved **participant rolling outage plan** in implementing outages, or taking any other action, in accordance with directions given by the **system operator** under clause 9.15.

Compare: SR 2008/252 r 6

#### 9.5 Amendments and substitutions of system operator rolling outage plans

- (1) The **system operator** may—
  - (a) amend a **system operator rolling outage plan**; or
  - (b) revoke a **system operator rolling outage plan** and substitute a new plan.
- (2) This subpart applies to an amendment to a plan or a substitute plan—
  - (a) as if the amendment or substitute plan were the original plan; and
  - (b) with other necessary modifications.
- (3) The **system operator** must not submit an amended or new **system operator rolling outage plan** to the **Authority** under clause 9.2(2) unless the **system operator** has—
  - (a) consulted with persons that the **system operator** thinks are representative of the interests of persons likely to be substantially affected by the amended or new plan; and
  - (b) considered submissions made on the amended or new plan.
- (4) Subclause (3) does not apply if the **system operator** considers that it is necessary or desirable in the public interest that the proposed **system operator rolling outage plan** be **published** urgently, and, in this case, the **system operator rolling outage plan** must state that the plan is **published** in reliance on this subclause and then, within 6 months of the plan being **published**, the **system operator** must—
  - (a) comply with subclause (3); and
  - (b) decide whether or not the plan should be amended or revoked and a new plan substituted; and

- (c) no later than 10 **business days** after making that decision, **publish** the decision; and
  - (d) if the **system operator** decides that the plan should be amended or revoked and a new plan substituted, comply with this clause in relation to the proposed amendment or revocation and substitution.
- (5) To avoid doubt, a **system operator rolling outage plan** is not invalid only because the **system operator** did all or any of the things referred to in subclause (3) before this clause came into force.

Compare: SR 2008/252 r 7 and 8

Clause 9.5(4): amended, on 5 October 2017, by clause 145(a) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 9.5(4)(c): amended, on 5 October 2017, by clause 145(b) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### *Participant rolling outage plans*

#### **9.6 System operator must require specified participants to develop participant rolling outage plans**

- (1) This clause applies when a **specified participant** is identified under a **system operator rolling outage plan** as being required to develop a **participant rolling outage plan**.
- (2) The **system operator** must send notice in writing to that **specified participant** of that requirement, including—
  - (a) specifying the requirements that the **participant rolling outage plan** must comply with under this Part and the **system operator rolling outage plan**; and
  - (b) specifying a date by which the **specified participant** must submit that plan to the **system operator**.
- (3) The **system operator** must send the notice under subclause (2) as soon as practicable after the **system operator publishes** its **system operator rolling outage plan**.

Compare: SR 2008/252 r 8A

#### **9.7 Specified participants must develop participant rolling outage plans**

- (1) Each **specified participant** who receives a notice under clause 9.6 must develop its **participant rolling outage plan** in accordance with the notice.
- (2) The **specified participant** must submit the plan to the **system operator** by the date specified under clause 9.6(2)(b).

Compare: SR 2008/252 r 8B

#### **9.8 Contents of participant rolling outage plans**

- (1) Each **participant rolling outage plan** must—
  - (a) be consistent with the **system operator rolling outage plan**; and
  - (b) comply with the requirements specified in the notice sent under clause 9.6(2)(a); and
  - (c) specify the actions that the **specified participant** will take to achieve, or contribute to achieving, reductions in the consumption of **electricity** (including any target level of reduction of consumption of **electricity** in accordance with criteria, methodologies, and principles specified in the **system operator rolling**

**outage plan**) to comply with a direction from the **system operator** given under clause 9.15.

- (2) This clause does not limit clause 9.6(2)(a).

Compare: SR 2008/252 r 8C

### 9.9 Approval of participant rolling outage plans

- (1) The **system operator** must, as soon as practicable after receiving a **participant rolling outage plan**, by notice in writing to the **specified participant** who submitted the plan,—

- (a) approve it; or
- (b) decline to approve it.

- (2) The **system operator** may decline to approve the plan only if the **system operator** is not satisfied that the plan complies with clause 9.8.

Compare: SR 2008/252 r 8D

### 9.10 Revision of participant rolling outage plans

If the **system operator** declines to approve a **participant rolling outage plan**,—

- (a) the **system operator** must—
  - (i) indicate the grounds on which it declines to approve the plan; and
  - (ii) direct the **specified participant** to submit a revised plan; and
- (b) the **specified participant** must submit a revised plan to the **system operator** no later than—
  - (i) 15 **business days** after the date on which the **specified participant** received the direction from the **system operator** to submit a revised plan; or
  - (ii) any later date that the **system operator** may allow in any particular case.

Compare: SR 2008/252 r 8E

Clause 9.10(b)(i): amended, on 5 October 2017, by clause 146 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### 9.11 Approval of revised participant rolling outage plans

- (1) As soon as practicable after receiving a revised **participant rolling outage plan**, the **system operator** must, by notice in writing to the **specified participant** who submitted the plan,—

- (a) approve the plan; or
- (b) decline to approve it.

- (2) If the **system operator** declines to approve the revised plan, clause 9.10 applies.

Compare: SR 2008/252 r 8F

### 9.12 Publishing of participant rolling outage plans

A **specified participant** must make its **participant rolling outage plan** available to the public, at no cost, on an Internet site maintained by or on behalf of the **specified participant**, at all reasonable times, as soon as practicable after it is approved by the **system operator**.

Compare: SR 2008/252 r 8G

### 9.13 Specified participants must keep participant rolling outage plans up to date

- (1) Each **specified participant** who has had a **participant rolling outage plan** approved under clauses 9.6 to 9.12 must—
  - (a) keep the plan under review, and (if necessary) amend the plan to take account of any change of circumstances and to ensure that the plan continues to comply with clause 9.8; and
  - (b) as soon as practicable after amending the plan, but in any case no later than 20 **business days** after amending it, submit the plan to the **system operator**.
- (2) Despite subclause (1), not later than 2 years after the date on which a **specified participant's participant rolling outage plan** was last approved, the **specified participant** must resubmit the plan to the **system operator** for approval.
- (3) A plan submitted to the **system operator** under subclause (1)(b) is deemed to be approved by the **system operator** unless, no later than 20 **business days** after the **system operator** receives the plan, the **system operator** advises the **specified participant** who submitted the plan, by notice in writing, that it declines to approve the plan.
- (4) Clauses 9.9 to 9.12 apply to a plan that is submitted or resubmitted or declined under this clause, except as provided in subclause (3).

Compare: SR 2008/252 r 8H

Clause 9.13(1)(b) and (3): amended, on 5 October 2017, by clause 147 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### Subpart 1A—Urgent temporary grid reconfigurations

Heading: inserted, on 16 December 2013, by clause 4 of the Electricity Industry Participation (Urgent Temporary Grid Reconfiguration) Code Amendment 2013.

#### 9.13A Purpose

The purpose of this subpart is to provide for the urgent temporary removal of **interconnection assets** from service, or temporary reconfiguration of the **grid**, in order to improve security of **supply**.

Clause 9.13A: inserted, on 16 December 2013, by clause 4 of the Electricity Industry Participation (Urgent Temporary Grid Reconfiguration) Code Amendment 2013.

#### 9.13B Request for urgent temporary grid reconfiguration

- (1) The **system operator** may give notice in writing to **Transpower** requesting that **Transpower** temporarily remove 1 or more **interconnection assets** from service, or temporarily reconfigure the **grid**, if the **system operator** considers that—
  - (a) exceptional circumstances exist—
    - (i) that are likely to lead, for a period of at least 3 weeks, to—
      - (A) a shortfall in thermal fuel; or
      - (B) a shortfall of hydro inflows; or
      - (C) the loss of a large generating **asset**; and
    - (ii) that make it necessary or desirable in the public interest to temporarily remove 1 or more **interconnection assets** from service or temporarily reconfigure the **grid**; and
  - (b) the removal or reconfiguration would improve security of **supply**.

- (2) A notice given under subclause (1) must specify—
  - (a) the exceptional circumstances; and
  - (b) the reasons why temporarily removing **assets** from service or temporarily reconfiguring the **grid** would improve security of **supply**.
- (3) No later than 10 **business days** after giving notice to **Transpower**, the **system operator** must give a written report to the **Authority** setting out the basis on which the **system operator** requested that **Transpower** remove 1 or more **interconnection assets** from service or temporarily reconfigure the **grid**.
- (4) The **system operator** must ensure that the report given under subclause (3) includes—
  - (a) the matters specified in subclause (2)(a) and (b); and
  - (b) sufficient information to demonstrate that in developing its request to **Transpower** the **system operator** followed a robust process, including the options the **system operator** considered and the extent of any analysis and consultation undertaken by the **system operator**.
- (5) The **Authority** must **publish** the report.  
Clause 9.13B: inserted, on 16 December 2013, by clause 4 of the Electricity Industry Participation (Urgent Temporary Grid Reconfiguration) Code Amendment 2013.  
Clause 9.13B(5): amended, on 5 October 2017, by clause 148 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

## Subpart 2—Outages in shortage of supply situation

### 9.14 Supply shortage declaration

- (1) The **system operator** may, after consultation with the **Authority**, make a **supply shortage declaration**.
- (2) The **system operator** may make a **supply shortage declaration** only if there is a shortage of **electricity** supply or transmission capacity such that the **system operator** considers—
  - (a) that the normal operation of the spot market for **electricity** is, or will soon be, unlikely to facilitate the adjustment of supply and demand necessary to ensure that supply matches demand; and
  - (b) that, if planned outages are not implemented, unplanned outages are likely.
- (2A) For the purposes of subclause (2), the spot market for **electricity** includes the processes for setting—
  - (a) **real time prices**;
  - (b) **forecast prices** and **forecast reserve prices**;
  - (c) **provisional prices** and **provisional reserve prices**;
  - (d) **interim prices** and **interim reserve prices**;
  - (e) **final prices** and **final reserve prices**.
- (3) A declaration applies to—
  - (a) all of New Zealand; or
  - (b) the regions specified in the declaration.
- (4) In making a declaration under subclause (1), the **system operator** must have regard to the **system operator rolling outage plan**.
- (5) The **system operator** must **publish** the declaration as soon as practicable after it is made.

Compare: SR 2008/252 r 9

Clause 9.14(2)(a): amended, on 18 July 2013, by clause 8(1) of the Electricity Industry Participation (Undesirable Trading Situation) Code Amendment 2013.

Clause 9.14(2A): inserted, on 18 July 2013, by clause 8(2) of the Electricity Industry Participation (Undesirable Trading Situation) Code Amendment 2013.

### 9.15 Power to direct outages in security of supply situation

- (1) The **system operator** may, at any time in the period during which a **supply shortage declaration** is in force, give a written direction to **specified participants** to contribute to achieving reductions in the consumption of **electricity** by implementing outages or taking any other action specified in the direction.
- (2) A direction must—
  - (a) be consistent with the **system operator rolling outage plan**; and
  - (b) be given only after consultation with the **Authority**; and
  - (c) if the direction requires a **specified participant** to implement outages, specify the savings targets that the **specified participant** must achieve.
- (3) *[Revoked]*
- (4) The **system operator** must **publish** each direction as soon as practicable after it is given.
- (5) The **system operator** may—
  - (a) amend a direction; or
  - (b) revoke a direction and, if the **system operator** considers it appropriate, substitute a new direction.
- (6) Subclauses (1) to (4) apply to an amendment to a direction or a substitute direction—
  - (a) as if the amendment or substitute direction were the original direction; and
  - (b) with other necessary modifications.

Compare: SR 2008/252 r 10

Clause 9.15(1): amended, on 5 October 2017, by clause 149(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 9.15(3): revoked, on 5 October 2017, by clause 149(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 9.15(4): amended, on 5 October 2017, by clause 149(3) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### 9.16 Specified participants must comply with direction

- (1) Each **specified participant** must comply with a direction given to it by the **system operator** under clause 9.15.
- (2) Each **specified participant** must, in complying with the direction, apply, to the extent practicable, the criteria, methodologies, and principles specified in the **system operator rolling outage plan**.
- (3) Each **specified participant** must comply with a direction in accordance with its **participant rolling outage plan**, if it has a plan that has been approved under subpart 1.
- (4) If a **specified participant** does not have a **participant rolling outage plan** approved under subpart 1, the **specified participant**,—
  - (a) in complying with the direction, must apply, to the extent practicable, the criteria, methodologies, and principles specified in the **system operator rolling outage plan**; and

- (b) as soon as practicable after the direction is given, must provide to the **system operator** information as to the steps the **specified participant** will take to comply with the direction (including any steps the **specified participant** has already taken to comply with the direction).

Compare: SR 2008/252 r 11

#### 9.17 Revocation of supply shortage declaration

- (1) The **system operator** must revoke a **supply shortage declaration** when it is satisfied that the circumstances that gave rise to the declaration no longer apply.
- (2) The **system operator** must **publish** the revocation as soon as practicable after it is made.

Compare: SR 2008/252 r 13

### Subpart 3—Miscellaneous

#### 9.18 Provision of information

- (1) The **system operator** may, by notice in writing to a **participant** who the **system operator** considers may have information relevant to any of the following, require the **participant** to provide the information to the **system operator**:
  - (a) the preparation by the **system operator** of the **system operator rolling outage plan** under clauses 9.1 to 9.5; and
  - (b) the need for a **supply shortage declaration**; and
  - (c) the need for a direction requiring outages under clause 9.15; and
  - (d) the number and extent of outages necessary under a direction; and
  - (e) monitoring compliance with a direction given under clause 9.15.
- (2) Subclause (1) applies only to information that is—
  - (a) reasonably necessary for the **system operator** to undertake its functions under this Part or to monitor compliance with a direction regarding outages; and
  - (b) in that **participant's** possession or that the **participant** can obtain without unreasonable difficulty or expense.
- (3) The **system operator** must specify in the notice given under subclause (1) the date by which the **participant** must provide the information required.
- (4) A **participant** who has received a notice under subclause (1) must provide the information required by the **system operator** by the date specified by the **system operator** in the notice.
- (5) The **system operator** may require **specified participants** to provide to the **system operator** contact information specified by the **system operator** that would enable the **system operator** to communicate with the **specified participants**.

Compare: SR 2008/252 r 14



## Subpart 4—Customer compensation schemes

Subpart 4: inserted, on 1 April 2011, by clause 5 of the Electricity Industry Participation (Customer Compensation Schemes) Code Amendment 2011.

### 9.19 Contents of this subpart

This subpart provides a framework under which each **retailer** must have a **customer compensation scheme** for all of the **retailer's qualifying customers**, including—

- (a) a **default customer compensation scheme** that a **retailer** must have; and
- (b) **additional customer compensation schemes** that a **retailer** may have; and
- (c) determining when a **public conservation period** commences and ends, during which a **retailer** must make payments under its **customer compensation schemes**; and
- (d) a process by which the **Authority** can require that a **retailer's** compliance with this subpart is **audited**.

Clause 9.19: inserted, on 1 April 2011, by clause 5 of the Electricity Industry Participation (Customer Compensation Schemes) Code Amendment 2011.

#### *Requirement for retailers to have customer compensation scheme*

### 9.20 Retailer must have customer compensation scheme

- (1) Each **retailer** who has 1 or more **qualifying customers**—
  - (a) must, at all times, have a **default customer compensation scheme**; and
  - (b) may, in addition to a **default customer compensation scheme**, have 1 or more **additional customer compensation schemes**.
- (2) Each of a **retailer's qualifying customers** must be covered by the **retailer's default customer compensation scheme**, unless the **retailer's qualifying customer** has elected to be covered by 1 of the **retailer's additional customer compensation scheme** (if any) in accordance with clause 9.27.
- (3) A **retailer's customer compensation scheme** may cover a **customer** who is not a **qualifying customer**.

Clause 9.20: inserted, on 1 April 2011, by clause 5 of the Electricity Industry Participation (Customer Compensation Schemes) Code Amendment 2011.

### 9.21 Qualifying customers

- (1) A **retailer's qualifying customer** is a person who, as at the end of the last day of a **public conservation period**, —
  - (a) is a **customer** of the **retailer**; and
  - (b) has a contract with the **retailer** for the supply of **electricity** in respect of an **ICP** at which—
    - (i) there is a **category 1 metering installation** or a **category 2 metering installation**; and
    - (ii) there was consumption, in the 12 months immediately before the start of the **public conservation period**, of 3000 kWh or more.
- (2) Despite subclause (1), a person is not a **qualifying customer** if the price of all of the **electricity** provided under the person's contract with the **retailer** for the supply of **electricity** is determined by reference to the **final price** at a **GXP**.

- (3) For the purposes of subclause (1)(b)(ii), if a **qualifying customer's** consumption at the **ICP** in the 12 months immediately before the start of the **public conservation period** is not available to the **retailer**, the **retailer** must make a reasonable estimate of the consumption.
- (4) To avoid doubt,—
- (a) there is no **qualifying customer** at an **ICP** if, at the end of the last day of a **public conservation period**,—
- (i) the premises to which the **ICP** is **electrically connected** are vacant; or
- (ii) the **ICP** is **electrically disconnected**:
- (b) a **retailer's qualifying customers** includes a **customer** who switched—
- (i) to the **retailer** from another **retailer** on or before the last day of a **public conservation period**, including during that **public conservation period**; or
- (ii) from the **retailer** to another **retailer** between the last day of a **public conservation period** and the date on which the **retailer** pays compensation under the **customer compensation scheme**.

Clause 9.21: inserted, on 1 April 2011, by clause 5 of the Electricity Industry Participation (Customer Compensation Schemes) Code Amendment 2011.

Clause 9.21: amended, on 5 October 2017, by clause 150(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 9.21(1)(b)(i): amended, on 1 December 2011, by clause 6 of the Electricity Industry Participation Code (Distributor Use-of-System Agreements and Distributor Tariffs) Amendment 2011.

Clause 9.21(1)(b)(ii): amended, on 5 October 2017, by clause 150(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 9.21(3): amended, on 5 October 2017, by clause 150(3) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 9.21(4)(a)(i) and (ii): amended, on 5 October 2017, by clause 150(4)(a) and (b) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 9.21(4)(b)(i): amended, on 5 October 2017, by clause 150(4)(c) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

## 9.22 Requirement to implement customer compensation schemes

- (1) A **retailer** must make payments to its **qualifying customers**, in respect of **ICPs** described in clause 9.21(1)(b), under its **customer compensation schemes** during a **public conservation period**.
- (2) Despite subclause (1), if a **public conservation period** is running because the **system operator** has commenced an **official conservation campaign** under clause 9.23(1), a **retailer** must make payments under its **customer compensation scheme** to its **qualifying customers** only in respect of **ICPs**, as described in clause 9.21(1)(b), in the South Island.

Clause 9.22: inserted, on 1 April 2011, by clause 5 of the Electricity Industry Participation (Customer Compensation Schemes) Code Amendment 2011.

Clause 9.22(2): amended, on 21 September 2012, by clause 12 of the Electricity Industry Participation (Minor Amendments) Code Amendment 2012.

### *Official conservation campaign*

## 9.23 System operator commences official conservation campaign

- (1) The **system operator** must commence an **official conservation campaign** for the South Island—

- (a) when a comparison of storage in the South Island hydro lakes with the South Island hydro risk curves, as that term is defined in the **security of supply forecasting and information policy**,—
    - (i) shows a risk of shortage for the South Island of 10% or more; and
    - (ii) forecasts that the risk of shortage for the South Island will be 10% or more for 1 week or more; or
  - (b) despite paragraph (a), if it has agreed a date with the **Authority** for an **official conservation campaign** to commence for the South Island, on that date.
- (2) The **system operator** must commence an **official conservation campaign** for New Zealand—
  - (a) when a comparison of storage in New Zealand's hydro lakes with the hydro risk curves, as that term is defined in the **security of supply forecasting and information policy**,—
    - (i) shows a risk of shortage for New Zealand of 10% or more; and
    - (ii) forecasts that the risk of shortage for New Zealand will be 10% or more for 1 week or more; or
  - (b) despite paragraph (a), if it has agreed a date with the **Authority** for an **official conservation campaign** to commence for New Zealand, on that date.
- (3) The **system operator** must use reasonable endeavours to give each **participant** and the **Authority** at least 2 weeks' notice of an **official conservation campaign** commencing.
- (4) If the **system operator** has commenced an **official conservation campaign**, it must—
  - (a) during the period of the **official conservation campaign**, regularly review the steps that the **system operator** must take, and encourage **participants** to take, under the **emergency management policy**; and
  - (b) end the **official conservation campaign**—
    - (i) when a comparison of storage in the hydro lakes with the hydro risk curves, as that term is defined in the **security of supply forecasting and information policy**, shows a risk of shortage for New Zealand or the South Island (as the case may be) of 8% or less; and
    - (ii) despite subparagraph (i), if it has agreed a date with the **Authority** for an **official conservation campaign** to end, on that date.
- (5) If the **system operator** and the **Authority** agree under subclause (1)(b) or (2)(b) that an **official conservation campaign** will commence, the **system operator** must **publish** the reasons for agreeing that the **official conservation campaign** will commence.
- (6) The **system operator** must, as soon as practicable after ending an **official conservation campaign**, give notice to each **participant** and the **Authority** of the date on which the **official conservation campaign** ended.

Clause 9.23: inserted, on 1 April 2011, by clause 5 of the Electricity Industry Participation (Customer Compensation Schemes) Code Amendment 2011.

Clause 9.23(4)(b)(i): amended, on 21 September 2012, by clause 13 of the Electricity Industry Participation (Minor Amendments) Code Amendment 2012.

Clause 9.23(5): amended, on 5 October 2017, by clause 151 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

*Default customer compensation scheme*

**9.24 Requirements of default customer compensation schemes**

- (1) A **retailer's default customer compensation scheme** must provide for the **retailer**—
  - (a) during an **official conservation campaign** for the South Island, to pay each of its **qualifying customers** in the South Island at least the minimum weekly amount of compensation, determined by the **Authority** under clause 9.25, for each week of the **official conservation campaign**; and
  - (b) at any other time during a **public conservation period**, to pay each of its **qualifying customers** at least the minimum weekly amount of compensation, determined by the **Authority** under clause 9.25, for each week of the **public conservation period**; and
  - (c) to pay at least the minimum weekly amount—
    - (i) to each of its **qualifying customers** in the South Island or New Zealand (as the case may be), for each of the **qualifying customer's ICPs** described in clause 9.21(1)(b);
    - (ii) no later than the end of 2 **billing periods** after the last day of a **public conservation period**.
- (2) Each **retailer's default customer compensation scheme** must provide that if a **public conservation period** runs for more than a whole number of weeks, the **retailer** must, in addition to making payments in accordance with subclause (1) for each whole week of the **public conservation period**, pay at least the minimum weekly amount of compensation at a pro rata daily rate for the number of days that exceed the whole number of weeks of the **public conservation period**.
- (3) For the purposes of this clause—
  - (a) compensation includes—
    - (i) money;
    - (ii) a credit on the **qualifying customer's electricity** account with the **retailer**; and
  - (b) the form of the compensation is to be determined by the **retailer**.

Clause 9.24: inserted, on 1 April 2011, by clause 5 of the Electricity Industry Participation (Customer Compensation Schemes) Code Amendment 2011.

Clause 9.24(1)(c)(ii): amended, on 5 October 2017, by clause 152 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

*Minimum weekly amount of compensation*

**9.25 Authority must determine minimum weekly amount**

- (1) In determining the minimum weekly amount that each **retailer** must pay to its **qualifying customers**, the **Authority** must take into account—
  - (a) the estimated value, in dollars/MWh, of the savings that the **Authority** expects all **qualifying customers** in the South Island or New Zealand, as the case may be, of all **retailers**, will achieve during an **official conservation campaign**; and
  - (b) any other factors that the **Authority** considers relevant.
- (2) The **Authority** must—

- (a) **publish** the minimum weekly amount; and
- (b) review the minimum weekly amount—
  - (i) after each **public conservation period** ends; and
  - (ii) at least once every 3 years; and
- (c) following a review under paragraph (b), ensure that it gives **participants** at least 3 months' notice if it determines a new minimum weekly amount.

Clause 9.25: inserted, on 1 April 2011, by clause 5 of the Electricity Industry Participation (Customer Compensation Schemes) Code Amendment 2011.

Clause 9.25(2)(a): amended, on 5 October 2017, by clause 153(a) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 9.25(2)(b)(ii): amended, on 5 October 2017, by clause 153(b) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

*Additional customer compensation schemes*

**9.26 Retailer may have additional customer compensation schemes**

A **retailer** may have 1 or more **additional customer compensation schemes**.

Clause 9.26: inserted, on 1 April 2011, by clause 5 of the Electricity Industry Participation (Customer Compensation Schemes) Code Amendment 2011.

**9.27 Qualifying customer may elect to be covered by additional customer compensation scheme**

- (1) If a **retailer** has 1 or more **additional customer compensation schemes**, each of the **retailer's qualifying customers** is covered by—
  - (a) 1 of the **retailer's additional customer compensation schemes** only if the **qualifying customer** elects to be covered by the **additional customer compensation scheme**; or
  - (b) in the absence of an election, the **retailer's default customer compensation scheme**.
- (2) Before accepting a **qualifying customer's** election, a **retailer** must ensure that it informs the **qualifying customer** of—
  - (a) the details of the **additional customer compensation scheme**; and
  - (b) the differences between the **retailer's default customer compensation scheme** and the **additional customer compensation scheme**.
- (3) A **retailer** must keep a record of each **qualifying customer's** election.
- (4) A **qualifying customer's** election must not—
  - (a) be part of the contract between the **qualifying customer** and the **retailer** for the supply of **electricity**; or
  - (b) affect the tariff options that the **retailer** offers to the **qualifying customer**; or
  - (c) be affected by the tariff option in the **qualifying customer's** contract with the **retailer**.

Clause 9.27: inserted, on 1 April 2011, by clause 5 of the Electricity Industry Participation (Customer Compensation Schemes) Code Amendment 2011.

**9.28 Publishing description of additional customer compensation schemes**

A **retailer** who has 1 or more **additional customer compensation schemes** must—

- (a) **publish** and keep **published** a description of its **additional customer**

**compensation schemes; and**

- (b) on request from a **customer**, provide a written description of the **additional customer compensation schemes**.

Clause 9.28: inserted, on 1 April 2011, by clause 5 of the Electricity Industry Participation (Customer Compensation Schemes) Code Amendment 2011.

Clause 9.28(a): amended, on 5 October 2017, by clause 154 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### *Certification of compliance*

Cross heading: replaced, on 5 October 2017, by clause 155 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

## **9.29 Each retailer must provide certification**

- (1) Each **retailer** must certify to the **Authority** that—
- (a) the **retailer's customer compensation scheme** complies with this subpart; and
  - (b) the **retailer** has provided compensation to its **qualifying customers**, to the extent required by this subpart.
- (2) The certification provided under subclause (1) must be—
- (a) *[Revoked]*
  - (b) in the form specified by the **Authority**; and
  - (c) signed and dated by a director of the **retailer** and either—
    - (i) another director of the **retailer**; or
    - (ii) the **retailer's** chief financial officer, or a person holding an equivalent position; or
    - (iii) the **retailer's** chief executive officer, or a person holding an equivalent position.
- (3) A **retailer** must provide certifications as follows:
- (a) within 7 months of the end of a **public conservation period**;
  - (b) within 1 month of receiving a request to do so by the **Authority**.
- (4) *[Revoked]*

Clause 9.29: inserted, on 1 April 2011, by clause 5 of the Electricity Industry Participation (Customer Compensation Schemes) Code Amendment 2011.

Heading: amended, on 5 October 2017, by clause 156(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 9.29(1): amended, on 5 October 2017, by clause 156(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 9.29(2): amended, on 5 October 2017, by clause 156(3) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 9.29(3): amended, on 5 October 2017, by clause 156(4) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 9.29(4): revoked, on 5 October 2017, by clause 156(5) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### *Audit*

## **9.30 Audit of compliance**

- (1) The **Authority** may, in its discretion, carry out an **audit** to determine whether a **retailer** has complied with this subpart.
- (2) If the **Authority** decides to **audit** a **retailer** under subclause (1), the **Authority** must require the **retailer** to nominate an appropriate **auditor**.

- (3) The **retailer** must nominate an **auditor** within a reasonable timeframe, and the **Authority** must appoint the nominated **auditor**.
- (4) If the **retailer** fails to nominate an appropriate **auditor** within a reasonable timeframe, the **Authority** may appoint an **auditor** of its own choice.

Clause 9.30: inserted, on 1 April 2011, by clause 5 of the Electricity Industry Participation (Customer Compensation Schemes) Code Amendment 2011.

### **9.31 Retailer must provide information to auditor**

- (1) A **retailer** subject to an **audit** under this subpart must, on request from the **auditor**, provide the **auditor** with information relating to its compliance with this subpart in the previous 12 months or such other period specified by the **auditor**.
- (2) The **retailer** must provide the information within 20 **business days** after receiving a request from the **auditor**.

Clause 9.31: inserted, on 1 April 2011, by clause 5 of the Electricity Industry Participation (Customer Compensation Schemes) Code Amendment 2011.

### **9.32 Auditor must provide audit report**

- (1) The **retailer** must ensure that the **auditor** provides the **Authority** with an **audit** report on the **retailer's** compliance with this subpart that has been prepared in accordance with this clause.
- (2) The **audit** report must include any comments from the **retailer** on any non-compliance found by the **auditor** if the **retailer** provided the comments to the **auditor** within a time specified by the **auditor**.
- (3) *[Revoked]*
- (4) The **audit** report must not contain any of the information provided by the **retailer** to the **auditor** under clause 9.31 unless requested by the **Authority**.

Clause 9.32: inserted, on 1 April 2011, by clause 5 of the Electricity Industry Participation (Customer Compensation Schemes) Code Amendment 2011.

Clause 9.32(1): amended, on 1 February 2016, by clause 24(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

Clause 9.32(2): substituted, on 1 February 2016, by clause 24(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

Clause 9.32(3): revoked, on 1 February 2016, by clause 24(3) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

Clause 9.32(4): amended, on 1 February 2016, by clause 24(4) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

### **9.33 Payment of auditor's costs**

- (1) If an **audit** establishes, to the **Authority's** reasonable satisfaction, that a **retailer** has not complied with this subpart (whether or not the **Authority** appoints an investigator to investigate the alleged breach), the **retailer** must pay the **auditor's** costs.
- (2) If the **Authority** considers that the **retailer's** non-compliance is minor or relates to some (but not all) of the clauses in this subpart, the **Authority** may, in its discretion, determine the proportion of the **auditor's** costs that the **retailer** must pay, and the **retailer** must pay those costs.
- (3) If an **audit** establishes to the **Authority's** reasonable satisfaction that a **retailer** has complied with this subpart, the **Authority** must pay the **auditor's** costs.

Clause 9.33: inserted, on 1 April 2011, by clause 5 of the Electricity Industry Participation (Customer Compensation Schemes) Code Amendment 2011.

# Electricity Industry Participation Code 2010

## Part 10 Metering

### Contents

- 10.1 Contents of this Part
  - Subpart 1—Preliminary provisions
- 10.2 Authority's discretion and powers
- 10.3 Use of contractors
- 10.4 Participant obligations
- 10.5 References to timing
- 10.6 Participant to provide accurate information
- 10.7 Access to premises in which metering installation located
- 10.8 Requirements for information to be recorded, given, produced, or received
- 10.9 Demarcation of responsibility between metering equipment provider and reconciliation participant
- 10.10 Standards used
  - Metering installations*
- 10.11 Categories of metering installation
- 10.12 Interference with metering installation
- 10.13 Electricity conveyed
  - Unmetered load*
- 10.14 Unmetered load
  - Metering data*
- 10.15 Security of metering data
- 10.16 Metering data exchange timing and formats
  - Audits*
- 10.17 *[Revoked]*
- 10.17A Metering equipment providers and ATHs to arrange for regular audits
- 10.17B Authority and participant requested audits
  - Subpart 2—Ongoing obligations
  - Metering equipment providers*
- 10.18 Category 1 metering installations and higher categories of metering installations must have metering equipment provider
- 10.19 Metering equipment provider
- 10.20 Obligations of metering equipment provider
- 10.21 When metering equipment provider's obligations come into effect
- 10.22 Change of metering equipment provider
- 10.23 Termination of metering equipment provider responsibility
  - Responsibility for ensuring there are metering installations*
- 10.24 Responsibility for ensuring there is metering installation for ICP that is not also NSP
- 10.25 Responsibility for ensuring there is metering installation for NSP that is not point of connection to grid
- 10.26 Responsibility for ensuring there is metering installation for point of connection to



- grid
- 10.27 Change in responsibility for ensuring metering installation for point of connection to grid
- Connecting and electrically connecting points of connection*
- 10.28 *[Revoked]*
- 10.29 When grid owner may connect point of connection to grid
- 10.29A When grid owner may temporarily electrically connect point of connection to grid
- 10.30 When distributor or embedded network owner may connect NSP that is not point of connection to grid
- 10.30A When distributor may temporarily electrically connect NSP that is not point of connection to grid
- 10.31 When distributor may connect ICP that is not NSP
- 10.31A When distributor may temporarily electrically connect ICP that is not NSP
- 10.32 Reconciliation participant requesting connection of point of connection
- 10.33 When reconciliation participant may temporarily electrically connect point of connection
- 10.33A When reconciliation participant may electrically connect point of connection
- General metering installation requirements*
- 10.34 Installation and modification of metering installations
- 10.35 Physical location of metering installations
- 10.36 Reconciliation participant to have arrangement with metering equipment provider
- Active and reactive energy metering*
- 10.37 Active and reactive measuring and recording requirements
- Certification of metering installations*
- 10.38 Certification of metering installations
- Metering infrastructure*
- 10.39 Responsibility for metering infrastructure integration
- Approved test houses and ATHs*
- 10.40 General requirements for approval as ATH
- 10.41 Requirements applying to ATHs
- 10.42 ATH's functions and ongoing obligations
- Metering installations that are inaccurate, defective, or not fit for purpose*
- 10.43 Metering installations that are inaccurate, defective, or not fit for purpose to be investigated
- 10.44 Metering installations that are inaccurate, defective, or not fit for purpose to be tested
- 10.45 Investigation and testing costs
- 10.46 Statement of situation
- 10.47 Correction of defects and inaccuracies in metering installation
- 10.48 Correction of defects and inaccuracies in raw meter data
- NSP table*
- 10.49 NSP table
- Dispute resolution*
- 10.50 Dispute resolution

*Transitional provisions*

10.51 Transitional provisions

**Schedule 10.1**

**Tables**

**Schedule 10.2**

*[Revoked]*

**Schedule 10.3**

**ATHs – approval, expiry, cancellation, and renewal of approval**

**Schedule 10.4**

**ATH ongoing functions and obligations**

*Requirements for calibration of metering components*

**Schedule 10.5**

*[Revoked]*

**Schedule 10.6**

**Metering equipment provider ongoing obligations and functions**

**Schedule 10.7**

**Metering installation requirements**

*Metering installation general requirements*

*Metering installation design reports*

*Determination of metering installation categories*

*Certification of metering installation*

*Statistical sampling recertification*

*Certification validity periods*

*Accuracy and error calculation*

*Installation of metering components in metering installations*

*Certification of metering components*

*Inspection requirements*

*Sealing*

**Schedule 10.8**

**Metering component requirements**

*Meters*

*Measuring transformers*

*Control devices*

*Data storage devices*

*Wiring*

*Fuses and circuit breakers*

*Certification stickers*

*Onsite calibration and certification*

## 10.1 Contents of this Part

This Part provides for—

- (a) ensuring the accuracy of the clearing and settlement of **electricity** trading in the wholesale **electricity** market by regulating how existing and new **metering installations** are used to accurately measure and record **electricity** conveyed; and
- (b) the responsibility for ensuring a **metering installation** is in place; and
- (c) the responsibility for ensuring the compliance of **metering installations**; and
- (d) the processes and procedures that apply to testing, **calibrating**, and **certifying metering installations**; and
- (e) *[Revoked]*
- (f) the processes and procedures that apply to approving **ATHs**; and
- (g) regulating the data use, handling, storage, and transmission processes associated with **metering installations** and **metering data**; and
- (h) regulating **metering installations** that are used for **electricity** trading; and
- (i) the processes and procedures relating to the **registry** and information for the purposes of Part 15; and
- (j) related matters, processes, and procedures.

Clause 10.1(e): revoked, on 1 June 2017, by clause 5 of the Electricity Industry Participation Code Amendment (Requirements and Processes for Audits) 2016.

## Subpart 1—Preliminary provisions

## 10.2 Authority's discretion and powers

- (1) A clause in this Part that gives the **Authority** a discretion or power—
  - (a) confers an absolute discretion to the **Authority**—
    - (i) taking into account any specific requirements set out in the clause; and
    - (ii) observing the principles of natural justice; and
  - (b) to approve an application by a person to carry out an activity under this Part, may be exercised by—
    - (i) granting the application; or
    - (ii) declining the application; or
    - (iii) granting the application with any conditions that the **Authority** considers appropriate in the circumstances.
- (2) The **Authority**, when exercising a discretion or power under this Part, must act in a timely manner.
- (3) The **Authority** must give an applicant reasons for its decision if the **Authority**—
  - (a) declines an application for approval to carry out an activity under this Part; or
  - (b) grants an application for approval to carry out an activity under this Part with any conditions that the **Authority** considers appropriate in the circumstances.
- (4) Nothing in this Part limits any of the **Authority's** rights and obligations under the **Act**.

Heading: amended, on 5 October 2017, by clause 157(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 10.2(1), (2) and (3): amended, on 5 October 2017, by clause 157(2) and (3) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### 10.3 Use of contractors

- (1) A **participant** may perform its obligations and exercise its rights under this Part by using a contractor.
- (2) A **participant** who uses a contractor to perform the **participant's** obligation under this Part—
  - (a) remains responsible and liable for, and is not released from, the obligation, or any other obligation under this Part; and
  - (b) cannot assert that it is not responsible or liable for the obligation on the ground that the contractor—
    - (i) has done or not done something; or
    - (ii) has failed to meet a relevant standard; and
  - (c) must ensure that the contractor has at least the specified level of skill, expertise, experience, or qualification that the **participant** would be required to have if it were performing the obligation itself.
- (3) If a **participant** is a party to a contract or arrangement containing a provision, or part of a provision, which is inconsistent with this Part, the provision, or part of the provision, has no effect.

### 10.4 Participant obligations

- (1) If this Part provides that a **participant** must obtain a **consumer's** consent, approval, or authorisation, the **participant** must, if relevant, ensure that the consent, approval, or authorisation extends, for the full term of the contract or arrangement in relation to which the consent, approval, or authorisation is given, to any **participant** who may be expected to rely on that consent, approval, or authorisation to remain in compliance with this Part.
- (2) If a **participant** (**participant A**) incorrectly populates the **registry**, causing another **participant** (**participant B**) to breach an obligation under this Code, and **participant B** relies, in good faith, on the incorrect information in the **registry**, **participant B** has not breached its obligation.
- (3) A **participant** must comply with all applicable enactments.
- (4) A **participant** is, unless it is specified otherwise in this Part, responsible for all costs of its compliance with this Part.
- (5) A reference in this Part to a **participant** knowing, or being or becoming aware of, a fact, includes reference to when a **participant** should have, in the circumstances, known, or been or become aware of, the fact.

Clause 10.4(2): amended, on 5 October 2017, by clause 158 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### 10.5 References to timing

- (1) If an event is described in this Part as taking place on, or an obligation becoming effective from, a date, it takes place on, or becomes effective from, the beginning of the first **trading period** on the date, unless specified otherwise.
- (2) If a time period is expressed in this Part as—
  - (a) commencing on a date, it commences at the beginning of the first **trading period** on the date, unless specified otherwise:

- (b) ending on a date, it ends at the close of the final **trading period** on the date, unless specified otherwise.

#### 10.6 Participant to provide accurate information

- (1) A **participant** must take all practicable steps to ensure that information that it provides under this Part is—
  - (a) complete and accurate;
  - (b) not misleading or deceptive;
  - (c) not likely to mislead or deceive.
- (2) If a **participant** becomes aware that the information the **participant** provided under this Part does not comply with subclause (1)(a) to (c), even if the **participant** has taken all practicable steps to ensure that the information complies, the **participant** must, except if clause 10.43 applies, as soon as practicable provide such further information, or corrected information, as is necessary to ensure that the information complies with subclause (1)(a) to (c).

Clause 10.6(2): substituted, on 19 December 2014, by clause 20 of the Electricity Industry Participation Code Amendment (Minor Code Amendments) (No 3) 2014.

#### 10.7 Access to premises in which metering installation located

- (1) In this clause, access to a **metering installation**—
  - (a) means physical access to the premises in which the **metering installation** is located; but
  - (b) does not include access to the following, which are dealt with in Schedule 10.6:
    - (i) **raw meter data** from the **metering installation**; and
    - (ii) the **metering installation** itself and its **metering components**.
- (2) A **reconciliation participant** must, upon receiving a request from 1 of the following parties, arrange access to a **metering installation** for which it is responsible:
  - (a) the **Authority**;
  - (b) an **ATH**;
  - (c) an **auditor**;
  - (d) a **metering equipment provider**;
  - (e) a **gaining metering equipment provider**.
- (3) A party listed in subclause (2) may only request access to the **metering installation** for the purposes of exercising the party's rights and performing the party's obligations under this Code or any relevant **regulations** in relation to 1 or more of the following:
  - (a) the party's **audit** functions;
  - (b) the party's administration functions;
  - (c) the party's testing functions;
  - (d) the provision of **metering components**.
- (4) A **reconciliation participant** who is required to give a party listed in subclause (2) access to a **metering installation** must use its best endeavours to do so—
  - (a) in accordance with the authorisation, and any conditions or restrictions contained in the authorisation, referred to in subclause (5); and
  - (b) subject to and to the extent allowed by the authorisation, in a manner and within a timeframe which are appropriate in the circumstances, to enable the party to

exercise the party's rights, or perform the party's obligations, that are dependent, either directly or indirectly, on access being given.

- (5) If the **reconciliation participant** referred to in subclause (2) is a **trader** responsible for an **ICP** that—
- (a) has a **consumer**, the **trader** must have obtained the authorisation from the **consumer** to access the **metering installation** before arranging access; or
  - (b) does not have a **consumer**, the **trader** must arrange for access to the **metering installation**.
- (6) The **reconciliation participant** must arrange for the party listed in subclause (2) to be provided with any necessary facilities, codes, keys, or other means to enable the party to obtain access to the **metering installation** by the most practicable means.

Clause 10.7(3): amended, on 5 October 2017, by clause 159 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### 10.8 Requirements for information to be recorded, given, produced, or received

- (1) In this Part, a **participant** who must record, give, produce, or receive information, must do so in accordance with 1 or more of the following requirements **published** or **notified** by the **Authority**:
- (a) requirements providing for particular electronic technology;
  - (b) requirements providing for the use of a particular kind of **data storage device**;
  - (c) requirements providing for the use of a particular kind of electronic **communication**.
- (2) Part 3 of the Electronic Transactions Act 2002 does not, because of section 14(2)(a) of that Act, apply to this Part.
- (3) The **Authority** must act reasonably when determining the requirements referred to in subclause (1).

### 10.9 Demarcation of responsibility between metering equipment provider and reconciliation participant

- (1) The demarcation of the responsibility of a **metering equipment provider** under this Part and a **reconciliation participant** under Part 15, is at the **services access interface**.
- (2) A **metering equipment provider** is responsible for providing and maintaining the **services access interface**.
- (3) The **services access interface** for a **metering installation** is—
- (a) determined by the **ATH** certifying the **metering installation** under clause 10 of Schedule 10.4; and
  - (b) recorded in the **metering installation certification report** under clause 10 of Schedule 10.4.

### 10.10 Standards used

In this Part a reference to compliance with a standard, including an AS/NZS or IEC standard, is a reference to—

- (a) the version of the standard existing as at 29 August 2013; or
- (b) any amendment to or replacement of the standard incorporated by the **Authority** in accordance with section 32 of the **Act**; or

- (c) any equivalent standard incorporated by the **Authority** in accordance with section 32 of the **Act**.

Clause 10.10(a): amended, on 29 August 2013, by clause 11 of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011, Amendment 2013 (No 2).

### *Metering installations*

#### **10.11 Categories of metering installation**

- (1) An **ATH** must, before it **certifies a metering installation**, determine the category of the **metering installation** by reference to the characteristics of the **metering installation**, in accordance with clauses 5 and 6 of Schedule 10.7.
- (2) A **metering installation** used solely for **unmetered load** is category 0.
- (3) The category of each **metering installation**, other than a category 0 **metering installation**, is for all purposes of this Part—
  - (a) determined by the **ATH** **certifying the metering installation** under clauses 5 and 6 of Schedule 10.7; and
  - (b) recorded in the **metering installation certification report** under clause 8(4) of Schedule 10.7.

#### **10.12 Interference with metering installation**

A **participant** must not directly or indirectly interfere with a **metering installation** for which it is not the **metering equipment provider**, unless—

- (a) it is instructed or permitted to do so by the **metering equipment provider** responsible for the **metering installation**; or
- (b) the **participant** has an arrangement with the **trader** responsible for the **metering installation** as the **gaining metering equipment provider** who will be responsible for the **metering installation**.

#### **10.13 Electricity conveyed**

- (1) A **participant** must use the quantity of **electricity** measured by a **metering installation** for a **point of connection** as the **raw meter data** for the quantity of **electricity** conveyed through the **point of connection**.
- (2) Subclause (1) does not apply to **electricity** that is—
  - (a) estimated in accordance with this Code; or
  - (b) supplied by an **embedded generator** who has given the **reconciliation manager** a notification under clause 15.13.
- (3) A **metering equipment provider** must, for each **point of connection** at which it is the **metering equipment provider**, ensure that all **electricity** conveyed through the **point of connection** is measured by a **metering installation** or **metering installations**, in accordance with this Part.
- (4) Despite subclause (3), a **metering equipment provider** is not required to measure **electricity** conveyed through a **point of connection** if the **electricity** is—
  - (a) **unmetered load**; or
  - (b) supplied by an **embedded generator** who has given the **reconciliation manager** a notification under clause 15.13.

*Unmetered load*

**10.14 Unmetered load**

- (1) This clause applies to a **retailer** who is recorded in the **registry** as being responsible for an **ICP**.
- (2) A **retailer**—
  - (a) must quantify any **unmetered load** at the **ICP** in accordance with Parts 11 and 15; and
  - (b) may, subject to subclause (3), only treat load as **unmetered load** if it reasonably expects, in any rolling 12 month period, the load to be not greater than—
    - (i) 3,000 kWh; or
    - (ii) 6,000 kWh if the load is predictable load of a type approved and **published** by the **Authority**.
- (3) Subclause (2)(b) does not apply to **distributed unmetered load** managed in accordance with Part 15.
- (4) If the load during a rolling 12 month period exceeds the applicable limit under subclause (2)(b), the **retailer** breaches this clause from the date on which the limit was, or was calculated or estimated to have been, first exceeded.
- (5) A **retailer** described in subclause (4) must—
  - (a) as soon as reasonably practicable, but no later than 20 **business days** after the limit was calculated or estimated to have been first exceeded, commence corrective measures to ensure that it complies with this Part; and
  - (b) within 20 **business days** of commencing the corrective measures referred to in paragraph (a), complete the corrective measures so that it complies with this Part; and
  - (c) as soon as reasonably practicable, but no later than 10 **business days** after it becomes aware of the limit having been calculated or estimated to have been first exceeded, advise each **participant** who is, or would reasonably be expected to be, affected, of—
    - (i) the date on which the limit was calculated or estimated to have been first exceeded; and
    - (ii) the details of the corrective measures that the **retailer** proposes to take, has taken, or is taking, to reduce the **unmetered load**.

Clause 10.14(5)(c)(ii): amended, on 29 August 2013, by clause 12 of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011, Amendment 2013 (No 2).

*Metering data*

**10.15 Security of metering data**

- (1) This clause applies to—
  - (a) a **participant** who has the right to collect, obtain, use, or store **metering data**; and
  - (b) the **Authority**.
- (2) A person to whom this clause applies must take security measures, as are reasonable in



the circumstances, to protect **metering data** against loss or unauthorised access, use, modification, or disclosure.

- (3) Subclause (2) is subject to—
- (a) the person's obligations under any other enactment; and
  - (b) the person being otherwise compelled by law; and
  - (c) any applicable material that the **Authority** incorporates into this Code under section 32(3) of the **Act**.

#### 10.16 Metering data exchange timing and formats

- (1) A **participant** (other than a **market operation service provider**) must, if it is under an obligation to provide **metering data** under this Part, provide the **metering data** to the relevant person—
- (a) in the absence of any timeframe specified in this Code, within a reasonable timeframe **notified** by the **Authority**; and
  - (b) in the format **notified** to **participants** from time to time by the **Authority**.
- (2) The **Authority** must provide reasonable notice of any changes to the format **notified** under subclause (1)(b).
- (3) Despite subclause (1)(b), a **participant** may provide the **metering data** in an alternative format if it has an arrangement with the recipient to use the alternative format.
- (4) Despite subclause (3), the **participant** must be able to comply with any format requirements **notified** by the **Authority** under subclause (1)(b), within 1 **business day** of ceasing to have an arrangement with the recipient under subclause (3).
- (5) Despite using an alternative format under subclause (3), a **participant** must still comply with all other obligations in this Code.

#### *Audits*

#### 10.17 [Revoked]

Clause 10.17(1): revoked, on 1 February 2016, by clause 25 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

Clause 10.17(1): inserted, on 1 May 2016, by clause 5(1) of the Electricity Industry Participation Code Amendment (Minor Code Amendments) 2016.

Clause 10.17(2): revoked, on 1 May 2016, by clause 5(2) of the Electricity Industry Participation Code Amendment (Minor Code Amendments) 2016.

Clause 10.17: revoked, on 1 June 2017, by clause 6 of the Electricity Industry Participation Code Amendment (Requirements and Processes for Audits) 2016.

#### 10.17A Metering equipment providers and ATHs to arrange for regular audits

Each **metering equipment provider** and each **ATH** must arrange to be **audited** regularly in accordance with Part 16A in respect of the **metering equipment provider's** or **ATH's** obligations under this Part.

Clause 10.17A: inserted, on 1 June 2017, by clause 7 of the Electricity Industry Participation Code Amendment (Requirements and Processes for Audits) 2016.

#### 10.17B Authority and participant requested audits

- (1) The **Authority** may at any time carry out, or appoint an **auditor** to carry out, an **audit** of a **participant** in respect of the **participant's** obligations under this Part.

- (2) If a **participant** considers that another **participant** may not have complied with this Part, the **participant** may request that the **Authority** carry out, or appoint an **auditor** to carry out, an **audit** of the other **participant**.
- (3) Part 16A applies to an **audit** carried out under this clause.  
Clause 10.17B: inserted, on 1 June 2017, by clause 7 of the Electricity Industry Participation Code Amendment (Requirements and Processes for Audits) 2016.

## Subpart 2—Ongoing obligations

### *Metering equipment providers*

#### **10.18 Category 1 metering installations and higher categories of metering installations must have metering equipment provider**

- (1) A **participant** who is responsible under Part 15 for providing **submission information** to the **reconciliation manager** for a **point of connection** must ensure that, for each **metering installation** for the **point of connection** used for an activity regulated under this Code, there is a **metering equipment provider**.
- (2) A **participant** must not use, and must not permit any person to use, a **category 1 metering installation**, or higher category of **metering installation**, for a **point of connection** for an activity regulated under this Code unless, at the time of such use, there is a **metering equipment provider** for the **metering installation**.
- (3) Despite subclauses (1) and (2), a **point of connection** at which all **electricity** conveyed is **unmetered load**—
  - (a) does not require a **metering equipment provider**; and
  - (b) may be used for an activity regulated under this Code.
- (4) If there is more than 1 **metering installation** for a **point of connection**, the **metering equipment provider** for each **metering installation** must be the same **participant**.

#### **10.19 Metering equipment provider**

- (1) The **metering equipment provider** for each existing **category 1 metering installation**, or higher category of **metering installation**, being used on 29 August 2013 for an activity regulated under this Code, for a **point of connection**—
  - (a) that is an **ICP** and not also an **NSP**, is the **participant**, or a **consumer**, who is identified in the **registry** as being the primary metering contact at 2400 hours on 28 August 2013;
  - (b) that is an **NSP** and not also a **point of connection** to the **grid**—
    - (i) is the **participant** who owns the **meter** for the **point of connection**;
    - (ii) if there is more than 1 **meter** for the **point of connection**, is the **participant** who is appointed by the **meter** owners for the **point of connection**, or failing agreement, appointed by the **Authority**;
  - (c) to the **grid**, is the **participant** responsible for **metering** as set out in the **NSP** table on the **Authority's** website at 2400 hours on 28 August 2013.
- (2) The **metering equipment provider** for each **category 1 metering installation**, or higher category of **metering installation** for a **point of connection**, other than a **metering installation** referred to in subclause (1),—

- (a) that is an **ICP** and not also an **NSP**, is the person recorded in the **registry** as accepting responsibility as the **metering equipment provider** under clause 1(1)(a)(ii) of Schedule 11.4;
- (b) that is an **NSP** and not also a **point of connection** to the **grid**, is—
  - (i) the **network** owner referred to in clause 10.25(2)(a)(i); or
  - (ii) if a person has contracted with the **network** owner under clause 10.25(2)(a)(ii), that person;
- (c) that is a **point of connection** to the **grid**, is—
  - (i) the **participant** referred to in clause 10.26(7)(b); or
  - (ii) if a person has contracted with the **participant** responsible for providing a **metering installation** under clause 10.26(7)(b), that person.

Clause 10.19(1): amended, on 29 August 2013, by clause 13(1) of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011, Amendment 2013 (No 2).

Clause 10.19(1)(a): amended, on 29 August 2013, by clause 13(2) of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011, Amendment 2013 (No 2).

Clause 10.19(1)(b)(ii): amended, on 5 October 2017, by clause 160(a) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 10.19(1)(c): amended, on 29 August 2013, by clause 13(3) of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011, Amendment 2013 (No 2).

Clause 10.19(2)(a): amended, on 5 October 2017, by clause 160(b) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

## 10.20 Obligations of metering equipment provider

A **metering equipment provider** must—

- (a) *[Revoked]*
- (b) comply with all of its obligations in this Code including the obligations under Schedules 10.6, 10.7, and 10.8.

Clause 10.20(a): revoked, on 1 June 2017, by clause 8 of the Electricity Industry Participation Code Amendment (Requirements and Processes for Audits) 2016.

## 10.21 When metering equipment provider's obligations come into effect

- (1) The obligations under this Part of a person who assumes responsibility, or is appointed to be responsible, as the **metering equipment provider**, under clauses 10.19(2) or 10.22, for a **metering installation**, commence,—
  - (a) for an **ICP** that is not also an **NSP**, on the date that is recorded in the **registry** as being the date on which the **metering installation equipment** was installed; or
  - (b) for an **NSP**, on the effective date set out in the **NSP** table on the **Authority's** website.
- (2) Despite subclause (1), if a person fails to become the **metering equipment provider** due solely to an administrative failure or similar reason, the **Authority** may determine the date that the person becomes the **metering equipment provider**.

Clause 10.21(1)(a): substituted, on 29 August 2013, by clause 14 of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011, Amendment 2013 (No 2).

## 10.22 Change of metering equipment provider

- (1) The **metering equipment provider** for a **metering installation** may change only if the **participant** responsible for ensuring there is a **metering installation** under clause 10.24, 10.25, or 10.26 enters into an arrangement with another person to become the **metering equipment provider** for the **metering installation** and—

- (a) in the case of a **metering installation** for an **ICP** that is not also an **NSP**—
  - (i) the **trader** for the **metering installation** records the name of the **gaining metering equipment provider** in the **registry** in accordance with Part 11; and
  - (ii) the **gaining metering equipment provider** records in the **registry** that it accepts becoming the **metering equipment provider** (including the effective date from which the **gaining metering equipment provider** assumes its responsibility as **metering equipment provider** for the **metering installation**) in accordance with Part 11; or
- (b) in the case of a **metering installation** for an **NSP**, the **participant** responsible for the provision of the **metering installation** under clause 10.25 advises the **reconciliation manager** of the **gaining metering equipment provider**.
- (2) The **gaining metering equipment provider** must, within 20 **business days** of assuming responsibility for a **metering installation**, pay the **losing metering equipment provider** the proportion of the costs described in subclause (3).
- (3) The costs payable under subclause (2) are those directly and solely attributable to the **certification** tests and **calibration** tests of the **metering installation** or any of its **metering components** from the period beginning on the date the **gaining metering equipment provider** assumes responsibility for the **metering installation**, for the remainder of the **certification** validity period for the **metering installation** or the **metering component**.

Clause 10.22(1)(a)(i) and (ii): amended, on 5 October 2017, by clause 161(a) and (b) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### 10.23 Termination of metering equipment provider responsibility

- (1) Subject to subclause (2), a **metering equipment provider's** obligations under this Part for a **metering installation** terminate only when—
  - (a) for an **ICP** that is not also an **NSP**, the **metering equipment provider** changes under clause 10.22(1)(a), in which case the **metering equipment provider's** obligations terminate from the date on which the **gaining metering equipment provider** assumes responsibility, set out in clause 10.21(1)(a); or
  - (b) for an **NSP**, the **metering equipment provider** changes under clause 10.22(1)(b), in which case the **metering equipment provider's** obligations terminate from the date on which the **gaining metering equipment provider** assumes responsibility, set out in clause 10.21(1)(b); or
  - (c) the **metering installation** is no longer required for the purposes of Part 15 and the **point of connection** for the **metering installation** has been **decommissioned**; or
  - (d) the **ICP** for the **metering installation** is converted to be used solely for **unmetered load** in accordance with this Code.
- (2) Despite subclause (1), a **metering equipment provider** must either—
  - (a) comply with its continuing obligations, including record keeping obligations, which—
    - (i) are expressed in this Part as having minimum time periods, until that period expires; or
    - (ii) by their nature extend beyond the date or event referred to in subclause (1);

or

- (b) before its obligations terminate under subclause (1), enter into an arrangement with a **participant** to assume its obligations referred to in paragraph (a).

*Responsibility for ensuring there are metering installations*

**10.24 Responsibility for ensuring there is metering installation for ICP that is not also NSP**

A **trader** must, for each **electrically connected ICP** that is not also an **NSP**, and for which it is recorded in the **registry** as being responsible, ensure that—

- (a) there is 1 or more **metering installations**; and
- (b) all **electricity** conveyed is quantified in accordance with this Code; and
- (c) it does not use subtraction to determine **submission information** for the purposes of Part 15.

Clause 10.24: amended, on 5 October 2017, by clause 162 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

**10.25 Responsibility for ensuring there is metering installation for NSP that is not point of connection to grid**

- (1) A **distributor** must, for each **NSP** that is not a **point of connection** to the **grid**, and for which it is recorded in the **NSP** table on the **Authority's** website as being responsible, ensure that—
  - (a) there is 1 or more **metering installations**; and
  - (b) all **electricity** conveyed is quantified in accordance with this Code:
- (2) A **distributor** must, if it proposes the creation of a new **NSP** that is not a **point of connection** to the **grid**,—
  - (a) for each **metering installation** for the **NSP**, either—
    - (i) assume responsibility for being the **metering equipment provider**; or
    - (ii) contract with a person who, in that contract, assumes responsibility for being the **metering equipment provider**; and
  - (b) no later than 20 **business days** after assuming responsibility or entering into the contract under paragraph (a), advise the **reconciliation manager** of—
    - (i) the **reconciliation participant** for the **NSP**; and
    - (ii) the **participant identifier** of the **metering equipment provider** for the **metering installation**; and
  - (c) no later than 20 **business days** after the date of **certification** of each **metering installation**, advise the **reconciliation manager** of the **certification** expiry date of the **metering installation**.
- (3) In relation to an **NSP** of the type described in subclause (1), a **distributor** must, no later than 20 **business days** after a **metering installation** for such an **NSP** is **recertified**, advise the **reconciliation manager** of the following:
  - (a) the **reconciliation participant** for the **NSP**;
  - (b) the **participant identifier** of the **metering equipment provider** for the **metering installation**;
  - (c) the **certification** expiry date of the **metering installation**.

Clause 10.25(1): amended, on 29 August 2013, by clause 15(1) of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011, Amendment 2013 (No 2).

Clause 10.25(2): amended, on 29 August 2013, by clause 15(2) of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011, Amendment 2013 (No 2).

Clause 10.25(2)(b)(ii): amended, on 29 August 2013, by clause 15(3) of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011, Amendment 2013 (No 2).

Clause 10.25(2)(b)(ii): amended, on 1 February 2016, by clause 26(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

Clause 10.25(2)(c): amended, on 1 February 2016, by clause 26(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

Clause 10.25(3): inserted, on 1 February 2016, by clause 26(3) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

## **10.26 Responsibility for ensuring there is metering installation for point of connection to grid**

- (1) A **grid owner** must, for each **GXP** which connects to its **grid**, ensure that there is 1 or more **certified metering installations** for the **GXP**.
- (2) An **asset owner** must, for each **GIP** which connects to the **grid**, ensure that there is 1 or more **certified metering installations** for the **GIP**.
- (3) A **participant** who proposes to connect to the **grid** at a new **point of connection** must take all practicable steps and use its best endeavours to agree with the **grid owner** and any other affected **participants**, on which **participant** will provide the **metering installation** for the proposed new **point of connection**.
- (4) If the **participants** cannot agree, within 60 **business days** of the **grid owner** first being advised of the proposed new **point of connection** to the **grid**, on the **participant** to be responsible for providing the **metering installation**,—
  - (a) any affected **participant** may advise the **Authority**—
    - (i) that agreement has not been reached; and
    - (ii) of the identity of all affected **participants**; and
    - (iii) of the reasons (if and to the extent known) that agreement was not reached; and
  - (b) the **Authority** must determine which **participant** must provide the **metering installation**; and
  - (c) the **Authority** must advise—
    - (i) the relevant **participant** of its responsibility to provide the **metering installation**; and
    - (ii) the **participant** intending to connect to the **grid** of its determination; and
    - (iii) the **grid owner** of its determination.
- (5) When determining which **participant** is responsible for providing the **metering installation**, the **Authority** must, unless it is satisfied that there is good reason not to do so, do so on the basis that—
  - (a) the **grid owner** is responsible if the **Authority** anticipates that the **point of connection** is a **GXP**; and
  - (b) the **participant** connecting **assets** to the **grid** at the **point of connection** is responsible if the **Authority** anticipates that the **point of connection** is a **GIP**.
- (6) The **participant** responsible for providing the **metering installation** (unless the **participant** is a **grid owner**) must also, for each proposed new **metering installation** for a **point of connection** to the **grid**,—
  - (a) provide a copy of the **metering installation** design to the **grid owner** before ordering equipment; and

- (b) provide the **grid owner** with at least 3 months to review and comment on the **metering installation** design; and
  - (c) respond, within 3 **business days** of receipt, to any request from the **grid owner** for additional details or required changes to the **metering installation**; and
  - (d) ensure that any reasonable changes to the **metering installation** or the **metering installation** configuration requested by the **grid owner** are carried out.
- (7) The **participant** responsible for providing the **metering installation** must—
- (a) advise the **reconciliation manager** of the **certification** expiry date of the **metering installation** no later than 10 **business days** after **certification** of the **metering installation**; and
  - (b) assume responsibility for being the **metering equipment provider** for the **metering installation** or contract with a person to assume responsibility for being the **metering equipment provider** for the **metering installation**; and
  - (c) advise the **reconciliation manager** of the **participant identifier** of the **metering equipment provider** under paragraph (b) by no later than 20 **business days** after,—
    - (i) if it is appointed under a contract, entering into the contract under paragraph (b); or
    - (ii) if it assumes responsibility for being the **metering equipment provider**, other than under a contract, assuming responsibility.
- (8) The **participant** responsible for providing the **metering installation** (unless the **participant** is a **grid owner**) must, in the case of a proposed modification to an existing **metering installation** under clause 19 of Schedule 10.7—
- (a) provide a copy of the **metering installation** design to the **grid owner** before ordering equipment or carrying out the modification to the **metering installation** design; and
  - (b) provide the **grid owner** with at least 3 months to review and comment on the **metering installation** design; and
  - (c) respond, within 3 **business days** of receipt, to any request from the **grid owner** for additional details or required changes to the **metering installation** or its configuration; and
  - (d) ensure that any reasonable changes to the **metering installation** or the **metering installation** configuration requested by the **grid owner** are carried out.
- (9) If the **grid owner** considers, acting reasonably, that a proposed new **metering installation**, or a proposed change to an existing **metering installation**, or its configuration, requires subtraction or a **loss compensation** or **error compensation** process to determine **submission information** for the purposes of Part 15, the **grid owner** must, unless an **error compensation** process is to be applied to the **metering installation** that is already within the applicable accuracy tolerances set out in Table 1 of Schedule 10.1—
- (a) provide all relevant details to the **Authority**, in the **prescribed form**, at least 20 **business days** before—
    - (i) the proposed date for installing the **metering installation**; or
    - (ii) the proposed date for changing the **metering installation** or **metering**

- installation's** configuration; and
- (b) respond, within 3 **business days** of receipt, to any request from the **Authority** for additional details; and
  - (c) ensure that any reasonable changes to the **metering installation** or its configuration requested by the **Authority** are carried out.
- (10) A **metering equipment provider** must ensure that the quantity of **electricity** conveyed through a **point of connection** to the **grid** for which there is a **metering installation** for which it is responsible is measured using a **half-hour metering installation**.
- (11) If a **metering installation** for a **point of connection** to the **grid** is **recertified**, the **participant** responsible for providing the **metering installation** must, within 10 **business days** of the date of **recertification**, advise the **reconciliation manager** of the **metering installation's** new **certification** expiry date.

Clause 10.26(1): amended, on 29 August 2013, by clause 16(1) of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011, Amendment 2013 (No 2).

Clause 10.26(2): amended, on 29 August 2013, by clause 16(2) of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011, Amendment 2013 (No 2).

Clause 10.26(3): amended, on 23 February 2015, by clause 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 10.26(4)(c)(ii): amended, on 23 February 2015, by clause 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 10.26(5)(b): amended, on 23 February 2015, by clause 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 10.26(3), (4), (5) and 9: amended, on 5 October 2017, by clause 163 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

#### **10.27 Change in responsibility for ensuring metering installation for point of connection to grid**

- (1) If a **participant** considers, on the basis of historical **metering data**, that there has been a change in the overall net flow of **electricity** at a **point of connection** to the **grid** over any 12 month period, the **participant** who is responsible for ensuring there is a **metering installation** may initiate the process under clauses 10.26(3) to 10.26(5) with all necessary amendments, in order to change the **participant** responsible for providing the **metering installation**.
- (2) If the **participant** who is responsible for ensuring there is a **metering installation** changes under subclause (1), the responsibility for providing **submission information** to the **reconciliation manager** under Part 15 changes.

#### *Connecting and electrically connecting points of connection*

Heading: amended, on 29 August 2013, by clause 17(1) of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011, Amendment 2013 (No 2).

Heading: amended, on 5 October 2017, by clause 164 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

#### **10.28 [Revoked]**

Clause 10.28: substituted, on 29 August 2013, by clause 17 of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011, Amendment 2013 (No 2).

Clause 10.28(2)(a), (2)(b) and (3): amended, on 23 February 2015, by clause 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 10.28: revoked, on 5 October 2017, by clause 165 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.



### **10.29 When grid owner may connect point of connection to grid**

(1A) Only a **grid owner** may connect a **point of connection** to the **grid**.

- (1) Despite subclause (1A), a **grid owner** must not connect a **point of connection** to the **grid** unless it has—
- (a) ensured that the processes described in clause 10.26 have been carried out; and
  - (b) requested, in the **prescribed form**, not less than 20 **business days** before the proposed connection date, authorisation from the **Authority**, to connect the **point of connection**; and
  - (c) obtained the authorisation referred to in paragraph (b) from the **Authority**.
- (2) The **grid owner** must, within 5 **business days** of connecting a **point of connection** to the **grid**, advise the **reconciliation manager** of—
- (a) the **point of connection** that has been connected; and
  - (b) the connection date.

Heading: amended, on 5 October 2017, by clause 166(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 10.29(1A): inserted, on 5 October 2017, by clause 166(2)(a) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 10.29(1) and (2): amended, on 5 October 2017, by clause 166(2)(b) to (d) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017. Clause 10.29: substituted, on 29 August 2013, by clause 18 of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011, Amendment 2013 (No 2).

Clause 10.29: amended, on 23 February 2015, by clause 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

### **10.29A When grid owner may temporarily electrically connect point of connection to grid**

- (1) Subject to clause 10.33, only a **grid owner** may temporarily **electrically connect** a **point of connection** to the **grid**.
- (2) A **grid owner** may temporarily **electrically connect** a **point of connection** to the **grid** that is to be quantified with a **category 1 metering installation**, or higher category of **metering installation**, only if a **metering equipment provider** requests that the **grid owner** temporarily **electrically connect** the **point of connection** to the **grid** for the purposes of—
- (a) **certifying a metering installation** at the **point of connection** to the **grid**; or
  - (b) maintaining, repairing, testing, or **commissioning a metering installation** at the **point of connection** to the **grid**.
- (3) Despite subclause (2), a **metering equipment provider** must not request that a **grid owner** temporarily **electrically connect** a **point of connection** to the **grid** unless—
- (a) the **grid owner** responsible for the **point of connection** has authorised the **metering equipment provider** to do so; and
  - (b) the **metering equipment provider** has an arrangement with that **grid owner** to provide **metering** services.

Clause 10.29A: inserted, on 5 October 2017, by clause 167 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

**10.30 When distributor or embedded network owner may connect NSP that is not point of connection to grid**

- (1A) Only a **distributor** that initiates, under Part 11, the creation of an **NSP** on the **distributor's network** that is not a **point of connection** to the **grid** may connect the **NSP** to—
- (a) an **embedded network**, if the **embedded network** owner has agreed to the connection; or
  - (b) a **local network**, if the **local network** owner has agreed to the connection.
- (1B) Only an **embedded network** owner that initiates, under Part 11, the creation of an **NSP** on its **embedded network**—
- (a) may connect the **NSP** to another **embedded network**; but
  - (b) can only do so if the other **embedded network** owner has agreed to the connection.
- (1) Despite subclause (1A), a **distributor** must not connect an **NSP** on its **network** that is not a **point of connection** to the **grid** unless requested to do so by the **reconciliation participant** responsible for ensuring there is a **metering installation** for the **point of connection**.
- (2) A **distributor** must, within 5 **business days** of connecting an **NSP**, advise the **reconciliation manager** of the following:
- (a) the **NSP** that has been connected; and
  - (b) the connection date; and
  - (c) the **participant identifier** of the **metering equipment provider** for each **metering installation** for the **NSP**; and
  - (d) the **certification** expiry date of each **metering installation** for the **NSP**.

Clause 10.30: substituted, on 29 August 2013, by clause 19 of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011, Amendment 2013 (No 2).

Clause 10.30: amended, on 23 February 2015, by clause 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 10.30: replaced, on 5 October 2017, by clause 168 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

**10.30A When distributor may temporarily electrically connect NSP that is not point of connection to grid**

- (1) Subject to clause 10.33, only a **distributor** that initiates, under Part 11, the creation of an **NSP** on the **distributor's network** that is not a **point of connection** to the **grid** may temporarily **electrically connect** the **NSP** to—
- (a) an **embedded network**, if the **embedded network** owner has agreed to the temporary **electrical connection**; or
  - (b) a **local network**, if the **local network** owner has agreed to the temporary **electrical connection**.
- (2) Subject to clause 10.33, only an **embedded network** owner that initiates, under Part 11, the creation of an **NSP** on its **embedded network**—
- (a) may temporarily **electrically connect** the **NSP** to another **embedded network**; but

- (b) can only do so if the other **embedded network** owner has agreed to the temporary **electrical connection**.
- (3) A **distributor** may only temporarily **electrically connect** an **NSP** that is not a **point of connection** to the **grid** if a **metering equipment provider** requests that the **distributor** temporarily **electrically connect** the **NSP** for the purposes of—
  - (a) **certifying a metering installation** at the **NSP**; or
  - (b) maintaining, repairing, testing, or **commissioning a metering installation** at the **NSP**.
- (4) Despite subclause (3), a **metering equipment provider** must not request that a **distributor** temporarily **electrically connect** an **NSP** that is not a **point of connection** to the **grid** unless—
  - (a) the **reconciliation participant** responsible for the **NSP** authorises the **metering equipment provider** to do so; and
  - (b) the **metering equipment provider** has an arrangement with that **reconciliation participant** to provide **metering** services.

Clause 10.30A: inserted, on 5 October 2017, by clause 169 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### 10.31 When distributor may connect ICP that is not NSP

- (1) Only a **distributor** may connect an **ICP** that is not an **NSP**.
- (2) Despite subclause (1), a **distributor** must not connect an **ICP** that is not an **NSP** unless the **trader** trading at the **ICP** has requested the connection.

Clause 10.31: substituted, on 29 August 2013, by clause 20 of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011, Amendment 2013 (No 2).

Clause 10.31(a): amended, on 23 February 2015, by clause 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 10.31: replaced, on 5 October 2017, by clause 170 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### 10.31A When distributor may temporarily electrically connect ICP that is not NSP

- (1) Subject to clause 10.33, only a **distributor** may temporarily **electrically connect** an **ICP** that is not an **NSP**.
- (2) A **distributor** may only temporarily **electrically connect** an **ICP** that is not an **NSP** if a **metering equipment provider** requests that the **distributor** temporarily **electrically connect** the **ICP** for the purposes of—
  - (a) **certifying a metering installation** at the **ICP**; or
  - (b) maintaining, repairing, testing, or **commissioning a metering installation** at the **ICP**.
- (3) Despite subclause (2), a **metering equipment provider** must not request that a **distributor** temporarily **electrically connect** an **ICP** that is not an **NSP** unless—
  - (a) the **trader** responsible for the **ICP** has authorised the **metering equipment provider** to do so; and
  - (b) the **metering equipment provider** has an arrangement with that **trader** to provide **metering** services.

Clause 10.31A: inserted, on 5 October 2017, by clause 171 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### 10.32 Reconciliation participant requesting connection of point of connection

For the purposes of clauses 10.30(1) and 10.31(2), a **reconciliation participant** must only request the connection of a **point of connection** if the **reconciliation participant**—

- (a) accepts responsibility for the **reconciliation participant's** obligations in this Part and Parts 11 and 15 for the **point of connection**; and
- (b) has an arrangement with a **metering equipment provider** to provide 1 or more **metering installations** for the **point of connection**.

Clause 10.32 Heading: amended, on 29 August 2013, by clause 21(1) of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011, Amendment 2013 (No 2).

Clause 10.32 Heading: amended, on 5 October 2017, by clause 172(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 10.32: amended, on 29 August 2013, by clause 21(2) of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011, Amendment 2013 (No 2).

Clause 10.32: amended, on 5 October 2017, by clause 172(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### 10.33 When reconciliation participant may temporarily electrically connect point of connection

- (1) A **reconciliation participant** may temporarily **electrically connect** a **point of connection**, or authorise a **metering equipment provider** to temporarily **electrically connect** a **point of connection** under subclause (2), only if—
  - (a) the **reconciliation participant** is recorded in the **registry** as being responsible for the **ICP**; and
  - (b) 1 or more **certified metering installations** are in place in accordance with this Part; and
  - (c) in the case of an **ICP** that has not previously been **electrically connected**, the owner of the **network** to which the **point of connection** is connected has given written approval of the temporary **electrical connection**.
- (2) A **reconciliation participant** described in subclause (1)(a) may authorise a **metering equipment provider**, with which the **reconciliation participant** has an arrangement, to request the temporary **electrical connection** of a **point of connection** only for the purposes of—
  - (a) **certifying a metering installation** at the **point of connection**; or
  - (b) **maintaining, repairing, testing, or commissioning a metering installation** at the **point of connection**.
- (3) *[Revoked]*
- (4) *[Revoked]*

Heading: amended, on 5 October 2017, by clause 173(a) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 10.33: substituted, on 29 August 2013, by clause 22 of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011, Amendment 2013 (No 2).

Clause 10.33(1): amended, on 5 October 2017, by clause 173(b) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 10.33(1)(c): amended, on 23 February 2015, by clause 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 10.33(1)(c): amended, on 1 February 2016, by clause 27 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

Clause 10.33(2): replaced, on 5 October 2017, by clause 173(c) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 10.33(3) and (4): revoked, on 5 October 2017, by clause 173(d) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

**10.33A When reconciliation participant may electrically connect point of connection**

- (1) A **reconciliation participant** may **electrically connect** a **point of connection**, or authorise the **electrical connection** of a **point of connection**, only if—
  - (a) the **reconciliation participant** is recorded in the **registry** as being responsible for the **ICP**; and
  - (b) 1 or more **certified metering installations** are in place at the **ICP** in accordance with this Part; and
  - (c) in the case of an **ICP** that has not previously been **electrically connected**, the owner of the **network** to which the **point of connection** is connected has given written approval of the **electrical connection**.
- (2) A **reconciliation participant** described in subclause (1)(a)—
  - (a) may authorise the **electrical connection** of an **ICP** if—
    - (i) a **metering installation** is in place at the **ICP**; and
    - (ii) the **metering installation** is operational but not **certified**; and
    - (iii) the **reconciliation participant** arranges for the **certification** of the **metering installation** to be completed within 5 **business days** of the **ICP** being **electrically connected**;
  - (b) may **electrically connect** an **ICP** if the **point of connection** is solely for **unmetered load**.
- (3) A **reconciliation participant** must not authorise the **electrical connection** of a **point of connection** in either of the following circumstances:
  - (a) a **distributor** has **electrically disconnected** the **point of connection** for safety reasons, and has not subsequently approved the **electrical connection** of the **point of connection**;
  - (b) **electrically connecting** the **point of connection** would breach the Electricity (Safety) Regulations 2010.
- (4) No **participant** may **electrically connect** a **point of connection**, or authorise the **electrical connection** of a **point of connection**, other than a **reconciliation participant** in the circumstances described in subclause (1), (2), or (3).

Clause 10.33A: inserted, on 5 October 2017, by clause 174 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

*General metering installation requirements*

**10.34 Installation and modification of metering installations**

- (1) This clause applies to a **metering equipment provider** that proposes to install or modify a **metering installation** at a **point of connection** other than a **point of connection** to the **grid**.
- (2) The **metering equipment provider** must consult with the **distributor** and the **trader** for the **point of connection** on the matters specified in subclause (2A), before—
  - (a) finalising the design of a **metering installation** for the **point of connection**; or
  - (b) modifying the design of a **metering installation** installed at the **point of connection**.
- (2A) The matters referred to in subclause (2) are the **metering installation's**—

- (a) required functionality; and
  - (b) terms of use; and
  - (c) required interface format; and
  - (d) integration of the ripple receiver and the **meter**; and
  - (e) functionality for controllable load.
- (3) Each **participant** involved in the consultation referred to in subclause (2) must—
- (a) use its best endeavours to reach agreement; and
  - (b) act reasonably and in good faith.
- (4) If the **participants** referred to in subclause (2) cannot agree, within 20 **business days** of the **distributor** first being advised of the proposed new or modified **metering installation**, on the **metering installation's** requirements set out in subclause (2A)(a) to (e)—
- (a) an affected **participant** may refer the matter to the **Authority** under clause 10.50 by advising the **Authority**—
    - (i) that agreement has not been reached; and
    - (ii) of the identity of all affected **participants**; and
    - (iii) the reasons (if and to the extent known) why agreement was not reached; and
  - (b) the **Authority**—
    - (i) may, at its discretion, determine the **metering installation** requirements; and
    - (ii) must, if it determines the **metering installation** requirements,—
      - (A) do so in accordance with clause 10.50(4); and
      - (B) advise each affected **participant** of the determination it has made

Clause 10.34(1) and (2): substituted, on 1 February 2016, by clause 28(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

Clause 10.34(2): amended, on 1 May 2016, by clause 6 of the Electricity Industry Participation Code Amendment (Minor Code Amendments) 2016.

Clause 10.34(2A): inserted, on 1 February 2016, by clause 28(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

Clause 10.34(4): amended, on 1 February 2016, by clause 28(3) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

### 10.35 Physical location of metering installations

- (1) A **reconciliation participant** responsible for ensuring there is a **category 1 metering installation** or **category 2 metering installation** must ensure that the **metering installation** is located as physically close to a **point of connection** as practical in the circumstances.
- (2) A **reconciliation participant** responsible for ensuring there is a category 3 or higher **metering installation** must,—
- (a) if practical in the circumstances, ensure that the **metering installation** is located at a **point of connection**; or
  - (b) if it is not practical in the circumstances to locate the **metering installation** at the **point of connection**, calculate the quantity of **electricity** conveyed through the **point of connection** using a **loss compensation** process approved by the **certifying ATH**.
- (3) If a calculation is carried out under subclause (2)(b), the certifying **ATH** must record in

the **metering installation certification report**—

- (a) the details of the calculation; and
  - (b) any assumption used; and
  - (c) any measurement used.
- (4) This clause does not apply to an existing **metering installation** that is in place on 29 August 2013.

Clause 10.35(3): amended, on 29 August 2013, by clause 23(1) of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011, Amendment 2013 (No 2).

Clause 10.35(4): amended, on 29 August 2013, by clause 23(2) of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011, Amendment 2013 (No 2).

### 10.36 Reconciliation participant to have arrangement with metering equipment provider

A **reconciliation participant** must, before accepting responsibility to be the **reconciliation participant** for a **point of connection**, enter into an arrangement with a **metering equipment provider**—

- (a) for the **reconciliation participant** to provide the **metering equipment provider** with physical access to the **metering installation** for the **point of connection** and the premises at which it is situated; and
- (b) arranging for the **electrical disconnection** of the **point of connection**, if required by the **metering equipment provider** to enable the **metering equipment provider** to comply with its obligations under this Part; and
- (c) for the **metering equipment provider** to provide the **reconciliation participant** with access at the **services access interface** to the **metering data** from the **metering installation** for the **point of connection**, in accordance with an authorisation from—
  - (i) in the case of an **ICP**, the **consumer**; or
  - (ii) in the case of an **NSP**, the **network owner**.

Clause 10.36(b): amended, on 5 October 2017, by clause 175 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### *Active and reactive energy metering*

### 10.37 Active and reactive measuring and recording requirements

- (1) A **metering equipment provider** must ensure that each **half-hour metering installation** that is a **category 3 metering installation**, or higher category of **metering installation**, **certified** after 29 August 2013, measures and separately records, in accordance with this Part,—
- (a) if the measuring and recording requirement is for consumption only—
    - (i) import **active energy**; and
    - (ii) import **reactive energy**; and
    - (iii) export **reactive energy**; or
  - (b) if the measuring and recording requirement is for consumption and generation, or generation only—
    - (i) import **active energy**; and
    - (ii) export **active energy**; and
    - (iii) import **reactive energy**; and
    - (iv) export **reactive energy**.

- (1A) A **metering equipment provider** must ensure that each **half-hour metering installation** that is a **category 2 metering installation, certified** after 29 August 2013, is capable of measuring and recording—
- (a) import **active energy**; and
  - (b) export **active energy**; and
  - (c) import **reactive energy**; and
  - (d) export **reactive energy**.
- (1B) A **metering equipment provider** must ensure that each **half-hour metering installation** that is a **category 2 metering installation, certified** after 29 August 2013, measures and separately records, in accordance with this Part,—
- (a) if the measuring and recording requirement is for consumption only, import **active energy**; or
  - (b) if the measuring and recording requirement is for consumption and generation, or generation only—
    - (i) import **active energy**; and
    - (ii) export **active energy**.
- (2) Despite subclauses (1)(a) and (1B)—
- (a) each **metering installation**, for a **point of connection** to the **grid, certified** after 29 August 2013, must measure and separately record—
    - (i) import **active energy**; and
    - (ii) export **active energy**; and
    - (iii) import **reactive energy**; and
    - (iv) export **reactive energy**; and
  - (b) the accuracy of each local service **metering installation** for **electricity** used in and by a **grid** substation must be within the applicable accuracy tolerances set out in Table 1 of Schedule 10.1.

Clause 10.37: amended, on 29 August 2013, by clause 24 of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011, Amendment 2013 (No 2).

Clause 10.37(1): amended, on 1 February 2016, by clause 29(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

Clause 10.37(1A) and (1B): inserted, on 1 February 2016, by clause 29(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

Clause 10.37(2): amended, on 1 February 2016, by clause 29(3) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

### *Certification of metering installations*

#### **10.38 Certification of metering installations**

A **metering equipment provider** must—

- (a) obtain and maintain **certification** in accordance with this Part—
  - (i) for each **metering installation** for which it is responsible; and
  - (ii) for each **metering component** in a **metering installation** for which it is responsible; and
- (b) ensure that any tests required for **certification** under paragraph (a) are conducted in accordance with this Code including the obligations under Schedule 10.7 or 10.8 (whichever is applicable) by an **ATH** contracted by the **metering equipment provider**.



*Metering infrastructure*

**10.39 Responsibility for metering infrastructure integration**

- (1) A **metering equipment provider** must ensure that—
  - (a) for each **metering installation** for which it is responsible, an appropriately designed **metering infrastructure** is in place; and
  - (b) in each **metering installation** for which it is responsible,—
    - (i) each **metering component** is compatible with, and will not cause any interference with the operation of, any other **metering component** in the **metering installation**; and
    - (ii) collectively, all **metering components** integrate to provide a functioning system; and
  - (c) each **metering installation** for which it is responsible is correctly and accurately integrated within the associated **metering infrastructure**.
- (2) Subclause (1) does not apply to an **electrically disconnected metering installation** for an **ICP**.

Clause 10.39(2): amended, on 5 October 2017, by clause 176 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

*Approved test houses and ATHs*

**10.40 General requirements for approval as ATH**

- (1) A person wishing to be approved as an **ATH**, or an **ATH** wishing to renew its approval, must apply to the **Authority**—
  - (a) at least 2 months before the intended effective date of the approval or renewal; and
  - (b) in writing; and
  - (c) in the **prescribed form**; and
  - (d) in accordance with Schedule 10.3.
- (2) A person making an application must satisfy the **Authority** (providing, where appropriate, suitable evidence) that the person—
  - (a) has the facilities and procedures to reliably meet, for the requested term of the approval, the minimum requirements of this Code for the class or classes of **ATH** for which it is seeking approval; and
  - (b) has had an **audit** under Part 16A; and
  - (c) is a fit and proper person for approval.
- (3) Any **approved test house** operated solely by an **ATH** is, for all purposes of this Code and the **Act**, deemed to be approved in accordance with the procedures in the Code.

Clause 10.40(2)(b): amended, on 1 June 2017, by clause 9 of the Electricity Industry Participation Code Amendment (Requirements and Processes for Audits) 2016.

**10.41 Requirements applying to ATHs**

An **ATH** must, when carrying out activities under this Part,—

- (a) only carry out activities for which it has been approved by the **Authority**; and
- (b) exercise a degree of skill, diligence, prudence, foresight, and economic management, taking into account the technological complexity of the **metering**

- components** and **metering installations** being tested—
- (i) determined by reference to good industry practice; and
  - (ii) that would reasonably be expected from a skilled and experienced **ATH** engaged in the management and operation of an **approved test house**; and
- (c) comply with all applicable safety, employment, environmental, and other enactments; and
- (d) exercise any discretion given to it under this Part by—
- (i) taking into account the relevant circumstances of the particular instance; and
  - (ii) acting professionally; and
- (e) record the manner in which it carried out its activities and its reasons for carrying the activities out in that manner.

#### 10.42 ATH's functions and ongoing obligations

- (1) An **ATH** must comply with this Code including Schedules 10.4, 10.7, and 10.8.
- (2) An **ATH** must, if this Part requires an **ATH** to complete a function or activity before a **metering installation** is **certified**, complete the function or activity as part of the process undertaken to obtain **certification** for the **metering installation**.

*Metering installations that are inaccurate, defective, or not fit for purpose*

#### 10.43 Metering installations that are inaccurate, defective, or not fit for purpose to be investigated

- (1) For the purposes of this clause and clauses 10.44 to 10.48, a **metering installation** is—
  - (a) accurate, if it is within the applicable accuracy tolerances set out in Table 1 of Schedule 10.1;
  - (b) inaccurate, if it is outside the applicable accuracy tolerances set out in Table 1 of Schedule 10.1.
- (2) A **participant** must comply with this clause and clauses 10.44 to 10.48 if—
  - (a) in the case of a **metering equipment provider**, it is advised under subclause (3)(a); or
  - (b) it becomes aware of an event or circumstance that leads it to believe a **metering installation** is or could be—
    - (i) inaccurate; or
    - (ii) defective; or
    - (iii) not fit for purpose.
- (3) A **participant** referred to in subclause (2)(b), other than the **metering equipment provider** responsible for the **metering installation**, must—
  - (a) advise the **metering equipment provider** responsible for the **metering installation** that it has become aware of an event or circumstance that leads it to believe the **metering installation** is or could be—
    - (i) inaccurate; or
    - (ii) defective; or
    - (iii) not fit for purpose; and
  - (b) include, with the advice (if and to the extent they are known), all relevant details.

- (4) A **metering equipment provider** must, if it is advised under subclause (3)(a), or becomes aware as referred to in subclause (2)(b), within the period set out in subclause (5),—
  - (a) investigate—
    - (i) if it is advised under subclause (3)(a), the event or circumstance that it is advised of; or
    - (ii) if it becomes aware as referred to in subclause (2)(b), the event or circumstance that leads it to believe the **metering installation** is or could be—
      - (A) inaccurate; or
      - (B) defective; or
      - (C) not fit for purpose; and
  - (b) complete, or arrange the completion of, a report that contains details of the **metering equipment provider's** investigation, its conclusion, and the reasons for its conclusion; and
  - (c) provide the report to all affected **participants**.
- (5) The time period for the purposes of subclause (4) is as soon as reasonably practicable, but no later than—
  - (a) 20 **business days** after becoming aware of the event or circumstance, for a **category 1 metering installation**;
  - (b) 10 **business days** after becoming aware of the event or circumstance, for a **category 2 metering installation**;
  - (c) 5 **business days** after becoming aware of the event or circumstance, for a category 3 or higher **metering installation**.

#### 10.44 Metering installations that are inaccurate, defective, or not fit for purpose to be tested

- (1) A **metering equipment provider** must, if a report provided under clause 10.43(4)(c) demonstrates that a **metering installation** for which it is responsible is inaccurate, defective, or not fit for purpose—
  - (a) arrange testing of the **metering installation** by an **ATH**; and
  - (b) arrange the provision of a statement of situation referred to in clause 10.46 by the **ATH**.
- (2) If the report demonstrates that a **metering installation** is accurate, not defective, and fit for purpose, a **participant** who believes that the **metering installation** is inaccurate, defective, or not fit for purpose, may require testing of the **metering installation** by—
  - (a) advising the **metering equipment provider** responsible for the **metering installation**, within 5 **business days** of receiving the report, of—
    - (i) its reasons for requiring testing; and
    - (ii) the scope of the testing required; and
  - (b) using its best endeavours to agree with the **metering equipment provider** on an **ATH** who will test the **metering installation** and provide a statement of situation under subclause (1).
- (3) A **metering equipment provider** who has been advised under subclause (2)(a) that a

**participant** believes that a **metering installation**, for which the **metering equipment provider** is responsible, requires testing, must arrange for an **ATH**—

- (a) to test the **metering installation**; and
  - (b) to provide the **metering equipment provider** with a statement of situation under subclause (1)(b) within 5 **business days** of—
    - (i) becoming aware that a **metering installation** for which it is responsible may be inaccurate, defective, or not fit for purpose under subclause (1); or
    - (ii) reaching an agreement with the **participant** under subclause (2)(b).
- (4) If the **metering equipment provider** and the **participant** requesting the test under subclause (2) cannot, within 5 **business days** of the **metering equipment provider** being advised under subclause (2)(a), agree on an **ATH**, either **participant** may advise the **Authority**, including the reasons, if and to the extent known, why agreement was not reached.
- (5) The **Authority** must, within 5 **business days** of being advised under subclause (4), advise the **metering equipment provider** of the **ATH** that it must instruct to carry out the testing and to provide a statement of situation under subclause (1)(b).
- (6) The **metering equipment provider** must instruct the **ATH** referred to in subclause (5) within 5 **business days** of being advised by the **Authority**.
- (7) The **metering equipment provider** must ensure that the **ATH**, as soon as practicable after being contracted under subclause (1) or subclause (5), carries out the required testing and delivers the statement of situation to the **metering equipment provider**.
- (8) Despite anything else in this Code, a **participant** is in breach of this Code from when the tests carried out by an **ATH** under this clause demonstrate that a **metering installation** is—
- (a) inaccurate; or
  - (b) defective; or
  - (c) not fit for purpose.

Clause 10.44(4), (5) and (6): amended, on 5 October 2017, by clause 177 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

#### 10.45 Investigation and testing costs

The **ATH**'s costs incurred by the **metering equipment provider** under clause 10.44 must be borne by—

- (a) the **metering equipment provider**, if the investigation or test demonstrates that the **metering installation** is—
  - (i) defective; or
  - (ii) inaccurate; or
  - (iii) not fit for purpose; or
- (b) the **participant** who required that the **metering installation** be investigated or tested, if the investigation or test demonstrates that the **metering installation** is—
  - (i) not defective; and
  - (ii) accurate; and
  - (iii) fit for purpose.

#### 10.46 Statement of situation

- (1) A statement of situation provided by an **ATH** under clause 10.44(1)(b) must include—
  - (a) details of the tests carried out; and
  - (b) results of the tests carried out; and
  - (c) full details of what was found; and
  - (d) conclusions of whether the **metering installation** is—
    - (i) accurate;
    - (ii) defective;
    - (iii) fit for purpose; and
  - (e) the reasons for the conclusions in paragraph (d); and
  - (f) an assessment of the risk to the completeness and accuracy of the **raw meter data**; and
  - (g) the details of any remedial action proposed or undertaken; and
  - (h) any correction factors to apply to **raw meter data** to ensure that the **volume information** is accurate; and
  - (i) the period over which the correction factor must be applied to the **raw meter data**.
- (2) A **metering equipment provider** must, within 3 **business days** of receiving the statement of situation, provide copies of it—
  - (a) to the relevant affected **participants** for all **metering installations**; and
  - (b) to the **Authority**—
    - (i) for all category 3 and above **metering installations**; and
    - (ii) if requested by the **Authority**, for each **category 1 metering installation** and each **category 2 metering installation**.

Clause 10.46(2): substituted, on 15 May 2014, by clause 13 of the Electricity Industry Participation (Minor Code Amendments) Code Amendment 2014.

Clause 10.46(2) (b): amended, on 5 October 2017, by clause 178 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

#### 10.47 Correction of defects and inaccuracies in metering installation

An **ATH** must, when taking action to remedy an inaccuracy or defect within a **metering installation**, ensure that records of any modifications that are carried out to the **metering installation** are kept for each **metering component** of the **metering installation** in the **metering records** and in a manner reasonable in the circumstances to ensure that further investigation can be carried out.

#### 10.48 Correction of defects and inaccuracies in raw meter data

- (1) A **participant** may, within 40 **business days** of receiving a statement of situation under clause 10.46(2), advise the **metering equipment provider** of any questions, or requests for clarification, it has in relation to the corrections needed to the **raw meter data** from the **metering installation**.
- (2) A **metering equipment provider** must, within 10 **business days** of being advised under subclause (1), respond in detail to the questions or requests for clarification.
- (3) A **metering equipment provider** must, within 10 **business days** of being advised under subclause (1), advise the **reconciliation participant** responsible for providing

**submission information** for the **point of connection**, of the correction factors referred to in clause 10.46(1)(h) and the period referred to clause 10.46(1)(i).

- (4) The **reconciliation participant** must apply the correction factors advised under subclause (3), for the period advised under subclause (3), to the **raw meter data** to obtain more accurate information as required under clause 15.12.

#### *NSP table*

##### **10.49 NSP table**

- (1) The **Authority** must **publish** an **NSP table**.(2)The **reconciliation manager** must advise the **Authority** of any change to the information contained in the **NSP table** within 1 **business day** of becoming aware of such change.
- (3) The **Authority** must update the **NSP table** within 2 **business days** of being advised by the **reconciliation manager** under subclause (2).

Clause 10.49(1): replaced, on 5 October 2017, by clause 179(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 10.49(2) and (3): amended, on 5 October 2017, by clause 179(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

#### *Dispute resolution*

##### **10.50 Dispute resolution**

- (1) A **participant** must, in good faith, use its best endeavours to resolve any dispute with any other person about a matter dealt with in this Part.
- (2) A **participant** may refer any dispute or failure to reach agreement within the required timeframe in this Part to the **Authority** for determination.
- (3) A complaint may, if it is not resolved under subclause (1), or by determination of the **Authority** under subclause (2), be referred to the **Rulings Panel** in accordance with subpart 4 of Part 2 of the **Act** and the **regulations**, by the **Authority** or a **participant**.
- (4) When determining a dispute, or failure to reach agreement, under subclause (2), the **Authority** must do so in a way that—
  - (a) is consultative with the parties involved; and
  - (b) encourages the parties, where possible, to work together on matters that are agreed; and
  - (c) takes into account the costs to be borne by, and the benefits that would accrue to, the **participants** involved; and
  - (d) maximises the use of informal means to resolve the dispute or conclude an agreement.
- (5) The existence of a dispute or failure to reach agreement does not excuse a **participant** from complying with this Code.
- (6) A **participant's** obligations in this clause are subject to the **Act** and the **regulations**.

*Transitional provisions*

**10.51 Transitional provisions**

- (1) In this clause—
  - (a) Part 10 means Part 10 of the Code that was effective prior to 29 August 2013; and
  - (b) reference to a COP means a **code of practice** under Part 10.
- (2) The intent of this clause is—
  - (a) as far as practicable, to preserve the effect of Part 10, prior to 29 August 2013; and
  - (b) to clarify that a breach of Part 10 will subsist as a breach of the Code, despite the coming into force of this Part; and
  - (c) to clarify that disputes and complaints about breaches under Part 10 must be resolved under this Part, and to provide the procedure to ensure that will happen; and
  - (d) to clarify that certain exemptions, authorisations, and **code of practice 10.5** variations under Part 10 will remain in force in accordance with their terms, as if they had been made under this Part; and
  - (e) to clarify the effect of certain contractual arrangements after this Part comes into force; and
  - (f) to clarify the effect of a **participant** being in compliance with certain of the provisions in Part 10, after this Part comes into force.
- (3) A **certification**, as at 28 August 2013, of—
  - (a) a **metering installation**—
    - (i) as a **category 1 metering installation** that had interim **certification** under Part 10, continues under this Part until 1 April 2015; and
    - (ii) as a category 6 **metering installation**, continues as a category 5 **metering installation** and otherwise in accordance with the terms of the **certification**; and
    - (iii) as any other category, continues under this Part in accordance with the terms of the **certification**; and
  - (b) a **metering component** continues under this Part in accordance with the terms of the **certification**.
- (4) An **audit** that was carried out under the Code by an **auditor**, that was completed, immediately prior to 29 August 2013, continues to have the effect and status of an **audit** under this Part.
- (5) The following persons **certified** and approved by the Electricity Commission or the **Authority**, under the Code, immediately prior to 29 August 2013, remain, for all purposes of this Part, **certified** and approved by the **Authority**, in accordance with the terms and scope of the relevant **certification** and approval as if such **certification** and approval had been issued under this Part:
  - (a) an **auditor**; and
  - (b) an **approved test house**, which will be approved as an **ATH** under this Part.
- (6) The following continue in effect despite anything else in, or the coming into force of, this Part, to the extent that they relate to or concern the same, or similar, obligations

- under this Part, and will apply to a **participant's** obligations under or compliance with, the relevant obligation under this Part:
- (a) an approval for an alternative quality management system previously issued under clauses 4(4) and 6(12) of COP 10.2;
  - (b) an approval for an alternative standard previously issued under clause 3(4) of COP 10.2 and clause 2 of COP 10.2 and 10.3;
  - (c) a variation under clause 3(15) or 4(7) to 4(9) of COP 10.3;
  - (d) a temporary **certification** under clause 9(17) of COP 10.3;
  - (e) an alternative standard that an **approved test house** has used in the **certification** of a **metering installation** under clause 2 of COP 10.3 and clause 2 of COP 10.4;
  - (f) a variation approved by the market administrator under COP 10.5;
  - (g) a statistical sampling process under clause 5(18) of COP 10.3;
  - (h) an exemption under section 11 of the **Act**.
- (7) An **ATH** must, if it has **certified a metering installation** using an alternative standard referred to in subclause (6)(e), in accordance with Part 10, advise the **Authority** of that alternative standard within 3 **business days** of 29 August 2013.
- (8) The following continue in effect, despite anything else in, or the coming into force of, this Part, to the extent that they relate to or concern the same, or similar, obligations under this Part, and apply to a **participant's** obligations under or compliance with, the relevant obligation under this Part:
- (a) **calibration** intervals referred to in clause 6(1) of COP 10.2; and
  - (b) the maximum intervals between inspections referred to in clause 9(2) of COP 10.3, provided that if the date by which the next inspection would, under this Part, be later, then such later date will apply.
- (9) Despite anything else in, or the coming into force of, this Part—
- (a) clause 10.4 and clauses 10.12 to 10.15 of Part 10 continue to apply insofar as they relate to all **raw meter data interrogated** and processed under Part 10, on which **submission information** is based that is still subject to the reconciliation process under Part 15, until the reconciliation process for the **submission information** has been concluded in accordance with Part 15; and
  - (b) clauses 10.7(b) and (c) of Part 10 continue to apply in relation to all **raw meter data** recorded before 29 August 2013; and
  - (c) an **approved test house's** obligations under clauses 5(16) and 5(17) of COP 10.2 and clause 4(12) of COP 10.3 will continue in accordance with their terms in relation to all records created before 29 August 2013.
- (10) If a **participant** is a party to an arrangement, assignment, or contract (including an agency agreement) previously entered into under clauses 10.2, 10.3, or 10.6 of Part 10 in relation to a **participant's** responsibilities under Part 10 and a provision in that arrangement, assignment, or contract is inconsistent with this Part, the provision ceases to be effective from 29 August 2013, but this is without prejudice to any existing disputes under such arrangements, assignments, or contracts, that must be resolved between the relevant persons concerned in accordance with the arrangement, assignment, or contract as if it remained effective.
- (11) Despite anything else in, or the coming into force of, this Part—



- (a) any dispute concerning a **metering installation, metering data, raw meter data**, and all related matters that were in existence immediately before 29 August 2013,—
    - (i) remain in existence; and
    - (ii) may be resolved under clause 10.50; and
  - (b) any breaches or alleged breaches of Part 10, and investigations of rule breaches or alleged rule breaches under Part 10, are unaffected and must be concluded as if the relevant provisions alleged to have been breached, under Part 10, and the relevant Part 10 definitions remain in force; and
  - (c) any rule breaches or alleged rule breaches described in paragraph (b) will be dealt with by the **Authority** and the **Rulings Panel** under clause 10.50 and the **Act**.
- (12) Despite anything else in, or the coming into force of, this Part, subclause (13) applies to a **participant** who was immediately prior to 29 August 2013 responsible under Part 10 for—
- (a) measuring the quantity of **electricity** at any **metering installation**; or
  - (b) estimating the quantity of **unmetered load**.
- (13) A **participant** described in subclause (12), who is responsible for **volume information** which has not, at 29 August 2013, been submitted to the **reconciliation manager** in accordance with Part 15 must complete the submission of the **volume information** to the **reconciliation manager** in accordance with Part 10, as if that Part remained effective.
- (14) Despite anything else in, or the coming into force of, this Part, a **participant** who is responsible for a **metering installation** under Part 10, immediately prior to 29 August 2013 must remain in compliance with—
- (a) clauses 10.7(b) and 10.7(c) of Part 10, in respect of **raw meter data** kept before 29 August 2013, and does not breach any of the corresponding obligations in this Part, provided that the **participant** keeps the **raw meter data** in compliance with clauses 10.7(b) and 10.7(c) of Part 10; and
  - (b) clause 10 of COP 10.3, in respect of records kept before 29 August 2013, and does not breach any of the corresponding obligations in this Part, provided that the **participant** keeps the records in compliance with rule 10 of COP 10.3.
- (15) The following procedures commenced before, but not completed by, 29 August 2013 are not valid unless they are completed in compliance with this Part:
- (a) **metering installation** tests; and
  - (b) **audits** of an **approved test house** under Part 10 (which must be completed as an **audit** of an **ATH** under this Part).
- (16) The obligations of a **metering equipment provider** expressed in this Part as applying in relation to arranging **certification** of a **metering installation** or a **metering component** after 29 August 2013 do not apply to—
- (a) a **metering installation** referred to in subclause (3)(a);
  - (b) a **metering component** referred to in subclause 3(b).

Clause 10.51: amended, on 29 August 2013, by clause 25 of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011, Amendment 2013 (No 2).

Clause 10.51(6)(f): amended, on 5 October 2017, by clause 180 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

## Schedule 10.1 Tables

cls 10.37 and 10.43

**Table 1: Metering installation characteristics and associated requirements**

Defining Characteristics				Associated Requirements of active energy metering							
Metering installation category	Primary voltage (V)	Primary current (I)	Measuring transformers	Metering installation certification type	Accuracy tolerances		Selected component metering installation minimum IEC class (more accurate components may be used)		Metering installation certification and inspection		
					Maximum permitted error	Maximum site uncertainty	Meter	Current Transformer	Maximum metering installation certification validity period	Maximum sample inspection and recertification period	Inspection period
1	V < 1kV	I ≤ 160A	None	NHH or HHR	± 2.5%	0.6%	2	N/A	180 months	84 months	120 months ± 6 months
2	V < 1kV	I ≤ 500A	CT	NHH or HHR	± 2.5%	0.6%	2	1	120 months	N/A	120 months ± 6 months
3	V < 1kV	500A < I ≤ 1200A	CT	HHR only	± 1.25%	0.3%	1	0.5	120 months	N/A	60 months ± 3 months
	1kV ≤ V ≤ 11kV	I ≤ 100A	N/A				N/A				
	11kV < V ≤ 22kV	I ≤ 50A	N/A				N/A				
4	V < 1kV	I > 1200A	CT	HHR only	± 1.25%	0.3%	N/A	N/A	60 months	N/A	30 months ± 3 months
	1kV ≤ V ≤ 6.6kV	100A < I ≤ 400A	VT & CT								
	6.6kV < V ≤ 11kV	100A < I ≤ 200A									
	11kV < V ≤ 22kV	50A < I ≤ 100A									
5	1kV ≤ V ≤ 6.6kV	I > 400A	VT & CT	HHR only	± 0.75%	0.2%	N/A	N/A	36 months	N/A	18 months ± 1 month
	6.6kV < V ≤ 11kV	I>200A									
	V > 11kV	I > 100A									
	V > 22kV	Any current									

**Table 2: Maximum certification validity periods for the purposes of clause 1(2) of Schedule 10.8**

<b>Metering installation category</b>	<b>Class 0.2 meter (months)</b>	<b>Class 0.5 meter (months)</b>	<b>Class 1.0 meter (months)</b>	<b>Class 2.0 meter (months)</b>
1	180	180	180	180
2	120	120	120	120
3 where $V < 1\text{kV}$	120	120	120	N/A
3 where $V \geq 1\text{kV}$	120	120	N/A	N/A
4	60	60	N/A	N/A
5	36	N/A	N/A	N/A

**Table 3: Selected component certification and comparative recertification minimum test requirements**

Event		Design	Measuring transformer	Meter	Primary injection to meter	Prevailing load	Data storage device	Software security and communication equipment	Control device	Wiring check	Component certification check	Review of compensation factors	Raw meter data output	Supply polarity	Register advance	Installation or component configuration
Metering installation	Initial certification category 1	M						M		M	M	M	M	M	M	M
	Initial certification categories 2 and 3	M				M		M		M	M	M	M	M	M	M
	Recertification of category 1 if the meter is not replaced and recertification of categories 2 and 3	M				M		M		M	M	M	M	M	M	M
	Recertification category 1 where meter is replaced with a certified meter	M						M		M	M	M	M	M	M	M
Component change or recertification	Meter change including internal data storage devices	M		M		M	M	M		M		M	M	M	M	M
	Metrology change either onsite or remote	M		M			M	M				M	M		M	M
	External data storage device change	M					M	M		M		M	M		M	M
	Measuring transformer change or ratio change	M	M			M				M		M	M	M	M	
	Control device change	M					MI		M	M			M			M

**Electricity Industry Participation Code 2010**  
**Schedule 10.1**

---

	<b>Additional equipment (eg wiring)</b>	M				M				M			M	M	M	
--	---	---	--	--	--	---	--	--	--	---	--	--	---	---	---	--

**Key:** **M** = mandatory, **MI** = mandatory if the control device is integral with the meter.

Table 3: rows 6 and 8 amended, on 15 May 2014, by clause 14 of the Electricity Industry Participation (Minor Code Amendments) Code Amendment 2014.

Table 3: row 3 amended, on 19 December 2014, by clause 21 of the Electricity Industry Participation Code Amendment (Minor Code Amendments) (No 3) 2014.

Electricity Industry Participation Code 2010  
Schedule 10.1

**Table 4: Fully calibrated certification minimum test requirements**

Event		Design	Measuring transformer	Meter	Primary injection to meter	Prevailing load	Data storage device	Software security and communication equipment	Control device	Wiring check	Component certification check	Review of compensation factors	Raw meter data output	Supply polarity	Register advance	Installation or component configuration
Metering installation	Initial certification	M	M	M	T	M	M	M	M	M	M	M	M	M	M	M
	Recertification	M		M		M	M	M	M	M	M	M	M	M	M	M
	Meter change including internal data storage	M		M		M	M	M		M		M	M	M	M	M
	Metrology change either onsite or remote	M		M			M	M				M	M		M	M
Component change or recertification	External data storage device change	M					M	M		M		M	M		M	M
	Measuring transformer change or ratio change	M	M		T	M				M		M	M	M	M	
	Control device change	M					MI		M	M			M			M
	Additional equipment (eg wiring)	M			T	M				M			M	M	M	
	Initial certification	M	M	M	T	M	M	M	M	M	M	M	M	M	M	M
	Recertification	M		M		M	M	M	M	M	M	M	M	M	M	M

**Key:** M = mandatory, T = mandatory if test method and test equipment permit, **MI** = mandatory if the control device is integral with the meter.

**Table 5: Standards for metering components**

<b>Meter and data storage device standards</b>	<b>Standards</b>
Electricity metering equipment (AC) – Part 1: General requirements, tests and test conditions (classes 0.5, 1 and 2)	EN 50470-1
Electricity metering equipment (AC) – Part 2: Particular requirements – Electromechanical meters for active energy (classes 1 and 2)	EN 50470-2
Electricity metering equipment (AC) – Part 3: Particular requirements – Static meters for active energy (classes 0.5, 1 and 2)	EN 50470-3
Electricity metering equipment (AC) – Particular requirements – Part 11: Electromechanical meters for active energy (classes 0.5, 1 and 2)	IEC 62053-11
Electricity metering equipment (AC) – Particular requirements – Part 21: Static meters for active energy (classes 1 and 2)	IEC 62053-21
Electricity metering equipment (AC) – Particular requirements – Part 22: Static meters for active energy (classes 0.2 S and 0.5 S)	IEC 62053-22
Electricity metering equipment (AC) – Particular requirements – Part 23: Static meters for reactive energy (classes 2 and 3)	IEC 62053-23
Electricity metering equipment (AC) – Particular requirements – Part 61: Power consumption and voltage requirements	IEC 62053-61
Electricity metering equipment (AC) – General requirements, tests and test conditions – Part 11: Metering equipment	IEC 62052-11
Measuring transformer standards	
Instrument transformers – Part 1: Current transformers	IEC 60044-1
Instrument transformers – Part 2: Inductive voltage transformers	IEC 60044-2
Instrument transformers – Part 3: Combined transformers	IEC 60044-3
Instrument transformers – Part 5: Capacitor voltage transformers	IEC 60044-5
Coupling capacitors and capacitor dividers	IEC 60358
Instrument transformers – Part 7: Electronic voltage transformers	IEC 60044-7
Instrument transformers – Part 8: Electronic current transformers	IEC 60044-8
Other standards	
Electricity metering equipment (AC) – Tariff and load control – Part 11: Particular requirements for electronic ripple control receivers	IEC 62054-11
Electricity metering equipment (AC) – Tariff and load control – Part 21: Particular requirements for time switches	IEC 62054-21

Table 5: row 1 amended, on 15 May 2014, by clause 15 of the Electricity Industry Participation (Minor Code Amendments) Code Amendment 2014.

**Table 6: Standards of accuracy and overall uncertainty for active and reactive meter calibration and testing**

Value of Current %	Power Factor	Maximum Overall Uncertainty %	Percentage Error Limits of Meter, Including Uncertainty
<b>Class of meter 2.0 and 2.0S</b>			
5 to 120	1	±0.4	±1.9
10 to 120	0.5 lagging	±0.6	±1.9
10 to 120	0.8 leading	±0.6	±1.9
<b>Class of meter 1.0 and 1.0S</b>			
5 to 120	1	±0.2	±0.9
10 to 120	0.5 lagging	±0.25	±0.9
10 to 120	0.8 leading	±0.25	±0.9
<b>Class of meter 0.5 and 0.5S</b>			
5 to 120	1	±0.1	±0.5
10 to 120	0.5 lagging	±0.12	±0.6
10 to 120	0.8 leading	±0.12	±0.6
<b>Class of meter 0.2S</b>			
5 to 120	1	±0.06	±0.2
10 to 120	0.5 lagging	±0.09	±0.3
10 to 120	0.8 leading	±0.09	±0.3
<b>Class of meter 3.0 reactive</b>			
20 to 120	Zero	±1.0	±3.0
20 to 120	0.8 leading	±1.5	±3.5
20 to 120	0.8 lagging	±1.5	±3.5
<b>Class of meter 2.0 reactive</b>			
20 to 120	Zero	±0.5	±2.0
20 to 120	0.8 leading	±1.0	±2.5
20 to 120	0.8 lagging	±1.0	±2.5



**Table 7: Voltage, current, and phase displacement parameters for polyphase meters**

Polyphase meters	Class of meter			
	0.2 and 0.5	1.0	2.0	3.0
Each of the voltages between line and neutral or between any 2 <b>lines</b> will not differ from the average corresponding voltage by more than:	±0.1%	±1.0%	±1.0%	±1.0%
Each of the currents in the conductors will not differ from the average current by more than:	±1.0%	±2.0%	±2.0%	±2.0%
The phase displacements of each of these currents from the corresponding line-to-neutral voltage, irrespective of the power factor, will not differ from each other by more than:	2°	2°	2°	2°

Schedule 10.1, Table 7: amended, on 1 February 2016, by clause 30 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

**Table 8: Required minimum sample size for category 1 metering installation inspections required under clause 45(2)(c) of Schedule 10.7**

Number of metering installations identified	Minimum sample size
1	1
2-8	2
9-15	3
16-25	5
26-50	8
51-90	13
91-150	20
151-280	32
281-500	50
501-1200	80
1201-3200	125
3201-10,000	200
10,001-35,000	315
35,001-150,000	500
150,001+	800

**Schedule 10.2**  
*[Revoked]*

cl 10.17

Schedule 10.2: revoked, on 1 June 2017, by clause 10 of the Electricity Industry Participation Code Amendment (Requirements and Processes for Audits) 2016.

## Schedule 10.3

cl 10.40

### ATHs – approval, expiry, cancellation, and renewal of approval

#### 1 Applications for approval and renewal of approval

- (1) A person wishing to be approved as an **ATH**, or an **ATH** wishing to renew its approval, must apply, in the **prescribed form**, to the **Authority** at least 2 months before the intended effective date of the approval or renewal.
- (2) An applicant must—
  - (a) include in its application—
    - (i) the final **audit** report obtained under Part 16A, together with its responses to the report; and
    - (ii) a copy of any quality management certificates it holds; and
    - (iii) a copy of its most recent quality management audit report; and
    - (iv) the class of **ATH** for which it is seeking approval; and
    - (v) the functions under clauses 3(2) and 4(2) for which it is seeking approval; and
    - (vi) the **calibration** expiry date of each of its **working standards** and **reference standards**; and
  - (b) provide promptly any other information or documentation the **Authority** may reasonably request.
- (3) The **Authority** must, within 2 months of receiving an application, advise the applicant of—
  - (a) the approval of the application, if the applicant satisfies the **Authority** that it has met the requirements set out in clause 10.40; or
  - (b) the declination of the application, providing reasons, if the **Authority** considers that—
    - (i) the information supplied by the applicant is incomplete or unsatisfactory; or
    - (ii) the applicant otherwise fails to demonstrate that it would be, and would remain for the period and functions for which the application is made, compliant with the requirements set out in clause 10.40.
- (4) If an application is approved, the **Authority** must issue a certificate of approval specifying the—
  - (a) period of the term of approval, which must not exceed 12 months from the date of approval; and
  - (b) functions that the applicant has been approved to carry out; and
  - (c) *[Revoked]*
  - (d) date of approval.

Clause 1(2)(a)(i): amended, on 1 June 2017, by clause 11(1) of the Electricity Industry Participation Code Amendment (Requirements and Processes for Audits) 2016.

Clause 1(4)(a): amended, on 5 October 2017, by clause 181 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 1(4)(c): revoked, on 1 June 2017, by clause 11(2) of the Electricity Industry Participation Code Amendment (Requirements and Processes for Audits) 2016.

**2** [Revoked]

Clause 2: revoked, on 1 June 2017, by clause 12 of the Electricity Industry Participation Code Amendment (Requirements and Processes for Audits) 2016.

**3 Approval of class A ATHs**

- (1) An applicant applying for approval, or renewal of approval, as a **class A ATH** must, as part of its application, confirm that—
  - (a) it holds and complies with AS/NZS ISO 17025 accreditation, for at least the requested term of the approval; and
  - (b) the scope of its AS/NZS ISO 17025 accreditation covers the activities that it undertakes, or proposes to undertake; and
  - (c) it complies, and will be likely to continue to comply during the requested term of the approval, with any requirements of its ISO accreditation; and
  - (d) if it proposes to carry out field work—
    - (i) it is certified to the relevant AS/NZS ISO 9001:2008 or AS/NZS ISO 9001:2016 and will remain certified during the requested term of the approval; and
    - (ii) the scope of its AS/NZS ISO 17025 accreditation has been extended to cover the carrying out of the field work.
- (2) The **Authority** may approve an applicant to be, or renew an applicant's approval as, a **class A ATH** to carry out 1 or more of the following functions:
  - (a) **calibration** of—
    - (i) **working standards**;
    - (ii) **metering components** (other than a **calibration** referred to in paragraph (c));
    - (iii) **metering installations**;
  - (b) issuing **calibration reports**;
  - (c) **calibration** of **metering components** onsite;
  - (d) installation and modification of **metering installations**;
  - (e) installation and modification of **metering components**;
  - (f) **certification** of all categories of **metering installations** under this Code, and issuing of **certification reports**;
  - (g) testing of **metering installations** under clause 10.44 and production of statements of situation under clause 10.46;
  - (h) inspection of **metering installations**.
- (3) A **class A ATH** may only carry out 1 or more of the functions listed in subclause (2), subject to—
  - (a) the current scope of its approval under subclause (2); and
  - (b) any limitations that may be specified in the **class A ATH's** AS/NZS ISO 17025 accreditation or the relevant AS/NZS ISO 9001:2008 or AS/NZS ISO 9001:2016 certification.
- (4) The **Authority** may decline an application for approval as a **class A ATH** even if the applicant—
  - (a) has obtained the necessary ISO accreditation or certification; or

(b) has obtained or satisfied any other pre-requisite to approval.

Clause 3(1)(b): amended, on 29 August 2013, by clause 26 of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011, Amendment 2013 (No 2).

Clause 3(1)(d)(i) and 3(3)(b) amended, on 1 June 2017, by clause 13 of the Electricity Industry Participation Code Amendment (Requirements and Processes for Audits) 2016.

#### 4 Approval of class B ATHs

- (1) An applicant applying for approval, or renewal of approval, as a **class B ATH** must, as part of its application to the **Authority**, confirm that—
  - (a) it holds and complies with AS/NZS ISO 9001:2008 or AS/NZS ISO 9001:2016 certification for at least the requested term of the approval; and
  - (b) the scope of its AS/NZS ISO 9001:2008 or AS/NZS ISO 9001:2016 certification covers the activities that it undertakes, or proposes to undertake; and
  - (c) it will develop and at all times during the requested term of the approval maintain a conflict of interest policy in compliance with AS/NZS ISO 17025.
- (2) The **Authority** may approve an applicant to be, or renew an applicant's approval as, a **class B ATH** to carry out 1 or more of the following functions:
  - (a) **calibration** of class 0.5 **meters**, class 1 **meters** and class 2 **meters**, and class 0.5 current transformers and class 1.0 current transformers, provided that the **calibrations** are carried out under their approved quality certification and in accordance with this Part, and included within the **ATH audit** for approval:
  - (b) installation and modification of **metering installations**:
  - (c) installation and modification of **metering components**:
  - (d) **calibration** of **metering components** onsite:
  - (e) **certification**, using the **selected component certification** method, of—
    - (i) **category 1 metering installations**:
    - (ii) **category 2 metering installations**:
    - (iii) category 3 **metering installations** with a primary voltage of less than 1kV:
  - (f) **certification**, using the **fully calibrated certification** method, of—
    - (i) **category 1 metering installations**:
    - (ii) **category 2 metering installations**:
    - (iii) category 3 **metering installations** with a primary voltage of less than 1kV:
  - (g) **certification**, using the **comparative recertification** method, of **category 2 metering installations**:
  - (h) issuing of **certification reports** in respect of **certifications** of **metering installations** under paragraphs (e) to (g):
  - (i) inspection of—
    - (i) **category 1 metering installations**:
    - (ii) **category 2 metering installations**:
    - (iii) category 3 **metering installations** with a primary voltage of less than 1kV.
- (3) A **class B ATH** may only carry out 1 or more of the functions listed in subclause (2), subject to—
  - (a) the current scope of its approval under subclause (2); and
  - (b) any limitations that may be specified in the relevant AS/NZS ISO 9001:2008 or AS/NZS ISO 9001:2016 certification.

- (4) The **Authority** may decline an application for approval as a **class B ATH** even if the applicant—

- (a) has obtained the necessary ISO certification; or
- (b) has obtained or satisfied any other pre-requisite to approval.

Clause 4(1)(a) and (b) amended, on 1 June 2017, by clause 14 of the Electricity Industry Participation Code Amendment (Requirements and Processes for Audits) 2016.

Clause 4(1)(b): amended, on 29 August 2013, by clause 27 of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011, Amendment 2013 (No 2).

Clause 4(3)(b) amended, on 1 June 2017, by clause 14 of the Electricity Industry Participation Code Amendment (Requirements and Processes for Audits) 2016.

#### **4A Incorporation of AS/NZS ISO 9001:2008 and AS/NZS ISO 9001:2016 by reference**

- (1) The New Zealand Standards AS/NZS ISO 9001:2008 and AS/NZS ISO 9001:2016 are incorporated by reference in this Code in accordance with section 32 of the **Act**.
- (2) Subclause (1) is subject to Schedule 1 of the **Act**, which includes a requirement that the **Authority** must give notice in the *Gazette* before an amended AS/NZS ISO 9001:2008 or AS/NZS ISO 9001:2016 becomes incorporated by reference in this Code.
- (3) Clause 10.10 does not apply in relation to the incorporation by reference of AS/NZS ISO 9001:2008 or AS/NZS ISO 9001:2016.

Clause 4A inserted, on 1 June 2017, by clause 15 of the Electricity Industry Participation Code Amendment (Requirements and Processes for Audits) 2016.

#### **5 Expiry and cancellation of approval**

- (1) If the **Authority** believes that an **ATH** is or was in breach of this Part the **Authority** may cancel the approval of the **ATH** with immediate effect by advising the **ATH**.
- (2) An **ATH** must not, at any time after the expiry or cancellation of its approval, display or use its certificate of approval.

#### **6 Changes that affect approval**

- (1) If an **ATH** intends to make a material change to any of its facilities, processes, or procedures, or the scope of the **ATH's** ISO accreditation is reduced during the term of its approval, the **ATH** must, at least 5 **business days** before the change is to take place or reduction in scope is effected,—
  - (a) advise the **Authority** of all relevant details of the change or reduction in scope; and
  - (b) in the case of a material change, submit to the **Authority** an **audit** report confirming that, after the change has come into effect, the **ATH** will continue to meet the requirements under clause 10.40(2)(a).
- (2) An **ATH's** approval is automatically cancelled from the date of the change or reduction in scope under subclause (1), if the **ATH** fails to advise the **Authority** under subclause (1)(a).
- (3) The **Authority** may, if it is advised by an **ATH** under subclause (1), either—
  - (a) cancel an **ATH's** approval from the date that the **Authority** advises the **ATH** that the **Authority** is not satisfied that the **ATH** will continue to meet the requirements under clause 10.40(2)(a) after the change or reduction in scope has come into effect; or

- (b) revise the scope of the **ATH's** approval.

## **7 Notification of cancellation, expiry, or revision of scope of ATH approval**

- (1) The **Authority** must give written notice to all **metering equipment providers** if—
  - (a) an **ATH's** approval expires and the **Authority** does not renew it;
  - (b) the **Authority** cancels an **ATH's** approval under clause 5;
  - (c) an **ATH's** approval is cancelled under clause 6(2) or 6(3)(a);
  - (d) the scope of an **ATH's** approval has been revised under clause 6(3)(b).
- (2) The **Authority** must include with the notice under subclause (1) the date on which the approval expired or was cancelled, or the scope of the approval was revised.
- (3) A **metering equipment provider** given notice under subclause (1) must treat all **metering installations certified** by the **ATH** during the period during which it was not validly approved, or was performing activities outside its scope of approval, as being defective from the date of which the **Authority** gave notice under subclause (2) and follow the procedures set out in clauses 10.43 to 10.48.
- (4) Despite subclause (3), the **Authority** may give a **metering equipment provider** written notice that the **metering equipment provider** must treat a **metering installation certified** by the **ATH** as being defective and follow the procedures set out in clauses 10.43 to 10.48.

Clause 7: amended, on 5 October 2017, by clause 182 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

## **8 Register of ATHs**

- (1) The **Authority** must, keep, maintain, and **publish** a register of approved **ATHs**.
- (2) The **Authority** must remove an **ATH's** details from the register if the **ATH's** approval—
  - (a) expires and the **Authority** does not renew it; or
  - (b) is cancelled.



## Schedule 10.4

### ATH ongoing functions and obligations

cl 10.42

#### 1 Accommodation and environment

An **ATH** must, for each **approved test house** that it operates,—

- (a) maintain a list of personnel who are authorised to access and use its laboratory and storage facilities; and
- (b) restrict access to its laboratory and storage facilities to—
  - (i) the personnel specified under paragraph (a); and
  - (ii) the **Authority**; and
  - (iii) an **auditor** conducting an **audit**; and
  - (iv) any other person who is, at all times, directly supervised by a member of personnel specified under paragraph (a); and
- (c) restrict access to its **metering records** to—
  - (i) the relevant **metering equipment provider**;
  - (ii) the **Authority**;
  - (iii) an **auditor** conducting an **audit**;
  - (iv) the relevant **metering component** owner; and
- (d) ensure that the environment in which its activities are undertaken does not, or could not reasonably be expected to, invalidate test results or adversely affect the required accuracy of measurement; and
- (e) monitor and record the environmental conditions within its **approved test house's** laboratory and storage facilities; and
- (f) comply with the specific requirements of the applicable standard listed in Table 5 of Schedule 10.1 for the **calibrations** or tests being carried out.

Clause 1(c)(iv): amended, on 29 August 2013, by clause 28 of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011, Amendment 2013 (No 2).

#### 2 Equipment

(1) An **ATH** must, at all times, ensure that—

- (a) it has access to all items of equipment required for the performance of the **calibrations** and tests it is approved to undertake under this Part; and
- (b) each item of equipment it uses is maintained in accordance with the manufacturer's recommendations and this Code (but if there is any inconsistency or contradiction between the manufacturer's recommendations and this Code, this Code takes precedence); and
- (c) it maintains records about each item of its equipment, including—
  - (i) details of—
    - (A) maintenance history; and
    - (B) the **ATH's** maintenance programme; and
  - (ii) **calibration reports**, including before and after **adjustment** results; and
  - (iii) in-service checks; and
  - (iv) a history of any damage, malfunction, modification, or repair.

- (2) A **class B ATH** must have and maintain procedures for the purchase of test equipment and associated consumables.

### 3 Reference standards and working standards

- (1) An **ATH** must not use a **reference standard** or **working standard** for any activity regulated under this Part unless—
- (a) in the case of—
    - (i) a **reference standard**, the **reference standard** has been **calibrated** by an **approved calibration laboratory**; or
    - (ii) a **working standard**, the **working standard** has been **calibrated** by an **approved calibration laboratory** or a **class A ATH**; and
  - (b) the current **calibration report** for the **reference standard** or **working standard** confirms that it—
    - (i) performs within the manufacturer's accuracy specifications; and
    - (ii) has been **calibrated** under subclause (2) at an interval not exceeding the **calibration** intervals set out in the following table.

**Table 1: Calibration intervals**

Standard		Initial calibration interval (months beginning from the date of the first calibration)	Maximum calibration interval (months beginning from the date of the current calibration report)
<b>Reference standard or working standard (other than a working standard used for on-site calibration)</b>	Measuring transformers	36	60
	Comparator bridges	36	60
	Meters	12	24
	Power factor, voltage and current meters	12	24
<b>Working standard used for on-site calibration</b>	All	2	12

- (2) An **ATH** must ensure that a **reference standard** or **working standard** is **calibrated**—
- (a) for the first time, within the applicable initial **calibration** interval set out in Table 1 of subclause (1); and
  - (b) for each subsequent **calibration**, within the applicable maximum **calibration** interval set out in Table 1 of subclause (1).

- (3) A **class A ATH** must ensure that—
- (a) in all cases of **calibration** of its **reference standards**, the **uncertainties** given in the **reference standard calibration report** are sufficiently small so that the overall **uncertainty** in the measurements used to test a **metering installation** does not exceed one third of the maximum permitted error set out in Table 1 of Schedule 10.1 for the category of **metering installation** that the **reference standard** will be used to **calibrate**; and
  - (b) it does not use a **working standard** on a system operating at a voltage of 33kV or above between active conductors, unless the **working standard** has been **calibrated** by an **approved calibration laboratory**; and
  - (c) it does not use a **reference standard**, other than a standard **measuring transformer**, unless it is maintained at the appropriate reference conditions set out in the **reference standard's** current **calibration report**.
- (4) If appropriate reference conditions under subclause (3)(c) cannot be achieved, the **class A ATH** must calculate and apply adjustments in accordance with the processes and procedures under subclause (5) so that the **reference standard** achieves the errors and uncertainties set out in the **reference standard's** current **calibration report**.
- (5) An **ATH** must develop and maintain processes and procedures for calculating and applying adjustments to a **reference standard's** errors and uncertainties to compensate for deviations from the reference conditions contained in the **reference standard's** current **calibration report**.
- (6) An **ATH** must retain a copy of the current **calibration report** for each of its **reference standards** and **working standards**.

#### **4 Metering component testing systems**

An **ATH** may use a complete **calibrated metering component** testing system (also known as a test bench) as an alternative to a separately **calibrated working standard** only if—

- (a) the **ATH** **calibrates** the complete **calibrated metering component** testing system under clause 3 as if it was a **working standard**; and
- (b) before completing the **calibration report**, the **ATH** carries out a testing system accuracy test, using approved **reference standards**.

#### **5 Calibration errors**

- (1) For the purposes of this clause, a **reference standard** or **working standard** has a **calibration** error if it is performing outside of the manufacturer's accuracy specifications.
- (2) An **ATH** must not use a **reference standard** or **working standard** for **calibration**, if it believes, or should reasonably be expected in the circumstances to believe, that the **reference standard** or **working standard** has a **calibration** error.
- (3) An **ATH** must, as soon as reasonably practicable, but no more than 3 months after becoming aware of a **calibration** error—
  - (a) investigate the error; and

- (b) ensure the cause of the error is recorded in a **calibration report**; and
  - (c) if the investigation indicates that the **reference standard** or **working standard** performs outside the manufacturer's accuracy specifications, advise each **ATH** that has used any equipment that was **calibrated** using the **reference standard** or **working standard** since the previous **calibration**, of the error.
- (4) An **ATH** must, if a **reference standard** or a **working standard** has a **calibration** error,—
- (a) treat each **metering installation** that it has **calibrated** using the **reference standard** or **working standard** as outside the applicable accuracy tolerances set out in Table 1 of Schedule 10.1; and
  - (b) comply with clause 10.43.
- (5) For the purposes of this clause, a **working standard** includes a complete **calibrated metering component** testing system referred to in clause 4.

## 6 Measurement traceability

An **ATH** must document, maintain, and comply with, a system that ensures, whenever it undertakes a **calibration** test or measurement,—

- (a) it keeps sufficient records to enable the **ATH** to replicate the test or measurement in every respect should the need arise; and
- (b) the results of the measurements are **traceable**.

### *Requirements for calibration of metering components*

## 7 Calibration methods

- (1) An **ATH** must, before it **certifies** a **metering installation** or **metering component**, ensure that 1 of the following persons has **calibrated** the **metering components** under this Part:
- (a) an **approved calibration laboratory**; or
  - (b) an **ATH** with the appropriate approval under Schedule 10.3.
- (2) An **ATH** must, before it **certifies** a **metering component**, ensure that the **metering component** is **calibrated** or **adjusted** under—
- (a) the appropriate physical and electrical reference conditions detailed in the standard listed in Table 5 of Schedule 10.1; or
  - (b) conditions which permit the **ATH** to calculate the results and their **uncertainty** at the reference conditions detailed in the standard listed in Table 5 of Schedule 10.1.
- (3) A **class B ATH** must, when **calibrating** a **metering component**,—
- (a) follow all relevant requirements of NZ/AS ISO 17025 for **calibration**; and
  - (b) only use the relevant methodologies that have been **audited** in the **class B ATH's** most recent **audit** for approval.
- (4) If an **ATH** **calibrates** a **metering component**, it must ensure that the individual test points that it uses are—
- (a) no less than the minimum set out in the standards listed in Table 5 of Schedule 10.1; or

- (b) sufficient and appropriate in the circumstances to ensure that the **calibration** allows calculation of the **metering installation** error as set out in clause 22 of Schedule 10.7.
- (5) An **ATH** must, when **calibrating** a **metering component**,—
  - (a) if necessary, **adjust** and document the **error compensation**; and
  - (b) ensure that any **adjustment** carried out under paragraph (a) is appropriate to achieve an error as close as practicable to zero; and
  - (c) ensure that the **uncertainty** of measurement during the **calibration** of the **metering component** does not exceed one third of the maximum permitted error in the relevant standard listed in Table 5 of Schedule 10.1; and
  - (d) if the **metering component** is intended for a **metering installation** which is to be **certified** using the **selected component certification** method, ensure that the **ATH** records the errors of a current transformer from 5% to 120% of rated primary current.
- (6) An **ATH** must ensure that—
  - (a) it has documented instructions on the use and operation of all relevant equipment it uses for **calibration**; and
  - (b) it has documented **calibration** procedures that it must make available to, and ensure are followed by, its staff carrying out the **calibration**; and
  - (c) its **calibration** procedures are aligned with the standards listed in Table 5 of Schedule 10.1.
- (7) An **ATH**—
  - (a) may select a test point other than those specified in the relevant standard listed in Table 5 of Schedule 10.1, or at a lower burden than specified in the standard; but
  - (b) must, if it does this, document its reasons for the selection of these test points in the **calibration report**.

## 8 Compensation factors

An **ATH** must, if it is approved to **certify metering installations**, have a documented process for determining **compensation factors**.

## 9 Seals

An **ATH** must have a documented system for applying seals to a **metering installation**, that—

- (a) meets the requirements of clause 47 of Schedule 10.7; and
- (b) is appropriate in the circumstances to ensure—
  - (i) the **ATH's** ability to monitor the **metering installation's** continued integrity; and
  - (ii) the relevant **metering equipment provider** is alerted as soon as practicable to any unauthorised access to the **metering installation**.

## 10 Services access interface

An **ATH** must, when preparing a **metering installation certification report**,

determine, and record in the **certification report**, the **services access interface**.

## **11 Certification and calibration reports**

- (1) An **ATH** must, for each **metering installation** that it **certifies**, produce a **certification report** in accordance with Schedule 10.7.
- (2) An **ATH** must, for each **metering component**—
  - (a) that it **calibrates**, produce a **calibration report** in accordance with Schedule 10.8; and
  - (b) that it **certifies**, produce a **certification report** in accordance with Schedule 10.8.

## **12 ATH record keeping and documentation**

- (1) An **ATH** must ensure it documents and maintains a record system for all records, certificates, and reports for any activity regulated under this Part.
- (2) An **ATH** must ensure that—
  - (a) all its records, certificates, and reports are stored securely; and
  - (b) each of its test records for a **metering installation** is identified by a unique identifier; and
  - (c) all of its records, certificates, and reports are sufficiently detailed to enable verification of all aspects of all tests it carries out, including the following:
    - (i) test conditions; and
    - (ii) specific test equipment used; and
    - (iii) personnel carrying out the tests.

## **13 Retention of ATH records**

An **ATH** must, for each activity regulated under this Part in relation to a **metering installation** and **metering component** that it **certifies** and a **metering component** that it **calibrates**, retain, for at least 48 months after the date of **decommissioning** the **metering installation** or **removal** of a **metering component**,—

- (a) all of its records, certificates, and reports; and
- (b) all **certification reports** produced by the **ATH**.

## **14 Making available of ATH records**

An **ATH** must, within 5 **business days** of creating a record, certificate, or report for a **metering installation** that it **certifies**,—

- (a) send, in electronic form or such other form as may be agreed between the parties, a copy of the record, certificate, or report to the **metering equipment provider** responsible for the **metering installation**; and
- (b) ensure that the **metering equipment provider** receives the record, certificate, or report.

## **15 ATH organisation and management**

- (1) An **ATH** must ensure that—
  - (a) it has managerial staff who, unless otherwise permitted in the relevant approval,

- all have the authority and resources needed to discharge their duties; and
- (b) the responsibilities, authority, and functional relationships of all its personnel are fully and accurately specified and recorded in the **ATH's** records.
- (2) An **ATH** must appoint—
- (a) a technical manager (however named) with overall responsibility for technical operations, who must have appropriate engineering qualifications and experience in the operation of an **approved test house**; and
  - (b) a quality manager (however named), with responsibility for the quality management certification and the implementation of the quality management system.
- (3) An **ATH** must ensure that all staff who perform or supervise work or activities regulated under this Part are technically competent, experienced, qualified, and trained for the functions they perform.

#### **16 Quality management system**

An **ATH** must establish, document, implement, maintain, and comply with a quality management system which records its processes and procedures to ensure compliance with this Part.

#### **17 Field work**

A **class A ATH** must, if it arranges for another person to carry out field work, ensure that person is certified to the relevant AS/NZS ISO 9001:2008 or AS/NZS ISO 9001:2016 at all times while the person carries out the work.

Clause 17 amended, on 1 June 2017, by clause 16 of the Electricity Industry Participation Code Amendment (Requirements and Processes for Audits) 2016.

**Schedule 10.5**

**cl 10.20**

*[Revoked]*

Schedule 10.5: revoked, on 1 June 2017, by clause 17 of the Electricity Industry Participation Code Amendment (Requirements and Processes for Audits) 2016.



## Schedule 10.6

cl 10.20

### Metering equipment provider ongoing obligations and functions

- 1 Metering equipment provider must provide access to raw meter data**
- (1) A **metering equipment provider** must, within 10 **business days** of receiving a request from a **trader** with whom it has an arrangement to access **raw meter data** from a **metering installation** for which the **metering equipment provider** is responsible, give remote or onsite access at the **services access interface** to the **trader** to collect, obtain, and use **raw meter data** from the **metering installation**.
- (2) A **metering equipment provider** may, if it receives a request from a person with whom it has an arrangement, other than a **trader** under subclause (1), to access **raw meter data** from a **metering installation** for which the **metering equipment provider** is responsible, give remote or onsite access at the **services access interface** to the person to collect, obtain, and use **raw meter data** from the **metering installation**.
- (3) A **metering equipment provider** must only give access to a **trader** under subclause (1), or a person under subclause (2), if the **trader** or person has entered into a contract to collect, obtain, and use the **raw meter data**, with the **consumer** whose **electricity** is measured or estimated, or whose load is controlled at the **metering installation**.
- (4) A **metering equipment provider** must, within 10 **business days** of receiving a request from 1 of the following parties, give the party access to **raw meter data** from a **metering installation** for which it is responsible:
  - (a) a relevant **reconciliation participant** with whom it has an arrangement, other than a **trader**;
  - (b) the **Authority**;
  - (c) an **ATH**;
  - (d) an **auditor**.
- (5) A party listed in subclause (4) may only request access to **raw meter data** for the purposes of exercising the party's rights and performing the party's obligations under this Code or any relevant **regulations** in relation to 1 or more of the following:
  - (a) the party's **audit** functions;
  - (b) the party's administration functions;
  - (c) the party's testing functions;
  - (d) the provision of **submission information** to the **reconciliation manager**.
- (6) The **metering equipment provider** must provide a **trader** under subclause (1) or a party under subclause (4) with—
  - (a) the **raw meter data**; or
  - (b) any necessary facilities, codes, keys, or other means to enable the **trader** or party to access the **raw meter data** by the most practicable means.
- (7) The **metering equipment provider** must, when complying with subclause (6), or when providing access to a person under subclause (2), use appropriate procedures to ensure that—
  - (a) the **raw meter data** is received only by—
    - (i) the **trader**, person, or party; or

- (ii) a contractor to a **trader**, person, or party; and
- (b) the security of the **raw meter data** and the **metering installation** is maintained; and
- (c) access to **raw meter data** under subclauses (1) to (6) is limited to only the specific **raw meter data**—
  - (i) authorised by a contract described in subclause (3), in the case of a **trader** under subclause (1) or a person under subclause (2); or
  - (ii) required for the purposes of exercising the party's rights and performing the party's obligations under this Code, any relevant **regulations**, or the **Act** in relation to the party's **audit**, administration, and testing functions, in the case of a party referred to in subclause (4).
- (8) Nothing in this Part affects proprietary interests in **metering data**.  
Clause 1(5) and (7)(c)(ii): amended, on 5 October 2017, by clause 183 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

## 2 Restrictions on use of raw meter data

- (1) A **metering equipment provider** must not give a **trader** under clause 1(1), a person under clause 1(2), or a party under clause 1(3), access to **raw meter data** from a **metering installation** for which it is responsible, if to do so would, or would reasonably be expected to,—
  - (a) breach any regulatory or legal requirement; or
  - (b) prejudice the maintenance and monitoring of this Code, including the prevention, investigation, and detection of Code breaches and the right to a fair hearing before the **Authority** or the **Rulings Panel**; or
  - (c) result in the **metering equipment provider** breaching an obligation of confidentiality; or
  - (d) interfere with the privacy of a natural person; or
  - (e) create an improper gain or improper advantage for any **participant** or person; or
  - (f) commercially disadvantage the **metering equipment provider** or any other **participant** or person, in a material manner; or
  - (g) prejudice the future supply of **raw meter data** that is required by a **market operation service provider** to perform an obligation under this Code.
- (2) A **metering equipment provider** must not limit or restrict a person's or party's right to access information from a **metering installation** for which the **metering equipment provider** is responsible, if the right of access is provided for in this Part.

## 3 Metering equipment provider must provide access to metering installation

- (1) A **metering equipment provider** must, within 10 **business days** of receiving a request from 1 of the following parties, arrange physical access to each **metering component** in a **metering installation** for which it is responsible:
  - (a) a relevant **reconciliation participant** with whom it has an arrangement, other than a **trader**;
  - (b) the **Authority**;
  - (c) an **ATH**;
  - (d) an **auditor**;

- (e) a **gaining metering equipment provider**.
- (2) A party listed in subclause (1) may only request physical access to a **metering component** in the **metering installation** for the purposes of exercising the party's rights and performing the party's obligations under this Code or any relevant **regulations** in relation to 1 or more of the following:
  - (a) the party's **audit** functions;
  - (b) the party's administration functions;
  - (c) the party's testing functions;
  - (d) the provision of **metering components**.
- (3) The **metering equipment provider** must arrange for a party under subclause (1) to be provided with any necessary facilities, codes, keys, or other means to enable the party to obtain physical access to all **metering components** in the **metering installation** by the most practicable means.
- (4) In complying with subclause (3), the **metering equipment provider** must use appropriate procedures to ensure that—
  - (a) the security of the **metering installation** is maintained; and
  - (b) physical access to the **metering installation** under subclause (1) is limited to only the physical access required for the purposes of exercising the party's rights and performing the party's obligations under this Code or any relevant **regulations** in relation to the party's **audit**, administration, and testing functions.
- (5) If a party referred to in subclause (1) requires urgent physical access to a **metering installation**, it must advise the relevant **metering equipment provider**, giving all relevant particulars of the physical access required and the reason for the urgency, and the **metering equipment provider** must use its best endeavours to arrange physical access in accordance with the requested urgency.

Clause 3(2) and (4)(b): amended, on 5 October 2017, by clause 184 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

#### **4 Metering equipment provider record keeping and documentation**

- (1) A **metering equipment provider** must—
  - (a) for each **metering installation** for which it is responsible, keep accurate and complete records as specified in Table 1 of Schedule 11.4; and
  - (b) for each **metering installation** for which it is responsible other than an **interim certified metering installation**, keep accurate and complete records of—
    - (i) the **certification** expiry date of each **metering component** in the **metering installation**; and
    - (ii) all equipment used in relation to the **metering installation**, including serial numbers and details of the equipment's manufacturer; and
    - (iii) the manufacturer's, or if different the most recent, test certificate for each **metering component** in the **metering installation**; and
    - (iv) the **metering installation** category for the **metering installation**; and
    - (v) all **certification reports** and **calibration reports** showing dates tested, tests carried out, and test results for all **metering components** in the **metering installation**; and
    - (vi) the contractor who installed each **metering component** in the **metering**

- installation; and**
- (vii) the **certification sticker**, or equivalent details, for each **metering component** that is **certified** under Schedule 10.8 in the **metering installation; and**
  - (viii) seal identification information under clause 47 of Schedule 10.7 relating to the **metering installation; and**
  - (ix) any applicable **compensation factors; and**
  - (x) the owner of each **metering component** within the **metering installation; and**
  - (xi) any applications installed within each **metering component** within the **metering installation; and**
  - (xii) the signed inspection report under clause 44 of Schedule 10.7, confirming that the **metering installation** continues to comply with the requirements of this Part.
- (2) A **metering equipment provider** must, within 10 **business days** of receiving a request from a **participant** for a signed inspection report prepared under clause 44 of Schedule 10.7, make a copy of the report available to the **participant**.
- (3) A **metering equipment provider** must retain **metering records** relating to—
- (a) a **metering component** in a **metering installation** for which it is or was responsible, for at least 48 months after the **metering component** is removed from the **metering installation**, even if—
    - (i) the **metering installation** is subsequently **decommissioned; or**
    - (ii) the **metering equipment provider** ceases to be responsible for the **metering installation; and**
  - (b) a **metering installation** for which it is responsible, for at least 48 months after the date on which—
    - (i) the **metering installation** is **decommissioned; or**
    - (ii) the **metering equipment provider** ceases to be responsible for the **metering installation.**

Clause 4(3): substituted, on 1 February 2016, by clause 31 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

## **5 Metering equipment provider to provide access to metering records**

- (1) A **gaining metering equipment provider** may request that a **losing metering equipment provider** provide it with access to **metering records** required for the **gaining metering equipment provider** to exercise its rights and perform its obligations under this Code or any relevant **regulations** in relation to its respective **auditing, administration, and testing functions.**
- (2) The **losing metering equipment provider** must, within 10 **business days** of receiving a request under subclause (1), provide the **gaining metering equipment provider** with—
- (a) the **metering records; or**
  - (b) any necessary facilities, codes, keys, or other means to enable the **gaining metering equipment provider** to obtain access to the **metering records** by the most practicable means.
- (3) In complying with subclause (2), the **losing metering equipment provider** must use

appropriate procedures to ensure that—

- (a) the **metering records** are received only by the **gaining metering equipment provider** or its contractor; and
- (b) the security of the **metering records** is maintained; and
- (c) it only provides access to the specific **metering records** required for the purposes of the **gaining metering equipment provider** exercising its rights and performing its obligations under this Code or any relevant **regulations** in relation to its **auditing**, administration, and testing functions.

Clause 5(1) and (3)(c): amended, on 5 October 2017, by clause 185 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

## **6 Provision of metering records when ATH recertifying metering installation**

- (1) This clause applies if—
  - (a) a **metering equipment provider** contracts with an **ATH** to **recertify** a **metering installation** for which the **metering equipment provider** is responsible; and
  - (b) the **ATH** did not perform the previous **certification** of the **metering installation**.
- (2) If this clause applies, the **metering equipment provider** must, no later than 10 **business days** after the effective date of the contract, provide the **ATH** with a copy of all relevant **metering records**.

## **7 Metering equipment provider must use participant identifier**

- (1) A **metering equipment provider** must—
  - (a) ensure that it has a unique **participant identifier** for its activities as **metering equipment provider** under this Code; and
  - (b) use its **participant identifier**, if required under this Code, to correctly identify its information.
- (2) A **metering equipment provider** must apply to the **Authority** in the **prescribed form** for a **participant identifier** at least 5 **business days** before the **metering equipment provider** requires the **participant identifier**.
- (3) The **Authority** may change a **metering equipment provider's participant identifier**.
- (4) If the **Authority** changes a **metering equipment provider's participant identifier**—
  - (a) it must advise the **metering equipment provider** of the date on which the change takes effect at least 3 months before the date; and
  - (b) the new **participant identifier** becomes effective from the date advised under paragraph (a).

## **8 Electronic interrogation of metering installation**

- (1) This clause applies when **raw meter data** can only be obtained from a **metering equipment provider's back office**.
- (2) A **metering equipment provider** must—
  - (a) ensure that the **interrogation cycle** for each **metering installation** that it electronically **interrogates** does not exceed the maximum **interrogation cycle** in the **registry**; and
  - (b) **interrogate** a **metering installation** for which it is responsible at least once in each maximum **interrogation cycle** in the **registry**; and

- 
- (c) when electronically **interrogating a metering installation**, ensure that the **interrogation** and processing system electronically monitors and corrects its internal clocks against a time source with a verifiable standard, at a frequency sufficient, and no longer than 1 week, to ensure the internal clock is accurate, when carrying out an **interrogation**, to within  $\pm 5$  seconds of—
- (i) **New Zealand standard time**; or
  - (ii) **New Zealand daylight time**.
- (3) A **metering equipment provider** must, for each **metering installation** for which it is responsible, record in the **interrogation** and processing system logs, the time, the date, and the extent of any change in the internal clock setting in the **metering installation**.
- (4) A **metering equipment provider** must ensure that a **data storage device** in a **metering installation** for which it is responsible for **interrogating** does not exceed the maximum time error set out in Table 1 of subclause (5).
- (5) A **metering equipment provider** must, when **interrogating a metering installation**,—
- (a) compare the time on the internal clock of the **data storage device** with the time on the **interrogation** and processing system clock; and
  - (b) calculate the time error for the **data storage device**; and
  - (c) if the time error calculated under paragraph (b) is equal to or less than the applicable time error set out in Table 1, correct the clock of the **data storage device**; and
  - (d) if the time error calculated under paragraph (b) is greater than the applicable time error set out in Table 1,—
    - (i) correct the clock of the **data storage device**; and
    - (ii) compare the time of the clock with the time of the **interrogation** and processing system clock; and
    - (iii) advise the affected **reconciliation participant** for the **point of connection**, within 5 **business days** of correcting the clock, of any affected **raw meter data**; and
    - (iv) comply with the requirements of clause 10.43; and
  - (e) download the **event log**; and
  - (f) check the **event log** for evidence of malfunctioning or tampering and if this is detected, carry out the appropriate requirements of this Part.

**Table 1: Maximum permitted time errors**

<b>Metering installation category</b>	<b>Half-hour metering installations (seconds)</b>	<b>Non half-hour metering installations (seconds)</b>
1	$\pm 30$	$\pm 60$
2	$\pm 10$	$\pm 60$
3	$\pm 10$	NA
4	$\pm 10$	NA
5	$\pm 5$	NA

- (6) The **metering equipment provider** must, when **interrogating** a **metering installation**, ensure that all **raw meter data** downloaded as part of the **interrogation**, and used for submitting information for the purposes of Part 15, is archived—
  - (a) for no less than 48 months after the **interrogation** date; and
  - (b) in a form that cannot be modified without an **audit** trail being created; and
  - (c) in a form that is secure and prevents access by any unauthorised person; and
  - (d) in a form that is accessible to authorised personnel.
- (7) A **metering equipment provider** must, when **interrogating** a **metering installation**,—
  - (a) ensure that for all **metering information**, an **interrogation** log is generated by the **interrogation software** to record details of each **interrogation**; and
  - (b) review the **event log** either manually or by an automated **software** function which flags exceptions and—
    - (i) take appropriate action where problems are apparent; and
    - (ii) pass relevant **event log** entries to the **reconciliation participant** for the **metering installation**; and
  - (c) ensure that the **interrogation** log forms part of the **interrogation audit** trail and contains the following as a minimum:
    - (i) the date of **interrogation**; and
    - (ii) the time of commencement of **interrogation**; and
    - (iii) the operator of the **interrogation** system identification (where available); and
    - (iv) the unique identifier of the **data storage device** being **interrogated**; and
    - (v) any clock errors outside the range specified in Table 1 of subclause (5); and
    - (vi) the method of **interrogation**; and
    - (vii) the identifier of the reading device used for **interrogation** (if applicable).
- (8) Subclause (9) applies when—
  - (a) a **metering equipment provider** **interrogates** a **half-hour metering installation** which is a **category 1 metering installation** or a **category 2 metering installation**; and
  - (b) the **certifying ATH** confirmed, as a part of the **metering installation's** most recent **certification**, that the **metering equipment provider's back office** processes include, for each **interrogation** cycle, a comparison of the difference in the increment of the **meter** registers to the **half-hour metering raw meter data**.
- (9) When this subclause applies, the **metering equipment provider** must ensure that each electronic **interrogation** of the **metering installation** that retrieves **half hour metering information** compares that information against the increment of the **metering installation's** accumulating **meter** registers.

## 9 Contracting with ATH

A **metering equipment provider** must, when contracting with an **ATH** in relation to the required activities for the **certification** of a **metering installation** for which it is responsible, ensure that an **ATH** contracted to perform work under this Part has the appropriate scope of approval for such work.

## **Schedule 10.7** cls 10.11, 10.20, 10.26, 10.38 and 10.42 **Metering installation requirements**

### *Metering installation general requirements*

#### **1 Maintenance and repair of metering installations**

- (1) A **metering equipment provider** must comply with subclause (2)—
  - (a) for each **metering installation** for which it is responsible; and
  - (b) for each **metering component** in a **metering installation** for which it is responsible.
- (2) A **metering equipment provider** must ensure that—
  - (a) it carries out regular maintenance, including battery monitoring and replacement, in accordance with the applicable requirements in the **metering records**; and
  - (b) it carries out all necessary repairs; and
  - (c) if it is not possible to repair a **metering installation** or **metering component** so that it complies with the applicable requirements in this Part, it is—
    - (i) replaced with a **metering installation** or **metering component** that complies with the applicable requirements in this Part; or
    - (ii) in the case of a **metering installation**, **decommissioned**; and
  - (d) it documents in the **metering records** all maintenance, repairs, or replacements it carries out at the time it carries out the maintenance, repairs, or replacement.

### *Metering installation design reports*

#### **2 Design reports for metering installations**

- (1) A **metering equipment provider** must obtain a design report under this clause for—
  - (a) a proposed new **metering installation** for which it will be responsible, before it installs the **metering installation**; and
  - (b) a modification to an existing **metering installation** for which it is responsible before the modification commences.
- (2) The **metering equipment provider** must ensure that a design report is prepared by a person with an appropriate level of skill, expertise, experience, and qualification.
- (3) The **metering equipment provider** must ensure that a design report includes—
  - (a) a schematic drawing of the **metering installation** for use by an **ATH**; and
  - (b) details of the configuration scheme that programmable **metering components** are to include; and
  - (c) confirmation that the configuration scheme has been approved by an **approved test laboratory**; and
  - (d) the maximum **interrogation** cycle specified in clause 36(4); and
  - (e) any **compensation factor** arrangements; and
  - (f) the method of **certification** required under this Part to be used for the **metering installation**; and
  - (g) the name and signature of the person who prepared the design report and the date



on which it was signed.

- (4) The **metering equipment provider** must provide the design report to the **certifying ATH** before the **ATH** installs or modifies—
- (a) the **metering installation**; or
  - (b) a **metering component** in the **metering installation**.

### 3 **ATH design report obligations**

- (1) A **certifying ATH** must, before it **certifies** a new or modified **metering installation**, check and approve, in writing, the design report provided under clause 2 (including the configuration scheme and the schematic drawing), to ensure that the proposed new or modified **metering installation**—
- (a) will function correctly; and
  - (b) will provide the required accuracy and **raw meter data**; and
  - (c) complies with this Part.
- (2) The **certifying ATH** must, within 10 **business days** of the date on which it **certifies** the **metering installation**—
- (a) update the design report with any changes to the **metering installation** design; and
  - (b) provide a copy of the updated design report to the **metering equipment provider** responsible for the **metering installation**.

### 4 **Metering equipment provider obligations**

- (1) A **metering equipment provider** must, for each **metering installation** for which it is responsible,—
- (a) ensure that the sum of the measured error and **uncertainty** does not exceed the maximum permitted error set out in Table 1 of Schedule 10.1 for the category of the **metering installation**; and
  - (b) ensure that the design of the **metering installation**, including its **data storage device** and **interrogation** system, will ensure that the sum of the measured error and the smallest possible increment of the energy value of the **raw meter data** obtained from the **metering installation** does not exceed the maximum permitted error set out in Table 1 of Schedule 10.1 for the category of the **metering installation**; and
  - (c) comply with the requirements applying to the **metering equipment provider** in the design report provided under clause 2; and
  - (d) ensure that the **metering installation** complies with—
    - (i) the design report provided under clause 2; and
    - (ii) this Part.
- (2) A **metering equipment provider** must ensure that, for each **metering installation** for which it is responsible for an **ICP** that is not also an **NSP**,—
- (a) the **metering installation** configuration does not use subtraction to determine **submission information** used for the purposes of Part 15; and
  - (b) which is a category 3 or higher **metering installation**, is a **half-hour metering installation**.

- (3) A **metering equipment provider** must ensure that, for each **metering installation** for which it is responsible for an **NSP** that is not a **point of connection** to the **grid**,—
  - (a) the **metering installation** configuration does not use subtraction to determine **submission information** used for the purposes of Part 15; and
  - (b) it is a **half-hour metering installation**.
- (4) A **metering equipment provider** must, for each **metering installation** for which it is responsible, ensure that it is appropriate having regard to the physical and electrical characteristics of the **point of connection**.

*Determination of metering installation categories*

**5 Determination of metering installation category**

An **ATH** must, before it **certifies** a **metering installation**, determine the category of the **metering installation** in accordance with the following:

- (a) subject to clause 6, if the **metering installation** incorporates a current transformer, its category must be determined according to the primary current rating of the current transformer and the connected voltage set out in Table 1 of Schedule 10.1:
- (b) if the **metering installation** does not incorporate a current transformer and the quantity of **electricity** conveyed is measured by a **meter**, it must be category 1.

Clause 5(a): amended, on 23 February 2015, by clause 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 5(a): amended, on 5 October 2017, by clause 186 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

**6 Determination of metering installation incorporating current transformer to be lower category**

- (1) An **ATH** may, when determining the category of a **metering installation** under clause 5(a), determine under subclause (2) that the category is lower than would otherwise be the case under clause 5(a), only in 1 of the following circumstances:
  - (a) if a protection device, including a fuse or a **circuit breaker**, is installed that limits the maximum current of the **metering installation**; or
  - (b) if the **metering equipment provider**, acting reasonably on the basis of historical **metering data**, believes that the maximum current to be conveyed through the **point of connection** will, at all times during the intended **certification** period, be lower than the current setting of the protection device for the category for which the **metering installation**—
    - (i) is **certified**; or
    - (ii) is required to be **certified** by this Code; or
  - (c) if the **metering installation** uses less than 0.5 GWh in any 12 month period; or
  - (d) if the **metering equipment provider**, acting reasonably on the basis of historical **metering data**, believes that the **metering installation** (including, for example, a **metering installation** for an emergency fire pump or flood pump) will use less than 0.5 GWh in any 12 month period.
- (2) If an **ATH** determines the category of a **metering installation** under—
  - (a) subclause (1)(a), the **ATH** must, when **certifying** the **metering installation**,

- determine the category of the **metering installation** by reference to the maximum current setting of the protection device. The **ATH** must, when doing so—
- (i) confirm the suitability and operational condition of the protection device; and
  - (ii) record, in the **metering records**, the rating and setting of the protection device; and
  - (iii) seal the protection device under clause 47; and
  - (iv) apply, if practicable, a warning tag to the seal under clause 47(6):
- (b) subclause (1)(b), the **ATH** may, only if it considers it appropriate in the circumstances, at the request of the **metering equipment provider**, determine the **metering installation** category according to the **metering installation's** expected maximum current. If the **ATH** determines the category of a **metering installation** under this clause, then—
- (i) the **metering equipment provider** responsible for the **metering installation** must, each month, obtain a report from the **participant interrogating** the **metering installation**, detailing the maximum current conveyed through the **point of connection** for the prior month. For the purposes of this subparagraph, the **metering equipment provider** must determine the maximum current from **raw meter data** from the **metering installation** by either calculation from the kVA by **trading period** if available, or from a maximum current indicator if fitted in the **metering installation**; and
  - (ii) if the **metering equipment provider** does not receive the report in any month, or the report demonstrates that the maximum current conveyed through the **point of connection**, at any time during the previous month, exceeded the maximum permitted current for the **metering installation** category as **certified, certification** for the **metering installation** is automatically cancelled from the date on which the **metering equipment provider** should have received the report, or the date on which the **metering equipment provider** received the report:
- (c) subclause (1)(c) or subclause (1)(d),—
- (i) if the primary voltage is—
    - (A) less than 1kV, the **ATH** must determine the **metering installation** as category 2; or
    - (B) greater than or equal to 1kV, the **ATH** must determine the **metering installation** as category 3; and
  - (ii) the **metering equipment provider** responsible for the **metering installation** must, each month during the **certification** period, obtain a report from the **participant interrogating** the **metering installation** detailing the total kWh consumption of the **metering installation** for the prior 12 months:
- (d) subclause (1)(d), if the **metering equipment provider** does not receive the report in any month, or the report identifies that the **electricity** conveyed through the **point of connection** exceeded 0.5 GWh during the previous 12 month period, the

**certification** for the **metering installation** is automatically cancelled from the date on which the **metering equipment provider** should have received the report, or the date on which the **metering equipment provider** received the report.

- (3) The **ATH** must, before it determines a **metering installation** to be a lower category under this clause, visit the site of the **metering installation** to ensure that the installation is suitable for the **metering installation** to be determined to be a lower category.
- (4) If an **ATH** determines a **metering installation** to be a lower category under this clause the **metering installation certification report** must include all information required to demonstrate, as at the **certification** date, compliance with this clause.

Clause 6(1)(b): amended, on 29 August 2013, by clause 30(1) of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011, Amendment 2013 (No 2).

Clause 6(2)(b)(i): amended, on 29 August 2013, by clause 30(2) of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011, Amendment 2013 (No 2).

Clause 6(2)(c): amended, on 29 August 2013, by clause 30(3) and (4) of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011, Amendment 2013 (No 2).

Clause 6(2)(c)(iii): amended, on 29 August 2013, by clause 30(5) of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011, Amendment 2013 (No 2).

### *Certification of metering installation*

## **7 Method of certification**

- (1) An **ATH** must, when **certifying a metering installation**, only use—
  - (a) the **selected component certification** method under clause 11, if the **metering installation** is a **category 1 metering installation**, a **category 2 metering installation** or a **category 3 metering installation**; or
  - (b) the **fully calibrated certification** method under clause 13.
- (2) Despite subclause (1), an **ATH** may **recertify**—
  - (a) a **category 1 metering installation** using statistical sampling under clause 16; or
  - (b) a **category 2 metering installation** using the approved **comparative recertification** method under clause 12.
- (3) If an **ATH** uses statistical sampling under subclause (2)(a), it must use the applicable method described in subclause (1)(a) and (1)(b) to **certify each metering installation** in the sample.

## **8 Metering installation certification requirements**

- (1) An **ATH** must not **certify a metering installation** unless the **metering installation** complies with this Part.
- (2) An **ATH** must, when **certifying a metering installation**,—
  - (a) prepare a **certification report** for the **metering installation**; and
  - (b) specify in the **certification report** whether the **metering installation** is either—
    - (i) **half hour**; or
    - (ii) **non half hour**; and
  - (c) determine the **services access interface** for the **metering installation** under clause 10 of Schedule 10.4 and record it in the **metering installation certification report**; and

- (d) ensure that each **metering component** in the **metering installation** functions correctly.
- (3) An **ATH** may only **certify** a **metering installation** as category 3 or higher if the **metering installation** incorporates a **half hour meter** or **half hour data storage device** to quantify the **electricity** conveyed.
- (4) An **ATH** must, when preparing a **metering installation certification report**, record the category of the **metering installation**.

Clause 8(3): amended, on 29 August 2013, by clause 31 of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011, Amendment 2013 (No 2).

## 9 Certification tests

- (1) An **ATH**, when carrying out a test set out in Table 3 or 4 of Schedule 10.1,—
  - (a) to carry out a prevailing load test on a **metering installation** or **metering component**, must do so by using a **working standard** connected to the **metering installation**:
  - (b) to carry out an installation or component configuration test on a **metering installation** or **metering component**, must ensure that the actual configuration scheme is the same as the scheme for the **metering installation** or **metering component** recorded in the design report:
  - (c) to carry out a **raw meter data** output test for a **category 1 metering installation** or **category 2 metering installation**, must do so by applying a measured increase in load and measuring—
    - (i) the increment of the sum of the **meter** registers; or
    - (ii) the accumulation of pulses resulting from the increase in load:
  - (d) to carry out a **raw meter data** output test for a **half-hour metering installation** which is a **category 1 metering installation** or for a **half-hour metering installation** which is a **category 2 metering installation**, must either—
    - (i) compare the output from a **working standard** to the **raw meter data** from the **metering installation** for a minimum of 1 **trading period**; or
    - (ii) confirm that the **metering equipment provider's back office** processes include a comparison of the difference in the increment of the **meter** registers to the **half-hour metering raw meter data**, if the **raw meter data** is to be used for the purposes of Part 15:
  - (e) to carry out a **raw meter data** output test for a category 3 or higher **half-hour metering installation**, must compare the output of a **working standard** to the **raw meter data** from the **metering installation** for a minimum of 1 **trading period**:
  - (f) to carry out a **raw meter data** output test for a **non half-hour metering installation** which is a **category 2 metering installation**, must do so by comparing the output of a **working standard** to the increment of the sum of the **meter** registers.
- (1A) If an **ATH** performs a **raw meter data** output test under subclause (1)(c) or subclause (1)(d), for a **metering installation** that will be **certified** for remote **meter** reading, the **ATH** must—

- (a) obtain the **raw meter data** from the **back office** system where the **raw meter data** is held; or
  - (b) ensure that the **metering equipment provider** responsible for the **metering installation** has a process to validate a **meter** reading taken at the time of the **metering installation certification** with a **meter** reading from the **metering equipment provider's back office** system.
- (2) If an **ATH** performs a test under subclause (1) that requires a comparison between 2 quantities, the **ATH** must not **certify** the **metering installation** unless the **metering installation** passes the test.
- (3) For the purposes of subclause (2), a **metering installation** passes if the test demonstrates that the difference between the 2 quantities is within the applicable accuracy tolerances set out in Table 1 of Schedule 10.1.

Clause 9(1): amended, on 29 August 2013, by clause 32(1) of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011, Amendment 2013 (No 2).

Clause 9(1)(c)(i) and (ii): inserted, on 29 August 2013, by clause 32(2) of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011, Amendment 2013 (No 2).

Clause 9(1A): inserted, on 29 August 2013, by clause 32(3) of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011, Amendment 2013 (No 2).

## 10 Test results

- (1) An **ATH** must, before it **certifies** a **metering installation** or any of a **metering installation's metering components**, review the relevant test results for each of the **metering installation's metering components** to ensure that—
- (a) the **metering component** passed all the tests; and
  - (b) the **metering installation** meets the requirements for **certification**.
- (2) If the **ATH** considers that the test results show that the requirements in this Part for **certification** of the **metering installation** are not met, it must—
- (a) within 5 **business days** of reviewing the tests, advise the relevant **metering equipment provider** providing detailed reasons; and
  - (b) not **certify** the **metering installation**.

## 11 Selected component certification of metering installation

- (1) This clause applies only when an **ATH** uses the **selected component certification** method.
- (2) An **ATH** may use the **selected component certification** method to **certify** a **metering installation** only for the categories of **metering installation** for which the stated requirements are set out in Table 1 of Schedule 10.1.
- (3) An **ATH** must only use the **selected component certification** method to **certify** a **metering installation**—
- (a) by carrying out the tests set out in Table 3 of Schedule 10.1; and
  - (b) if an **ATH** or an **approved test laboratory** or an **approved calibration laboratory** has **calibrated** each of the following **metering components** in the **metering installation** in accordance with clause 1(1)(a)(ii) or 1(1)(b) of Schedule 10.8:
    - (i) **meter**:

- (ii) **measuring transformer**; and
  - (c) if each **data storage device** in the **metering installation** has been **certified** in accordance with clause 5 of Schedule 10.8.
- (4) An **ATH** must, before it uses the **selected component certification** method,—
  - (a) check the design report of the **metering installation** to—
    - (i) confirm the **metering installation** functions in accordance with the design report; and
    - (ii) ensure the **metering installation** complies with this Part; and
  - (b) ensure that each **metering component** in the **metering installation** is used only in a permitted combination as set out in Table 1 of Schedule 10.1; and
  - (c) check and confirm that the **metering installation** is correctly wired in accordance with all applicable requirements and enactments; and
  - (d) ensure that each **metering component** in the **metering installation** is fit for purpose.
- (5) An **ATH** must, when it **certifies** a **metering installation** under this clause, ensure that the **metering installation certification report** includes confirmation that the **ATH** has—
  - (a) checked the design report of the **metering installation** to—
    - (i) confirm the **metering installation** functions in accordance with the design report; and
    - (ii) ensure the **metering installation** complies with this Part; and
  - (b) ensured that each **metering component** in the **metering installation** has been **calibrated** and **certified** as required in this Part; and
  - (c) ensured that the **metering installation** has passed the relevant tests and checks set out in Table 3 of Schedule 10.1; and
  - (d) checked and confirmed that the **metering installation** is correctly wired in accordance with all applicable requirements and enactments; and
  - (e) carried out any tests and checks required to confirm the integrity of the **metering installation** and recorded these and their results in the **metering installation certification report**.
- (6) An **ATH** must, when it **certifies** a **metering installation** under this clause, include in the **metering installation certification report**—
  - (a) any **compensation factors** that must be applied; and
  - (b) how the **compensation factors** must be applied under clause 2 of Schedule 15.3.

Clause 11(3)(b): substituted, on 29 August 2013, by clause 33(1) of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011, Amendment 2013 (No 2).

Clause 11(3)(b): amended, on 15 May 2014, by clause 18 of the Electricity Industry Participation (Minor Code Amendments) Code Amendment 2014.

Clause 11(3)(c): inserted, on 29 August 2013, by clause 33(1) of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011, Amendment 2013 (No 2).

Clause 11(5)(e): amended, on 29 August 2013, by clause 33(2) of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011, Amendment 2013 (No 2).

## 12 Comparative recertification

- (1) This clause only applies when an **ATH** uses the **comparative recertification** method.
- (2) An **ATH** may only use the **comparative recertification** method to **recertify** a **category**

**2 metering installation** in accordance with this Part if—

- (a) the **certification** of the current transformers in the **metering installation** expires before the **meter certification** expiry date; and
  - (b) each of the following **metering components** in the **metering installation** has been **certified** in accordance with Schedule 10.8:
    - (i) **data storage device**;
    - (ii) **meter**.
- (3) An **ATH** must, when **recertifying** a **category 2 metering installation** under this clause, ensure that—
- (a) the **metering installation** has passed the tests set out in Table 3 of Schedule 10.1, using a **working standard** connected to the **metering installation**; and
  - (b) the current measurement sensor connected around the cables or bus-bars adjacent to the **metering installation** is sufficiently accurate so that the sum of the measured **metering installation** accuracy, the **uncertainty** of the **metering installation**, and the **uncertainty** of the current measurement sensor does not exceed the maximum permitted error set out in Table 1 of Schedule 10.1 for the category of the **metering installation**; and
  - (c) the overall **metering installation** accuracy meets the requirements of Table 1 of Schedule 10.1.
- (4) An **ATH** must, before it uses the **comparative recertification** method—
- (a) check the design report of the **metering installation** to—
    - (i) confirm the **metering installation** functions in accordance with the design report; and
    - (ii) ensure the **metering installation** complies with this Part; and
  - (b) check and confirm that the **metering installation** is correctly wired in accordance with all applicable requirements and enactments; and
  - (c) carry out any tests and checks required to confirm the integrity of the **metering installation** and record these and their results in the **metering installation certification report**.
- (5) An **ATH** must, for each **metering installation** it **certifies** under this clause,—
- (a) prepare a **certification report**; and
  - (b) ensure that each **metering component** in the **metering installation** is fit for purpose.

### **13 Fully calibrated metering installation certification**

- (1) This clause only applies when an **ATH** uses the **fully calibrated certification** method.
- (2) An **ATH** may only use the **fully calibrated certification** method to **certify** a **category 1 metering installation**, or higher category of **metering installation**.
- (3) An **ATH** must use the **fully calibrated certification** method to **certify** a **metering installation**—
  - (a) by carrying out the tests set out in Table 4 of Schedule 10.1; and
  - (b) only if each of the following **metering components** in the **metering installation** has been **certified** in accordance with Schedule 10.8:
    - (i) **data storage device**;



- (ii) **meter:**
  - (iii) **measuring transformer.**
- (4) An **ATH** must ensure that each **metering component** in a **metering installation** which is **certified** under this clause has a current **certification report** that—
  - (a) complies with the requirements of this Part; and
  - (b) if the **metering component** is a **calibrated metering component**, includes a **calibration report** that—
    - (i) confirms that the **metering component** complies with the requirements of its accuracy class set out in Table 1 of Schedule 10.1; and
    - (ii) includes the **certification** date of the **metering component**.
- (5) An **ATH** must, when preparing a **metering installation certification report** under this clause, include confirmation that the **ATH** has—
  - (a) checked the design report of the **metering installation** to—
    - (i) confirm the **metering installation** functions in accordance with the design report; and
    - (ii) ensure the **metering installation** complies with this Part; and
  - (b) ensured that each **metering component** in the **metering installation** has been **calibrated** and **certified** as required in this Part; and
  - (c) ensured that the relevant tests and checks set out in Table 4 of Schedule 10.1 have been passed; and
  - (d) checked and confirmed that the **metering installation** is correctly wired in accordance with all applicable requirements and enactments; and
  - (e) carried out any tests and checks required to confirm the integrity of the **metering installation**.
- (6) An **ATH** must, when it **certifies** a **metering installation** under this clause, include in the **metering installation certification report**—
  - (a) any **compensation factors** that must be applied; and
  - (b) how the **compensation factors** must be applied under clause 2 of Schedule 15.3.
- (7) An **ATH** must, before it **certifies** a **metering installation** under this clause, ensure that the **ATH** uses the manufacturer's **meter** class accuracy, and not the **meter's** actual tested accuracy, to determine whether the **metering installation** is within the relevant maximum permitted error set out in Table 1 of Schedule 10.1.

#### **14 Insufficient load for metering installation certification tests**

- (1) This clause only applies if there is insufficient **electricity** conveyed through a **point of connection** to allow an **ATH** to complete a prevailing load test for a **metering installation** that is being **certified** as a **half-hour metering installation**.
- (2) When this clause applies, the **ATH** must, when **certifying** the **metering installation**, ensure that—
  - (a) it performs an additional integrity check of the **metering installation** wiring, and records the results of this check in the **certification report**; and
  - (b) it records in the **certification report** that the **metering installation** is **certified** under this clause.
- (3) A **metering equipment provider** must, for each **metering installation** for which it is

responsible, and that is **certified** under this clause, obtain and monitor **raw meter data** from the **metering installation** at least once each month during the period of **certification** to determine if load during the month is sufficient for a prevailing load test to be completed.

- (4) Despite subclause (1), the **metering equipment provider** must, if **raw meter data** obtained under subclause (3) demonstrates, at any time, that there is sufficient **electricity** conveyed through the **point of connection** for a prevailing load test to be completed, ensure that the **certifying ATH** makes a subsequent visit to the **metering installation** as soon as practicable, but no later than 20 **business days** after the **metering equipment provider** has obtained the **raw meter data**, to carry out and complete the tests set out in Table 4 of Schedule 10.1.
- (5) The **certifying ATH** must, if the tests referred to in subclause (4) demonstrate that the **metering installation** performs within the relevant maximum permitted error set out in Table 1 of Schedule 10.1,—
  - (a) update the **metering installation certification report**, within 5 **business days** of completing the tests, to include the results of the tests carried out; and
  - (b) leave the original **metering installation certification** expiry date unchanged.
- (6) If the tests referred to in subclause (4) demonstrate that the **metering installation** does not perform within the relevant maximum permitted error set out in Table 1 of Schedule 10.1—
  - (a) the **metering installation certification** is automatically cancelled from the date of the tests; and
  - (b) the **certifying ATH** must advise the **metering equipment provider** of the cancellation within 1 **business day** of carrying out the tests; and
  - (c) the **metering equipment provider** must follow the procedure set out in clauses 10.43 to 10.48.

Clause 14(1): amended, on 29 August 2013, by clause 34 of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011, Amendment 2013 (No 2).

Clause 14(3): amended, on 5 October 2017, by clause 187 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

## 15 Recertification programme

- (1) A **metering equipment provider** must have a **recertification** programme for all **metering installations** for which it is responsible to ensure that each **metering installation** is **recertified** prior to the expiry date of its then current **certification** if the **metering installation** is not **decommissioned**.
- (2) Subclause (1) does not apply to an **electrically disconnected metering installation** for an **ICP**.

Clause 15(2): amended, on 5 October 2017, by clause 188 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### *Statistical sampling recertification*

## 16 Recertification of group of category 1 metering installations by statistical sampling

- (1) A **metering equipment provider** may arrange for an **ATH** to **recertify** a group of **category 1 metering installations** for which the **metering equipment provider** is responsible using a statistical sampling process set out in subclause (2).

- (2) To **recertify** a group of **category 1 metering installations**, an **ATH** must—
- (a) select a sample from the group, using a statistical sampling process—
    - (i) prescribed in AS/NZS 1284; or
    - (ii) that is approved and **published** by the **Authority**; and
  - (aa) use the pass/fail criteria in AS/NZS 1284 to evaluate whether the group meets the **recertification** requirements of this Part; and
  - (b) **recertify** each **metering component** in the **metering installation** in the sample using—
    - (i) the **fully calibrated certification** method; or
    - (ii) the **selected component certification** method; and
  - (c) advise the **metering equipment provider** as soon as reasonably practicable, if the group—
    - (i) meets the **recertification** requirements of this Part; or
    - (ii) fails to meet the **recertification** requirements of this Part.
- (3) An **ATH** must, when selecting a sample from the group under subclause (2)(a),—
- (a) document the process it follows and any assumptions it makes; and
  - (b) keep records in accordance with clause 13 of Schedule 10.4, of—
    - (i) each step in the process; and
    - (ii) each **metering installation** in the sample; and
    - (iii) each **metering installation** in the group that is **recertified** using this process.
- (4) The **recertification** of a **metering installation** in the group—
- (a) commences from the date of the advice referred to in subclause (2)(c)(i) if the sample meets the **recertification** requirements of this Part;
  - (b) is automatically cancelled from the date of the advice referred to in subclause (2)(c)(ii) if the sample fails to meet the **recertification** requirements of this Part.
- (5) The **metering equipment provider** must, upon being advised under subclause (2)(c), update the **registry** in accordance with Part 11.
- (6) Despite clause 41(1), an **ATH** who **recertifies** a group of **metering installations** using a statistical sampling process is not required to apply a **certification sticker** to a **metering installation** in the group that was not part of the sample.

Clause 16(2)(a)(i): amended, on 29 August 2013, by clause 35(1) of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011, Amendment 2013 (No 2).

Clause 16(2)(aa): inserted, on 29 August 2013, by clause 35(3) of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011, Amendment 2013 (No 2).

Clause 16(2)(b): substituted, on 29 August 2013, by clause 35(4) of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011, Amendment 2013 (No 2).

Clause 16(2)(c): amended, on 29 August 2013, by clause 35(5) of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011, Amendment 2013 (No 2).

### *Certification validity periods*

## **17 Determination of expiry dates for certification of metering components and metering installations**

- (1) An **ATH** must, when **certifying** a **metering installation**,—

- (a) determine, in accordance with this clause, the date on which the **metering installation's certification** will expire; and
- (b) record the expiry date in the **metering installation certification report**.
- (2) The expiry date for a **metering installation's certification** is the earliest of—
  - (a) the date falling after the date of its **commissioning** by the number of months equivalent to the maximum **metering installation certification** validity period for the relevant category of **metering installation**, as set out in Table 1 of Schedule 10.1; and
  - (b) the earliest **certification** expiry date of a **metering component** in the **metering installation**; and
  - (c) a date determined by the **ATH** taking into account—
    - (i) the condition of each **metering component** in the **metering installation**; and
    - (ii) all relevant circumstances relating to the **metering installation**.
- (3) Despite subclause (2), the expiry date for each **metering installation** in a group of **metering installations recertified** under clause 16, that does not form a part of the sample, is the earliest expiry date of the **metering installations** in the sample.

## 18 Interim certified metering installations

A **metering equipment provider** must ensure that each **interim certified metering installation** on 28 August 2013 is **certified** under this Part by no later than 1 April 2015.

Clause 18: amended, on 29 August 2013, by clause 36 of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011, Amendment 2013 (No 2).

## 19 Modification of metering installations

- (1) If a **metering installation** is modified, the **certification** of the **metering installation** is automatically cancelled with effect from—
  - (a) the date the modification began; or
  - (b) if the **metering equipment provider** responsible for the **metering installation** does not know the date in subclause (a), the date on which the **metering equipment provider** became aware of, or would reasonably have been expected to have become aware of, the modification.
- (2) For the purposes of this clause, a modification of a **metering installation** includes, any 1 or more of the following:
  - (a) any change to the **software**, ROM, or firmware in the **metering installation** that may affect the operation of the **metrology layer** unless the change is made under subclause (3);
  - (b) installation, removal, repair, or modification, of a **metering component** in the **metering installation**, other than the temporary connection of testing or monitoring equipment by using a **test facility**;
  - (c) any change to the burdening of a **measuring transformer** in the **metering installation**, unless changed under clause 31(6);
  - (d) reconfiguration of any wiring (but not straight replacement of wiring in a **category 1 metering installation**):

- (e) relocation of a **metering component** in the **metering installation** or the **metering installation** enclosure;
  - (f) any interference with the **metering installation** that affects the accuracy of the **metering installation**.
- (2A) For the purposes of subclause (1), and despite subclause (2), a modification of a **metering installation** does not include the replacement of a modem in the **metering installation** by the **ATH** that is responsible for **certifying** the **metering installation**.
- (3) Despite subclauses (1) and (2)(a), the **certification** of a **metering installation** is not cancelled if—
- (a) an **approved test laboratory** has tested and confirmed under clause 39 that the integrity of the measurement and logging of a **data storage device** in the **metering installation** would be unaffected by the change; and
  - (b) the change does not, or would not be considered by the **ATH** who most recently **certified** the **metering installation** to, affect—
    - (i) the accuracy of the **raw meter data** obtained from the **metering installation**; or
    - (ii) the accuracy of the **metrology layer** of the **metering installation**; or
    - (iii) a **compensation factor** programmed into any **metering component** in the **metering installation**; and
  - (c) the **ATH** who most recently **certified** the **metering installation** approves, in advance, the process of changing the **software**, ROM, or firmware in the **metering installation**; and
  - (d) the change is carried out in accordance with a documented methodology that has been **audited** under this Part; and
  - (e) the **metering equipment provider** responsible for the **metering installation** records in the **metering records** the details of the change, including the time and date; and
  - (f) any change of the **metering installation's** parameters does not affect the **metrology layer**.
  - (g) *[Revoked]*
- (3A) Despite subclauses (1) and (2)(b), the **certification** of a **metering installation** is not cancelled if—
- (aa) a **control device** that does not switch **meter** registers has malfunctioned and been replaced with a **certified control device**; and
  - (a) the replacement **control device** has the same characteristics as the **control device** it replaces and—
    - (i) is **certified** in accordance with this Part; and
    - (ii) will not adversely affect the operation of any other **metering components** or connections to those **metering components**; and
    - (iii) is likely to receive control signals, as required by clause 34; and
    - (iv) is correctly connected and programmed; and
  - (b) the **metering equipment provider** responsible for the **metering installation** has in place—

- (i) an appropriate agreement with the **approved test house** that is responsible for the **certification** of the **metering installation**, to record the replacement in its **metering installation certification** records; and
  - (ii) appropriate procedures for ensuring that replacements are carried out only by persons authorised by the **metering equipment provider**; and
- (c) the **metering equipment provider** updates—
  - (i) the **metering records** with the details of the replacement, including the date; and
  - (ii) the **registry metering records**.
- (3B) A procedure under subclause (3A)(b)(ii) must ensure that, within 10 **business days** of the replacement occurring, the person carrying out the replacement provides the notification and **metering records** for the replaced **control device** and the replacement **control device** to—
  - (a) the **metering equipment provider**; and
  - (b) the **approved test house** that is responsible for the **certification** of the **metering installation**.
- (4) Despite subclause (2)(e), the **certification** of a **metering installation** continues if—
  - (a) there is a minor repositioning of 1 of the following in a **category 1 metering installation** which does not involve disconnection of wiring:
    - (i) the **meter** in the existing **metering installation** enclosure; or
    - (ii) the existing **metering installation** enclosure; or
  - (b) the relocation does not cause, directly or indirectly, the **metering installation** to be—
    - (i) outside the applicable accuracy tolerances set out in Table 1 of Schedule 10.1; or
    - (ii) defective; or
    - (iii) not fit for purpose.
- (5) If a **metering component** that must be **certified** under this Part and which is in an **interim certified metering installation** is modified, or replaced with a **metering component** that is not **certified** under Schedule 10.8, the **interim certified metering installation's certification** is automatically cancelled from the date of the modification or replacement.
- (6) Despite subclause (5), if an **ATH** modifies an **interim certified metering installation** by replacing a **metering component** that must be **certified** under this Part with an equivalent **certified metering component**, the **interim certified metering installation's certification** is not cancelled.
- (7) A replacement **metering component** under subclauses (5) or (6) must comply with this Code.

Clause 19(2A): inserted, on 29 August 2013, by clause 37(1) of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011, Amendment 2013 (No 2).

Clause 19(3)(f): amended, on 29 August 2013, by clause 37(2) of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011, Amendment 2013 (No 2).

Clause 19(3)(f): amended, on 1 February 2016, by clause 32(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

Clause 19(3)(g): revoked, on 1 February 2016, by clause 32(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

Clause 19(3)(g): inserted, on 29 August 2013, by clause 37(3) of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011, Amendment 2013 (No 2).

Clause 19(3A): amended, on 1 February 2016, by clause 32(3)(a) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

Clause 19(3A)(aa): inserted, on 1 February 2016, by clause 32(3)(b) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

Clause 19(3A) and 19(3B): inserted, on 29 August 2013, by clause 37(3) of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011, Amendment 2013 (No 2).

## **20 Cancellation of certification of metering installations**

- (1) The **certification of a metering installation** is automatically cancelled on the date on which any 1 of the following events takes place:
- (a) the **metering installation** is modified otherwise than under clause 19(3), 19(3A), or 19(6):
  - (b) the **metering installation** is classed as outside the applicable accuracy tolerances set out in Table 1 of Schedule 10.1, defective, or not fit for purpose under—
    - (i) this Part; or
    - (ii) any **audit**:
  - (c) an **ATH** advises the **metering equipment provider** responsible for the **metering installation** of—
    - (i) a **reference standard** or **working standard** used to **certify** the **metering installation** not being compliant with this Part when it was used to **certify** the **metering installation**; or
    - (ii) the failure of a group of **meters** in the statistical sampling **recertification** process for the **metering installation**; or
    - (iii) the failure of a **certification** test for the **metering installation**:
  - (d) the manufacturer of a **metering component** in the **metering installation** determines that the **metering component** does not comply with the standards to which the **metering component** was tested:
  - (e) an inspection of the **metering installation**, that is required under this Part, is not carried out in accordance with the relevant clauses of this Part:
  - (f) if the **metering installation** has been determined to be a lower category under clause 6 and the maximum current conveyed through the **metering installation** at any time exceeds the current rating of its **metering installation** category as set out in Table 1 of Schedule 10.1:
  - (g) the **metering installation**—
    - (i) is **certified** under clause 14 and sufficient load is available for full **certification** testing; and
    - (ii) has not been retested under clause 14(4):
  - (h) a **control device** in the **metering installation certification** is, and remains for a period of at least 10 **business days**, bridged out under clause 35(1):
  - (i) the **metering equipment provider** responsible for the **metering installation** is advised by an **ATH** under clause 48(6)(b) that a seal has been removed or broken and the accuracy and continued integrity of the **metering installation** has been affected.
- (2) A **metering equipment provider** must, within 10 **business days** of becoming aware

that 1 of the events in subclause (1) has occurred in relation to a **metering installation** for which it is responsible, update the **metering installation's certification** expiry date in the **registry**.

Clause 20(1): amended, on 1 February 2016, by clause 33(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

Clause 20(1)(a): amended, on 1 February 2016, by clause 33(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

### *Accuracy and error calculation*

## **21 Metering installation accuracy**

An **ATH** must not **certify** a **metering installation** if the **metering installation** exceeds the maximum permitted error for the relevant **metering installation** category set out in Table 1 of Schedule 10.1, after the application of any external **compensation factors**.

## **22 Error Calculation**

- (1) An **ATH** must, before it **certifies** a **metering installation** under clauses 12 or 13, calculate the error of the **metering installation** in accordance with the following:
  - (a) the **ATH** must calculate the percentage error of the **metering installation** using appropriate mathematical methods, taking account of—
    - (i) all sources of measurement error; and
    - (ii) the estimated total quantity of **electricity** to be conveyed through the **metering installation** over the next 12 months; and
  - (b) the error calculation must include **uncertainty** in measurement; and
  - (c) for the purposes of paragraph (b), the **ATH** must calculate **uncertainty** at a 95% level of confidence and in compliance with JCGM 100:2008.
- (2) The **ATH** must not **certify** the **metering installation** if—
  - (a) the **uncertainty** for the **metering installation** is greater than the relevant maximum site **uncertainty** set out in Table 1 of Schedule 10.1; and
  - (b) the sum of the measured error and the **uncertainty** of the **metering installation** is greater than the relevant maximum permitted error set out in Table 1 of Schedule 10.1.
- (3) The **ATH** must record the calculation under subclause (1)(a) in the **metering installation certification report**.

## **23 Time keeping requirements**

A **metering equipment provider** must, if a time keeping device that is not remotely monitored and corrected controls the switching of a **meter** register in a **metering installation** for which it is responsible, ensure that the time keeping device—

- (a) has a time keeping error of not greater than an average of 2 seconds per day over a period of 12 months; and
- (b) is monitored and corrected at least once every 12 months.

## **24 Compensation factors**

- (1) An **ATH** must, before it **certifies** a **metering installation** that requires a **compensation factor** to adjust **raw meter data**—



- (a) advise the **metering equipment provider** responsible for the **metering installation** of the **compensation factor**; and
- (b) ensure that the **compensation factor** to be applied to **raw meter data** external to the **metering installation** can only be applied as follows:
  - (i) for **ratio compensation**, on a **category 1 metering installation**, or higher category of **metering installation**; or
  - (ii) for **error compensation**, on a **metering installation** that quantifies **electricity** conveyed through a **point of connection** to the **grid**; or
  - (iii) for **loss compensation**, only on a category 3 or higher **metering installation**.
- (2) An **ATH** must, when it prepares a **certification report** for a **metering installation** that requires a **compensation factor**, record the methodology, assumptions, measurements, calculation, and details of—
  - (a) each **compensation factor** that is included within the internal configuration of the **metering installation**; and
  - (b) each **compensation factor** that must be applied to the **raw meter data**.
- (3) A **metering equipment provider** must, for a **metering installation** in relation to which a **compensation factor** must be applied,—
  - (a) if the **metering installation** is for a **point of connection** that is an **NSP**, advise the **reconciliation participant** responsible for the **metering installation** of the **compensation factor** within 10 **business days** of the date on which the **metering installation** is **certified**; or
  - (b) in all other cases, update the **compensation factor** recorded in the **registry** in accordance with Part 11.

Clause 24(3)(b): amended, on 5 October 2017, by clause 189 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### *Installation of metering components in metering installations*

## **25 Installation of metering components**

- (1) An **ATH** must, before it **certifies a metering installation**, ensure that installation of—
  - (a) **measuring transformers**, and associated burden if required, **test facilities**, potential fuses, and switchboard wiring, was carried out by—
    - (i) a suitably qualified person (for example by a switchboard manufacturer); or
    - (ii) an **ATH**; and
  - (b) each **metering component** in the **metering installation**, other than a **metering component** referred to in paragraph (a), is carried out by an **ATH**.
- (2) An **ATH** must, before it **certifies a metering installation**, ensure that each **metering component** in the **metering installation** has been installed in accordance with the design report under clause 2.

## **26 Requirements for metering installation incorporating meter**

- (1) A **metering equipment provider** must ensure that each **meter** in a **metering installation** for which it is responsible is **certified** in accordance with this Part.
- (2) An **ATH** must, unless clause 43(2) applies, before it **certifies a metering installation**

incorporating a **meter**, if the **meter** had previously been used in another **metering installation**, ensure that the **meter** has been **recalibrated** since it was removed from the previous **metering installation**, by—

- (a) an **approved calibration laboratory**; or
  - (b) an **ATH**.
- (3) The **ATH** must, before it **certifies** a **metering installation** incorporating a **meter**, document in the **metering records**—
- (a) any regular maintenance required for the **meter** in accordance with the manufacturer's recommendations; and
  - (b) any maintenance that has been carried out on the **meter** (for example battery monitoring and replacement).
- (4) An **ATH** must, before it **certifies** a **metering installation** incorporating a **meter**, record in the **metering installation certification report**, the maximum **interrogation** cycle for the **metering installation**.
- (5) The maximum **interrogation** cycle for a **metering installation** referred to in subclause (4) is the period of memory availability given the **meter** configuration.
- (6) Subclause (4) does not apply to a **metering installation** incorporating both a **meter** and a **data storage device** (*see* clause 36 of Schedule 10.7).

Clause 26(2): amended, on 1 February 2016, by clause 34(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

Clause 26(6): substituted, on 1 February 2016, by clause 34(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

## **27 Meter certification expiry date**

- (1) An **ATH** must, before it **certifies** a **metering installation** incorporating a **meter**, determine the **meter certification** expiry date for each **meter** in the **metering installation** in accordance with this clause.
- (2) The **meter certification** expiry date must be the earliest end date of the following periods, calculated from the date of **commissioning** of the **metering installation**:
- (a) the maximum **metering installation certification** validity period set out in Table 1 of Schedule 10.1 for the relevant category of **metering installation**; or
  - (b) the maximum **meter certification** validity period set out in Table 2 of Schedule 10.1 for the relevant class of **meter** for the **metering installation**; or
  - (c) the **certification** period specified in the **meter certification report**.
- (3) Despite subclause (2), the **meter certification** expiry date for a **meter** that has been **certified** and subsequently installed in, but then removed from, a **category 1 metering installation**, remains the **meter certification** expiry date determined for that **meter** when it was installed in the **category 1 metering installation**.
- (4) Despite subclauses (2) and (3), if an electromechanical **meter** is not installed in a **metering installation** within 24 months of the date of the **meter's certification report**, the **meter** must be **recertified** before it is installed.
- (5) The **ATH** must record the **certification** expiry date for each **meter** in a **metering installation** in—
- (a) the **metering installation certification report**; and
  - (b) the **meter certification report**.

Clause 27(3): amended, on 29 August 2013, by clause 38 of the Electricity Industry Participation (Metering

Arrangements) Code Amendment 2011, Amendment 2013 (No 2).

**28 Requirements for metering installation incorporating measuring transformer**

- (1) A **metering equipment provider** must ensure that each **measuring transformer** in a **metering installation** for which it is responsible is **certified** in accordance with this Part.
- (2) An **ATH** must, before it **certifies** a **metering installation** which includes a **measuring transformer** that had previously been used in another **metering installation**, ensure that the **measuring transformer** has been **recalibrated**, since it was removed from the previous **metering installation**, by—
  - (a) an **approved calibration laboratory**; or
  - (b) an **ATH**.
- (3) The **ATH** must, before it **certifies** a **metering installation** incorporating a **measuring transformer**, document in the **metering records**—
  - (a) any regular maintenance required for the **measuring transformer** in accordance with the manufacturer's recommendations; and
  - (b) any maintenance that has been carried out on the **measuring transformer**.
- (4) An **ATH** must, before it **certifies** a **metering installation** incorporating a **measuring transformer**,—
  - (a) ensure that—
    - (i) the **measuring transformer** is connected to a **meter** through a **test facility** that has provision for isolation; and
    - (ia) the **test facility** and the provision for isolation are installed as physically close to the **meter** as practicable in the circumstances; and
    - (ii) the **test facility** has a transparent cover that is not obscured; and
  - (b) using the **fully calibrated certification** method, ensure that the **ATH** uses the **measuring transformer's** actual accuracy (rather than class accuracy) when calculating the maximum permitted error for the relevant **metering installation** category set out in Table 1 of Schedule 10.1; and
  - (c) carry out primary injection tests on the **measuring transformer** if it considers it is appropriate in the circumstances; and
  - (d) ensure that the **measuring transformer** is—
    - (i) mounted securely; and
    - (ii) if practicable, in an enclosure that is sealed in accordance with clause 47 against unauthorised access; and
  - (e) ensure that any voltage supply from a voltage transformer to a **meter**, or other equipment in the **metering installation**, is protected by appropriately rated fuses or **circuit breakers** dedicated to the supply; and
  - (f) ensure that all fuses and **circuit breakers** are sealed or located in sealed enclosures under clause 47; and
  - (g) ensure that, if an enclosure also contains fuses or **circuit breakers** supplying other circuits, those supplying **metering** circuits are individually sealed; and
  - (h) ensure that if the **measuring transformer's** secondary circuit in the **metering installation** is earthed, it is earthed at no more than 1 point; and
  - (i) ensure that the total burden (magnitude and phase angle, where appropriate) on

the **measuring transformer** does not exceed—

- (i) its name plate rating; or
- (ii) an alternative rating lower than the name plate rating, if specified in the **metering installation** design report.

- (5) Despite subclause (4)(d)(ii), if access to the enclosure is required by a person other than an employee or subcontractor of an **ATH**, the **ATH** may use alternative sealing arrangements (for example, terminal studs drilled so that sealing wire can be passed through the holes to secure the connections, or the use of sealing paint applied to terminal screws).

Clause 28(4)(a): substituted, on 29 August 2013, by clause 39 of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011, Amendment 2013 (No 2).

## **29 Measuring transformer certification expiry date**

- (1) An **ATH** must, before it **certifies** a **metering installation** incorporating a **measuring transformer**, determine the **measuring transformer certification** expiry date for each **measuring transformer** in the **metering installation** in accordance with this clause.
- (2) The **measuring transformer certification** expiry date must be no later than the last day of the **measuring transformer certification** validity period specified in the **measuring transformer certification report**, after the date of **commissioning**.
- (3) The **ATH** must record the **measuring transformer certification** expiry date for each **measuring transformer** in a **metering installation** in—
  - (a) the **certification report** for the **metering installation**; and
  - (b) the **certification report** for the **measuring transformer**.

## **30 Other equipment using measuring transformer**

- (1) A **metering equipment provider** must not permit a **measuring transformer**, in a **metering installation** for which it is responsible, to be connected to equipment used at any time for a purpose other than **metering**, unless it is not practical for the equipment to have a separate **measuring transformer**.
- (2) An **ATH** must, before it **certifies** a **metering installation** incorporating a **measuring transformer** used by—
  - (a) another **metering installation**, ensure, where voltage transformers are connected to more than 1 **meter**, that—
    - (i) the **meters** are included in the **metering installation** being **certified**; and
    - (ii) appropriate fuses or **circuit breakers** are provided to protect the **metering** circuit from short circuits or overloads affecting the other **meter**;
  - (b) equipment referred to in subclause (1), ensure that—
    - (i) the accuracy of the **metering installation** remains within the maximum permitted error for the relevant **metering installation** category set out in Table 1 of Schedule 10.1; and
    - (ii) the **metering installation certification report** confirms that the accuracy of the **metering installation** remains within the maximum permitted error for the relevant **metering installation** set out in Table 1 of Schedule 10.1; and
    - (iii) any wiring between the equipment and any part of the **metering installation** has no intermediate joints; and

- (iv) the equipment referred to in subclause (1) is labelled appropriately, including with any restrictions regarding being **electrically disconnected**; and
- (v) the connection details of the equipment referred to in subclause (1) are recorded in the **metering installation** design report; and
- (vi) appropriate fuses or **circuit breakers** are provided to protect the voltage transformer and **metering** circuit from short circuits or overloads affecting the other equipment; and
- (vii) the wiring referred to in subparagraph (iii) is **certified** as part of the **metering installation**.

(3) *[Revoked]*

Clause 30(2)(b)(iv): amended, on 5 October 2017, by clause 190 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 30(2)(b)(vi): amended, on 29 August 2013, by clause 40(1) of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011, Amendment 2013 (No 2).

Clause 30(2)(b)(vii): inserted, on 29 August 2013, by clause 40(2) of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011, Amendment 2013 (No 2).

Clause 30(3): revoked, on 29 August 2013, by clause 40(3) of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011, Amendment 2013 (No 2).

### 31 Measuring transformer burden and compensation requirements

- (1) An **ATH** may **certify** a **metering installation** for a **point of connection** to the **grid** that includes **error compensation** factors as an alternative to the use of burden resistors, only if the **ATH** is satisfied the **error compensation** factors will provide a more accurate result than the use of burden resistors.
- (2) A **metering equipment provider** must ensure that a change to, or addition of, a **measuring transformer** burden or **compensation factor** related to a **measuring transformer**, in a **metering installation** for which it is responsible, is only carried out by:
  - (a) the **ATH** who most recently **certified** the **metering installation**; or
  - (b) if the **metering installation** is for a **point of connection** to the **grid**, a suitably qualified person approved by both—
    - (i) the **metering equipment provider** responsible for the **metering installation**; and
    - (ii) the **ATH** who most recently **certified** the **metering installation**.
- (3) An **ATH** must, before it may add or change any burden or **compensation factor** detailed in the design report referred to in clause 2,—
  - (a) obtain the approval of the **metering equipment provider** responsible for the **metering installation**, which may be withheld in the **metering equipment provider's** absolute discretion; and
  - (b) if it obtains the approval referred to in paragraph (a), record in the **metering records** the reason for the proposed addition or change.
- (4) A **metering equipment provider** must, before it may approve the addition of, or change to, the burden or **compensation factor** of a **measuring transformer** in a **metering installation** for which it is responsible, consult with the **ATH** who carried out the most recent **certification** of the **metering installation**.

- (5) If the **metering equipment provider** approves the addition of, or change to, the burden or **compensation factor** under subclause (4), it must ensure that the **metering installation**, other than a **metering installation** for a **point of connection** to the **grid**, is **recertified** by an **ATH** for the addition of or change to the burden or **compensation factor** before the addition or change becomes effective.
- (6) Despite subclause (3)(a), an **ATH** may change the burden on a voltage transformer, without obtaining the approval of the **metering equipment provider**, if the **ATH** confirms in the **certification report** that the difference between the new burden and the burden at the time of the most recent **metering installation certification** is—
- (a) less than or equal to one thirtieth of the rating, in VA, of the voltage transformer if the voltage transformer is rated at less than 30 VA; or
  - (b) no greater than 1 VA, if the voltage transformer is rated at equal to or greater than 30 VA.
- (7) An **ATH** must, before it **certifies** a **measuring transformer**, if the in-service burden is less than the lowest burden test point specified in a standard set out in Table 5 of Schedule 10.1,—
- (a) install burdening resistors to increase the in-service burden to be equal to or greater than the lowest test point specified in the standard; or
  - (b) confirm that—
    - (i) a **class A ATH** has confirmed by **calibration** that the accuracy of the **measuring transformer** will not be adversely affected by the in-service burden being less than the lowest burden test point specified in the standard; or
    - (ii) the **measuring transformer's** manufacturer has confirmed that the accuracy of the **metering transformer** will not be adversely affected by the in-service burden being less than the lowest burden test point specified in the standard.

Clause 31(7): substituted, on 29 August 2013, by clause 41 of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011, Amendment 2013 (No 2).

Clause 31(7)(b): amended, on 15 May 2014, by clause 19 of the Electricity Industry Participation (Minor Code Amendments) Code Amendment 2014.

Clause 31(7)(b): substituted, on 19 December 2014, by clause 22 of the Electricity Industry Participation Code Amendment (Minor Code Amendments) (No 3) 2014.

### **32 Alternative certification requirements for metering installation incorporating measuring transformer**

- (1) An **ATH** may, if it cannot comply with the requirements of clause 2 of Schedule 10.8 due solely to its inability to obtain physical access to test an installed **measuring transformer** in a **metering installation**, **certify** the **metering installation** for a period not exceeding 24 months, if—
- (a) the **measuring transformer** has not previously been **certified** under this clause; and
  - (b) the **ATH** is satisfied, having made due enquiry, that the **metering installation** will comply with the applicable accuracy requirements as set out in Table 1 of Schedule 10.1; and
  - (c) the **ATH** has advised the **metering equipment provider** responsible for the

- metering installation** that this clause applies; and
- (d) the **metering equipment provider** has updated the **metering installation's certification** in the **registry**.
- (2) The **metering equipment provider** must, if a **metering installation** for which it is responsible has been **certified** under subclause (1),—
- (a) by no later than 10 **business days** after the date of **certification** of the **metering installation**, advise the **Authority** in the **prescribed form** of—
- (i) all relevant details of the **metering installation**; and
- (ii) the reason or reasons why the **ATH** could not obtain physical access to the **measuring transformer**; and
- (iii) the reason or reasons why the accuracy of the **metering installation** cannot be outside of the applicable accuracy requirements set out in Table 1 of Schedule 10.1; and
- (iv) the **metering installation certification** expiry date; and
- (b) respond, within 5 **business days**, to any requests from the **Authority** for additional information; and
- (c) ensure that all of the details are recorded in the **metering installation certification report**.
- (3) If an **ATH** **certifies** a **metering installation** under subclause (1), the **metering equipment provider** responsible for the **metering installation** must take all steps to ensure that the **metering installation** is **certified**, before the **metering installation certification** expiry date referred to in subclause (2)(a)(iv), in accordance with all other applicable requirements of this Part.
- (4) If the **Authority** subsequently determines that the **ATH** could have obtained physical access to test an installed **measuring transformer** in the **metering installation**, the **metering installation** is deemed to be defective and the **metering equipment provider** responsible for the **metering installation** must comply with clauses 10.43 to 10.48.
- Clause 32(1)(d), (2) and (4): amended, on 5 October 2017, by clause 191 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### **33 Requirements for metering installation incorporating control device**

- (1A) A **reconciliation participant** that is responsible for a **point of connection** must advise the **metering equipment provider** responsible for the **metering installation** at the **point of connection** if a **control device** in the **metering installation** is to be used by the **reconciliation participant** for any purpose under Part 15 to do either of the following:
- (a) control a load;
- (b) switch **meter** registers.
- (1) A **reconciliation participant** must ensure that a **control device** is **certified** under this Part by an **ATH** before the **reconciliation participant** uses any **raw meter data** that depends on the operation of the **control device**, for any purpose under Part 15.
- (2) An **ATH** must, before it **certifies** a **metering installation** incorporating a **control device** that must be **certified** under subclause (1),—
- (a) determine the **control device certification** expiry date for each **control device** contained in the **metering installation** as being the same as the **metering**

- installation certification** expiry date; and
- (b) record the expiry date, for each **control device**, in the **metering installation certification report**; and
  - (c) if the **metering installation** contains a **control device** that had previously been used in another **metering installation**, ensure that the **control device** has been **certified** in accordance with Schedule 10.8 after it was removed from the other **metering installation**; and
  - (d) ensure that the **metering installation certification report** includes confirmation that—
    - (i) the **control device** complies with any applicable standards listed in Table 5 of Schedule 10.1; and
    - (ii) the **control device** is fit for purpose; and
  - (e) check that the **control device** is—
    - (i) likely to receive control signals, as required under clause 34; and
    - (ii) correctly connected; and
    - (iii) correctly programmed.

Clause 33(1A): inserted, on 29 August 2013, by clause 42(1) of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011, Amendment 2013 (No 2).

Clause 33(1): substituted, on 29 August 2013, by clause 42(2) of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011, Amendment 2013 (No 2).

#### **34 Control device reliability requirements**

- (1) An **ATH** must, before it **certifies** a **metering installation** incorporating a **control device** that is required to be **certified** under clause 33, determine, in consultation with the relevant **distributor** if appropriate, if the likelihood of the **control device** not receiving control signals would affect the accuracy or completeness of the information for the purposes of Part 15.
- (2) A control signal provider, if it is a **participant**, must respond in a timely manner to any requests from the **ATH** referred to in subclause (1).
- (3) The **ATH** must, if it determines under subclause (1) that the likelihood of the **control device** not receiving control signals would affect the accuracy or completeness of the information for the purposes of Part 15, advise the **metering equipment provider** responsible for the **metering installation** of its determination, including all relevant details, within 3 **business days** of making its determination.
- (4) If subclause (3) applies—
  - (a) the **ATH** may **certify** the **metering installation** excluding the **control device**; and
  - (b) the **ATH** must not **certify** the **control device**.
- (5) The **metering equipment provider** must, as soon as reasonably practicable, and at least within 3 **business days** after being advised under subclause (3), advise the following parties of the **ATH's** determination, including all relevant details:
  - (a) the **reconciliation participant** for the **point of connection** for the **metering installation**; and
  - (b) the control signal provider.

Clause 34(4)(a): substituted, on 29 August 2013, by clause 43 of the Electricity Industry Participation (Metering



Arrangements) Code Amendment 2011, Amendment 2013 (No 2).

**35 Control device bridged out**

- (1) A **participant** must, within 10 **business days** of bridging out a **control device**, or becoming aware of a **control device** being bridged out, advise the following persons:
  - (a) the **reconciliation participant** for the **point of connection** for the **metering installation**; and
  - (b) the **metering equipment provider** responsible for the **metering installation** incorporating the **control device**.
- (2) A **metering installation** incorporating a **control device** referred to in subclause (1) is defective for the purposes of clause 10.43 if it is used for the purposes of providing information for the purposes of Part 15.

**36 Requirements for metering installation incorporating data storage device**

- (1) A **metering equipment provider** must ensure that each **data storage device** incorporated in a **metering installation** for which it is responsible, is **certified** in accordance with this Part.
- (2) An **ATH** must, before it **certifies** a **metering installation** incorporating a **data storage device** that had previously been used in another **metering installation**, ensure that the **data storage device** has been **recalibrated** since it was removed from the previous **metering installation**, by—
  - (a) an **approved calibration laboratory**; or
  - (b) an **approved test laboratory**; or
  - (c) an **ATH**.
- (3) An **ATH** must, before it **certifies** a **metering installation** incorporating a **data storage device** (including a **metering installation** incorporating both a **meter** and a **data storage device**), record in the **metering installation certification report**, the maximum **interrogation** cycle for the **data storage device**.
- (4) The maximum **interrogation** cycle for a **metering installation** incorporating a **data storage device** is the shortest of the following periods:
  - (a) the period of inherent data loss protection for the **metering installation**; and
  - (b) the period of memory availability given the **data storage device** configuration; and
  - (c) the longest period in which the accumulated drift of a **data storage device** clock is expected to remain in compliance with the maximum time error set out in Table 1 of clause 2 of Schedule 15.2 for the category of the **metering installation**.

Clause 36(3): amended, on 29 August 2013, by clause 44 of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011, Amendment 2013 (No 2).

Clause 36(3): amended, on 1 February 2016, by clause 35 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

**37 Data storage device certification expiry date**

- (1) An **ATH** must, before it **certifies** a **metering installation** incorporating a **data storage device**—
  - (a) determine, in accordance with this clause, the **data storage device certification** expiry date for each **data storage device** contained in the **metering installation**;

- and
- (b) record the expiry date in the **metering installation certification report**.
- (2) The **data storage device certification expiry date** must—
  - (a) for a **data storage device** that is integral to a **meter**, be no later than the **meter certification** expiry date; or
  - (b) for a **data storage device** that is not integral to a **meter**, be no later than the earlier of—
    - (i) the date falling the number of days equivalent to the **data storage device certification** validity period specified in the **data storage device certification report**, after the **commissioning** date; and
    - (ii) the **meter certification** expiry date.
- (3) The **ATH** must record the **data storage device certification** expiry date for a **data storage device** in a **metering installation** in—
  - (a) the **certification report** for the **metering installation**; and
  - (b) the **certification report** for the **data storage device**.

**38 Requirements for certification of metering installation incorporating data storage device**

- (1) An **ATH** must, before it **certifies** a **metering installation**, ensure that each **data storage device** in the **metering installation**—
  - (a) is installed so that onsite **interrogation** is possible without the need to interfere with seals; and
  - (b) has a dedicated power supply unless the **data storage device** is integrated with another **metering component**.
- (2) An **ATH** must, before it **certifies** a **metering installation**,—
  - (a) ensure that each **data storage device** in the **metering installation**—
    - (i) is compatible with each other **metering component** of the **metering installation**; and
    - (ii) is suitable for the electrical and environmental site conditions in which it is installed; and
    - (iii) has been **certified** under Schedule 10.8; and
    - (iv) has appropriate electrical separation between all of its outputs and inputs, and all of its outputs and inputs are rated for purpose; and (v) has no outputs that will interfere with the operation of the **metering installation**; and
    - (vi) records periods of data identifiable or deducible by both date and time on **interrogation**; and
  - (b) check and confirm in the **metering installation certification report** that each **data storage device** in the **metering installation**—
    - (i) has memory capacity and functionality that is suitable for the proposed functions of the **data storage device** specified in the design report for the **metering installation**; and
    - (ii) has availability of memory for a period that is suitable for the proposed functions as set out in the design report for the **metering installation**, and

for a minimum continuous period of 15 days.

- (3) An **ATH** must, before it **certifies a metering installation** incorporating a **data storage device**, document in the **metering records**—
- (a) any regular maintenance required for the **data storage device** in accordance with the manufacturer's recommendations; and
  - (b) any maintenance that has been carried out on the **data storage device** (for example battery monitoring and replacement).

Heading: amended, on 1 February 2016, by clause 36 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

Clause 38(2)(a)(iv): replaced, on 5 October 2017, by clause 192 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### **39 Changes to data storage device software, ROM, or firmware**

- (1) A **metering equipment provider** must, if it proposes to change the **software**, ROM, or firmware of a **data storage device** installed in a **metering installation** for which it is responsible, ensure that, before the change is carried out, an **approved test laboratory**—
- (a) tests and confirms that the integrity of the measurement and logging of the **data storage device** would be unaffected by the proposed change; and
  - (b) documents the methodology and conditions necessary to implement the proposed change; and
  - (c) advises the **ATH** that **certified the metering installation** of any change that would, or would be likely to, affect the accuracy of the **data storage device**.
- (2) A **metering equipment provider** must, when implementing a proposed change described in subclause (1),—
- (a) carry out the change in accordance with the documented methodology and conditions referred to in subclause (1)(b); and
  - (b) keep a list of **data storage devices** to which the change was made; and
  - (c) update the **metering records** for each **metering installation** referred to in subclause (1) with details of the change and the methodology referred to in subclause (1)(b).

### **40 Communication equipment requirements**

A **metering equipment provider** must ensure that the use of its **communication equipment** complies with the compatibility and connection requirements of any communication network operator to whose communication network the **metering equipment provider** has **communication equipment** connected.

### **41 Certification stickers**

- (1) An **ATH** must, except as provided for in clause 16(6) and subclause (4), if it has **certified a metering installation** under this Part, confirm the **certification** by attaching a **metering installation certification sticker** as physically close as practicable to (including, if practicable, on) the **meter** while maintaining reasonable visibility of the **certification sticker** and the **meter**.
- (2) An **ATH** attaching a **metering installation certification sticker** must ensure that it shows—

- (a) the name of the **ATH** who **certified** the **metering installation**; and
  - (b) the most recent **certification date** of the **metering installation**; and
  - (c) the **metering installation** category for which the **metering installation** has been **certified**; and
  - (d) the **ICP identifier** for the **metering installation**; and
  - (e) the **certification** number for the **metering installation**; and
  - (f) any other information that the **Authority** may, from time to time, **notify** giving reasonable notice.
- (3) An **ATH** must, when **certifying** a **metering installation** that includes a **metering component** that does not have a **certification sticker** attached—
- (a) obtain the **metering component certification sticker** required under clause 8 of Schedule 10.8; and
  - (b) attach it next to the **metering installation certification sticker**.
- (4) Despite subclauses (1) and (3)(b), the **ATH** must, if attaching a **metering installation certification sticker** as required under subclause (1) is not practicable,—
- (a) devise and use an alternative means of documenting, providing, and maintaining information in a manner at least equivalent in its effect to that required under subclause (1); and
  - (b) keep any **metering component certification sticker** with the information referred to in paragraph (a).

## 42 Enclosures

An **ATH** must, before it **certifies** a **metering installation**, ensure that, if a **metering component** in the **metering installation** is housed in a separate enclosure from the **meter** enclosure, the enclosure is—

- (a) appropriate to the environment in which it is located; and
- (b) has a warning label attached stating that the enclosure houses a **metering component**.

### *Certification of metering components*

## 43 Metering components must be certified

- (1) An **ATH** must, before it **certifies** a **metering installation**, ensure that each **metering component** that is required to be **certified** under this Part and which is in the **metering installation**—
- (a) is **certified** by an **ATH** in accordance with this Part; and
  - (b) since **certification**, has been appropriately stored and not used.
- (2) Despite subclause (1) and clause 26(2), an **ATH** may **certify** a **category 1 metering installation** that contains a **meter** which has been removed from another **category 1 metering installation** (the "previous **metering installation**") if the **ATH**—
- (a) is satisfied that external factors have not affected the accuracy of the **meter**; and

- (b) has confirmed that it has been no more than 12 months since the **meter** was installed in the previous **metering installation**; and
- (c) has confirmed that the **meter** was **calibrated** or **recalibrated** before being installed in the previous **metering installation** and after being removed from any other **metering installation** in which the **meter** was previously installed.

Clause 43(1): amended, on 1 February 2016, by clause 37(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

Clause 43(2): substituted, on 1 February 2016, by clause 37(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

### *Inspection requirements*

#### **44 General inspection requirements**

- (1) An **ATH** must, when carrying out an inspection of a **metering installation**,—
  - (a) check and confirm that the **data storage device** in the **metering installation** operates in accordance with the requirements of this Part; and
  - (b) check and confirm that the expected remaining lifetime of each battery in the **metering installation** will be reasonably likely to meet or exceed the **metering installation certification** expiry date; and
  - (c) ensure that no modifications under clause 19 have been made to the **metering installation** without the change having been documented and **certification** requirements satisfied; and
  - (d) visually inspect all seals, enclosures, **metering components**, and wiring of the **metering installation** for evidence of damage, deterioration, or tampering; and
  - (e) ensure that the **metering installation** and its **metering components** carry appropriate **certification stickers** in accordance with clause 41; and
  - (f) in the case of a **category 1 metering installation** incorporating a **data storage device**, check and confirm there is no difference between the volume of **electricity** recorded by the master accumulation register of a **data storage device**, and the sum of the **meter** registers.
- (2) An **ATH** must, for each inspection of a **metering installation** that it carries out, prepare an inspection report that details—
  - (a) the checks that were carried out; and
  - (b) the results of the checks; and
  - (c) the **metering installation certification** expiry date; and
  - (d) the serial numbers of each **metering component** in the **metering installation**; and
  - (e) any instances of non-compliance with this Part, and the actions taken to remedy such a breach; and
  - (f) the name and signature of the person who carried out the inspection and the date on which it was signed.
- (3) The **ATH** must, within 10 **business days** of carrying out the inspection, provide the inspection report to the **metering equipment provider** who is responsible for the **metering installation**.
- (4) If an **ATH** has not performed an inspection of a **metering installation**, other than an

**interim certified metering installation**, within the specified timeframe under clauses 45(1) or 46(1), the **certification** of the **metering installation** is automatically cancelled on the date by which the **metering installation** was required to have been inspected.

- (5) A **metering equipment provider** must, within 20 **business days** of receiving the inspection report,—
- (a) undertake a comparison of—
    - (i) the information recorded under subclauses (2)(c) and (d); and
    - (ii) the information in its own records; and
  - (b) investigate and correct any discrepancies found under paragraph (a); and
  - (c) update the **registry** with the relevant changes.

Clause 44(5)(c): amended, on 5 October 2017, by clause 193 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

#### **45 Category 1 metering installation inspection requirements**

- (1) A **metering equipment provider** must ensure that—
- (a) each **category 1 metering installation** for which it is responsible, other than an **interim certified metering installation**, has been inspected by an **ATH** within the period set out in Table 1 of Schedule 10.1 starting from the date of the **metering installation's** most recent **certification**; or
  - (b) for each 12 month period commencing 1 January and ending 31 December, a sample, selected under subclause (2), of the **category 1 metering installations** for which it is responsible has been inspected by an **ATH** within the period set out in Table 1 of Schedule 10.1 starting from the date of the earliest **certification** date of a **metering installation** in the group.
- (2) A **metering equipment provider** must, for the purposes of subclause (1)(b), select a sample by—
- (a) producing a list of all **ICP identifiers** of each **category 1 metering installation** for which it is responsible, other than **interim certified metering installations**; and
  - (b) removing from the list of **ICP identifiers**, any **ICP identifier** for a **metering installation** that has been **certified** or inspected in the 84 months prior to the date on which the list was produced; and
  - (c) identifying the applicable required minimum sample size set out in Table 8 of Schedule 10.1, based on the number of **metering installations** identified in the list of **ICP identifiers** in produced in accordance with paragraphs (a) and (b); and
  - (d) randomly selecting a sample, of the size required under paragraph (c), from the list produced in accordance with paragraphs (a) and (b).
- (3) A **metering equipment provider** must, before it carries out inspections under subclause (1)(b),—
- (a) submit a documented process for randomly selecting a sample to the **Authority** at least 2 months before the first date on which it proposes to carry out the inspections; and
  - (b) provide promptly any other information or documentation the **Authority** may reasonably request.
- (4) The **Authority** must, within 2 months of receiving the documented process under

- subclause (3), advise the **metering equipment provider** that the documented process—
- (a) has been approved; or
  - (b) has not been approved, providing reasons.
- (5) A **metering equipment provider** must not inspect a sample under this clause unless the **Authority** has approved the documented process.
- (6) A **metering equipment provider** must, for each inspection of a **category 1 metering installation** conducted under subclause (1)(b), keep records that detail—
- (a) any defects identified that have affected the accuracy or integrity of the **raw meter data** recorded by the **metering installation**; and
  - (b) any discrepancies identified under clause 44(5)(b); and
  - (c) relevant characteristics, sufficient to enable reporting that identifies any correlations or relationships between inaccuracy and characteristics (for example the **meter** make, model, and **network** area, for each **metering installation**); and
  - (d) the procedure used, and the lists generated, to select a sample under subclause (2).
- (7) A **metering equipment provider** must, if it believes that a **metering installation** that an **ATH** has inspected under this clause is or could be outside the applicable accuracy tolerances set out in Table 1 of Schedule 10.1, defective, or not fit for purpose,—
- (a) comply with clause 10.43;
  - (b) arrange for an **ATH** to **recertify** the **metering installation** under this Schedule, if the **metering installation** is found to be—
    - (i) outside the applicable accuracy tolerances set out in Table 1 of Schedule 10.1; or
    - (ii) defective; or
    - (iii) not fit for purpose.
- (8) A **metering equipment provider** must, by 1 April in each year, provide to the **Authority** a report in the **prescribed form** that states whether the **metering equipment provider** has, for the previous 1 January to 31 December period, arranged for an **ATH** to inspect each **category 1 metering installation** for which it is responsible—
- (a) under subclause (1)(a), in which case the report must also include, for the period—
    - (i) a list showing the **ICP identifier** for each **ICP** which has a **metering installation** that was due for inspection, the dates by which the **metering installation** was due for inspection, and the date on which it was inspected; and
    - (ii) a summary of the instances of non-compliance of each **category 1 metering installation** inspected; and
    - (iii) the detailed records required under subclauses (6)(a) and (6)(b); or
  - (b) under subclause (1)(b), in which case the report must also include, for the period—
    - (i) the number of **metering installations** identified under subclause (2)(a) to (2)(c); and
    - (ii) a summary of the instances of non-compliance of each **category 1 metering installation** inspected; and
    - (iii) the detailed records required under subclauses (6)(a) and (6)(b).

- (9) The **Authority** may, if it considers that the report provided under subclause (8) indicates that there is a statistically significant number of **metering installations** in the sample which are outside the applicable accuracy tolerances set out in Table 1 of Schedule 10.1, defective, or not fit for purpose, despite subclause (1)(b), advise the **metering equipment provider** that it must select another sample in accordance with subclause (2) and comply with the applicable requirements of this clause in respect of the sample.

- (10) The **metering equipment provider** must select the additional sample under subclause (9), carry out the required inspections and report to the **Authority** under subclause (8), within 40 **business days** of being advised by the **Authority** under subclause (9).

Clause 45(2)(b): amended, on 1 February 2016, by clause 38(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

Clause 45(2)(c): amended, on 1 February 2016, by clause 38(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

Clause 45(2)(d): amended, on 1 February 2016, by clause 38(3) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

Clause 45(10): amended, on 29 August 2013, by clause 45 of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011, Amendment 2013 (No 2).

#### **46 Category 2 metering installation or higher category of metering installation inspection requirements**

- (1) A **metering equipment provider** must ensure that each **category 2 metering installation**, or higher category of **metering installation**, for which it is responsible is inspected by an **ATH** at least once within the applicable period set out in Table 1 of Schedule 10.1 starting from the date of the **metering installation's** most recent **certification**.
- (2) An **ATH** must, when conducting an inspection of a **category 2 metering installation**, or higher category of **metering installation**, and in addition to complying with clause 44, conduct the following checks:
- (a) a visual inspection of each **metering component** in the **metering installation** for damage, tampering, or defect; and
  - (b) if the current transformer can be safely accessed, check the position of the current transformer tap to ensure it is still appropriate for the expected maximum current for the **metering installation**; and
  - (c) check for the presence of appropriate voltages at the **metering installation**; and
  - (d) check the voltage circuit alarms and fault indicators.

#### *Sealing*

#### **47 Sealing requirements**

- (1) For the purposes of this clause and clause 48, a reference to something being sealed includes being contained in a sealed enclosure.
- (2) An **ATH** must, before it **certifies a metering installation**, ensure that each **metering component** in the **metering installation** that could reasonably be expected to affect the accuracy or reliability of the **metering installation**, is sealed.
- (3) An **ATH** must, before leaving a **metering installation** unattended, ensure that each part and connection of a **data storage device** that is contained in, or attached to, the



**metering installation** is sealed.

- (4) Subclause (3) does not apply to a port for on-site reading that is not capable of carrying out any other function.
- (5) An **ATH** must, before it **certifies** a **metering installation**, ensure that the main switch cover is sealed if the main switch—
  - (a) is on the supply side of the **metering installation**; and
  - (b) has provision for sealing.
- (6) An **ATH** must, when applying a seal to a **metering component** in an enclosure, attach a label in a prominent position inside the enclosure, warning—
  - (a) of the presence of a sealed **metering component** in the enclosure; and
  - (b) that care must be taken not to disturb the connections to the **metering component**.
- (7) An **ATH** must use a sealing system that enables the following information to be determined:
  - (a) the **ATH** who affixed the seal; and
  - (b) the person (or the sealing tool) who applied the seal; and
  - (c) when the seal was applied.

#### **48 Removal or breakage of seals**

- (1) Despite clause 10.12, a **participant** who removes or breaks a seal without authorisation of the **metering equipment provider** responsible for the **metering installation** must, within 10 **business days** of removing or breaking the seal,—
  - (a) advise the **metering equipment provider** of—
    - (i) the removal or breakage; and
    - (ii) the reason for the removal or breakage; and
  - (b) reimburse the **metering equipment provider** for the cost of reinstating the seal and **recertification** if required by the **metering equipment provider**.
- (2) A **participant** who is required under subclause (1)(b) to reimburse the cost of reinstating and **recertifying** a seal, must do so within 10 **business days** of the **metering equipment provider** advising the **participant** of the cost.
- (3) A **participant** who becomes aware that another person has removed or broken a seal, must, within 3 **business days** of becoming aware, advise the **metering equipment provider** who is responsible for the **metering installation**.
- (4) A **metering equipment provider** must, if it is advised under subclauses (1) or (3)—
  - (a) use all reasonable endeavours to ascertain—
    - (i) who removed or broke the seal; and
    - (ii) the reason for the removal or breakage; and
  - (b) arrange for an **ATH** to carry out, as soon as practicable, an inspection of the removal or breakage, and to determine any work required to remedy the removal or breakage.
- (5) A **metering equipment provider** must make the arrangements required under subclause (4)(b) within—
  - (a) 3 **business days** of being advised under subclauses (1) or (3), if the **metering installation** is category 3 or higher; or

- (b) 10 **business days** of being advised under subclauses (1) or (3), if the **metering installation** is a **category 2 metering installation**; or
  - (c) 20 **business days** of being advised under subclauses (1) or (3), if the **metering installation** is a **category 1 metering installation**.
- (6) An **ATH** must, when investigating an unauthorised removal or breakage under subclause (4)(b), assess the accuracy and continued integrity of the **metering installation** and—
  - (a) if, in its opinion, the accuracy and continued integrity is unaffected, replace the removed or broken seals; or
  - (b) if, in its opinion, the accuracy and continued integrity is affected, replace the removed or broken seal and advise the **metering equipment provider** under clause 10.43.
- (7) If subclause (6)(b) applies, the **certification** of the **metering installation** is automatically cancelled from the date on which a **participant** became aware, or should have become aware, of the removed or broken seal.

## Schedule 10.8 Metering component requirements

cl 10.20, 10.38 and 10.42

### *Meters*

#### **1 Meter certification requirements**

- (1) An **ATH** must, before it **certifies** a **meter**, ensure that—
- (a) an **approved test laboratory** has—
    - (i) conducted **type-testing** that the **ATH** considers appropriate for the model and version of **meter**; and
    - (ii) produced a **type-test** certificate that—
      - (A) confirms the **meter's** technical characteristics; and
      - (B) confirms the range of environmental conditions within which the **meter** has been proven accurate and reliable; and
      - (C) confirms that the **meter** performs the functions for which it was designed; and
      - (D) confirms that the **meter** complies with the requirements of this Part; and
      - (E) records the tests undertaken by the **approved test laboratory** and the reasons why the **ATH** considers that they are appropriate; and
  - (b) the **meter** has a current **calibration report** issued by an **approved calibration laboratory** or an **ATH** approved to carry out **calibration** under Schedule 10.3; and
  - (c) the **meter calibration report**—
    - (i) confirms that the **meter** complies with the standards listed in Table 5 of Schedule 10.1; and
    - (ii) records any tests the **ATH** has performed to confirm compliance under subparagraph (i) and the results of those tests; and
    - (iii) confirms that the **meter** has passed the tests; and
    - (iv) records any recommendations on **error compensation**; and
    - (v) includes any manufacturer's **calibration** test reports; and
  - (d) it produces a **meter certification report** that includes—
    - (i) the date on which it **certified** the **meter**; and
    - (ii) the **certification** validity period for the **meter** for each category of **metering installation** that the **meter** may be used in; and
    - (iii) the maintenance requirements for the **meter**; and
    - (iv) the **meter calibration report**; and
    - (v) whether the **certification** was based on batch test certificates; and
    - (vi) if the **certification** was based on batch test certificates, confirmation that the manufacturer's batch testing facility is, in the **ATH's** opinion, of an acceptable standard; and
  - (e) the percentage values of current set out in Table 6 or Table 7 of Schedule 10.1, as applicable, are relative to the **meter's** base or rated current ( $I_b$  or  $I_n$ ) as

appropriate, and this current is selected at a level appropriate for the **metering installation** in which the **meter** is to be installed.

- (2) The **certification** validity period referred to in subclause (1)(d)(ii) must not be greater than the maximum **certification** validity period set out in Table 2 of Schedule 10.1 for the relevant class of **meter**.

Clause 1(1)(b): amended, on 19 December 2014, by clause 23(1) of the Electricity Industry Participation Code Amendment (Minor Code Amendments) (No 3) 2014.

Clause 1(1)(c)(ii): amended, on 19 December 2014, by clause 23(2) of the Electricity Industry Participation Code Amendment (Minor Code Amendments) (No 3) 2014.

### *Measuring transformers*

## **2 Measuring transformer certification requirements**

- (1) An **ATH** must, before it **certifies** a **measuring transformer**,—
- (a) ensure, by testing, that a current **calibration report** sets out the **measuring transformer's** errors at a range of primary values at their rated burdens; and
  - (b) that is a multi-tap current transformer, carry out the **calibration** tests and only **certify** the transformer for the ratios that have been **calibrated** if the test is passed; and
  - (c) if the in-service burden is lower than a test point specified in a standard listed in Table 5 of Schedule 10.1, confirm the accuracy of the **measuring transformer** at the in-service burden by—
    - (i) obtaining confirmation of accuracies at the in-service burden from the **measuring transformer's** manufacturer; or
    - (ii) if the primary voltage of the **measuring transformer** is greater than 1kV, a **class A ATH** calibrating the **measuring transformer** at the in-service burden; and
  - (d) determine the **measuring transformer certification** validity period under clause 3(c)(ii).
- (2) An **ATH** must, before it **certifies** an epoxy insulated current transformer, ensure that the **certification** tests allow for, and the **metering installation certification report** shows, the current transformer's age, temperature, and batch.

Clause 2(1)(c): amended, on 29 August 2013, by clause 46 of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011, Amendment 2013 (No 2).

Clause 2(1)(c): substituted, on 19 December 2014, by clause 24 of the Electricity Industry Participation Code Amendment (Minor Code Amendments) (No 3) 2014.

## **3 Measuring transformer certification report**

An **ATH** must, before it **certifies** a **measuring transformer**, ensure that—

- (a) the **measuring transformer** has a current **calibration report** issued by an **approved calibration laboratory** or an **ATH** approved to carry out **calibration** under Schedule 10.3; and
- (b) the **measuring transformer calibration report**—
  - (i) confirms that the **measuring transformer** complies with the standards listed in Table 5 of Schedule 10.1; and
  - (ii) records any tests the **ATH** has performed to confirm compliance under subparagraph (i) and the results of those tests; and

- (iii) confirms that the **measuring transformer** has passed the tests; and
- (iv) records any recommendations made by the **ATH** on **error compensation**; and
- (v) includes any manufacturer's **calibration** test reports; and
- (c) it produces a **measuring transformer certification report** that includes—
  - (i) the date on which it **certified** the **measuring transformer**; and
  - (ii) the **certification** validity period for the **measuring transformer** which must be no more than 120 months; and
  - (iii) the **measuring transformer calibration report**; and
  - (iv) whether the **certification** was based on batch test certificates; and
  - (v) if the **certification** was based on batch test certificates, confirmation that the manufacturer's batch testing facility is, in the **ATH's** opinion, of an acceptable standard; and
- (d) it confirms that it has inspected the manufacturer's test certificates, and carried out any additional tests it considers necessary, to satisfy itself that the **measuring transformer** meets the accuracy requirements of this Part.

Clause 3(a): amended, on 19 December 2014, by clause 25(1) of the Electricity Industry Participation Code Amendment (Minor Code Amendments) (No 3) 2014.

Clause 3(b)(ii): amended, on 19 December 2014, by clause 25(2) of the Electricity Industry Participation Code Amendment (Minor Code Amendments) (No 3) 2014.

#### *Control devices*

### **4 Control device certification report**

- (1) An **ATH** must, before it **certifies** a new **control device**, produce a **certification report** that—
  - (a) confirms that the **control device** complies with the applicable standards listed in Table 5 of Schedule 10.1; and
  - (b) includes the details and results of any test that the **ATH** has carried out to confirm compliance under paragraph (a); and
  - (c) confirms that the **control device** has passed such tests.
- (2) An **ATH** must, before it **certifies** an existing installed **control device**, produce a **certification report** that—
  - (a) confirms that the **control device** is fit for purpose; and
  - (b) confirms the **control device certification** validity period that the **ATH** considers appropriate, which must be no more than 180 months.

Clause 4: substituted, on 29 August 2013, by clause 47 of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011, Amendment 2013 (No 2).

Clause 4(1)(b): amended, on 15 May 2014, by clause 20 of the Electricity Industry Participation (Minor Code Amendments) Code Amendment 2014.

#### *Data storage devices*

### **5 Data storage device certification requirements**

- (1) An **ATH** must, before it **certifies** a **data storage device** used for storing information that is used for the purposes of Part 15, ensure that—
  - (a) an **approved test laboratory** has—

- (i) conducted **type-testing** that the **ATH** considers appropriate for the model and version of **data storage device**; and
- (ii) produced a **type-test** certificate that—
  - (A) confirms the **data storage device's** technical characteristics; and
  - (B) confirms the range of environmental conditions within which the **data storage device** has been proven accurate and reliable; and
  - (C) confirms that the **data storage device** performs the functions for which it was designed; and
  - (D) confirms that the **data storage device** complies with this Part; and
  - (E) records the tests undertaken by the **approved test laboratory** to confirm compliance under sub-subparagraph (D) and the reasons why the **ATH** considers that they are appropriate; and
- (b) it produces a **certification report** that—
  - (i) confirms the **data storage device** complies with the applicable standards listed in Table 5 of Schedule 10.1; and
  - (ii) records the tests the **ATH** has performed to confirm compliance with subparagraph (i) and the results of those tests; and
  - (iii) confirms that the **data storage device** has passed the tests; and
  - (iv) includes the date on which it **certified** the **data storage device**; and
  - (v) includes the **certification** validity period for the **data storage device** for each category of **metering installation** in which the **data storage device** may be used; and
  - (vi) records the maintenance requirements for the **data storage device**; and
  - (vii) confirms that each period of data is identifiable or deducible by both date and time on **interrogation**; and
  - (viii) confirms that the time and date of the following event conditions are recorded in an **event log**:
    - (A) a loss of the power supply to the **data storage device**; and
    - (B) critical internal alarms such as memory integrity checking, battery low, battery failed, and tampering; and
    - (C) phase failure to the **meter**, if the **data storage device** is integral to the **meter**; and
    - (D) any **software** configuration changes; and
    - (E) results of time setting comparisons and corrections; and
    - (F) the transition from, and to, **New Zealand daylight time**, if the **data storage device** operates in **New Zealand daylight time**; and
  - (ix) confirms that the **data storage device** has the available memory capacity required by the **type-test**; and
  - (x) confirms that the **data storage device** has the functionality—
    - (A) to validate instructions from an **interrogation** system; and
    - (B) for time comparisons and corrections, in response to a valid instruction; and
  - (xi) confirms that all information logged is referenced to **New Zealand Standard Time** or **New Zealand daylight time**; and

- (xii) confirms that the **data storage device** has data loss protection providing a continued clock and memory operation for a continuous period of at least 15 days when the power supply to the **data storage device** is lost.
- (2) The **data storage device certification** validity period referred to in subclause (1)(b)(v) must be—
  - (a) no more than 180 months, if the **data storage device** is a discrete **metering component**; or
  - (b) the same as the **meter certification** validity period, if the **data storage device** is integral to the **meter**.
- (3) Despite subclause (1)(b)(ix), the memory capacity of the **data storage device** must not be less than 15 days.
- (4) For the purposes of subclause (1), a new version of the **data storage device** includes any change to the specification, hardware, or metrology **software** of the **data storage device**.

### *Wiring*

## **6 Wiring**

- (1) An **ATH** must, before it **certifies a metering installation**, ensure that all wiring in the **metering installation** is—
  - (a) suitable for the environment in which the **metering installation** is located; and
  - (b) fit for purpose; and
  - (c) securely fastened; and
  - (d) compliant with all applicable requirements and enactments.
- (2) An **ATH** must, before it **certifies a metering installation**, ensure that the wiring between **metering components** in the **metering installation**—
  - (a) is run as directly as practicable; and
  - (b) is appropriately sized and protected; and
  - (c) does not, to the extent practicable, include intermediate joints for any **measuring transformer** circuits; and
  - (d) subject to subclause (4), includes conductors that are clearly and permanently identified, by the use of any 1 or more of the following:
    - (i) colour coding;
    - (ii) marker ferrules;
    - (iii) conductor numbering.
- (3) For the purposes of subclause (2)(c), if it is not practicable to exclude intermediate joints for any **measuring transformer** circuits, the **ATH** must ensure that the intermediate joints are—
  - (a) sealed or in a sealed enclosure; and
  - (b) located in a secure position; and
  - (c) recorded in the **metering installation certification report**.
- (4) The **ATH** must, if the wiring is in a **metering installation** and does not comply with subclause (2)(d)—
  - (a) ensure, by testing, that the wiring has been correctly installed; and

- (b) record the nature of the test or the tests, and the results of the test or tests, in the **metering installation certification report**.

*Fuses and circuit breakers*

**7 Fuses and circuit breakers**

An **ATH** must, before it **certifies** a **metering installation**, ensure that all fuses and **circuit breakers** that are part of the **metering installation** are—

- (a) appropriately rated for the electrical duty and discrimination required; and
- (b) clearly labelled and—
  - (i) sealed; or
  - (ii) located in sealed enclosures.

*Certification stickers*

**8 Metering component certification stickers**

- (1) An **ATH** must, when **certifying** a **metering component** under this Part, confirm the **certification** by attaching a **metering component certification sticker** to the **metering component** or, if not practicable, provide the sticker with the **metering component**.
- (2) An **ATH** referred to in subclause (1) must ensure that a **metering component certification sticker** shows—
  - (a) the name of the **metering component** owner (if available); and
  - (b) if the **metering component** is a **meter** or a **measuring transformer**, the name of the **ATH** or the **approved calibration laboratory** who **calibrated** the **metering component**; and
  - (c) the name of the **ATH** who **certified** the **metering component**; and
  - (d) the date on which the **metering component** was **certified**; and
  - (e) the initials or other unique identifier of the person who carried out the **certification** of the **metering component**.
- (3) An **ATH** must ensure that a **certification sticker** is—
  - (a) made of weather-proof material; and
  - (b) permanently attached; and
  - (c) filled out using permanent markings.

*Onsite calibration and certification*

**9 Onsite calibration and certification**

- (1) A **certifying ATH** may only **calibrate** a **metering component** onsite—
  - (a) in the **metering component's** normal working environment; and
  - (b) by—
    - (i) measuring the influence of all onsite variables and including their estimated effects in the **uncertainty** calculation; and
    - (ii) ensuring that—
      - (A) the effects of any departures from the **reference conditions** specified in the relevant standards listed in Table 5 of Schedule 10.1 can



- accurately and reliably be calculated; and
- (B) the **metering installation**, in which the **metering component** is incorporated, is within the applicable accuracy tolerances set out in Table 1 of Schedule 10.1 after taking into account all known influences including temperature and temperature co-efficient measurements.
- (2) If an **ATH** **calibrates** a **metering component** onsite using manual methods, computers, or automated equipment for the capture, processing, manipulation, recording, reporting, storage, or retrieval of **calibration** data, it must ensure that its computer **software**—
- (a) is documented in the **ATH's** procedures; and
  - (b) can manipulate the variables that affect the performance of the **metering component** in a manner that will produce results that would correctly indicate the level of compliance of the **metering component** with this Code.
- (3) An **ATH** who **certifies** a **metering component** onsite must include in the **metering component certification report** confirmation that—
- (a) it has calculated the **uncertainty** of measurement taking into account all environmental factors for both the **metering component** being **calibrated** and the **working standards**; and
  - (b) the calculation of the **uncertainty** referred to in paragraph (a) comprises all **uncertainties** in the chain of **calibration**; and
  - (c) the **ATH** has used a **calibration** procedure to **calibrate** the **metering component** that—
    - (i) was included in the **ATH's** most recent **audit**; and
    - (ii) is appropriate for onsite **calibration**; and
    - (iii) includes the methodologies, calculations, and assumptions used by the **ATH** in determining the **uncertainty**; and
  - (d) the **ATH** believes the methodologies, calculations, and assumptions are appropriate, including reasons for that belief.

# Electricity Industry Participation Code 2010

## Part 11 Registry information management

### Contents

11.1	Contents of this Part
11.2	Requirement to provide complete and accurate information
11.2A	Use of contractors
11.3	Certain points of connection must have ICP identifiers
11.4	Distributors must create ICP identifiers for ICPs
11.5	Participants may request that distributors create ICP identifiers for ICPs
11.6	ICP status
11.7	Provision of ICP information
11.8	Provision of and changes to ICP information and NSP information by participants
11.8A	Metering equipment providers to provide registry metering records to registry manager
11.8B	Metering equipment providers to arrange for regular audits
11.9	<i>[Revoked]</i>
11.10	Distributors to arrange for regular audits
11.11	Authority and participant requested audits
11.12	<i>[Revoked]</i>
11.13	<i>[Revoked]</i>
11.14	Process for maintaining shared unmetered load
11.15	Process for customer or embedded generator switching
11.15AA	Trader may elect to have switch saving protection
11.15AB	Switch saving protection
11.15AC	Trader may communicate with customers for certain purposes
11.15AD	Cancellation of switch saving protection
11.15A	Application of Schedule 11.4
11.15B	Trader contracts with customers to permit assignment by Authority
11.15C	Process for trader events of default
11.16	Parties to ensure arrangements for line function services
11.17	Connecting ICP that is not also NSP
11.18	Trader responsibility for ICP
11.18A	Registry manager to advise metering equipment providers
11.18B	Metering equipment provider responsibility for metering installation for ICP
11.19	Authority to specify timeframes and formats of information
11.20	Registry must be available between 0730 and 1930 each day
11.21	Confirmation of receipt of data
11.22	Registry manager must maintain register of information
11.23	Reports from registry manager
11.24	Registry manager delivers reports to specific participants
11.25	Reports to clearing manager, system operator or reconciliation manager
11.26	Reports to reconciliation manager
11.27	Reports to Authority
11.28	Access to registry

- 11.29 Registry information change
- 11.30 Use of ICP identifier on invoices
- 11.31 Customer and embedded generator queries
- 11.32 Reliance on registry
  - Access by consumers to information about their own electricity consumption*
  - 11.32A Retailers must give information about consumer electricity consumption
  - 11.32B Requests for information
  - 11.32C Retailers must give written notice to consumers of availability of information
  - 11.32D Information security
  - 11.32E Agents
  - 11.32F Authority to publish procedures for responding to requests for consumption information
  - 11.32G Retailers must provide information about generally available retail tariff plans
- 11.33 *[Expired]*
- 11.34 *[Expired]*
- 11.35 *[Expired]*
- 11.36 *[Expired]*

#### **Schedule 11.1**

#### **Creation and management of ICPs, ICP identifiers and NSPs**

##### *ICPs and ICP identifiers*

##### *Provision of ICP Information to the registry manager*

##### *Management of ICP status*

##### *Updating registry standing information*

#### **Schedule 11.2**

#### **Transfer of ICPs between distributors' networks**

#### **Schedule 11.3**

#### **Switching**

##### *Standard switching process*

##### *Switch move process*

##### *Half-hour switching process*

##### *Withdrawing a switch request*

##### *Exchange of information*

#### **Schedule 11.4**

#### **Metering equipment provider switching and registry metering records**

#### **Schedule 11.5**

#### **Process for trader event of default**

---

### **11.1 Contents of this Part**

This Part—

- (a) provides for the management of information in the **registry**; and
- (b) prescribes a process for switching **customers** and **embedded generators** between **traders**; and

- (c) prescribes a process for a **distributor** to change the record in the **registry** of an **ICP** so that the **ICP** is recorded as being usually connected to an **NSP** in the **distributor's network**; and
- (d) prescribes a process for switching responsibility for **metering installations** for **ICPs** between **metering equipment providers**; and
- (e) prescribes a process for dealing with **trader events of default**; and
- (f) requires **retailers** to give **consumers** information about their own consumption of **electricity**; and
- (g) requires **retailers** to give information about their **generally available retail tariff plans** to any person on request.

Compare: Electricity Governance Rules 2003 rule 1 part E

Clause 11.1(a) and (c): amended, on 5 October 2017, by clause 194 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 11.1(c): amended, on 23 February 2015, by clause 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 11.1(d): inserted, on 29 August 2013, by clause 6 of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011.

Clause 11.1(e): inserted, on 16 December 2013, by clause 5 of the Electricity Industry Participation (Managing Retailer Default Situations) Code Amendment 2013.

Clause 11.1(e): amended, on 28 February 2015, by clause 5 of the Electricity Industry Participation Code Amendment (Trader Default) 2014.

Clause 11.1(e): amended, on 1 February 2016, by clause 4(1) of the Electricity Industry Participation Code Amendment (Access to Retail Data) 2014.

Clause 11.1(f): inserted, on 1 February 2016, by clause 4(2) of the Electricity Industry Participation Code Amendment (Access to Retail Data) 2014.

Clause 11.1(f): amended, on 1 February 2016, by clause 5(1) of the Electricity Industry Participation Code Amendment (Access to Retail Tariff Information) 2015.

Clause 11.1(g): inserted, on 1 February 2016, by clause 5(2) of the Electricity Industry Participation Code Amendment (Access to Retail Tariff Information) 2015.

## 11.2 Requirement to provide complete and accurate information

- (1) A **participant** must take all practicable steps to ensure that information that the **participant** is required to provide to any person under this Part is—
  - (a) complete and accurate; and
  - (b) not misleading or deceptive; and
  - (c) not likely to mislead or deceive.
- (2) If a **participant** becomes aware that the information the **participant** provided under this Part does not comply with subclause (1)(a) to (c), even if the **participant** has taken all practicable steps to ensure that the information complies, the **participant** must, as soon as practicable, provide such further information as is necessary to ensure that the information complies with subclause (1)(a) to (c).

Compare: Electricity Governance Rules 2003 rule 1A part E

Clause 11.2(2): substituted, on 19 December 2014, by clause 26 of the Electricity Industry Participation Code Amendment (Minor Code Amendments) (No 3) 2014.

### 11.2A Use of contractors

- (1) A **participant** may perform its obligations and exercise its rights under this Part by using a contractor.
- (2) A **participant** who uses a contractor to perform the **participant's** obligation under this Part—

- (a) remains responsible and liable for, and is not released from the obligation or any other obligation under this Part; and
  - (b) cannot assert that it is not responsible or liable for the obligation on the ground that the contractor—
    - (i) has done or not done something; or
    - (ii) has failed to meet a relevant standard; and
  - (c) must ensure that the contractor has at least the specified level of skill, expertise, experience, or qualification that the **participant** would be required to have if it were performing the obligation itself.
- (3) If a **participant** is a party to a contract or arrangement containing a provision, or part of a provision, which is inconsistent with this Part, the provision, or part of the provision, has no effect.

Clause 11.2A: inserted, on 29 August 2013, by clause 7 of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011.

### 11.3 Certain points of connection must have ICP identifiers

- (1) This clause applies to the following:
- (a) a **trader** who has agreed to purchase **electricity** from an **embedded generator** or sell **electricity** to a **consumer**:
  - (b) an **embedded generator** who sells **electricity** directly to the **clearing manager**:
  - (c) a **direct purchaser** connected to a **local network** or an **embedded network**:
  - (d) an **embedded network** owner in relation to a **point of connection** on an **embedded network** that is settled by differencing:
  - (e) a **network** owner in relation to a **shared unmetered load point of connection** to the **network** owner's **network**:
  - (f) a **network** owner in relation to a **point of connection** between the **network** owner's **network** and an **embedded network**.
- (2) A **participant** to whom this clause applies must, before the **participant** assumes responsibility for a **point of connection** described in subclause (3) on a **local network** or **embedded network**, obtain an **ICP identifier** for the **point of connection**.
- (3) The **points of connection** for which **ICP identifiers** must be obtained under subclause (2) are **points of connection** at which any of the following occurs:
- (a) a **consumer** purchases **electricity** from a **trader**:
  - (b) a **trader** purchases **electricity** from an **embedded generator**:
  - (c) a **direct purchaser** purchases **electricity** from the **clearing manager**:
  - (d) an **embedded generator** sells **electricity** directly to the **clearing manager**:
  - (e) a **network** is settled by differencing:
  - (f) there is a **distributor** status **ICP**—
    - (i) at the **point of connection** between an **embedded network** and the **distributor's network**; or
    - (ii) at the **point of connection** of **shared unmetered load**.

Compare: Electricity Governance Rules 2003 rule 2 part E

Clause 11.3(1)(c): amended, on 23 February 2015, by clause 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 11.3(1)(c): amended, on 5 October 2017, by clause 195 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

#### 11.4 Distributors must create ICP identifiers for ICPs

- (1) Each **distributor** must create an **ICP identifier** in accordance with clause 1 of Schedule 11.1 for each **ICP** on each **network** for which the **distributor** is responsible.
- (2) A **distributor** must create an **ICP identifier** for the **point of connection** at which an **embedded network** connects to the **distributor's network** in accordance with subclause (1).
- (3) An **ICP identifier** for an **ICP** may not be changed.

Compare: Electricity Governance Rules 2003 rule 3 part E

#### 11.5 Participants may request that distributors create ICP identifiers for ICPs

- (1) A **participant** to whom clause 11.3 applies may request that a **distributor** create an **ICP identifier** for an **ICP** on a **network** for which the **distributor** is responsible.
- (2) A **participant** may make a request under subclause (1) only if the **participant** has an arrangement with the **distributor** for **line function services** in accordance with clause 11.16.
- (3) A **distributor** to whom a request is made must, within 3 **business days** of receiving the request, create a new **ICP identifier** for each **ICP** to which the request relates in accordance with clause 1 of Schedule 11.1, or advise the **participant** of the **distributor's** reasons for not complying with the request.

Compare: Electricity Governance Rules 2003 rule 4 part E

Clause 11.5(2): amended, on 1 February 2016, by clause 39 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

#### 11.6 ICP status

The **participant** specified in clause 12 of Schedule 11.1 must manage the status of an **ICP** in accordance with clause 12 of Schedule 11.1.

Compare: Electricity Governance Rules 2003 rule 5 part E

#### 11.7 Provision of ICP information

- (1) A **distributor** whose **network** includes 1 or more **ICPs** must provide information about each of those **ICPs** to the **registry manager** in accordance with Schedule 11.1.
- (2) A **trader** must provide information about each **ICP** at which the **trader** trades **electricity** to the **registry manager** in accordance with Schedule 11.1.

Compare: Electricity Governance Rules 2003 rule 6 part E

Clause 11.7(1) and (2): amended, on 5 October 2017, by clause 196 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

#### 11.8 Provision of and changes to ICP information and NSP information by participants

- (1) This clause applies if—
  - (a) an **NSP** is to be created or **decommissioned**; or
  - (b) a **distributor** wishes to change the record in the **registry** of an **ICP** that is not recorded as being usually connected to an **NSP** in the **distributor's network**, so that the **ICP** is recorded as being usually connected to an **NSP** in the **distributor's network** (a "transfer").

- (2) The **participant** specified in clause 25(3) of Schedule 11.1 must give the notification required by clause 25(1) of Schedule 11.1.
- (3) A **distributor** to whom subclause (1)(b) applies must comply with clause 25(2) of Schedule 11.1.
- (4) The **participants** specified in clauses 25 to 27 of Schedule 11.1 must comply with those clauses.
- (5) If a **network** owner acquires all or part of an existing **network**, the **network** owner must give the notification required by clause 29 of Schedule 11.1.

Compare: Electricity Governance Rules 2003 rule 8 part E

Clause 11.8(1)(a) and (b): amended, on 5 October 2017, by clause 197 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 11.8(1)(b): amended, on 23 February 2015, by clause 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

#### **11.8A Metering equipment providers to provide registry metering records to registry manager**

- (1) A **metering equipment provider** must, for each **metering installation** described in subclause (2) for which it is responsible,—
  - (a) provide to the **registry manager** the **registry metering records** for the **metering installation** in the **prescribed form**; and
  - (b) update the **registry metering records** in accordance with Schedule 11.4.
- (2) Subclause (1) applies to a **metering installation** that is—
  - (a) a **category 1 metering installation**, or higher category of **metering installation**; and
  - (b) for an **ICP** that is not also an **NSP**.

Clause 11.8A Heading: amended, on 5 October 2017, by clause 198(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 11.8A: inserted, on 29 August 2013, by clause 8 of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011.

Clause 11.8A(1)(a): amended, on 5 October 2017, by clause 198(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

#### **11.8B Metering equipment providers to arrange for regular audits**

Each **metering equipment provider** must arrange to be **audited** regularly in accordance with Part 16A in respect of the **metering equipment provider's** obligations under this Part.

Clause 11.8B: inserted, on 29 August 2013, by clause 8 of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011.

Clause 11.8B: replaced, on 1 June 2017, by clause 18 of the Electricity Industry Participation Code Amendment (Requirements and Processes for Audits) 2016.

#### **11.9 [Revoked]**

Compare: Electricity Governance Rules 2003 rule 8 part E

Clause 11.9: revoked, on 29 August 2013, by clause 9 of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011.

#### **11.10 Distributors to arrange for regular audits**

Each **distributor** must arrange to be **audited** regularly in accordance with Part 16A in respect of the **distributor's** obligations under this Part.

Compare: Electricity Governance Rules 2003 rule 10 part E

Clause 11.10(1)(c): substituted, on 29 August 2013, by clause 5(1) of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2013.

Clause 11.10(1A): inserted, on 29 August 2013, by clause 5(2) of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2013.

Clause 11.10: replaced, on 1 June 2017, by clause 19 of the Electricity Industry Participation Code Amendment (Requirements and Processes for Audits) 2016.

### 11.11 Authority and participant requested audits

- (1) The **Authority** may at any time carry out, or appoint an **auditor** to carry out, an **audit** of a **participant** in respect of the **participant's** obligations under this Part.
- (2) If a **participant** considers that another **participant** may not have complied with this Part, the **participant** may request that the **Authority** carry out, or appoint an **auditor** to carry out, an **audit** of the other **participant**.
- (3) Part 16A applies to an **audit** carried out under this clause.

Compare: Electricity Governance Rules 2003 rule 10A part E

Clause 11.11: replaced, on 1 June 2017, by clause 20 of the Electricity Industry Participation Code Amendment (Requirements and Processes for Audits) 2016.

### 11.12 *[Revoked]*

Compare: Electricity Governance Rules 2003 rule 10B part E

Clause 11.12: revoked, on 1 June 2017, by clause 21 of the Electricity Industry Participation Code Amendment (Requirements and Processes for Audits) 2016.

### 11.13 *[Revoked]*

Compare: Electricity Governance Rules 2003 rule 10C part E

Clause 11.13: revoked, on 1 June 2017, by clause 22 of the Electricity Industry Participation Code Amendment (Requirements and Processes for Audits) 2016.

### 11.14 Process for maintaining shared unmetered load

- (1) This clause applies if **shared unmetered load** is connected to a **distributor's network**.
- (2) The **distributor** must give written notice to the **registry manager**, and each **trader** responsible under clause 11.18(1) for the **ICPs** across which the **unmetered load** is shared, of the **ICP identifiers** of those **ICPs**.
- (3) A **trader** who receives notification under subclause (2) must give written notice to the **distributor** if it wishes to add an **ICP** to or omit an **ICP** from the **ICPs** across which the **unmetered load** is shared.
- (4) A **distributor** who receives notification under subclause (3) must give written notice to the **registry manager** and each **trader** responsible for any of the **ICPs** across which the **unmetered load** is shared of the addition or omission of the **ICP**.
- (5) If a **distributor** becomes aware of a change to the capacity of an **ICP** across which the **unmetered load** is shared or that an **ICP** across which the **unmetered load** is shared is decommissioned, it must give written notice to all **traders** who receive notification under subclause (2) of the change or decommissioning as soon as practicable after the change or decommissioning.
- (6) A **trader** who receives notification under subclause (5) must, as soon as practicable after receiving the notification, adjust the **unmetered load** information for each **ICP** for which it is responsible, so that the **unmetered load** is shared equally across each of those **ICPs**.



- (7) A **trader** must take responsibility for **shared unmetered load** assigned to an **ICP** for which the **trader** becomes responsible as a result of a switch in accordance with this Part.
- (8) A **trader** must not relinquish responsibility for **shared unmetered load** assigned to an **ICP** if there would then be no **ICPs** left across which the load could be shared.
- (9) A **trader** who changes the status of an **ICP** across which the **unmetered load** is shared to inactive in accordance with clause 19 of Schedule 11.1 is not required to give written notice to the **distributor** of the change under subclause (3). The amount of **electricity** attributable to that **ICP** becomes **UFE**.

Compare: Electricity Governance Rules 2003 rule 14 part E

Clause 11.14(1): amended, on 23 February 2015, by clause 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 11.14(1), (2), (3), (4), (5) and (9): amended, on 5 October 2017, by clause 199 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### 11.15 Process for customer or embedded generator switching

- (1) This clause applies if a **trader** (“the gaining **trader**”) has an arrangement with a **customer** or **embedded generator** to—
  - (a) commence trading **electricity** with the **customer** or **embedded generator** at an **ICP** at which another **trader** (“the losing **trader**”) trades **electricity** with the **customer** or **embedded generator**; or
  - (b) assume responsibility under clause 11.18(1) for such an **ICP**.
- (2) The gaining **trader** and the losing **trader** must comply with Schedule 11.3.

Compare: Electricity Governance Rules 2003 rule 15 part E

### 11.15AA Trader may elect to have switch saving protection

- (1) A **trader** that buys **electricity** from the **clearing manager** may elect to have switch saving protection by giving written notice to the **Authority**.
- (2) The **Authority** must **publish** the name of each **trader** that has elected to have switch saving protection as soon as practicable after receiving the written notice from the **trader**.
- (3) A **trader’s** switch saving protection comes into effect on the day after the day on which the **Authority publishes** the **trader’s** election.

Clause 11.15AA: inserted, on 12 January 2015, by clause 4 of the Electricity Industry Participation Code Amendment (Switch Saving Protection) 2014.

Clause 11.15AA(2) and (3): amended, on 5 October 2017, by clause 200 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### 11.15AB Switch saving protection

- (1) This clause applies if a **trader** (the “protected **trader**”) has switch saving protection.
- (2) If the protected **trader** enters into an arrangement with a **customer** of another **trader** (the “losing **trader**”) to commence trading **electricity** with the **customer**, the losing **trader** must comply with subclause (4).
- (3) If a **trader** enters into an arrangement with a **customer** of a protected **trader** to commence trading **electricity** with the **customer**, the protected **trader** must comply with subclause (4).
- (4) A losing **trader** referred to in subclause (2) or a protected **trader** referred to in subclause (3) must not, by any means, initiate contact with the **customer** to attempt to

persuade the **customer** to terminate the arrangement referred to in subclause (2) or subclause (3) (as the case may be) during the period specified in subclause (5), including by—

- (a) making a counter-offer to the **customer**; or
  - (b) offering an enticement to the **customer**.
- (5) The period starts on the day on which the **trader** receives notice of the switch request under clause 22(a) of Schedule 11.3, and ends on the **event date** for the switch.

Clause 11.15AB: inserted, on 12 January 2015, by clause 4 of the Electricity Industry Participation Code Amendment (Switch Saving Protection) 2014.

#### **11.15AC Trader may communicate with customers for certain purposes**

Clause 11.15AB(4) does not prohibit a **trader** from—

- (a) contacting a **customer** to advise the **customer** of any termination fees that the **customer** is required to pay as a result of the **customer** ceasing to trade with the **trader**; or
- (b) contacting a **customer** regarding administrative matters, including—
  - (i) any fees the **customer** owes the **trader**;
  - (ii) the **customer's** final meter reading;
  - (iii) how the **trader** will return any keys it holds on the **customer's** behalf;
  - (iv) the effect of the **customer** ceasing to buy **electricity** from the **trader** on other contracts between the **customer** and the **trader**, for example, for the supply of gas; or
- (c) providing a factual response to a question asked by a **customer**; or
- (d) making a counter-offer or offering an enticement to a **customer** who has invited the **trader** to attempt to persuade the **customer** to terminate the arrangement referred to in clause 11.15AB(2) or (3); or
- (e) offering an enticement to a **customer** as part of a general marketing campaign.

Clause 11.15AC: inserted, on 12 January 2015, by clause 4 of the Electricity Industry Participation Code Amendment (Switch Saving Protection) 2014.

#### **11.15AD Cancellation of switch saving protection**

- (1) A **trader** that has elected to have switch saving protection may cancel its switch saving protection by giving written notice to the **Authority**.
- (2) However,—
  - (a) a **trader** may not cancel its switch saving protection earlier than 12 months after the date on which the switch saving protection came into effect; and
  - (b) a **trader** that has cancelled its switch saving protection may not elect to have switch saving protection earlier than 12 months after the date on which the **trader** cancelled its switch saving protection.

Clause 11.15AD: inserted, on 12 January 2015, by clause 4 of the Electricity Industry Participation Code Amendment (Switch Saving Protection) 2014.

#### **11.15A Application of Schedule 11.4**

The following parties must comply with Schedule 11.4:

- (a) a **trader** that gives written notice to the **registry manager** of the **gaining metering equipment provider** responsible for each **metering installation** for an **ICP**;
- (b) the **registry manager**;

(c) the **gaining metering equipment provider**.

Clause 11.15A: inserted, on 29 August 2013, by clause 10 of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011.

Clause 11.15A(a) and (b): amended, on 5 October 2017, by clause 201 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### **11.15B Trader contracts with customers to permit assignment by Authority**

- (1) Each **trader** must at all times ensure that the terms of each contract under which a **customer** of the **trader** purchases **electricity** from the **trader** permit—
  - (a) the **Authority** to assign the rights and obligations of the **trader** under the contract to another **trader** if the **trader** commits an **event of default** under paragraph (a) or (b) or (f) or (h) of clause 14.41(1); and
  - (b) the terms of the assigned contract to be amended on such an assignment to—
    - (i) the standard terms that the recipient **trader** would normally have offered to the **customer** immediately before the **event of default** occurred; or
    - (ii) such other terms that are more advantageous to the **customer** than the standard terms, as the recipient **trader** and the **Authority** agree; and
  - (c) the terms of the assigned contract to be amended on such an assignment to include a minimum term in respect of which the **customer** must pay an amount for cancelling the contract before the expiry of the minimum term; and
  - (d) the **trader** to provide information about the **customer** to the **Authority** and for the **Authority** to provide the information to another **trader** if required under Schedule 11.5; and
  - (e) the **trader** to assign the rights and obligations of the **trader** to another **trader**.
- (2) The terms specified in subclause (1) must—
  - (a) be expressed to be for the benefit of the **Authority** for the purposes of the Contracts (Privity) Act 1982; and
  - (b) not be able to be amended without the consent of the **Authority**.
- (3) *[Revoked]*

Clause 11.15B: inserted, on 16 December 2013, by clause 6 of the Electricity Industry Participation (Managing Retailer Default Situations) Code Amendment 2013.

Heading clause 11.15B: amended, on 28 February 2015, by clause 6(1) of the Electricity Industry Participation Code Amendment (Trader Default) 2014.

Clause 11.15B(1): amended, on 28 February 2015, by clause 6(2)(a) of the Electricity Industry Participation Code Amendment (Trader Default) 2014.

Clause 11.15B(1)(a): amended, on 28 February 2015, by clause 6(2)(b) of the Electricity Industry Participation Code Amendment (Trader Default) 2014.

Clause 11.15B(1)(a): amended, on 1 February 2016, by clause 40 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

Clause 11.15B(1)(a): amended, on 5 October 2017, by clause 202 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 11.15B(3): revoked, on 28 August 2015, by clause 6(3) of the Electricity Industry Participation Code Amendment (Trader Default) 2014.

### **11.15C Process for trader events of default**

- (1) This clause applies if the **Authority** is satisfied that a **trader** has committed an **event of default** under paragraph (a) or (b) or (f) or (h) of clause 14.41.

- (2) The **Authority** and each **participant** must comply with Schedule 11.5.
- (3) This clause ceases to apply, and the **Authority** and each **participant** must cease to comply with Schedule 11.5, if the **Authority** is advised under clause 14.41(2), 14.43(3B), or 14.43(4A) that the relevant **participant** considers that the **event of default** has been remedied.

Clause 11.15C: inserted, on 16 December 2013, by clause 6 of the Electricity Industry Participation (Managing Retailer Default Situations) Code Amendment 2013.

Heading, clause 11.15C: amended, on 28 February 2015, by clause 7(1) of the Electricity Industry Participation Code Amendment (Trader Default) 2014.

Clause 11.15C(1): amended, on 28 February 2015, by clause 7(2) of the Electricity Industry Participation Code Amendment (Trader Default) 2014.

Clause 11.15C(1): amended, on 24 March 2015, by clause 5 of the Electricity Industry Participation Code Amendment (Settlement and Prudential Security) 2014.

Clause 11.15C(2): amended, on 15 May 2014, by clause 21 of the Electricity Industry Participation (Minor Code Amendments) Code Amendment 2014.

Clause 11.15C(3): inserted, on 1 February 2016, by clause 41 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

### 11.16 Trader to ensure arrangements for line function services and metering

Before providing the **registry manager** with information in accordance with clause 11.7(2) or clause 11.18(4), a **trader** must—

- (a) ensure that it, or its **customer**, has made any necessary arrangements for the provision of **line function services** in relation to the **ICP**; and
- (b) have entered into an arrangement with a **metering equipment provider** to be responsible for each **metering installation** for the **ICP**.

Compare: Electricity Governance Rules 2003 rule 15 part E

Clause 11.16: substituted, on 29 August 2013, by clause 11 of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011.

Clause 11.16: amended, on 5 October 2017, by clause 203 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 11.16(a): amended, on 1 February 2016, by clause 42 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

### 11.17 Connecting ICP that is not also NSP

- (1A) A **distributor** must, when connecting an **ICP** that is not also an **NSP**, follow the connection process set out in clause 10.31.
- (1) A **distributor** must not connect an **ICP** across which **unmetered load** is shared unless a **trader** is recorded in the **registry** as accepting responsibility for the **shared unmetered load**.
- (2) A **distributor** must not connect an **ICP** of any other kind unless a **trader** is recorded in the **registry** as accepting responsibility for the **ICP**.
- (3) Subclause (2) does not apply to an **ICP** that is—
  - (a) the **point of connection** between a **network** and an **embedded network**; or
  - (b) the **point of connection** of **shared unmetered load**.

Compare: Electricity Governance Rules 2003 rule 17 part E

Clause 11.17: heading amended, on 29 August 2013, by clause 12(1) of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011.

Clause 11.17: heading amended, on 29 August 2013, by clause 5 of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011, Amendment 2013 (No 2).

Clause 11.17 Heading: amended, on 5 October 2017, by clause 204(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 11.17(1A): inserted, on 29 August 2013, by clause 12 of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011.

Clause 11.17(1A): substituted, on 29 August 2013, by clause 5 of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011 Amendment 2013 (No 2).

Clause 11.17(1A), (1) and (2): amended, on 23 February 2015, by clause 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 11.17(1A), (1) and (2): amended, on 5 October 2017, by clause 204(2) and (3) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### 11.18 Trader responsibility for ICP

- (1) If a **trader** is recorded in the **registry** as accepting responsibility for an **ICP** that is not also an **NSP**, the **trader** is responsible for all obligations in this Part that—
  - (a) apply to **traders**; and
  - (b) relate to an **ICP** that is not also an **NSP**.
- (2) A **trader** ceases to be responsible for obligations in this Part relating to an **ICP** that is not also an **NSP** if—
  - (a) another **trader** is recorded in the **registry** as being responsible for the **ICP**; or
  - (b) the **ICP** is **decommissioned** in accordance with clause 20 of Schedule 11.1.
- (3) If an **ICP** is to be **decommissioned**, the **trader** who is responsible for the **ICP** must—
  - (a) arrange for a final **interrogation** to take place before or on removal of the **meter**; and
  - (b) advise the **metering equipment provider** responsible for each **metering installation** for the **ICP** that it is to be **decommissioned**.
- (4) A **trader** who is responsible for an **ICP**, other than an **ICP** at which there is only **unmetered load**, must ensure that a **metering equipment provider** is recorded in the **registry** as being responsible for each **metering installation** for the **ICP**.
- (5) The **trader** must not trade at an **ICP** if a **metering equipment provider** is not recorded in the **registry** as being responsible for each **metering installation** for the **ICP**, unless the **trader** trades only **unmetered load** at that **ICP**.

Compare: Electricity Governance Rules 2003 rule 17 part E

Clause 11.18: substituted, on 29 August 2013, by clause 13 of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011.

Clause 11.18(5): amended, on 15 May 2014, by clause 22 of the Electricity Industry Participation (Minor Code Amendments) Code Amendment 2014.

### 11.18A Registry manager to advise metering equipment providers

The **registry manager** must, within 1 **business day** of being advised by a **trader** of a **metering equipment provider's participant identifier** for an **ICP identifier**, —

- (a) if there is not already a **metering equipment provider** assigned to the **ICP identifier**, advise the **gaining metering equipment provider** that the **registry manager** has been advised that it is the **gaining metering equipment provider** for each **metering installation** for the **ICP**; or
- (b) if there is a **losing metering equipment provider**, advise both the **gaining metering equipment provider** and the **losing metering equipment provider** of the advice.

Clause 11.8A Heading: amended, on 5 October 2017, by clause 205(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 11.18A: inserted, on 29 August 2013, by clause 13 of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011.

Clause 11.18A: amended, on 5 October 2017, by clause 205(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### **11.18B Metering equipment provider responsibility for metering installation for ICP**

- (1) This clause applies to a **metering equipment provider** who assumes responsibility, or is appointed to be responsible, as the **metering equipment provider** for an **ICP**.
- (2) The obligations under this Part, of a **metering equipment provider** to whom this clause applies,—
  - (a) commence at the same time as the **metering equipment provider's** obligations under clause 10.21(1):
  - (b) terminate when the **metering equipment provider's** obligations under Part 10 terminate under clause 10.23.
- (3) If an **ICP** is to be **decommissioned**, the **metering equipment provider** who is responsible for each **metering installation** for the **ICP** must, —
  - (a) if the **trader** is responsible for the **interrogation** of the **metering installation**, prior to the **decommissioning**, advise the **trader**, not less than 3 **business days** prior to the **decommissioning**, that the **trader** must, when the status of the **ICP** is changed to inactive in accordance with clause 19 of Schedule 11.1, as part of the **decommissioning** of the **ICP**, carry out a final **interrogation**; or
  - (b) if the **metering equipment provider** is responsible for the **interrogation** of the **metering installation**, when the status of the **ICP** is changed to inactive in accordance with clause 19 of Schedule 11.1, as part of the **decommissioning** of the **ICP**, arrange for a final **interrogation** to take place and provide the **raw meter data** to the **trader** who is recorded in the **registry** as being responsible for the **ICP**.

Clause 11.18B: inserted, on 29 August 2013, by clause 13 of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011.

### **11.19 Authority to specify timeframes and formats of information**

- (1) Subject to subclause (3), subclause (2) applies if a **participant** is required to provide information under this Part, but this Code does not specify any 1 or more of the following:
  - (a) the time by which, or the period within which, the information must be provided:
  - (b) the format in which the information must be provided:
  - (c) the method by which the information must be provided.
- (2) The **participant** must provide the information in accordance with requirements as to those matters specified by the **Authority**.
- (3) Unless otherwise specified in this Part, information or notices that must be provided under this Part by the **registry manager** or to the **registry manager**, must be provided using the **registry**.

Compare: Electricity Governance Rules 2003 rule 20 part E

Clause 11.19(1): amended, on 5 October 2017, by clause 206(a) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 11.19(3): inserted, on 5 October 2017, by clause 206(b) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### 11.20 Registry must be available between 0730 and 1930 each day

- (1) The **registry manager** must ensure that the **registry** is available to receive and provide information under this Part between 0730 hours and 1930 hours each day.
- (2) Information provided to the **registry manager** after 1930 hours is deemed to be provided at 0730 the next day.

Compare: Electricity Governance Rules 2003 rule 21 part E

Clause 11.20 Heading: amended, on 5 October 2017, by clause 207(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 11.20: amended, on 5 October 2017, by clause 207(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### 11.21 Confirmation of receipt of data

- (1) Information provided to the **registry manager** is deemed, for the purposes of this Part, not to have been received until the **registry manager** has confirmed receipt in accordance with this clause.
- (2) The **registry manager** must confirm receipt of information received by it in accordance with this Part within 4 hours of the information being provided to it.
- (3) In determining whether the **registry manager** has confirmed receipt within the time specified in subclause (2), no account is to be taken of any period during which the **registry** is not required to be available under clause 11.20.
- (4) If the **participant** providing the information does not receive confirmation that the **registry manager** has received the **participant's** information, the **participant** must contact the **registry manager** to check whether the **registry manager** has received the information.
- (5) If the **registry manager** has not received the information, the **participant** must re-send the information. This process must be repeated until the **registry manager** has confirmed receipt of the information in accordance with this clause.

Compare: Electricity Governance Rules 2003 rules 22.1 and 22.2 part E

Clause 11.21(1), (2), (4) and (5): amended, on 5 October 2017, by clause 208(1) and (3) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 11.21(3): replaced, on 5 October 2017, by clause 208(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### 11.22 Registry manager must maintain register of information

- (1) The **registry manager** must maintain a register of information received by it and updated in accordance with this Code.
- (2) The **registry manager** must ensure that a complete **audit** trail exists for all information received by it in accordance with this Code.

Compare: Electricity Governance Rules 2003 rule 22.3 part E

Clause 11.22 Heading: amended, on 5 October 2017, by clause 209(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 11.22: amended, on 5 October 2017, by clause 209(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### 11.23 Reports from registry manager

By 1600 hours on the 6<sup>th</sup> **business day** of each **reconciliation period**, the **registry manager** must **publish** a report containing the following information:

- (a) the number of **ICPs** notified to the **registry manager** and contained on its register at the end of the immediately preceding **consumption period**:

- (b) the number of notifications received by the **registry manager** in accordance with clause 2 of Schedule 11.3 during the previous **reconciliation period**;
- (c) such other information as may be agreed from time to time between the **registry manager** and the **Authority**.

Compare: Electricity Governance Rules 2003 rule 23 part E

Clause 11.23 Heading: amended, on 5 October 2017, by clause 210(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 11.23: amended, on 5 October 2017, by clause 210(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

#### 11.24 Registry manager delivers reports to specific participants

The **registry manager** must deliver the reports specified in clauses 11.25 to 11.27 in the manner specified in those clauses.

Compare: Electricity Governance Rules 2003 rule 24.1A part E

Clause 11.24 Heading: amended, on 5 October 2017, by clause 211(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 11.24: amended, on 5 October 2017, by clause 211(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

#### 11.25 Reports to clearing manager, system operator or reconciliation manager

- (1) The **clearing manager**, or the **system operator**, or the **reconciliation manager** may request in writing, no later than 5 **business days** before the last day of the month before the 1<sup>st</sup> month for which the report is requested, a report that includes any or all of the following information:
  - (a) all active **NSPs** connected to a **local network** during the immediately preceding 14 calendar months;
  - (b) all active **NSPs** connected to a **network** for which a **trader** is, and has over the immediately preceding 14 calendar months been, responsible;
  - (c) the dates on which each **trader's** responsibility under this Code at an **NSP** commenced and ceased.
- (2) The **system operator** may at any time request, in writing, a report that sets out every switch made under clauses 2, 9 or 14 of Schedule 11.3, the effect of which is that a **trader** has commenced trading at an **NSP** or a **trader** has ceased trading at an **NSP**.
- (3) A request made under subclauses (1) or (2) may—
  - (a) be a one-off request; or
  - (b) specify a frequency over a particular period; or
  - (c) specify a frequency over an indefinite period until terminated by the requesting person.
- (4) If the request is received by the time specified in this clause, the **registry manager** must provide the report by 1000 hours on the 1<sup>st</sup> **business day** of the month following the month in which the request was made, or if the request for the report specifies a later date, by the later date.
- (5) The person who requested the report may vary any of the details set out in the request, by giving notification to the **registry manager** of the relevant details in writing by no later than 5 **business days** before the last day of the month before the 1<sup>st</sup> month for which the person requests the variation.



- (6) The **registry manager** must comply with a request made in accordance with subclause (5) by 1000 hours on the 1<sup>st</sup> **business day** of the month following the month in which the request was made.

Compare: Electricity Governance Rules 2003 rule 24.1 part E

Clause 11.25 Heading: amended, on 5 October 2017, by clause 212(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 11.25(1), (4), (5) and (6): amended, on 5 October 2017, by clause 212(2) to (4) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 11.25(1)(a) and (b): amended, on 23 February 2015, by clause 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

### 11.26 Reports to reconciliation manager

By 1600 hours on the 4<sup>th</sup> **business day** of each calendar month, in respect of the immediately preceding **consumption period**, and by 1600 hours on the 13<sup>th</sup> **business day** of each calendar month in respect of the immediately preceding 14 **consumption periods**, the **registry manager** must deliver the following reports to the **reconciliation manager**:

- (a) a report identifying the number of **ICP days** per **NSP**, differentiated by **half-hour metering** type or non **half-hour metering** type (for the purpose of this clause, **half-hour metering** type on the **registry** must be reported as **half hour**, and all other metering types must be reported as non **half hour**) attributable to each **trader** for those **NSPs** that are recorded on the **registry** as consuming **electricity** at any time during, as the case may be, that **consumption period** or any of those **consumption periods**:
- (b) a report detailing the **loss factor** values for each **loss category** code recorded in the **registry** in respect of all **trading periods**:
- (c) a report detailing the **balancing area** to which each **NSP** belongs recorded in the **registry** in respect of all **trading periods** (including any changes during that month):
- (d) a report detailing the **half hour ICP identifiers** and the **NSPs** to which they are assigned for each individual **trader** (including any changes during that month):
- (e) a report that sets out every switch made under clauses 2, 9 or 14 of Schedule 11.3, the effect of which is that a **trader** has commenced trading at an **NSP** or a **trader** has ceased trading at an **NSP**.

Compare: Electricity Governance Rules 2003 rule 24.2 part E

Clause 11.26 Heading: amended, on 5 October 2017, by clause 213(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 11.26: amended, on 5 October 2017, by clause 213(2) and (3) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### 11.27 Reports to Authority

By 1600 hours on the 1<sup>st</sup> **business day** of each calendar month, the **registry manager** must deliver to the **Authority** a report summarising the number of events that have not been notified to the **registry manager**, of which it is aware, within the timeframes specified in this Part.

Compare: Electricity Governance Rules 2003 rule 24.3 part E

Clause 11.27 Heading: amended, on 5 October 2017, by clause 214(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 11.27: amended, on 5 October 2017, by clause 214(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### 11.28 Access to registry

- (1) A **participant** may apply to the **Authority** to have access to information held in the **registry**.
- (2) If the **Authority** grants a **participant's** application, the **Authority** must specify terms and conditions under which the **Authority** grants access to the information.
- (2A) The **participant** must comply with the terms and conditions specified by the **Authority** under subclause (2).
- (3) The **registry manager** must provide to the **participant** access to information held in the **registry** in accordance with those terms and conditions.
- (4) If the **Authority** grants a **participant** access to information in the **registry**, and the **participant** requests a report, the **registry manager** must provide the report to the **participant** within 4 hours of receiving the request.<sup>(5)</sup> In determining whether the **registry manager** has provided the report within the time specified in subclause (4), no account is to be taken of any period during which the **registry** is not required to be available under clause 11.20.

Compare: Electricity Governance Rules 2003 rule 25 part E

Clause 11.28(1), (2), (3) and (5): amended, on 5 October 2017, by clause 215(1) to (3) and (5) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 11.28(2A): inserted, on 29 August 2013, by clause 14(2) of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011.

Clause 11.28(4): replaced, on 5 October 2017, by clause 215(4) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### 11.29 Registry information change

If a change to **registry** information is provided in accordance with clause 11.7, the **registry manager** must, within 1 **business day** of receiving the information, advise affected **participants** of the change.

Compare: Electricity Governance Rules 2003 rule 26 part E

Clause 11.29: substituted, on 29 August 2013, by clause 15 of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011.

Clause 11.29: amended, on 5 October 2017, by clause 216 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### 11.30 Use of ICP identifier on invoices

Each **trader** must ensure that the relevant **ICP identifier** is printed on every invoice or associated document relating to the sale of **electricity** rendered by the **trader**, and that the **ICP identifier** is clearly labelled "ICP" on the invoice.

Compare: Electricity Governance Rules 2003 rule 27 part E

### 11.31 Customer and embedded generator queries

- (1) If a **trader** receives a request from a **customer** of the **trader** or a person authorised by a **customer** of the **trader** for the **customer's ICP identifier**, the **trader** must provide that information no later than 3 **business days** after receiving the request.
- (2) If a **distributor** receives a request from a **customer** or **embedded generator** whose **ICP** is connected to the **distributor's network** for the **customer** or **embedded**

**generator's ICP identifier**, or a person authorised by such a **customer** or **embedded generator**, the **distributor** must provide that information no later than 3 **business days** after receiving the request.

Compare: Electricity Governance Rules 2003 rule 28 part E

Clause 11.31(2): amended, on 23 February 2015, by clause 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 11.31(2): amended, on 5 October 2017, by clause 217 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### 11.32 Reliance on registry

A **participant** does not breach this Code just because the **participant** does something relying on an incorrect record in the **registry**.

Compare: Electricity Governance Rules 2003 rule 29 part E

#### *Access by consumers to information about their own electricity consumption*

Cross Heading: inserted, on 1 February 2016, by clause 5 of the Electricity Industry Participation Code Amendment (Access to Retail Data) 2014.

### 11.32A Retailers must give information about consumer electricity consumption

- (1) Each **retailer** must, if requested by a **consumer** with whom the **retailer** has a contract to supply **electricity**, or with whom the **retailer** has had such a contract in the last 24 months, give the **consumer** any of the information specified in subclause (2) that the **consumer** requests.
- (2) The information referred to in subclause (1) is information relating to any period in the 24 months preceding the request—
  - (a) about the **consumer's** consumption of **electricity** relating to each **ICP** at which the **retailer** supplied **electricity** to the **consumer**; and
  - (b) used by the **retailer** to—
    - (i) calculate the amount of **electricity** consumed by the **consumer** at each **ICP**; or
    - (ii) provide any service to the **consumer**.

Clause 11.32A: inserted, on 1 February 2016, by clause 5 of the Electricity Industry Participation Code Amendment (Access to Retail Data) 2014.

### 11.32B Requests for information

- (1) A **retailer** to which a request is made must give the information to the **consumer** no later than 5 **business days** after the date on which the request is made.
- (2) In responding to a request, the **retailer** must comply with the procedures, and any relevant **EIEP**, published by the **Authority** under clause 11.32F.
- (3) A **retailer** must not charge a fee for responding to a request, but if 4 requests in respect of a **consumer's** information have been made in a 12 month period, the **retailer** may impose a reasonable charge for further requests in that 12 month period.

Clause 11.32B: inserted, on 1 February 2016, by clause 5 of the Electricity Industry Participation Code Amendment (Access to Retail Data) 2014.

Clause 11.32B(2): amended, on 1 February 2016, by clause 43 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

Clause 11.32B(2): amended, on 5 October 2017, by clause 218 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### 11.32C Retailers must give written notice to consumers of availability of information

Each **retailer** must give written notice to each **consumer** with whom it has a contract to supply **electricity** of the **consumer's** ability to make a request to the **retailer** under clause 11.32B, so that the **consumer** is given written notice at least once in each year.

Clause 11.32C Heading: amended, on 5 October 2017, by clause 219(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 11.32C: inserted, on 1 February 2016, by clause 5 of the Electricity Industry Participation Code Amendment (Access to Retail Data) 2014.

Clause 11.32C: amended, on 5 October 2017, by clause 219(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### 11.32D Information security

A **retailer** that receives a request for information under clause 11.32B—

- (a) must not give access to that information unless it is satisfied as to the identity of the **consumer** making the request; and
- (b) must ensure, by the adoption of appropriate procedures, that any information intended for a **consumer** is received—
  - (i) only by the **consumer**; or
  - (ii) where the request is made by an agent of the **consumer**, only by the **consumer** or the **consumer's** agent.

Clause 11.32D: inserted, on 1 February 2016, by clause 5 of the Electricity Industry Participation Code Amendment (Access to Retail Data) 2014.

### 11.32E Agents

If a **consumer** authorises an agent to request information under clause 11.32B, a **retailer** must treat a request from the agent as if it were a request from the **consumer**, if the agent has the written authority of the **consumer** to obtain the information or is otherwise properly authorised by that **consumer** to obtain the information.

Clause 11.32E: inserted, on 1 February 2016, by clause 5 of the Electricity Industry Participation Code Amendment (Access to Retail Data) 2014.

### 11.32F Authority to publish procedures for responding to requests for consumption information

- (1) The **Authority** must—
  - (a) **publish**, and keep **published**, procedures under which a **retailer** must respond to a request from a **consumer** under clause 11.32B; and
  - (b) prescribe 1 or more **EIEPs** with which a **retailer** must comply when responding to such a request.
- (1A) The **Authority** must **publish** an **EIEP** it prescribes under subclause (1).
- (2) The procedures **published** by the **Authority** must specify the manner in which information must be given to **consumers**.
- (3) Each **EIEP** prescribed by the **Authority** must specify 1 or more formats in which information must be given to **consumers**.
- (4) Before the **Authority** prescribes an **EIEP** under subclause (1), or amends an **EIEP** that it has prescribed under subclause (1), it must consult with the **participants** that the **Authority** considers are likely to be affected by the **EIEP**.

- (5) The **Authority** need not comply with subclause (4) if it proposes to amend an **EIEP** prescribed under subclause (1) if the **Authority** is satisfied that—
- (a) the nature of the amendment is technical and non-controversial; or
  - (b) there has been adequate prior consultation so that the **Authority** has considered all relevant views.

Clause 11.32F Heading: amended, on 5 October 2017, by clause 220(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 11.32F: inserted, on 1 February 2016, by clause 5 of the Electricity Industry Participation Code Amendment (Access to Retail Data) 2014.

Clause 11.32F: substituted, on 1 February 2016, by clause 44 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

Clause 11.32F(1): replaced, on 5 October 2017, by clause 220(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 11.32F(1A): inserted, on 5 October 2017, by clause 220(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 11.32F(2) to (5): amended, on 5 October 2017, by clause 220(3) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### **11.32G Retailers must provide information about generally available retail tariff plans**

- (1) If any person asks a **retailer** to provide information about 1 or more of the **retailer's** current **generally available retail tariff plans**, the **retailer** must give the requested information to the person no later than **5 business days** after receiving the request.
- (2) If the person requests that information be provided under subclause (1) in a manner or format that differs from the manner or format the **retailer** typically uses to provide such information, the **retailer** may impose a reasonable charge for providing the information in the manner or form requested.

Clause 11.32G: inserted, on 1 February 2016, by clause 6 of the Electricity Industry Participation Code Amendment (Access to Retail Tariff Information) 2015.

### **11.33 Authority may direct registry to be suspended *[Expired]***

Clause 11.33: inserted, from 24 May 2013 to 29 December 2013, by clause 4 of the Electricity Industry Participation (Transitional Provisions for New Metering Arrangements) Code Amendment 2013.

### **11.34 Registry manager, distributors, and traders not required to comply with obligations when registry suspended *[Expired]***

Clause 11.34: inserted, from 24 May 2013 to 29 December 2013, by clause 4 of the Electricity Industry Participation (Transitional Provisions for New Metering Arrangements) Code Amendment 2013.

### **11.35 Registry manager and traders not required to comply with specified provisions after registry resumes operation *[Expired]***

Clause 11.35: inserted, from 24 May 2013 to 29 December 2013, by clause 4 of the Electricity Industry Participation (Transitional Provisions for New Metering Arrangements) Code Amendment 2013.

### **11.36 Clauses to expire *[Expired]***

Clause 11.36: inserted, from 24 May 2013 to 29 December 2013, by clause 4 of the Electricity Industry Participation (Transitional Provisions for New Metering Arrangements) Code Amendment 2013.

## Schedule 11.1

cl 11.7

### Creation and management of ICPs, ICP identifiers and NSPs

#### *ICPs and ICP identifiers*

#### 1 ICP identifiers

- (1) A **distributor** must create an **ICP identifier** for each **ICP** on each **network** for which the **distributor** is responsible in accordance with the following format:

xxxxxxxxxxxccc

where

xxxxxxxxxx is a numerical sequence provided by the **distributor**

xx is a code assigned by the **Authority** to the issuing **distributor** that ensures the **ICP** is unique

ccc is a checksum generated according to the algorithm provided by the **Authority**.

- (2) The **ICP identifier** must be used by a **participant** in all communications with the **registry manager** to identify—
- (a) the point at which a **trader** is deemed to convey **electricity** to a **consumer** or from an **embedded generating station**; and
  - (b) the **point of connection** between an **embedded network** and its parent **network**, or the **point of connection** between a **shared unmetered load** and its **network**.
- (3) Despite any clause to the contrary, only the obligations in this clause and clauses 2, 6 and 7(1)(a) to (e), (l) and (m) apply if an **ICP identifier** is used to **identify** a—
- (a) **point of connection** between an **embedded network** and its parent **network**; or
  - (b) **point of connection** between **shared unmetered load** and its **network**.
- (4) If an **ICP identifier** is used in the management of the status of the **ICP**, the obligations in clauses 13, 16 and 20 also apply.

Compare: Electricity Governance Rules 2003 clause 1.1 schedule E1  
Clause 1(1) and (2): amended, on 5 October 2017, by clause 221 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

#### 2 Address

- (1) Each **ICP identifier** must have a location address that allows the **ICP** to be readily located.
- (2) Despite subclause (1), the address of an **ICP identifier** for **distributed unmetered load** may be the location of the **distributed unmetered load** database.

Compare: Electricity Governance Rules 2003 clause 1.2 schedule E1

Clause 2(2): inserted, on 29 August 2013, by clause 6 of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2013.

### 3 **Electrically disconnecting**

Each **ICP** created after 7 October 2002 must be able to be **electrically disconnected** without **electrically disconnecting** another **ICP**, except for the following **ICPs**:

- (a) an **ICP** that is the **point of connection** between a **network** and an **embedded network**:
- (b) an **ICP** that represents the consumption calculated by the difference between the total consumption for the **embedded network** and all other **ICPs** on the **embedded network**.

Compare: Electricity Governance Rules 2003 clause 1.3 schedule E1

Clause 3 Heading: replaced, on 5 October 2017, by clause 222(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 3: amended, on 5 October 2017, by clause 222(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### 4 **Authority may grant dispensation**

The **Authority** may, by notification in writing, grant a dispensation from the requirements of clause 3 for an **ICP** that cannot be **electrically disconnected** without **electrically disconnecting** another **ICP**.

Compare: Electricity Governance Rules 2003 clause 1.4 schedule E1

Clause 4: amended, on 5 October 2017, by clause 223 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### 5 **Electrical load**

The electrical load associated with an **ICP** is deemed to be supplied through 1 **network supply point** only.

Compare: Electricity Governance Rules 2003 clause 1.5 schedule E1

### 6 **Loss category**

An **ICP** must have a single **loss category** code that is referenced in such a way as to identify the associated **loss factors**.

Compare: Electricity Governance Rules 2003 clause 1.6 schedule E1

#### *Provision of ICP information to the registry manager*

Cross heading: amended, on 5 October 2017, by clause 224 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### 7 **Distributors to provide ICP information to registry manager**

- (1) A **distributor** must, for each **ICP** on the **distributor's network**, provide the following information to the **registry manager**:

- (a) the location address of the **ICP identifier**:
- (b) subject to subclause (4), the **NSP identifier** of the **NSP** to which the **ICP** is usually connected:
- (c) the **installation type** code assigned to the **ICP**:
- (d) the **reconciliation type** code assigned to the **ICP**:

- (e) the **loss category** code and **loss factors** for each **loss category** code assigned to the **ICP**;
  - (f) if the **ICP** connects the **distributor's network** to an **embedded generating station** that has a capacity of 10 MW or more, the information required by subclause (6), in accordance with subclause (7):
  - (g) the **price category** code assigned to the **ICP**, which may be a placeholder **price category** code only if the **distributor** is unable to assign the actual **price category** code because the capacity or **volume information** required to assign the actual **price category** code cannot be determined before **electricity** is traded at the **ICP**;
  - (h) if the **price category** code assigned under paragraph (g) requires a value for the capacity of the **ICP**, the **chargeable capacity** of the **ICP**, as follows:
    - (i) if the **chargeable capacity** cannot be determined before **electricity** is traded at the **ICP**, a placeholder **chargeable capacity**;
    - (ii) if the capacity value can be determined from the **metering information**, no **chargeable capacity**;
    - (iii) in any other case, the actual **chargeable capacity**;
  - (i) the **distributor** installation details of the **ICP** determined by the **price category** code assigned to the **ICP** (if any), which may be placeholder **distributor** installation details only if the **distributor** is unable to assign the actual **distributor** installation details because the capacity or **volume information** required to assign the actual **distributor** installation details cannot be determined before **electricity** is traded at the **ICP**;
  - (j) the **participant identifier** of the first **trader** who has entered into an arrangement with a **customer** or an **embedded generator** to sell or purchase **electricity** at the **ICP** (only if the information is provided by the first **trader**);
  - (k) the status of the **ICP** determined in accordance with clauses 12 to 20;
  - (l) designation of the **ICP** as "Dedicated" if the **ICP** is located in a **balancing area** that has more than 1 **NSP** located within it, and—
    - (i) the **ICP** will be supplied only from the **NSP** with the **NSP identifier** provided under paragraph (b); or
    - (ii) the **ICP** is a **point of connection** between a **network** and an **embedded network**;
  - (m) if **unmetered load**, other than **distributed unmetered load**, is associated with the **ICP**, the type and capacity in kW of the **unmetered load** (if the **distributor** knows that information);
  - (n) if **shared unmetered load** is associated with the **ICP**, a list of the **ICP identifiers** of the **ICPs** that are associated with the **unmetered load**;
  - (o) if the **ICP** connects the **distributor's network** to **distributed generation**,—
    - (i) the **nameplate capacity** of the **distributed generation**; and
    - (ii) the generation fuel type of the **distributed generation**;
  - (p) the date on which the **ICP** is initially **electrically connected**.
- (1A) For the purposes of subclause (1)(h), if the **price category** assigned to the **ICP** requires information additional to **chargeable capacity** to unambiguously define the line



charges, the additional information may be contained in the **distributor** installation details field of the **registry**.

- (2) The **distributor** must provide the information specified in subclauses (1)(a) to (1)(o) to the **registry manager** as soon as practicable after the **ICP identifier** for the **ICP** to which the information relates is created, and before **electricity** is traded at the **ICP**.
- (2A) The **distributor** must provide the information specified in subclause (1)(p) to the **registry manager** no later than 10 **business days** after the date on which the **ICP** is initially **electrically connected**.
- (2B) Despite subclause (2A), the **distributor** is not required to provide the information specified in subclause (1)(p) if the date on which the **ICP** is initially **electrically connected** is earlier than 29 August 2013.
- (3) The **distributor** must provide the following information to the **registry manager** no later than 10 **business days** after the trading of **electricity** at the **ICP** commences:
  - (a) the actual **price category** code assigned to the **ICP**;
  - (b) the actual **chargeable capacity** of the **ICP** determined by the **price category** code assigned to the **ICP** (if any);
  - (c) the actual **distributor** installation details of the **ICP** determined by the **price category** code assigned to the **ICP** (if any).
- (4) If a **distributor** cannot identify the **NSP** that is connected to an **ICP**, the **distributor** must nominate the **NSP** that the **distributor** thinks is most likely to be connected to the **ICP**, taking into account the flow of **electricity** within the **distributor's network**.
- (5) An **ICP** is deemed to be connected to the **NSP** nominated by the **distributor** under subclause (1)(b).
- (6) If a **distributor** assigns a **loss category** code to an **ICP** on the **distributor's network** that connects the **distributor's network** to an **embedded generating station** that has a capacity of 10MW or more—
  - (a) the **loss category** code assigned to the **ICP** must be unique and must not be assigned to any other **ICP** on the **distributor's network**; and
  - (b) the **distributor** must provide the following information to the **reconciliation manager**:
    - (i) the unique **loss category** code assigned to the **ICP**;
    - (ii) the **ICP identifier** of the **ICP**;
    - (iii) the **NSP identifier** of the **NSP** to which the **ICP** is connected;
    - (iv) the plant name of the **embedded generating station**.
- (7) The **distributor** must provide the information in subclause (6) no later than 5 **business days** before the **distributor** assigns the **loss category** code.
- (8) A **distributor** may provide the **registry manager** with global positioning system coordinates for each **ICP** on the **distributor's network**.
- (9) If a **distributor** provides the global positioning system coordinates of an **ICP** to the **registry manager** under subclause (8), it must provide the coordinates—
  - (a) as New Zealand Transverse Mercator 2000 (NZTM2000) coordinates as defined in Land Information New Zealand's LINZS25002 standard (Standard for New Zealand Geodetic Datum 2000 Projections); or
  - (b) in a format specified by the **Authority**.

Compare: Electricity Governance Rules 2003 clause 2 schedule E1

Clause 7(1) Heading: amended, on 5 October 2017, by clause 225(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 7(1): amended, on 15 May 2014, by clause 23 of the Electricity Industry Participation (Minor Code Amendments) Code Amendment 2014.

Clause 7(1), (2), (2A), (3), (8) and (9): amended, on 5 October 2017, by clause 225(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 7(1)(a): amended, on 29 August 2013, by clause 16 of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011.

Clause 7(1)(b): amended, on 23 February 2015, by clause 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 7(1)(b), (4), (5) and (6)(b)(iii): amended, on 5 October 2017, by clause 225(3) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 7(1)(h): substituted, on 29 August 2013, by clause 7(1) of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2013.

Clause 7(1)(o) and (p): inserted, on 29 August 2013, by clause 5(1) of the Electricity Industry Participation (Additional Registry Fields) Code Amendment 2012.

Clause 7(1)(p), (2A) and (2B): amended, on 5 October 2017, by clause 225(4) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 7(1A): inserted, on 29 August 2013, by clause 7(2) of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2013.

Clause 7(2): amended, on 29 August 2013, by clause 5(2) of the Electricity Industry Participation (Additional Registry Fields) Code Amendment 2012.

Clause 7(2A) and (2B): inserted, on 29 August 2013, by clause 5(3) of the Electricity Industry Participation (Additional Registry Fields) Code Amendment 2012.

Clause 7(4): amended, on 23 February 2015, by clause 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 7(5): amended, on 23 February 2015, by clause 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 7(6): amended, on 21 September 2012, by clause 15(1) of the Electricity Industry Participation (Minor Amendments) Code Amendment 2012.

Clause 7(6)(b)(iii): amended, on 23 February 2015, by clause 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 7(8) and (9): inserted, on 29 August 2013, by clause 5(4) of the Electricity Industry Participation (Additional Registry Fields) Code Amendment 2012.

## **8 Distributors to change ICP information provided to registry manager**

- (1) If information about an **ICP** provided to the **registry manager** in accordance with clause 7 changes, the **distributor** in whose **network** the **ICP** is located must give written notice to the **registry manager** of the change.
- (2) The **distributor** must give the notice—
  - (a) in the case of a change to the information referred to in clause 7(1)(b) (other than a change that is the result of the **commissioning** or **decommissioning** of an **NSP**), no later than **8 business days** after the change takes effect; and
  - (b) in every other case, no later than **3 business days** after the change takes effect.
- (3) A **distributor** is not required to give written notice of a change of information provided in accordance with clause 7(1)(b) if the change is for less than 14 days.
- (4) If a change of information provided in accordance with clause 7(1)(b) is for more than 14 days, subclause (2) applies as if the change had taken effect on the 15th day after the change takes effect.

Compare: Electricity Governance Rules 2003 clause 2A schedule E1

Clause 8 Heading: amended, on 5 October 2017, by clause 226(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 8(1): amended, on 5 October 2017, by clause 226(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 8(2): amended, on 5 October 2017, by clause 226(3) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 8(3): amended, on 5 October 2017, by clause 226(4) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

**9 Traders to provide ICP information to registry manager**

- (1) Each **trader** must provide the following information to the **registry manager** for each **ICP** for which it is recorded in the **registry** as having responsibility:
- (a) the **participant identifier** of the **trader**;
  - (b) the **profile** code of each **profile** at that **ICP** approved by the **Authority** in accordance with clause 13 of Schedule 15.5;
  - (c) the **participant identifier** of the **metering equipment provider** for each **category 1 metering installation**, or higher category **metering installation**, for the **ICP**;
  - (d) *[Revoked]*
  - (e) *[Revoked]*
  - (ea) the type of **submission information** that the **trader** will provide to the **reconciliation manager** for the **ICP**;
  - (f) if the settlement type UNM is assigned to the **ICP**—
    - (i) if the load is profiled through an engineering **profile** in accordance with **profile class 2.1**, the code ENG; or
    - (ii) in all other cases, the daily average **unmetered load** in kWh at the **ICP**;
  - (g) the type and capacity of the **unmetered load** at the **ICP** (if any);
  - (h) *[Revoked]*
  - (i) *[Revoked]*
  - (j) the status of the **ICP** determined in accordance with clauses 12 to 20.
  - (k) except as provided in subclause (1A), the relevant business classification code applicable to the **customer** at the **ICP**, in accordance with business classification codes **published** by the **Authority**.
- (1A) A **trader** must not provide the information specified in subclause (1)(k) if—
- (a) the **ICP** exists for the purpose of reconciling **embedded network** residual load; or
  - (b) the **ICP** has "Distributor" status as specified in clause 16.
- (2) The **trader** must provide the information specified in subclause (1)(a) to subclause (1)(j) to the **registry manager** no later than 5 **business days** after the **trader** commences trading at the **ICP** to which the information relates.
- (3) The **trader** must provide the information specified in subclause (1)(k) to the **registry manager** no later than 20 **business days** after the **trader** commences trading at the **ICP** to which the information relates.

Compare: Electricity Governance Rules 2003 clause 3 schedule E1

Clause 9 Heading: amended, on 5 October 2017, by clause 227(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 9(1): amended, on 29 August 2013, by clause 8(1) of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2013.

Clause 9(1): amended, on 5 October 2017, by clause 227(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 9(1)(c): amended, on 29 August 2013, by clause 8(2) of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2013.

Clause 9(1)(d): substituted, on 1 December 2011, by clause 14 of the Electricity Industry Participation Code (Distributor Use-of-System Agreements and Distributor Tariffs) Amendment 2011.

Clause 9(1)(d): amended, on 21 September 2012, by clause 15(2) of the Electricity Industry Participation (Minor Amendments) Code Amendment 2012.

Clause 9(1)(d): revoked, on 29 August 2013, by clause 8(3) of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2013.

Clause 9(1)(e): revoked, on 15 May 2014, by clause 24 of the Electricity Industry Participation (Minor Code Amendments) Code Amendment 2014.  
Clause 9(1)(ea): inserted, on 29 August 2013, by clause 8(5) of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2013.  
Clause 9(1)(f): amended, on 29 August 2013, by clause 8(6) of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2013.  
Clause 9(1)(h) and (i): revoked, on 29 August 2013, by clause 8(7) and (8) of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2013.  
Clause 9(1)(k): inserted, on 29 August 2013, by clause 5(5) of the Electricity Industry Participation (Additional Registry Fields) Code Amendment 2012 and Clause 8(9) of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2013.  
Clause 9(1A): inserted, on 29 August 2013, by clause 8(9) of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2013.  
Clause 9(2): amended, on 29 August 2013, by clause 8(10) of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2013.  
Clause 9(2) and (3): amended, on 5 October 2017, by clause 227(3) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.  
Clause 9(3): inserted, on 29 August 2013, by clause 8(11) of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2013.

## **10 Traders to change ICP information provided to registry manager**

- (1) If information about an **ICP** provided to the **registry manager** in accordance with clause 9 changes, the **trader** who trades at the **ICP** must give written notice to the **registry manager** of the change.
- (2) The **trader** must give the notice no later than **5 business days** after the change.
- (3) Despite subclause (2), if the **trader** is not able to give the notice within the timeframe specified in subclause (2) because of the implementation of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011, the **trader** may give the notice up to **20 business days** after the change.
- (4) Subclause (3) and this subclause expire **20 business days** after the date on which the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011 comes into force.

Compare: Electricity Governance Rules 2003 clause 3A schedule E1

Clause 10 Heading: amended, on 5 October 2017, by clause 228(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 10(1): amended, on 5 October 2017, by clause 228(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 10(2) and (3): amended, on 5 October 2017, by clause 228(3) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 10(3) and (4): inserted, on 29 August 2013, by clause 9 of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2013 and expire on 26 September 2013.

## **11 Correction of errors in the registry**

- (1) By 0900 hours on the 1<sup>st</sup> **business day** of each **reconciliation period**, the **registry manager** must provide to each **participant** who is required to submit **submission information**, the following:
  - (a) a list of the **ICPs** at which the **participant** is recorded on the **registry** as **trading** during each **consumption period** being revised in the **reconciliation period**;
  - (b) all information associated with the **participant's participant identifier**, including the **profiles** for each **ICP**.
- (2) If there is an error in the information provided under subclause (1), the **participant** must change the information in the **registry** as soon as practicable after becoming aware of the error.

Compare: Electricity Governance Rules 2003 clause 3B schedule E1  
Clause 11(1): amended, on 5 October 2017, by clause 229 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

*Management of ICP status*

**12 Management of ICP status by distributors and traders**

The status of an **ICP**, as recorded on the **registry**, must be managed by **distributors** and **traders** in accordance with clauses 13 to 20.

Compare: Electricity Governance Rules 2003 clause 4 schedule E1

**13 “New” status**

The **ICP** status of “New” must be managed by the relevant **distributor** and indicates that—

- (a) the associated **electrical installations** are in the construction phase; and
- (b) the **ICP** is not ready for the **trader** to authorise the **electrical connection** of the **ICP**.

Compare: Electricity Governance Rules 2003 clause 4.1 schedule E1

Clause 13(b): amended, on 5 October 2017, by clause 230 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

**14 “Ready” status**

- (1) The **ICP** status of “Ready” must be managed by the relevant **distributor** and indicates that—
  - (a) the associated **electrical installations** are ready for connecting to the **electricity** supply; or
  - (b) the **ICP** is ready for the **trader** to authorise the **electrical connection** of the **ICP**.
- (2) Before an **ICP** is given the “Ready” status, the relevant **distributor** must—
  - (a) identify the **trader** that has taken responsibility for the **ICP**; and
  - (b) ensure that the **ICP** has a single **price category** code.

Compare: Electricity Governance Rules 2003 clauses 4.2 and 4.3 schedule E1

Clause 14(1): amended, on 5 October 2017, by clause 231 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 14(1)(a): amended, on 15 May 2014, by clause 25 of the Electricity Industry Participation (Minor Code Amendments) Code Amendment 2014.

Clause 14(1)(a): amended, on 23 February 2015, by clause 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

**15 “New” or “Ready” status for 24 months or more**

- (1) Subclause (2) applies if—
  - (a) an **ICP** has had the status of “New” for 24 months or more; or
  - (b) an **ICP** has had the status of “Ready” for 24 months or more.
- (2) The **distributor** must—
  - (a) ask the **trader** who intends to trade at the **ICP** whether the **ICP** should continue to have that status; and
  - (b) **decommission** the **ICP** if the **trader** advises that the **ICP** should not continue to have that status.

Compare: Electricity Governance Rules 2003 clause 4.3A schedule E1

Clause 15 Heading: amended, on 5 October 2017, by clause 232 (1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 15: substituted, on 15 May 2014, by clause 26 of the Electricity Industry Participation (Minor Code Amendments) Code Amendment 2014.

Clause 15(1): amended, on 5 October 2017, by clause 232(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 15(2)(b): amended, on 5 October 2017, by clause 232(3) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

## **16 “Distributor” status**

- (1) The **ICP** status of “Distributor” must be managed by the relevant **distributor** and indicates that the **ICP** record represents a **shared unmetered load** installation or the **point of connection** between an **embedded network** and its parent **network**.
- (2) A **trader** cannot change the status of an **ICP** record with the **ICP** status of “Distributor”.

Compare: Electricity Governance Rules 2003 clause 4.4 schedule E1

## **17 “Active” status**

- (1) The **ICP** status of “Active” must be managed by the relevant **trader** and indicates that—
  - (a) the associated **electrical installations** are **electrically connected**; and
  - (b) a **trader** must provide information related to the **ICP**, in accordance with Part 15, to the **reconciliation manager** for the purpose of compiling **reconciliation information**.
- (2) Before an **ICP** is given the “Active” status, the **trader** must ensure that—
  - (a) the **ICP** has only 1 **customer, embedded generator, or direct purchaser**; and
  - (b) the **electricity** consumed is quantified by a **metering installation** or a method of calculation approved by the **Authority**.

Compare: Electricity Governance Rules 2003 clauses 4.5 and 4.6 schedule E1

Clause 17(1)(a): amended, on 29 August 2013, by clause 18 of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011.

Clause 17(1)(a): amended, on 5 October 2017, by clause 233 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

## **18 [Revoked]**

Compare: Electricity Governance Rules 2003 clause 4.6A schedule E1

Clause 18: revoked, on 29 August 2013, by clause 5(7) of the Electricity Industry Participation (Additional Registry Fields) Code Amendment 2012.

## **19 “Inactive” status**

The **ICP** status of “Inactive” must be managed by the relevant **trader** and indicates that—

- (a) the **ICP** is **electrically disconnected**; or
- (b) **submission information** related to the **ICP** is not required by the **reconciliation manager** for the purpose of compiling **reconciliation information**.

Compare: Electricity Governance Rules 2003 clause 4.7 schedule E1

Clause 19(a): substituted, on 29 August 2013, by clause 20 of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011.

Clause 19(a): amended, on 5 October 2017, by clause 234 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

## **20 “Decommissioned” status**

- (1) The **ICP** status of “Decommissioned” must be managed by the relevant **distributor** and indicates that the **ICP** is permanently removed from future switching and reconciliation processes.
- (2) **Decommissioning** occurs when—
  - (a) **electrical installations** associated with the **ICP** are physically removed; or
  - (b) there is a change in the allocation of electrical loads between **ICPs** with the effect of making the **ICP** obsolete; or
  - (c) in the case of a **distributor-only ICP** for an **embedded network**, the **embedded network** no longer exists.

Compare: Electricity Governance Rules 2003 clause 4.8 schedule E1

Clause 20(2): amended, on 5 October 2017, by clause 235 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### *Updating registry standing information*

## **21 Updating table of loss category codes**

- (1) Each **distributor** must keep up to date the table in the **registry** of the **loss category** codes that may be assigned to **ICPs** on each **distributor’s network**, by entering in the table any new **loss category** codes that may be assigned to an **ICP** on the **distributor’s network**.
- (2) Each entry in the table must specify the date on which each **loss category** code takes effect.
- (3) The date that a **loss category** code takes effect must not be earlier than 2 months after the date on which the **loss category** code is entered in the table.
- (4) A **loss category** code takes effect on the specified date.
- (5) To avoid doubt, subclause (3) does not apply to the creation of an **ICP** or to the transfer of an **ICP** from 1 **distributor's network** to another **distributor's network**.

Compare: Electricity Governance Rules 2003 clause 5 schedule E1

## **22 Updating loss factors for loss category codes**

- (1) A **distributor** must enter **loss factors** in the **registry** for each **loss category** code entered on the table in the **registry** under clause 21.
- (2) A **distributor** must ensure that—
  - (a) each **loss category** code has no more than 2 **loss factors** in a calendar month; and
  - (b) each **loss factor** covers a range of **trading periods** within that month so that all **trading periods** have a single applicable **loss factor**.
- (3) A **distributor** who wishes to replace an existing **loss factor** on the table in the **registry** must enter the replaced **loss factor** on the table in the **registry**.
- (4) Each entry in the table must specify the date on which the replaced **loss factor** takes effect.
- (5) The date that a **loss factor** takes effect must not be earlier than 2 months after the date on which the **loss factor** is entered in the table.
- (6) A replaced **loss factor** takes effect on the specified date.

- (7) To avoid doubt, subclause (5) does not apply to the creation of an **ICP** or to the transfer of an **ICP** from 1 **distributor's network** to another **distributor's network**.
- (8) The **registry manager** must **publish** an updated schedule of all **loss category** codes and the **loss factors** for each **loss category** code no later than 1 **business day** after receiving notice of a change.

Compare: Electricity Governance Rules 2003 clause 5A schedule E1

Clause 22(1): amended, on 5 October 2017, by clause 236(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 22(8): amended, on 21 September 2012, by clause 15(3) of the Electricity Industry Participation (Minor Amendments) Code Amendment 2012.

Clause 22(8): amended, on 5 October 2017, by clause 236(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

## 23 Updating table of price category codes

- (1) Each **distributor** must keep up to date the table in the **registry** of the **price category** codes that may be assigned to **ICPs** on each **distributor's network**, by entering in the table any new **price category** codes that may be assigned to an **ICP** on the **distributor's network**.
- (2) Each entry in the table must specify the date on which each **price category** code takes effect.
- (3) The date that a **price category** code takes effect must not be earlier than 2 months after the date on which the **price category** code is entered in the table.
- (4) A **price category** code takes effect on the specified date.
- (5) To avoid doubt, subclause (3) does not apply to the creation of an **ICP** or to the transfer of an **ICP** from 1 **distributor's network** to another **distributor's network**.

Compare: Electricity Governance Rules 2003 clause 6 schedule E1

## 24 Balancing area information

- (1) A **distributor** must give written notice to the **reconciliation manager** of the establishment of a **balancing area** associated with an **NSP** supplying the **distributor's network**, in accordance with clause 26.
- (2) A **distributor** must give written notice to the **reconciliation manager** of any change to the information provided under subclause (1).
- (3) The notice must—
  - (a) specify the date and **trading period** from which the change takes effect; and
  - (b) be given no later than 3 **business days** after the change takes effect.
- (4) The **reconciliation manager** must give written notice to the **registry manager** of changes to **balancing areas** within 1 **business day** after receiving the notice.
- (5) The **registry manager** must **publish** an updated schedule of the mapping between **NSPs** and **balancing areas** within 1 **business day** after receiving the notice.
- (6) The schedule must specify the date and **trading period** from which the change took effect.

Compare: Electricity Governance Rules 2003 clause 7 schedule E1

Clause 24(1), (2) and (4): amended, on 5 October 2017, by clause 237(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 24(3), (4) and (5): amended, on 5 October 2017, by clause 237(3) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.



Clause 24(4) and (5): amended, on 5 October 2017, by clause 237(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

**25 Creation and decommissioning of NSPs and transfer of ICPs from 1 distributor's network to another distributor's network**

- (1) If an **NSP** is to be created or **decommissioned**,—
  - (a) the **participant** specified in subclause (3) in relation to the **NSP** must give written notice to the **reconciliation manager** of the creation or **decommissioning**; and
  - (b) the **reconciliation manager** must give written notice to the **Authority** and affected **reconciliation participants** of the creation or **decommissioning** no later than 1 **business day** after receiving the notice in paragraph (a).
- (2) If a **distributor** wishes to change the record in the **registry** of an **ICP** that is not recorded as being usually connected to an **NSP** in the **distributor's network**, so that the **ICP** is recorded as being usually connected to an **NSP** in the **distributor's network** (a "transfer"), the **distributor** must give written notice to the **reconciliation manager**, the **Authority**, and each affected **reconciliation participant** of the transfer.
- (3) The notice required by subclause (1) must be given by—
  - (a) the **grid owner**, if—
    - (i) the **NSP** is a **point of connection** between the **grid** and a **local network**; or
    - (ii) if the **NSP** is a **point of connection** between a **generator** and the **grid**; or
  - (b) the **distributor** for the **local network** who initiated the creation or **decommissioning**, if the **NSP** is an **interconnection point** between 2 **local networks**; or
  - (c) the **embedded network** owner who initiated the creation or **decommissioning**, if the **NSP** is an **interconnection point** between 2 **embedded networks**; or
  - (d) the **distributor** for the **embedded network**, if the **NSP** is a **point of connection** between an **embedded network** and another **network**.
- (4) A **distributor** who is required to give written notice of a transfer under subclause (2) or subclause (3)(d) must comply with Schedule 11.2.

Compare: Electricity Governance Rules 2003 clause 8 schedule E1

Clause 25(1), (2), (3) and (4): amended, on 5 October 2017, by clause 238(1) to (6) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 25(2): amended, on 23 February 2015, by clause 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

**26 Information to be provided if NSPs are created or ICPs are transferred from 1 distributor's network to another distributor's network**

- (1) If a **participant** gives notice under clause 25(1) or (2) of the creation of an **NSP** or the transfer of an **ICP** from 1 **distributor's network** to another **distributor's network**, the **participant** must request that the **reconciliation manager** create a unique **NSP identifier** for the **NSP**.
- (2) The **participant** must make the request—
  - (a) in the case of notice given under clause 25(3)(b) or (c), at least 10 **business days** before the **NSP** is **electrically connected**; and
  - (b) in every other case, at least 1 month before the **NSP** is **electrically connected** or the **ICP** is transferred.

- (3) If a **participant** gives notice under clause 25(1) of the creation of an **NSP**, the **distributor** on whose **network** the **NSP** is located must give the **reconciliation manager** the following information:
- (a) if the **NSP** is to be located in a new **balancing area** to be created—
    - (i) all relevant details necessary for the **balancing area** to be created; and
    - (ii) notice that the **NSP** to be created is to be assigned to the new **balancing area**; and
  - (b) in every other case, notice of the **balancing area** in which the **NSP** is located.
- (4) If a **participant** gives notice under clause 25(1) or (2) of a creation or transfer that relates to an **NSP** between a **network** and an **embedded network**, the **distributor** who owns the **embedded network** must give written notice to the **reconciliation manager** of the following:
- (a) the **network** on which the **NSP** will be located after the creation or transfer;
  - (b) the **ICP identifier** for the **ICP** that connects the **network** and the **embedded network**;
  - (c) the date on which the creation or transfer will take effect.
- (5) The **distributor** must give the notice at least 1 month before the creation or transfer.

Compare: Electricity Governance Rules 2003 clause 9 schedule E1

Clause 26(1): amended, on 5 October 2017, by clause 239(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 26(2): amended, on 5 October 2017, by clause 239(2) and (3) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 26(2)(a) and (b): amended, on 23 February 2015, by clause 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 26(3): amended, on 21 September 2012, by clause 15(4) of the Electricity Industry Participation (Minor Amendments) Code Amendment 2012.

Clause 26(3): amended, on 5 October 2017, by clause 239(4) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 26(4): amended, on 5 October 2017, by clause 239(1) and (5) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 26(5): amended, on 5 October 2017, by clause 239(3) and (6) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

## 27 Information to be provided if ICPs become NSPs

- (1) If a transfer for which notice is given under clause 25 results in an **ICP** becoming an **NSP** at which an **embedded network** connects to a **network**, or in an **ICP** becoming an **NSP** that is an **interconnection point**, the **distributor** who owns the **network** on which the **NSP** will be located after the change must give written notice to any **trader** trading at the **ICP** of the transfer.
- (2) The **distributor** must give the notice at least 1 month before the transfer.

Compare: Electricity Governance Rules 2003 clause 10 schedule E1

Clause 27(1): amended, on 5 October 2017, by clause 240(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 27(2): amended, on 5 October 2017, by clause 240(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

## 28 Reconciliation manager to allocate new identifiers

The **reconciliation manager** must, within 1 **business day** of receiving notice under clause 25(1) or (2), allocate a unique **NSP identifier** to each **point of connection** or

**interconnection point** to which the notice relates in accordance with the following format:

bbbqqqz nnnn

where

bbbqqqz is, in the case of a **local network**, the code for the **GXP** or **GIP** or, in the case of an **embedded network** or the **point of connection** between 2 **local networks**, the code for the **point of connection** to its parent **network**

where

bbb is a combination of 3 alpha characters that form a unique location identifier

qqq is the voltage in kV of the supply bus

z is a numeral allocated to distinguish it from any other supply bus of the same voltage at the same location

nnnn is a **participant identifier** for the **network** owner who from time to time owns the **network** being supplied.

Compare: Electricity Governance Rules 2003 clause 11 schedule E1  
Clause 28: amended, on 5 October 2017, by clause 241 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

## 29 Obligations concerning change in network owner

- (1) If a **network** owner acquires all or part of an existing **network**, the **network** owner must give written notice to the following of the acquisition:
  - (a) the previous **network** owner;
  - (b) the **reconciliation manager**;
  - (c) the **Authority**;
  - (d) every **reconciliation participant** who trades at an **ICP** connected to the **network** or part of the **network** acquired.
- (2) The **network** owner must give the notice at least 1 month before the acquisition.
- (3) The notice must specify—
  - (a) the **ICP identifiers** for which the **network** owner's **participant identifier** must be amended to reflect the acquisition of the **network** or part of the **network** by the **network** owner; and
  - (b) the effective date of the acquisition.
- (4) A **network** owner who acquires all or part of an existing **network** must comply with Schedule 11.2.

Compare: Electricity Governance Rules 2003 clause 12 schedule E1

Clause 29(1): amended, on 5 October 2017, by clause 242(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 29(1)(d): amended, on 23 February 2015, by clause 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 29(2): amended, on 5 October 2017, by clause 242(2) and (3) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 29(3): amended, on 5 October 2017, by clause 242(3) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### **30 Reconciliation manager to advise registry manager**

- (1) The **reconciliation manager** must—
  - (a) advise the **registry manager** of any new or deleted **NSP identifier** no later than 1 **business day** after receiving notice of its creation or deletion; and
  - (b) advise the **registry manager** of any changes to supporting **NSP** information provided by a **distributor** in accordance with clause 26(4) no later than 1 **business day** after receiving the notice.
- (2) The **registry manager** must **publish** an updated schedule of all **NSP identifiers** and supporting information within 1 **business day** of receiving notice in accordance with subclause (1).

Compare: Electricity Governance Rules 2003 clause 13 schedule E1

Clause 30 Heading: amended, on 5 October 2017, by clause 243(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 30(1): amended, on 5 October 2017, by clause 243(2) and (3) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 30(2): amended, on 5 October 2017, by clause 243(3) and (4) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

## Schedule 11.2 Transfer of ICPs between distributors' networks

cls 25 and 29 of Schedule 11.1

- 1 This Schedule applies if a **distributor** (the applicant **distributor**) wishes to change the record in the **registry** of an **ICP** that is not recorded as being usually connected to an **NSP** in the **distributor's network**, so that the **ICP** is recorded as being usually connected to an **NSP** in the applicant **distributor's network** (a "transfer").

Compare: Electricity Governance Rules 2003 clause 1 schedule E1A

Clause 1: amended, on 23 February 2015, by clause 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 1: amended, on 5 October 2017, by clause 244 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

- 2 The applicant **distributor** must give written notice to the **Authority** of the transfer.

Compare: Electricity Governance Rules 2003 clause 2 schedule E1A

Clause 2: amended, on 5 October 2017, by clause 245 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

- 3 The notice must be in the **prescribed form**.

Compare: Electricity Governance Rules 2003 clause 3 schedule E1A

Clause 3: amended, on 5 October 2017, by clause 246 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

- 4 The notice must be given no later than **3 business days** before the transfer takes effect.

Compare: Electricity Governance Rules 2003 clause 4 schedule E1A

Clause 4: amended, on 5 October 2017, by clause 247 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

- 5 The applicant **distributor** must give the **Authority** confirmation that the applicant **distributor** has received written consent to the proposed transfer from—

- (a) the **distributor** whose **network** is associated with the **NSP** to which the **ICP** is recorded as being connected immediately before the notice, except if the notice relates to the creation of an **embedded network**; and
- (b) every **trader** who trades **electricity** at any **ICP** nominated at the time of notice as being supplied from the same **NSP** to which the notice relates.

Compare: Electricity Governance Rules 2003 clause 5 schedule E1A

Clause 5(a): amended, on 23 February 2015, by clause 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 5: amended, on 5 October 2017, by clause 248 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

- 6 If a notice relates to an **embedded network**, it must relate to every **ICP** on the **embedded network**.

Compare: Electricity Governance Rules 2003 clause 6 schedule E1A

Clause 6: amended, on 5 October 2017, by clause 249 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

- 7 The **Authority** must not authorise the change of any information in the **registry** if clauses 2 to 5 are not complied with.  
Compare: Electricity Governance Rules 2003 clause 7 schedule E1A  
Clause 7: amended, on 29 August 2013, by clause 10 of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2013.  
Clause 7: amended, on 15 May 2014, by clause 27 of the Electricity Industry Participation (Minor Code Amendments) Code Amendment 2014.  
Clause 7: amended, on 5 October 2017, by clause 250 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.
- 7A Despite clause 7, the **Authority** may authorise the change if the applicant **distributor** has not given written notice to the **Authority** within the time frame required under clause 4, if—  
(a) the applicant **distributor** has complied with clauses 2, 3 and 5; and  
(b) the **Authority** considers that it has not been materially disadvantaged by the applicant **distributor's** failure to comply with clause 4.  
Clause 7A: inserted, on 15 May 2014, by clause 28 of the Electricity Industry Participation (Minor Code Amendments) Code Amendment 2014.  
Clause 7A: amended, on 5 October 2017, by clause 251 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.
- 8 The notice must include any information requested by the **Authority** from time to time.  
Compare: Electricity Governance Rules 2003 clause 8 schedule E1A  
Clause 8: amended, on 5 October 2017, by clause 252 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.
- 9 The **registry manager** must remove from the **registry** any information the **registry manager** has received under clause 7 of Schedule 11.1 if the information—  
(a) relates to an **ICP** for which an applicant **distributor** has given written notice of a transfer under this Schedule; and  
(b) was to come into effect after the date on which the **Authority** authorises the change of information in the **registry** under this Schedule.  
Compare: Electricity Governance Rules 2003 clause 9 schedule E1A  
Clause 9: replaced, on 5 October 2017, by clause 253 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.
- 10 A transfer may take effect on a date that is before the date on which the notice is given only with the consent of the **Authority**.  
Compare: Electricity Governance Rules 2003 clause 10 schedule E1A  
Clause 10: amended, on 5 October 2017, by clause 254 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.
- 11 Each **reconciliation participant** must take a **validated meter reading** or **permanent estimate** on the date a transfer becomes effective for use in the creation of the **reconciliation participant's** submission file, unless the **Authority** authorises the **reconciliation manager** to provide additional **seasonal adjustment shapes** under clause 12.  
Compare: Electricity Governance Rules 2003 clause 11 schedule E1A

- 12 The **Authority** may authorise the **reconciliation manager** to provide additional **seasonal adjustment shapes** for use in the creation of each **reconciliation participant's** submission file.

Compare: Electricity Governance Rules 2003 clause 12 schedule E1A

## Schedule 11.3 Switching

cl 11.15

### *Overview*

Cross heading: inserted on 9 October 2015, by clause 5(1) of the Electricity Industry Participation Code Amendment (ICP Switching) 2014.

#### 1A Overview of Schedule

This Schedule prescribes 3 processes for switching **ICPs** as follows:

- (a) a standard switch process that applies in the circumstances described in clause 1(1):
- (b) a switch move process that applies in the circumstances described in clause 8(1):
- (c) a gaining **trader** switch process that applies in the circumstances described in clause 13(1).

Clause 1A: inserted on 9 October 2015, by clause 5(2) of the Electricity Industry Participation Code Amendment (ICP Switching) 2014.

### *Standard switch process*

Cross heading: amended on 9 October 2015, by clause 6 of the Electricity Industry Participation Code Amendment (ICP Switching) 2014.

#### 1 Standard switch process for ICPs

- (1) A standard switch process applies when a **trader** (the "gaining **trader**") has an arrangement with a **customer** or **embedded generator** to commence trading **electricity** with the **customer** or **embedded generator** at, or to otherwise assume responsibility under clause 11.18(1) for, an **ICP** at which another **trader** (the "losing **trader**") trades **electricity**, and the gaining **trader** switch process under clauses 13 to 16 does not apply.
- (1A) This clause and clauses 2 to 7 apply to a standard switch process.
- (2) If subpart 2 of Part 4A of the Fair Trading Act 1986 applies to an arrangement described in subclause (1),—
  - (a) the gaining **trader** must identify the period within which the **customer** or **embedded generator** may cancel the arrangement in accordance with section 36M of the Fair Trading Act 1986; and
  - (b) for the purpose of this Schedule, the arrangement is deemed to come into effect on the day after the expiry of the period.

Compare: Electricity Governance Rules 2003 clauses 1.1A and 1.1B schedule E2  
Clause 1 Heading: amended, on 29 August 2013, by clause 11(1) of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2013.

Clause 1 Heading: amended on 9 October 2015, by clause 7(1) of the Electricity Industry Participation Code Amendment (ICP Switching) 2014.

Clause 1(1) and 1(1A): substituted on 9 October 2015, by clause 7(2) of the Electricity Industry Participation Code Amendment (ICP Switching) 2014.

Clause 1(1)(a): substituted, on 29 August 2013, by clause 11(2) of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2013.

Clause 1(2): amended, on 6 November 2014, by clause 7(3) of the Electricity Industry Participation Code Amendment (ICP Switching) 2014.

Clause 1(2)(a): amended, on 6 November 2014, by clause 7(4) of the Electricity Industry Participation Code Amendment (ICP Switching) 2014.



## **2 Gaining trader advises registry manager of standard switch request**

- (1) For each **ICP** to which a switch relates, the gaining **trader** must advise the **registry manager** of the switch no later than **2 business days** after the arrangement with the **customer** or **embedded generator** comes into effect.
- (2) The gaining **trader** must include in its advice to the **registry manager**—
  - (a) *[Revoked]*
  - (b) that the switch type is **TR**; and
  - (c) **1** or more **profile** codes of a **profile** at the **ICP**.

Compare: Electricity Governance Rules 2003 clause 1.1 schedule E2

Clause 2 Heading: substituted on 9 October 2015, by clause 8(1) of the Electricity Industry Participation Code Amendment (ICP Switching) 2014.

Heading: amended, on 5 October 2017, by clause 255(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 2(1) and (2): amended, on 5 October 2017, by clause 255(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 2(2): inserted on 9 October 2015, by clause 8(2) of the Electricity Industry Participation Code Amendment (ICP Switching) 2014.

Clause 2(2)(a): revoked on 9 October 2015, by clause 4 of the Electricity Industry Participation Code Amendment (ICP Switching) 2015.

## **3 Losing trader response to standard switch request**

No later than **3 business days** after receiving notice of a switch request from the **registry manager** under clause 22(a), the losing **trader** must,—

- (a) either—
  - (i) acknowledge the switch request by providing the following information to the **registry manager**:
    - (A) the proposed **event date**; and
    - (B) a valid switch response code approved by the **Authority**; or
  - (ii) provide the final information specified in clause 5(a) to (c) to complete the switch; or
- (b) *[Revoked]*
- (c) request that the switch be withdrawn in accordance with clause 17.

Compare: Electricity Governance Rules 2003 clause 1.2 schedule E2

Clause 3: substituted on 9 October 2015, by clause 9 of the Electricity Industry Participation Code Amendment (ICP Switching) 2014.

Clause 3: amended, on 5 October 2017, by clause 256 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 3(a): substituted on 9 October 2015, by clause 5(1) of the Electricity Industry Participation Code Amendment (ICP Switching) 2015.

Clause 3(b): revoked on 9 October 2015, by clause 5(2) of the Electricity Industry Participation Code Amendment (ICP Switching) 2015.

## **4 Event dates**

- (1) The losing **trader** must establish **event dates** so that—
  - (a) no **event date** is more than **10 business days** after the date on which the losing **trader** receives notice from the **registry manager** in accordance with clause 22(a); and

- (b) in any 12 month period at least 50% of the **event dates** established by the losing **trader** are no more than 5 **business days** after the date on which the losing **trader** receives notice from the **registry manager** in accordance with clause 22(a).
- (2) When establishing an **event date** under this clause, the losing **trader** must disregard every **event date** established by the losing **trader** for a **customer** who, at the time that the **event date** is established, has been a **customer** of the losing **trader** for less than 2 months.

Compare: Electricity Governance Rules 2003 clause 1.2A schedule E2

Clause 4(1): amended on 9 October 2015, by clause 6 of the Electricity Industry Participation Code Amendment (ICP Switching) 2015.

Clause 4(1): amended, on 5 October 2017, by clause 257(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 4(1)(a): amended, on 15 May 2014, by clause 29 of the Electricity Industry Participation (Minor Code Amendments) Code Amendment 2014.

Clause 4(2): amended on 9 October 2015, by clause 10 of the Electricity Industry Participation Code Amendment (ICP Switching) 2014.

Clause 4(2): amended, on 5 October 2017, by clause 257(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

## 5 Losing trader must provide final information

If the losing **trader** has provided information under clause 3(a)(i) rather than under clause 3(a)(ii), no later than 5 **business days** after the **event date**, the losing **trader** must complete the switch by providing final information to the **registry manager**, including—

- (a) the **event date**; and
- (b) a **switch event meter reading** as at the **event date** for each **meter** or **data storage device** that is recorded in the **registry** with an accumulator type of C and a settlement indicator of Y; and
- (c) if the **switch event meter reading** is not a **validated meter reading**, the date of the last **meter reading** of the **meter** or **data storage device** described in paragraph (b).

Compare: Electricity Governance Rules 2003 clause 1.3 schedule E2

Clause 5: substituted on 9 October 2015, by clause 11 of the Electricity Industry Participation Code Amendment (ICP Switching) 2014.

Clause 5: amended on 9 October 2015, by clause 7 of the Electricity Industry Participation Code Amendment (ICP Switching) 2015.

Clause 5: amended, on 5 October 2017, by clause 258 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

## 6 Traders must use same reading

- (1) The losing **trader** and the gaining **trader** must both use the same **switch event meter reading** for the **event date** as determined by the following procedure:
  - (a) if the **switch event meter reading** provided by the losing **trader** differs by less than 200 kWh from a value established by the gaining **trader**, the gaining **trader** must use the losing **trader's switch event meter reading**; or
  - (b) if the **switch event meter reading** provided by the losing **trader** differs by 200 kWh or more from a value established by the gaining **trader**, the gaining **trader** may dispute the **switch event meter reading**.
- (2) Despite subclause (1), subclause (3) applies if—

- (a) the losing **trader** trades **electricity** at the **ICP** through a **metering installation** with a submission type of non **half hour** in the **registry**; and
  - (b) the gaining **trader** will trade **electricity** at the **ICP** through a **metering installation** with a submission type of **half hour** in the **registry**, as a result of the gaining **trader's** arrangement with the **customer** or **embedded generator**; and
  - (c) a **switch event meter reading** provided by the losing **trader** under subclause (1) has not been obtained from an **interrogation** of a **certified metering installation** with an AMI flag of Y in the **registry**.
- (3) No later than 5 **business days** after receiving final information from the **registry manager** under clause 22(d),—
- (a) the gaining **trader** may provide the losing **trader** with a **switch event meter reading** obtained from an **interrogation** of a **certified metering installation** with an AMI flag of Y in the **registry**; and
  - (b) the losing **trader** must use that **switch event meter reading**.

Compare: Electricity Governance Rules 2003 clause 1.4 schedule E2

Clause 6: amended on 9 October 2015, by clause 12(1) of the Electricity Industry Participation Code Amendment (ICP Switching) 2014.

Clause 6(a): amended on 9 October 2015, by clause 12(2) of the Electricity Industry Participation Code Amendment (ICP Switching) 2014.

Clause 6(b): substituted on 9 October 2015, by clause 12(3) of the Electricity Industry Participation Code Amendment (ICP Switching) 2014.

Clause 6(2) and (3): inserted on 9 October 2015, by clause 8 of the Electricity Industry Participation Code Amendment (ICP Switching) 2015.

Clause 6(3): amended, on 5 October 2017, by clause 259 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

## **6A Gaining trader disputes reading**

- (1) If a gaining **trader** disputes a **switch event meter reading** under clause 6(1)(b), the gaining **trader** must, no later than 4 months after the **event date**, provide to the losing **trader** a revised **switch event meter reading** supported by 2 **validated meter readings**.
- (2) On receipt of a revised **switch event meter reading** from the gaining **trader** under subclause (1), the losing **trader** must either,—
  - (a) if the losing **trader** accepts the revised **switch event meter reading**, or does not respond to the gaining **trader**, use the revised **switch event meter reading**; or
  - (b) if the losing **trader** does not accept the revised **switch event meter reading**, advise the gaining **trader** (giving all relevant details) no later than 5 **business days** after receiving the revised **switch event meter reading**.

Clause 6A: inserted on 9 October 2015, by clause 13 of the Electricity Industry Participation Code Amendment (ICP Switching) 2014.

Clause 6A Heading: amended on 9 October 2015, by clause 9(a) of the Electricity Industry Participation Code Amendment (ICP Switching) 2015.

Clause 6A: amended on 9 October 2015, by clause 9(b) and (c) of the Electricity Industry Participation Code Amendment (ICP Switching) 2015.

Clause 6A: replaced, on 5 October 2017, by clause 260 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

## **7 Disputes**

- (1) A losing **trader** or a gaining **trader** may give written notice to the other **trader** that it disputes a **switch event meter reading** provided under clauses 1 to 6.

- (2) The dispute must be resolved in accordance with the disputes procedure in clause 15.29 (with all necessary amendments).

Compare: Electricity Governance Rules 2003 clause 1.5 schedule E2

Clause 7(1): amended on 9 October 2015, by clause 14 of the Electricity Industry Participation Code Amendment (ICP Switching) 2014.

Clause 7(1): amended, on 5 October 2017, by clause 261 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### *Switch move process*

## **8 Switch move process for ICPs**

- (1) A switch move process applies when a **trader** (the “gaining **trader**”) has an arrangement with a **customer** or **embedded generator** to commence trading **electricity** with the **customer** or **embedded generator** at, or to otherwise assume responsibility under clause 11.18(1) for, an **ICP** for which no **trader** has an agreement to trade **electricity** and the gaining **trader** switch process under clauses 13 to 16 does not apply.
- (1A) This clause and clauses 9 to 12 apply to a switch move process.
- (2) If subpart 2 of Part 4A of the Fair Trading Act 1986 applies to an arrangement described in subclause (1)—
- (a) the gaining **trader** must identify the period within which the **customer** or **embedded generator** may cancel the arrangement in accordance with section 36M of the Fair Trading Act 1986; and
  - (b) for the purpose of this Schedule, the arrangement is deemed to come into effect on the day after the expiry of the period.

Compare: Electricity Governance Rules 2003 clauses 2.1A and 2.1B schedule E2

Clause 8 Heading: amended, on 29 August 2013, by clause 12(1) of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2013.

Clause 8(1) and 8(1A): substituted on 9 October 2015, by clause 15 of the Electricity Industry Participation Code Amendment (ICP Switching) 2014.

Clause 8(1)(a): substituted, on 29 August 2013, by clause 12(2) of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2013.

Clause 8(2): amended, on 6 November 2014, by clause 15(2) of the Electricity Industry Participation Code Amendment (ICP Switching) 2014.

Clause 8(2)(a): amended, on 6 November 2014, by clause 15(3) of the Electricity Industry Participation Code Amendment (ICP Switching) 2014.

## **9 Gaining trader informs registry manager of switch request**

- (1) For each **ICP** to which a switch relates, the gaining **trader** must advise the **registry manager** of the switch request no later than 2 **business days** after the arrangement with the **customer** or **embedded generator** comes into effect.
- (2) The gaining **trader** must include in its advice to the **registry manager**—
- (a) a proposed **event date**; and
  - (b) that the switch type is **MI**; and
  - (c) 1 or more **profile codes** of a **profile** at the **ICP**.

Compare: Electricity Governance Rules 2003 clause 2.1 schedule E2

Clause 9 Heading: amended, on 5 October 2017, by clause 262(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 9(1): amended, on 9 October 2015, by clause 16(1)(a) and 16(1)(b) of the Electricity Industry Participation Code Amendment (ICP Switching) 2014.

Clause 9(2): inserted, on 9 October 2015, by clause 16(2) of the Electricity Industry Participation Code Amendment (ICP Switching) 2014.

Clause 9(1) and (2): amended, on 5 October 2017, by clause 262(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

## **10 Losing trader response to switch move request**

- (1) After receiving notice of a switch request from the **registry manager** under clause 22(a), the **trader** that is recorded in the **registry** as being responsible for the **ICP** (the “losing **trader**”) must, no later than 5 **business days** after receiving the notice,—
- (a) if the losing **trader** accepts the **event date** proposed by the gaining **trader**, complete the switch by providing to the **registry manager**—
- (i) *[Revoked]*
- (ia) confirmation of the **event date**; and
- (ib) a valid switch response code approved by the **Authority**; and
- (ii) final information in accordance with clause 11; or
- (b) if the losing **trader** does not accept the **event date** proposed by the gaining **trader**, acknowledge the switch request to the **registry manager** and determine a different **event date** that—
- (i) is not earlier than the gaining **trader’s** proposed **event date**; and
- (ii) is no later than 10 **business days** after the date the losing **trader** receives the notice; or
- (c) request that the switch be withdrawn in accordance with clause 17.
- (2) If the losing **trader** determines a different **event date** under subclause (1)(b), the losing **trader** must also complete the switch by providing to the **registry manager** the information described in subclause (1)(a), but in that case the **event date** is the **event date** determined by the losing **trader**.

Compare: Electricity Governance Rules 2003 clause 2.2 schedule E2

Clause 10: substituted, on 9 October 2015, by clause 17 of the Electricity Industry Participation Code Amendment (ICP Switching) 2014.

Clause 10(1): amended, on 9 October 2015, by clause 10(1) of the Electricity Industry Participation Code Amendment (ICP Switching) 2015.

Clause 10(1): amended, on 5 October 2017, by clause 263(1), (2) and (3) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 10(1)(a)(i): revoked, on 9 October 2015, by clause 10(2)(a) of the Electricity Industry Participation Code Amendment (ICP Switching) 2015.

Clause 10(1)(a)(ia) and (ib): inserted, on 9 October 2015, by clause 10(2)(b) of the Electricity Industry Participation Code Amendment (ICP Switching) 2015.

Clause 10(1)(b): amended, on 9 October 2015, by clause 10(3) of the Electricity Industry Participation Code Amendment (ICP Switching) 2015.

Clause 10(1)(c): amended, on 9 October 2015, by clause 10(4) of the Electricity Industry Participation Code Amendment (ICP Switching) 2015.

Clause 10(2): amended, on 5 October 2017, by clause 263(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

## **11 Losing trader must provide final information**

The losing **trader** must provide final information to the **registry manager** for the purposes of clause 10(1)(a)(ii), including—

- (a) the **event date**; and

- (b) a **switch event meter reading** as at the **event date** for each **meter** or **data storage device** that is recorded in the **registry** with an accumulator type of C and a settlement indicator of Y; and
- (c) if the **switch event meter reading** is not a **validated meter reading**, the date of the last **meter reading** of the **meter** or **data storage device** described in paragraph (b).

Compare: Electricity Governance Rules 2003 clause 2.3 schedule E2

Clause 11: substituted, on 9 October 2015, by clause 17 of the Electricity Industry Participation Code Amendment (ICP Switching) 2014.

Clause 11: amended, on 9 October 2015, by clause 11 of the Electricity Industry Participation Code Amendment (ICP Switching) 2015.

Clause 11: amended, on 5 October 2017, by clause 264 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

## 12 Gaining trader may change switch event meter reading

- (1) The gaining **trader** may use the **switch event meter reading** supplied by the losing **trader** or may, at its own cost, obtain its own **switch event meter reading**.
- (2) If the gaining **trader** elects to use the new **switch event meter reading**, the gaining **trader** must advise the losing **trader** of the new **switch event meter reading** and the **event date** to which it refers as follows:
  - (a) if the **switch event meter reading** established by the gaining **trader** differs by less than 200 kWh from that provided by the losing **trader**, both **traders** must use the **switch event meter reading** provided by the gaining **trader**; or
  - (b) if the **switch event meter reading** provided by the losing **trader** differs by 200 kWh or more from a value established by the gaining **trader**, the gaining **trader** may dispute the **switch event meter reading**.
- (2A) Despite subclauses (1) and (2), subclause (2B) applies if—
  - (a) the losing **trader** trades **electricity** at the **ICP** through a **metering installation** with a submission type of non **half hour** in the **registry**; and
  - (b) the gaining **trader** will trade **electricity** at the **ICP** through a **metering installation** with a submission type of **half hour** in the **registry**, as a result of the gaining **trader's** arrangement with the **customer** or **embedded generator**; and
  - (c) a **switch event meter reading** provided by the losing **trader** under subclause (1) has not been obtained from an **interrogation** of a **certified metering installation** with an AMI flag of Y in the **registry**.
- (2B) No later than 5 **business days** after receiving final information from the **registry manager** under clause 22(d),—
  - (a) the gaining **trader** may provide the losing **trader** with a **switch event meter reading** obtained from an **interrogation** of a **certified metering installation** with an AMI flag of Y in the **registry**; and
  - (b) the losing **trader** must use that **switch event meter reading**
- (3) If the gaining **trader** disputes a **switch event meter reading** under subclause (2)(b), the gaining **trader** must, no later than 4 months after the actual **event date**, provide to the losing **trader** a changed **validated meter reading** or a **permanent estimate** supported by 2 **validated meter readings**, and the losing **trader** must either,—
  - (a) no later than 5 **business days** after receiving the **switch event meter reading** from the gaining **trader**, the losing **trader**, if it does not accept the **switch event**

**meter reading**, must advise the gaining **trader** (giving all relevant details), and the losing **trader** and the gaining **trader** must use reasonable endeavours to resolve the dispute in accordance with the disputes procedure contained in clause 15.29 (with all necessary amendments); or

- (b) if the losing **trader** advises its acceptance of the **switch event meter reading** received from the gaining **trader**, or does not provide any response, the losing **trader** must use the **switch event meter reading** supplied by the gaining **trader**.

Compare: Electricity Governance Rules 2003 clause 2.4 schedule E2

Clause 12 Heading: amended, on 9 October 2015, by clause 18(1) of the Electricity Industry Participation Code Amendment (ICP Switching) 2014.

Clause 12(1) and (3): amended, on 9 October 2015, by clause 18(2) of the Electricity Industry Participation Code Amendment (ICP Switching) 2014.

Clause 12(2): substituted, on 9 October 2015, by clause 18(3) of the Electricity Industry Participation Code Amendment (ICP Switching) 2014.

Clause 12(2), (2B) and (3): amended, on 5 October 2017, by clause 265 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 12(2A) and (2B): inserted, on 9 October 2015, by clause 12 of the Electricity Industry Participation Code Amendment (ICP Switching) 2015.

Clause 12(3): amended, on 9 October 2015, by clause 18(4) of the Electricity Industry Participation Code Amendment (ICP Switching) 2014.

Clause 12(3)(a): amended, on 9 October 2015, by clause 18(5) of the Electricity Industry Participation Code Amendment (ICP Switching) 2014.

Clause 12(3)(b): amended, on 9 October 2015, by clause 18(6) of the Electricity Industry Participation Code Amendment (ICP Switching) 2014.

#### *Gaining trader switch process*

Cross heading: amended, on 9 October 2015, by clause 19 of the Electricity Industry Participation Code Amendment (ICP Switching) 2014.

### **13 Gaining trader switch processes**

- (1) A gaining **trader** switch process applies when a **trader** (the “gaining **trader**”) has an arrangement with a **customer** or **embedded generator** to—
- (a) trade **electricity** through—
- (i) a **half-hour metering installation** (not being a **category 1 metering installation** or a **category 2 metering installation**) at an **ICP** with a submission type of **half hour** in the **registry** and an AMI flag of "N" at which another **trader** (the "losing **trader**") trades **electricity** through a **half-hour metering installation** with the same submission type and AMI flag; or
- (ii) a **half-hour metering installation** at an **ICP** with a submission type of **half hour** in the **registry** and an AMI flag of "N" at which another **trader** (the "losing **trader**") trades **electricity** through a non **half-hour metering installation** with the **customer** or **embedded generator** with a submission type of non **half hour** in the **registry** and an AMI flag of "N"; or
- (iii) a non **half-hour metering installation** at an **ICP** at which another **trader** (the "losing **trader**") trades **electricity** through a **half-hour metering installation** with an AMI flag of "N" with the **customer** or **embedded generator**; or

- (b) assume responsibility under clause 11.18(1) for an **ICP** described in paragraph (a).
- (1A) This clause and clauses 14 to 16 apply to a gaining **trader** switch process.
- (2) If subpart 2 of Part 4A of the Fair Trading Act 1986 applies to an arrangement described in subclause (1)—
  - (a) the gaining **trader** must identify the period within which the **customer** or **embedded generator** may cancel the arrangement in accordance with section 36M of the Fair Trading Act 1986; and
  - (b) for the purpose of this Schedule, the arrangement is deemed to come into effect on the day after the expiry of the period.

Compare: Electricity Governance Rules 2003 clauses 3.1 and 3.1A schedule E2

Clause 13 Heading: amended, on 9 October 2015, by clause 20(1) of the Electricity Industry Participation Code Amendment (ICP Switching) 2014.

Clause 13(1): amended, on 9 October 2015, by clause 20(2) of the Electricity Industry Participation Code Amendment (ICP Switching) 2014.

Clause 13(1)(a): substituted, on 29 August 2013, by clause 13 of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2013.

Clause 13(1)(a)(i): amended, on 9 October 2015, by clause 13(a) and (b) of the Electricity Industry Participation Code Amendment (ICP Switching) 2015.

Clause 13(1)(a)(i) and (1)(a)(ii): amended, on 5 October 2017, by clause 266 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 13(1)(b): amended, on 9 October 2015, by clause 20(3) of the Electricity Industry Participation Code Amendment (ICP Switching) 2014.

Clause 13(1A): inserted, on 9 October 2015, by clause 20(4) of the Electricity Industry Participation Code Amendment (ICP Switching) 2014.

Clause 13(2): amended, on 6 November 2014, by clause 20(5) of the Electricity Industry Participation Code Amendment (ICP Switching) 2014.

Clause 13(2)(a): amended, on 6 November 2014, by clause 20(6) of the Electricity Industry Participation Code Amendment (ICP Switching) 2014.

#### **14 Gaining trader informs registry manager of switch request**

- (1) For each **ICP** to which a switch relates, the gaining **trader** must advise the **registry manager** of the switch request no later than 3 **business days** after the arrangement with the **customer** or **embedded generator** comes into effect.
- (2) The gaining **trader** must include in its advice to the **registry manager**—
  - (a) a proposed **event date**; and
  - (b) that the switch type is HH.
- (3) Unless subclause (4) applies, the proposed **event date** must be a date that is after the date on which the gaining **trader** advises the **registry manager**.
- (4) The proposed **event date** may be a date that is before the date on which the gaining **trader** advises the **registry manager**, if—
  - (a) the proposed **event date** is in the same month as the date on which the gaining **trader** advises the **registry manager**; or
  - (b) the proposed **event date** is no more than 90 days before the date on which the gaining **trader** advises the **registry manager**, and the losing **trader** and gaining **trader** agree on the proposed **event date**.

Compare: Electricity Governance Rules 2003 clause 3.2 schedule E2

Clause 14 Heading: amended, on 5 October 2017, by clause 267(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 14: amended, on 5 October 2017, by clause 267(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.



Clause 14(1): amended, on 9 October 2015, by clause 21(1) of the Electricity Industry Participation Code Amendment (ICP Switching) 2014.

Clause 14(2), (3), and (4): inserted, on 9 October 2015, by clause 21(2) of the Electricity Industry Participation Code Amendment (ICP Switching) 2014.

## 15 Losing trader provides information

No later than 3 **business days** after the losing **trader** receives notice from the **registry manager** in accordance with clause 22(a), the losing **trader** must—

- (a) provide the **registry manager** with a valid switch response code approved by the **Authority**; or
- (b) request that the switch be withdrawn in accordance with clause 17.

Compare: Electricity Governance Rules 2003 clause 3.3 schedule E2

Clause 15: amended, on 9 October 2015, by clause 22(1) of the Electricity Industry Participation Code Amendment (ICP Switching) 2014.

Clause 15: amended, on 9 October 2015, by clause 14 of the Electricity Industry Participation Code Amendment (ICP Switching) 2015.

Clause 15: amended, on 5 October 2017, by clause 268 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 15(a): amended, on 9 October 2015, by clause 22(2) of the Electricity Industry Participation Code Amendment (ICP Switching) 2014.

Clause 15(b): amended, on 9 October 2015, by clause 22(3) of the Electricity Industry Participation Code Amendment (ICP Switching) 2014.

## 16 Gaining trader obligations

- (1) The gaining **trader** must complete the switch by advising the **registry manager** of the **event date** no later than 3 **business days** after receiving a valid switch response code from the **registry manager** under clause 22(c).
- (2) If the **ICP** is being **electrically disconnected** or if **metering** equipment is being removed, the gaining **trader** must either—
  - (a) give the losing **trader** or the **metering equipment provider** for the **ICP** an opportunity to **interrogate** the **metering installation** immediately before the **ICP** is **electrically disconnected** or the **metering** equipment is removed; or
  - (b) carry out an **interrogation** and, no later than 5 **business days** after the **metering installation** is **electrically disconnected** or removed, advise the losing **trader** of—
    - (i) the results of the **interrogation**; and
    - (ii) the **metering component** numbers for each data channel in the **metering installation**.

Compare: Electricity Governance Rules 2003 clause 3.4 schedule E2

Clause 16 Heading: amended, on 9 October 2015, by clause 23(1) of the Electricity Industry Participation Code Amendment (ICP Switching) 2014.

Clause 16(1): amended, on 9 October 2015, by clause 23(2) of the Electricity Industry Participation Code Amendment (ICP Switching) 2014.

Clause 16(1): amended, on 9 October 2015, by clause 15 of the Electricity Industry Participation Code Amendment (ICP Switching) 2015.

Clause 16(1) and (2): amended, on 5 October 2017, by clause 269 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 16(2): inserted, on 9 October 2015, by clause 23(3) of the Electricity Industry Participation Code Amendment (ICP Switching) 2014.

*Withdrawing a switch request*

**17 Withdrawal of switch requests**

A losing **trader** or gaining **trader** may request that a switch request be withdrawn at any time until the expiry of 2 months after the **event date**.

Compare: Electricity Governance Rules 2003 clause 3A schedule E2

Clause 17: amended, on 9 October 2015, by clause 24 of the Electricity Industry Participation Code Amendment (ICP Switching) 2014.

**18 Withdrawing a switch request**

If a **trader** requests the withdrawal of a switch under clause 17, the following provisions apply:

- (a) the **Authority** must determine the valid codes for withdrawing a switch request (“withdrawal advisory codes”);
- (b) the **Authority** must **publish** the withdrawal advisory codes;
- (c) for each **ICP**, the **trader** withdrawing the switch request must provide the **registry manager** with the following information:
  - (i) the **participant identifier** of the **trader**; and
  - (ii) the withdrawal advisory code **published** by the **Authority** in accordance with paragraph (b);
- (d) no later than 5 **business days** after receiving notice from the **registry manager** in accordance with clause 22(b), the **trader** receiving the withdrawal must advise the **registry manager** that the switch withdrawal request is accepted or rejected. A switch withdrawal request must not become effective until accepted by the **trader** who received the withdrawal;
- (e) on receipt of a rejection notice from the **registry manager** in accordance with paragraph (d), a **trader** may re-submit a switch withdrawal request for an **ICP** in accordance with paragraph (c). All switch withdrawal requests must be resolved no later than 10 **business days** after the date of the initial switch withdrawal request;
- (f) if a **trader** requests that a switch request be withdrawn and the resolution of that switch withdrawal request results in the switch proceeding, no later than 2 **business days** after receiving notice from the **registry manager** in accordance with clause 22(b), the losing **trader** must comply with clauses 3, 5, 10 and 11 (whichever is appropriate) and the gaining **trader** must comply with clause 16.

Compare: Electricity Governance Rules 2003 clause 4 schedule E2

Clause 18(b): amended, on 21 September 2012, by clause 16(1) of the Electricity Industry Participation (Minor Amendments) Code Amendment 2012.

Clause 18(c)(i): amended, on 21 September 2012, by clause 16(2) of the Electricity Industry Participation (Minor Amendments) Code Amendment 2012.

Clause 18(c) to (f): amended, on 5 October 2017, by clause 270 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 18(d), (e), and (f): amended, on 9 October 2015, by clause 25 of the Electricity Industry Participation Code Amendment (ICP Switching) 2014.

*Exchange of information*

**19 Participants to use file formats**

**Participants** who exchange information in accordance with this Schedule must use the file formats determined and **published** by the **Authority**.

Compare: Electricity Governance Rules 2003 clause 5.1 schedule E2

**20 Method of exchanging files**

- (1) The **Authority** may, from time to time, after consultation with **participants**, do all or any of the following:
- (a) determine the method by which **participants** exchange information;
  - (b) determine the file formats that **participants** must use to exchange information;
  - (c) alter the file formats or the method by which **participants** exchange information.
- (2) The **Authority** must **publish** the file formats.

Compare: Electricity Governance Rules 2003 clause 5.2 schedule E2

Clause 20(1): substituted, on 15 May 2014, by clause 30 of the Electricity Industry Participation (Minor Code Amendments) Code Amendment 2014.

**21 Metering information**

For each **interrogation** or **switch event meter reading** carried out in accordance with this Schedule,—

- (a) the **trader** who carries out the **interrogation** or **switch event meter reading** must ensure that the **interrogation** is as accurate as possible, or that the **switch event meter reading** is fair and reasonable (as the case may be); and
- (b) the cost of each **interrogation** or **switch event meter reading** must be met as follows:
  - (i) for each **interrogation** or **switch event meter reading** carried out in accordance with clauses 5(b) or 11(b) or (c), the cost must be met by the losing **trader**; and
  - (ii) in every other case, the cost must be met by the gaining **trader**.

Compare: Electricity Governance Rules 2003 clause 5.3 schedule E2

Clause 21: amended, on 9 October 2015, by clause 26(1) of the Electricity Industry Participation Code Amendment (ICP Switching) 2014.

Clause 21(a): amended, on 9 October 2015, by clause 26(2) of the Electricity Industry Participation Code Amendment (ICP Switching) 2014.

Clause 21(b), and (c): substituted, on 9 October 2015, by clause 26(3) of the Electricity Industry Participation Code Amendment (ICP Switching) 2014.

**22 Registry manager notices**

The **registry manager** must provide notice to **participants** required by this Schedule as follows:

- (a) on receipt of information about a switch request in accordance with clauses 2, 9 and 14, the **registry manager** must give written notice to the losing **trader** of the information received:

- (b) on receipt of information about a withdrawal request in accordance with clauses 18(c) and (d), the **registry manager** must give written notice to the other relevant **trader** of the information received:
- (c) on receipt of information about a switch acknowledgement in accordance with clauses 3(a) and 15, the **registry manager** must give written notice to the gaining **trader** of the information received:
- (d) on receipt of information about a switch completion in accordance with clauses 3(a)(ii), 5, 10 and 16, the **registry manager** must give written notice to the gaining **trader**, the losing **trader**, the **metering equipment provider**, and the relevant **distributor** of the information received.

Compare: Electricity Governance Rules 2003 clause 5.4 schedule E2

Clause 22 Heading: amended, on 5 October 2017, by clause 271(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 22: amended, on 5 October 2017, by clause 271(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 22(d): amended, on 29 August 2013, by clause 14 of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2013.

Clause 22(d): amended, on 9 October 2015, by clause 16 of the Electricity Industry Participation Code Amendment (ICP Switching) 2015.

## Schedule 11.4

cls 11.8A and 11.15A

### Metering equipment provider switching and registry metering records

Schedule 11.4: inserted on 29 August 2013, by clause 22 of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011.

#### 1 Metering equipment provider receives notice for ICP identifier

- (1) Within 10 **business days** of being advised by the **registry manager** under clause 11.18A, a **gaining metering equipment provider**,—
  - (a) must, if it intends to accept responsibility for each **metering installation** for the **ICP**—
    - (i) enter into an arrangement with the **trader**; and
    - (ii) advise the **registry manager** in the **prescribed form** that it accepts responsibility for each **metering installation** for the **ICP** and of the proposed date on which the **metering equipment provider** will assume responsibility for each **metering installation** for the **ICP**; or
  - (b) may, if it intends to decline responsibility for each **metering installation** for the **ICP**, advise the **registry manager** in the **prescribed form** that it declines to accept responsibility for each **metering installation** for the **ICP**.
- (2) The **registry manager** must, within 1 **business day** of a **metering equipment provider** advising under subclause (1)(b) that it declines to accept responsibility for each **metering installation** for the **ICP**, advise the **trader** of the declinature.
- (3) The **registry manager** must, within 1 **business day** of a **gaining metering equipment provider** advising of acceptance under subclause (1)(a), advise the following **participants** for the **ICP** of the acceptance and proposed date on which the **gaining metering equipment provider** will assume responsibility for each **metering installation** for the **ICP**:
  - (a) the **trader**; and
  - (b) the **distributor**; and
  - (c) if relevant, the **losing metering equipment provider**.

Clause 1 Heading: amended, on 5 October 2017, by clause 272(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 1(1): amended, on 29 August 2013, by clause 49 of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011, Amendment 2013 (No 2).

Clause 1: amended, on 5 October 2017, by clause 272(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

#### 2 Gaining metering equipment provider to advise registry manager of registry metering records

If the **metering equipment provider** who is responsible for a **metering installation** for an **ICP** changes, the **metering equipment provider** must, within 15 **business days** of becoming the **metering equipment provider** for the **metering installation**, advise the **registry manager** of the **registry metering records** for the **metering installation**.

Clause 2 Heading: amended, on 5 October 2017, by clause 273(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 2: amended, on 5 October 2017, by clause 273(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

**3 Metering equipment provider to advise registry manager of changes to registry metering records**

A **metering equipment provider** must advise the **registry manager** of the **registry metering records**, or any change to the **registry metering records**, for a **metering installation** for which it is responsible, no later than 10 **business days** following:

- (a) the **electrical connection** of an **ICP** that is not also an **NSP**;
- (b) any subsequent change in any matter covered by the **metering records**.

Clause 3 Heading: amended, on 5 October 2017, by clause 274(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 3: amended, on 5 October 2017, by clause 274(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 3(a): amended, on 29 August 2013, by clause 50 of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011, Amendment 2013 (No 2).

**4 Registry manager requirement to advise**

The **registry manager** must, within 1 **business day** of being advised—

- (a) under clauses 2 or 3, advise the **trader** and **distributor** of the **registry metering records**;
- (b) under clauses 3 or 6, advise—
  - (i) the **trader** and **distributor** of the details of the change to the **registry metering records**; and
  - (ii) the **losing metering equipment provider** of the date of change of the **metering equipment provider** for the **ICP identifier**.

Clause 4 Heading: amended, on 5 October 2017, by clause 275(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 4: amended, on 5 October 2017, by clause 275(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

**5 Changes to registry metering records for ICP identifier**

The **registry manager** must, within 1 **business day** of being advised of 1 or more of the following changes relating to an **ICP identifier** record, advise the **metering equipment provider** of the change:

- (a) the **trader participant identifier**;
- (b) the **distributor participant identifier**;
- (c) the settlement type;
- (d) the status of the **ICP**.

Clause 5 Heading: amended, on 5 October 2017, by clause 276(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 5: amended, on 5 October 2017, by clause 276(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

**6 Correction of errors in registry**

- (1) A **metering equipment provider** must, by 0900 hours on the 13<sup>th</sup> **business day** of each **reconciliation period**, obtain the following information from the **registry**:

- (a) a list of the **ICP identifiers** for the **ICPs** for the **metering installations** for which the **metering equipment provider** is recorded in the **registry** as being responsible; and

- (b) the **registry metering records** for each **ICP identifier** obtained under paragraph (a).
- (2) A **metering equipment provider** must, as soon as reasonably practicable but not later than 5 **business days** after it obtains the information under subclause (1), compare the information obtained with its own records.
- (3) If the **metering equipment provider** finds a discrepancy between the information obtained under subclause (1) and its own records, the **metering equipment provider** must, within 5 **business days** of becoming aware of the discrepancy,—
  - (a) correct its records that are in error; and
  - (b) advise the **registry manager** of any necessary changes to the **registry manager metering records**.

Clause 6(3)(b): amended, on 5 October 2017, by clause 277 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

## **7 Metering equipment provider to provide registry metering records to registry manager**

- (1) A **metering equipment provider** must, if required under this Part, provide to the **registry manager** the information indicated in Table 1 as being "Required", in the **prescribed form**, for each **metering installation** for which it is responsible.
- (2) Despite anything to the contrary in this Code (except clause 11.2) the **metering equipment provider** must—
  - (a) provide the information set out in Table 1 indicated as being required for **interim certified metering installations** to the **registry manager** for all **category 1 metering installations** for which it is responsible; and
  - (b) ensure that the **registry metering records** provided in accordance with this clause are, for not less than 50% of the **category 1 metering installations** for which it is responsible, complete, accurate, not misleading or deceptive, and not likely to mislead or deceive, by no later than 1 October 2014; and
  - (c) ensure that the **registry metering records** provided in accordance with this clause are, for each **category 1 metering installation** for which it is responsible, complete, accurate, not misleading or deceptive, and not likely to mislead or deceive, by no later than 1 April 2015.
- (3) The **metering equipment provider** must derive the information provided under subclause (2)(a) from—
  - (a) the **metering equipment provider's metering records**; or
  - (b) the **metering records** contained within the current **trader's** system.

Clause 7 Heading: amended, on 5 October 2017, by clause 278(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 7(1) and 2(a): amended, on 5 October 2017, by clause 278(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 7(2): amended, on 29 August 2013, by clause 51 of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011, Amendment 2013 (No 2).

**Table 1: Registry metering records**

The following table sets out the **registry metering records**:

No	Registry term	Description	Fully certified metering installation	Interim certified metering installation
For each <b>ICP identifier</b>				
1	the <b>metering equipment provider participant identifier</b>	<b>participant identifier</b>	Required	Required
For each <b>metering installation</b> for an <b>ICP</b>				
2	<b>metering installation</b> number	a sequential number that is unique to the <b>ICP's identifier</b> , to identify the <b>metering installation</b>	Required	Required
3	highest <b>metering</b> category	the category recorded in the <b>metering installation certification report</b>	Required	Required
4	<b>metering installation</b> location code	a code from the list of codes in the <b>registry</b> , that identifies the location of the <b>metering installation</b> on a premises	Required	Required
5	the <b>ATH participant identifier</b>	the <b>participant identifier</b> of the <b>ATH</b> who <b>certified</b> the <b>metering installation</b>	Required	Optional



No	Registry term	Description	Fully certified metering installation	Interim certified metering installation
6	<b>metering installation certification type</b>	the <b>certification</b> type of the <b>metering installation</b> which may be either <b>half hour</b> or non <b>half hour</b> identified in the <b>metering installation certification report</b>	Required	Required
7	<b>metering installation certification date</b>	the effective <b>certification</b> date identified in the <b>metering installation certification report</b>	Required	Optional
8	the <b>metering installation certification</b> expiry date	the <b>metering installation certification</b> expiry date, identified in the <b>metering installation certification report</b> , or the date that the <b>metering installation certification</b> is cancelled	Required	Required
9	<b>control device certification</b>	confirmation that the <b>control device</b> used in the <b>metering installation</b> is included in the <b>metering installation certification report</b>	Required	Optional

No	Registry term	Description	Fully certified metering installation	Interim certified metering installation
10	<b>certification</b> variations	(a) Does an exemption under the <b>Act</b> for the <b>metering installation</b> apply? (b) Has the alternate <b>measuring transformer certification</b> process been used?	Required	Optional
11	<b>certification</b> variations expiry date	the earlier of the expiry date of any <b>certification</b> variation under item 10	Required	Optional
12	<b>certification</b> number	the <b>certification</b> number assigned to a <b>metering installation's certification</b>	Required	Optional
13	maximum <b>interrogation</b> cycle	the maximum <b>interrogation</b> cycle for the <b>metering installation</b> included in its <b>certification report</b>	Required	Required

No	Registry term	Description	Fully certified metering installation	Interim certified metering installation
14	price code	if the <b>metering equipment provider</b> considers it relevant, an identifier that may be used to indicate the price that would apply to a lease for the use of the <b>metering installation</b>	Optional	Optional
The following details for each <b>metering component</b> in the <b>metering installation</b> for each <b>ICP</b>				
15	<b>metering component</b> type	an identifier used to identify the type of <b>metering component</b> in the <b>metering installation</b> selected from the list of codes in the <b>registry</b>	Required	Required
16	<b>metering component</b> identifier	an identifier visible on the installed <b>metering component</b> that is either the manufacturer's serial number or the owner's component asset number	Required	Required for <b>meter or data storage device</b> .  Optional for all other <b>metering components</b> .

No	Registry term	Description	Fully certified metering installation	Interim certified metering installation
17	<b>meter or data storage device type</b>	an identifier used to identify the type of <b>meter or data storage device</b> in the <b>metering installation</b> , which may be <b>half hour</b> , non <b>half hour</b> , or prepay selected from the list of codes in the <b>registry</b>	Required for <b>meter or data storage device</b> .	Required for <b>meter or data storage device</b> .
18	AMI type	an identifier to identify if the <b>metering component</b> is an advanced metering infrastructure device	Required for <b>meter or data storage device</b> .  Optional for all other <b>metering components</b> .	Required for <b>meter or data storage device</b> .  Optional for all other <b>metering components</b> .
19	<b>compensation factor</b>	the <b>compensation factor</b> , which in the case of a complex <b>compensation factor</b> , must be obtained from the <b>metering equipment provider</b>	Required for <b>meter or data storage device</b> . Optional for all other <b>metering components</b> .	Required for <b>meter or data storage device</b> . Optional for all other <b>metering components</b> .
20	owner of a <b>metering component</b>	a free text field to identify the owner of a <b>metering component</b> , which may be a <b>participant identifier</b> if the owner is a <b>participant</b>	Optional	Optional
21	removal date of a <b>meter or data storage device</b>	a date that a <b>meter or data storage device</b> is removed	Optional for <b>meter or data storage device</b>	Optional for <b>meter or data storage device</b>

Electricity Industry Participation Code 2010  
Schedule 11.4

No	Registry term	Description	Fully certified metering installation	Interim certified metering installation
The following details for each <b>metering component</b> identified in rows 15 to 21 above				
22	<b>metering component type</b>	the <b>metering component</b> type identifier selected from the list of codes in the <b>registry</b>	Required for <b>meter or data storage device</b> that returns any 1 or more of the following values as a result of an <b>interrogation</b> : (a) <b>active energy</b> : (b) <b>reactive energy</b> : (c) apparent energy: (d) apparent power.  Optional for all other <b>metering components</b> .	Required for <b>meter or data storage device</b> that returns any 1 or more of the following values as a result of an <b>interrogation</b> : (a) <b>active energy</b> : (b) <b>reactive energy</b> : (c) apparent energy: (d) apparent power.  Optional for all other <b>metering components</b> .
23	register number	a sequential number that identifies each data channel that is present in the <b>metering component</b>	Required for <b>meter or data storage device</b> that returns any 1 or more of the following values as a result of an <b>interrogation</b> : (a) <b>active energy</b> : (b) <b>reactive energy</b> : (c) apparent energy: (d) apparent power.  Optional for all other <b>metering components</b> .	Required for <b>meter or data storage device</b> that returns any 1 or more of the following values as a result of an <b>interrogation</b> : (a) <b>active energy</b> : (b) <b>reactive energy</b> : (c) apparent energy: (d) apparent power.  Optional for all other <b>metering components</b> .

No	Registry term	Description	Fully certified metering installation	Interim certified metering installation
24	number of dials	the number of dials or digits that relate to the data channel	<p>Required for <b>meter</b> or <b>data storage device</b> that returns any 1 or more of the following values as a result of an <b>interrogation</b>:</p> <p>(a) <b>active energy</b>: (b) <b>reactive energy</b>: (c) apparent energy: (d) apparent power.</p> <p>Optional for all other <b>metering components</b>.</p>	<p>Required for <b>meter</b> or <b>data storage device</b> that returns any 1 or more of the following values as a result of an <b>interrogation</b>:</p> <p>(a) <b>active energy</b>: (b) <b>reactive energy</b>: (c) apparent energy: (d) apparent power.</p> <p>Optional for all other <b>metering components</b>.</p>
25	register content code	an identifier for the contents of a channel or a data channel, selected from a list in the <b>registry</b>	<p>Required for <b>meter</b> or <b>data storage device</b> that returns any 1 or more of the following values as a result of an <b>interrogation</b>:</p> <p>(a) <b>active energy</b>: (b) <b>reactive energy</b>: (c) apparent energy: (d) apparent power.</p> <p>Optional for all other <b>metering components</b>.</p>	<p>Required for <b>meter</b> or <b>data storage device</b> that returns any 1 or more of the following values as a result of an <b>interrogation</b>:</p> <p>(a) <b>active energy</b>: (b) <b>reactive energy</b>: (c) apparent energy: (d) apparent power.</p> <p>Optional for all other <b>metering components</b>.</p>

No	Registry term	Description	Fully certified metering installation	Interim certified metering installation
26	period of availability	an identifier for the period of availability for which a <b>control device</b> is configured, selected from a list in the <b>registry</b>	Required for <b>meter</b> or <b>data storage device</b> that returns any 1 or more of the following values as a result of an <b>interrogation</b> : (a) <b>active energy</b> : (b) <b>reactive energy</b> : (c) apparent energy: (d) apparent power.  Optional for all other <b>metering components</b> .	Required for <b>meter</b> or <b>data storage device</b> that returns any 1 or more of the following values as a result of an <b>interrogation</b> : (a) <b>active energy</b> : (b) <b>reactive energy</b> : (c) apparent energy: (d) apparent power.  Optional for all other <b>metering components</b> .
27	unit of measurement	an identifier for the units recorded in a data channel, selected from a list in the <b>registry</b>	Required for <b>meter</b> or <b>data storage device</b> that returns any 1 or more of the following values as a result of an <b>interrogation</b> : (a) <b>active energy</b> : (b) <b>reactive energy</b> : (c) apparent energy: (d) apparent power.  Optional for all other <b>metering components</b> .	Required for <b>meter</b> or <b>data storage device</b> that returns any 1 or more of the following values as a result of an <b>interrogation</b> : (a) <b>active energy</b> : (b) <b>reactive energy</b> : (c) apparent energy: (d) apparent power.  Optional for all other <b>metering components</b> .

No	Registry term	Description	Fully certified metering installation	Interim certified metering installation
28	energy flow direction	an identifier for the import or export recording in the data channel, selected from a list in the <b>registry</b>	Required for <b>meter</b> or <b>data storage device</b> that returns any 1 or more of the following values as a result of an <b>interrogation</b> : (a) <b>active energy</b> : (b) <b>reactive energy</b> : (c) apparent energy: (d) apparent power.  Optional for all other <b>metering components</b> .	Required for <b>meter</b> or <b>data storage device</b> that returns any 1 or more of the following values as a result of an <b>interrogation</b> : (a) <b>active energy</b> : (b) <b>reactive energy</b> : (c) apparent energy: (d) apparent power.  Optional for all other <b>metering components</b> .
29	accumulator type	an identifier for either absolute or cumulative recording in the data channel, selected from a list in the <b>registry</b>	Required for <b>meter</b> or <b>data storage device</b> that returns any 1 or more of the following values as a result of an <b>interrogation</b> : (a) <b>active energy</b> : (b) <b>reactive energy</b> : (c) apparent energy: (d) apparent power.  Optional for all other <b>metering components</b> .	Required for <b>meter</b> or <b>data storage device</b> that returns any 1 or more of the following values as a result of an <b>interrogation</b> : (a) <b>active energy</b> : (b) <b>reactive energy</b> : (c) apparent energy: (d) apparent power.  Optional for all other <b>metering components</b> .



No	Registry term	Description	Fully certified metering installation	Interim certified metering installation
30	settlement indicator	<p>an identifier determined as follows:</p> <p>(a) if the relevant <b>meter</b> or <b>data storage device</b> has an AMI flag of "Y", the cumulative data channel identifier must be "Y" and the other data channel identifiers must be "N"; and</p> <p>(b) for any other <b>meter</b> or <b>data storage device</b>, or for a <b>control device</b>, the data channel identifier must be the appropriate identifier selected from the list in the <b>registry</b></p>	<p>Required for <b>meter</b> or <b>data storage device</b> that returns any 1 or more of the following values as a result of an <b>interrogation</b>:</p> <p>(a) <b>active energy</b>;</p> <p>(b) <b>reactive energy</b>;</p> <p>(c) apparent energy;</p> <p>(d) apparent power.</p> <p>Optional for all other <b>metering components</b>.</p>	<p>Required for <b>meter</b> or <b>data storage device</b> that returns any 1 or more of the following values as a result of an <b>interrogation</b>:</p> <p>(a) <b>active energy</b>;</p> <p>(b) <b>reactive energy</b>;</p> <p>(c) apparent energy;</p> <p>(d) apparent power.</p> <p>Optional for all other <b>metering components</b>.</p>
31	event reading	the event <b>meter</b> read of a <b>meter</b> or <b>data storage device</b>	Optional	Optional

Table 1: row 6, column 2 amended, on 5 October 2017, by clause 279(a) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Table 1: row 16 amended, on 29 August 2013, by clause 52(1) of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011, Amendment 2013 (No 2).

Table 1: row 19 amended, on 29 August 2013, by clause 52(2) of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011, Amendment 2013 (No 2).

**Electricity Industry Participation Code 2010**  
**Schedule 11.4**

---

Table 1: row 21 amended, on 29 August 2013, by clause 52(3) of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011, Amendment 2013 (No 2).

Table 1: row 21 replaced, on 5 October 2017, by clause 279(b) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Table 1: row 23 amended, on 15 May 2014, by clause 31 of the Electricity Industry Participation (Minor Code Amendments) Code Amendment 2014.

Table 1: row 30 amended, on 29 August 2013, by clause 5(1) of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011, Amendment 2013 (No 3).

Table 1: rows 22 to 30 substituted, on 1 February 2016, by clause 45 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

## Schedule 11.5

cl 11.15C

### Process for trader event of default

Schedule 11.5: inserted, on 16 December 2013, by clause 7 of the Electricity Industry Participation (Managing Retailer Default Situations) Code Amendment 2013.

Schedule 11.5, heading: amended, on 28 February 2015, by clause 8 of the Electricity Industry Participation Code Amendment (Trader Default) 2014.

#### 1 Purpose

The purpose of this Schedule is to set out the process that the **Authority** and each **participant** must comply with when the **Authority** is satisfied that a **trader** has committed an **event of default** under paragraph (a) or (b) or (f) or (h) of clause 14.41.

Clause 1: amended, on 28 February 2015, by clause 9 of the Electricity Industry Participation Code Amendment (Trader Default) 2014.

Clause 1: amended, on 24 March 2015, by clause 6 of the Electricity Industry Participation Code Amendment (Settlement and Prudential Security) 2014.

#### 2 Notice to trader who has committed event of default

- (1) If the **Authority** is satisfied that a **trader** ("defaulting trader") has committed an **event of default** under paragraph (a) or (b) or (f) or (h) of clause 14.41 the **Authority** must give written notice to the defaulting **trader** that—

- (a) the defaulting **trader** must—
- (i) remedy the **event of default**; or
  - (ii) assign its rights and obligations under every contract under which a **customer** of the defaulting **trader** purchases **electricity** from the defaulting **trader** to another **trader**, and assign to another **trader** all **ICPs** for which the defaulting **trader** is recorded in the **registry** as being responsible; and
- (b) if the defaulting **trader** does not comply with the requirements set out in paragraph (a) within 7 days of the notice, clause 4 will apply.

- (2) The **Authority** may give written notice to the defaulting **trader** requiring the defaulting **trader** to provide to the **Authority**, within a time specified by the **Authority**, information about the defaulting **trader's customers**.

- (3) The defaulting **trader** must provide the information requested by the **Authority** under subclause (2) within the time specified by the **Authority**.

Clause 2, heading: amended, on 28 February 2015, by clause 10(1) of the Electricity Industry Participation Code Amendment (Trader Default) 2014.

Clause 2(1): amended, on 28 February 2015, by clause 10(2) of the Electricity Industry Participation Code Amendment (Trader Default) 2014.

Clause 2(1): amended, on 24 March 2015, by clause 7 of the Electricity Industry Participation Code Amendment (Settlement and Prudential Security) 2014.

Clause 2(1) and (2): amended, on 5 October 2017, by clause 280 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 2(2): amended, on 28 February 2015, by clause 10(3) of the Electricity Industry Participation Code Amendment (Trader Default) 2014.

Clause 2(3): amended, on 28 February 2015, by clause 10(4) of the Electricity Industry Participation Code Amendment (Trader Default) 2014.

#### 3 Authority may require distributor and registry manager to provide information

- (1) The **Authority** may, by notice in writing to a **distributor** on whose **network** a defaulting **trader** trades **electricity**, require the **distributor** to provide to the **Authority**

the information about the defaulting **trader's customers** specified in the notice (if the **distributor** holds the information), within the period specified in the notice.

- (2) If the **distributor** holds the information, the **distributor** must provide the information requested by the **Authority** under subclause (1) within the time specified by the **Authority**.
- (3) The **Authority** may, by notice in writing to the **registry manager**, require the **registry manager** to provide to the **Authority** information about **ICPs** for which the defaulting **trader** is recorded in the **registry** as being responsible, within the period specified in the notice.
- (4) The **registry manager** must provide the information requested by the **Authority** under subclause (3) within the time specified by the **Authority**.

Clause 3 Heading: amended, on 5 October 2017, by clause 281(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 3(1): amended, on 28 February 2015, by clause 11(1) of the Electricity Industry Participation Code Amendment (Trader Default) 2014.

Clause 3(3): amended, on 28 February 2015, by clause 11(2) of the Electricity Industry Participation Code Amendment (Trader Default) 2014.

Clause 3(3) and (4): amended, on 5 October 2017, by clause 281(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

#### **4 Failure by defaulting trader to remedy event of default**

- (1) This clause applies if—
  - (a) 7 days have elapsed since the **Authority** gave notice to the defaulting **trader** under clause 2(1); and
  - (b) the **Authority** considers that—
    - (i) the defaulting **trader** has not remedied the **event of default** or, in the case of an **event of default** under clause 14.41(b) in respect of which there is an unresolved invoice dispute under clause 14.25, has not reached an agreement with the **Authority** to resolve the **event of default**; and
    - (ii) the defaulting **trader** still has 1 or more contracts under which a **customer** of the defaulting **trader** purchases **electricity** from the defaulting **trader** or is still recorded in the **registry** as being responsible for 1 or more **ICPs**.
- (2) The **Authority** must—
  - (a) give written notice to the defaulting **trader** that the **Authority** considers that this clause applies; and
  - (b) attempt to advise **customers** of the defaulting **trader** that—
    - (i) the defaulting **trader** has committed an **event of default**; and
    - (ii) the **customer** should enter into a contract for the purchase of **electricity** with another **trader** by the date that is 14 days after the day on which the **Authority** gave written notice to the defaulting **trader** under clause 2(1); and
    - (iii) if the **customer** fails to enter into a contract with another **trader** by that date, the **Authority** may assign the defaulting **trader's** rights and obligations under the **customer's** contract with the defaulting **trader** to another **trader** under clause 5.
- (3) *[Revoked]*

(4) *[Revoked]*

Clause 4, heading: amended, on 28 February 2015, by clause 12(1) of the Electricity Industry Participation Code Amendment (Trader Default) 2014.

Clause 4(1): amended, on 28 February 2015, by clause 12(2) of the Electricity Industry Participation Code Amendment (Trader Default) 2014.

Clause 4(1)(b)(i): amended, on 24 March 2015, by clause 8 of the Electricity Industry Participation Code Amendment (Settlement and Prudential Security) 2014.

Clause 4(2)(a): amended, on 28 February 2015, by clause 12(3)(a) of the Electricity Industry Participation Code Amendment (Trader Default) 2014.

Clause 4(2)(a) and (b): amended, on 5 October 2017, by clause 282 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 4(2)(b): substituted, on 28 February 2015, by clause 12(3)(b) of the Electricity Industry Participation Code Amendment (Trader Default) 2014.

Clause 4(3) and 4(4): revoked, on 28 August 2015, by clause 12(4) of the Electricity Industry Participation Code Amendment (Trader Default) 2014.

**4A Trader to provide information about NSPs and ICPs at which it cannot trade**

- (1) If the **Authority** gives written notice to a **trader** under clause 4, the **Authority** must give written notice to each **trader** (except the defaulting **trader**) that it must provide the information specified in subclause (2) to the **registry manager** by no later than 1600 on the **business day** following the day on which the notice under this subclause was given.
- (2) The information that a **trader** must provide to the **registry manager** is—
  - (a) the **NSPs** at which the **trader** cannot trade because it does not have an arrangement with the relevant **distributor** on whose network the **NSPs** are located to trade at the **NSP**; and
  - (b) the **ICPs** at which the **trader** cannot trade for any of the following reasons:
    - (i) the type of each **meter** at the **ICPs** (for example, **half hour**, non **half hour**, or **prepay**);
    - (ii) the **price category code** assigned to the **ICPs**;
    - (iii) the **metering installation** category of the **metering installation** at the **ICPs**;
    - (iv) the **installation type** code assigned to the **ICPs**; and
  - (c) the reasons, being 1 or more reasons specified in paragraph (a) and (b), for the **trader** being unable to trade at the **NSPs** or **ICPs**.
- (3) A **trader** must comply with a notice given to it under subclause (1).

Clause 4A: inserted, on 28 August 2015, by clause 13 of the Electricity Industry Participation Code Amendment (Trader Default) 2014.

Clause 4A(1): amended, on 5 October 2017, by clause 283 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

**4B Authority may direct registry manager to take certain actions**

- (1) If the **Authority** gives written notice to a **trader** under clause 4, the **Authority** may, by written notice to the **registry manager**, direct the **registry manager** not to—
  - (a) complete the switch of any **ICP** to the defaulting **trader**; or
  - (b) accept a request from the defaulting **trader** to withdraw a switch under clauses 17 and 18 of Schedule 11.3.
- (2) If the **Authority** gives written notice under subclause (1), the **registry manager** must not—
  - (a) complete the switch of any **ICP** to the defaulting **trader**; or

- (b) accept a request from the defaulting **trader** to withdraw a switch under clauses 17 and 18 of Schedule 11.3.

Clause 4B Heading: amended, on 5 October 2017, by clause 284(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 4B: amended, on 5 October 2017, by clause 284(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 4B: inserted, on 28 August 2015, by clause 13 of the Electricity Industry Participation Code Amendment (Trader Default) 2014.

## **5 Authority may assign contracts and ICPs**

- (1) This clause applies if, by the end of the 17<sup>th</sup> day after the defaulting **trader** was given notice under clause 2(1),—
- (a) the defaulting **trader** has not remedied the **event of default** or, in the case of an **event of default** under clause 14.41(b) in respect of which there is an unresolved invoice dispute under clause 14.25, has not reached an agreement with the **Authority** to resolve the **event of default**; and
  - (b) the defaulting **trader** continues to have 1 or more contracts under which a **customer** of the defaulting **trader** purchases **electricity** from the defaulting **trader** or the defaulting **trader** is still recorded in the **registry** as being responsible for 1 or more **ICPs**.
- (2) The **Authority** may—
- (a) exercise its right under a contract under which a **customer** purchases **electricity** from the defaulting **trader** to assign the rights and obligations of the defaulting **trader** under the contract to a recipient **trader** in accordance with the contract; and
  - (b) assign an **ICP** to a recipient **trader** and direct the **registry manager** to amend the record in the **registry** so that the recipient **trader** is recorded as being responsible for the **ICP**; and
  - (c) specify the recipient **trader** to whom the rights and obligations under the contract or the **ICP** will be assigned.
- (3) The **Authority** must, by notice in writing to each recipient **trader**, direct the recipient **trader** to accept an assignment under subclause (2).
- (4) Before the **Authority** gives notice to a recipient **trader** under subclause (3), the **Authority** may decide not to assign rights and obligations of the defaulting **trader** under a contract or an **ICP** to a recipient **trader** if the recipient **trader** satisfies the **Authority** that the assignment would pose a serious threat to the financial viability of the recipient **trader**.
- (5) A recipient **trader** must comply with a direction given to it under subclause (3).
- (6) The **registry manager** must comply with a direction given to it under subclause (2).
- (7) Before the **Authority** exercises its right to assign rights and obligations or an **ICP** under subclause (2), the **Authority** must, if the **Authority** considers it is practicable, consult with the defaulting **trader** as to the need for the notice.
- (8) Nothing in this clause prevents the **Authority** from deciding to give a notice under subclause (3) to 1 or more recipient **traders** by undertaking a tender or other competitive process.

Clause 5, heading: amended, on 28 February 2015, by clause 14(1) of the Electricity Industry Participation Code

Amendment (Trader Default) 2014.

Clause 5(1): amended, on 28 February 2015, by clause 14(2) of the Electricity Industry Participation Code

Amendment (Trader Default) 2014.

Clause 5(1)(a): amended, on 24 March 2015, by clause 9 of the Electricity Industry Participation Code Amendment (Settlement and Prudential Security) 2014.

Clause 5(2) to (8): amended, on 28 February 2015, by clause 14(3) of the Electricity Industry Participation Code Amendment (Trader Default) 2014.

Clause 5(2)(b): amended, on 5 October 2017, by clause 285(a) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 5(6): amended, on 5 October 2017, by clause 285(b) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

## 5A Effect of assignment

If the **Authority** assigns an **ICP** to a recipient **trader** under clause 5, and at the time of the assignment the recipient **trader** does not comply with clause 10.24(a) in relation to the **ICP**, the recipient **trader** is excused from complying with that clause for the first 3 months after the assignment.

Clause 5A: inserted, on 28 August 2015, by clause 15 of the Electricity Industry Participation Code Amendment (Trader Default) 2014.

## 6 Authority must provide information to recipient trader

If the **Authority** exercises its right to assign rights and obligations or an **ICP** under clause 5(2), the **Authority** must provide the following information to each recipient **trader**:

- (a) the number of **customer** contracts (to the extent that the **Authority** has the information) and **ICPs** assigned to the **trader**; and
- (b) any information that the **Authority** holds about the **customers** and **ICPs** assigned to the **trader**.

Clause 6, heading: amended, on 28 February 2015, by clause 16(1) of the Electricity Industry Participation Code Amendment (Trader Default) 2014.

Clause 6: amended, on 28 February 2015, by clause 16(2) of the Electricity Industry Participation Code Amendment (Trader Default) 2014.

## 7 Registry manager may complete switch without required information

If the **Authority** gives written notice under clause 2, the **registry manager** may complete the switch of any **ICP** for which the defaulting **trader** is recorded in the **registry** as being responsible even if the defaulting **trader** has not complied with its obligations under Schedule 11.3.

Clause 7 Heading: amended, on 5 October 2017, by clause 286(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 7: amended, on 28 February 2015, by clause 17 of the Electricity Industry Participation Code Amendment (Trader Default) 2014.

Clause 7: amended, on 5 October 2017, by clause 286(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

**8 Terms of assigned contract**

- (1) If the **Authority** exercises its right to assign rights and obligations under clause 5(2), the **Authority** must attempt to advise the **customer** that the terms of the contract may be amended on assignment.
- (2) The recipient **trader** must use reasonable endeavours to advise the **customer** of those terms.

Clause 8(2): amended, on 28 February 2015, by clause 18 of the Electricity Industry Participation Code Amendment (Trader Default) 2014.



# Electricity Industry Participation Code 2010

## Part 12 Transport

### Contents

#### Subpart 1—General

- 12.1 Contents of this Part
- 12.2 Discretion to waive Code requirements
- 12.3 Interaction between Parts 7 and 8 and this Part

#### Subpart 2—Transmission agreements

- 12.4 Contents of this subpart
- 12.5 Structure for transmission agreements
- 12.6 Review of structure for transmission agreements
- 12.7 Categories of participants required to enter into transmission agreements

#### *Transpower and designated transmission customers must enter transmission agreements*

- 12.8 Obligation to enter transmission agreements
- 12.9 When designated transmission customer must enter into transmission agreement
- 12.10 Benchmark agreements to be default transmission agreements
- 12.11 Subsequent transmission agreements
- 12.12 Changes to connection assets under default transmission agreements
- 12.13 Expiry or termination of transmission agreements

#### *Content of transmission agreements*

- 12.14 Transmission agreements to be consistent with benchmark agreements and grid reliability standards
- 12.15 Transpower to publish information about transmission agreements and provide them on request

#### *Connection Code*

- 12.16 Connection Code
- 12.17 Purpose of Connection Code
- 12.18 Review of Connection Code
- 12.19 Transpower to submit Connection Code
- 12.20 Required content of Connection Code
- 12.21 Principles for developing Connection Code
- 12.22 Authority may initially approve proposed Connection Code or refer back to Transpower
- 12.23 Amendment of proposed Connection Code by Authority
- 12.24 Authority must consult on proposed Connection Code
- 12.25 Decision on Connection Code
- 12.26 Incorporation of Connection Code by reference

#### *Benchmark agreements for connection and/or use of the grid*

- 12.27 Benchmark agreement
- 12.28 Authority may initiate review
- 12.29 Purpose of benchmark agreements
- 12.30 Principles for benchmark agreements

- 12.31 Contents of benchmark agreements
- 12.32 Authority must consult on draft benchmark agreement
- 12.33 Decision on benchmark agreement
- 12.34 Incorporation of benchmark agreement by reference
- Variations from benchmark agreements and grid reliability standards and enhancement and removal of connection assets*
- 12.35 Increased service levels and reliability
- 12.36 Decreased service levels and reliability
- 12.37 Variations that may increase or decrease reliability
- 12.38 Other variations from terms of benchmark agreements
- 12.39 Customer specific value of expected unserved energy
- 12.40 Replacement and enhancement of shared connection assets
- 12.41 Removal of shared connection assets from service
- 12.42 Reconfiguration of shared connection assets
- 12.43 Net benefits test
- 12.44 Request to the Commerce Commission to request an investment proposal be submitted
- Resolutions of disputes*
- 12.45 Certain disputes relating to transition agreements may be referred to Rulings Panel
- 12.46 Rulings Panel has discretion to determine dispute
- 12.47 Determinations by Rulings Panel
- 12.48 Status of default transmission agreement while Rulings Panel determining dispute
- Existing agreements not affected*
- 12.49 Existing agreements
- 12.50 Copies of other agreements to be provided to the Authority
- 12.51 Application to Rio Tinto agreements[Revoked]
- Subpart 3—Grid reliability and industry information
- 12.52 Contents of this subpart
- 12.53 Purpose of the reliability and industry information clauses
- 12.54 Obligations to provide information
- Grid reliability standards*
- 12.55 Authority determines grid reliability standards
- 12.56 Purpose of grid reliability standards
- 12.57 Principles of grid reliability standards
- 12.58 Content of grid reliability standards
- Review of grid reliability standards*
- 12.59 Interested parties may request review of grid reliability standards
- 12.60 Authority review of grid reliability standards
- 12.61 Authority must publish draft grid reliability standards
- 12.62 Decision on grid reliability standards
- Core grid determination*
- 12.63 Authority determines core grid determination
- 12.64 Purpose of core grid determination
- 12.65 Objectives of core grid determination

*Review of core grid determination*

- 12.66 Interested parties may request review of core grid determination
- 12.67 Authority review of grid determination
- 12.68 Authority must publish draft core grid determination
- 12.69 Decision on core grid determination

*Investment contracts*

- 12.70 Purpose
- 12.71 Investment contracts

*Centralised data set[Revoked]*

- 12.72 Authority to establish and maintain centralised data set[Revoked]
- 12.73 Purpose of centralised data set[Revoked]
- 12.74 Contents of centralised data set[Revoked]
- 12.75 Public access to centralised data set[Revoked]

*Grid reliability reporting*

- 12.76 Transpower to publish grid reliability report
  - Subpart 4—Transmission pricing methodology
- 12.77 Recovery of investment costs by Transpower
- 12.78 Purpose for establishing transmission pricing methodology
- 12.79 Statutory objective
- 12.80 Application and interpretation of pricing principles [Revoked]
- 12.81 Authority must prepare an issues paper
- 12.82 Authority must consult on issues paper
- 12.83 Authority must publish process and guidelines for development of transmission pricing methodology

*Development of transmission pricing methodology by Transpower*

- 12.84 A Transmission pricing methodology

*Review of an approved transmission pricing methodology*

- 12.85 Review by Transpower
- 12.86 Review by the Authority
- 12.87 Process for review
- 12.88 Transpower to submit methodology
- 12.89 Form of proposed transmission pricing methodology
- 12.90 Authority may decline to consider proposed transmission pricing methodology

*Process for Authority determination of transmission pricing methodology*

- 12.91 Authority may approve proposed transmission pricing methodology or refer back to Transpower
- 12.92 Authority must publish proposed transmission pricing methodology
- 12.93 Decision on transitional pricing methodology
- 12.94 Authority to determine commencement date

*Application of approved transmission pricing methodology*

- 12.95 Charges to comply with approved transmission methodology
- 12.96 Development of transmission prices

*Audit of transmission prices*

- 12.97 Audit of transmission prices

- 12.98 Transpower may respond to auditor's report
- 12.99 Final auditor report to the Authority
- 12.100 Transpower to redetermine transmission prices
- 12.101 Auditor's costs
- 12.102 Enforcement of transmission charges
  - Subpart 5—Financial transmission rights *[Revoked]*
- 12.103 Contents of this subpart *[Revoked]*
- 12.104 Design *[Revoked]*
  - Subpart 6—Interconnection asset services
- 12.105 Purpose of this subpart
- 12.106 Interconnection asset capacity and grid configuration
- 12.107 Transpower to identify interconnection branches, and propose service measures and levels
- 12.108 Consultation on proposed interconnection asset capacity and grid configuration
- 12.109 Decision on interconnection asset capacity and grid configuration
- 12.110 Incorporation of interconnection asset capacity and grid configuration by reference
- 12.111 Transpower to make interconnection branches and other assets available and keep grid configuration
- 12.112 Exceptions to clause 12.111
- 12.113 Transpower to maintain interconnection assets
  - Transpower to propose investments*
- 12.114 Investments to meet the grid reliability standards
- 12.115 Other investments
- 12.116 Information on capacities of individual interconnection assets
- 12.116AA Temporary removal of interconnection assets from service or temporary grid reconfiguration
- 12.116AB *[Expired]*
- 12.116AC Information to be published
- 12.116A *[Expired]*
- 12.116B *[Expired]*
- 12.116C *[Expired]*
- 12.117 Permanent removal of interconnection assets from service or permanent grid reconfiguration
- 12.118 Transpower to provide and publish annual report on interconnection asset capacity and grid configuration
  - Reporting on availability and reliability*
- 12.119 Index measures for availability and reliability
- 12.120 Updating of availability and reliability index measures
- 12.121 Transpower to submit draft index measures for availability and reliability
- 12.122 Requirements for index measures
- 12.123 Authority may initially approve proposed index measures or refer back to Transpower
- 12.124 Amendment of proposed index measures by the Authority
- 12.125 Authority must consult on proposed index measures
- 12.126 Decision on index measures

- 12.127 Transpower to report on availability and reliability  
12.128 Transpower and designated transmission customers may agree on other requirements
- Subpart 7—Preparation of Outage Protocol
- 12.129 Purpose of this subpart  
12.130 Definition of outage  
12.131 Outage protocol
- Review of Outage Protocol*
- 12.132 Review of Outage Protocol  
12.133 Transpower to submit proposed Outage Protocol
- Principles and required content of Outage Protocol*
- 12.134 Principles for developing Outage Protocol  
12.135 Required content of Outage Protocol  
12.136 Planning for outages  
12.137 Transpower and designated transmission customers to act reasonably and in good faith  
12.138 Reconsideration of planned outages  
12.139 Variations to planned outages  
12.140 Net benefit principle, requirements and methodologies  
12.141 Consideration of the likely effects of planned outages  
12.142 Planned outages required in order to give effect to an investment or required by the Act  
12.143 Required content of Outage Protocol in relation to unplanned outages  
12.144 Reporting on compliance with Outage Protocol
- Decisions on Outage Protocol*
- 12.145 Authority may initially approve the proposed Outage Protocol or refer back to Transpower  
12.146 Reconsideration of revised Outage Protocol by the Authority  
12.147 Authority must consult on the proposed Outage Protocol  
12.148 Authority may undertake additional consultation  
12.149 Decision on Outage Protocol  
12.150 Incorporation of Outage Protocol by reference
- Complying with Outage Protocol*
- 12.151 Compliance with Outage Protocol

**Schedule 12.1**

**Categories of designated transmission customers**

**Schedule 12.2**

**Grid reliability standards**

**Schedule 12.3**

**Core grid determination**

**Schedule 12.4**

**Transmission Pricing Methodology**

*Connection charges*

*Interconnection charge*

*HVDC charge*

*Transmission alternatives*

*Prudent Discount Policy*

*Appendix A: Allocation of Transpower's AC Revenue and HVDC Revenue to its charges*

*Appendix B: Regions*

*Appendix C: Information Required to Support a Prudent Discount Application*

## **Schedule 12.5**

### **Availability and reliability index measures**

---

## **Subpart 1—General**

### **12.1 Contents of this Part**

This Part relates to the following aspects of transmission:

- (a) **transmission agreements** (subpart 2):
- (b) **grid** reliability and industry information (subpart 3):
- (c) the **transmission pricing methodology** (subpart 4):
- (d) *[Revoked]*
- (e) **interconnection asset** services (subpart 6):
- (f) the **Outage Protocol** (subpart 7).

Compare: Electricity Governance Rules 2003 rule 1 section I part F

Clause 12.1(d): revoked, on 1 October 2011, by clause 5 of the Electricity Industry Participation (Financial Transmission Rights) Code Amendment 2011.

### **12.2 Discretion to waive Code requirements**

- (1) The **Authority** may agree to waive Code requirements under this Part if, before the commencement of an amendment to this Part,—
  - (a) **Transpower** or any other **participant** required to complete actions under this Code has in substance done what it would have been required to do under this Code; and
  - (b) the **Authority** is satisfied that the actions have been completed.
- (2) If the **Authority** agrees to waive Code requirements under subclause (1), the **Authority** must **publish** its decision and reasons for agreeing to waive Code requirements.

Compare: Electricity Governance Rules 2003 rule 2 section I part F

### **12.3 Interaction between Parts 7 and 8 and this Part**

- (1) The **principal performance obligations** in relation to the real time delivery of **common quality** and **dispatch** under Part 7 relate to the functions and obligations of the **system operator**.
- (2) When it is exercising its functions and powers under this Part, the **Authority** must have regard to the desirability of Parts 7 and 8 and this Part operating in an integrated and consistent manner.
- (3) The performance or non-performance of a function or obligation of the **system operator** under Parts 7 or 8, and a claim against the **system operator** under Parts 7 or 8, is

without prejudice to the functions and obligations of **Transpower** under this Part.

- (4) The performance or non-performance of a function or obligation of **Transpower** under this Part, and any claim against **Transpower** under this Part or a **transmission agreement**, is without prejudice to the functions and obligations of the **system operator** under Parts 7 or 8.

Compare: Electricity Governance Rules 2003 rule 3 section I part F

## Subpart 2—Transmission agreements

### 12.4 Contents of this subpart

This subpart deals with **transmission agreements**, and provides for the following:

- (a) a process for the **Authority** to determine the structure of **transmission agreements**:
- (b) the categories of **participants** that must enter into **transmission agreements**:
- (c) an obligation on **Transpower** and **designated transmission customers** to enter into **transmission agreements**:
- (d) matters to be included in **transmission agreements**:
- (e) a process for the **Authority** to determine **benchmark agreements** that—
  - (i) provide the basis for the negotiation of **transmission agreements**; or
  - (ii) act as a default **transmission agreement** if **Transpower** and a **designated transmission customer** fail to execute a **transmission agreement**:
- (f) a process for the **Authority** to determine a **Connection Code**:
- (g) a process for variations in **transmission agreements** from **benchmark agreements**:
- (h) a process for resolving disputes arising from the negotiation of **transmission agreements**, and the application of the **benchmark agreement** as a default **transmission agreement**:
- (i) existing agreements.

Compare: Electricity Governance Rules 2003 rule 1 section II part F

### 12.5 Structure for transmission agreements

- (1) The structure for **transmission agreements** that applies at the commencement of this Code is the structure for **transmission agreements** published by the Electricity Commission under rule 2 of section II of part F of the **rules** on 21 May 2007.
- (2) Until the **Authority** reviews the structure for **transmission agreements**, it must continue to **publish** the structure referred to in subclause (1).

Compare: Electricity Governance Rules 2003 rule 2.1.2 section II part F

### 12.6 Review of structure for transmission agreements

- (1) This clause applies if the **Authority** wishes to review the structure for **transmission agreement** referred to in clause 12.5, or a structure for **transmission agreements** determined by the **Authority** under this clause.
- (2) The **Authority** must **publish** a proposed structure for **transmission agreements**.
- (3) When the **Authority publishes** its proposed structure, the **Authority** must notify

**registered participants** of the date by which submissions on the proposed structure are to be received by the **Authority**. The date must be no earlier than 15 **business days** from the date of **publication** of the proposed structure.

- (4) Each submission on the proposed structure must be made in writing to the **Authority** and received on or before the **submission expiry date**. In addition to receiving written submissions, the **Authority** may elect to hear 1 or more oral submissions.
- (5) Within 20 **business days** after the **submission expiry date** (or such longer period as the **Authority** may allow), the **Authority** must complete its consideration of all submissions it receives and determine an appropriate **transmission agreement** structure.
- (6) The **transmission agreement** structure determined by the **Authority** under this clause must be the structure of the **benchmark agreements** to be developed and approved by the **Authority** under clauses 12.27 to 12.34.

Compare: Electricity Governance Rules 2003 rules 2.1.3 to 2.1.5 section II part F

#### **12.7 Categories of participants required to enter into transmission agreements**

- (1) The categories of **designated transmission customers** required to enter into **transmission agreements** with **Transpower** under clause 12.8 are as specified in Schedule 12.1.
- (2) The **Authority** must record in the **register** whether a **registered participant** is a **designated transmission customer**.
- (3) Registration has no effect on a **participant's** status as a **designated transmission customer**.

Compare: Electricity Governance Rules 2003 rule 2.2 section II part F

*Transpower and designated transmission customers must enter transmission agreements*

#### **12.8 Obligation to enter transmission agreements**

**Transpower** and **designated transmission customers** must enter into **transmission agreements**.

Compare: Electricity Governance Rules 2003 rule 3.1.1 section II part F

#### **12.9 When designated transmission customer must enter into transmission agreement**

A **participant** who becomes a **designated transmission customer** must enter into a **transmission agreement** with **Transpower** within 2 months after the **participant** becomes a **designated transmission customer**.

Compare: Electricity Governance Rules 2003 rule 3.1.2.3 section II part F

#### **12.10 Benchmark agreements to be default transmission agreements**

- (1) Subject to clauses 12.49 and 12.50, if, at the expiry of 2 months after a **participant** becomes a **designated transmission customer**, the **designated transmission customer** and **Transpower** have not entered into a **transmission agreement** in accordance with clause 12.9, the **benchmark agreement** applies as a binding contract between the **designated transmission customer** and **Transpower**, and the **designated transmission customer** and **Transpower** must comply with the process specified in



this clause.

(2) If this clause applies:

- (a) within 10 **business days** of the date that is 2 months after the **participant** became a **designated transmission customer**, the **designated transmission customer** must provide **Transpower**, at the address for service for **Transpower** registered at the New Zealand Companies Office, with—
  - (i) the **designated transmission customer's** full name; and
  - (ii) the **designated transmission customer's** physical address, postal address and electronic address to which notices under the default **transmission agreement** are to be sent; and
  - (iii) the name of the contact person of the **designated transmission customer** to whom such notices should be addressed:
- (b) by the date 20 **business days** after the receipt of the **designated transmission customer's** details under paragraph (a), **Transpower** must provide the **designated transmission customer** with a draft default **transmission agreement** completed in accordance with the **benchmark agreement**, which must include the following:
  - (i) the **designated transmission customer's** details as provided under paragraph (a):
  - (ii) **Transpower's** physical address, postal address and electronic address to which notices under the default **transmission agreement** are to be sent:
  - (iii) the contact person to whom notices under the default **transmission agreement** should be addressed:
  - (iv) **Transpower's** designated bank account for the purposes of receiving payments under the default **transmission agreement**:
  - (v) a draft Schedule 1, which sets out the **connection locations**, **points of service** and **points of connection** of the **assets** owned or operated by the **designated transmission customer** to the **grid**:
  - (vi) a draft Schedule 4 setting out, in the same form as the diagram in Schedule 4 of the **benchmark agreement**, the configuration of the **connection assets** in relation to each **connection location** listed in Schedule 1:
  - (vii) a draft Schedule 5 setting out proposed service levels for each **connection location** listed in Schedule 1 determined in accordance with subclause (3):
  - (viii) if applicable, a draft Schedule 6, including identifying the facilities, facilities area, and land that are to be subject to the access and occupation terms set out in the schedule and the licence charges under the schedule:
- (c) the **designated transmission customer** and **Transpower** may discuss the schedules proposed under paragraph (b)(v) to (viii), as a result of which **Transpower** may amend any of the schedules:
- (d) the **designated transmission customer** must advise **Transpower** in writing no later than 20 **business days** after receiving the draft default **transmission agreement** under paragraph (b) whether—
  - (i) it accepts the schedules as proposed by **Transpower** under paragraph (b)(v) to (viii); or

- (ii) if **Transpower** has amended any of those schedules under paragraph (c), it accepts the schedules as amended.
- (3) The service levels set out in Schedule 5 of a default **transmission agreement** must be determined on the following basis:
  - (a) the capacity service levels for each **branch** must be consistent with—
    - (i) the capacities of the **branch** or component **assets** in the most recent **asset capability statement** provided by **Transpower** under clause 2(5) of **Technical Code A** of Schedule 8.3; or
    - (ii) if the relevant information is not contained in the **asset capability statement**, the **manufacturer's specification** for the component **assets**:
  - (b) the service levels for the voltage range specified in the capacity service measures for each **branch** must be consistent with,—
    - (i) for **assets** of voltages of 50kV or above,—
      - (A) the voltage ranges for the component **assets** specified in the **AOPOs**, if any; or
      - (B) the voltage range specified in any **equivalence arrangement** approved or any **dispensation** granted under clauses 8.29 to 8.31 in respect of any **asset** that does not comply with the voltage range specified in the **AOPOs**; or
    - (ii) for assets of voltages less than 50kV, the normal operating voltage of the component **assets**:
  - (c) **Transpower** must ensure that each **connection asset** is included in a **branch**:
  - (d) the availability and reliability service levels must—
    - (i) be set at a level equivalent to the average annual availability and reliability at each **point of service** subject to the default **transmission agreement** over the 5 year period (being years ending 30 June) immediately before the date that is 2 months after the **participant** became a **designated transmission customer**; or
    - (ii) if a **point of service** subject to the default **transmission agreement** has not been in existence for 5 years (being years ending 30 June) before the date referred to in subparagraph (i), reflect a reasonable estimate of the expected availability and reliability at the **point of service** having regard to the performance data available for the **point of service** and average annual availability and reliability of **assets** similar to the **connection assets** at the **connection location** at which the **point of service** is located:
  - (e) the reporting and response service levels must be consistent with **Transpower's** practices existing on the date that is 2 months after the **participant** became a **designated transmission customer**, including **Transpower's** documented policies and procedures, and must not result in changes to the management or operation of the **grid** that could materially affect **Transpower** or any other **participant** or end use customer, or require **Transpower** to materially alter the level of its normal on-going **grid** expenditure.
- (4) If the **designated transmission customer** accepts the schedules as proposed by **Transpower** under subclause (2)(b)(v) to (viii), or as amended by **Transpower** under

subclause (2)(c), the default **transmission agreement** applies as a binding contract between **Transpower** and the **designated transmission customer** from the date that is 2 months after the **participant** became a **designated transmission customer**.

- (5) If **Transpower** and a **designated transmission customer** are unable to agree on the terms of any of the schedules to a default **transmission agreement** proposed by **Transpower** under subclause (2)(b)(v) to (viii), or as amended by **Transpower** under subclause (2)(c), either party may refer the matter to the **Rulings Panel** for determination under clauses 12.45 to 12.48.
- (6) If a dispute is referred to the **Rulings Panel**, under subclause (5)—
- (a) the default **transmission agreement** as determined by the **Rulings Panel** in accordance with clauses 12.45 to 12.48 applies as a binding agreement between **Transpower** and the **designated transmission customer** from the date that is 2 months after the **participant** became a **designated transmission customer** or the date on which the **Rulings Panel** makes its determination or its determination is expressed to come into effect, whichever is later; and
  - (b) if the **Rulings Panel** has not made a determination by the date that is 2 months after the **participant** became a **designated transmission customer**, the draft default **transmission agreement** provided under subclause (2)(b) applies as a binding agreement between **Transpower** and the **designated transmission customer** until the date on which the **Rulings Panel** makes its determination or the determination comes into effect.

Compare: Electricity Governance Rules 2003 rule 3.1.3 section II part F

Clause 12.10(1): amended, on 16 December 2013, by clause 5 of the Electricity Industry Participation (Revocation of Part 16) Code Amendment 2013.

Clause 12.10(2)(a)(ii) and (b)(ii): amended, on 5 October 2017, by clause 287 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### 12.11 Subsequent transmission agreements

If a **benchmark agreement** applies as a default **transmission agreement**, the **benchmark agreement** may be superseded by a subsequent **transmission agreement** entered into by **Transpower** and the **designated transmission customer**.

Compare: Electricity Governance Rules 2003 rule 3.1.4 section II part F

### 12.12 Changes to connection assets under default transmission agreements

- (1) If **Transpower** reconfigures, replaces, enhances, or permanently removes a **connection asset** from service in accordance with the provisions of a default **transmission agreement** that applies under clauses 12.10 or 12.13,—
- (a) within 20 **business days**, to the extent necessary, **Transpower** must provide the **designated transmission customer** who is a party to that agreement with a revised Schedule 1, a revised Schedule 4, and a revised Schedule 5 for that agreement, reflecting any changes to the description of the **connection locations**, **points of service**, or **points of connection** in Schedule 1, the diagram in Schedule 4, or to the service levels specified in Schedule 5 resulting from the replacement or enhancement of the **connection asset**; and
  - (b) the **designated transmission customer** and **Transpower** may discuss the revised schedules, as a result of which **Transpower** may amend any of the revised

- schedules; and
- (c) the **designated transmission customer** must advise **Transpower** within 20 **business days** of receiving the revised schedules under paragraph (a) whether—
    - (i) it accepts the revised schedules as proposed by **Transpower** under paragraph (a); or
    - (ii) if **Transpower** has amended any of those revised schedules under paragraph (b), it accepts the revised schedules as amended; and
  - (d) the revised schedules apply under the default **transmission agreement** from the date that acceptance is received by **Transpower** under paragraph (c).
- (2) If the **designated transmission customer** does not accept the revised schedules under subclause (1)(c), either party may refer the matter to the **Rulings Panel** for determination under clauses 12.45 to 12.48.
- (3) If a dispute is referred to the **Rulings Panel** in accordance with subclause (2)—
- (a) the revised schedules proposed by **Transpower** under subclause (1)(a) apply from the date on which **Transpower** provides the **designated transmission customer** with the revised schedules under subclause (1)(a) until the date on which the **Rulings Panel** makes its determination or the determination comes into effect; and
  - (b) the revised schedules as determined by the **Rulings Panel** under clauses 12.45 to 12.48 apply under the default **transmission agreement** from the date determined by the **Rulings Panel**.

Compare: Electricity Governance Rules 2003 rule 3.1.5 section II part F

### 12.13 Expiry or termination of transmission agreements

If a **transmission agreement**, or an existing written agreement to which clause 12.49 applies, expires or terminates on or after the date that is 2 months after the **participant** became a **designated transmission customer** and **Transpower** and the **designated transmission customer** do not enter into a new **transmission agreement** within 2 months of that date, the following procedure applies:

- (a) within 10 **business days**, the **designated transmission customer** must provide **Transpower**, at the address for service for **Transpower** registered at the New Zealand Companies Office, with—
  - (i) the **designated transmission customer's** full name; and
  - (ii) the **designated transmission customer's** physical address, postal address and electronic address to which notices under the default **transmission agreement** are to be sent; and
  - (iii) the name of the contact person of the **designated transmission customer** to whom such notices should be addressed:
- (b) within 20 **business days** of receipt of the **designated transmission customer's** details under paragraph (a), **Transpower** must provide the **designated transmission customer** with a draft default **transmission agreement** completed in accordance with the **benchmark agreement**, which must include—
  - (i) the **designated transmission customer's** details as provided under paragraph (a); and

- (ii) **Transpower's** physical address, postal address and electronic address to which notices under the default **transmission agreement** are to be sent; and
- (iii) the contact person to whom notices under the default **transmission agreement** should be addressed; and
- (iv) **Transpower's** designated bank account for the purposes of receiving payments under the default **transmission agreement**; and
- (v) a draft Schedule 1, which sets out the **connection locations, points of service** and **points of connection** of the **assets** owned or operated by the **designated transmission customer** to the **grid**; and
- (vi) a draft Schedule 4 setting out, in the same form as the diagram in Schedule 4 of the **benchmark agreement**, the configuration of the **connection assets** in relation to each **connection location** listed in Schedule 1; and
- (vii) a draft Schedule 5 setting out proposed service levels for each **connection location** listed in Schedule 1 determined in accordance with clause 12.10(3); and
- (viii) if applicable, a draft Schedule 6, including identifying the facilities, facilities area, and land that are to be subject to the access and occupation terms set out in that schedule and the licence charges under that schedule:
- (c) the **designated transmission customer** and **Transpower** may discuss the schedules proposed under paragraph (b)(v) to (viii), as a result of which **Transpower** may amend any of the schedules:
- (d) the **designated transmission customer** must advise **Transpower** in writing within 20 **business days** of receiving the draft default **transmission agreement** under paragraph (b) above whether—
  - (i) it accepts the schedules as proposed by **Transpower** under paragraph (b)(v) to (viii); or
  - (ii) if **Transpower** has amended any of those schedules under paragraph (c), it accepts the schedules as amended:
- (e) if the **designated transmission customer** accepts the schedules as proposed by **Transpower** under paragraph (b)(v) to (viii), or as amended by **Transpower** under paragraph (c), the default **transmission agreement** applies as a binding contract between **Transpower** and the **designated transmission customer**, effective from the date on which the previous **transmission agreement** or existing written agreement to which clause 12.49 applies expired:
- (f) if **Transpower** and a **designated transmission customer** are unable to agree on the terms of any of the schedules to a default **transmission agreement** proposed by **Transpower** under paragraph (b)(v) to (viii), or as amended by **Transpower** under paragraph (c), either party may refer the matter to the **Rulings Panel** for determination under clauses 12.45 to 12.48:
- (g) if a dispute has been referred to the **Rulings Panel** in accordance with paragraph (f)—
  - (i) the draft default **transmission agreement** provided under paragraph (b) applies as a binding agreement between **Transpower** and the **designated transmission customer**, effective from the date on which the previous

**transmission agreement** or existing written agreement to which clause 12.49 applies expired, until the date on which the **Rulings Panel** makes its determination or the determination comes into effect; and

- (ii) the default **transmission agreement** as determined by the **Rulings Panel** in accordance with clauses 12.45 to 12.48 applies as a binding agreement between **Transpower** and the **designated transmission customer** from the date determined by the **Rulings Panel**.

Compare: Electricity Governance Rules 2003 rule 3.1.6 section II part F

Clause 12.13(a)(ii) and (b)(ii): amended, on 5 October 2017, by clause 288 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### *Content of transmission agreements*

#### **12.14 Transmission agreements to be consistent with benchmark agreements and grid reliability standards**

Subject to clauses 12.35 to 12.38, a **transmission agreement** entered into between **Transpower** and a **designated transmission customer** under clause 12.8 must be consistent in all material respects with—

- (a) the **benchmark agreement**; and
- (b) the **grid reliability standards**,—

as at the date the **transmission agreement** is entered into.

Compare: Electricity Governance Rules 2003 rule 3.2.1 section II part F

#### **12.15 Transpower to publish information about transmission agreements and provide them on request**

- (1) **Transpower** must **publish** and update annually a list of all **transmission agreements** it has with **designated transmission customers** that includes, in respect of each **transmission agreement** contained in the list, the following information:
  - (a) the full name of the **designated transmission customer** that is a party to the **transmission agreement**; and
  - (b) the date on which the **transmission agreement** was executed; and
  - (c) whether the **transmission agreement** includes any material variations from the **benchmark agreement**; and
  - (d) if the **transmission agreement** includes any material variations from the **benchmark agreement**, a description of the variations; and
  - (e) if any schedule to the **transmission agreement** has been revised in accordance with clause 12.12, the date from which the revised schedule began to apply.
- (2) A person may request from **Transpower** a copy of a **transmission agreement** that **Transpower** has with a **designated transmission customer**, and **Transpower** must provide a copy to the person as soon as practicable after receiving the request.
- (3) Despite subclause (2), **Transpower** may refuse to provide information from a **transmission agreement** if it considers that there would be grounds for withholding the information under the Official Information Act 1982.

Compare: Electricity Governance Rules 2003 rule 3.2.2 section II part F  
Clause 12.15: substituted, on 1 February 2016, by clause 46 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

### *Connection Code*

#### **12.16 Connection Code**

- (1) The **Connection Code** set out in schedule F2 of section II of part F of the **rules** immediately before this Code came into force, continues in force and is deemed to be the **Connection Code** that applies at the commencement of this Code, with the following amendments:
  - (a) every reference to the **rules** must be read as a reference to the Code;
  - (b) every reference to a provision of the **rules** must be read as a reference to the corresponding provision of the Code.
- (2) The **Authority** must, as soon as practicable after this Code comes into force, publish a version of the **Connection Code** in which the provisions of this Code that correspond to the provisions of the **rules** referred to in the **Connection Code** are shown.
- (3) Clause 12.26 applies to the **Connection Code**.

#### **12.17 Purpose of Connection Code**

The purpose of the **Connection Code** is to set out the technical requirements and standards that **designated transmission customers** must meet in order to be connected to the **grid** and that **Transpower** must comply with. **Transpower** and **designated transmission customers** must comply with the **Connection Code** under default **transmission agreements** that apply under clauses 12.10 and 12.13.

Compare: Electricity Governance Rules 2003 rule 3.3.1 section II part F  
Clause 12.17: amended, on 23 February 2015, by clause 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.  
Clause 12.17: amended, on 5 October 2017, by clause 289 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

#### **12.18 Review of Connection Code**

- (1) The **Authority** may review the **Connection Code** at any time.
- (2) Clauses 12.19 to 12.25 apply to any such review.

Compare: Electricity Governance Rules 2003 rule 3.3.10 section II part F

#### **12.19 Transpower to submit Connection Code**

- (1) **Transpower** must submit a proposed **Connection Code** to the **Authority** within 90 days (or such longer period as the **Authority** may allow) of receipt of a written request from the **Authority**. The **Authority** may issue such a request at any time. The proposed **Connection Code** must provide for the matters set out in clause 12.20 and give effect to the principles set out in clause 12.21.
- (2) With its proposed **Connection Code**, **Transpower** must submit to the **Authority** an explanation of the proposed **Connection Code** and a **statement of proposal** for the proposed **Connection Code**.

Compare: Electricity Governance Rules 2003 rule 3.3.2 section II part F

### 12.20 Required content of Connection Code

The **Connection Code** must provide for the following matters:

- (a) connection requirements for **designated transmission customers**:
- (b) technical requirements for **assets**, including **assets** owned by **Transpower**, and for other equipment and plant that is connected to a **local network** or an **embedded network** or that forms part of an **embedded network** or **embedded generating station** if the operation of that equipment and plant could affect the **grid assets**:
- (c) operating standards for equipment that is owned by a **designated transmission customer**, used in relation to the conveyance of **electricity**, and that is situated on land owned by **Transpower**:
- (d) information requirements to be met by **designated transmission customers** before equipment is connected to the **grid** and before changes are made to the equipment:
- (e) an obligation on **Transpower** to provide a 10 year forecast of the expected maximum fault level of each point of service to **designated transmission customers** set out in the **transmission agreement** between **Transpower** and each **designated transmission customer**.

Compare: Electricity Governance Rules 2003 rule 3.3.3 section II part F

Clause 20.20: amended, on 23 February 2015, by clause 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 12.20(a): amended, on 5 October 2017, by clause 290(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 12.20(b) and (d): amended, on 5 October 2017, by clause 290(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 12.20(c): amended, on 5 October 2017, by clause 290(3) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 12.20(e): amended, on 5 October 2017, by clause 290(4) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### 12.21 Principles for developing Connection Code

The **Connection Code** must give effect to the following principles:

- (a) the principles of the **benchmark agreement** in clause 12.30:
- (b) the desirability of the **Connection Code** and Part 8 operating in an integrated and consistent manner, if possible:
- (c) the need to ensure that the **grid owner** can meet all obligations placed on it by the **system operator** for the purpose of meeting common security and power quality requirements under Part 8:
- (d) the need to ensure that the safety of all personnel is maintained:
- (e) the need to ensure that the safety and integrity of equipment is maintained.

Compare: Electricity Governance Rules 2003 rule 3.3.4 section II part F

### 12.22 Authority may initially approve proposed Connection Code or refer back to Transpower

- (1) After consideration of **Transpower's** proposed **Connection Code**, and accompanying explanation and **statement of proposal**, the **Authority** may—
  - (a) provisionally approve the proposed **Connection Code** having regard to the



- matters set out in clause 12.20 and the principles in clause 12.21; or
- (b) refer the proposed **Connection Code** and accompanying explanation and **statement of proposal** back to **Transpower** if, in the **Authority's** view,—
- (i) the proposed **Connection Code** does not contain the matters set out in clause 12.20; or
  - (ii) the proposed **Connection Code** does not adequately provide for the principles in clause 12.21; or
  - (iii) the explanation or **statement of proposal** provided with the proposed **Connection Code** in accordance with clause 12.19(2) is inadequate.
- (2) **Transpower** may, no later than 20 **business days** (or such longer period as the **Authority** may allow) after the **Authority** notifies **Transpower** of its decision under subclause (1), consider the **Authority's** concerns and resubmit its proposed **Connection Code** and accompanying explanation and **statement of proposal** for consideration by the **Authority**.

Compare: Electricity Governance Rules 2003 rule 3.3.5 section II part F

#### **12.23 Amendment of proposed Connection Code by Authority**

If the **Authority** considers that the **Connection Code** resubmitted by **Transpower** under clause 12.22(b) does not adequately provide for the matters set out in clause 12.20 or adequately give effect to the principles in clause 12.21, the **Authority** may make any amendments to the proposed **Connection Code** it considers necessary.

Compare: Electricity Governance Rules 2003 rule 3.3.6 section II part F

#### **12.24 Authority must consult on proposed Connection Code**

- (1) The **Authority** must **publish** the proposed **Connection Code**, either as provisionally approved by the **Authority** or as amended by the **Authority**, as soon as practicable, for consultation with any person that the **Authority** thinks is likely to be materially affected by the proposed **Connection Code**.
- (2) As well as the consultation required under subclause (1), the **Authority** may undertake any other consultation it considers necessary.

Compare: Electricity Governance Rules 2003 rules 3.3.7 and 3.3.8 section II part F

#### **12.25 Decision on Connection Code**

- (1) When the **Authority** has completed its consultation on the proposed **Connection Code** it must consider whether to incorporate the **Connection Code** by reference in this Code.
- (2) If the **Authority** decides to incorporate the **Connection Code** by reference in this Code, the **Authority** must determine a date on which the incorporation by reference takes effect and comply with Schedule 1 of the **Act** in relation to it.

Compare: Electricity Governance Rules 2003 rule 3.3.9 section II part F

#### **12.26 Incorporation of Connection Code by reference**

- (1) The **Connection Code** is incorporated by reference in this Code in accordance with section 32 of the **Act**.

- (2) Subclause (1) is subject to Schedule 1 of the **Act**, which includes a requirement that the **Authority** must give notice in the *Gazette* before an amended or substituted **Connection Code** becomes incorporated by reference in this Code.

Clause 12.26(1): amended, on 5 October 2017, by clause 291 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

*Benchmark agreements for connection to and/or use of the grid*

### 12.27 Benchmark agreement

- (1) The **benchmark agreement** set out in schedule F2 of section II of part F of the **rules** immediately before this Code came into force, continues in force and is deemed to be the **benchmark agreement** that applies at the commencement of this Code, with the following amendments:
- (a) every reference to the Board must be read as a reference to the **Authority**;
  - (b) every reference to the **rules** must be read as a reference to the Code;
  - (c) every reference to the Electricity Governance Regulations must be read as a reference to the Code;
  - (d) every reference to a provision of the **rules** or the Electricity Governance Regulations must be read as a reference to the corresponding provision of the Code;
  - (e) the references in clause 40.2 to the value of unserved energy in schedule F4 of section III of part F of the **rules** must be read as references to the **value of expected unserved energy** in clause 4 of Schedule 12.2;
  - (f) the reference in clause 40.2(f)(2) to **Transpower** asking the Board of the Electricity Commission to request **Transpower** to submit a grid upgrade plan must be read as a reference to **Transpower** asking the Commerce Commission under clause 12.44 to request **Transpower** to submit an investment proposal.
- (2) The **Authority** must, as soon as practicable after this Code comes into force, publish a version of the **benchmark agreement** in which the provisions of this Code that correspond to the provisions of the **rules** referred to in the **benchmark agreement** are shown.
- (3) Clause 12.34 applies to the **benchmark agreement**.

Clause 12.27(1)(e): amended, on 1 February 2016, by clause 47 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

### 12.28 Authority may initiate review

- (1) Having regard to the statutory objective of the **Authority** in section 15 of the **Act** and to the principles for **benchmark agreements** set out in clause 12.30, the **Authority** may initiate a review of a **benchmark agreement** at any time. Reviews of the **Connection Code** must be carried out in accordance with clause 12.18.
- (2) A review of a **benchmark agreement** must follow the purpose, process and principles in clauses 12.29 to 12.33.

Compare: Electricity Governance Rules 2003 rule 7 section II part F

### 12.29 Purpose of benchmark agreements

The purpose of **benchmark agreements** is to—

- (a) facilitate commercial arrangements between **Transpower** and **designated transmission customers** by providing a basis for negotiating **transmission agreements** required under clause 12.8 that meet the particular requirements of **Transpower** and **designated transmission customers**; and
- (b) act as a default **transmission agreement** if **Transpower** and a **designated transmission customer** fail to enter into a **transmission agreement** by the date that is 2 months after the **participant** became a **designated transmission customer**.

Compare: Electricity Governance Rules 2003 rule 4.1 section II part F

### 12.30 Principles for benchmark agreements

A **benchmark agreement** should—

- (a) reflect a fair and reasonable balance between the requirements of **designated transmission customers** and the legitimate interests of **Transpower** as **asset owner**; and
- (b) reflect the interests of end use customers; and
- (c) reflect the reasonable requirements of **designated transmission customers** at the **grid injection points** and **grid exit points**, and the ability of **Transpower** to meet those requirements; and
- (d) reflect the differing needs of different classes of **designated transmission customers**; and
- (e) be appropriate to the technical requirements of services provided at the **point of connection** to the **grid**, but not duplicate requirements that are more appropriately included in the **grid reliability standards**; and
- (f) establish common standards for a common configuration based on factors such as size of connection and voltage level; and
- (g) encourage efficient and effective processes for enforcement of obligations and dispute resolution.

Compare: Electricity Governance Rules 2003 rule 4.2 section II part F

Clause 12.30(f): amended, on 23 February 2015, by clause 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 12.30(f): amended, on 5 October 2017, by clause 292 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### 12.31 Contents of benchmark agreements

(1) A **benchmark agreement** must include—

- (a) an obligation on the parties to design, construct, maintain and operate all relevant plant and equipment in accordance with—
  - (i) relevant laws; and
  - (ii) the requirements of this Code (including obligations on **designated transmission customers** to provide information to facilitate system planning, as set out in clause 12.54); and
  - (iii) **good electricity industry practice** and applicable New Zealand technical and safety standards; and
- (b) an obligation on **designated transmission customers** to comply with **Transpower's** reasonable technical connection and safety requirements; and

- (c) an obligation on **designated transmission customers** to pay prices calculated in accordance with the **transmission pricing methodology** approved by the **Authority** under subpart 4; and
  - (d) arbitration or mediation processes for resolving disputes; and
  - (e) service definitions, service levels, and service measures to the extent practicable for transmission services, other than the services to which the clauses in subpart 6 apply.
- (2) A **benchmark agreement** must be consistent in all material respects with the **grid reliability standards**.

Compare: Electricity Governance Rules 2003 rule 4.3 section II part F

Clause 12.31(1)(b): amended, on 23 February 2015, by clause 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 12.31(1)(b): amended, on 5 October 2017, by clause 293 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### 12.32 Authority must consult on draft benchmark agreement

- (1) The **Authority** must **publish** draft **benchmark agreements**.
- (2) When the **Authority publishes** a draft **benchmark agreement**, the **Authority** must notify **registered participants** of the date (which must not be earlier than 15 **business days** after the date of publication of the draft **benchmark agreement**) by which submissions on the draft **benchmark agreement** must be received by the **Authority**.
- (3) Each submission on a draft **benchmark agreement** must be made in writing to the **Authority** and received on or before the **submission expiry date**. In addition to receiving written submissions, the **Authority** may elect to hear 1 or more oral submissions.

Compare: Electricity Governance Rules 2003 rules 4.4 and 4.5 section II part F

### 12.33 Decision on benchmark agreement

- (1) Within 20 **business days** after the **submission expiry date** (or such longer period as the **Authority** may allow), the **Authority** must complete its consideration of all submissions it receives on the draft **benchmark agreement** and consider whether to **incorporate** the draft **benchmark agreement** by reference as the **benchmark agreement**.
- (2) If the **Authority** decides to incorporate the **benchmark agreement** by reference in this Code, the **Authority** must determine a date on which the incorporation by reference takes effect and comply with Schedule 1 of the **Act** in relation to it.

Compare: Electricity Governance Rules 2003 rule 4.6 section II part F

### 12.34 Incorporation of benchmark agreement by reference

- (1) The **benchmark agreement** is incorporated by reference in this Code in accordance with section 32 of the **Act**.
- (2) Subclause (1) is subject to Schedule 1 of the **Act**, which includes a requirement that the **Authority** must give notice in the *Gazette* before an amended or substituted **benchmark agreement** becomes incorporated by reference in this Code.

Clause 12.34(1): amended, on 5 October 2017, by clause 294 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

*Variations from benchmark agreements and grid reliability standards and enhancement and removal of connection assets*

**12.35 Increased service levels and reliability**

- (1) This clause applies if—
- (a) a proposed **transmission agreement** is not consistent in all material respects with the **benchmark agreement** because it increases the service levels above those that would apply if the **benchmark agreement** applied in accordance with clauses 12.10 or 12.13; or
  - (b) subject to clause 12.39, a proposed **transmission agreement** or other agreement between **Transpower** and a **designated transmission customer** increases the level of reliability above the **grid reliability standards** for a particular **grid injection point** or **grid exit point**.
- (2) If this clause applies, the parties to the proposed **transmission agreement** must confirm in writing to the **Authority** that—
- (a) they have consulted with affected end use customers in relation to—
    - (i) the proposed service levels or the proposed increase in reliability; and
    - (ii) any resulting price implications; and
  - (b) there are no material unresolved issues affecting the interests of those end use customers.

Compare: Electricity Governance Rules 2003 rule 5.1 section II part F

Clause 12.35 Heading: amended, on 15 May 2014, by clause 32(a) of the Electricity Industry Participation (Minor Code Amendments) Code Amendment 2014.

Clause 12.35(1)(a): amended, on 15 May 2014, by clause 32(b) of the Electricity Industry Participation (Minor Code Amendments) Code Amendment 2014.

Clause 12.35(2): replaced, on 5 October 2017, by clause 295 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

**12.36 Decreased service levels and reliability**

- (1) This clause applies if—
- (a) a proposed **transmission agreement** is not consistent in all material respects with the **benchmark agreement** because it decreases the service levels below those that would apply if the **benchmark agreement** applied in accordance with clauses 12.10 or 12.13; or
  - (b) subject to clause 12.39, a proposed **transmission agreement** or other agreement between **Transpower** and a **designated transmission customer** decreases the level of reliability below the **grid reliability standards** for a particular **grid injection point** or **grid exit point**.
- (2) If this clause applies, the parties must obtain the **Authority's** approval of the proposed service levels or the lower level of reliability.
- (3) The parties must satisfy the **Authority** that the **Authority** should grant an approval under subclause (2), having regard to any potential material adverse impacts of the proposed service levels or the lower level of reliability on—
- (a) current and future service levels or reliability for any affected **designated transmission customer** or end use customer; and
  - (b) the price paid for transmission or distribution services, or **electricity**, by any affected **designated transmission customer** or end use customer.

Compare: Electricity Governance Rules 2003 rule 5.2 section II part F

Clause 12.36 Heading: amended, on 15 May 2014, by clause 33(a) of the Electricity Industry Participation (Minor Code Amendments) Code Amendment 2014.

Clause 12.36(1)(a): amended, on 15 May 2014, by clause 33(b) of the Electricity Industry Participation (Minor Code Amendments) Code Amendment 2014.

### 12.37 Variations that may increase or decrease reliability

If it is uncertain whether, subject to clause 12.39, a proposed **transmission agreement** or other agreement increases or decreases the service levels from those that would apply if the **benchmark agreement** applied, or whether a proposed **transmission agreement** or other agreement increases or decreases the level of reliability above or below the **grid reliability standards**, for a particular **grid injection point** or **grid exit point**, the parties must obtain the **Authority's** approval described in clause 12.36(2).

Compare: Electricity Governance Rules 2003 rule 5.3 section II part F

### 12.38 Other variations from terms of benchmark agreements

- (1) This clause applies if a proposed **transmission agreement** to be entered into by **Transpower** and a **designated transmission customer** under clause 12.8 is not consistent in all material aspects with the **benchmark agreement**, other than a situation to which clauses 12.35 to 12.37 apply.
- (2) If this clause applies, the parties must obtain the **Authority's** approval to the proposed variation from the **benchmark agreement**. The parties to the proposed **transmission agreement** must satisfy the **Authority** that they have consulted with any affected end use customers and **designated transmission customers** in relation to the proposed variation, and there are no material unresolved issues affecting the interests of those persons.

Compare: Electricity Governance Rules 2003 rule 5.4 section II part F

### 12.39 Customer specific value of expected unserved energy

- (1) *[Revoked]*
- (2) **Transpower** or a **designated transmission customer** may apply to the **Authority**—
  - (a) if permitted under a **transmission agreement**, for provisional approval to use a different **value of expected unserved energy** than the value specified in clause 4 of Schedule 12.2 for the purposes of determining whether to replace or enhance **connection assets** as provided for under that **transmission agreement**; or
  - (b) for approval to use a different **value of expected unserved energy** than the value specified in clause 4 of Schedule 12.2 for the purposes of applying the **grid reliability standards** under clauses 12.35 to 12.37 for a **grid injection point** or **grid exit point**, regardless of whether **Transpower** or the **designated transmission customer** has applied for the **Authority's** provisional approval under subclause (4).
- (3) An application under subclause (2) must be made in writing to the **Authority**—
  - (a) in the case of an application under subclause (2)(a), within 20 **business days** of the **designated transmission customer** proposing that different value to **Transpower** under the **transmission agreement**; and

- (b) in the case of an application under subclause (2)(b), within 20 **business days** of the **designated transmission customer** reaching an agreement with **Transpower** to which clauses 12.35 to 12.37 apply.
- (4) If **Transpower** or a **designated transmission customer** applies for approval of a different **value of expected unserved energy** under subclause (2)(a), the **Authority** may provisionally approve that value if the **Authority** considers that the value is a reasonable estimate of the **value of expected unserved energy** in respect of the **grid injection point** or **grid exit point** for the **designated transmission customer** concerned.
- (5) If **Transpower** or a **designated transmission customer** applies for approval of a different **value of expected unserved energy** under subclause (2)(b) the **Authority**—
  - (a) may approve that value if the **Authority** considers that the value is a reasonable estimate of the **value of expected unserved energy** in respect of the **grid injection point** or **grid exit point** for the **designated transmission customer** concerned; and
  - (b) may decline to approve that value despite having provisionally approved that value under subclause (4).
- (6) If the **Authority** approves the **value of expected unserved energy** proposed by **Transpower** or the **designated transmission customer** under subclause (2)(b), that **value of expected unserved energy** applies for the purposes of applying the **grid reliability standards** under clauses 12.35 to 12.37 for the **grid injection point** or **grid exit point** instead of the **value of expected unserved energy** specified under clause 4 of Schedule 12.2.
- (7) If the **Authority** does not approve the **value of expected unserved energy** proposed by **Transpower** or the **designated transmission customer** under subclause (2)(b), the **value of expected unserved energy** under clause 4 of Schedule 12.2 applies for the purposes of applying the **grid reliability standards** under clauses 12.35 to 12.37 for the **grid injection point** or **grid exit point**.

Compare: Electricity Governance Rules 2003 rule 5.5 section II part F

Clause 12.39 Heading: amended, on 1 February 2016, by clause 48(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

Clause 12.39: amended, on 1 February 2016, by clause 48(3) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

Clause 12.39(1): revoked, on 1 February 2016, by clause 48(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

Clause 12.39(2)(b): amended, on 1 February 2016, by clause 48(4) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

Clause 12.39(4): amended, on 1 February 2016, by clause 48(5) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

Clause 12.39(6): amended, on 1 February 2016, by clause 48(6) and (7) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

Clause 12.39(7): amended, on 1 February 2016, by clause 48(8) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

#### **12.40 Replacement and enhancement of shared connection assets**

- (1) If 2 or more **designated transmission customers** are connected to a **point of connection** and **Transpower** has notified those **designated transmission customers**, in accordance with the provisions of a **transmission agreement** between **Transpower** and each of the **designated transmission customers**, that a **grid reliability report**

**published by Transpower** in accordance with clause 12.76 sets out that the power system is not reasonably expected to meet the **N-1 criterion** at all times over the next 5 years because of a **connection asset** related to that **point of connection**, **Transpower** must—

- (a) as soon as practicable after notifying the **designated transmission customers**, investigate whether the **connection asset** meets the **grid reliability standards**; and
  - (b) if it finds that the **connection asset** does not meet the **grid reliability standards**, develop proposals for investment in the **grid** to ensure that the **connection asset** meets the **grid reliability standards** and propose them to the **designated transmission customers** as soon as reasonably possible after **publication** of the **grid reliability report**.
- (2) **Transpower** and the **designated transmission customers** notified under subclause (1) must attempt in good faith, within 6 months of the date on which **Transpower** makes its proposals to the **designated transmission customers** under subclause 1(b), or such longer period as the **Authority** may allow, to reach an agreement for an investment or other solution that will have the effect of—
- (a) maintaining the level of reliability for the **connection asset** at the level of reliability in the **grid reliability standards**; or
  - (b) increasing or decreasing the level of reliability for the **connection asset** above or below the **grid reliability standards**, so long as **Transpower** and the **designated transmission customers** have complied with clauses 12.35 to 12.37 and 12.39.
- (3) **Transpower** may undertake an investment proposed under subclause (2) only—
- (a) if the **designated transmission customers** unanimously agree with the proposal in accordance with subclause (2); or
  - (b) if the **designated transmission customers** do not unanimously agree or none of the **designated transmission customers** agree with the proposed investment, if—
    - (i) the proposal has been approved under a grid upgrade plan requested by the Electricity Commission in accordance with rule 5.10 of section II of part F of the **rules** before this Code came into force; or
    - (ii) the proposal is approved by the Commerce Commission under an investment proposal requested by the Commerce Commission in accordance with clause 12.44(1); or
    - (iii) the proposal is permitted under an input methodology determined by the Commerce Commission under section 54S of the Commerce Act 1986.

Compare: Electricity Governance Rules 2003 rule 5.6 section II part F

Clause 12.40(1): amended, on 23 February 2015, by clause 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 12.40(1): amended, on 5 October 2017, by clause 296 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

#### **12.41 Removal of shared connection assets from service**

- (1) If 2 or more **designated transmission customers** are connected to a **point of connection**, and **Transpower** is required by a **transmission agreement** between **Transpower** and each of those **designated transmission customers** to provide the **connection assets** at the **point of connection**, **Transpower** may **decommission** a



**connection asset** at that **point of connection** from service only—

- (a) if the **designated transmission customers** unanimously agree with the **decommissioning** and clauses 12.35 to 12.37 (if applicable) are complied with; or
  - (b) if the **designated transmission customers** do not unanimously agree, or none of the **designated transmission customers** agree, with the **decommissioning**, if the **decommissioning** results in a net benefit, as calculated under the test set out in clause 12.43.
- (2) To avoid doubt, this clause applies only if **Transpower** proposes to remove a **connection asset** from service and not replace the **asset** with another **connection asset**.

Compare: Electricity Governance Rules 2003 rule 5.7 section II part F

Clause 12.41(1): amended, on 23 February 2015, by clause 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 12.41(1): amended, on 5 October 2017, by clause 297 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

#### 12.42 Reconfiguration of shared connection assets

If 2 or more **designated transmission customers** are connected to a **point of connection**, and **Transpower** is required by a **transmission agreement** between **Transpower** and each of those **designated transmission customers** to provide the **connection assets** in the configuration specified in each of those **transmission agreements**, **Transpower** may only change that configuration—

- (a) if the **designated transmission customers** unanimously agree with the reconfiguration and clauses 12.35 to 12.37 (if applicable) are complied with; or
- (b) if the **designated transmission customers** do not unanimously agree, or none of the **designated transmission customers** agree with the reconfiguration, if the reconfiguration results in a net benefit, as calculated under the test set out in clause 12.43.

Compare: Electricity Governance Rules 2003 rule 5.8 section II part F

Clause 12.42: amended, on 23 February 2015, by clause 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 12.42: amended, on 5 October 2017, by clause 298 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

#### 12.43 Net benefits test

- (1) When **Transpower** is required to apply a net benefit test, **Transpower** must—
- (a) estimate the following costs:
    - (i) any additional fuel costs incurred by a **generator** in respect of any **generating units** that will be **dispatched** or are likely to be **dispatched** during or after the removal of the **connection asset** or the reconfiguration of the **connection assets**, arising as a result of the removal or reconfiguration:
    - (ii) any direct labour and material costs that will be incurred by **Transpower** and the **designated transmission customers** undertaking the removal of the **connection asset** or the reconfiguration of the **connection assets**:
    - (iii) any increase in the estimate of **expected unserved energy** in MWh multiplied by the value per MWh of that **expected unserved energy**, arising as a result of the removal of the **connection asset** or the reconfiguration of the **connection assets**:

- (iv) any of the following costs, if the cost is to a person that produces, transmits, retails, or consumes **electricity** in New Zealand:
  - (A) changes in fuel costs of **existing assets, committed projects and modelled projects**:
  - (B) changes in the value of involuntary **demand** curtailment:
  - (C) changes in the costs of **demand**-side management:
  - (D) changes in costs resulting from deferral of capital expenditure on **modelled projects**:
  - (E) changes in costs resulting from differences in the amount of capital expenditure on **modelled projects**:
  - (F) changes in costs resulting from differences in operations and maintenance expenditure on **existing assets, committed projects, and modelled projects**:
  - (G) changes in costs for **ancillary services**:
  - (H) changes in **losses**, including **local losses**:
  - (I) subsidies or other benefits provided under or arising pursuant to all applicable laws, regulations and administrative determinations:
  - (J) the value of the expected change in economic surplus due to a change in competition among **participants** arising as a result of the removal of the **connection asset** or the reconfiguration of the **connection assets**, excluding any expected change in economic surplus due to a change in another cost in this net benefit test:
- (v) any other relevant cost to a person that produces, transmits, retails or consumes **electricity** in New Zealand; and
- (b) estimate the following benefits:
  - (i) any reduction in maintenance costs arising as a result of the removal of the **connection asset** or the reconfiguration of the **connection assets** (including **Transpower's** and any **designated transmission customer's** costs):
  - (ii) any reduction in fuel costs incurred by a **generator** in respect of any **generating units**, arising or likely to arise during or after the removal of the **connection asset** or the reconfiguration of the **connection assets**, as a result of the removal or reconfiguration:
  - (iii) any decrease in the estimate of **expected unserved energy** in MWh multiplied by the value per MWh of that **expected unserved energy**, arising as a result of the removal of the **connection asset** or the reconfiguration of the **connection assets**:
  - (iv) any of the following benefits, if the benefit is to a person that produces, transmits, retails or consumes **electricity** in New Zealand:
    - (A) changes in fuel costs of **existing assets, committed projects and modelled projects**:
    - (B) changes in the value of involuntary **demand** curtailment:
    - (C) changes in the costs of **demand**-side management:
    - (D) changes in costs resulting from the deferral of capital expenditure on **modelled projects**:

- (E) changes in costs resulting from differences in the amount of capital expenditure on **modelled projects**:
- (F) changes in costs resulting from differences in operations and maintenance expenditure on **existing assets, committed projects, and modelled projects**:
- (G) changes in costs for **ancillary services**:
- (H) changes in **losses**, including **local losses**:
- (I) subsidies or other benefits provided under or arising pursuant to all applicable laws, regulations and administrative determinations:
- (J) the value of the expected change in economic surplus due to a change in competition among **participants** arising as a result of the removal of the **connection asset** or the reconfiguration of the **connection assets**, excluding any expected change in economic surplus due to a change in another benefit in this net benefit test:
- (v) any other relevant benefit to a person that produces, transmits, retails or consumes **electricity** in New Zealand; and
- (c) deduct the costs estimated under paragraph (a) from the benefits estimated under paragraph (b) to determine the net benefit of the proposed removal of the **connection asset** or the reconfiguration of the **connection assets**.
- (2) **Transpower** may apply the test under this clause at differing levels of rigour in different circumstances, which may include taking into account the number of **assets** to be removed or reconfigured, the value of the **assets** involved, and the size of the load served by the **assets**.
- (3) **Transpower** is only required to—
  - (a) make a reasonable estimate of the costs and benefits identified in subclause (1), based on information reasonably available to it at the time it undertakes the test, and taking into account the proposed number of **assets** to be removed or reconfigured, the value of the **assets** involved, and the size of the load served by the **assets**; and
  - (b) take account of events that can be reasonably foreseen.
- (4) **Transpower's** estimate of fuel costs under subclause (1) must—
  - (a) in relation to thermal **generating stations**, be a reasonable estimate of the fuel costs, based on the economic value of the fuel required for the relevant thermal **generating station**, and justified by **Transpower** with reference to opinions on the economic value of the fuel, provided by 1 or more independent and suitably qualified persons; and
  - (b) in relation to hydroelectric **generating stations**—
    - (i) be a reasonable estimate of the fuel costs, based on the economic value of the water stored at a hydroelectric **generating station**, provided by a suitably qualified person other than—
      - (A) **Transpower**; or
      - (B) an employee of **Transpower**; and
    - (ii) be **published**, as provided for in the **Outage Protocol**.

- (5) The direct labour costs of **Transpower** and **designated transmission customers** under subclause (1)(a) may include any amounts paid to contractors, but must not include any apportionment of the overheads or office costs of **Transpower** or **designated transmission customers**.
- (6) The material costs of **Transpower** and **designated transmission customers** under subclause (1)(a) are the costs of the materials used in carrying out the work during the removal of the **connection asset** or the reconfiguration of the **connection assets**.
- (7) In assessing costs and benefits under subclause (1), **Transpower** must consider any reasonably expected operating conditions, forecasts in the **system security forecast**, likely fuel costs, and any other reasonable assumptions.
- (8) The estimate of **expected unserved energy** in MWh multiplied by the value per MWh of that **expected unserved energy** under subclause (1) must be based on—
  - (a) the estimated amount and value of the **expected unserved energy** as agreed between **Transpower** and each affected **designated transmission customer**; or
  - (b) if **Transpower** and a **designated transmission customer** cannot agree on the amount and value of the **expected unserved energy** under paragraph (a), the **value of expected unserved energy** in clause 4 of Schedule 12.2 and **Transpower's** estimate of the **expected unserved energy** in respect of each affected **designated transmission customer** and end use **customer**.

Compare: Electricity Governance Rules 2003 rule 5.9 section II part F

Clause 12.43: substituted, on 16 December 2013, by clause 5 of the Electricity Industry Participation (Urgent Temporary Grid Reconfiguration) Code Amendment 2013.

Clause 12.43(8)(b): amended, on 1 February 2016, by clause 49 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

#### **12.44 Request to the Commerce Commission to request an investment proposal be submitted**

- (1) **Transpower** may request in writing that the Commerce Commission request that **Transpower** submit an investment proposal to the Commerce Commission—
  - (a) for the purposes of clause 12.40(3); or
  - (b) if permitted by a **transmission agreement**.
- (2) Unless requested to do so by the Commerce Commission, **Transpower** must not submit an investment proposal to the Commerce Commission for approval in respect of an investment that has been proposed by **Transpower** in accordance with a **transmission agreement** or clause 12.40(3).

Compare: Electricity Governance Rules 2003 rules 5.10 section II, and 12.2.2 section III part F

#### *Resolutions of disputes*

#### **12.45 Certain disputes relating to transmission agreements may be referred to Rulings Panel**

If a dispute between **Transpower** and a **designated transmission customer** concerning—

- (a) the customer specific terms of a **transmission agreement** being negotiated between those parties; or
- (b) a requested variation of any of the terms of a default **transmission agreement**

(other than a variation under clause 12.12) that applies between **Transpower** and the **designated transmission customer** in accordance with clauses 12.10 to 12.13 (including a requested variation from the services described in the default **transmission agreement**); or

- (c) the schedules proposed by **Transpower** under clauses 12.10(2)(b)(v) to (viii) for a default **transmission agreement**; or
- (d) any revision to Schedule 4 or Schedule 5 of a default **transmission agreement** proposed by **Transpower** under clause 12.12; or
- (e) the schedules proposed by **Transpower** under clauses 12.13(1)(b)(v) to (viii) on the expiry or termination of a **transmission agreement**—

is not resolved within a reasonable time, either party may refer the matter to the **Rulings Panel** for determination.

Compare: Electricity Governance Rules 2003 rule 6.1 section II part F

#### **12.46 Rulings Panel has discretion to determine dispute**

- (1) The **Rulings Panel** may, in its discretion, decide whether or not to undertake the determination of a dispute under clause 12.45(a) or (b).
- (2) If the **Rulings Panel** decides not to undertake the determination of the dispute, the **Rulings Panel** must inform **Transpower** or the **designated transmission customer**—
  - (a) that the **Rulings Panel** intends to do no more in relation to the matter; and
  - (b) of the reasons for that intention.

Compare: Electricity Governance Rules 2003 rule 6.2 section II part F

#### **12.47 Determinations by Rulings Panel**

- (1) In determining a dispute under this clause, the **Rulings Panel** must take into account—
  - (a) the principles for **benchmark agreements** in clause 12.30; and
  - (b) the desirability of consistent treatment of **designated transmission customers** except if special circumstances justify a departure; and
  - (c) the potential impact of a decision on the contents of other **transmission agreements** or existing agreements as described in clauses 12.49 and 12.50.
- (2) The **Rulings Panel** must not determine disputes relating to the interpretation or enforcement of a **transmission agreement** including a **benchmark agreement**.
- (3) The **Rulings Panel** must give notice to the parties of its determination, as soon as reasonably practicable.

Compare: Electricity Governance Rules 2003 rules 6.3 and 6.4 section II part F

Clause 12.47(1)(c): amended, on 16 December 2013, by clause 6 of the Electricity Industry Participation (Revocation of Part 16) Code Amendment 2013.

#### **12.48 Status of default transmission agreement while Rulings Panel determining dispute**

Nothing in clauses 12.45 to 12.47 overrides the application of a **benchmark agreement** as a default **transmission agreement** under clause 12.10, pending a determination of the **Rulings Panel**.

Compare: Electricity Governance Rules 2003 rule 6.5 section II part F

*Existing agreements not affected*

### 12.49 Existing agreements

- (1) Except as provided for by clause 12.95, this Part does not apply to or affect the rights, powers or obligations of a **participant** or **Transpower** under a written agreement entered into between that **participant** and **Transpower** for connection to and/or use of the **grid** that is—
  - (a) entered into before 29 October 2003; or
  - (b) based on **Transpower's** standard connection contract and entered into before 28 June 2007.
- (2) The exception from this Part in subclause (1) does not apply to a right, power or obligation of a **participant** that arises because of the variation of an agreement described in subclause (1).
- (3) To avoid doubt, the posted terms and conditions of **Transpower** do not constitute a written agreement.

Compare: Electricity Governance Rules 2003 rule 8.1 section II part F

Clause 12.49(1): amended, on 23 February 2015, by clause 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 12.49(1): amended, on 5 October 2017, by clause 299 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### 12.50 Copies of other agreements to be provided to Authority

- (1) If requested to do so by the **Authority**, **Transpower** or a **participant** must provide a copy of any written agreement for connection to and/or use of the **grid** that **Transpower** or the **participant** is a party to and that was entered into before 28 June 2007.
- (2) The copy that is provided must be—
  - (a) a copy of the complete agreement; and
  - (b) certified by a director or the chief executive of **Transpower** or the **participant**, to the best of the director's or chief executive's knowledge and belief, to be a true and complete copy of the agreement.
- (3) An agreement must be **published** by the **Authority**, unless the parties establish to the satisfaction of the **Authority** that there is good reason for not **publishing** the agreement.

Compare: Electricity Governance Rules 2003 rule 8.2 section II part F

Clause 12.50(1): amended, on 23 February 2015, by clause 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 12.50(1): amended, on 5 October 2017, by clause 300 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### 12.51 Application to Rio Tinto agreements *[Revoked]*

Compare: Electricity Governance Rules 2003 rule 8.3 section II part F

Clause 12.51: revoked, on 16 December 2013, by clause 7 of the Electricity Industry Participation (Revocation of Part 16) Code Amendment 2013.

## Subpart 3— Grid reliability and industry information

### 12.52 Contents of this subpart

This subpart relates to—

- (a) **grid reliability standards**; and

- (b) **investment contracts**; and
- (c) *[Revoked]*
- (d) **grid reliability reporting**.

Compare: Electricity Governance Rules 2003 rule 1 section III part F

Clause 12.52(c): revoked, on 1 February 2016, by clause 50 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

### 12.53 Purpose of the reliability and industry information clauses

The purposes of this subpart are to—

- (a) facilitate **Transpower's** ability to develop and implement long term plans (including timely securing of land access and resource consents) for investment in the **grid**; and
- (b) assist **participants** to identify and evaluate investments in **transmission alternatives**; and
- (c) facilitate efficient investment in generation; and
- (d) facilitate any processes pursuant to Part 4 of the Commerce Act 1986.

Compare: Electricity Governance Rules 2003 rule 2 section III part F

### 12.54 Obligations to provide information

- (1) Each **participant** must provide information reasonably required by the **Authority** for the purposes of this subpart and respond to requests from the **Authority** under this subpart promptly and accurately.
- (2) Each **participant** must use reasonable endeavours to provide accurate information.
- (3) The **Authority** is not liable for the accuracy of information provided by a **participant**.
- (4) Subject to the Official Information Act 1982, the **Authority** may at its discretion, or on the application of an affected party, withhold **publication** of confidential aspects of the information provided by a **participant** to the **Authority** if the **Authority** reasonably considers that there is good reason for withholding it.

Compare: Electricity Governance Rules 2003 rule 3 section III part F

### *Grid reliability standards*

### 12.55 Authority determines grid reliability standards

- (1) The **Authority** must determine the most appropriate **grid reliability standards**.
- (2) The **Authority** must consider and determine **grid reliability standards**, having regard to the purposes set out in clause 12.56 and the principles set out in clause 12.57.
- (3) The **grid reliability standards** that apply at the commencement of this Code are the **grid reliability standards** in Schedule 12.2.

Compare: Electricity Governance Rules 2003 rule 4.1 section III part F

### 12.56 Purpose of grid reliability standards

The purpose of the **grid reliability standards** is to provide a basis for **Transpower** and other parties to appraise opportunities for transmission investments and **transmission alternatives**.

Compare: Electricity Governance Rules 2003 rule 4.2 section III part F

### 12.57 Principles of grid reliability standards

The **grid reliability standards** should—

- (a) take into account that transmission investments are long-lived assets and require a long-term planning perspective; and
- (b) reflect the public interest in reasonable stability in planning, having regard to the long term nature of investment in transmission assets; and
- (c) be consistent with **good electricity industry practice**; and
- (d) provide flexibility to allow the form of the standards to evolve over time, reflecting any changes in **good electricity industry practice**.

Compare: Electricity Governance Rules 2003 rule 4.3 section III part F

### 12.58 Content of grid reliability standards

- (1) The **grid reliability standards** must contain 1 or more standards for reliability of the **grid**, which may include without limitation a primary reliability standard and other reliability standards.
- (2) The reliability standards set out in the **grid reliability standards** may differ to reflect differing circumstances in different regions supplied by the **grid**.
- (3) The **grid reliability standards** may include 1 or more standards for reliability of the **core grid**.
- (4) The **grid reliability standards** may contain supporting information, such as information summarising economic assessments balancing different levels of reliability and the expected value of energy at risk.

Compare: Electricity Governance Rules 2003 rule 4.4 section III part F

#### *Review of grid reliability standards*

### 12.59 Interested parties may request review of grid reliability standards

- (1) 1 or more interested parties may request a review by the **Authority** of the **grid reliability standards**. The request must be in the form of a written submission to the **Authority** describing—
  - (a) the nature of the interest of each party seeking the review; and
  - (b) how the review might enable the **grid reliability standards** to better reflect the purpose and principles set out in clauses 12.56 and 12.57
- (2) In addition to receiving written submissions, the **Authority** may elect to hear 1 or more oral submissions.
- (3) The **Authority** must either undertake a review of the **grid reliability standards**, or decline to review the **grid reliability standards** and **publish** reasons for declining.

Compare: Electricity Governance Rules 2003 rule 5.1 section III part F

### 12.60 Authority review of grid reliability standards

The **Authority** may initiate a review of the **grid reliability standards** for any reason consistent with the statutory objective of the Authority in section 15 of the **Act** and the purpose and principles set out in clauses 12.56 and 12.57.

Compare: Electricity Governance Rules 2003 rule 5.2 section III part F



### 12.61 Authority must publish draft grid reliability standards

- (1) This clause applies if the **Authority** undertakes a review of the **grid reliability standards** under clauses 12.59 or 12.60.
- (2) The **Authority** must **publish** draft **grid reliability standards**.
- (3) At the time the **Authority publishes** the draft **grid reliability standards** the **Authority** must **publish** the date by which submissions on the draft **grid reliability standards** are to be received by the **Authority**. The date must be no earlier than 15 **business days** from the date of **publication** of the draft **grid reliability standards**.
- (4) Each submission on the draft **grid reliability standards** must be made in writing to the **Authority** and be received on or before the **submission expiry date**. In addition to receiving written submissions, the **Authority** may elect to hear 1 or more oral submissions.

Compare: Electricity Governance Rules 2003 rules 4.5 and 4.6 section III part F

Clause 12.61(3): amended, on 5 October 2017, by clause 301 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### 12.62 Decision on grid reliability standards

Within 20 **business days** of the **submission expiry date** (or such longer period as the **Authority** may allow), the **Authority** must complete its consideration of all submissions it receives on the draft **grid reliability standards** and consider whether to include the **grid reliability standards** as a schedule to this Part, in accordance with the **Act**.

Compare: Electricity Governance Rules 2003 rule 4.7 section III part F

### *Core grid determination*

### 12.63 Authority determines core grid determination

- (1) The **Authority** must determine the most appropriate **core grid determination**.
- (2) The **core grid** specified in the **core grid determination** must include—
  - (a) at a minimum, those **assets** that comprise the main elements of the **grid**; and
  - (b) at most, all **assets** that form part of the **grid** and operate at nominal voltages of 66kV and above.
- (3) In determining the most appropriate **core grid determination**, and in a subsequent review of the **core grid determination**, the **Authority** must have regard to—
  - (a) the purposes set out in clause 12.64; and
  - (b) the principles set out in clause 12.57 for the **grid reliability standards**; and
  - (c) the objectives set out in clause 12.65.
- (4) In determining the most appropriate **core grid determination**, the **Authority** may engage **Transpower** or any other person to assist in the preparation of all or part of the **core grid determination**.
- (5) The **core grid determination** that applies at the commencement of this Code is the **core grid determination** in Schedule 12.3.

Compare: Electricity Governance Rules 2003 rule 5A.1 section III part F

#### 12.64 Purpose of core grid determination

The purpose of the **core grid determination** is to provide a basis for—

- (a) the **Authority** to determine the **grid reliability standards**; and
- (b) **Transpower** and other parties to appraise opportunities for transmission investment and **transmission alternatives**.

Compare: Electricity Governance Rules 2003 rule 5A.2 section III part F

#### 12.65 Objectives of core grid determination

The **Authority** must have regard to the following objectives in determining, and in any subsequent review of, the **core grid determination**:

- (a) avoiding the failure or removal from service of any **asset** forming part of the **core grid**, if the failure or removal from service of that **asset** may result in cascade failure;
- (b) providing flexibility to allow the **core grid** to evolve over time, reflecting any changes in the **grid**;
- (c) reflecting the public interest in reasonable stability in planning for transmission.

Compare: Electricity Governance Rules 2003 rule 5A.3 section III part F

#### *Review of core grid determination*

#### 12.66 Interested parties may request review of core grid determination

- (1) 1 or more interested parties may request a review by the **Authority** of the **core grid determination**. The request must be in the form of a written submission to the **Authority** describing—
  - (a) the nature of the interest of each party seeking the review; and
  - (b) how the review might enable the **core grid determination** to better reflect the purpose and objectives set out in clauses 12.64 and 12.65 respectively.
- (2) In addition to receiving written submissions, the **Authority** may elect to hear 1 or more oral submissions.
- (3) The **Authority** must either undertake a review of the **core grid determination**, or decline to review the **core grid determination** and **publish** reasons for declining.

Compare: Electricity Governance Rules 2003 rule 5B.1 section III part F

#### 12.67 Authority review of grid determination

The **Authority** may initiate a review of the **core grid determination** for any reason consistent with the statutory objective of the Authority in section 15 of the **Act** and the purpose and objectives set out in clauses 12.64 and 12.65 respectively.

Compare: Electricity Governance Rules 2003 rule 5B.2 section III part F

#### 12.68 Authority must publish draft core grid determination

- (1) This clause applies if the **Authority** undertakes a review of the **core grid determination** in accordance with clauses 12.66 or 12.67.
- (2) The **Authority** must **publish** a draft **core grid determination**.
- (3) When the **Authority publishes** the draft **core grid determination** the **Authority** must

**publish** the date by which submissions on the draft **core grid determination** are to be received by the **Authority**. The date must be no earlier than 15 **business days** from the date of publication of the draft **core grid determination**.

- (4) Each submission on the draft **core grid determination** must be made in writing to the **Authority** and be received on or before the **submission expiry date**. In addition to receiving written submissions, the **Authority** may elect to hear 1 or more oral submissions.

Compare: Electricity Governance Rules 2003 rules 5A.4 and 5A.5 section III part F

Clause 12.68(3): amended, on 5 October 2017, by clause 302 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### 12.69 Decision on core grid determination

Within 20 **business days** of the **submission expiry date** (or such longer period as the **Authority** may allow), the **Authority** must complete its consideration of all submissions it receives on the draft **core grid determination** and consider whether to include the **core grid determination** in a schedule to this Part.

Compare: Electricity Governance Rules 2003 rule 5A.6 section III part F

## *Investment contracts*

### 12.70 Purpose

Clause 12.71 provides for **investment contracts** to be agreed between **designated transmission customers** and **Transpower**, and establishes a process to manage any potential implications for **grid reliability standards**.

Compare: Electricity Governance Rules 2003 rule 8.1 section III part F

### 12.71 Investment contracts

**Transpower** may enter into an **investment contract** with implications for **grid reliability standards** only if—

- (a) the **investment contract** is consistent with the **grid reliability standards** or the proposed investment has been approved by the **Authority** under clause 12.36(2), and clause 12.36(2) will apply as if the **investment contract** was a **transmission agreement**; and
- (b) **Transpower** notifies the **Authority** of the proposed **investment contract**.

Compare: Electricity Governance Rules 2003 rule 8.2 section III part F

## *[Revoked]*

Cross Heading: revoked, on 1 February 2016, by clause 51(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

### 12.72 *[Revoked]*

Compare: Electricity Governance Rules 2003 rule 11.1 section III part F

Clause 12.72: revoked, on 1 February 2016, by clause 51(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

### 12.73 *[Revoked]*

Compare: Electricity Governance Rules 2003 rule 11.2 section III part F

Clause 12.73: revoked, on 1 February 2016, by clause 51(2) of the Electricity Industry Participation Code

Amendment (Code Review Programme) 2015.

**12.74** *[Revoked]*

Compare: Electricity Governance Rules 2003 rule 11.3 section III part F  
Clause 12.74: revoked, on 1 February 2016, by clause 51(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

**12.75** *[Revoked]*

Compare: Electricity Governance Rules 2003 rule 11.4 section III part F  
Clause 12.75: revoked, on 1 February 2016, by clause 51(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

*Grid reliability reporting*

**12.76 Transpower to publish grid reliability report**

- (1) **Transpower** must **publish a grid reliability report** setting out—
  - (a) a forecast of **demand** at each **grid exit point** over the next 10 years; and
  - (b) a forecast of **supply** at each **grid injection point** over the next 10 years; and
  - (c) whether the power system is reasonably expected to meet the **N-1 criterion**, including in particular whether the power system would be in a **secure state** at each **grid exit point**, at all times over the next 10 years; and
  - (d) proposals for addressing any matters identified in accordance with paragraph (c).
- (2) **Transpower** must **publish a grid reliability report** no later than 2 years after the date on which it **published** the previous **grid reliability report**, or such other date as determined by the **Authority** (having consulted with **Transpower**).
- (3) If there is a material change in the forecast **demand** at a **grid exit point** or in the forecast **supply** at a **grid injection point** in the period to which the most recent **grid reliability report** relates, **Transpower** must **publish** a revised **grid reliability report** as soon as reasonably practicable after the material change.

Compare: Electricity Governance Rules 2003 rule 12A section III part F  
Clause 12.76(2): amended, on 21 September 2012, by clause 17 of the Electricity Industry Participation (Minor Amendments) Code Amendment 2012.  
Clause 12.76(1): amended, on 5 October 2017, by clause 303 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

**Subpart 4—Transmission pricing methodology**

**12.77 Recovery of investment costs by Transpower**

The costs incurred by **Transpower** (irrespective of when they are incurred) in relation to an **approved investment** are recoverable by **Transpower** from **designated transmission customers** on the basis of the **transmission pricing methodology** and must be paid by **designated transmission customers** accordingly.

Compare: Electricity Governance Rules 2003 rule 17.1 section III part F

**12.78 Purpose for establishing transmission pricing methodology**

The purpose of the **transmission pricing methodology** is to ensure that, subject to Part 4 of the Commerce Act 1986, the full economic costs of **Transpower's** services are allocated in accordance with the **Authority's** objective in section 15 of the **Act**.

Compare: Electricity Governance Rules 2003 rule 1 section IV part F  
Clause 12.78: amended, on 1 June 2011, by clause 4 of the Electricity Industry Participation (Transmission Pricing) Code Amendment 2011.

### 12.79 Statutory objective

**Transpower**, in developing the **transmission pricing methodology**, and the **Authority**, in approving the **transmission pricing methodology**, must assess the **transmission pricing methodology** against the **Authority's** objective in section 15 of the **Act**.

Compare: Electricity Governance Rules 2003 rule 2 section IV part F  
Clause 12.79: substituted, on 1 June 2011, by clause 5 of the Electricity Industry Participation (Transmission Pricing) Code Amendment 2011.

### 12.80 Application and interpretation of pricing principles

*[Revoked]*

Compare: Electricity Governance Rules 2003 rule 3 section IV part F  
Clause 12.80: revoked, on 1 June 2011, by clause 6 of the Electricity Industry Participation (Transmission Pricing) Code Amendment 2011.

### 12.81 Authority must prepare an issues paper

- (1) The **Authority** must prepare an issues paper on—
  - (a) the process for development and approval of the **transmission pricing methodology**; and
  - (b) the guidelines to be followed by **Transpower** in preparing a methodology for allocating **Transpower's** revenues to **designated transmission customers**.
- (2) The process and guidelines must be developed in accordance with the **Authority's** objective in section 15 of the **Act**.

Compare: Electricity Governance Rules 2003 rule 4 section IV part F  
Clause 12.81: substituted, on 1 June 2011, by clause 7 of the Electricity Industry Participation (Transmission Pricing) Code Amendment 2011.

### 12.82 Authority must consult on issues paper

- (1) When the **Authority publishes** the issues paper, the **Authority** must **publish** of the date by which submissions are to be received by the **Authority**. The date must be no earlier than 15 **business days** from the date of **publication** of the issues paper.
- (2) Each submission on the issues paper must be made in writing to the **Authority** and received on or before the **submission expiry date**. In addition to receiving written submissions, the **Authority** may elect to hear one or more oral submissions.
- (3) Within 20 **business days** of the **submission expiry date** (or such longer period as the **Authority** may allow), the **Authority** must complete its consideration of all submissions it receives on the issues paper.

Compare: Electricity Governance Rules 2003 rule 5 section IV part F  
Clause 12.82(1): amended, on 5 October 2017, by clause 304 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### 12.83 Authority must publish process and guidelines for development of transmission pricing methodology

After consideration of submissions in clause 12.82(3), the **Authority** must, as soon as reasonably practicable, **publish**—

- (a) the process for the development of the **transmission pricing methodology**; and
- (b) any guidelines that **Transpower** must follow in developing the **transmission pricing methodology**.

Compare: Electricity Governance Rules 2003 rule 6 section IV part F

Clause 12.83: heading amended, on 1 June 2011, by clause 8(1) of the Electricity Industry Participation (Transmission Pricing) Code Amendment 2011.

Clause 12.83(b): amended, on 1 June 2011, by clause 8(2) of the Electricity Industry Participation (Transmission Pricing) Code Amendment 2011.

*Development of transmission pricing methodology by Transpower*

#### **12.84 A Transmission pricing methodology**

The **transmission pricing methodology** that applies at the commencement of this Code is the **transmission pricing methodology** in Schedule 12.4.

*Review of an approved transmission pricing methodology*

Heading: amended, on 1 June 2011, by clause 9 of the Electricity Industry Participation (Transmission Pricing) Code Amendment 2011.

#### **12.85 Review by Transpower**

At any time, **Transpower** may submit to the **Authority** a proposed variation of its **transmission pricing methodology**, provided that the submission is made at least 12 months after the last **Authority** approval of the **transmission pricing methodology**.

Compare: Electricity Governance Rules 2003 rule 11.1 section IV part F

#### **12.86 Review by the Authority**

The **Authority** may review an approved **transmission pricing methodology** if it considers that there has been a material change in circumstances.

Compare: Electricity Governance Rules 2003 rule 11.2 section IV part F

#### **12.87 Process for review**

A review of the **transmission pricing methodology** must take into account the requirements of clauses 12.79 and 12.89(1). The **Authority** must follow the processes outlined in clauses 12.91 to 12.94 when reviewing a **transmission pricing methodology**.

Compare: Electricity Governance Rules 2003 rule 11.3 section IV part F

#### **12.88 Transpower to submit methodology**

- (1) **Transpower** must submit a proposed **transmission pricing methodology** to the **Authority** within 90 days (or such longer period as the **Authority** may allow) of receipt of a written request from the **Authority**.
- (2) The **Authority** may, after **publishing** the process described in clause 12.83(a) and the guidelines described in clause 12.83(b), issue such a request.

Compare: Electricity Governance Rules 2003 rule 7.1 section IV part F

#### **12.89 Form of proposed transmission pricing methodology**

- (1) **Transpower** must develop its proposed **transmission pricing methodology** consistent

with—

- (a) any determination made under Part 4 of the Commerce Act 1986; and
  - (b) the **Authority's** objective in section 15 of the **Act**; and
  - (c) any guidelines **published** under clause 12.83(b).
- (2) **Transpower's** proposed **transmission pricing methodology** must include indicative prices to allow the **Authority** and interested parties to understand the impact of the methodology on **designated transmission customers**.

Compare: Electricity Governance Rules 2003 rule 7.2 section IV part F

Clause 12.89 (1)(b): substituted, on 1 June 2011, by clause 10 of the Electricity Industry Participation (Transmission Pricing) Code Amendment 2011.

#### **12.90 Authority may decline to consider proposed transmission pricing methodology**

- (1) The **Authority** may decline to consider the proposed **Transpower transmission pricing methodology** if, in the **Authority's** view, **Transpower** has not provided sufficient information for the **Authority** to make an informed assessment of the matters referred to in clauses 12.91 to 12.94.
- (2) If the **Authority** so declines, the **Authority** must advise **Transpower** of the extra information required, and **Transpower** must provide a revised **transmission pricing methodology** by a date specified by the **Authority**.

Compare: Electricity Governance Rules 2003 rule 7.3 section IV part F

#### *Process for determination of transmission pricing methodology*

#### **12.91 Authority may approve proposed transmission pricing methodology or refer back to Transpower**

- (1) After consideration of **Transpower's** proposed **transmission pricing methodology**, the **Authority** may either—
  - (a) approve the proposed **transmission pricing methodology** having regard to the requirements of clause 12.89(1); or
  - (b) refer the proposed **transmission pricing methodology** back to **Transpower** if in the **Authority's** view the proposed **transmission pricing methodology** does not adequately conform to the requirements of clause 12.89(1) and **Transpower** will have 20 **business days** to consider the **Authority's** concerns and to resubmit its proposed **transmission pricing methodology** for consideration by the **Authority**.
- (2) If the **Authority** considers that the **transmission pricing methodology** resubmitted by **Transpower** under subclause (1)(b) does not conform to the requirements of clause 12.89(1), the **Authority** may make any amendments it considers necessary to ensure that the proposed **transmission pricing methodology** adequately conforms to the requirements of clause 12.89(1).

Compare: Electricity Governance Rules 2003 rule 8.1 section IV part F

#### **12.92 Authority must publish proposed transmission pricing methodology**

- (1) The **Authority** must **publish** the proposed **transmission pricing methodology** as soon as practicable.
- (2) At the time the **Authority publishes** the proposed **transmission pricing methodology** the **Authority** must **publish** the date by which submissions are to be received by the

**Authority.** The date must be no earlier than 15 **business days** from the date of **publication** of the proposed **transmission pricing methodology**.

- (3) Each submission on the proposed **transmission pricing methodology** must be made in writing to the **Authority** and received on or before the **submission expiry date**. In addition to receiving written submissions, the **Authority** may elect to hear 1 or more oral submissions.

Compare: Electricity Governance Rules 2003 rules 8.2 and 8.3 section IV part F

Clause 12.92(2): amended, on 5 October 2017, by clause 305 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### 12.93 Decision on transmission pricing methodology

Within 40 **business days** of the **submission expiry date** (or such longer period as the **Authority** may allow), the **Authority** must complete its consideration of all submissions it receives on a proposed **transmission pricing methodology** and consider whether to include the **transmission pricing methodology** in a schedule to this Part and, if so, the date that the **transmission pricing methodology** will take effect.

Compare: Electricity Governance Rules 2003 rule 8.4 section IV part F

### 12.94 Authority to determine commencement date

In determining a date on which the **transmission pricing methodology** must take effect, the **Authority** must consult with **Transpower**.

Compare: Electricity Governance Rules 2003 rule 8.5 section IV part F

### *Application of approved transmission pricing methodology*

### 12.95 Charges to comply with approved transmission methodology

- (1) Except for the **input connection contracts**, **new investment agreement contracts**, and **notional embedding contracts**, **Transpower** must charge for those transmission services affected only in accordance with the approved **transmission pricing methodology**.

- (2) *[Revoked]*

Compare: Electricity Governance Rules 2003 rule 9.1 section IV part F

Clause 12.95(1): amended, on 16 December 2013, by clause 8(1) of the Electricity Industry Participation (Revocation of Part 16) Code Amendment 2013.

Clause 12.95(2): revoked, on 16 December 2013, by clause 8(2) of the Electricity Industry Participation (Revocation of Part 16) Code Amendment 2013.

### 12.96 Development of transmission prices

After approval of the **transmission pricing methodology**, **Transpower** must—

- (a) develop and **publish** transmission prices consistent with the **transmission pricing methodology** based on its total revenue requirement for connection to or use of the **grid**; and
- (b) demonstrate to the **Authority** that the prices are consistent with the **transmission pricing methodology**.

Compare: Electricity Governance Rules 2003 rule 9.2 section IV part F

Clause 12.96(a): amended, on 23 February 2015, by clause 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 12.96(a): amended, on 5 October 2017, by clause 306 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.



*Audit of transmission prices*

**12.97 Audit of transmission prices**

- (1) The **Authority** may appoint an **auditor** to confirm whether **Transpower's** transmission prices have been calculated in accordance with the **transmission pricing methodology**.
- (2) **Transpower** must ensure that the **auditor's** report includes the **auditor's** view on whether the application of the **transmission pricing methodology** by **Transpower** contains errors or inconsistencies that may have a material impact on the prices of any individual **designated transmission customers**, or **designated transmission customers** in general.
- (3) **Transpower** must provide the **auditor** with all relevant information required by the **auditor** to complete its review.

Compare: Electricity Governance Rules 2003 rule 9.3 section IV part F  
Clause 12.97(2): amended, on 1 February 2016, by clause 52 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

**12.98 Transpower may respond to auditor's report**

**Transpower** must ensure that the **auditor's** report includes any comments that **Transpower** provided to the **auditor** within 15 **business days** of **Transpower** receiving a draft of the report.

Compare: Electricity Governance Rules 2003 rule 9.4 section IV part F  
Clause 12.98: substituted, on 1 February 2016, by clause 53 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

**12.99 Final auditor report to the Authority**

- (1) **Transpower** must ensure that, within 10 **business days** after the **auditor** receives **Transpower's** response under clause 12.98, the **auditor** provides a report to the **Authority** certifying that either—
  - (a) **Transpower** had applied correctly the approved **transmission pricing methodology**; or
  - (b) material errors remained in **Transpower's** application of the **transmission pricing methodology**.
- (2) Within 5 **business days** of receiving the report, the **Authority** must **publish** the **auditor's** report.

Compare: Electricity Governance Rules 2003 rules 9.5 and 9.6 section IV part F  
Clause 12.99(1): amended, on 1 February 2016, by clause 54 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

**12.100 Transpower to redetermine transmission prices**

If the **auditor** concludes that there are material errors in **Transpower's** application of the **transmission pricing methodology**, **Transpower** must recalculate and **publish** revised transmission prices to correct identified errors.

Compare: Electricity Governance Rules 2003 rule 9.7 section IV part F

### 12.101 Auditor's costs

**Transpower** must meet the actual and reasonable expenses of the **auditor**.

Compare: Electricity Governance Rules 2003 rule 9.8 section IV part F

### 12.102 Enforcement of transmission charges

- (1) The approved **transmission pricing methodology** must be incorporated in **transmission agreements** between **Transpower** and **designated transmission customers**.
- (2) The amount payable by a **designated transmission customer** under a **transmission agreement** under subclause (1)—
  - (a) is recoverable in any court of competent jurisdiction as a debt due to **Transpower**; and
  - (b) may be challenged in any proceedings to recover the debt on the ground that **Transpower** has incorrectly applied the **transmission pricing methodology** in a manner that is adverse to the **designated transmission customer** but the **transmission pricing methodology** itself may not be challenged.

Compare: Electricity Governance Rules 2003 rule 10 section IV part F

## Subpart 5—Financial transmission rights *[Revoked]*

Subpart 5: revoked, on 1 October 2011, by clause 6 of the Electricity Industry Participation (Financial Transmission Rights) Code Amendment 2011.

### 12.103 Contents of this subpart

*[Revoked]*

Compare: Electricity Governance Rules 2003 rule 1 section V part F

Clause 12.103: revoked, on 1 October 2011, by clause 6 of the Electricity Industry Participation (Financial Transmission Rights) Code Amendment 2011.

### 12.104 Design

*[Revoked]*

Compare: Electricity Governance Rules 2003 rule 2 section V part F

Clause 12.104: revoked, on 1 October 2011, by clause 6 of the Electricity Industry Participation (Financial Transmission Rights) Code Amendment 2011.

## Subpart 6—Interconnection asset services

### 12.105 Purpose of this subpart

The purpose of this subpart is to—

- (a) create incentives on **Transpower**, through enforceable service measures, to provide **interconnection assets** at the capacity ratings required by **designated transmission customers** and other **grid** users; and
- (b) ensure that **Transpower** provides information on the capacity of **interconnection assets**, and their reliability and availability, to enable **grid** users to monitor the capacity and performance of **interconnection assets**; and
- (c) establish processes for the identification of investments in the **grid**, and alternatives to such investments, to ensure efficient decision-making on the use of

and upgrades to the **grid**; and

- (d) specify the circumstances in which **Transpower** may permanently or temporarily remove **interconnection assets** from service or reconfigure the **grid**.

Compare: Electricity Governance Rules 2003 rule 1 section VI part F

Clause 12.105(d): amended, from 2 March 2012 to 3 December 2012, by clause 4 of the Electricity Industry Participation (Temporary Grid Reconfiguration) Code Amendment 2012.

Clause 12.105(d): amended, from 15 March 2013 to 15 December 2013, by clause 4 of the Electricity Industry Participation (Temporary Grid Reconfiguration) Code Amendment 2013.

Clause 12.105(d): amended, 16 December 2013, by clause 6 of the Electricity Industry Participation (Urgent Temporary Grid Reconfiguration) Code Amendment 2013.

### 12.106 Interconnection asset capacity and grid configuration

- (1) The interconnection asset capacity and grid configuration set out in schedule F6 of section VI of part F of the **rules** immediately before this Code came into force, continues in force and is deemed to be the interconnection asset capacity and grid configuration that applies at the commencement of this Code.
- (2) Clause 12.110 applies to the interconnection asset capacity and grid configuration.

### 12.107 Transpower to identify interconnection branches, and propose service measures and levels

- (1) **Transpower** must provide the **Authority** with the information set out in subclause (4) and a diagram showing the configuration of the **grid**, other than **connection assets**.
- (2) **Transpower** must provide the information and diagram referred to in subclause (1) to the **Authority** in the form specified by the **Authority**.
- (3) The interconnection asset capacity and grid configuration referred to in subclause (1) must be provided within 3 months of the date on which the **Authority**, in accordance with subclause (2), sets the form in which the interconnection asset capacity and grid configuration must be provided.
- (4) The information required under subclause (1) is—
- (a) for each **interconnection circuit branch**, the following service measures and service levels:
- (i) the overall continuous capacity rating of the **interconnection circuit branch**, for both summer and winter periods in MVA and amperes:
  - (ii) the level of impedance of the interconnection **circuit branch** both **resistive** and **reactive** and for **assets** arranged in both **shunt** and **series** in PU, using a base of 100 MVA, provided the impedance of the **interconnection circuit branch** is equal to or more than 0.0001 PU, using 100 MVA as the base:
  - (iii) the nominal high voltage rating of each interconnection **circuit branch** in kV:
  - (iv) the high voltage range that each **interconnection circuit branch** can be operated over in kV, specified as a maximum and a minimum; and
- (b) for each **interconnection transformer branch**, the following information:
- (i) the overall 24 hour post contingency capacity rating of the **interconnection transformer branch**, for both the summer and winter period, in amperes and MVA as follows:
    - (A) for 2 Winding **interconnection transformer branches**, the overall 24

- hour post contingency capacity rating:
- (B) for 3 Winding **interconnection transformer branches**, the overall 24 hour post contingency capacity rating, at HV, MV, and LV:
  - (ii) the continuous capacity rating of the **interconnection transformer branch** in amperes and MVA as follows:
    - (A) for 2 Winding **interconnection transformer branches**, the continuous capacity rating:
    - (B) for 3 Winding **interconnection transformer branches**, the continuous capacity rating, at HV, MV, and LV:
  - (iii) the level of impedance of the **interconnection transformer branch**, both **resistive** and **reactive** and for **assets** arranged in both **shunt** and in **series** in PU, using a base of 100 MVA, as follows:
    - (A) for 2 Winding **interconnection transformer branches**, the level of impedance of the **interconnection transformer branch**:
    - (B) for 3 Winding **interconnection transformer branches**, the level of impedance of the **interconnection transformer branch**, at HV, MV, and LV:
  - (iv) the nominal high voltage rating of the interconnection **transformer branch** in kV:
  - (v) the high voltage range that the interconnection **transformer branch** can be operated over in kV, specified as a maximum, and a minimum:
  - (vi) in respect of the tapping steps and ranges of the **interconnection transformer branch**:
    - (A) the tap voltage range in volts, specified as a maximum and a minimum:
    - (B) the **number** of tapping steps:
    - (C) the size of each tapping step as a percentage of the operational voltage range:
    - (D) whether the tapping step is on-load or off-load:
    - (E) whether on-load tapping capacity is automatic or manual;
    - (F) if on-load tapping capacity is automatic, whether it is auto-selected:
    - (G) if on-load tapping capacity is manual, the tap step it is normally set to, which for the purposes of this clause is the actual or expected position at winter peak demand; and
  - (c) the **transfer** capacity in the North and South transfer for each **configuration** of the **HVDC link** expressed as follows:
    - (i) DC sent in **MW**:
    - (ii) AC received in **MW**; and
  - (d) for each **shunt asset**, the following service measures and service levels:
    - (i) the overall capacity rating, in MVar, in terms of both absorption or provision:
    - (ii) the nominal voltage rating of the **shunt asset** in kV:
    - (iii) the maximum and minimum voltage range in kV that the **shunt asset** can operate over; and

- (e) in addition to the information required under paragraph (d) in relation to **shunt assets**:
    - (i) whether each **shunt asset** is dynamic or static;
    - (ii) if the **shunt asset** is dynamic, whether it is an SVC or synchronous compensator;
    - (iii) any **shunt assets** that may directly affect the capacity of the **HVDC link** as set out in paragraph (c) and the likely magnitude of such effect; and
  - (f) the dates for the summer and winter periods or other such defined periods as may apply for the purposes of paragraphs (a) and (b).
- (5) The information provided under subclause (4) must,—
- (a) in the case of information provided under subclause (4)(a), (c) and (d), be consistent with the information disclosed by **Transpower** in the most recent **asset capability statement** provided by **Transpower** under clause 2(5) of **Technical Code A** of Schedule 8.3; and
  - (b) in the case of information provided under subclause (4)(b), be consistent with the **manufacturer's specification** for the component **assets** and the information disclosed by **Transpower** in the most recent **asset capability statement** provided under clause 2(5) of **Technical Code A** of Schedule 8.3, if this differs from the **manufacturer's specifications**;
  - (c) in the case of information provided under subclause (4)(a), be consistent with the thermal design rating of each **interconnection branch**; and
  - (d) cover every **interconnection asset**, either as part of an **interconnection circuit branch**, **interconnection transformer branch**, the **HVDC link** or as a **shunt asset**.
- (6) After reviewing the interconnection asset capacity and grid configuration provided under subclause (1), the **Authority** may request **Transpower** to reconsider whether any of the interconnection asset capacity and grid configuration, is accurate, and require **Transpower** to resubmit the interconnection asset capacity and grid configuration to the **Authority** for reconsideration.

Compare: Electricity Governance Rules 2003 rules 2.1 to 2.6 section VI part F

Clause 12.107(2): replaced, on 5 October 2017, by clause 307(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 12.107(4): amended, on 5 October 2017, by clause 307(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 12.107(5): amended, on 5 October 2017, by clause 307(3) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### **12.108 Consultation on proposed interconnection asset capacity and grid configuration**

- (1) If the **Authority** is provisionally satisfied that the interconnection asset capacity and grid configuration provided under clause 12.107(1) or resubmitted under clause 12.107(6) are correct, the **Authority** must **publish** the proposed interconnection asset capacity and grid configuration as soon as practicable for consultation with any person that the **Authority** thinks is likely to be materially affected by the incorporation of the proposed interconnection asset capacity and grid configuration by reference in this Code.
- (2) As well as the consultation required under subclause (1), the **Authority** may undertake

any other consultation it considers necessary.

Compare: Electricity Governance Rules 2003 rules 2.7 and 2.8 section VI part F

#### 12.109 Decision on interconnection asset capacity and grid configuration

- (1) When the **Authority** has completed its consultation on the proposed interconnection asset capacity and grid configuration, it must consider whether to incorporate the proposed interconnection asset capacity and grid configuration by reference in this Code.
- (2) If the **Authority** decides to incorporate the interconnection asset capacity and grid configuration by reference in this Code, the **Authority** must determine a date on which the incorporation by reference takes effect and comply with Schedule 1 of the **Act** in relation to it.

Compare: Electricity Governance Rules 2003 rule 2.9 section VI part F

#### 12.110 Incorporation of interconnection asset capacity and grid configuration by reference

- (1) The interconnection asset capacity and grid configuration is incorporated by reference in this Code in accordance with section 32 of the **Act**.
- (2) Subclause (1) is subject to Schedule 1 of the **Act**, which includes a requirement that the **Authority** must give notice in the *Gazette* before an amended or substituted interconnection asset capacity and grid configuration becomes incorporated by reference in this Code.

Clause 12.110(1): amended, on 5 October 2017, by clause 308 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

#### 12.111 Transpower to make interconnection branches and other assets available and keep grid configuration

- (1) **Transpower** must make each **interconnection circuit branch**, **interconnection transformer branch**, the **HVDC link**, and each **shunt asset** identified in the interconnection asset capacity and grid configuration available for use by the **system operator** for the conveyance of **electricity**—
  - (a) at least at the service levels specified in the interconnection asset capacity and grid configuration in accordance with clause 12.107(4); and
  - (b) in accordance with **good electricity industry practice** and relevant health and safety standards.
- (2) **Transpower** must keep the **grid** in the configuration set out in the interconnection asset capacity and grid configuration.
- (3) **Transpower** is not required to comply with subclauses (1)(a) or (2) if clause 12.112(1) applies.

Compare: Electricity Governance Rules 2003 rule 3 section VI part F

#### 12.112 Exceptions to clause 12.111

- (1) **Transpower** is not required to comply with clause 12.111(1)(a) or (2) if—
  - (a) permitted under the **Outage Protocol** made under subpart 7; or
  - (b) an **interconnection asset** that forms part of an interconnection **branch** or the

**HVDC link, or a shunt asset—**

- (i) is permanently removed from service, the **grid** is permanently reconfigured, or the transmission capacity of such an **asset** is reduced, and the decision to remove the **asset** from service or reconfigure the **grid** or reduce the transmission capacity of the **asset** takes into account the effect of the removal of the **asset**, reconfiguration of the **grid**, or the reduction in transmission capacity of the **asset**, on other materially affected parties, and is undertaken—
    - (A) in order to maintain the health and safety of any person; or
    - (B) in order to maintain the safety and integrity of equipment; or
    - (C) in accordance with demonstrably prudent economic criteria; or
  - (iaa) has been temporarily removed from service, or the **grid** has been temporarily reconfigured, in accordance with clause 12.116AA; or
  - (ia) *[Expired]*
  - (ii) has been permanently removed from service, or the **grid** has been permanently reconfigured, in accordance with clause 12.117; or
  - (c) a modification to an **interconnection branch**, the **HVDC link**, a **shunt asset** or to the configuration of the **grid**, has been made as a result of an investment in the **grid**; or
  - (d) a modification to an **interconnection branch**, the **HVDC link**, a **shunt asset** or to the configuration of the **grid** has been made as a result of an investment made under an **investment contract** entered into in accordance with clauses 12.70 and 12.71; or
  - (e) the voltage range specified in the **AOPs** for an **interconnection asset** that forms part of an **interconnection branch** is modified, or any **equivalence arrangement** is approved or **dispensation** is granted under clauses 8.29 to 8.31 in respect of the **asset**; or
  - (ea) in relation to the **HVDC link**—
    - (i) the **HVDC owner** is operating the **HVDC link** in accordance with—
      - (A) a **commissioning** plan agreed with the **system operator** under clause 2(6) to (9) of **Technical Code A** of Schedule 8.3; or
      - (B) a test plan provided to the **system operator** under clause 2(6) to (9) of **Technical Code A** of Schedule 8.3; and
    - (ii) the **configuration** of the **HVDC link** is—
      - (A) Pole 3 and Pole 2 bipole **round power**; or
      - (B) Pole 3 and Pole 2 bipole not **round power**; or
  - (f) **Transpower** and a **designated transmission customer** have agreed otherwise in accordance with clause 12.128.
- (2) If subclause (1)(c) to (e) applies, or the **grid** is reconfigured under subclause (1)(b)(i) or (ii), **Transpower** must—
- (a) make the **interconnection branch**, the **HVDC link** or the **shunt asset** available to the **system operator** at least at its modified capacity rating, and at its modified service levels; and
  - (b) keep the **grid** in its modified configuration.

- (2AA) Subclause (2AB) applies—
- (a) if subclause (1)(b)(iaa) applies; and
  - (b) while—
    - (i) an **interconnection asset** that forms part of an **interconnection branch** or the **HVDC link**, or a **shunt asset**, has been temporarily removed; or
    - (ii) the **grid** has been temporarily reconfigured.
- (2AB) **Transpower** must make the **interconnection branch**, the **HVDC link** or the **shunt asset** available to the **system operator** at least at its modified capacity rating, and at its modified service levels.
- (2A) *[Expired]*
- (2B) *[Expired]*
- (3) If a decision to remove an **asset**, or reconfigure the **grid**, or reduce the transmission capacity of an **asset** has been made under subclause (1)(b)(i) or (ii), **Transpower** must as soon as reasonably possible **publish** the analysis it undertook in accordance with subclause (1)(b)(i) or (ii), or a summary of that analysis.

Compare: Electricity Governance Rules 2003 rule 4 section VI part F

Clause 12.112(1)(b): amended, from 2 March 2012 to 3 December 2012, by clause 5(1) of the Electricity Industry Participation (Temporary Grid Reconfiguration) Code Amendment 2012.

Clause 12.112(1)(b)(i): amended, from 15 March 2013 to 15 December 2013, by clause 5(1)(a) of the Electricity Industry Participation (Temporary Grid Reconfiguration) Code Amendment 2013.

Clause 12.112(1)(b)(i): amended, on 16 December 2013, by clause 7(1) of the Electricity Industry Participation (Urgent Temporary Grid Reconfiguration) Code Amendment 2013.

Clause 12.112(1)(b)(iaa): inserted, from 15 March 2013 to 15 December 2013, by clause 5(1)(b) of the Electricity Industry Participation (Temporary Grid Reconfiguration) Code Amendment 2013.

Clause 12.112(1)(b)(iaa): inserted, on 16 December 2013, by clause 7(2) of the Electricity Industry Participation (Urgent Temporary Grid Reconfiguration) Code Amendment 2013.

Clause 12.112(1)(b)(ii): amended, from 15 March 2013 to 15 December 2013, by clause 5(1)(c) of the Electricity Industry Participation (Temporary Grid Reconfiguration) Code Amendment 2013.

Clause 12.112(1)(b)(ii): amended, on 16 December 2013, by clause 7(3) of the Electricity Industry Participation (Urgent Temporary Grid Reconfiguration) Code Amendment 2013.

Clause 12.112(1)(ea): inserted, on 26 September 2013, by clause 4 of the Electricity Industry Participation (HVDC Link Bipole Control System Testing) Code Amendment 2013.

Clause 12.112(1)(ea)(i)(A): amended, on 5 October 2017, by clause 309(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 12.112(2): amended, from 2 March 2012 to 3 December 2012, by clause 5(2) of the Electricity Industry Participation (Temporary Grid Reconfiguration) Code Amendment 2012.

Clause 12.112(2): amended, from 15 March 2013 to 15 December 2013, by clause 5(2) of the Electricity Industry Participation (Temporary Grid Reconfiguration) Code Amendment 2013.

Clause 12.112(2): amended, on 16 December 2013, by clause 7(4) of the Electricity Industry Participation (Urgent Temporary Grid Reconfiguration) Code Amendment 2013.

Clause 12.112(2): amended, on 5 October 2017, by clause 309(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 12.112(2AA) and (2AB): inserted, from 15 March 2013 to 15 December 2013, by clause 5(3) of the Electricity Industry Participation (Temporary Grid Reconfiguration) Code Amendment 2013.

Clause 12.112(2AA) and (2AB): inserted, on 16 December 2013, by clause 7(5) of the Electricity Industry Participation (Urgent Temporary Grid Reconfiguration) Code Amendment 2013.

Clause 12.112(2A) and (2B): inserted, from 2 March 2012 to 3 December 2012, by clause 5(3) of the Electricity Industry Participation (Temporary Grid Reconfiguration) Code Amendment 2012.

Clause 12.112(3): amended, from 15 March 2013 to 15 December 2013, by clause 5(4) of the Electricity Industry Participation (Temporary Grid Reconfiguration) Code Amendment 2013.

Clause 12.112(3): amended, on 16 December 2013, by clause 7(6) of the Electricity Industry Participation (Urgent Temporary Grid Reconfiguration) Code Amendment 2013.

Clause 12.112(3): amended, on 5 October 2017, by clause 309(3) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.



### 12.113 Transpower to maintain interconnection assets

Transpower must design, construct, maintain and operate all **interconnection assets** in accordance with **good electricity industry practice**.

Compare: Electricity Governance Rules 2003 rule 5 section VI part F

### *Transpower to propose investments*

### 12.114 Investments to meet the grid reliability standards

- (1) If a **grid reliability report** identifies, in accordance with clause 12.76(1)(c), that the power system is not reasonably expected to meet the **N-1 criterion** at a **grid exit point** at all times over the 5 years following the date on which the report is **published** and that this is due to an **interconnection asset**, **Transpower** must—
  - (a) as soon as practicable, investigate whether the **interconnection asset** meets the **grid reliability standards**; and
  - (b) if the **interconnection asset** does not **meet** the **grid reliability standards**, consider reasonably practicable options for ensuring that the **grid reliability standards** can be met in respect of that asset; and
  - (c) if **Transpower** considers that 1 or more investments are required in respect of that **interconnection asset** in order to meet the **grid reliability standards**, submit an investment proposal to the Commerce Commission—
    - (i) in sufficient time to avoid a breach of the **grid reliability standards**; or
    - (ii) if the **grid reliability standards** have already been breached, within 6 months, or such longer period as the **Authority** may allow, after the publication of the **grid reliability report** that sets out the investment or investments that **Transpower** proposes to make; and
  - (d) if it considers that an investment is not necessary, **publish** the reasons for this and any alternative measures that **Transpower** proposes to undertake.
- (2) If an investment proposal submitted under this clause is approved by the Commerce Commission under section 54R of the Commerce Act 1986 or permitted under an input methodology determined under section 54S of that Act, **Transpower** must undertake the investment—
  - (a) before the **grid** falls below the **grid reliability standards** for the reason referred to in subclause (1); or
  - (b) if the **grid** had already fallen below the **grid reliability standards**, or if it is not reasonably practicable to undertake the investment as provided in paragraph (a), as soon as reasonably practicable.
- (3) **Transpower** does not need to submit an investment proposal under subclause (1)(c) if the investment to which the proposal relates has previously been included in an investment proposal submitted to, and considered—
  - (a) before this Code came into force, by the Electricity Commission under section III of part F of the **rules**; or
  - (b) after this Code came into force, by the Commerce Commission under section 54R or section 54S of the Commerce Act 1986.

Compare: Electricity Governance Rules 2003 rule 6.1 section VI part F

### 12.115 Other investments

- (1) **Transpower** must publish a **grid economic investment report** on whether there are investments that it considers, other than the investments identified under clause 12.114, could be made in respect of the **interconnection assets**.
- (2) **Transpower** must publish a **grid economic investment report** no later than 2 years after the date on which it published the previous **grid economic investment report**, or such other date as determined by the **Authority**.
- (3) If a **grid economic investment report** identifies that there are investments that could be made, **Transpower** must **publish** within 6 months a report setting out a proposed timetable for **Transpower** to consider whether to submit 1 or more investment proposals to the Commerce Commission in respect of those possible investments.
- (4) The **grid economic investment report** does not need to report on possible investments that have been previously included in an investment proposal submitted to, and considered,—
  - (a) before this Code came into force, by the Electricity Commission under section III of part F of the **rules**; or
  - (b) after this Code came into force, by the Commerce Commission under section 54R or section 54S of Part 4 of the Commerce Act 1986.

Compare: Electricity Governance Rules 2003 rule 6.2 section VI part F

### 12.116 Information on capacities of individual interconnection assets

- (1) **Transpower** must **publish** the following information in respect of each **interconnection asset**:
  - (a) for each transformer that is an **interconnection asset**, the overall 24 hour post contingency capacity rating of the **asset** in amperes and MVA, for both the summer and winter periods;
  - (b) for all other **interconnection assets**, the overall capacity rating of the **asset** in amperes and MVA and, if the **interconnection assets** are circuits, for both the summer and winter periods.
- (2) The information required under subclause (1)—
  - (a) must be consistent with the **manufacturer's specification** for the **asset** or with the most recent **asset capability statement** provided by **Transpower** under clause 2(5) of **Technical Code A** of Schedule 8.3, if this differs from the **manufacturer's specification**; and
  - (b) must be in a form that allows the **branch** to which each **asset** belongs to be easily identified; and
  - (c) must be **published** in the form determined by the **Authority** as soon as reasonably practicable after the **Authority** has determined the form.

Compare: Electricity Governance Rules 2003 rule 7 section VI part F

Clause 12.116(1): amended, on 5 October 2017, by clause 310(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 12.116(2)(b): amended, on 5 October 2017, by clause 310(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 12.116(2)(c): substituted, on 1 February 2016, by clause 55 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

### 12.116AA Temporary removal of interconnection assets from service or temporary grid reconfiguration

- (1) **Transpower** must temporarily remove 1 or more **interconnection assets** from service, or temporarily reconfigure the **grid** as permitted under clause 12.112(1)(b)(iaa), if—
- (a) the removal or reconfiguration is requested by the **system operator** in accordance with clause 9.13B; and
  - (b) the removal or reconfiguration will result in a net benefit, as calculated under the test set out in clause 12.117.
- (2) If **Transpower** temporarily removes **interconnection assets** from service or temporarily reconfigures the **grid** in response to a notice given under clause 9.13B, **Transpower** must, as soon as is reasonably practicable after the circumstances specified in that notice cease to exist—
- (a) restore the **interconnection assets** to service; or
  - (b) restore the **grid** to its original configuration.

Clause 12.116AA: inserted, from 15 March 2013 to 15 December 2013, by clause 6 of the Electricity Industry Participation (Temporary Grid Reconfiguration) Code Amendment 2013.

Clause 12.116AA: inserted, on 16 December 2013, by clause 8 of the Electricity Industry Participation (Urgent Temporary Grid Reconfiguration) Code Amendment 2013.

Clause 12.116AA(1): amended, on 5 October 2017, by clause 311 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### 12.116AB *[Expired]*

Clause 12.116AB: inserted, from 15 March 2013 to 15 December 2013, by clause 6 of the Electricity Industry Participation (Temporary Grid Reconfiguration) Code Amendment 2013.

### 12.116AC Information to be published

If **Transpower** receives a notice given in accordance with clause 9.13B, **Transpower** must **publish**,—

- (a) as soon as practical, a copy of the notice; and
- (b) by no later than 5 **business days** after receiving the notice, a summary of **Transpower's** application of the net benefit test that relates to the exceptional circumstances stated in the notice.

Clause 12.116AC Heading: amended, on 5 October 2017, by clause 312(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 12.116AC: inserted, from 15 March 2013 to 15 December 2013, by clause 6 of the Electricity Industry Participation (Temporary Grid Reconfiguration) Code Amendment 2013.

Clause 12.116AC: inserted, on 16 December 2013, by clause 8 of the Electricity Industry Participation (Urgent Temporary Grid Reconfiguration) Code Amendment 2013.

Clause 12.116AC: amended, on 5 October 2017, by clause 312(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### 12.116A *[Expired]*

Clause 12.116A: inserted, from 2 March 2012 to 3 December 2012, by clause 6 of the Electricity Industry Participation (Temporary Grid Reconfiguration) Code Amendment 2012.

### 12.116B *[Expired]*

Clause 12.116B: inserted, from 2 March 2012 to 3 December 2012, by clause 6 of the Electricity Industry Participation (Temporary Grid Reconfiguration) Code Amendment 2012.

**12.116C** *[Expired]*

Clause 12.116C: inserted, from 2 March 2012 to 3 December 2012, by clause 6 of the Electricity Industry Participation (Temporary Grid Reconfiguration) Code Amendment 2012.

**12.117 Permanent removal of interconnection assets from service or permanent grid reconfiguration**

- (1) **Transpower** may permanently remove **interconnection assets** from service or permanently reconfigure the **grid** as permitted under clause 12.112(1)(b) only if removal of the **asset** or reconfiguration of the **grid** results in a net benefit, as calculated under the test set out in subclause (2).
- (2) When **Transpower** is required to apply a net benefit test, **Transpower** must—
  - (a) estimate the following costs:
    - (i) any additional fuel costs incurred by a **generator** in respect of any **generating units** that will be **dispatched** or are likely to be **dispatched** during or after the removal of the **interconnection asset** or the reconfiguration of the **grid**, arising as a result of the removal or reconfiguration;
    - (ii) any direct labour and material costs that will be incurred by **Transpower** and the **designated transmission customers** undertaking the removal of the **interconnection asset** or the reconfiguration of the **grid**;
    - (iii) any increase in the estimate of **expected unserved energy** in MWh multiplied by the value per MWh of that **expected unserved energy**, arising as a result of the removal of the **interconnection asset** or the reconfiguration of the **grid**;
    - (iv) any relevant cost specified in clause 12.43(1)(a)(iv);
    - (v) any other relevant cost to a person that produces, transmits, retails or consumes **electricity** in New Zealand; and
  - (b) estimate the following benefits:
    - (i) any reduction in maintenance costs arising as a result of the removal of the **interconnection asset** or the reconfiguration of the **grid** (including **Transpower's** and any **designated transmission customer's** costs);
    - (ii) any reduction in fuel costs incurred by a **generator** in respect of any **generating units**, arising or likely to arise during or after the removal of the **interconnection asset** or the reconfiguration of the **grid**, as a result of the removal or reconfiguration;
    - (iii) any decrease in the estimate of **expected unserved energy** in MWh multiplied by the value per MWh of that **expected unserved energy**, arising as a result of the removal of the **interconnection asset** or the reconfiguration of the **grid**;
    - (iv) any relevant benefit specified in clause 12.43(1)(b)(iv);
    - (v) any other relevant benefit to a person that produces, transmits, retails or consumes **electricity** in New Zealand; and

- (c) deduct the costs estimated under paragraph (a) from the benefits estimated under paragraph (b) to determine the net benefit of the proposed removal of the **interconnection asset** or the reconfiguration of the **grid**.
- (3) **Transpower** may apply the test under this clause at differing levels of rigour in different circumstances, which may include taking into account the number of **assets** to be removed or reconfigured, the value of the **assets** involved, and the size of the load served by the **assets**.
- (4) **Transpower** is only required to—
  - (a) make a reasonable estimate of the costs and benefits identified in subclause (2), based on information reasonably available to it at the time it undertakes the test, and taking into account the proposed number of **assets** to be removed or reconfigured, the value of the **assets** involved, and the size of the load served by the **assets**; and
  - (b) take account of events that can be reasonably foreseen.
- (5) **Transpower's** estimate of fuel costs under subclause (2) must—
  - (a) in relation to thermal **generating stations**, be a reasonable estimate of the fuel costs, based on the economic value of the fuel required for the relevant thermal **generating station**, and justified by **Transpower** with reference to opinions on the economic value of the fuel, provided by 1 or more independent and suitably qualified persons; and
  - (b) in relation to hydroelectric **generating stations**—
    - (i) be a reasonable estimate of the fuel costs, based on the economic value of the water stored at a hydroelectric **generating station**, provided by a suitably qualified person other than—
      - (A) **Transpower**; or
      - (B) an employee of **Transpower**; and
    - (ii) be **published**, as provided for in the **Outage Protocol**.
- (6) The direct labour costs of **Transpower** and **designated transmission customers** under subclause (2)(a) may include any amounts paid to contractors, but must not include any apportionment of the overheads or office costs of **Transpower** or **designated transmission customers**.
- (7) The material costs of **Transpower** and **designated transmission customers** under subclause (2)(a) are the costs of the materials used in carrying out the work during the removal of the **interconnection asset** or the reconfiguration of the **grid**.
- (8) In assessing the costs and benefits under subclause (2), **Transpower** must consider any reasonably expected operating conditions, forecasts in the **system security forecast**, likely fuel costs, and any other reasonable assumptions.
- (9) The estimate of **expected unserved energy** in MWh multiplied by the value per MWh of that **expected unserved energy** under subclause (2) must be based on the **value of expected unserved energy** in clause 4 of Schedule 12.2 and **Transpower's** estimate of the **expected unserved energy** in respect of each affected **designated transmission customer** and end use **customer**.

- (10) To avoid doubt, this clause applies to the removal of **interconnection assets** from service if **Transpower** does not propose to replace those **assets** with another **asset**.

Compare: Electricity Governance Rules 2003 rule 8 section VI part F

Clause 12.117 Heading: amended, on 5 October 2017, by clause 313(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 12.117: substituted, on 16 December 2013, by clause 9 of the Electricity Industry Participation (Urgent Temporary Grid Reconfiguration) Code Amendment 2013.

Clause 12.117(1): amended, from 2 March 2012 to 3 December 2012, by clause 7 of the Electricity Industry Participation (Temporary Grid Reconfiguration) Code Amendment 2012.

Clause 12.117(1): amended, from 15 March 2013 to 15 December 2013, by clause 7 of the Electricity Industry Participation (Temporary Grid Reconfiguration) Code Amendment 2013.

Clause 12.117(1): amended, on 5 October 2017, by clause 313(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 12.117(9): amended, on 1 February 2016, by clause 56 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

### **12.118 Transpower to provide and publish annual report on interconnection asset capacity and grid configuration**

- (1) **Transpower** must provide the **Authority** with and **publish** an annual report including—
- (a) any matter required to be reported on for the purposes of this clause by the **Outage Protocol**; and
  - (b) the extent to which, in the preceding year ending 30 June, it has complied with the requirements of clause 12.111(1)(a) and (2); and
  - (c) any specific instances in which **Transpower** has not complied with clause 12.111(1)(a) and (2); and
  - (d) to the extent practicable, the circumstances that have given rise to any failure to comply with clause 12.111(1)(a) and (2); and
  - (e) to the extent practicable, any steps that it intends to take or other options to reduce the likelihood of failing to comply with clause 12.111(1)(a) and (2) in the future; and
  - (f) any modifications made to **interconnection circuit branches**, the **HVDC link**, and each **shunt asset** under clause 12.112(c) to (e) in the preceding year ending 30 June and the extent to which it has complied with clause 12.112(2) in respect of those modifications, including any specific instances in which **Transpower** has not complied; and
  - (g) any **interconnection assets** that have been removed from service, or any reconfigurations to the **grid** made, in accordance with clause 12.116AA or clause 12.117; and
  - (h) copies of any agreements made under clause 12.128 or, in respect of **interconnection assets** only, clause 12.151 in the preceding year ending 30 June; and
  - (i) an update of the interconnection asset capacity and grid configuration required under clause 12.107(1), as at the end of the preceding year ending 30 June.
- (2) **Transpower** must provide to the **Authority** and **publish**, the report referred to in subclause (1) by 30 November each year.
- (3) The **Authority** may incorporate by reference in this Code the updated interconnection

asset capacity and grid configuration referred to in subclause (1)(i) in accordance with clause 12.110. The **Authority** may consult with any person the **Authority** considers is likely to be materially affected by the proposed amendments to the interconnection asset capacity and grid configuration, as it sees fit. **Transpower** must comply with the interconnection asset capacity and grid configuration incorporated by reference in this Code in accordance with clause 12.110.

Compare: Electricity Governance Rules 2003 rule 9 section VI part F

Clause 12.118(1)(g): amended, from 2 March 2012 to 3 December 2012, by clause 8 of the Electricity Industry Participation (Temporary Grid Reconfiguration) Code Amendment 2012.

Clause 12.118(1)(g): amended, from 15 March 2013 to 15 December 2013, by clause 8 of the Electricity Industry Participation (Temporary Grid Reconfiguration) Code Amendment 2013.

Clause 12.118(1)(g): amended, on 16 December 2013, by clause 10 of the Electricity Industry Participation (Urgent Temporary Grid Reconfiguration) Code Amendment 2013.

Clause 12.118(1): amended, on 5 October 2017, by clause 314(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 12.118(2): amended, on 5 October 2017, by clause 314(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### *Reporting on availability and reliability*

#### **12.119 Index measures for availability and reliability**

The index measures for availability and reliability for each **interconnection branch**, **shunt asset** and the **HVDC link** are the index measures for reliability for each **interconnection branch**, **shunt asset** and the **HVDC link** in Schedule 12.5.

#### **12.120 Updating of availability and reliability index measures**

- (1) This clause applies if **interconnection assets**—
  - (a) are modified or replaced as permitted under clause 12.112(1); or
  - (b) have been damaged or degraded but, after conducting the investigation required under clause 12.114(1), **Transpower** considers that they still meet the **grid reliability standards**.
- (2) If this clause applies, if, after the availability and the reliability or availability index measures for an **interconnection branch**, **shunt asset** and the **HVDC link** or aggregated **interconnection branches** or **shunt assets** no longer meet the requirements of clause 12.122, the availability and reliability index measures in Schedule 12.5 must be updated following the procedure specified in clauses 12.121 to 12.127.
- (3) **Transpower** must propose the revised index measures under clause 12.121 within 20 **business days** of the modification or replacement, or such longer period as the **Authority** may allow.

Compare: Electricity Governance Rules 2003 rule 10.9 section VI part F

#### **12.121 Transpower to submit draft index measures for availability and reliability**

- (1) **Transpower** must provide the **Authority** with proposed index measures for availability and reliability for each **interconnection branch**, **shunt asset** and the **HVDC link**, in accordance with this clause.
- (2) For the purposes of subclause (1), **Transpower** must categorise **interconnection branches** and **shunt assets** into groups of **interconnection branches** and **shunt assets** comprising similar **assets**.

- (3) The index measures to be provided under subclause (1) are—
- (a) annual unavailability of each **interconnection branch**, **shunt asset** and the **HVDC link** due to **planned outages** of 1 minute or longer in hours per year ending 30 June, expressed as a percentage; and
  - (b) annual unavailability of each **interconnection branch**, **shunt asset** and the **HVDC link** due to **unplanned outages** of 1 minute or longer in hours per year ending 30 June, expressed as a percentage; and
  - (c) annual number of **planned interruptions** of 1 minute or longer caused by **planned outages** of 1 minute or longer of each **interconnection branch**, **shunt asset** and the **HVDC link**; and
  - (d) annual number of **unplanned interruptions** of 1 minute or longer caused by **unplanned outages** of 1 minute or longer of each **interconnection branch**, **shunt asset** and the **HVDC link**;
  - (e) total unserved energy per year ending 30 June in **MWh** resulting from **planned interruptions** of 1 minute or longer caused by **planned outages** of 1 minute or longer of each **interconnection branch**, **shunt asset** and the **HVDC link**; and
  - (f) total unserved energy per year ending 30 June in **MWh** resulting from **unplanned interruptions** of 1 minute or longer caused by **unplanned outages** of 1 minute or longer of each **interconnection branch**, **shunt asset** and the **HVDC link**.
- (4) At the same time, **Transpower** must propose availability and reliability index measures for aggregated **interconnection branches** and **shunt assets**, such as by **asset** class or for all of the **grid**.

Compare: Electricity Governance Rules 2003 rule 10.1 section VI part F

Clause 12.121(2): amended, on 5 October 2017, by clause 315(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 12.121(3): amended, on 5 October 2017, by clause 315(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### 12.122 Requirements for index measures

- (1) The proposed availability and reliability index measures under clause 12.121(3) must be based on the average annual availability and reliability of each category of **interconnection branch**, or **shunt asset** and of the **HVDC link** over the 5 year period (ending 30 June) immediately before this clause came into force.
- (2) The proposed index measures under clause 12.121(3) must be accompanied by an explanation showing how the requirements of subclause (1) were applied.
- (3) The index measure for unserved energy under clause 12.121(3)(e) and (f) must be determined in accordance with the methodology for determining **expected unserved energy** relating to **outages of interconnection assets** specified in the **Outage Protocol**.
- (4) In proposing the availability and reliability index measures under clause 12.121(4), **Transpower** must specify its reasons for proposing those measures.

Compare: Electricity Governance Rules 2003 rule 10.2 section VI part F

Clause 12.122(1): amended, on 5 October 2017, by clause 316 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### 12.123 Authority may initially approve proposed index measures or refer back to Transpower

After considering **Transpower's** proposed availability and reliability index measures



and accompanying reasons the **Authority** may either—

- (a) provisionally approve the proposed availability and reliability index measures; or
- (b) refer the proposed availability and reliability index measures and accompanying explanation back to **Transpower** if in the **Authority's** view—
  - (i) the proposed availability and reliability index measures under clause 12.121 are not consistent with the requirements of clause 12.122(1) or the methodology referred to in clause 12.122(3); or
  - (ii) the proposed availability and reliability index measures under clause 12.121 do not provide sufficient information to meet the reasonable needs of **grid** users; or
  - (iii) the reasons provided with the availability and reliability targets in accordance with clause 12.122 are inadequate—

and **Transpower** must within 20 **business days** (or such longer period as the **Authority** may allow) consider the **Authority's** concerns and resubmit the proposed availability and reliability index measures and accompanying explanations for consideration by the **Authority**.

Compare: Electricity Governance Rules 2003 rule 10.3 section VI part F

#### **12.124 Amendment of proposed index measures by the Authority**

If the **Authority** considers that the availability and reliability index measures resubmitted by **Transpower** under clause 12.123(b) are not consistent with the requirements of clause 12.122(1) or the methodology referred to in clause 12.122(3), or do not provide relevant information to **grid** users, the **Authority** may make any amendments to the index measures it considers necessary.

Compare: Electricity Governance Rules 2003 rule 10.4 section VI part F

#### **12.125 Authority must consult on proposed index measures**

- (1) The **Authority** must **publish** the proposed availability and reliability index measures, either as provisionally approved by the **Authority** or as amended by the **Authority**, as soon as is practicable, for consultation with any person that the **Authority** thinks is likely to be materially affected by the proposed index measures.
- (2) As well as the consultation required under subclause (1), the **Authority** may undertake any other consultation it considers necessary.

Compare: Electricity Governance Rules 2003 rules 10.5 and 10.6 section VI part F

#### **12.126 Decision on index measures**

When the **Authority** has completed its consultation on the proposed availability and reliability measures it must consider whether to include the index measures as a schedule to this Part.

Compare: Electricity Governance Rules 2003 rule 10.7 section VI part F

#### **12.127 Transpower to report on availability and reliability**

- (1) By 30 November in each year, **Transpower** must **publish** and provide to the **Authority** information on availability and reliability of **interconnection assets** including—
  - (a) annual unavailability of each **interconnection branch**, **shunt asset** and the

- HVDC link** due to **planned outages** of 1 minute or longer in the preceding year ending 30 June in hours per year expressed as a percentage; and
- (b) annual unavailability of each **interconnection branch, shunt asset** and the **HVDC link** due to **unplanned outages** of 1 minute or longer in the preceding year ending 30 June in hours per year, expressed as a percentage; and
  - (c) annual number of **planned interruptions** of 1 minute or longer caused by **planned outages** of one minute or longer of each **interconnection branch, shunt asset** and the **HVDC link** in the preceding year ending 30 June; and
  - (d) annual number of **unplanned interruptions** of 1 minute or longer caused by **unplanned outages** of 1 minute or longer of each **interconnection branch, shunt asset** and the **HVDC link** in the preceding year ending 30 June; and
  - (e) total unserved energy in the preceding year ending 30 June resulting from **planned interruptions** of 1 minute or longer caused by **planned outages** of 1 minute or longer of **interconnection branches, shunt assets** and the **HVDC link**; and
  - (f) total unserved energy in the preceding year ending 30 June resulting from **unplanned interruptions** of 1 minute or longer caused by **unplanned outages** of 1 minute or longer of **interconnection branches, shunt assets** and the **HVDC link**; and
  - (g) annual number of **outages** of each **interconnection branch, shunt asset** and the **HVDC link** that are shorter than 1 minute in the preceding year ending 30 June; and
  - (h) the annual number of **interruptions** shorter than 1 minute caused by **outages** that are shorter than 1 minute of each **interconnection branch, shunt asset** and the **HVDC link**, in the preceding year ending 30 June; and
  - (i) a comparison of the information required by paragraphs (a) to (f) against the availability and reliability index measures for **interconnection branches, shunt assets** and the **HVDC link** included in a schedule to this Part under clause 12.126;
  - (j) to the extent practicable, an explanation of the reasons for not meeting the reliability and availability index measures for **interconnection branches, shunt assets** and the **HVDC link** included in a schedule to this Part under clause 12.126 and any steps or other options it intends to take in future to meet the index measures; and
  - (k) information on its performance against the reliability and availability index measures for aggregated **interconnection branches** included in a schedule to this Part under clause 12.126.
- (2) The information **published** under subclause (1) must be specified in the same units of measurement as the corresponding index measures included in a schedule to this Part under clause 12.126.
- (3) **Transpower** does not breach this Code by reason of a failure to meet the index measures included in a schedule to this Part under clause 12.126.

Compare: Electricity Governance Rules 2003 rule 10.8 section VI part F

Clause 12.127(1): amended, on 5 October 2017, by clause 317 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

**12.128 Transpower and designated transmission customers may agree on other requirements**

- (1) **Transpower** and each **designated transmission customer** must comply with this Part, unless agreed otherwise by **Transpower** and the **designated transmission customer** in respect of specified **interconnection circuit branches**, the **HVDC link**, **shunt assets** or **interconnection assets**, or the **designated transmission customer** in accordance with subclause (2).
- (2) An agreement between **Transpower** and a **designated transmission customer** under this clause must not exclude the application of subclause (3)(b) and must be conditional in all respects on—
  - (a) obtaining agreement from all other potentially affected **designated transmission customers** that this Part does not apply to the specified **interconnection circuit branches**, the **HVDC link**, **shunt assets** or **interconnection assets**, or the **designated transmission customer**; and
  - (b) **Transpower** and the **designated transmission customer** confirming in writing to the **Authority** that they have consulted with all potentially affected end use customers on this Part not applying to the specified **interconnection branches**, **circuit branches**, the **HVDC link**, **shunt assets** or **interconnection assets** or the **designated transmission customer**, and that there are no material unresolved issues affecting the interests of those end use customers.
- (3) **Transpower** must—
  - (a) give written notice to the **Authority** as soon as practicable if **Transpower** enters into an agreement with a **designated transmission customer** under this clause; and
  - (b) **publish** the agreement no later than 20 **business days** after entering into the agreement.

Compare: Electricity Governance Rules 2003 rule 11 section VI part F

Clause 12.128(2): amended, on 5 October 2017, by clause 318(a) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 12.128(3): replaced, on 5 October 2017, by clause 318(b) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

## Subpart 7—Preparation of Outage Protocol

**12.129 Purpose of this subpart**

The purpose of this subpart is to provide for the making of an **Outage Protocol**, with input from **Transpower** and in consultation with other interested parties, that—

- (a) specifies the circumstances in which **Transpower** may temporarily remove any **assets** forming part of the **grid** from service or reduce the capacity of assets to efficiently manage the operation of the **grid**; and
- (b) specifies procedures and policies for **Transpower** to plan for **outages** and for carrying out such **outages** to—
  - (i) ensure **Transpower** involves **designated transmission customers** in making decisions on **planned outages** as much as possible; and

- (ii) ensure coordination between **Transpower** and **designated transmission customers**; and
- (iii) enable **Transpower** to efficiently manage the operation of the **grid**; and
- (c) specifies procedures and policies for dealing with **unplanned outages** of the **grid**.

Compare: Electricity Governance Rules 2003 rule 1 section VII part F

#### 12.130 Definition of outage

- (1) An **outage** exists when **interconnection assets** or **connection assets** are temporarily not provided in accordance with—
  - (a) the requirements of a **transmission agreement**; or
  - (b) the requirements of subpart 6.
- (2) Without limiting subclause (1), an **outage** includes any situation in which—
  - (a) **Transpower** removes **assets** from service temporarily; or
  - (b) **assets** are not able to be provided due to **grid emergencies**, in order to deal with health and safety issues, or due to circumstances beyond **Transpower's** reasonable control; or
  - (c) **Transpower** reduces the capacity of **branches** below the capacity required by a **transmission agreement** or clause 12.111; or
  - (d) **Transpower** changes the configuration of the **grid**; or
  - (e) **Transpower** is required by law to carry out an **outage**.

Compare: Electricity Governance Rules 2003 rule 2 section VII part F

#### 12.131 Outage Protocol

- (1) The **Outage Protocol** set out in schedule F7 of section VII of part F of the **rules** immediately before this Code came into force, continues in force and is deemed to be the **Outage Protocol** that applies at the commencement of this Code, with the following amendments:
  - (a) every reference to the Board must be read as a reference to the **Authority**;
  - (b) every reference to the **rules** must be read as a reference to the Code;
  - (c) every reference to a provision of the **rules** must be read as a reference to the corresponding provision of the Code;
  - (d) the reference in clause 3.1.2(d), clause 3.3.5(c), and clause 3.3.8(a) to a reliability investment or an economic investment approved by the Board must be read as a reference to an **approved investment**;
  - (e) the reference in clause 10.2.1(a) and (b) to the **benchmark agreement** in schedule F2 must be read as a reference to the **benchmark agreement** incorporated by reference into this Code under clause 12.34;
  - (f) the reference in clauses A1.1(a)(ii), A7.2(a)(ii), and A7.2(b)(i) to the value of unserved energy in clause 8.3.4 of schedule F4 of section III must be read as a reference to the **value of expected unserved energy** in clause 4 of Schedule 12.2;
  - (g) the reference in clauses A6.1(f) and A6.2(e) to the matters specified in clauses 27.1 to 27.9 of schedule F4 of section III must be read as the matters specified in clause 12.43(1)(a)(iv) and (b)(iv):

- (h) the reference in clause A8.1(a)(i) to fuel costs specified in the statement of opportunities must be read as a reference to fuel costs calculated in accordance with clause 12.141(3)(a)(i).
- (2) The **Authority** must as soon as practicable after this Code comes into force, publish a version of the **Outage Protocol** in which the provisions of this Code that correspond to the provisions of the **rules** referred to in the **Outage Protocol** are shown.
- (3) Clause 12.150 applies to the **Outage Protocol**.

*Review of Outage Protocol*

**12.132 Review of Outage Protocol**

The **Authority** may review the **Outage Protocol** at any time, in accordance with the requirements of clauses 12.133 and 12.145 to 12.149.

Compare: Electricity Governance Rules 2003 rule 14 section VII part F

**12.133 Transpower to submit proposed Outage Protocol**

- (1) **Transpower** must submit a proposed **Outage Protocol** to the **Authority** within 3 months (or such longer period as the **Authority** may allow) of receipt of a written request from the **Authority**. The **Authority** may issue such a request at any time.
- (2) The proposed **Outage Protocol** must give effect to or promote the principles set out in clause 12.134 and provide for the matters set out in clauses 12.135 to 12.144.
- (3) With its proposed **Outage Protocol**, **Transpower** must submit to the **Authority** an explanation of the proposed **Outage Protocol** and a **statement of proposal** for the proposed **Outage Protocol**.

Compare: Electricity Governance Rules 2003 rule 8 section VII part F

*Principles and required content of Outage Protocol*

**12.134 Principles for developing Outage Protocol**

The **Outage Protocol** must give effect to the following principles:

- (a) the matters in clause 12.129;
- (b) the need for a fair and reasonable balance of interests between the **grid owner** and **designated transmission customers**;
- (c) the need to ensure that the **grid owner** can meet all obligations placed on it by the **system operator** for the purpose of meeting common security and power quality requirements under Part 8 of this Code;
- (d) the need to ensure that the safety of all personnel is maintained;
- (e) the need to ensure that the safety and integrity of equipment is maintained;
- (f) the desirability of the **Outage Protocol** and Part 8 operating in an integrated and consistent manner, if possible.

Compare: Electricity Governance Rules 2003 rule 3 section VII part F

**12.135 Required content of Outage Protocol**

- (1) The **Outage Protocol** must—

- (a) require **Transpower** to plan for **outages**, other than **outages** that are not reasonably foreseeable, in accordance with clause 12.136; and
  - (b) require **Transpower** and **designated transmission customers** to act reasonably and in good faith in planning for **outages**, in accordance with clause 12.137; and
  - (c) set out the situations and times at which **Transpower** must reconsider the timing of proposed **planned outages**, as specified in clause 12.138; and
  - (d) permit **Transpower** to vary a proposed **planned outage**, as specified in clause 12.139;
  - (e) set out the requirements for **Transpower** to consider when planning for **outages**, in order to give effect to the net benefit principle, as specified in clause 12.140; and
  - (f) permit **Transpower** to undertake **outages** in order to give effect to an **approved investment**, and to undertake **outages** that are required by the Electricity Act 1992, as specified in clause 12.142; and
  - (g) permit **Transpower** to undertake **outages**, or take such other steps, as the **system operator** may reasonably require.
- (2) The **Outage Protocol** must require **Transpower** to set out the procedures and policies for dealing with **unplanned outages**, as specified in clause 12.143.
- (3) The **Outage Protocol** must require **Transpower** to report on compliance with the **Outage Protocol**, in accordance with clause 12.144.
- (4) The **Outage Protocol** must set out—
- (a) processes for **Transpower** to consult with **designated transmission customers** and to determine an **outage plan** setting out **planned outages** for each year ending 30 June, and processes for the **outage plan** to be updated; and
  - (b) requirements on **Transpower** to keep **designated transmission customers** informed about **planned outages**, including minimum notice periods for **Transpower** to advise affected **designated transmission customers** of **planned outages** not set out in the **outage plan**; and
  - (c) procedures for **outage** co-ordination by **Transpower** and between **Transpower** and **designated transmission customers**; and
  - (d) requirements on **Transpower** to provide information to **designated transmission customers** about **unplanned outages**.
- (5) The **Outage Protocol** is not limited to the matters referred to in this clause, and may provide for any other matters related to **outages**.

Compare: Electricity Governance Rules 2003 rule 4 section VII part F

Clause 12.135(4)(a): amended, on 5 October 2017, by clause 319 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### 12.136 Planning for outages

The **Outage Protocol** must require **Transpower** to plan for **outages**, other than **outages** that are not reasonably foreseeable—

- (a) in respect of **interconnection assets**, in accordance with the requirements of the **Outage Protocol** specified under clause 12.140(1); and
- (b) in respect of **connection assets**, by agreeing with each affected **designated transmission customer** on the timing and duration of the **outage** or, failing

agreement, in accordance with the requirements of the **Outage Protocol** specified under clause 12.140(1); and

- (c) in respect of outages of both **interconnection assets** and **connection assets** that are required in order to give effect to an **approved investment** or are required by the Electricity Act 1992, in accordance with the requirements of the **Outage Protocol** specified under clause 12.142.

Compare: Electricity Governance Rules 2003 rule 5.1 section VII part F

#### **12.137 Transpower and designated transmission customers to act reasonably and in good faith**

- (1) The **Outage Protocol** must require **Transpower**, in planning for **outages** in accordance with clauses 12.136, 12.140, and 12.142, reconsidering the timing of proposed **planned outages** in accordance with clause 12.138 or varying proposed **planned outages** in accordance with clause 12.139, to act reasonably and in good faith, taking into account the information reasonably known at the time or that can be reasonably forecast.
- (2) The **Outage Protocol** must require **designated transmission customers**, in exercising rights or undertaking obligations under the **Outage Protocol**, to act reasonably and in good faith.

Compare: Electricity Governance Rules 2003 rule 5.2 section VII part F

#### **12.138 Reconsideration of planned outages**

The **Outage Protocol** must set out the situations and the times at which **Transpower** must reconsider the timing of proposed **planned outages**, and the extent to which the proposed timing of **planned outages** needs to be reconsidered, which may include—

- (a) whenever material new information has been provided to **Transpower** about the likely effect of a proposed **planned outage**; and
- (b) whenever circumstances relating to a proposed **planned outage** have changed sufficiently to justify reconsideration of the requirements specified under clauses 12.140 or 12.142, and **Transpower** is aware or has been made aware of the change in circumstances.

Compare: Electricity Governance Rules 2003 rule 5.3 section VII part F

#### **12.139 Variations to planned outages**

- (1) The **Outage Protocol** may permit **Transpower** to vary a proposed **planned outage** only if—
  - (a) in respect of a proposed **planned outage** of **interconnection assets**, the variation of the proposed **planned outage** is permitted in accordance with the requirements of the **Outage Protocol** specified under clauses 12.140 or 12.142; or
  - (b) in respect of a proposed **planned outage** of **connection assets**, **Transpower** and each affected **designated transmission customer** agree on the variation as provided for in the **Outage Protocol** or, failing agreement, the variation of the proposed **planned outage** is permitted in accordance with the requirements of the **Outage Protocol** specified under clauses 12.140 or 12.142; or

- (c) the variation is necessary as a result of a **grid emergency**, in order to deal with health and safety issues, in order to comply with the **Act** or due to other circumstances beyond **Transpower's** reasonable control; or
  - (d) the variation is required to meet a request of the **system operator** that **Transpower** vary a proposed **planned outage**.
- (2) The **Outage Protocol** must require **Transpower**, if possible, to give notice of a variation before the proposed **planned outage**, and if prior notice is not possible, to advise of the variation to the proposed **planned outage** as soon as possible after the variation occurs.

Compare: Electricity Governance Rules 2003 rule 5.4 section VII part F

#### 12.140 Net benefit principle, requirements and methodologies

- (1) The requirements of the **Outage Protocol** relating to planning for **outages** under clause 12.136(a) or (b), or for varying proposed **planned outages** under clause 12.139(1)(a) or (b)—
- (a) must give effect to the net benefit principle specified in subclause (2), in determining the timing and duration of a **planned outage**, and whether to undertake a **planned outage**, either by including the particular requirements set out in clause 12.141(2), or by some other means; and
  - (b) may include methodologies and processes for **Transpower** to apply when planning for **outages**; and
  - (c) may include other requirements that may apply in different situations.
- (2) The net benefit principle is that, in planning and varying a **planned outage**, **Transpower** must ensure that the **planned outage** is likely to result in net benefits to persons who produce, transmit, distribute, retail or consume **electricity**—
- (a) in respect of **interconnection assets**, to the extent those persons are affected by an **outage**; and
  - (b) in respect of **connection assets**, if **Transpower** has not agreed the timing and duration of the **outage** with the relevant **designated transmission customer** in accordance with the **Outage Protocol**, to the extent those persons are affected by an **outage**.

Compare: Electricity Governance Rules 2003 rule 5.5 section VII part F

#### 12.141 Consideration of the likely effects of planned outages

- (1) The **Outage Protocol** may require **Transpower** to determine the likely effect of a proposed **planned outage** on the power system, **generators** and **consumers**, and—
- (a) if a proposed **outage** is not reasonably expected to—
    - (i) result in the power system failing to meet the **grid reliability standards**; and/or
    - (ii) give rise to **binding constraints**; and/or
    - (iii) result in loss of supply to **consumers**, may permit **Transpower** to undertake the **outage**; and



- (b) if a proposed **outage** is likely to result in, or give rise to, the matters referred to in paragraph (a), the **Outage Protocol** may require **Transpower** to comply with the particular requirements specified in subclause (2).
- (2) The requirements in subclause (1) that the **Outage Protocol** may provide are—
  - (a) if a proposed **planned outage** is likely to result in the power system failing to meet the **grid reliability standards**, but is not expected to give rise to **binding constraints** or result in loss of **supply** to **consumers**, **Transpower** must—
    - (i) estimate the following costs:
      - (A) any direct labour and material costs that **Transpower** will incur in undertaking the **outage**;
      - (B) any direct labour and material costs that **designated transmission customers** will incur as a result of **Transpower** undertaking the **outage**;
      - (C) if the **outage** will result in an increased risk of loss of **supply**, any increase in the estimate of **expected unserved energy** in MWh multiplied by the value per MWh of that **expected unserved energy**;
      - (D) any relevant cost specified in clause 12.43(1)(a)(iv);
      - (E) any other relevant cost to a person that produces, transmits, retails or consumes **electricity** in New Zealand; and
    - (ii) estimate the following benefits:
      - (A) if the **outage** will result in a decreased risk of loss of **supply**, any decrease in the estimate of **expected unserved energy** in MWh multiplied by the value per MWh of that **expected unserved energy**;
      - (B) any reduction in maintenance costs arising as a result of the **outage** (including **Transpower's** and any **designated transmission customer's** costs);
      - (C) any relevant benefit specified in clause 12.43(1)(b)(iv);
      - (D) any other relevant benefit to a person that produces, transmits, retails or consumes **electricity** in New Zealand; and
    - (iii) carry out the **outage** only if the costs estimated under subparagraph (i) are less than the benefits estimated under subparagraph (ii); and
  - (b) if a proposed **planned outage** is likely to give rise to **binding constraints**, whether or not the **outage** is also likely to result in a loss of **supply** to **consumers**, **Transpower** must—
    - (i) estimate the following costs:
      - (A) any direct labour and material costs that **Transpower** will incur in undertaking the **outage**;
      - (B) any direct labour and material costs that **designated transmission customers** will incur as a result of **Transpower** undertaking the **outage**;
      - (C) if the **outage** will result in an increased risk of loss of **supply**, any increase in the estimate of **expected unserved energy** in MWh multiplied by the value per MWh of that **expected unserved energy**;

- (D) any additional fuel costs incurred by a **generator** in respect of any **generating units** that will be **dispatched** or are likely to be **dispatched** during or after the **outage** and as a result of the **outage**:
    - (E) any relevant cost specified in clause 12.43(1)(a)(iv):
    - (F) any other relevant costs to a person that produces, transmits, retails or consumes **electricity** in New Zealand; and
  - (ii) estimate the following benefits:
    - (A) any reduction in maintenance costs resulting from the **outage** (including **Transpower's** and any **designated transmission customer's** costs):
    - (B) any reduction in fuel costs incurred by a **generator** in respect of any **generating units**, arising or likely to arise during or after the **outage** and as a result of the **outage**:
    - (BA) if the **outage** will result in a decreased risk of loss of **supply**, any decrease in the estimate of **expected unserved energy** in MWh multiplied by the value per MWh of that **expected unserved energy**:
    - (C) any relevant benefit specified in clause 12.43(1)(b)(iv):
    - (D) any other relevant benefit to a person that produces, transmits, retails or consumes **electricity** in New Zealand; and
  - (iii) carry out the **outage** only if the costs estimated under subparagraph (i) are less than the benefits estimated under subparagraph (ii); and
- (c) if a proposed planned **outage** is likely to lead to loss of **supply** to **consumers**, whether or not the **outage** is also likely to give rise to **binding constraints**, **Transpower** must—
- (i) estimate the following costs:
    - (A) any direct labour and material costs that **Transpower** will incur in undertaking the **outage**:
    - (B) any direct labour and material costs that **designated transmission customers** will incur as a result of **Transpower** undertaking the **outage**:
    - (C) any increase in the estimate of **expected unserved energy** in MWh multiplied by the value per MWh of that **expected unserved energy**, arising from the loss of **supply** during the **outage**:
    - (CA) any additional fuel costs incurred by a **generator** in respect of any **generating units** that will be **dispatched** or are likely to be **dispatched** during or after the **outage** and as a result of the **outage**:
    - (D) any relevant cost specified in clause 12.43(1)(a)(iv):
    - (E) any other relevant cost to a person that produces, transmits, retails or consumes **electricity** in New Zealand; and
  - (ii) estimate the following benefits:
    - (A) any reduction in maintenance costs resulting from the **outage** (including **Transpower's** and any **designated transmission customer's** costs):

- (B) if the **outage** will result in a decreased risk of loss of **supply**, any decrease in the estimate of **expected unserved energy** in MWh multiplied by the value per MWh of that **expected unserved energy**;
    - (C) any reduction in fuel costs incurred by a **generator** in respect of any **generating units**, arising or likely to arise during or after the **outage** and as a result of the **outage**;
    - (D) any relevant benefit specified in clause 12.43(1)(b)(iv);
    - (E) any other relevant benefit to a person that produces, transmits, retails or consumes **electricity** in New Zealand; and
  - (iii) carry out the **outage** only if the costs estimated under subparagraph (i) are less than the benefits estimated under subparagraph (ii).
- (3) In providing for the matters referred to in subclause (2), the **Outage Protocol** must include the following requirements:
- (a) **Transpower's** estimate of the fuel costs under subclause (2)(b) and (c) must—
    - (i) in relation to thermal **generating stations**, be a reasonable estimate of the fuel costs, based on the economic value of the fuel required for the relevant thermal **generating station**, and justified by **Transpower** with reference to opinions on the economic value of the fuel, provided by 1 or more independent and suitably qualified persons; and
    - (ii) in relation to hydroelectric **generating stations**—
      - (A) be a reasonable estimate of the fuel costs, based on the economic value of the water stored at a hydroelectric **generating station**, provided by a suitably qualified person other than—
        - (1) **Transpower**; or
        - (2) an employee of **Transpower**; and
      - (B) be **published**, as provided for in the **Outage Protocol**:
  - (b) the direct labour costs of **Transpower** and **designated transmission customers** under subclause (2) may include any amounts paid to contractors, but must not include any apportionment of the overheads or office costs of **Transpower** or **designated transmission customers**;
  - (c) the material costs of **Transpower** and **designated transmission customers** under subclause (2) are the costs of the materials used in carrying out the work during the **outage**;
  - (d) the estimate of **expected unserved energy** in MWh multiplied by the value per MWh of that **expected unserved energy** under subclause (2) must—
    - (i) in the case of **connection assets**, be based on—
      - (A) the estimated amount and value of the **expected unserved energy** as agreed between **Transpower** and each affected **designated transmission customer**; or
      - (B) if **Transpower** and a **designated transmission customer** cannot agree on the amount and value of the **expected unserved energy** under subsubparagraph (A), the **value of expected unserved energy** in clause 4 of Schedule 12.2 and **Transpower's** estimate of the

- expected unserved energy** in respect of each affected **designated transmission customer** and end use **customer**; and
- (ii) in the case of **interconnection assets**, be based on—
    - (A) the **value of expected unserved energy** in clause 4 of Schedule 12.2; and
    - (B) **Transpower's** estimate of the **expected unserved energy** in respect of each affected **designated transmission customer** and end use **customer**.
  - (4) In addition to the requirements in subclause (3), the **Outage Protocol** must require **Transpower**, in planning for **outages**, to consider any reasonably expected operating conditions, forecasts in the **system security forecast**, likely fuel costs, and any other reasonable assumptions.
  - (5) The **Outage Protocol** must include a methodology for determining **expected unserved energy** for the purposes of subclause (2)(a) to (c) that complies with subclauses (3)(d) and (4).
  - (6) The **Outage Protocol** may permit **Transpower** to—
    - (a) make only a reasonable estimate of the matters specified in subclauses (2) to (4) based on information reasonably available to it at the time **Transpower** considers whether to carry out a **planned outage**, and taking into account the number of **assets** to which the proposed **outage** applies, the value of the **assets** involved, the size of the load served by the **assets**, the proposed duration of the **outage**; and
    - (b) apply differing levels of rigour in different circumstances, which may include taking into account the number of **assets** to which a proposed **outage** applies, the value of the **assets** involved, the size of the load served by the **assets**, the proposed duration of the **outage**, and any other relevant matters.

Compare: Electricity Governance Rules 2003 rule 5.6 section VII part F

Clause 12.141(2) to (4): substituted, on 16 December 2013, by clause 11 of the Electricity Industry Participation (Urgent Temporary Grid Reconfiguration) Code Amendment 2013.

Clause 12.141(3)(d)(i)(B): amended, on 1 February 2016, by clause 57(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

Clause 12.141(3)(d)(ii)(A): amended, on 1 February 2016, by clause 57(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

#### **12.142 Planned outages required in order to give effect to an investment or required by the Act**

- (1) The **Outage Protocol** must set out requirements for **Transpower** to consider when determining the timing of **planned outages** that are required in order to give effect to an **approved investment** or that are required by the Electricity Act 1992.
- (2) The requirements specified under subclause (1) must require **Transpower** to give effect to the net benefit principle in clause 12.140(2) in determining the timing and duration of **outages** subject to this clause, and may require **Transpower** to consider some or all of the costs and benefits specified in clause 12.141.

Compare: Electricity Governance Rules 2003 rule 5.7 section VII part F

### 12.143 Required content of Outage Protocol in relation to unplanned outages

- (1) The **Outage Protocol** must—
  - (a) set out procedures and policies for dealing with **unplanned outages**, so as to minimise the costs and, if relevant, maximise the benefits arising from an **unplanned outage**; and
  - (b) set out the reasonable steps and measures that **Transpower** must take in order to be prepared for **unplanned outages**, so as to ensure that it is readily able to deal with **unplanned outages** in a way that minimises the costs and, if relevant, maximises the benefits arising from an **unplanned outage**; and
  - (c) require **Transpower** to deal with **unplanned outages** as quickly as reasonably possible, in accordance with the procedures specified in the **Outage Protocol**.
- (2) The costs and benefits under subclause (1) are the costs and benefits of the **outage** to persons who produce, transmit, distribute, retail, or consume **electricity**.

Compare: Electricity Governance Rules 2003 rule 6 section VII part F

### 12.144 Reporting on compliance with Outage Protocol

The **Outage Protocol** must require **Transpower** to publish and report to **designated transmission customers** and the **Authority**, whether in the report provided under clause 12.118 or otherwise, on its compliance with the requirements of the **Outage Protocol**, including the requirements specified in clause 12.140(1) for giving effect to the net benefit principle specified in clause 12.140(2) and the requirements of the **Outage Protocol** relating to **unplanned outages** specified in clause 12.143.

Compare: Electricity Governance Rules 2003 rule 7 section VII part F

### *Decisions on Outage Protocol*

### 12.145 Authority may initially approve the proposed Outage Protocol or refer back to Transpower

After consideration of **Transpower's** proposed **Outage Protocol** and accompanying explanation and **statement of proposal**, the **Authority** may—

- (a) provisionally approve the proposed **Outage Protocol** having regard to the principles in clause 12.134 and the matters set out in clauses 12.135 to 12.144; or
- (b) refer the proposed **Outage Protocol** and accompanying explanation and regulatory statement back to **Transpower**, if in the **Authority's** view—
  - (i) the proposed **Outage Protocol** does not adequately give effect to or promote the principles in clause 12.134; or
  - (ii) the proposed **Outage Protocol** does not adequately provide for the matters set out in clauses 12.135 to 12.144; or
  - (iii) the explanation or **statement of proposal** provided with the **Outage Protocol** in accordance with clause 12.133(3) is not adequate—

and **Transpower** must, within 20 **business days** (or such longer period as the **Authority** may allow), consider the **Authority's** concerns and resubmit its proposed **Outage Protocol** and accompanying explanation and **statement of proposal** for reconsideration by the **Authority**.

Compare: Electricity Governance Rules 2003 rule 9 section VII part F

#### **12.146 Reconsideration of revised Outage Protocol by the Authority**

After reconsideration of **Transpower's** proposed **Outage Protocol**, and accompanying explanation and **statement of proposal**, as revised under clause 12.145(b), the

**Authority** may either—

- (a) provisionally approve the proposed **Outage Protocol**, as revised, having regard to the principles in clause 12.134 and the matters set out in clauses 12.135 to 12.144; or
- (b) if the **Authority** considers that the **Outage Protocol** resubmitted by **Transpower** under clause 12.145(b) does not adequately give effect to or promote the principles in clause 12.134, or adequately provide for the matters set out in clauses 12.135 to 12.144, the **Authority** may make any amendments to the proposed **Outage Protocol**, as revised, that it considers necessary.

Compare: Electricity Governance Rules 2003 rule 10 section VII part F

#### **12.147 Authority must consult on the proposed Outage Protocol**

The **Authority** must **publish** the proposed **Outage Protocol**, either as provisionally approved by the **Authority** or as amended by the **Authority**, as soon as is practicable, for consultation with any person that the **Authority** thinks is likely to be materially affected by the proposed **Outage Protocol**.

Compare: Electricity Governance Rules 2003 rule 11 section VII part F

#### **12.148 Authority may undertake additional consultation**

As well as the consultation required under clause 12.147, the **Authority** may undertake any other consultation it considers necessary.

Compare: Electricity Governance Rules 2003 rule 12 section VII part F

#### **12.149 Decision on Outage Protocol**

- (1) When the **Authority** has completed its consultation on the proposed **Outage Protocol**, it must consider whether to incorporate the proposed **Outage Protocol** by reference as the **Outage Protocol**.
- (2) If the **Authority** decides to incorporate the **Outage Protocol** by reference in this Code, the **Authority** must determine a date on which the incorporation by reference takes effect and comply with Schedule 1 of the Act in relation to it.

Compare: Electricity Governance Rules 2003 rule 13 section VII part F

#### **12.150 Incorporation of Outage Protocol by reference**

- (1) The **Outage Protocol** is incorporated by reference in this Code in accordance with section 32 of the Act.
- (2) Subclause (1) is subject to Schedule 1 of the Act, which includes a requirement that the **Authority** must give notice in the *Gazette* before an amendment or substituted **Outage Protocol** becomes incorporated by reference in this Code.

Clause 12.150(1): amended, on 5 October 2017, by clause 320(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 12.150(2): amended, on 5 October 2017, by clause 320(2) of the Electricity Industry Participation Code

Amendment (Code Review Programme) 2017.

*Complying with Outage Protocol*

**12.151 Compliance with Outage Protocol**

- (1) **Transpower** and each **designated transmission customer** must comply with the **Outage Protocol**, unless agreed otherwise by **Transpower** and a **designated transmission customer** in respect of specified **assets** or the **designated transmission customer** in accordance with subclause (2).
- (2) An agreement between **Transpower** and a **designated transmission customer** to which the **Outage Protocol** does not apply in respect of specified **assets** must not exclude the application of subclause (3)(b) and must be conditional in all respects on—
  - (a) obtaining agreement from all other potentially affected **designated transmission customers** that the **Outage Protocol** does not apply in respect of the specified **assets** or the **designated transmission customer**; and
  - (b) **Transpower** and the **designated transmission customer** satisfying the **Authority** that they have consulted with all potentially affected end use customers on the **Outage Protocol** not applying in respect of the specified **assets** or the **designated transmission customer** and that there are no material unresolved issues affecting the interests of those end use customers.
- (3) **Transpower** must—
  - (a) give written notice to the **Authority** as soon as practicable if **Transpower** enters into an agreement with a **designated transmission customer** under this clause; and
  - (b) **publish** the agreement no later than 20 **business days** after entering into the agreement.

Compare: Electricity Governance Rules 2003 rule 15 section VII part F

Clause 12.151(2): amended, on 5 October 2017, by clause 321(a) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 12.151(3): replaced, on 5 October 2017, by clause 321(b) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

## Schedule 12.1

### Categories of designated transmission customers

cl 12.7

#### 1 Categories of designated transmission customers required to enter into transmission agreements with Transpower

(1) The categories of **designated transmission customers** required to enter into **transmission agreements** with **Transpower** are—

- (a) **connected asset owners**; and
- (b) *[Revoked]*
- (c) **generators** that are directly connected to the **grid**.

(2) *[Revoked]*

(3) *[Revoked]*

(4) *[Revoked]*

(5) *[Revoked]*

Compare: Electricity Governance Rules 2003 schedule F1 part F

Schedule 12.1, clause 1(1): amended, on 16 December 2013, by clause 9(1) of the Electricity Industry Participation (Revocation of Part 16) Code Amendment 2013.

Schedule 12.1, clause 1(1)(a): amended, on 1 February 2016, by clause 58(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

Schedule 12.1, clause 1(1)(b): revoked, on 1 February 2016, by clause 58(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

Schedule 12.1, clause 1(1)(c): amended, on 23 February 2015, by clause 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Schedule 12.1, clause 1(1)(c): amended, on 5 October 2017, by clause 322 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Schedule 12.1, clause 1(2) to (5): revoked, on 16 December 2013, by clause 9(2) of the Electricity Industry Participation (Revocation of Part 16) Code Amendment 2013.



## Schedule 12.2

### Grid reliability standards

cl 12.55

#### 1 Preamble

Clause 12.55 of this Code, requires the **Authority** to determine the most appropriate **grid reliability standards** and in so doing must have regard to the purposes in clause 12.56 and the principles set out in clause 12.57, as required by clause 12.55.

Compare: Electricity Governance Rules 2003 clause 2 schedule F3 part F

#### 2 The grid reliability standards

- (1) The purpose of the **grid reliability standards** is to provide a basis for **Transpower** and other parties to appraise opportunities for transmission investments and **transmission alternatives**.
- (2) For the purpose of subclause (1), the **grid** satisfies the **grid reliability standards** if—
  - (a) the power system is reasonably expected to achieve a level of reliability at or above the level that would be achieved if all **economic reliability investments** were to be implemented; and
  - (b) with all **assets** that are reasonably expected to be in service, the power system would remain in a **satisfactory state** during and following a **single credible contingency event** occurring on the **core grid**.
- (3) For the purpose of subclause (2)(a), the expected level of reliability of the power system must be assessed at each and every **grid exit point** and **grid injection point** (wherever located on the **grid**).
- (4) For the purpose of subclause (2)(a) and (b), the expected level of reliability, and state, of the power system must be assessed using the range of relevant operating conditions that could reasonably be expected to occur.

Compare: Electricity Governance Rules 2003 clauses 3 to 6 schedule F3 part F

#### 3 Interpretation and definitions

- (1) For the purposes of these **grid reliability standards**, unless the context calls for another interpretation—
  - (a) the terms defined in Part 1 of this Code take that defined meaning; and
  - (b) the term defined in subclause (2) takes that defined meaning; and
  - (c) a reference—
    - (i) to the singular includes the plural and conversely; and
    - (ii) to a person includes an individual, company, other body corporate, association, partnership, firm, joint venture, trust, or Government Agency; and
  - (d) the word including or includes means including, but not limited to, or includes, without limitation; and
  - (e) the other grammatical forms of the term defined in subclause (2) have a corresponding meaning.
- (2) **Economic reliability investments** means investments in the **grid** and **transmission**

**alternatives** that would satisfy the economic test for an investment proposal applied by the Commerce Commission under Part 4 of the Commerce Act 1986—

- (a) assuming that the economic test was applied to both investments in the **grid** and **transmission alternatives**; and
- (b) having regard to Parts 7 and 8 (including the **policy statement**).

Compare: Electricity Governance Rules 2003 clauses 7 and 8 schedule F3 part F

#### **4 Value of expected unserved energy**

- (1) The value of any **expected unserved energy** is—
  - (a) \$20,000 per **MWh**; or
  - (b) such other value as the **Authority** may determine.
- (2) The **Authority** may determine different **values of expected unserved energy** under this clause for different purposes and for different times.
- (3) If the **Authority** determines a **value of expected unserved energy** under this clause, the **Authority** must **publish** its determination.

Schedule 12.2, clause 4(1): amended, on 1 February 2016, by clause 59(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

Schedule 12.2, clause 4(2): amended, on 1 February 2016, by clause 59(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

Schedule 12.2, clause 4(3): amended, on 1 February 2016, by clause 59(3) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

## Schedule 12.3 Core grid determination

cl 12.63

### 1 Background

Clause 12.63 of this Code, requires the **Authority** to determine the most appropriate **core grid determination** and in so doing to have regard to the purposes set out in clause 12.64, the principles set out in clause 12.57 for the **grid reliability standards** and the objectives set out in clause 12.65.

Compare: Electricity Governance Rules 2003 clause 2 schedule F3A part F

### 2 The core grid determination

- (1) The purpose of this **core grid determination** is to define the **core grid** for the purposes of the **grid reliability standards** and so provide a basis for—
  - (a) the **Authority** to determine the **grid reliability standards**; and
  - (b) **Transpower** and other parties to appraise opportunities for transmission investment and **transmission alternatives**.
- (2) The **core grid** consists of those assets that comprise the transmission links listed in Table 1 below:

**Table 1**

North Island core grid links	South Island core grid links
220kV Huapai-Marsden	220kV Islington-Kikiwa
220kV Huapai-Bream Bay	220kV Kikiwa-Stoke
220kV Bream Bay-Marsden	220kV Twizel-Tekapo B
110kV Marsden-Maungatapere	220kV Tekapo B-Islington
220 kV Henderson-Huapai	220kV Twizel-Opihi-Timaru-Ashburton
220 kV Albany-Huapai	220kV Ashburton-Bromley
220 kV Albany-Henderson	220kV Bromley-Islington
110kV Albany-Henderson	220kV Twizel-Opihi-Timaru-Islington
110kV Henderson-Hepburn Rd	220kV Livingstone-Islington
220kV Otahuhu-Henderson	220kV Benmore-Ohau B
220kV Otahuhu-Southdown	220kV Ohau B-Twizel
220kV Southdown-Henderson	220kV Benmore-Twizel
220kV Otahuhu-Penrose	220kV Benmore-Ohau C
110kV Mangere-Roskill	220kV Ohau C-Twizel
110kV Otahuhu-Roskill	220kV Benmore-Aviemore
110kV Otahuhu-Pakuranga	220kV Clyde-Cromwell
110kV Otahuhu-Wiri	220kV Cromwell-Twizel
220kV Otahuhu-Takanini	220kV Roxburgh-Clyde
220kV Huntly-Takanini	220kV Naseby-Livingstone
110kV Wiri-Bombay	220kV Roxburgh-Naseby
220kV Huntly-Glenbrook	220kV Roxburgh-Three Mile Hill

North Island core grid links	South Island core grid links
220kV Glenbrook-Takanini	220kV Three Mile Hill-Half Way Bush
220kV Otahuhu-Whakamaru	220kV Three Mile Hill-Sth Dunedin
220kV Otahuhu-Huntly	220kV Sth Dunedin-Half Way Bush
220kV Huntly-Hamilton	220kV Manapouri-Invercargill
110kV Mt Maunganui-Tarukenga	220kV Manapouri-Nth Makarewa
110kV Tarukenga-Tauranga	220kV Nth Makarewa-Invercargill
220kV Tarukenga-Edgecumbe	220kV Invercargill-Roxburgh
220kV Edgecumbe-Kawerau	220kV Invercargill-Tiwai Pt
220kV Kawerau-Ohakuri	220kV Nth Makarewa-Tiwai Pt
220kV Wairakei-Ohakuri	220/66kV interconnection Islington
220kV Ohakuri-Atiamuri	66kV Islington-Addington
220kV Atiamuri-Tarukenga	220/66kV interconnection Bromley
220kV Atiamuri-Whakamaru	
220kV Wairakei-Redclyffe	
220kV Wairakei-Whirinaki	
220kV Whirinaki-Redclyffe	
220kV Hamilton-Whakamaru	
220kV Tokaanu-Whakamaru	
220kV Bunnythorpe-Tokaanu	
220kV Bunnythorpe-Tangiwai	
220kV Rangipo-Tangiwai	
220kV Rangipo-Wairakei	
220kV Wairakei-Poihipi	
220kV Poihipi-Whakamaru	
220kV Stratford-New Plymouth	
110kV New Plymouth-Carrington St	
220kV Bunnythorpe-Haywards	
220kV Haywards-Wilton	
220kV Haywards- Linton	
220kV Wilton-Linton	
220kV Bunnythorpe-Linton	
110kV Wilton-Central Park	
110kV Takapu Rd-Wilton	
220kV Bunnythorpe-Brunswick	
220kV Brunswick-Stratford	
110kV Otahuhu-Mangere	
110kV Haywards-Takapu Rd	
220/110kV interconnection Marsden	
220/110kV interconnection Albany	
220/110kV interconnection Henderson	
220/110kV interconnection Penrose	
220/110kV interconnection Otahuhu	
220/110kV interconnection Hamilton	

North Island core grid links	South Island core grid links
220/110kV interconnection Tarukenga 220/110kV interconnection New Plymouth 220/110kV interconnection Stratford 220/110kV interconnection Redclyffe 220/110kV interconnection Bunnythorpe 220/110kV interconnection Haywards 220/110kV interconnection Wilton	

Compare: Electricity Governance Rules 2003 clauses 3 and 4 schedule F3A part F

### 3 Interpretation

For the purposes of this **core grid determination**, unless the context calls for another interpretation, a term has the meaning given to that term in the **grid reliability standards**.

Compare: Electricity Governance Rules 2003 clause 5 schedule F3A part F

## Schedule 12.4 Transmission Pricing Methodology

cl 12.84

### 1 Introduction

The **transmission pricing methodology** is used to recover the full economic costs of **Transpower's** services, with the exception of investment contracts entered into under clauses 12.70 and 12.71 of this Code, existing new investment contracts and other contracts of the kind referred to in clause 12.95 of this Code. The full economic costs of **Transpower's** services include costs relating to investments which are not subject to approval by the Commerce Commission under section 54R of the Commerce Act 1986 or to which the input methodology under section 54S of that Act applies.

Compare: Electricity Governance Rules 2003 clause 1 schedule F5 part F

### 2 Overview of the Pricing Methodology—

- (1) **Transpower's** principal objective as a State Owned Enterprise is to operate as a successful business. To this end **Transpower's** pricing must, subject to Part 4 of the Commerce Act 1986, recover the costs of providing its transmission services, which include capital, maintenance, operating and overhead costs. Before the start of each **pricing year**, **Transpower's** Board approves forecasts of—
  - (a) the revenue required to recover the costs of providing AC transmission services during the **pricing year**. This forecast is referred to as the **AC revenue** for that **pricing year**; and
  - (b) the revenue required to recover the costs of providing the **HVDC assets** during the **pricing year**. This forecast is referred to as the **HVDC revenue** for that **pricing year**.
- (2) The **transmission pricing methodology** comprises—
  - (a) **connection** charges, which recover part of **Transpower's AC revenue** by reference to the cost of providing **connection assets**. Clauses 8 to 26 describe how **connection** charges are calculated;
  - (b) interconnection charges, which recover the remainder of **Transpower's AC revenue**. Clauses 27 to 30 describe how interconnection charges are calculated; and
  - (c) HVDC charges, which recover **Transpower's HVDC revenue**. Clauses 31 to 33D describe how HVDC charges are calculated.
- (3) An overview of how **Transpower's AC revenue** and **HVDC revenue** are recovered through these charges is shown in diagrammatic form in Appendix A.
- (4) The **transmission pricing methodology** also describes—
  - (a) how the costs of **transmission alternative** services are charged and recovered, if and when **transmission alternatives services** are provided and/or funded by **Transpower** (clause 35); and
  - (b) practical ways to facilitate greater transparency in relation to **Transpower's** prudent discount policy, which helps to ensure that the **transmission pricing**

**methodology** does not provide incentives for inefficient by-pass of the existing grid (clauses 36 to 42).

Compare: Electricity Governance Rules 2003 clause 2 schedule F5 part F

Schedule 12.4, clause 2(2)(a): amended, on 23 February 2015, by clause 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Schedule 12.4, clause 2(2)(c): amended, on 1 April 2017, by clause 4 of the Electricity Industry Participation Code Amendment (Transmission Pricing) 2015.

### 3 Definitions and interpretation

Unless the context otherwise requires—

**AC asset** means a **grid asset** other than an **HVDC asset**

**AC revenue** has the meaning set out in clause 2(1)

**AC switch** means a switch that is an **AC asset**

**alternative project** means an investment proposed by a **customer**, which if implemented, would bypass existing **grid assets**, but does not include proposed new generation

**annual charges** means any or all of the **annual connection charge**, **annual interconnection charge** and **annual HVDC charge** for a **customer** at a **connection location** for a **pricing year**

Schedule 12.4, clause 3, **annual charges**: amended, on 23 February 2015, by clause 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

**annual connection charge** has the meaning set out in clause 8(2)

**annual HVDC charge** has the meaning set out in clause 31

**annual interconnection charge** has the meaning set out in clause 27

**anytime maximum demand** or **AMD** for a **customer** at a **connection location** means the average of the 12 highest **offtake** quantities for that **customer** at that **connection location** during the **capacity measurement period** for the relevant **pricing year**. This definition is subject to clause 34 of this **transmission pricing methodology** and any prudent discount agreement

**anytime maximum injection** or **AMI** for a **customer** at a **connection location** means the average of the 12 highest **injection** quantities for that **customer** at that **connection location** during the **capacity measurement period** for the relevant **pricing year**. This definition is subject to clause 34 of this **transmission pricing methodology** and any prudent discount agreement

**capacity measurement period** means, for a **pricing year**—

- (a) for every purpose other than determining **regional peak demand periods** for the Lower South Island, Lower North Island and Upper North Island, the 12 month period commencing 1 September and ending with the close of 31 August, immediately before the commencement of the **pricing year**:
- (b) for the purpose of determining **regional peak demand periods** for the Lower South Island, Lower North Island, and Upper North Island, the period specified in

paragraph (a), excluding within that period the period commencing 1 November and ending with the close of 30 April

Schedule 12.4, clause 3, **capacity measurement period**: replaced, on 1 April 2017, by clause 5(1)(a) of the Electricity Industry Participation Code Amendment (Transmission Pricing) 2015.

**connection asset** has the meaning set out in clause 6(1)

**connection link** has the meaning set out in clause 5(c)

**connection location** means the **substation** or other location at which a **customer's assets** are directly **connected** to the **grid**

Schedule 12.4, clause 3, **connection location**: amended, on 23 February 2015, by clause 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

**connection node** has the meaning set out in clause 5(b)

**customer** means a person who has or controls **assets** directly **connected** to the **grid** and, in relation to a **connection location**, means a person who has or controls **assets** directly **connected** to the **grid** at that **connection location**. A **customer** may be both an **offtake customer** and an **injection customer** at the same **connection location**

Schedule 12.4, clause 3, **customer**: amended, on 23 February 2015, by clause 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

**customer allocation** has the meaning set out in clause 25(1)

**financial year** means the financial year adopted by **Transpower** from time to time, being a 12 month period or such other period as **Transpower** determines.

**Transpower's** current financial year is a 12 month period from 1 July to 30 June

**grid assets** means assets and other works (including **land and buildings**) owned or operated by **Transpower**, which form part of the **grid** or are required to support the **grid**

**GXP tie** means a situation in which **GXPs** are simultaneously **connected** to the **grid** at more than 1 **point of connection**

Schedule 12.4, clause 3, **GXP tie**: inserted, on 1 April 2017, by clause 5(2) of the Electricity Industry Participation Code Amendment (Transmission Pricing) 2015.

**historical anytime maximum injection** or **HAMI** is the value calculated under clauses 33D and 34

Schedule 12.4, clause 3, **historical anytime maximum injection** or **HAMI**: replaced, on 1 April 2017, by clause 5(1)(b) of the Electricity Industry Participation Code Amendment (Transmission Pricing) 2015.

**HVDC assets** means the **HVDC link** and all **land and buildings** associated with the **HVDC link**

**HVDC customer** means a **customer** who is, from time to time, the owner or operator of—

- (a) **South Island generation** which is directly **connected** to the **grid assets**; or
- (b) a **local network** to which **South Island generation** is **connected**, either directly or indirectly;

Schedule 12.4, clause 3, **HVDC customer**: amended, on 23 February 2015, by clause 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

**HVDC revenue** has the meaning set out in clause 2(1)



**independent expert** means an independent person who is a recognised technical expert in the matter that has been referred to him or her. In appointing an **independent expert** the party referring the matter to the **independent expert** must nominate 3 persons and the other party may agree that any one of them be appointed. Failing agreement between the parties, the **independent expert** will be appointed by the **Authority**

**injection** means the net quantity of **electricity** flow into the **grid** at a **connection location** from a **customer's assets** during a **half hour** determined from **metering information**. This definition is subject to clause 34 of this **transmission pricing methodology** and any prudent discount agreement

**injection customer** means, subject to clause 34, in relation to a **connection location**, a **customer** who has or controls assets from which electricity flowed into the **grid** at that **connection location** in any **half hour** during the **capacity measurement period** for the relevant **pricing year** or, if the **connection location** is a **South Island generation connection location**, an **HVDC customer** who has or controls assets from which electricity flowed into the **grid** at the **South Island generation connection location** in any **half hour** during the **capacity measurement period** for the relevant **pricing year** or a **capacity measurement period** for any of the 4 immediately preceding **capacity measurement periods**

**interconnection asset** has the meaning set out in clause 6(2)

**interconnection link** has the meaning set out in clause 5(d)

**interconnection node** has the meaning set out in clause 5(a)

**land and buildings** means any and all land or interest in land (including easements) acquired by **Transpower** for the purposes of establishing a **connection location** or **substation**, or for supporting **grid assets**, together with all buildings, oil containment facilities and the capitalised cost of establishing a **connection location** or **substation** or other **grid asset** (as the case may be)

**link** has the meaning set out in clause 4(3)

**monthly charges** means any or all of the **monthly connection charge**, **monthly interconnection charge** and **monthly HVDC charge** for a **customer** at a **connection location**

**monthly connection charge** has the meaning set out in clause 8(2)

**monthly HVDC charge** has the meaning set out in clause 31

**monthly interconnection charge** has the meaning set out in clause 27

**new investment contract** means a contract entered into at any time between **Transpower** and a **customer** of **Transpower**, under which **Transpower** agrees to provide any new or upgraded **grid assets** and the **customer** agrees to pay charges based on **Transpower's** cost of providing the new or upgraded **grid assets**. It includes, but is not limited to a **new investment agreement contract** as defined in Part 1 of this Code

**node** has the meaning set out in clause 4(1)

**offtake** means the net quantity of **electricity** flow out of the **grid** at a **connection location** into **customer assets** during a **half hour** determined from **metering information**. This definition is subject to clause 34 of this transmission pricing methodology and any prudent discount agreement

**offtake customer** means, subject to clause 34, in relation to a **connection location**, a **customer** who has or controls assets into which electricity flowed from the **grid** at that **connection location** in any **half hour** during the **capacity measurement period** for the relevant **pricing year**

**optimised replacement cost** means, for any assets or group of assets, the optimised replacement cost of that asset or group of assets recorded in a Transpower asset register as at the **transition date**

**point of injection** means a **connection location** at which an **injection customer** has assets **connected to the grid**

Schedule 12.4, clause 3, **point of injection**: amended, on 23 February 2015, by clause 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

**pricing year** means the period from April 1 to March 31, in respect of which **Transpower** calculates its prices

**region** means a group of **connection locations**, being one of the groups described in Appendix B as—

- (a) Upper North Island; and
- (b) Lower North Island; and
- (c) Upper South Island; and
- (d) Lower South Island

Schedule 12.4, clause 3, **region**: amended, on 1 April 2017, by clause 5(3) of the Electricity Industry Participation Code Amendment (Transmission Pricing) 2015.

**regional coincident peak demand** or **RCPD** for a **customer** at a **connection location** means the **customer's offtake** at that **connection location** during a **regional peak demand period**. This definition is subject to clause 34 of this **transmission pricing methodology** and any prudent discount agreement

Schedule 12.4, clause 3 **regional coincident peak demand**: inserted, on 15 May 2014, by clause 34(b) of the Electricity Industry Participation (Minor Code Amendments) Code Amendment 2014.

**regional demand** means, in any **half hour**, the sum over all **customers** at all **connection locations** in a **region** of all **offtake** quantities at those **connection locations**

**regional peak demand period** means, for each **region**, a **half hour** in which any of the 100 highest **regional demands** occur in the **region** during a **capacity measurement period** for the relevant **pricing year**. This definition is subject to clause 34 of this **transmission pricing methodology** and any prudent discount agreement

Schedule 12.4, clause 3, **regional peak demand period**: replaced, on 1 April 2017, by clause 5(1)(c) of the Electricity Industry Participation Code Amendment (Transmission Pricing) 2015.

**regional coincident peak** *[Revoked]*

Schedule 12.4, clause 3 **regional coincident peak**: revoked, on 15 May 2014, by clause 34(a) of the Electricity Industry Participation (Minor Code Amendments) Code Amendment 2014.

**replacement cost** means—

- (a) for a **connection asset** commissioned before the **transition date**, the cost of replacing that asset (either separately or as part of a group of assets) with a modern equivalent asset with the same service potential, multiplied by the **replacement cost adjustment factor**; and
- (b) for any other **grid asset**, the cost of replacing that asset (either separately or as part of a group of assets) with a modern equivalent asset with the same service potential,

as determined by **Transpower** and (unless stated otherwise) recorded in a **Transpower** asset register;

**replacement cost adjustment factor** means for any asset (or group of assets) the percentage which is the **optimised replacement cost** divided by the cost, as at (or about) the **transition date**, of replacing that asset (or group of assets) with the then modern equivalent asset with the same service potential

**reverse flow** means **electricity** exiting the **grid** at a **GXP** and entering the **grid** at another **GXP** as a result of a **GXP tie**

Schedule 12.4, clause 3, **reverse flow**: inserted, on 1 April 2017, by clause 5(2) of the Electricity Industry Participation Code Amendment (Transmission Pricing) 2015.

**South Island generation** means, subject to clause 34, any **generating unit** or **generating station** located in the South Island, which:

- (a) is directly **connected** to the **grid** or is **connected** to a **local network** which is **connected** (directly or indirectly) to the **grid**; and
- (b) has (directly or indirectly) injected electricity into the **grid** at any time during any **capacity measurement period** for all or any of the previous **5 pricing years**

Schedule 12.4, clause 3, **South Island generation**: amended, on 23 February 2015, by clause 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Schedule 12.4, clause 3, **South Island generation**: amended, on 1 April 2017, by clause 5(4) of the Electricity Industry Participation Code Amendment (Transmission Pricing) 2015.

**South Island generation connection location** means any **connection location** at which **South Island generation** is **connected** to the **grid** either directly, or indirectly via **connection** of a **local network**, to which **South Island generation** is in turn either directly or indirectly **connected** **substation** means a substation, including all **land and buildings**, switches, transformers, revenue meters and all other assets comprising or located at that substation

Schedule 12.4, clause 3, **South Island generation connection location**: amended, on 23 February 2015, by clause 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

**South Island mean injection** or **SIMI** is the value calculated under clauses 33B and 34

Schedule 12.4, clause 3, **South Island mean injection** or **SIMI**: inserted, on 1 April 2017, by clause 5(2) of the Electricity Industry Participation Code Amendment (Transmission Pricing) 2015.

**transition date** means the date of the last ODV report **published** by **Transpower** before the date on which this **transmission pricing methodology** takes effect

Schedule 12.4, clause 3, **transition date**: amended, on 5 October 2017, by clause 323 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.


**weighted average cost of capital** means, for any **pricing year**, the pre-tax nominal weighted average cost of capital used by **Transpower** to determine **AC revenue** or **HVDC revenue** (as the case may be) for that **pricing year**.

Compare: Electricity Governance Rules 2003 clauses 3.1 to 3.53 schedule F5 part F

#### 4 Definition of Nodes and Links


- (1) A **node** is any of the following:
  - (a) a **connection location**:
  - (b) a location where a circuit, which is **connected** to 2 or more other **nodes**, diverges or terminates (such as a “tee” point or a deviation):
  - (c) any **substation** or switching station.
- (2) Any **node** which connects with 1 or more multiple circuits on the same towers or poles where at least 1 of those circuits deviates or terminates at that **node** is treated as a single **node** encompassing all of those circuits at that location.

**Figure 1: Illustration of definition of a node**



- (3) A **link** is either a single circuit or multiple parallel circuits (of the same voltage) **connecting 2 nodes** (and includes any **grid assets**, such as circuit breakers, that are required to **connect the link** at either **node**).
- (4) Figures 1 and 2 illustrate how **nodes** and **links** are identified. In Figure 1, A, B, C, D, E, F and G are all **nodes**. C is a single **node**, because 1 of the circuits of the **link** AC terminates at C. AC, CD (and DE, EF, FG and GD) and BC are separate **links**, although AB may be recorded as a single line in a Transpower asset register. Figure 2 shows the same configuration as Figure 1 but describes the circuits by way of **links**.

**Figure 2 – Illustration of links and loop path**




Compare: Electricity Governance Rules 2003 clauses 3.54 to 3.57 schedule F5 part F  
Schedule 12.4, clause 4(1)(b): amended, on 23 February 2015, by clause 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.  
Schedule 12.4, clause 4(3): amended, on 23 February 2015, by clause 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

## 5 Identification of Nodes and Links as Connection or Interconnection

**Nodes** and **links** are identified as **connection nodes** or **connection links** or **interconnection nodes** or **interconnection links** according to the following:

- (a) an **interconnection node** is any **node connected** to 2 or more **nodes** in a “loop”, other than a “small regional loop”. A loop is a continuous path of **nodes** and **links** with the same start and end **node**. A “small regional loop” is where a loop path exists between any group of **nodes** (excluding the **nodes** at Benmore and Haywards) with only a single **link** from the loop back to the next **node** that is outside the loop (see Figure 3 below):
- (b) a **connection node** is any **node** that is not an **interconnection node**:

**Figure 3 – Example of a small regional loop**



- (c) a **connection link** is a **link** with a **connection node** at one or more of its ends;
- (d) an **interconnection link** is a **link** that connects 2 **interconnection nodes**;
- (e) **links** and **nodes** that comprise a “small regional loop” are **connection links** and **connection nodes**.

Compare: Electricity Governance Rules 2003 clause 3.58 schedule F5 part F

Schedule 12.4, clause 5: amended, on 5 October 2017, by clause 324 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Schedule 12.4, clause 5(a): amended, on 23 February 2015, by clause 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

## 6 Definition of Connection Assets and Interconnection Assets

### (1) A **connection asset** is—

- (a) any **grid asset** at a **connection node** other than **voltage support** equipment that is for **grid voltage support** purposes and has not been installed at a **customer's** request; and
- (b) at an **interconnection node** that is a **connection location**,—
  - (i) any **grid asset** that is specifically required to **connect** a **customer**, including a supply transformer, feeder bay or supply transformer high voltage or low voltage breaker. Low voltage breakers, low voltage bus section breakers, voltage transformers, revenue meters and other equipment where they are on the same bus as the feeders are also **connection assets**; and
  - (ii) any **grid asset** that is used both to **connect** a **customer** (whether injection or offtake) and for **grid** operation generally; and
  - (iii) a proportion of the **land and buildings** at that **connection location**. The proportion of **land and buildings** defined as a **connection asset** is that proportion which the **replacement cost** of the **connection assets** identified in subparagraph (i) but excluding **land and buildings**, bears to the **replacement cost** of all **grid assets** (excluding **land and buildings**) at the **connection location**; and
- (c) any **grid asset** that is a **connection link**. A single line, recorded as such in a **Transpower** asset register, may form part of more than 1 **link**, so that a portion of a line may be identified as a **connection asset** with the remaining portion identified as an **interconnection asset**. For example, in Figure 1, if a line AB were recorded in a **Transpower** asset register, it would form part of a **connection link** BC and an **interconnection link** AC. If part of a line is, or forms part of, a **connection link**, the value and costs ascribed to the **connection link** for the purposes of calculating **connection** charges is the same proportion that the ratio of the length of the **connection link** bears to the total length of the line.

### (2) An **interconnection asset** is any **grid asset** that is not a **connection asset**, or an **HVDC asset**.

### (3) A **connection asset** which connects a **customer's assets** at a **connection location** to the **interconnection assets** is referred to as a **connection asset** "for" or "which connects" (or other grammatical form of that phrase) that **connection location** or **customer's assets** (as the case may be).

Compare: Electricity Governance Rules 2003 clauses 3.59 to 3.61 schedule F5 part F

Schedule 12.4, clause 6(1)(b)(i) and (ii): amended, on 23 February 2015, by clause 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Schedule 12.4, clause 6(1)(c): amended, on 23 February 2015, by clause 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

## 7 Interpretation

Unless the context otherwise requires—

- (a) all defined terms are shown in bold text; and
- (b) terms defined in Part 1 of this Code have that defined meaning;
- (c) terms defined below and elsewhere in the text of this **transmission pricing methodology** take that defined meaning, and any other grammatical form of that term has a corresponding meaning; and
- (d) if there is any inconsistency between the text description of a calculation for which there is formula and the particular formula, the formula takes precedence; and
- (e) diagrams are for information only and do not form a binding part of this **transmission pricing methodology**; and
- (f) a reference—
  - (i) to the singular includes the plural and conversely; and
  - (ii) to a person includes an individual, company, other body corporate, association, partnership, firm, joint venture, trust or Government agency; and
- (g) the word "including" is to be read as "including, but not limited to", and the word "includes" is to be read as "includes, without limitation"; and
- (h) if any matter is to be determined by **Transpower** or **Transpower's** Board, it is to be determined in **Transpower's** or **Transpower's** Board (as the case may be) sole discretion while acting at all times reasonably; and
- (i) a reference to a preceding **financial year** is a reference to the first complete **financial year** that precedes the start of the **pricing year** in respect of which the relevant calculation is undertaken; and
- (j) a reference to a prudent discount agreement includes any agreement entered into under the prudent discount policy in clauses 36 to 42 and any agreement which has the same or similar purpose as the prudent discount policy (including a **notional embedding contract**) entered into between **Transpower** and a **customer** whether before or after commencement of this **transmission pricing methodology**.

Compare: Electricity Governance Rules 2003 clauses 3.62 to 3.71 schedule F5 part F

### *Connection Charges*

## 8 Calculation of the Connection Charges

- (1) A **connection** charge for each **connection asset** for a **connection location** is calculated for each **pricing year** for each **customer** at that **connection location** by multiplying the sum of the asset, maintenance, operating and (for **injection customers**) overhead cost components for a **connection asset** by the relevant **customer allocation**, as follows:

$$\text{connection charge} = (A_{\text{conn}} + M_{\text{conn}} + O_{\text{conn}} + IO_{\text{conn}}) \times CA_{\text{conn}}$$

where

- $A_{\text{conn}}$  is the asset component for the **connection asset** calculated in accordance with clauses 10 to 12
- $M_{\text{conn}}$  is the maintenance component for the **connection asset** calculated in accordance with clauses 13 to 17 and is  $M_{\text{conn subs}}$  or  $M_{\text{conn line type}}$  depending on the nature of the **connection asset**
- $O_{\text{conn}}$  is the operating component for the **connection asset** calculated in accordance with clauses 18 to 20
- $IO_{\text{conn}}$  is the injection overhead component for the **connection asset** calculated in accordance with clauses 21 to 24
- $CA_{\text{conn}}$  is the customer allocation for the **connection asset** for the **connection location** in respect of which the **connection charge** is being calculated, calculated in accordance with clause 25(1) and (2)(a) to (c).

- (2) The sum of all **connection charges** calculated for a **customer** for all **connection assets** for a **connection location** in accordance with subclause (1) is the **annual connection charge** for that **customer** at that **connection location** in that **pricing year**. The **customer's monthly connection charge** at that **connection location** for that **pricing year** is (subject to clause 34 of this **transmission pricing methodology**) calculated as 1/12 of the **annual connection charge**. The example **connection charge** report at clause 25(3) illustrates how a **customer's annual connection charge** for a **connection location** is calculated. (3) If a **customer** is both an **offtake customer** and an **injection customer** at a **connection location**, **connection charges** for that **connection location** are calculated separately for that **customer** as an **offtake customer** and an **injection customer**.

Compare: Electricity Governance Rules 2003 clauses 4.1 to 4.3 schedule F5 part F

Schedule 12.4, clause 8: amended, on 23 February 2015, by clause 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Schedule 12.4, clause 8(2): amended, on 1 April 2017, by clause 6 of the Electricity Industry Participation Code Amendment (Transmission Pricing) 2015.

## 9 Calculation of Connection Charge Components

- (1) Each of the asset, maintenance, operating and overhead cost components of the **connection charge** is calculated by reference to a rate set for that component which is then applied to the particular **connection asset**. Different rates may be set for different types of **connection assets**; for example, different rates are used to calculate the **maintenance component** depending on whether the **connection asset** is located at a **substation** or is a line. Different types of **lines** have different rates. Clauses 10 to 26 describe how the rates are set and applied to determine each component of the **connection charge**.



- (2) The rates for each component of the **connection** charge are recalculated for each **pricing year**.

Compare: Electricity Governance Rules 2003 clauses 4.4 and 4.5 schedule F5 part F

Schedule 12.4, clause 9: amended, on 23 February 2015, by clause 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Schedule 12.4, clause 9(1): amended, on 1 February 2016, by clause 60 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

## 10 Asset Component

The asset component of the **connection** charge allocates a portion of the cost of funding all **connection assets** plus their depreciation to the **connection asset** for which the **connection** charge is being calculated.

Compare: Electricity Governance Rules 2003 clause 4.6 schedule F5 part F

Schedule 12.4, clause 10: amended, on 23 February 2015, by clause 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

## 11 Asset Return Rate

The asset return rate used to calculate the asset component is referred to as **ARR<sub>conn</sub>** and is expressed as a proportion. **ARR<sub>conn</sub>** is calculated by dividing the product of the **weighted average cost of capital** and the regulatory asset value of all **connection assets** plus the annual depreciation of those assets by the **replacement cost** of all **connection assets** as follows:

$$ARR_{conn} = \frac{WACC \times RAV_{conn} + D_{conn}}{\sum_{conn} RC_{conn}}$$

where

**WACC** is the **weighted average cost of capital** (expressed as a percentage)

**RAV<sub>conn</sub>** is the regulatory asset value of all **connection assets**, as determined by **Transpower** and recorded in a **Transpower** asset register (expressed in dollars)

**D<sub>conn</sub>** is total annual depreciation of all **connection assets** in the preceding **financial year** as determined by **Transpower** and recorded in a **Transpower** asset register (expressed in dollars)

$\sum_{conn} RC_{conn}$  is the total **replacement cost** of all **connection assets**.

Compare: Electricity Governance Rules 2003 clause 4.7 schedule F5 part F

## 12 Calculation of Asset Component

The **asset component** of a **connection** charge is calculated by multiplying **ARR<sub>conn</sub>** by the **replacement cost** of the **connection asset** for which the **connection** charge is being calculated as follows:

$$A_{\text{conn}} = \text{ARR}_{\text{conn}} \times \text{RC}_{\text{conn}}$$

where

$\text{RC}_{\text{conn}}$  is the **replacement cost** of the **connection asset** for which the **connection** charge is being calculated (expressed in dollars).

Compare: Electricity Governance Rules 2003 clause 4.8 schedule F5 part F  
Schedule 12.4, clause 12: amended, on 23 February 2015, by clause 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

### 13 Maintenance component

- (1) The maintenance component of the **connection** charge allocates a portion of **Transpower's** total maintenance costs for all **connection assets** to the **connection asset** for which the **connection** charge is being calculated.
- (2) Maintenance recovery rates are set separately for **connection assets** located at **substations** and for the different types of **lines**. The different line types (all AC) used are—
  - (a) 220kV or higher voltage tower **lines**;
  - (b) other tower **lines**; and
  - (c) pole **lines**.

Compare: Electricity Governance Rules 2003 clauses 4.9 and 4.10 schedule F5 part F  
Schedule 12.4, clause 13(1): amended, on 23 February 2015, by clause 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.  
Schedule 12.4, clause 13(2): amended, on 1 February 2016, by clause 61 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

### 14 Substation Maintenance Recovery Rate

The maintenance recovery rate used to calculate the maintenance component of the **connection** charge for **connection assets** located at **substations** is referred to as  $\text{MRR}_{\text{conn subs}}$  and is expressed as a proportion.  $\text{MRR}_{\text{conn subs}}$  is calculated as the average of the annual maintenance costs incurred by **Transpower** for all **connection assets** located at all **substations** in each of the 4 immediately preceding **financial years** divided by the sum of the **replacement costs** of all **connection assets** located at all **substations** as follows:

$$\text{MRR}_{\text{conn subs}} = \frac{\text{MC}_{\text{conn subs}}}{\sum_{\text{subs}} \sum_{\text{conn}} \text{RC}_{\text{conn subs}}}$$

where

$\text{MC}_{\text{conn subs}}$  is the average of the annual maintenance costs incurred by **Transpower** for all **connection assets** located at all **substations** in each of the 4 immediately preceding **financial years**, as determined by **Transpower** and recorded in **Transpower's** Maintenance Management System accounts for each of those **financial years** (expressed in dollars)

$$\sum_{\text{subs conn}} \sum \text{RC}_{\text{conn subs}}$$

is the sum of the **replacement costs** of all **connection assets** located at all **substations**.

Compare: Electricity Governance Rules 2003 clause 4.11 schedule F5 part F  
Schedule 12.4, clause 14: amended, on 23 February 2015, by clause 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

## 15 Calculation of Maintenance Component for a Connection Asset Located at a Substation

The maintenance component of the **connection** charge for a **connection asset** located at a **substation** is calculated by multiplying  $\text{MRR}_{\text{conn subs}}$  by the **replacement cost** of the **connection asset** for which the **connection** charge is being calculated as follows:

$$\text{M}_{\text{conn subs}} = \text{MRR}_{\text{conn subs}} \times \text{RC}_{\text{conn subs}}$$

where

$\text{RC}_{\text{conn subs}}$  is the **replacement cost** of the **connection asset** for which the **connection** charge is being calculated (expressed in dollars).

Compare: Electricity Governance Rules 2003 clause 4.12 schedule F5 part F  
Schedule 12.4, clause 15: amended, on 23 February 2015, by clause 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

## 16 Line Maintenance Recovery Rate

The maintenance recovery rate used to calculate the maintenance component of the **connection** charge for **connection assets** which are **lines** is referred to as  $\text{MRR}_{\text{conn line type}}$  and is expressed as a dollar cost per length (expressed in km) of line for each line type.  $\text{MRR}_{\text{conn line type}}$  is calculated for each of the 3 types of line referred to in clause 13(2) and is the average of annual maintenance costs incurred by **Transpower** for all **lines** of the type for which  $\text{MRR}_{\text{conn line type}}$  is being calculated in each of the preceding 4 **financial years** divided by the total line length of line of that type as follows:

$$\text{MRR}_{\text{conn line type}} = \frac{\text{MC}_{\text{conn line type}}}{\text{TL}_{\text{conn line type}}}$$

where

$\text{MC}_{\text{conn line type}}$  is the average of the annual maintenance costs incurred by **Transpower** for all **lines** of the type for which the maintenance recovery rate is being calculated in each of the 4 immediately preceding **financial years**, as determined by **Transpower** and recorded in **Transpower's** Maintenance Management System accounts for each of those **financial years** (expressed in dollars)

$\text{TL}_{\text{conn line type}}$  is the total length of line of the type for which the maintenance recovery rate is being calculated forming part of the **grid assets** (other than **HVDC assets**), as determined by **Transpower** and

recorded in a **Transpower** asset register at the end of the immediately preceding **financial year** (expressed in km).

Compare: Electricity Governance Rules 2003 clause 4.13 schedule F5 part F

Schedule 12.4, clause 16: amended, on 23 February 2015, by clause 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Schedule 12.4, clause 16: amended, on 1 February 2016, by clause 62 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

## 17 Calculation of the Maintenance Component for Line Connection Assets

The maintenance component of the **connection** charge for a **connection asset** which is a line is calculated by multiplying  $MRR_{\text{conn line type}}$  by the length of the line which is the **connection asset** for which the **connection** charge is being calculated as follows:

$$M_{\text{conn line type}} = MRR_{\text{conn line type}} \times L_{\text{conn line}}$$

where

$L_{\text{conn line}}$  is the length of the line which is the **connection asset** for which the **connection** charge is being calculated, as determined by **Transpower** and recorded in a **Transpower** asset register (expressed in km).

Compare: Electricity Governance Rules 2003 clause 4.14 schedule F5 part F

Schedule 12.4, clause 17: amended, on 23 February 2015, by clause 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

## 18 Operating Component

The operating component of the **connection** charge allocates a portion of **Transpower's** total operating cost for all **AC assets** to the **connection asset** for which the **connection** charge is being calculated.

Compare: Electricity Governance Rules 2003 clause 4.15 Schedule F5 part F

Schedule 12.4, clause 18: amended, on 23 February 2015, by clause 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

## 19 Operating Recovery Rate

The operating recovery rate used to calculate the operating component of the **connection** charge is referred to as **ORR** and is expressed as a dollar cost per switch. **ORR** is calculated by dividing the cost of operating all **AC switches** incurred by **Transpower** in the preceding **financial year** by the total number of **AC switches** less the product of 0.1 multiplied by the total number of **AC switches** operated by **customers** as follows:

$$ORR = \frac{OC}{TS}$$

where

**OC** is the cost associated with operating all **AC switches** incurred by **Transpower** in the immediately preceding **financial year**, as determined by **Transpower** and recorded in its Maintenance

Management System accounts for that **financial year** (expressed in dollars)

TS is the total number of **AC switches**, based on the number of switching devices in a **substation** or switching station, (as determined by **Transpower** and recorded in a **Transpower** asset register as at the end of the immediately preceding **financial year**) less the product of 0.1 multiplied by the total number of **AC switches** operated by **customers**.

Compare: Electricity Governance Rules 2003 clause 4.16 schedule F5 part F  
Schedule 12.4, clause 19: amended, on 23 February 2015, by clause 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

## 20 Calculation of the Operating Component of the Connection Charge for a Connection Asset

The operating component of the **connection** charge for a **connection asset** is calculated by multiplying **ORR** by the number of **AC switches** that form part of the **connection asset** for which the **connection** charge is being calculated less the product of 0.1 multiplied by the number of **AC switches** within the **connection asset** that are operated by **customers** as follows:

$$O_{\text{conn}} = \text{ORR} \times S_{\text{conn}}$$

where

$S_{\text{conn}}$  is the number of switches that form part of the **connection asset** for which the **connection** charge is being calculated, (as determined by **Transpower** and recorded in a **Transpower** asset register) less the product of 0.1 multiplied by the number of **AC switches** within the **connection asset** that are operated by **customers**.

Compare: Electricity Governance Rules 2003 clause 4.17 schedule F5 part F  
Schedule 12.4, clause 20: amended, on 23 February 2015, by clause 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

## 21 Injection Overhead Component

**Offtake customers** pay a portion of **AC revenue** overhead costs through the interconnection charge. **Injection customers** are not charged an interconnection charge, so a share of **AC revenue** overhead cost is allocated through their **connection** charges. The injection overhead component of the **connection** charge is calculated only for **connection assets** that **connect a customer's assets** at a **point of injection** to the **interconnection assets** and therefore applies only to **injection customers**.

Compare: Electricity Governance Rules 2003 clause 4.18 schedule F5 part F  
Schedule 12.4, clause 21: amended, on 23 February 2015, by clause 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

## 22 Injection Overhead Revenue

The portion of AC overhead cost to be recovered from **injection customers** is referred to as  $\text{OHC}_{\text{inj}}$ .  $\text{OHC}_{\text{inj}}$  is calculated by reference to the proportion that the sum of the

maintenance components for all **connection assets** for all **points of injection** bears to total maintenance costs of **AC assets** as follows:

$$OHC_{inj} = OHC_{AC} \times \frac{MC_{inj}}{MC_{AC}}$$

where

$OHC_{AC}$  is the overhead cost component of **Transpower's AC revenue** for the relevant **pricing year**, as determined by Transpower when setting the **AC revenue**

$MC_{inj}$  is the sum of the maintenance cost of the **connection assets** for all **points of injection** in the preceding **financial year**, as determined by **Transpower** and recorded in **Transpower's** Maintenance Management System accounts for that **financial year**

$MC_{AC}$  is the sum of the maintenance cost of the **AC assets** in the preceding **financial year**, as determined by **Transpower** and recorded in **Transpower's** Maintenance Management System accounts for that **financial year**.

Compare: Electricity Governance Rules 2003 clause 4.19 schedule F5 part F

## 23 Injection Overhead Rate

The injection overhead rate used to calculate the injection overhead component of the **connection** charge is referred to as **IOR**. **IOR** is calculated by dividing  $OHC_{inj}$  by the sum of the proportion of the **replacement cost** of each **connection asset connecting injection customer** assets at all **points of injection** to the **interconnection assets** as follows:

$$IOR = \frac{OHC_{inj}}{\sum_{conn\ inj} RC_{conn\ inj} \times CA_{conn\ inj}}$$

where

$RC_{conn\ inj}$  is the **replacement cost** of a **connection asset connecting injection customer assets** at a point of injection to the **interconnection assets**

$CA_{conn\ inj}$  is the **customer allocation** of the relevant **connection asset** for the relevant **injection customer** at the relevant **connection location**

$\sum_{conn\ inj} RC_{conn\ inj} \times CA_{conn\ inj}$  is the sum of all amounts calculated as  $RC_{conn\ inj} \times CA_{conn\ inj}$  for all **injection customers' connection assets** for all **points of injection**.

Compare: Electricity Governance Rules 2003 clause 4.20 schedule F5 part F

Schedule 12.4, clause 23: amended, on 23 February 2015, by clause 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

## 24 Injection Overhead Component

The injection overhead component of the **connection** charge is calculated for a **connection asset** for a **point of injection** by multiplying the **IOR** by the **replacement cost** of that **connection asset** for which the **connection** charge is being calculated as follows:

$$IO_{\text{conn}} = \text{IOR} \times RC_{\text{conn inj}}$$

Compare: Electricity Governance Rules 2003 clause 4.21 schedule F5 part F

Schedule 12.4, clause 24: amended, on 23 February 2015, by clause 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

## 25 Customer Allocation

- (1) Each **customer** at a **connection location** is allocated a proportion (expressed as a percentage) of each **connection asset** for that **connection location**. This percentage is referred to as the **customer allocation** for that **connection asset** at that **connection location**. The **customer allocation** is calculated in accordance with subclause (2). If a **customer** is both an **offtake customer** and an **injection customer** at a **connection location**, a **customer allocation** for each **connection asset** for that **connection location** will be calculated for that **customer** as both an **offtake customer** and as an **injection customer**.
- (2) The **customer allocation** is calculated as follows:
  - (a) for a **connection asset** which connects only 1 **connection location** to **interconnection assets**, except for a **connection asset** of the kind referred to in clause (6)(1)(b)(ii), the **customer allocation** is the proportion that the **customer's anytime maximum demand** or **anytime maximum injection** (as the case may be) at that **connection location** bears to the sum of all **customers' anytime maximum demands** and **anytime maximum injections** at that **connection location**:
  - (b) for a **connection asset** which connects more than 1 **connection location** to **interconnection assets**, except for a **connection asset** of the kind referred to in clause (6)(1)(b)(ii), the **customer allocation** is the proportion that the **customer's anytime maximum demand** or **anytime maximum injection** (as the case may be) at that **connection location** bears to the sum of all **customers' anytime maximum demands** and **anytime maximum injections** at all **connection locations** for that **connection asset**:
  - (c) for a **connection asset** of the kind referred in clause (6)(1)(b)(ii), the **customer allocation** is the proportion that the **customer's anytime maximum demand** or **anytime maximum injection** (as the case may be) at the **connection location** bears to the total capacity of that **connection asset**, as specified in a **Transpower asset register**.
- (3) The following table illustrates the calculation of an **offtake customer's annual connection** charge at a particular **connection location**. It lists all **connection assets** for that **connection location** and the proportion of the **connection** charge for each of those **connection assets** (including the amount of each of the asset, maintenance, and

operating components of the **connection** charge) included in the **annual connection charge** together with the **customer allocation** for the relevant **connection asset**). The column headed "Recovery" is provided for information only and indicates whether the asset, maintenance and operating components (respectively) are recovered under this **transmission pricing methodology** (TPM) or under a **new investment contract** (NIC).

#### Connection charge report

2007 - Connection Charge Components

Customer Southern Electric

Substation: Johnsto

Load Type: OF

Asse	Asset	Physical Location	Recover			Asset Value	Asset Component	Maintenance Component	Operating Component	Customer Allocation	Connection Charge
			A	M	O						
						\$	\$	\$	\$	%	\$
LIN	JTN-PVL		TPM -			4,513,794	393,151	187,603	0	4.27	24,798
LAND/BLDG	JTN	JTN	TPM -			1,343,443	117,014	14,106	0	100.00	131,120
TRA	T1	JTN	NIC -			694,012	0	7,287	0	100.00	7,287
SWIT	1	JTN	TPM -TPM-			113,644	9,898	1,193	1,104	100.00	12,195
SWIT	2	JTN	TPM -TPM-			113,664	9,898	1,193	1,104	100.00	12,195
SWIT	3	JTN	NIC -TPM-			113,664	0	1,193	1,104	100.00	2,297
SWIT	92	PV	TPM -TPM-			344,087	29,970	3,613	2,208	100.00	35,791
Annual Connection Charge											225,683

Example figures only

Compare: Electricity Governance Rules 2003 clauses 4.22 to 4.24 schedule F5 part F  
Schedule 12.4, clause 25(3): amended, on 23 February 2015, by clause 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

## 26 Exceptions to the Application of the Connection Charge

- (1) If a **connection asset** is provided by **Transpower** under a **new investment contract**, in which the capital costs of that **connection asset** are recovered, calculation of the **connection** charge for that **connection asset** for the **customer** who is a party to that **new investment contract** (irrespective of when that agreement was entered into) is as follows:
  - (a) for the purposes of calculating the **connection** charge for that **connection asset** under clause 8(1), the asset component  $A_{\text{conn}}$  is \$0. Recovery of the amount that would otherwise be recovered as the asset component for that **connection asset** is determined by, and recovered under, the **new investment contract**, in accordance with the provisions of the **new investment contract**;
  - (b) the maintenance component and operating component of the **connection** charge are calculated as per clauses 15, 17, and 20; and
  - (c) if the **connection asset** connects more than 1 **connection location** or it connects a **connection location** at which there is more than 1 **customer**, the **customer allocation** is determined in accordance with the relevant **new investment contract**, rather than in accordance with clause 25(2) of this **transmission pricing methodology**.
- (2) If **Transpower** has entered into a prudent discount agreement in which it is agreed that notional **connection assets** that form part of the **alternative project** specified in the prudent discount agreement substitute for **connection assets** at a **connection location**, then for the purposes of clause 8(1) the **customer's customer allocation** for the **connection assets** so substituted is deemed to be 0.



- (3) If a **customer** is **connected** at a **connection location** subject to an **input connection contract**, the following apply:
- (a) those assets that the **customer** uses to **connect** at that **connection location** will not be included in the calculation of the total **connection** charge for that **connection location**:
  - (b) the **customer** will be charged in accordance with the terms of the applicable **input connection contract**.

Compare: Electricity Governance Rules 2003 clauses 4.25 to 4.27 schedule F5 part F  
Schedule 12.4, clause 26: amended, on 23 February 2015, by clause 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

### *Interconnection Charge*

## **27 Interconnection Charge**

The purpose of the interconnection charge is to recover the remainder of **Transpower's AC revenue** that is not recovered via **connection** charges. **Monthly interconnection charges** are paid by **offtake customers** in respect of each **connection location** at which they have **assets connected** to the **grid**. An **annual interconnection charge** is calculated for each **customer** at a **connection location** in accordance with clauses 28 to 30. A **customer's monthly interconnection charge** at that **connection location** is  $\frac{1}{12}$  of the **annual interconnection charge**, subject to clause 34 of this **transmission pricing methodology**.

Compare: Electricity Governance Rules 2003 clause 5.1 schedule F5 part F  
Schedule 12.4, clause 27: amended, on 23 February 2015, by clause 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

## **28 Interconnection Revenue**

The portion of **AC revenue** to be recovered by interconnection charges is calculated as the difference between **Transpower's AC revenue** and the amounts recovered by the **connection** charges for that **pricing year** as follows:

$$R_{IC} = \text{AC revenue} - \sum \text{connection charges}$$

where

AC revenue is **Transpower's AC revenue** for the relevant **pricing year**

$\sum$  connection charges is the sum of all **connection** charges calculated for the relevant **pricing year**.

Compare: Electricity Governance Rules 2003 clause 5.2 schedule F5 part F  
Schedule 12.4, clause 28: amended, on 23 February 2015, by clause 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

## **29 Interconnection Rate**

The interconnection rate used to determine the **annual interconnection charge** is referred to as **IR** and is the same for all **offtake customers** at all **connection locations** in all **regions**. The **IR** is calculated by dividing the interconnection revenue by the sum

of the average of the **RCPDs** for each **customer** at a **connection location** for all **customers** at all **connection locations** for all **regions** as follows:

$$IR = \frac{R_{IC}}{\sum_{regions} \sum_{cust} \sum_{loc} \frac{1}{N_{reg}} \sum_{i=1}^{N_{reg}} RCPD_i}$$

where

$R_{IC}$  is the interconnection revenue calculated in accordance with clause 28

$\sum_{regions} \sum_{cust} \sum_{loc} \frac{1}{N_{reg}} \sum_{i=1}^{N_{reg}} RCPD_i$  is the sum of the average **RCPDs** for each **customer** at a **connection location** for all **customers** at all **connection locations** for all **regions**.

Compare: Electricity Governance Rules 2003 clause 5.3 schedule F5 part F

### 30 Calculating the Interconnection Charge

An **annual interconnection charge** is calculated for each **offtake customer** at a **connection location** by multiplying the interconnection rate by the sum of the **customer's RCPD** at a **connection location** as follows:

$$\text{interconnection charge} = IR \times \frac{1}{N_{reg}} \sum_{i=1}^{N_{reg}} RCPD_i$$

where

$IR$  is  $IR$

$\frac{1}{N_{reg}} \sum_{i=1}^{N_{reg}} RCPD_i$  the average **RCPD** for the **offtake customer** in respect of whom the interconnection charge is being calculated at the relevant **connection locations**.

Compare: Electricity Governance Rules 2003 clause 5.4 schedule F5 part F

### *HVDC charge*

### 31 HVDC Charge

The purpose of the HVDC charge is to recover **Transpower's HVDC revenue**. HVDC charges are paid by all **HVDC customers**. An **annual HVDC charge** is calculated for each **HVDC customer** at each **South Island generation connection location**. The **monthly HVDC charge** is  $\frac{1}{12}$  of the **annual HVDC charge** subject to clause 34 of this **transmission pricing methodology**.

Compare: Electricity Governance Rules 2003 clause 6.1 schedule F5 part F

### 32 HVDC Rate

*[Revoked]*

Compare: Electricity Governance Rules 2003 clause 6.2 schedule F5 part F

Schedule 12.4, clause 32: revoked, on 1 April 2017, by clause 7 of the Electricity Industry Participation Code

Amendment (Transmission Pricing) 2015.

### 33 Calculating the HVDC charge

The **annual HVDC charge** is calculated for each **HVDC customer** at each **South Island generation connection location** as follows:

$$\text{HVDC charge} = (\text{DCR}_{\text{SIMI}} \times \text{SIMI}) + (\text{DCR}_{\text{HAMI}} \times \text{HAMI})$$

where

$\text{DCR}_{\text{SIMI}}$  is the **SIMI-based rate** calculated in accordance with clause 33A, in \$/MWh

$\text{SIMI}$  is the **South Island mean injection** for the **HVDC customer** at the **South Island generation connection location** calculated in accordance with clause 33B, in MWh

$\text{DCR}_{\text{HAMI}}$  is the **HAMI-based rate** calculated in accordance with clause 33C, in \$/kW

$\text{HAMI}$  is the **historical anytime maximum injection** for the **HVDC customer** at the **South Island generation connection location** as calculated in accordance with clause 33D, in kW.

Compare: Electricity Governance Rules 2003 clause 6.3 schedule F5 part F  
Schedule 12.4, clause 33: replaced, on 1 April 2017, by clause 8 of the Electricity Industry Participation Code Amendment (Transmission Pricing) 2015.

#### 33A SIMI-based rate

The **SIMI-based rate** is calculated for each **pricing year** by dividing **HVDC revenue** by the sum of the **SIMI** of all **HVDC customers** at all **South Island generation connection locations**, as follows:

$$\text{DCR}_{\text{SIMI}} = \left(\frac{i}{4}\right) \frac{R_{\text{HVDC}}}{\sum \text{SIMI}}$$

Where

$\text{DCR}_{\text{SIMI}}$  is the **SIMI-based rate** for the relevant **pricing year**, in \$/MWh

$i$	for the <b>pricing year</b> 2017/18	$i=1$
	for the <b>pricing year</b> 2018/19	$i=2$
	for the <b>pricing year</b> 2019/20	$i=3$
	for each subsequent <b>pricing year</b>	$i=4$

$R_{\text{HVDC}}$  is **HVDC revenue** for the relevant **pricing year**, in dollars

$\sum \text{SIMI}$  is the sum of the **SIMI** of all **HVDC customers** at all **South Island generation connection locations** for the relevant **pricing year**, in MWh.

Schedule 12.4, clause 33A: inserted, on 1 April 2017, by clause 8 of the Electricity Industry Participation Code Amendment (Transmission Pricing) 2015.

### 33B Calculation of South Island mean injection

**South Island mean injection** or **SIMI** is calculated for each **HVDC customer** at each **South Island generation connection location** for a **pricing year**, and is the average of the total **injection** from the **HVDC customer's assets** at the **South Island generation connection location** in the **capacity measurement period** for the **pricing year** and the **capacity measurement periods** for previous **pricing years**, as follows:

$$\text{SIMI} = \frac{\sum \text{injection}}{1 + p}$$

Where

**SIMI** is the **HVDC customer's South Island mean injection** for the relevant **pricing year**, in **MWh**

$\sum \text{injection}$  is the total **injection** from the **HVDC customer's assets** at the **South Island generation connection location** in the **capacity measurement period** for the **pricing year** for which **SIMI** is being calculated and the **capacity measurement periods** for the  $p$  immediately preceding **pricing years**, in **MWh**

$P$	for the <b>pricing year</b> 2017/18	$p=0$
	for the <b>pricing year</b> 2018/19	$p=1$
	for the <b>pricing year</b> 2019/20	$p=2$
	for the <b>pricing year</b> 2020/21	$p=3$
	for each subsequent <b>pricing year</b>	$p=4$ .

Schedule 12.4, clause 33B: inserted, on 1 April 2017, by clause 8 of the Electricity Industry Participation Code Amendment (Transmission Pricing) 2015.

### 33C HAMI-based rate

The **HAMI-based rate** is calculated for each **pricing year** by dividing **HVDC revenue** by the sum of the **HAMI** for all **HVDC customers** at all **South Island generation connection locations** for the relevant **pricing year**, as follows:

$$\text{DCR}_{\text{HAMI}} = \left( \frac{4-i}{4} \right) \frac{R_{\text{HVDC}}}{\sum \text{HAMI}}$$

Where

$\text{DCR}_{\text{HAMI}}$  is the **HAMI-based rate** for the relevant **pricing year**, in **\$/kW**

$I$	for the <b>pricing year</b> 2017/18	$i=1$
	for the <b>pricing year</b> 2018/19	$i=2$
	for the <b>pricing year</b> 2019/20	$i=3$

for each subsequent **pricing year**  $i=4$

$R_{\text{HVDC}}$  is **HVDC revenue** for the relevant **pricing year**, in dollars

$\sum \text{HAMI}$  is the sum of the **HAMI** of all **HVDC customers** at all **South Island generation connection locations** for the relevant **pricing year**, in kW.

Schedule 12.4, clause 33C: inserted, on 1 April 2017, by clause 8 of the Electricity Industry Participation Code Amendment (Transmission Pricing) 2015.

### 33D Calculation of historical anytime maximum injection

**Historical anytime maximum injection** or **HAMI** is calculated for each **HVDC customer** at each **South Island generation connection location** for a **pricing year**, and is—

- (a) for the **pricing year** 2017/18, the greater of the following:
  - (i) the average of the **customer's** 12 highest **injections** at the **connection location** during the **pricing year** 2013/14:
  - (ii) the average of the **customer's** 12 highest **injections** at the **connection location** during the **pricing year** 2014/15:
  - (iii) the average of the **customer's** 12 highest **injections** at the **connection location** during the period commencing on 1 April 2015 and ending with the close of 31 August 2015:
  - (iv) the average of the **customer's** 12 highest **injections** at the **connection location** during the **capacity measurement period** for the **pricing year** 2016/17; and
- (b) for the pricing year 2018/19, the greater of the following:
  - (i) the average of the **customer's** 12 highest **injections** at the **connection location** during the **pricing year** 2014/15:
  - (ii) the average of the **customer's** 12 highest **injections** at the **connection location** during the period commencing on 1 April 2015 and ending with the close of 31 August 2015:
  - (iii) the average of the **customer's** 12 highest **injections** at the **connection location** during the **capacity measurement period** for the **pricing year** 2016/17; and
- (c) for the pricing year 2019/20, the greater of the following:
  - (i) the average of the **customer's** 12 highest **injections** at the **connection location** during the period commencing on 1 April 2015 and ending with the close of 31 August 2015:
  - (ii) the average of the **customer's** 12 highest **injections** at the **connection location** during the **capacity measurement period** for the **pricing year** 2016/17.

Schedule 12.4, clause 33D: inserted, on 1 April 2017, by clause 8 of the Electricity Industry Participation Code Amendment (Transmission Pricing) 2015.

**34 Adjustments to AMD, AMI, HAMI, SIMI and RCPD and calculation of customer charges**

- (1) Before the start of a **pricing year**, and otherwise during a **pricing year** as provided in this clause, **Transpower** will calculate—

- (a) **AMD AMI, HAMI, SIMI and RCPD** quantities (for each **regional peak demand period**); and
- (b) **annual charges**; and
- (c) **monthly charges**—

in each case for every **customer** at every **connection location** for that **pricing year**.

When a **monthly charge** is recalculated for part of a **pricing year**, all inputs used in the calculation will be the same as those used to calculate that **monthly charge** before the start of the **pricing year** except for the adjustments specifically provided in this clause.

- (2) If, when calculating **AMD, AMI, HAMI, SIMI and RCPD** quantities before the start of a **pricing year**, **Transpower**, in its sole discretion, considers that exceptional operating circumstances during the relevant **capacity measurement period(s)** have resulted in—

- (a) abnormal **regional demand** resulting in an exceptional **regional peak demand period** for that **pricing year**; and/or
- (b) distortions to a **customer's AMD, AMI, HAMI, SIMI** and/or any **RCPD** quantity at a **connection location** for that **pricing year**—

**Transpower** may, but is under no obligation to—

- (c) determine that the exceptional **regional peak demand period** is to be ignored when assessing the **regional peak demand periods** for that **pricing year**; and/or
- (d) adjust the **customer's AMD, AMI, HAMI, SIMI** and/or any **RCPD** for the quantity at the relevant **connection location** to minimise the impact of such distortion, as assessed by **Transpower** acting reasonably but otherwise in its sole discretion, as applicable. Such adjusted **AMD, AMI, HAMI, SIMI and RCPD** qualities, as the case may be, shall be used to calculate **monthly charges** for that **customer** for that **connection location** for that **pricing year**.

- (3) If **Transpower**—

- (a) is notified that **South Island generation** at a **connection location** has been permanently de-rated (including decommissioning) to a specified aggregate rate capacity (“maximum de-rated capacity”); and
- (b) is satisfied that such **South Island generation** has been so permanently de-rated,—

then, for the purposes of calculating a **customer's HAMI and SIMI** at the relevant **connection location** for any **pricing year** that commences not less than 6 months after the date on which **Transpower** is satisfied under paragraph (b), any **injection** at that **connection location** in any **half-hour** period up to the date on which **Transpower** is satisfied under paragraph (b) which:

- (c) is used to determine the **customer's HAMI and SIMI**; and
  - (d) exceeds the maximum de-rated capacity,—
- will be deemed to be equal to the maximum de-rated capacity.

- (4) If not less than 6 months before the start of a **pricing year**, **Transpower**—
- (a) is notified that the **offtake** and/or **injection** capacity of a **customer's assets** at a **connection location** has been permanently de-rated (including decommissioning); and
  - (b) is satisfied that the **offtake** and/or **injection** capacity of such **assets** has been so permanently de-rated—
- then, for the purpose of calculating the **customer's AMD, AMI** and/or **RCPD** quantities at that **connection location** for any **pricing year** that commences not less than 6 months after the date on which **Transpower** is satisfied under paragraph (b),—
- (c) **Transpower** will estimate (acting reasonably but otherwise in its sole discretion) the **customer's** likely future **offtake** or **injection** (as the case may be) at that **connection location**, having regard to the change in the **customer's offtake** and/or **injection**; and
  - (d) **injection** or **offtake** quantities for any **half-hour** period up to the date on which **Transpower** is satisfied under paragraph (b) which—
    - (i) are used to determine the **customer's AMD, AMI** or **RCPD** quantities; and
    - (ii) exceed **Transpower's** estimate under paragraph (c),—will be deemed to be no more than the amounts estimated by **Transpower** under paragraph (c).
- (5) If—
- (a) **Transpower** decommissions a **connection location**; or
  - (b) a **customer** causes all of its **assets connected** to the grid at a **connection location** to be, and **Transpower** is satisfied that the **customer's assets** have been, permanently disconnected from the **grid** at that **connection location**,—
- then—
- (c) the **customer's monthly charges** for the month in which the **connection location** is decommissioned, will be pro-rated for the number of days that the **connection location** was decommissioned or **assets** were disconnected and the **monthly charges** will be reduced accordingly; and
  - (d) from the month following the month in which such decommissioning or disconnection occurred, the **customer's AMD, AMI, HAMI, SIMI** and all **RCPD** quantities at that **connection location** and the **customer's monthly charges** at that **connection location** will be deemed to be 0.
- (6) If a **customer** connects **assets** to the **grid** at a **connection location** where that **customer** does not already have **assets connected** to the **grid** (including a **new connection location**), the following applies:
- (a) **Transpower** will agree with the **customer** whether the **customer** is to be an **offtake customer** or an **injection customer** at the relevant **connection location** and the **customer** will, until such time as the **assets** have been **connected** for a full **capacity measurement period**, be deemed to be an **offtake customer** and/or an **injection customer** accordingly;
  - (b) if the **asset** is a **generating unit** or **generating station** located in the South Island, the **generating unit** or **generation station** will be deemed to be **South Island generation**:

- (c) **Transpower** will assign the **new connection location** to a **region** (unless it is an existing **connection location**):
  - (d) from the time of **connection** of the **assets** until such time as the **assets** have been **connected** to the **grid** for the whole of the **capacity measurement period** for a **pricing year**, or, in the case of assets which are deemed to be **South Island generation** under paragraph (b), have been **connected** to the grid for 5 consecutive **capacity measurement periods**, the **customer's AMD, AMI, HAMI, SIMI and RCPD** quantities at the **connection location** will be determined using **Transpower's** estimates of the customer's likely offtake and/or injection at the **connection location** for that period:
  - (e) the **customer** will pay **monthly charges** at the **connection location** from the date the **customer's assets** are **connected** to the **grid**. If the **customer's assets** are **connected** part way through a month, the **monthly charges** for that month will be reduced by an amount, being a pro-rata proportion of the **monthly charges** for the number of days in the month that the **customer's assets** were not **connected**.
- (7) If—
- (a) a **customer's connection** of new **assets** at a **connection location** to which subclause (5) applies, (the “**first connection location**”) is a direct consequence of that **customer's** de-rating of **assets** at another **connection location**, (the “**second connection location**”) without the **customer** terminating the second **connection location** as a **point of connection** under any relevant **transmission agreement**; and
  - (b) the **connection assets** for the second **connection location** are shared with any other **customer**,—
- then—
- (c) **Transpower** will estimate (acting reasonably but otherwise in its sole discretion) the **customer's** likely **offtake** or **injection** at the second **connection location** from the date on which the new **assets** are **connected** at the first **connection location** (“load transfer date”) until those assets have been **connected** to the **grid** for the whole of a **capacity measurement period** for a **pricing year**; and
  - (d) the **customer's monthly connection charges** at the second **connection** will be recalculated from the load transfer date. When recalculating the **customer's monthly connection charges** from the load transfer date, any **injection** and/or **offtake** prior to the load transfer date used to calculate the **customer's AMD** and/or **AMI** at the second **connection location** will be capped at **Transpower's** estimates in accordance with subclause (6)(a); and
  - (e) if the load transfer date occurs part way through a month, the **customer's monthly connection charges** at the second **connection location** for that month will be the sum of:
    - (i) a pro-rata proportion of the **customer's monthly connection charges** at the second **connection location** immediately before the load transfer date, based on the number of days in the month prior to the load transfer date; and
    - (ii) a pro-rata proportion of the **customer's** monthly **connection charges** at the second **connection location** recalculated in accordance with



- subclause (6)(e), based on the number of days in the month including and subsequent to the load transfer date.
- (8) If **Transpower** enhances or upgrades **connection assets** for a **connection location** under a **new investment contract** with a **customer** (a “NIC customer”), excluding NIC customers to whom subclause (5) applies,—
- (a) if the enhancement or upgrade is commissioned part way through a **pricing year**, **monthly connection charges** at that **connection location** for the NIC customer will be recalculated from the date the enhanced or upgraded **connection assets** are commissioned to take into account those enhanced or upgraded **connection assets**; and
  - (b) if the **connection asset** enhancement or upgrade is commissioned part way through a month, the NIC **customer’s monthly connection charge** for that month will be the recalculated **monthly connection charge** reduced by an amount, being a pro-rata proportion of the recalculated **monthly connection charge** for the number of days in the month before commissioning of the enhancement or upgrade.
- (9) If under this clause, **Transpower** estimates a **customer’s** likely **offtake** or **injection** over any period, **Transpower** may, but is not obliged to, review its estimate from time to time, but not more frequently than at 3 monthly intervals. If **Transpower** revises its estimate, the **customer’s**—
- (a) **AMD, AMI, HAMI, SIMI and RCPD** quantities; and
  - (b) **monthly charges**—
- will be recalculated accordingly and such recalculated **monthly charges** will be payable upon **Transpower** giving such notice as required in the relevant **transmission agreement** with the **customer**.
- (10) If subclauses (6), (7) or (8) apply, or **Transpower** revises any estimate and **monthly grid charges** under subclause (9), there will be a wash-up and reconciliation at the end of the relevant **pricing year** of—
- (a) **monthly connection charges** paid by—
    - (i) all **customers** at the **connection location**; and
    - (ii) all other **customers** at **connection locations** which share the same **connection assets**; and
  - (b) **monthly HVDC charges** paid by all **HVDC customers**,—
- in each case, in that **pricing year** as follows:
- (c) in the case of **monthly connection charges**, the wash-up and reconciliation is to be undertaken in respect of all charges calculated in accordance with clause 8(1) for each shared **connection asset**—
    - (i) using **AMD** or **AMI** for each **customer** as at the last day of the **pricing year** (including any **Transpower** estimate); and
    - (ii) so that the sum of the percentage proportions allocated to **customers** in accordance with clause 25(1) does not exceed 100% for any **connection asset** and so that **Transpower**, in turn, does not recover, in aggregate, more than 100% of the sum of the asset, maintenance, operating and overhead

- cost components calculated in accordance with clauses 8 to 26 for any **connection asset**:
- (d) in the case of **monthly HVDC charges**, the wash-up and reconciliation is to be undertaken—
    - (i) using **HAMI** and **SIMI** for each **HVDC customer** as at the last day of the **pricing year**; and
    - (ii) so that the sum of all **monthly HVDC charges** paid by the **HVDC customer** for that **pricing year** does not exceed the **HVDC revenue** for that **pricing year**:
  - (e) **Transpower** will issue a credit note for any overpayment by a **customer** consequent upon the wash-up.
- (11) If a prudent discount agreement commences part way through a **pricing year**, **Transpower** will recalculate the **customer's monthly charges** at the relevant **connection location(s)** consistently with the prudent discount agreement from the date the prudent discount agreement takes effect until it terminates or otherwise ceases to apply. If the prudent discount agreement commences part way through a month, the customer's **monthly charges** for that month will be the sum of—
- (a) a pro-rata proportion of the **monthly charges** calculated in accordance with this **transmission pricing methodology** being the proportionate number of days in the month before the commencement of the prudent discount agreement; and
  - (b) a pro-rata proportion of the **monthly charges** calculated in accordance with the prudent discount agreement being the proportionate number of days in the month on and from commencement of the prudent discount agreement.
- (12) **Transpower** must adjust a **customer's AMD, AMI, HAMI, SIMI, or RCPD** at a **connection location** to minimise the impact of **reverse flow** at the **connection location** if—
- (a) the **customer** has an agreement with the **system operator** under clause 6 of Technical Code A of Schedule 8.3; and
  - (b) within 20 **business days** after the **reverse flow** commences at the **connection location**, the **customer** has notified **Transpower** that there is **reverse flow** at the **connection location**; and
  - (c) **Transpower** agrees that there is **reverse flow** at the **connection location**.
- (13) If **Transpower** makes an adjustment under subclause (12), **Transpower** must, no later than 20 **business days** after making the adjustment, make available on its website the reasons for the adjustment, and how the adjustment was calculated.
- (14) **Transpower** is not required to calculate **HAMI** quantities under this clause for any **pricing year** after the **pricing year 2019/20**.

Compare: Electricity Governance Rules 2003 clause 7 schedule F5 part F

Schedule 12.4, clause 34 Heading: amended, on 1 April 2017, by clause 9(1) of the Electricity Industry Participation Code Amendment (Transmission Pricing) 2015.

Schedule 12.4, clause 34(1) to (10): amended, on 1 April 2017, by clause 9(2) to (4) of the Electricity Industry Participation Code Amendment (Transmission Pricing) 2015.

Schedule 12.4, clause 34(5), (6) and (7): amended, on 23 February 2015, by clause 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Schedule 12.4, clause 34(12), (13) and (14): inserted, on 1 April 2017, by clause 9(5) of the Electricity Industry Participation Code Amendment (Transmission Pricing) 2015.

### *Transmission alternatives*

#### **35 Transmission Alternatives**

- (1) Charges for **transmission alternative** services will apply when **transmission alternative** services are provided and/or funded by **Transpower**. **Transmission alternative** services are services which substitute for the services provided by **connection assets** or **interconnection assets** or both.
- (2) If a **transmission alternative** service substitutes for a service which would otherwise be provided by **connection assets**, a charge recovering **Transpower's** costs of funding that **transmission alternative** service is added to the **connection** charge(s) of the **customer(s)** for the relevant **connection location(s)**. The costs of the **transmission alternative** service are allocated between all **customers** at the relevant **connection locations(s)** in the same proportion that each **customer's** total **connection** charges for the relevant **connection location(s)** bears to the sum of all **customers' connection** charges for those **connection location(s)**.
- (3) If a **transmission alternative** service substitutes for services which would otherwise be provided by **interconnection assets** a charge recovering the cost of the **transmission alternative service** is allocated between **offtake customers** in the same proportion that each **offtake customer's** interconnection charges bears to the sum of all **offtake customers' interconnection** charges.
- (4) If a **transmission alternative** service substitutes for both **connection assets** and **interconnection assets**, the allocation of the costs of the **transmission alternative service** as between **connection assets** and **interconnection assets** must be calculated in accordance with clause 25(2) for shared **connection assets** at an **interconnection node**.
- (5) The costs of funding **transmission alternative** services will be charged to, and payable by, **customers** in the month following the month in which **Transpower** is invoiced for those costs.

Compare: Electricity Governance Rules 2003 clause 8 schedule F5 part F

Schedule 12.4, clause 35(2): amended, on 23 February 2015, by clause 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Schedule 12.4, clause 35(4): amended, on 5 October 2017, by clause 325 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### *Prudent Discount Policy*

#### **36 Purpose of the Prudent Discount Policy**

- (1) The purpose of the prudent discount policy is to help ensure that the **transmission pricing methodology** does not provide incentives for the uneconomic bypass of existing **grid assets**. The prudent discount policy aims to deter investment in **alternative projects** which would allow a **customer** to reduce its own transmission charges while increasing the total economic costs to the nation as a whole.
- (2) In order for a **customer** to obtain a prudent discount a **customer's alternative project** must be—

- (a) technically, operationally and commercially viable and have a reasonable prospect of being able to be successfully implemented; and
  - (b) uneconomic to implement given **Transpower's** economic costs of providing existing **grid assets** and the economic costs that would be incurred by the customer if it proceeded with the **alternative project**,—
- determined in accordance with this prudent discount policy.

Compare: Electricity Governance Rules 2003 clauses 9.1 and 9.2 schedule F5 part F

### **37 Information Required in a Prudent Discount Application**

- (1) In order for an **alternative project** to be accepted by **Transpower** as a prudent discount application it must be developed to a level of detail equivalent to the detail that a prudent company Board would reasonably expect when considering an investment proposal.
- (2) If a **customer** wishes to apply for a prudent discount, that **customer** must (at its own expense) submit to **Transpower** a written proposal describing the **alternative project** and the likely impact of that **alternative project** on that **customer's** transmission charges.
- (3) The proposal must, to the extent relevant, contain all of the information described in Appendix C, together with any other information which is likely to be relevant to **Transpower's** consideration of the **alternative project**.
- (4) Without limiting subclause (3) **Transpower** may require the **customer** to provide any additional information which **Transpower** considers is reasonably necessary to enable it to conduct its assessment of the **alternative project** in accordance with clauses 38 and 39.

Compare: Electricity Governance Rules 2003 clauses 9.3 to 9.6 schedule F5 part F

### **38 Assessment of Technical, Operational and Commercial Viability of Alternative Project**

- (1) **Transpower** will, within a reasonable time of receiving the proposal, assess the **alternative project** to determine whether or not—
  - (a) it is technically feasible; and
  - (b) it is operationally feasible and compliant with the **asset owner performance obligations** and **technical codes**, and any other relevant requirements as set out in Part 8 of this Code; and
  - (c) the **alternative project** could reasonably be expected to provide the **customer** with transmission charges that would result in a lower overall commercial cost having regard to the capital, operating, maintenance and all other costs likely to be incurred by the **customer** as a result of undertaking the **alternative project** to the **customer** than the current **Transpower** charges, for the same or a similar level of service.
- (2) In undertaking its assessment of the **alternative project**, **Transpower** may adjust any of the information provided by the **customer** to reflect **Transpower's** reasonable assessment of current market prices, good engineering practice and any consequential impacts of the **alternative project** on the **grid assets** and the **customer's** assets.

Compare: Electricity Governance Rules 2003 clauses 9.7 and 9.8 schedule F5 part F

**39 Assessment that the Alternative Project is Uneconomic**

- (1) If **Transpower** considers that the **alternative project** does not satisfy one or more of the criteria specified in clause 38(1), no prudent discount will be provided.
- (2) If **Transpower** considers that the **alternative project** satisfies all of the criteria specified in clause 38(1), **Transpower** will, within a reasonable time thereafter, assess the **alternative project** to determine whether or not it is uneconomic in accordance with subclauses (3) to (7).
- (3) **Transpower** will calculate the present value of the estimated total costs of the **alternative project** including capital costs and operating and maintenance costs. **Transpower** may use the cost estimates provided by the **customer** or may reasonably adjust those costs to reflect current market prices, good engineering practice and consequential impacts of the **alternative project** on **grid assets** and the **customer's assets**.
- (4) The discount rate used to undertake the calculations required by subclauses (3) to (7) must be a discount rate determined by the **Authority**, from time to time, or if the **Authority** has not determined a discount rate, a discount rate of, or equivalent to, a pre-tax real rate of 7%. The calculations required by subclauses (3) to (7) will be carried out using a period of 15 years or the remaining life of the **grid assets** which the **alternative project** would bypass, whichever is the lesser.
- (5) **Transpower** will then calculate the present values of—
  - (a) **Transpower's** costs of continuing to provide transmission services to the **customer** if the **alternative project** does not proceed, including operating and maintenance costs and planned future capital expenditure needed to maintain required service levels; and
  - (b) **Transpower's** costs of continuing to provide transmission services to the **customer** if the **alternative project** does proceed, including operating and maintenance costs and planned future capital expenditure needed to maintain required service levels.
- (6) If the amount calculated under subclause (5)(a) minus the amount calculated under subclause (5)(b) is greater than the amount calculated under subclause (3), the **alternative project** will be determined to be economic and no discount will be provided.
- (7) If the amount calculated under subclause (5)(a) minus the amount calculated under subclause (5)(b) is less than the amount calculated under subclause (3), the **alternative project** will be determined to be uneconomic.

Compare: Electricity Governance Rules 2003 clauses 9.9 to 9.15 schedule F5 part F

**40 Independent Review**

- (1) The **customer** may, within 60 days of being notified of **Transpower's** decision to offer a prudent discount agreement or that no discount will be provided, request a review by an **independent expert** of any or all of the assessments undertaken by **Transpower** for the purposes of that decision.

- (2) Within a reasonable time of being appointed, the **independent expert** is to report his or her findings to **Transpower** and the **customer**. The findings of the **independent expert** will be binding on **Transpower** and the **customer**. If the **independent expert** finds that the **customer's alternative project** is uneconomic and satisfies all the requirements of clause 38(1), the provisions of clause 41(1) will apply.
- (3) The costs of the **independent expert** are to be met by the party requesting the review if the information or assessments reviewed are confirmed as reasonable; otherwise the costs will be met by the other party.

Compare: Electricity Governance Rules 2003 clauses 9.16 to 9.18 schedule F5 part F

#### **41 Prudent Discount Agreement**

- (1) If the **customer's alternative project** is considered by **Transpower** to be uneconomic and to satisfy all the requirements of clause 38(1), **Transpower** will offer a prudent discount agreement to all **customers** that are directly affected by the proposal. The prudent discount agreement will provide for—
  - (a) the **customer** to pay to **Transpower** an annuity (the amount of which is to be specified in the prudent discount agreement) determined by reference to the **customer's** cost of funding, maintaining and operating the **alternative project** over the duration of the prudent discount agreement, applying a commercial discount rate; and
  - (b) **Transpower** to calculate the **customer's** transmission charges in accordance with this **transmission pricing methodology** as if the **alternative project** had been implemented.
- (2) The commencement date of a prudent discount agreement will take full account of the time that would reasonably be required for the **customer** to implement the **alternative project**.
- (3) The duration of a prudent discount agreement will be the lesser of the remaining economic life of the **grid assets** that are affected by the agreement, or 15 years.

Compare: Electricity Governance Rules 2003 clauses 9.19 to 9.21 schedule F5 part F


#### **42 Prudent Discount Details to be Published**

- (1) As soon as reasonably practicable after concluding a prudent discount agreement with a **customer**, **Transpower** must **publish** the decision made, the analysis supporting that decision and the following information:
  - (a) the cost estimate used by **Transpower** in assessing the **alternative project** and the calculations undertaken by **Transpower** using those cost estimates;
  - (b) any report prepared by an **independent expert**;
  - (c) the annual amount payable by the **customer** under clause 41(1)(a);
  - (d) details of how the **customer's** transmission charges will be calculated under clause 41(1)(b).

Compare: Electricity Governance Rules 2003 clause 9.22 schedule F5 part F

Schedule 12.4, clause 42(1): amended, on 5 October 2017, by clause 326 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

## Appendix A– Allocation of Transpower’s AC Revenue and HVDC Revenue to its



Compare: Electricity Governance Rules 2003 appendix A schedule F5 part F  
Schedule 12.4, Appendix A: amended, on 1 April 2017, by clause 10(1) and (2) of the Electricity Industry Participation Code Amendment (Transmission Pricing) 2015.

## Appendix B Regions

### North Island

- (a) Upper North Island (UNI): all **connection locations** on, or north and west of, a line—
  - (i) commencing at 38°02'S and 174°42'E; then
  - (ii) proceeding in a generally north-easterly direction directly to 37°36'S and 175°27'E; then
  - (iii) proceeding north along the 175°27'E line of longitude.
- (b) Lower North Island (LNI): all **connection locations** south and east of the line described in paragraph (a).

### South Island

- (a) Upper South Island (USI): all **connection locations** on, or north of, a line passing through 43°30'S and 169°30'E, and 44°40'S and 171°12'E.
- (b) Lower South Island (LSI): all **connection locations** south of the line described in paragraph (a).

Compare: Electricity Governance Rules 2003 appendix B schedule F5 part F

Schedule 12.4 Appendix B: replaced, on 1 April 2017, by clause 11 of the Electricity Industry Participation Code Amendment (Transmission Pricing) 2017.



## **Appendix C**

### **Information Required to Support a Prudent Discount Application**

#### **General information**

1. Location of the **alternative project**.
2. A brief description of the **alternative project**.
3. A sketch or schematic of the **alternative project**.

#### **Part A: Information required to enable a technical evaluation of the proposal**

- (1) A report on the technical viability of the **alternative project**, provided by either the **customer**, or an external consultant on behalf of the **customer**. The report must include details of voltage quality, especially if there are switched capacitors and/or switched loads, such as motor starting, and information on the size of load, the size of any capacitors, the frequency of switching and the size of voltage steps.
- (2) A circuit diagram.
- (3) For a **customer** who operates a distribution network, a diagram of the **customer's** distribution network that is sufficiently detailed to run load-flow models. The network diagram should contain load distribution data, circuit parameters and the parameters of any embedded generation.
- (4) A description of how the requirement for any additional physical space will be met. (When attaching to existing equipment, or to an existing facility, there may be a need for physical space for new equipment, e.g. a new circuit breaker bay or a **connection** point to a generator bus.)
- (5) The following information, except if it is not applicable to the **alternative project**:
  - Voltage (kV)
  - Demand (peak MW/low MW)
  - Conductor rating and type
  - Circuit length (km) and type (single or double)
  - Voltage support type and rating (VARs)
  - Estimated losses (MW/km)
  - Transformers: size (VA) and impedance ( $\Omega$ )

#### **Part B: Cost of the alternative project**

The following information is required to enable independent validation of the **customer's** cost estimates. This information must be provided, except if it does not apply to the **alternative project**.

##### **Capital cost (line)**

- (1) Conductor type, capital cost per metre, distance in metres and total estimated cost.
- (2) Type of structures (poles or lattice towers), number of structures, capital cost per structure and total estimated cost.
- (3) Type and number of insulators, capital cost per insulator and total estimated cost.
- (4) The capital cost of line fittings.

- (5) Any other capital costs of lines.

**Capital cost (substation)**

- (1) The type and number of transformers, the capital cost per unit and the total estimated cost.
- (2) The type and number of circuit breakers, the capital cost per unit and the total estimated cost.
- (3) The type and number of disconnectors, the capital cost per unit and the total estimated cost.
- (4) The type of protection and metering, the capital cost per unit and the total estimated cost.
- (5) The type and capital cost of buswork.
- (6) The type and capital cost of other infrastructure.
- (7) Any other miscellaneous substation costs.

**Labour cost**

- (1) Estimated labour costs.
- (2) Estimated design and project management costs.

**Cost of system losses**

The estimated cost of the electrical line losses that would result if the alternative were implemented, specifically:

- Estimated additional losses in MW/km.
- Estimated additional losses per annum in MWh.
- The estimated average price of energy in \$/MWh.
- Total estimated value of additional electrical losses per annum in dollars.

**The cost of easements and consents**

- (1) A topographical map of the line route in sufficient detail to verify estimates of the costs of easements and consents, or to verify that easements and consents are not required.
- (2) An estimate of consent costs.
- (3) An estimate of easements costs.
- (4) Estimate of property right costs.

**Part C: Commercial evaluation**

An analysis by the **customer** that provides a prima facie demonstration that the proposed **alternative project** would provide the **customer** with **Transpower** charges that would result in a lower overall commercial cost to the **customer** than the current **Transpower** charges, for the same or a similar level of service.

**Part D: Legal matters**

The implementation of some **alternative project** proposals will require the **customer** to enter into contractual agreements with third parties and to satisfy statutory requirements. In this

case, the **customer** must provide reasonable evidence that the **alternative project** would be able to be successfully implemented, including but not limited to—

- (1) a report from appropriately qualified planning, legal and property consultants that demonstrates that all consents required to implement the **alternative project** are either held, or are reasonably likely to be obtained; and
- (2) evidence of access, easement and other property rights required to implement the **alternative project**.

Compare: Electricity Governance Rules 2003 appendix C schedule F5 part F

Part A(4): amended, on 23 February 2015, by clause 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Part B(5): amended, on 1 February 2016, by clause 63 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

## Schedule 12.5 Availability and reliability index measures

cls 12.119 and 120

Asset type	Asset category		Planned unavailability	Unplanned unavailability	Number of planned interruptions	Planned unserved energy MWh	Number of unplanned interruptions	Unplanned unserved energy MWh
<b>Interconnection transformer branches</b>	220/110 kV interconnecting transformers and associated equipment		1.56%	0.06%	0.03	0.10	0.02	0.72
	220/066 kV interconnecting transformers and associated equipment		0.66%	0.02%	0.00	0.00	0.00	0.00
	110/066 kV interconnecting transformers and associated equipment		2.25%	0.02%	0.00	0.00	0.00	0.00
<b>Interconnection circuit branches</b>	220 kV interconnection circuit branches and associated line end equipment		0.88%	0.05%	0.00	0.00	0.13	9.87
	110 kV interconnection circuit branches and associated line end equipment		1.67%	0.07%	0.08	0.50	0.28	10.45
	66 kV interconnection circuit branches and associated line end equipment		1.25%	0.08%	0.14	0.46	1.31	1.88
<b>Shunt assets</b>	Capacitor banks and associated equipment	High (220kV – 66kV)	0.81%	1.33%	0.00	0.00	0.02	0.03
		Low (33kV – 11kV)	0.81%	1.33%	0.00	0.00	0.02	0.03

**Electricity Industry Participation Code 2010**  
**Schedule 12.5**

<b>Asset type</b>	<b>Asset category</b>	<b>Planned unavailability</b>	<b>Unplanned unavailability</b>	<b>Number of planned interruptions</b>	<b>Planned unserved energy MWh</b>	<b>Number of unplanned interruptions</b>	<b>Unplanned unserved energy MWh</b>
	Reactors and associated equipment	1.33%	0.31%	0.00	0.00	0.00	0.00
	Synchronous condensers and associated equipment	2.00%	1.00%	0.00	0.00	0.00	0.00
	Static var compensators and associated equipment	0.82%	0.04%	0.00	0.00	0.00	0.00
	Filter banks and associated equipment	1.03%	1.71%	0.00	0.00	0.00	0.00
<b>HVDC Link Pole 2</b>	One category including associated equipment	1.27%	0.51%	0.00	0.00	0.20	0.85

Compare: Electricity Governance Rules 2003 schedule F6A part F

# Electricity Industry Participation Code 2010

## Part 12A

### Distributor use-of-system agreements and distributor tariffs

#### Contents

- 12A.1 Contents of this Part
- Use-of-system agreements*
- 12A.2 Negotiating use-of-system agreements
- 12A.3 Mediation
- 12A.4 Prudential requirements
- 12A.4A Election of prudential requirements
- 12A.5 Requirements if distributors require additional security
- 12A.5A Agreement to less onerous terms
- 12A.6 *[Revoked]*
- Changes to tariff structures*
- 12A.7 Distributors must consult concerning changes to tariff structures
- Changes to tariff rates [Revoked]*
- 12A.8 Changes to tariff rates *[Revoked]*
- 12A.9 Requirement to comply with EIEP12 *[Revoked]*
- 12A.10 Requirement to use standard tariff codes *[Revoked]*
- Exchange of information*
- 12A.11 Application of clauses 12A.12 to 12A.14
- 12A.12 Distributor or trader may require provision of information
- 12A.13 Authority may prescribe EIEPs that must be used
- 12A.14 Distributors and traders must comply with EIEPs
- 12A.15 Authority may prescribe voluntary EIEPs
- 12A.16 Transitional provision relating to EIEPs

#### Schedule 12A.1

#### Distributor indemnity in use-of-system agreements *[Revoked]*

---

#### 12A.1 Contents of this Part

This Part—

- (a) specifies requirements that must be complied with in negotiating **use-of-system agreements**; and
- (b) specifies requirements that must be complied with if prudential requirements are included in **use-of-system agreements**; and
- (c) *[Revoked]*
- (d) requires that **distributors** who do not send accounts to **consumers** directly consult with **traders** about changes to the **distributor's** tariff structure; and
- (e) *[Revoked]*

(f) *[Revoked]*

(g) provides that the **Authority** may prescribe **EIEPs** that **distributors** and **traders** must comply with when exchanging information.

Clause 12A.1(c): revoked, on 1 February 2016, by clause 64 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

Clause 12A.1(e): revoked, on 16 December 2013, by clause 5(a) of the Electricity Industry Participation (Electricity Information Exchange Protocols) Code Amendment 2013

Clause 12A.1(f): revoked, on 21 October 2013, by clause 4 of the Electricity Industry Participation (Revocation of Standard Tariff Codes Requirement) Code Amendment 2013.

Clause 12A.1(g): inserted, on 16 December 2013, by clause 5(b) of the Electricity Industry Participation (Electricity Information Exchange Protocols) Code Amendment 2013.

Clause 12A.1(g): amended, on 5 October 2017, by clause 327 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### *Use-of-system agreements*

#### **12A.2 Negotiating use-of-system agreements**

(1) A **distributor** and a **trader** must negotiate the terms of a **use-of-system agreement** (including any amendment to a **use-of-system agreement**) in good faith.

(2) *[Revoked]*

Clause 12A.2(2): revoked, on 1 February 2016, by clause 65 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

#### **12A.3 Mediation**

(1) If a **distributor** or a **trader** considers that it is unlikely that it will agree the terms of a **use-of-system agreement** with the other party, the **distributor** or the **trader** may give written notice to the other party of that fact.

(2) The notice given under subclause (1) must—

(a) state that it is a notice given under subclause (1); and

(b) include a copy of subclause (1); and

(c) state that at the close of the 20th **business day** after the date of the notice, the **distributor** or **trader** (as the case may be) may require the other party to enter into mediation.

(3) No earlier than the close of the 20th **business day** after the date on which the notice referred to in subclause (2) is given, the **distributor** or the **trader** may, by written notice to the other party, require the other party to undertake mediation with the party who gave notice under this subclause.

(4) The notice given under subclause (3) must—

(a) state that it is a notice given under subclause (3); and

(b) include a copy of subclause (3).

(5) On receipt of a notice given under subclause (3), the **distributor** and the **trader** must attempt in good faith to agree on the following matters:

(a) the mediator:

(b) the date or dates for the mediation:

(c) the location of the mediation:

(d) the scope of the mediation:

(e) the allocation of the costs of the mediation.

- (6) If, at the close of the 15th **business day** after receipt of the notice given under subclause (3), the **distributor** and the **trader** are in dispute regarding 1 or more of the matters specified in subclause (5), either party may refer the dispute to the **Rulings Panel** for determination.
- (7) The **Rulings Panel** may make such determination as it thinks fit.
- (8) The **distributor** and the **trader** must carry out the mediation in accordance with any agreement reached under subclause (5) and any determination made under subclause (7).
- (9) *[Revoked]*

Clause 12A.3(9): revoked, on 1 February 2016, by clause 66 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

#### 12A.4 Prudential requirements

Clauses 12A.4A to 12A.5A apply in relation to a **use-of-system agreement** if—

- (a) the **distributor** party to the **use-of-system agreement** has 1 or more **consumers** connected to its **network** to whom the **distributor** does not send accounts for **line function services** directly; and
- (b) the **distributor's** charges for **line function services** are collected from **consumers** or paid by the **trader** party to the **use-of-system agreement** in accordance with the **use-of-system agreement**; and
- (c) the **distributor** requires that the **use-of-system agreement** provides that the **trader**—
  - (i) must comply with prudential requirements; or
  - (ii) must comply with prudential requirements if required to do so by the **distributor**.

Clause 12A.4: substituted, on 1 February 2016, by clause 67 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

#### 12A.4A Election of prudential requirements

- (1) Subject to clause 12A.5A, if a **use-of-system agreement** provides that the **trader** party to the **use-of-system agreement** must comply with prudential requirements, including if required to do so by the **distributor**, the **use-of-system agreement** must provide that the **trader** may elect to comply with the prudential requirements in either of the following ways:
  - (a) the **trader** must maintain an acceptable credit rating in accordance with subclause (3); or
  - (b) the **trader** must provide and maintain acceptable security by, at the **trader's** election,—
    - (i) providing the **distributor** with a cash deposit; or
    - (ii) arranging for a third party with an acceptable credit rating to provide that security in a form acceptable to the **distributor**; or
    - (iii) providing a combination of the securities described in subparagraphs (i) and (ii).
- (2) The **use-of-system agreement** must provide that the **trader** may change its election at any time.
- (3) For the purposes of this clause, a **trader** or third party has an acceptable credit rating if it—



- (a) carries a long term credit rating of at least—
    - (i) BBB- (Standard & Poors Rating Group); or
    - (ii) a rating that is equivalent to the rating specified in subparagraph (i) from a rating agency that is an approved rating agency for the purposes of Part 5D of the Reserve Bank of New Zealand Act 1989; and
  - (b) is not subject to negative credit watch or any similar arrangement by the agency that gave it the credit rating.
- (4) Subject to clause 12A.5, the value of the acceptable security described in subclause (1)(b) must be the **distributor's** reasonable estimate of the **line function services** charges that the **trader** will be required to pay to the **distributor** in respect of any period of not more than 2 weeks.
- (5) A **use-of-system agreement** must specify that, if the **trader** elects to provide acceptable security as described in subclause (1)(b), the **distributor** must—
- (a) hold any security provided by the **trader** in the form of a cash deposit in a trust account in the name of the **trader** at an interest rate that is the best on-call rate reasonably available at the time the **trader** provides the cash deposit; and
  - (b) pay interest earned in respect of the cash deposit to the **trader** on a quarterly basis, net of account fees and any amounts that are required to be withheld by law.

Clause 12A.4A: inserted, on 1 February 2016, by clause 68 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

#### 12A.5 Requirements if distributors require additional security

- (1) A **distributor** may require that its **use-of-system agreement** provides 1 or both of the following:
- (a) that if the **trader** elects to provide acceptable security as specified in clause 12A.4A(1)(b), the **trader** must provide acceptable security that is additional to the amount provided for in clause 12A.4A(4):
  - (b) that the **distributor** may, during the term of the **use-of-system agreement**, require the **trader** to provide such additional security.
- (2) If a **use-of-system agreement** has a provision provided for in subclause (1), the **distributor** must ensure that the total value of additional security specified in the **use-of-system agreement** must be such that the total value of all security required to be provided by the **trader** must not be more than the **distributor's** reasonable estimate of the **line function services** charges that the **trader** will be required to pay to the **distributor** in respect of any 2 month period.
- (3) If a **use-of-system agreement** has a provision provided for in subclause (1), the **distributor** must ensure that the **use-of-system agreement** provides the following:
- (a) if any additional security provided by the **trader** is in the form of a cash deposit, the **distributor** must pay a charge to the **trader** for each day that the **distributor** holds the additional security at a per annum rate equal to the sum of the bank bill yield rate for that day plus 15% on the amount of additional security held on that day:
  - (b) if any additional security provided by the **trader** is in the form of security from a third party, the **distributor** must pay a charge to the **trader** for each day that the **distributor** holds the additional security at a per annum rate of 3% on the amount of additional security held on that day:

- (c) any money required to be paid by the **distributor** to the **trader** as specified in paragraph (a) or (b) must be paid by the **distributor** to the **trader** on a quarterly basis.
- (4) For the purposes of this clause, the bank bill yield rate is—
  - (a) the daily bank bill yield rate (rounded upwards to 2 decimal places) published on the wholesale interest rates page of the website of the Reserve Bank of New Zealand (or its successor or equivalent page) on that day as being the daily bank bill yield for bank bills having a tenor of 90 days; or
  - (b) for any day for which such a rate is not available, the bank bill yield rate is deemed to be the bank bill yield rate determined in accordance with paragraph (a) on the last day that such a rate was available.

Clause 12A.5(1)(a): amended, on 1 February 2016, by clause 69(1)(a) and (b) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

Clause 12A.5(1)(b): amended, on 1 February 2016, by clause 69(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

Clause 12A.5(3)(c): amended, on 1 February 2016, by clause 69(3) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

### 12A.5A Agreement to less onerous terms

Despite clause 12A.4A, a **distributor** and a **trader** may agree prudential requirements that are less onerous on the **trader** than the requirements described in clauses 12A.4 to 12A.5.

Clause 12A.5A: inserted, on 1 February 2016, by clause 70 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

### 12A.6 Distributor indemnity [*Revoked*]

Clause 12A.6: revoked, on 1 February 2016, by clause 71 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

## *Changes to tariff structures*

### 12A.7 Distributors must consult concerning changes to tariff structures

- (1) This clause applies to each **distributor** who has 1 or more **consumers** connected to its **network** to whom the **distributor** does not send accounts for **line function services** directly.
- (2) The **distributor** must consult with each **trader** trading on the **distributor's network** in respect of the **distributor's** tariff structure for the **consumers** referred to in subclause (1) before making a change to the tariff structure that materially affects 1 or more **traders** or **consumers**.
- (3) For the purpose of subclause (2), changes to a **distributor's** tariff structure that may materially affect 1 or more **traders** or **consumers** include, but are not limited to, any of the following:
  - (a) a change by the **distributor** to the eligibility criteria for 1 or more of the **distributor's** tariff rates;
  - (b) a change by the **distributor** to the **distributor's** tariff structure by the introduction of a new tariff rate;

- (c) a change by the **distributor** to the **distributor's** tariff structure that means that 1 or more of the **distributor's** tariff rates are no longer available.
- (4) However, the fact that a change is listed in subclause (3) does not mean that a **distributor** is required to consult on the change if the change will not materially affect **traders or consumers**.
- (5) *[Revoked]*

Clause 12A.7(1): amended, on 23 February 2015, by clause 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 12A.7(1): amended, on 5 October 2017, by clause 328 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 12A.7(5): revoked, on 1 February 2016, by clause 72 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

*[Revoked]*

Changes to tariff rates cross heading: revoked, on 16 December 2013, by clause 6(1) of the Electricity Industry Participation (Electricity Information Exchange Protocols) Code Amendment 2013.

### **12A.8 Changes to tariff rates** *[Revoked]*

Clause 12A.8(1): amended, on 21 October 2013, by clause 5(a) of the Electricity Industry Participation (Revocation of Standard Tariff Codes Requirement) Code Amendment 2013.

Clause 12A.8(2): revoked, on 21 October 2013, by clause 5(b) of the Electricity Industry Participation (Revocation of Standard Tariff Codes Requirement) Code Amendment 2013.

Clause 12A.8: revoked, on 16 December 2013, by clause 6(2) of the Electricity Industry Participation (Electricity Information Exchange Protocols) Code Amendment 2013.

### **12A.9 Requirement to comply with EIEP12** *[Revoked]*

Clause 12A.9: revoked, on 16 December 2013, by clause 6(2) of the Electricity Industry Participation (Electricity Information Exchange Protocols) Code Amendment 2013.

### **12A.10 Requirement to use standard tariff codes** *[Revoked]*

Clause 12A.10: revoked, on 21 October 2013, by clause 6 of the Electricity Industry Participation (Revocation of Standard Tariff Codes Requirement) Code Amendment 2013.

### *Exchange of information*

Cross heading: inserted, on 16 December 2013, by clause 7 of the Electricity Industry Participation (Electricity Information Exchange Protocols) Code Amendment 2013.

### **12A.11 Application of clauses 12A.12 to 12A.14**

Clauses 12A.12 to 12A.14 apply to —

- (a) a **distributor** who has 1 or more **consumers** connected to its **network** to whom the **distributor** does not send accounts for **line function services** directly; and
- (b) a **trader** trading on the **network** of the **distributor** described in paragraph (a).

Clause 12A.11: inserted, on 16 December 2013, by clause 7 of the Electricity Industry Participation (Electricity Information Exchange Protocols) Code Amendment 2013.

Clause 12A.11(a): amended, on 23 February 2015, by clause 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 12A.11(a): amended, on 5 October 2017, by clause 329 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

#### 12A.12 Distributor or trader may require provision of information

- (1) The **distributor** may, by notice in writing, require the **trader** to provide information to the **distributor**, to enable the **distributor**—
  - (a) to invoice and reconcile charges for **line function services**; or
  - (b) to provide information to the **extended reserve manager**.
- (2) The **trader** may, by notice in writing, require the **distributor** to provide information to the **trader**, to enable the **trader** to invoice and reconcile charges for **line function services**.
- (3) A **trader** or **distributor** that receives a notice under subclause (1) or subclause (2) must provide the information within 15 **business days** (or such other date as agreed between the parties) after receiving the notice.
- (4) The **distributor** may use **volume information** to—
  - (a) enable invoicing and reconciling charges for **line function services**;
  - (b) enable the **distributor** to provide information to the **extended reserve manager**.
- (5) Nothing in this clause prevents the **distributor** and **trader** agreeing to provide **volume information** to each other for any other purpose.

Clause 12A.12: inserted, on 16 December 2013, by clause 7 of the Electricity Industry Participation (Electricity Information Exchange Protocols) Code Amendment 2013.

Clause 12A.12(1): replaced, on 19 January 2017, by clause 14(1) of the Electricity Industry Participation Code Amendment (Extended Reserve) 2016.

Clause 12A.12(4): replaced, on 19 January 2017, by clause 14(2) of the Electricity Industry Participation Code Amendment (Extended Reserve) 2016.

Clause 12A.12(5): inserted, on 19 January 2017, by clause 14(2) of the Electricity Industry Participation Code Amendment (Extended Reserve) 2016.

#### 12A.13 Authority may prescribe EIEPs that must be used

- (1) The **Authority** may **prescribe** 1 or more **EIEPs** that set out standard formats that **distributors** and **traders** must use when exchanging information.
- (1A) The **Authority** must **publish** an **EIEP** it prescribes under subclause (1).
- (2) When prescribing an **EIEP** under subclause (1), the **Authority** must specify the date on which the **EIEP** will come into effect.
- (3) The information to which an **EIEP** prescribed under subclause (1) may relate includes, but is not limited to, the following information:
  - (a) **ICP** level billing information;
  - (b) summary level billing information;
  - (c) **half hourly** billing information;
  - (d) **distributor** tariff rate change information.
- (4) Before the **Authority** prescribes an **EIEP** under subclause (1), or amends an **EIEP** it has prescribed under subclause (1), it must consult with the **participants** that the **Authority** considers are likely to be affected by the **EIEP**.
- (5) The **Authority** need not comply with subclause (4) if it proposes to amend an **EIEP** prescribed under subclause (1) if the **Authority** is satisfied that—
  - (a) the nature of the amendment is technical and non-controversial; or
  - (b) there has been adequate prior consultation so that the **Authority** has considered all relevant views.
- (6) *[Revoked]*

Heading: amended, on 5 October 2017, by clause 330(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 12A.13: inserted, on 16 December 2013, by clause 7 of the Electricity Industry Participation (Electricity Information Exchange Protocols) Code Amendment 2013.

Clause 12A.13(1): amended, on 5 October 2017, by clause 330(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 12A.13(1A): inserted, on 5 October 2017, by clause 330(3) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 12A.13(2): amended, on 1 February 2016, by clause 73(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

Clause 12A.13(2): amended, on 5 October 2017, by clause 330(4) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 12A.13(3), (4) and (5): amended, on 5 October 2017, by clause 330(5) and (6) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 12A.13(6): inserted, on 15 May 2014, by clause 36 of the Electricity Industry Participation (Minor Code Amendments) Code Amendment 2014.

Clause 12A.13(6): revoked, on 1 February 2016, by clause 73(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

#### **12A.14 Distributors and traders must comply with EIEPs**

- (1) If the **Authority** prescribes an **EIEP** under clause 12A.13, the **distributor** and the **trader** must, when exchanging information to which the **EIEP** relates, comply with the **EIEP** from the date on which the **EIEP** comes into effect.
- (2) *[Revoked]*
- (3) However, a **distributor** and a **trader** may, after the **Authority** prescribes an **EIEP**, agree to exchange information other than in accordance with the **EIEP**, by recording the agreement in each **use-of-system agreement** between the **distributor** and **trader**.
- (4) An agreement to exchange information other than in accordance with an **EIEP** is not effective in relieving a **distributor** and a **trader** of the obligation to comply with subclause (1), unless the agreement comes into effect on or after the date on which the relevant **EIEP** comes into effect.
- (5) An agreement under subclause (3) is not affected by the **Authority** prescribing an amendment to the **EIEP**.
- (6) Subclause (1) does not apply to an **EIEP** prescribed under clause 12A.15.

Clause 12A.14: inserted, on 16 December 2013, by clause 7 of the Electricity Industry Participation (Electricity Information Exchange Protocols) Code Amendment 2013.

Clause 12A.14(1): amended, on 1 February 2016, by clause 74(1)(a) and (b) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

Clause 12A.14(1): amended, on 5 October 2017, by clause 331(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 12A.14(2): revoked, on 1 February 2016, by clause 74(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

Clause 12A.14(3), (4), (5) and (6): inserted, on 1 February 2016, by clause 74(3) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

Clause 12A.14(3): amended, on 5 October 2017, by clause 331(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 12A.14(5): amended, on 5 October 2017, by clause 331(3) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 12A.14(6): amended, on 5 October 2017, by clause 331(4) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

#### **12A.15 Authority may prescribe voluntary EIEPs**

- (1) The **Authority** may prescribe 1 or more **EIEPs** that set out standard formats that **distributors** and **traders** may, but are not required to, use when exchanging information.
- (2) The **Authority** must **publish** an **EIEP** it prescribes under subclause (1)

Clause 12A.15 Heading: amended, on 5 October 2017, by clause 332(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 12A.15: inserted, on 16 December 2013, by clause 7 of the Electricity Industry Participation (Electricity Information Exchange Protocols) Code Amendment 2013.

Clause 12A.15 (1): amended, on 5 October 2017, by clause 332(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 12A.15(2): inserted, on 5 October 2017, by clause 332(3) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### **12A.16 Transitional provision relating to EIEPs**

- (1) This clause applies to any **EIEP** that a **distributor** or **trader** was required to comply with immediately before this clause came into force.
- (2) An **EIEP** to which this clause applies—
  - (a) is deemed to be an **EIEP** prescribed under clause 12A.13(1); and
  - (b) despite clause 12A.13(2), comes into effect on the date on which this clause comes into force.
- (3) The **Authority** need not comply with clause 12A.13(4) in respect of an **EIEP** to which this clause applies, unless the **Authority** proposes to amend the **EIEP**.
- (4) *[Revoked]*

Clause 12A.16: inserted, on 16 December 2013, by clause 7 of the Electricity Industry Participation (Electricity Information Exchange Protocols) Code Amendment 2013.

Clause 12A.16(2)(a): amended, on 5 October 2017, by clause 333 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 12A.16(4): revoked, on 1 February 2016, by clause 75 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

**Schedule 12A.1**

cl 12A.7

**Distributor indemnity in use-of-system agreements *[Revoked]***

Schedule 12A.1: revoked, on 1 February 2016, by clause 76 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

# Electricity Industry Participation Code 2010

## Part 13 Trading arrangements

### Contents

- 13.1 Contents of this Part
- 13.2 Misleading, deceptive, or incorrect information
- 13.2A Participant must make disclosure information readily available
- 13.3 Approval process for industrial co-generating stations
- 13.3A Approval process for dispatch-capable load stations
- 13.3B Purchasers to advise system operator of changes to dispatch-capable load station
- 13.3C System operator to publish dispatch-capable load station approval process guidelines
- Subpart 1—Bids and offers
- 13.4 Contents of this subpart
- 13.5 Bids and offers must be lawful
- 13.5A Conduct in relation to generators' offers and ancillary service agents' reserve offers
- 13.5B Safe harbours for clause 13.5A
- Bids and offer preparation*
- 13.6 Requirements for generators when submitting offers
- 13.7 Purchaser to submit bids for dispatch-capable load station
- 13.7AA Purchaser to submit bids for non-dispatch-capable load
- 13.7AB Timeframe for submitting bids to system operator
- 13.7AC Submitting bid for first time
- 13.7AD Submitting bid for last time
- 13.7A System operator to prepare forecast of non-dispatch-capable load at conforming GXP
- 13.7B Authority may request system operator to report on accuracy of forecasts of non-dispatch-capable load at conforming GXP
- 13.8 Deemed offers
- 13.8A Deemed nominated bids
- 13.8B Deemed reserve offers
- 13.9 Information that offers must contain
- 13.9A Offer not to exceed capability
- 13.10 Generators must specify units in offers
- 13.11 Offers may be made by unit or plant
- 13.12 Offers may contain up to 5 price bands
- 13.13 Information to be contained in bids
- 13.14 Nominated bids may contain up to 10 price bands
- 13.14A Difference bids may contain up to 10 price bands
- 13.15 How price is to be specified in bids or offers
- 13.16 How quantity is to be specified in bids or offers
- 13.17 Offers may be revised
- 13.18 When revised offer to be submitted
- 13.18A Intermittent generators to submit revised offers
- 13.19 When revised offers may be submitted during gate closure period



- 13.19AA Limitations on revised offers
- 13.19A Bids may be revised
- 13.19B Bids must be revised
- 13.20 System operator advised of revised nominated bids or offers in certain circumstances
- 13.21 Authority informed of revised nominated dispatch bid or offer during gate closure period
- 13.22 Transmission of information
- 13.23 Backup procedures if WITS is unavailable
- 13.24 Plant with special circumstances
- 13.25 Exception for small generation
- 13.26 Exception for embedded generation
- 13.27 System operator to retain bids and offers
- Process for determining conforming and non-conforming grid exit points*
- 13.27A Authority determines conforming and non-conforming GXPs on own initiative
- 13.27B Authority to determine conforming and non-conforming GXPs if requested
- 13.27C Process for making determination
- 13.27D System operator to provide advice within reasonable time
- 13.27E Authority may publish criteria for determining GXP to be non-conforming
- 13.27F GXP deemed to be conforming GXP before determination is made
- 13.27G Authority must publish and maintain list of non-conforming and conforming GXPs
- 13.27H Right to request determination or reconsideration of determination
- 13.27I Effect of determination
- 13.27J New GXPs
- 13.27K Authority to provide information at purchaser's request
- Special treatment of some grid exit points*
- 13.28 Special treatment of some grid exit points
- 13.29 Standing data on grid capability to be provided to system operator
- 13.30 Standing data on HVDC capability to be provided to system operator
- 13.31 Standing data on transformer capability to be provided to system operator
- 13.32 Transmission grid capability information to be updated
- 13.33 Grid owners must submit revised information to system operator
- 13.34 Changes may be made within 1 hour before trading period
- 13.35 System operator to confirm receipt of grid owner information
- 13.36 *[Revoked]*
- Offering instantaneous reserve*
- 13.37 System operator to approve ancillary service agents wishing to make reserve offers
- 13.38 Ancillary service agents to submit reserve offers to system operator
- 13.39 Inter-relationship between reserve and energy offers
- 13.40 Inter-relationship between reserve offers of interruptible load and bids
- 13.41 Reserve offers may contain up to 3 price bands
- 13.42 How price to be specified in reserve offers
- 13.43 *[Revoked]*
- 13.44 How quantity is to be specified in reserve offers
- 13.45 Reserve offers revised if energy offers revised
- 13.46 Reserve offers may be revised
- 13.47 MW change during gate closure period

- 13.48 System operator advised of revised reserve offers in certain circumstances
- 13.49 Authority advised of revised reserve offer during gate closure period
- 13.50 System operator to advise Authority of revision of reserve offers
- 13.51 Transmission of reserve offers
- 13.52 Backup procedures if WITS is unavailable
- 13.53 Additional information to be provided by participants
- 13.54 System operator to retain reserve offers
- 13.55 Availability of bids, offers, and reserve offers
- 13.55A System operator to make information available

Subpart 2—Scheduling and dispatch

- 13.56 Contents of this subpart
- 13.57 The dispatch objective
- 13.58 Process for preparing price-responsive schedule and non-response schedule
- 13.58A Inputs for price-responsive schedule and non-response schedule
- 13.59 Contents of each price-responsive schedule and non-response schedule
- 13.60 Block dispatch may occur
- 13.61 System operator to give notice of block security constraints
- 13.62 Frequency of price-responsive schedules and non-response schedules
- 13.63 Trading period information to be made available to pricing manager and clearing manager
- 13.64 Station dispatch may occur
- 13.65 System operator to give notice of station security constraints
- 13.66 Generator gives written notice of change from station to unit dispatch
- 13.67 Transmission of information

*The dispatch process*

- 13.68 Receipt of new non-response schedule supersedes old schedule *[Revoked]*
- 13.69 System operator may adjust dispatch schedule *[Revoked]*
- 13.69A System operator to prepare dispatch schedule
- 13.70 System operator may depart from dispatch schedule
- 13.71 System operator to use certain things
- 13.72 System operator to issue dispatch instructions
- 13.73 Content of dispatch instructions to generators, ancillary service agents, and dispatchable load purchasers
- 13.74 Content of dispatch instructions to reserve, interruptible load, and frequency keeping suppliers *[Revoked]*
- 13.75 Form of dispatch instruction
- 13.76 System operator to issue and log dispatch instructions
- 13.77 Dispatch instructions to plant required by system operator *[Revoked]*
- 13.78 Active power dispatch instructions to clearing manager *[Revoked]*
- 13.79 Acknowledgement of dispatch instructions
- 13.80 Dispatch instructions provided to grid owner
- 13.81 Backup procedures if communication not possible
- 13.82 Dispatch instructions to be complied with
- 13.83 Generators to make staff or facilities available to meet dispatch instructions
- 13.83A Dispatchable load purchasers to make staff or facilities available to meet dispatch instructions
- 13.84 Ancillary service agents to make staff or facilities available to meet dispatch

- instructions
- 13.85 Generators have flexibility within block dispatch group or station dispatch group
- 13.86 Generators and ancillary service agents not obliged to comply with dispatch instructions below threshold
- 13.87 *[Revoked]*

*Real time prices*

- 13.88 Preparation of schedule of real time prices
- 13.89 Publication of schedule of real time prices
- 13.90 Process for making real time prices available
- 13.91 System operator to use backup procedures if WITS unavailable
- 13.92 Transmission of information through publicly accessible approved system
- 13.93 Authority to appoint person to monitor and assess demand side participation and real time prices
- 13.94 System operator may suspend publication of real time prices
- 13.95 Real time prices not binding
- 13.96 Purchaser to co-operate with system operator to manage response to real time prices

*Grid emergencies*

- 13.97 Grid emergency situations
- 13.98 Generators and ancillary service agents may change other parameters
- 13.99 Effect of grid emergency on total quantities bid
- 13.99A Effect of grid emergency on nominated dispatch bids
- 13.100 Purchasers may change other parameters
- 13.101 Reporting requirements in respect of grid emergencies
- 13.102 Reporting obligations of system operator

*System operator to publish information*

- 13.103 *[Revoked]*
- 13.104 System operator to make information available
- 13.105 *[Revoked]*
- 13.105A Information to be made available to purchasers, generators, and ancillary service agents
- 13.106 Transmission of information

*Subpart 3—Must-run dispatch auction*

- 13.107 Contents of this subpart
- 13.108 Clearing manager to hold must-run dispatch auctions
- 13.109 Clearing manager authorises generators
- 13.110 Clearing manager must calculate amounts owing
- 13.111 Purchasers must receive auction revenue
- 13.112 Clearing manager must calculate amounts receivable
- 13.113 Generators choose grid injection points at which they will exercise rights conferred
- 13.114 Transmission of auction information
- 13.115 Trading in auction rights permitted
- 13.116 Offers at 0

*Must-run auction process*

- 13.117 Clearing manager must conduct auctions
- 13.118 *[Revoked]*

- 13.119 Historic load data
- 13.120 Quantity available for auction
- 13.121 Notice of auction and deadline for auction bids
- 13.122 Revising, cancelling and extending auction bids
- 13.123 Contents of auction bids
- 13.124 Ranking of auction bids
- 13.125 Matching auction bids to rights
- 13.126 Similar and identical auction bids
- 13.127 Auction payment
- 13.128 Results
- 13.129 Authorisation to successful bidders
- 13.130 Records

Subpart 4—Pricing

- 13.131 Contents of this subpart
- 13.132 Purpose of the pricing process
- 13.133 Trigger ratio for high spring washer price situation
- 13.134 Methodology to resolve high spring washer price situation
  - Rules governing the preparation of provisional, interim, and final prices*
  - 13.135 Methodology used to prepare provisional, interim, and final prices
  - 13.135A Notice of scarcity pricing situation
  - 13.135B Methodology to prepare interim prices and interim reserve prices if scarcity pricing situation exists
  - 13.135C Limitation on application of scarcity pricing provisions
    - Generators to give grid owner half-hour metering information*
  - 13.136 Generators to provide half-hour metering information
  - 13.137 Generators to provide half-hour metering information for unoffered and intermittent generation, and type B industrial co-generation
  - 13.138 Generator's half-hour metering information to be adjusted for losses
  - 13.138A Dispatchable load purchaser's half-hour metering information to be adjusted for losses
  - 13.138B System operator to give list of trading periods
  - 13.139 Half-hour metering information part of input information
  - 13.140 Generators and dispatchable load purchasers to advise grid owner of having provided half-hour metering information
  - 13.141 Pricing manager to use certain input information
  - 13.142 Pricing manager to make interim prices available unless notice is given of provisional price situation or shortage situation
  - 13.143 Grid owners to give written notice of SCADA situation
  - 13.144 Pricing manager to give written notice of infeasibility situation, metering situation, high spring washer price situation, or shortage situation
  - 13.145 Grid owner to give written notice that estimated data given
  - 13.146 Requirements if provisional price situation or shortage situation exists
  - 13.147 Revised data to be accompanied by written notice
  - 13.148 Failure to give revised data and notice not breach
  - 13.149 Pricing manager to make provisional prices and provisional reserve prices available if revised data and notice not given regarding provisional pricing situation arising on business day

- 13.150 Pricing manager to make provisional prices and provisional reserve prices available if revised data and notice not given regarding provisional price situation arising on day other than business day
- 13.151 Data to be used by pricing manager to determine provisional prices and provisional reserve prices
- 13.152 Pricing manager to make interim prices and interim reserve prices available if revised data resolves provisional price situation
- 13.153 Revised data gives rise to provisional price situation
- 13.154 Grid owner, generators, dispatchable load purchasers, and system operator to give revised data if provisional prices and provisional reserve prices have been made available
- 13.155 Revised data to be accompanied by written notice
- 13.156 Pricing manager to make interim prices available after provisional prices and provisional reserve prices are made available unless further provisional price situation arises
- 13.157 Requirements if infeasibility situation or high spring washer price situation exists
- 13.158 Revised data to be accompanied by written notice
- 13.159 Pricing manager to make interim prices available or give written notice that high spring washer price situation exists
- 13.160 Prohibition on notice of high spring washer price situation
- 13.161 System operator to apply high spring washer price relaxation factor and give notice
- 13.162 Pricing manager to make interim prices available
- 13.163 Revised data cannot be given or revised data gives rise to provisional price situation (other than high spring washer price situation)
- 13.164 If provisional price situation (other than high spring washer price situation) continues
- 13.165 System operator or grid owner to give written notice to Authority if provisional price situation not resolved
- 13.166 Generator, grid owner, or dispatchable load purchaser to give revised metering information following initial estimate
- 13.166A Pricing manager to recalculate and make interim prices available if infeasibility situation caused by shortage of instantaneous reserve
- Interim pricing period*
- 13.167 Pricing manager to make interim prices available
- 13.168 When pricing error may be claimed
- 13.169 Error claimant materially affected by pricing error
- 13.170 Method and timing for claiming pricing error has occurred
- 13.171 Pricing manager must make final prices available if no pricing error claimed
- 13.172 Effect of pricing error being claimed
- 13.173 Process when pricing error claimed
- 13.174 Recommendation to Authority
- 13.175 Authority to accept or reject recommendations
- 13.176 Pricing manager to give written notice
- 13.177 Pricing manager to implement Authority's decision
- 13.178 Effect of making recalculated interim prices available
- 13.179 Timing for resolution of pricing error claim process
- 13.180 Actions Authority may take to resolve pricing error
- 13.181 Obligation to comply with pricing manager

- 13.182 No pricing errors may be claimed after final prices calculated  
*Making final prices available*
- 13.183 Pricing manager must not make recalculated final prices available
- 13.184 Authority may order delay in making final prices available
- 13.185 Final prices for more than 1 trading day  
*Miscellaneous requirements relating to calculation of prices*
- 13.186 Revised data for more than 1 trading day
- 13.187 Daylight saving to be observed
- 13.188 Reconciliation manager to publish annual consumption list
- 13.189 System operator to give pricing manager and Authority list of model variable values
- 13.189A Pricing manager to give clearing manager information about dispatch-capable load station from schedule of final prices
- 13.190 All information and notices to be unconditional and final
- 13.191 Backup procedures if WITS or approved system is unavailable  
*Calculation of constrained off amounts*
- 13.192 Constrained off situations may occur
- 13.193 Determining affected price bands for block dispatch groups and station dispatch groups
- 13.194 Clearing manager to calculate constrained off amounts
- 13.195 Constrained off amount for block dispatch groups and station dispatch groups
- 13.196 Calculation of constrained off amounts attributable to system operator
- 13.197 Calculation of constrained off amounts
- 13.198 Clearing manager to send constrained off information to system operator
- 13.199 Clearing manager to make details of constrained off amounts available
- 13.200 Authority, generators and purchasers have rights to constrained off information
- 13.201 Generators do not get paid constrained off compensation
- 13.201A Dispatched purchasers entitled to constrained off compensation and purchasers to pay constrained off compensation  
*Calculation of constrained on amounts*
- 13.202 Constrained on situations may occur
- 13.203 Determining affected price bands for block dispatch groups or station dispatch groups
- 13.204 Calculation of constrained on amounts
- 13.205 Calculation of constrained on amounts attributable to system operator
- 13.206 Timeframe for calculating constrained on amounts
- 13.207 Clearing manager to send constrained on information to system operator
- 13.208 Clearing manager to make details of constrained on amounts available
- 13.209 Authority, generators, ancillary service agents, and purchasers have rights to constrained on information
- 13.210 *[Revoked]*
- 13.211 Backup procedures if WITS is unavailable
- 13.212 Payment of constrained on compensation  
*No payment of constrained on and off compensation for frequency keeping*
- 13.212A No payment of constrained on and off compensation for frequency keeping  
*Pricing manager's reporting obligations*

- 13.213 Daily reports
- 13.214 Authority to publish pricing manager reports
- 13.215 Generators and purchasers have right to information concerning pricing manager's action
- 13.216 Daily situation report

Subpart 5—Hedge arrangement disclosure

- 13.217 Contents of this subpart
- 13.218 Parties required to submit information
- 13.219 Information that must be submitted
- 13.220 Calculation of contract price
- 13.221 Node and grid zone area information
- 13.222 Other information that must be submitted
- 13.223 Modified or amended information
- 13.224 Correction of information
- 13.225 Timeframes for submitting information
- 13.226 WITS manager must make certain information available to the public
- 13.227 Verification of information
- 13.228 Confirmation of information submitted through approved system
- 13.229 Submitting party to check if no confirmation received
- 13.230 Certification of information
- 13.231 Audit of information
- 13.232 Payment of costs relating to audits
- 13.233 WITS manager and Authority must not publish certain information and may use information only under this subpart
- 13.234 No misleading information
- 13.235 Risk management contracts must be lawful
- 13.236 Availability of information

Subpart 5A—Spot price risk disclosure

- 13.236A Disclosing participants must prepare and submit spot price risk disclosure statements
- 13.236B Authority must appoint a person to receive and analyse spot price risk disclosure statements
- 13.236C Authority may approve consolidated spot price risk disclosure statements
- 13.236D Authority must publish base case, stress test, and method for calculating target cover ratio
- 13.236E Content of spot price risk disclosure statements
- 13.236F Certification of spot price risk disclosure statement
- 13.236G Authority may require disclosing participant to submit new spot price risk disclosure statement
- 13.236H Authority may require independent audit of spot price risk disclosure statement or certification
- 13.236I Payment of auditor's costs

Subpart 6—Financial transmission rights

- 13.237 Contents of this subpart
- FTR allocation plan*
- 13.238 Preparation and publication of FTR allocation plan

- 13.239 FTR manager gives draft FTR allocation plan to Authority  
13.240 Authority approves FTR allocation plan  
13.241 Variations to FTR allocation plan  
*Allocation, creation and reconfiguration of FTRs*
- 13.242 FTR manager must allocate and create FTRs  
13.242A FTR manager to adjust offered FTR and FTR acquisition cost after FTR reconfiguration auction  
13.243 Participation in FTR auction  
13.244 Acceptance of bids and offers in FTR auction  
*Auction revenue and FTR receipts and payments*
- 13.245 Clearing manager must collect and allocate auction revenue  
13.246 Clearing manager must deal with FTR receipts and payments  
*FTR register*
- 13.247 FTR manager must operate FTR register  
*Assignment of FTRs*
- 13.248 Assignment of FTRs  
13.249 Liability for FTR payments when FTR assigned and price disclosed  
13.250 Liability for FTR payments when FTR assigned and price not disclosed  
*Provision of information to the FTR manager and clearing manager*
- 13.251 Information to be provided to FTR manager  
13.252 Information to be provided to clearing manager  
13.253 *[Revoked]*  
13.254 Publication of results of FTR auctions  
*Suspension of FTR allocation*
- 13.255 Authority may direct FTR manager to suspend allocation of FTRs

**Schedule 13.1**

**Forms 1 to 9**

**Schedule 13.2**

**Model parameters**

**Schedule 13.3**

**The Modelling System**

*Inputs into the modelling system*

*Inputs used at each stage*

*The objective function*

**Schedule 13.3A**

**Calculation of interim prices and interim reserve prices in scarcity pricing situation**

**Schedule 13.4**

**Approval as type A or type B industrial co-generating station**

**Schedule 13.5**

**Requirements for FTR allocation plan**

**Schedule 13.6**

**Assignment of FTR**



**Schedule 13.7**  
**Methodology for Determining Conforming and Non-Conforming GXPs**  
**Schedule 13.8**  
**Approval of dispatch-capable load station**

---

**13.1 Contents of this Part**

This Part provides for processes by which—

- (a) **purchasers and generators** submit and revise **bids and offers for electricity**, **grid owners** submit and revise information, **ancillary service agents** submit and revise **reserve offers**, the **system operator** forecasts **demand** at **conforming GXPs**, and the **system operator** collects information to enable schedules to be prepared; and
- (b) the **system operator** prepares and **publishes** information from the **price-responsive schedules, non-response schedules, dispatch schedules, and real time price** schedules, and formulates and issues **dispatch instructions**; and
- (c) the **clearing manager** holds must-run dispatch **auctions**; and
- (d) the **pricing manager** collects data and produces **provisional prices, interim prices, and final prices**; and
- (da) the **Authority** determines whether each **GXP** is either a **conforming GXP** or a **non-conforming GXP**; and
- (db) the **clearing manager** calculates **constrained off amounts and constrained on amounts**; and
- (e) **generators** may apply to the **Authority** to have 1 or more **generating units** approved as—
  - (i) a **type A industrial co-generating station**; or
  - (ii) a **type B industrial co-generating station**; and
- (f) information about **risk management contracts** is disclosed; and
- (fa) **disclosing participants** prepare and submit **spot price risk disclosure statements**; and
- (g) the **FTR manager** prepares and **publishes** the **FTR allocation plan**, creates and allocates **FTRs**, and operates the **FTR register**; and
- (h) the **clearing manager** collects and allocates **FTR auction** revenue; and
- (i) information about **FTRs** is provided; and
- (j) a device or a group of devices may be approved to be a **dispatch-capable load station**.

Compare: Electricity Governance Rules 2003 rule 1 section I part G

Clause 13.1(a) and (b): substituted, on 28 June 2012, by clause 5(a) of the Electricity Industry Participation (Demand-side Bidding and Forecasting) Code Amendment 2011.

Clause 13.1(da): inserted, on 28 June 2012, by clause 5(b) of the Electricity Industry Participation (Demand-side Bidding and Forecasting) Code Amendment 2011.

Clause 13.1(db) and (fa): inserted, on 15 May 2014, by clause 37 of the Electricity Industry Participation (Minor Code Amendments) Code Amendment 2014.

Clause 13.1(e): substituted, on 27 May 2015, by clause 5 of the Electricity Industry Participation Code Amendment (Industrial Co-generation Dispatch Arrangements) 2015.

Clause 13.1(g)-(i): inserted, on 1 October 2011, by clause 7 of the Electricity Industry Participation (Financial Transmission Rights) Code Amendment 2011.

Clause 13.1(j): inserted, on 15 May 2014, by clause 6 of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

### 13.2 Misleading, deceptive, or incorrect information

- (1) A **participant** must not disclose to any person any information under this Part that, at the time the information was disclosed, was misleading or deceptive or likely to mislead or deceive when taken in the context of activities under this Part.
- (1A) In assessing whether information, at the time of disclosure, is misleading or deceptive or is likely to mislead or deceive, a **participant** must act reasonably and prudently.
- (2) If a **participant** discovers that information previously disclosed by it to a person under this Part was misleading, deceptive or incorrect, the **participant** must immediately—
  - (a) disclose further information so that the person is not misled or deceived by the information; or
  - (b) disclose corrected information to the person.

Clause 13.2: substituted, on 1 October 2013, by clause 5 of the Electricity Industry Participation (Disclosure Obligations) Code Amendment 2013.

### 13.2A Participant must make disclosure information readily available

- (1) Each **participant** must make all **disclosure information** in relation to the **participant** readily available to the public, free of charge, as soon as reasonably practicable after the **participant** becomes aware of the information.
- (2) Despite subclause (1), a **participant** is not required to make **disclosure information** readily available to the public if—
  - (a) the **disclosure information** is **excluded Code information**; or
  - (b) doing so will commercially disadvantage the participant in a material manner; or
  - (c) the **participant** is bound by a legal obligation to keep the **disclosure information** confidential; or
  - (d) doing so will be a breach of law; or
  - (e) the **disclosure information** is already readily available to the public; or
  - (f) the **disclosure information** concerns an incomplete proposal or negotiation; or
  - (g) the **disclosure information** comprises matters of supposition or is insufficiently definite to warrant being made readily available to the public; or
  - (h) the **participant** claims legal professional privilege or privilege against self-incrimination in respect of the **disclosure information**; or
  - (i) the **disclosure information** is a trade secret.
- (3) A **participant** that relies on subclause (2) must, as soon as reasonably practicable, make the **disclosure information** readily available to the public, free of charge, if subclause (2) ceases to apply to the **disclosure information**.
- (4) If information ceases to be **disclosure information**, a **participant** is no longer required to make the information readily available to the public.
- (5) A **participant** that does not make information readily available to the public under this clause must, if required to do so by the **Authority**,—
  - (a) satisfy the **Authority** that subclause (2) applies to the **disclosure information**, if the participant relies on subclause (2); or
  - (b) satisfy the **Authority** that the information is not **disclosure information**.
- (6) A **participant** must not enter into a confidentiality agreement with another person for the purpose of avoiding making **disclosure information** readily available to the public under this clause.

Clause 13.2A: inserted, on 1 October 2013, by clause 6 of the Electricity Industry Participation (Disclosure Obligations) Code Amendment 2013.

### 13.3 Approval process for industrial co-generating stations

A **generator** may apply to the **Authority** to have 1 or more **generating units** approved as—

- (a) a **type A industrial co-generating station** under clause 8(1)(a)(i) of Schedule 13.4; or
- (b) a **type B industrial co-generating station** under clause 8(1)(a)(ii) of Schedule 13.4.

Compare: Electricity Governance Rules 2003 rule 3 section I part G

Clause 13.3: substituted, on 27 May 2015, by clause 6 of the Electricity Industry Participation Code Amendment (Industrial Co-generation Dispatch Arrangements) 2015.

#### 13.3A Approval process for dispatch-capable load stations

- (1) A **purchaser** at a **GXP** may apply to the **system operator** for approval for a device or a group of devices at the **GXP** to be a **dispatch-capable load station** under Schedule 13.8.
- (2) The **system operator** must consider the application in accordance with Schedule 13.8.
- (3) If the **system operator** approves a device or a group of devices as a **dispatch-capable load station**,—
  - (a) the approval is valid until the date the approval is revoked under clause 10 of Schedule 13.8; but
  - (b) a device or group of devices in respect of which the approval is granted is not a **dispatch-capable load station** while its approval is suspended under clause 10 of Schedule 13.8.

Clause 13.3A: inserted, on 15 May 2014, by clause 7 of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

#### 13.3B Purchasers to advise system operator of changes to dispatch-capable load station

- (1) A **purchaser** to which a **dispatch-capable load station** approval is granted must advise the **system operator** of any change to the factors the **system operator** considered in granting approval, including an intended change of the **dispatchable load purchaser**.
- (2) A **purchaser** must advise the **system operator** of the change no later than 10 **business days** before the change takes effect.
- (3) The **system operator** must consider the change advised and decide whether—
  - (a) to amend the approval under clause 10 of Schedule 13.8; or
  - (b) to revoke the approval under clause 10 of Schedule 13.8; or
  - (c) to suspend the approval under clause 10 of Schedule 13.8.

Clause 13.3B Heading: replaced, on 5 October 2017, by clause 334 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 13.3B: inserted, on 15 May 2014, by clause 7 of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

#### 13.3C System operator to publish dispatch-capable load station approval process guidelines

- (1) The **system operator** must **publish** guidelines for the purpose of assisting **purchasers** to obtain approval under clause 13.3A.
- (2) Before **publishing** the guidelines under subclause (1), the **system operator** must consult with **participants** on the guidelines.

- (3) To avoid doubt, consultation undertaken before the commencement of this clause is to be treated as the consultation required for the purpose of subclause (2).

Clause 13.3C: inserted, on 15 May 2014, by clause 7 of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

## Subpart 1—Bids and offers

### 13.4 Contents of this subpart

This subpart provides for processes to facilitate **trading** by which—

- (a) **bids and offers** for **electricity** are submitted and revised by **generators** and **purchasers**; and
- (b) information from the **grid owners** is submitted and revised; and
- (c) **reserve offers** are submitted and revised by **ancillary service agents**; and
- (d) the **system operator** collects the information referred to in this subpart; and
- (e) information about **bids and offers** is to be made available.

Compare: Electricity Governance Rules 2003 rule 1 section II part G

### 13.5 Bids and offers must be lawful

A **purchaser**, **generator** or **ancillary service agent** must not make or maintain a **bid**, **offer** or **reserve offer** if the **purchaser** or **generator** or **ancillary service agent** knows or ought reasonably to know that acting in accordance with the **bid**, **offer** or **reserve offer** would contravene any law.

Compare: Electricity Governance Rules 2003 rule 2 section II part G

Clause 13.5: amended, on 28 June 2012, by clause 6 of the Electricity Industry Participation (Demand-side Bidding and Forecasting) Code Amendment 2011.

#### 13.5A Conduct in relation to generators' offers and ancillary service agents' reserve offers

- (1) Each **generator** and **ancillary service agent** must ensure that its conduct in relation to **offers** and **reserve offers** is consistent with a high standard of trading conduct.
- (2) Subclause (1) applies when—
  - (a) a **generator** submits or revises an **offer**; or
  - (b) an **ancillary service agent** submits or revises a **reserve offer**.

Clause 13.5A: inserted, on 17 July 2014, by clause 5 of the Electricity Industry Participation Code Amendment (Pivotal Supply) 2014.

Clause 13.5A(2): amended, on 29 June 2017, by clause 5 of the Electricity Industry Participation Code Amendment (Shortened Gate Closure and Revised Bid and Offer Provisions) 2017.

#### 13.5B Safe harbours for clause 13.5A

- (1) A **generator** complies with clause 13.5A if—
  - (a) the **generator** makes **offers** in respect of all of its generating capacity that is able to operate in a **trading period**; and
  - (b) when the **generator** decides to submit or revise an **offer**, it does so as soon as it can; and
  - (c) in the case of a **generator** that is **pivotal**,—
    - (i) prices and quantities in the **generator's offers** do not result in a material increase in the **final price** at which **electricity** is supplied in a **trading**

- period** at any **node** at which the **generator** is **pivotal**, compared with the **final price** at the **node** in an immediately preceding **trading period** or other comparable trading period in which the **generator** is not **pivotal** at that **node**; or
- (ii) the **generator's offers** are generally consistent with **offers** it has made when it has not been **pivotal**; or
  - (iii) the **generator** does not benefit financially from an increase in the **final price** at which **electricity** is supplied in a **trading period** at a **node** at which the **generator** is **pivotal**.
- (2) A **generator** does not breach clause 13.5A only because the **generator** does not comply with subclause (1).
- (3) An **ancillary service agent** complies with clause 13.5A if—
- (a) the **ancillary service agent** makes **reserve offers** in respect of all of its capacity to provide **instantaneous reserve** that is able to operate in a **trading period**; and
  - (b) when the **ancillary service agent** decides to submit or revise a **reserve offer**, it does so as soon as it can; and
  - (c) in the case of an **ancillary service agent** that is **pivotal**,—
    - (i) prices and quantities in the **ancillary service agent's reserve offers** do not result in a material increase in the **final reserve price** in a **trading period** in an **island** in which the **ancillary service agent** is **pivotal**, compared with the **final reserve price** in the **island** in an immediately preceding **trading period** or other comparable **trading period** in which the **ancillary service agent** is not **pivotal**; or
    - (ii) the **ancillary service agent's reserve offers** are generally consistent with **reserve offers** it has made when it has not been **pivotal**; or
    - (iii) the **ancillary service agent** does not benefit financially from an increase in the **final reserve price** in a **trading period** in an **island** in which the **ancillary service agent** is **pivotal**.
- (4) An **ancillary service agent** does not breach clause 13.5A only because the **ancillary service agent** does not comply with subclause (3).

Clause 13.5B: inserted, on 17 July 2014, by clause 5 of the Electricity Industry Participation Code Amendment (Pivotal Supply) 2014.

Clause 13.5B(1)(b) and (3)(b): amended, on 29 June 2017, by clause 6 of the Electricity Industry Participation Code Amendment (Shortened Gate Closure and Revised Bid and Offer Provisions) 2017.

### *Bids and offer preparation*

#### **13.6 Requirements for generators when submitting offers**

- (1) Each **generator** with a **point of connection** to the **grid**, and each **embedded generator** required by the **system operator** to submit an **offer** under clause 8.25(5), must—
- (a) submit to the **system operator** an **offer** for each **trading period** in the **schedule period**, under which the **generator** is prepared to sell **electricity** to the **clearing manager**; and
  - (b) ensure that the **system operator** receives an **offer** at least 71 **trading periods** before the beginning of the **trading period** to which the **offer** relates.

- (2) Despite subclause (1), a **generator** must give at least 5 **business days'** notice in writing to the **system operator** and the **pricing manager** before the **generator** makes an **offer** for the 1st time in respect of the **generating plant** that is the subject of the **offer**.
- (3) The notice must state—
  - (a) the **point of connection** to the **grid** at which **electricity** generated by the **generator** is sold to the **clearing manager** under clause 14.3 or 14.4; and
  - (b) whether the **generating plant** is an **intermittent generating station**.
- (4) A **generator** must comply with any request from the **system operator** for information concerning **generating plant** that is the subject of a notice under subclause (2) if the **system operator** requires the information for the purposes of scheduling and **dispatch** in accordance with this Code.
- (5) Despite subclause (1), if a **generator** intends to permanently cease to submit **offers** to the **system operator** in respect of any **generating plant**, the **generator** must give at least 5 **business days'** notice in writing to the **system operator**, the **pricing manager**, and the **clearing manager**.

Compare: Electricity Governance Rules 2003 rules 3.1 and 3.2 section II part G

Clause 13.6(1)-(3): substituted, on 28 June 2012, by clause 7 of the Electricity Industry Participation (Demand-side Bidding and Forecasting) Code Amendment 2011.

Clause 13.6(4): amended, on 23 February 2015, by clause 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 13.6: substituted, on 29 June 2017, by clause 7 of the Electricity Industry Participation Code Amendment (Shortened Gate Closure and Revised Bid and Offer Provisions) 2017.

### 13.7 Purchaser to submit bids for dispatch-capable load station

- (1) This clause applies to each **dispatchable load purchaser**.
- (2) Unless the **dispatchable load purchaser** relies on clause 13.8A, the **dispatchable load purchaser** must submit to the **system operator** for each of its **dispatch-capable load stations** for each **trading period** in the **schedule period**—
  - (a) a **nominated non-dispatch bid**; or
  - (b) a **nominated dispatch bid**.
- (3) A **nominated bid** submitted under subclause (2) must represent a reasonable estimate of the total quantity of **electricity** the **dispatchable load purchaser** will purchase—
  - (a) for the **dispatch-capable load station**; and
  - (b) for the **trading period**; and
  - (c) at the prices specified in the **nominated bid**.

Compare: Electricity Governance Rules 2003 rules 3.3 and 3.4 section II part G

Clause 13.7 Heading and (1): substituted, on 28 June 2012, by clause 8(1) of the Electricity Industry Participation (Demand-side Bidding and Forecasting) Code Amendment 2011.

Clause 13.7(1A) and (1B): inserted, on 28 June 2012, by clause 8(2) of the Electricity Industry Participation (Demand-side Bidding and Forecasting) Code Amendment 2011.

Clause 13.7(2): amended, on 28 June 2012, by clause 8(1) of the Electricity Industry Participation (Demand-side Bidding and Forecasting) Code Amendment 2011.

Clause 13.7: substituted, on 15 May 2014, by clause 8 of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

### 13.7AA Purchaser to submit bids for non-dispatch-capable load

- (1) This clause applies to each **purchaser** that—
  - (a) purchases **non-dispatch-capable load**; and
  - (b) in relation to a **nominated bid**, does not rely on clause 13.8A.
- (2) The **purchaser**—

- (a) must, if it purchases **non-dispatch-capable load** at a **non-conforming GXP**, submit to the **system operator** for each **trading period** in the **schedule period** a **nominated non-dispatch bid** that represents a reasonable estimate of the total **non-dispatch-capable load** that the **purchaser** will purchase—
  - (i) at the **GXP**; and
  - (ii) for the **trading period**; and
  - (iii) at the prices specified in the **nominated non-dispatch bid**; and
- (b) may, if it purchases **non-dispatch-capable load** at a **conforming GXP**, submit to the **system operator** for a **trading period** a **difference bid** that represents a reasonable estimate of an increase or decrease in the **purchaser's** usual **non-dispatch-capable load** purchased—
  - (i) at the **GXP**; and
  - (ii) for the **trading period**; and
  - (iii) at the prices specified in the **difference bid**.

Clause 13.7AA: inserted, on 15 May 2014, by clause 8 of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

#### **13.7AB Timeframe for submitting bids to system operator**

- (1) Each **purchaser** that submits a **nominated bid** to the **system operator** must submit the **nominated bid** at least 71 **trading periods** before the beginning of the **trading period** to which the **nominated bid** applies.
- (2) Each **purchaser** that submits a **difference bid** to the **system operator** must submit the **difference bid** at least 4 **trading periods** before the beginning of the **trading period** to which the **difference bid** applies.

Clause 13.7AB: inserted, on 15 May 2014, by clause 8 of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

#### **13.7AC Submitting bid for first time**

- (1) Despite anything in this Code, a **purchaser** must give at least 5 **business days'** notice in writing to the **system operator** and the **clearing manager** before the **purchaser** submits a **bid** for the first time.
- (2) The **system operator** may request from a **purchaser** information—
  - (a) about the **purchaser**; and
  - (b) that the **system operator** requires for the purposes of scheduling and **dispatch** in accordance with this Code.
- (3) A **purchaser** must comply with a request made under subclause (2).

Clause 13.7AC: inserted, on 15 May 2014, by clause 8 of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

#### **13.7AD Submitting bid for last time**

Despite anything in this Code, if a **purchaser** intends to permanently cease to provide **bids** to the **system operator**, the **purchaser** must give at least 5 **business days'** notice in writing to the **system operator**, the **pricing manager**, and the **clearing manager**.

Clause 13.7AD: inserted, on 29 June 2017, by clause 8 of the Electricity Industry Participation Code Amendment (Shortened Gate Closure and Revised Bid and Offer Provisions) 2017.

### **13.7A System operator to prepare forecast of non-dispatch-capable load at conforming GXP**

- (1) The **system operator** must prepare a forecast of **non-dispatch-capable load** for each **conforming GXP** for each **trading period** in a **schedule period**.
- (2) The **system operator** must—
  - (a) disclose to the **Authority** a description of the processes and methodology it uses to prepare the forecast under subclause (1); and
  - (b) **publish** and keep **published**, either—
    - (i) the description it disclosed to the **Authority** under paragraph (a); or
    - (ii) a summary of the processes and methodology it uses to prepare the forecast under subclause (1).
- (3) Despite subclause (2), the **system operator** is required to disclose or **publish** information under subclause (2) only if the information—
  - (a) is available to the **system operator**; and
  - (b) is not confidential or commercially sensitive.

Clause 13.7A: inserted, on 28 June 2012, by clause 9 of the Electricity Industry Participation (Demand-side Bidding and Forecasting) Code Amendment 2011.

Clause 13.7A Heading: amended, on 15 May 2014, by clause 9(a) of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

Clause 13.7A: amended, on 15 May 2014, by clause 9 of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

Clause 13.7A(2)(b): amended, on 5 October 2017, by clause 335(a) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 13.7A(3): amended, on 5 October 2017, by clause 335(b) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### **13.7B Authority may request system operator to report on accuracy of forecasts of non-dispatch-capable load at conforming GXPs**

- (1) The **Authority** may, from time to time, request the **system operator** to report to the **Authority** on the accuracy of the forecast that it prepares under clause 13.7A(1).
- (2) A request—
  - (a) must specify the period that must be covered by the report; and
  - (b) must specify a reasonable date by which the **system operator** must provide the report; and
  - (c) must be made no more frequently than once per calendar month, unless the **system operator** agrees otherwise.
- (3) The **system operator** must comply with a request made under this clause.

Clause 13.7B: inserted, on 28 June 2012, by clause 9 of the Electricity Industry Participation (Demand-side Bidding and Forecasting) Code Amendment 2011.

Clause 13.7B Heading: amended, on 15 May 2014, by clause 10(a) of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

Clause 13.7B(1): amended, on 15 May 2014, by clause 10(b) of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

## **13.8 Deemed offers**

- (1) This clause applies if, on any **trading day** ("the current **trading day**"), a **generator** has not submitted an **offer** for a **trading period** in the **trading day** following the next **trading day**.



- (2) A **generator** is deemed to have submitted, for that **trading period**, an **offer** that is the same as the **offer** the **generator** made for the corresponding **trading period** on the current **trading day**, and clause 13.9A applies accordingly.
- (3) A deemed **offer** under subclause (2) applies until the **generator** revises the **offer** in accordance with clauses 13.17 to 13.19.

Compare: Electricity Governance Rules 2003 rule 3.5 section II part G

Clause 13.8: substituted, on 28 June 2012, by clause 10 of the Electricity Industry Participation (Demand-side Bidding and Forecasting) Code Amendment 2011.

Clause 13.8(3): amended, on 15 May 2014, by clause 11 of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

Clause 13.8(2): amended, on 29 June 2017, by clause 9(1) of the Electricity Industry Participation Code Amendment (Shortened Gate Closure and Revised Bid and Offer Provisions) 2017.

Clause 13.8(3): amended, on 29 June 2017, by clause 9(2) of the Electricity Industry Participation Code Amendment (Shortened Gate Closure and Revised Bid and Offer Provisions) 2017

### 13.8A Deemed nominated bids

- (1) This clause applies if, on any **trading day** ("the current **trading day**"), a **purchaser** has not submitted a **nominated bid** for a **trading period** in the **trading day** following the next **trading day**.
- (2) A **purchaser** is deemed to have submitted, for that **trading period**, a **nominated bid** that is the same as the **nominated bid** the **purchaser** made for the corresponding **trading period** on the current **trading day**.
- (3) A deemed **nominated bid** under subclause (2) applies until the **purchaser** revises the **nominated bid** in accordance with clause 13.19A.
- (4) A **purchaser** must ensure that each of its deemed **nominated bids** under this clause,—
  - (a) if it is a **nominated bid** for a **dispatch-capable load station**, represents a reasonable estimate of the total quantity of **electricity** that the **purchaser** will purchase for the **dispatch-capable load station** at the specified prices for the **trading period**; or
  - (b) if it is a **nominated bid** for **non-dispatch-capable load**, represents a reasonable estimate of the **non-dispatch-capable load** that the **purchaser** will purchase at the **GXP** at the specified prices for the **trading period**.

Clause 13.8A: inserted, on 28 June 2012, by clause 10 of the Electricity Industry Participation (Demand-side Bidding and Forecasting) Code Amendment 2011.

Clause 13.8A(2) & (3): amended, on 15 May 2014, by clause 12(a) & (b) of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

Clause 13.8A(4): inserted, on 15 May 2014, by clause 12(c) of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

Clause 13.8A(3): amended, on 29 June 2017, by clause 10 of the Electricity Industry Participation Code Amendment (Shortened Gate Closure and Revised Bid and Offer Provisions) 2017.

### 13.8B Deemed reserve offers

- (1) This clause applies if, on a **trading day** ("the current **trading day**"), an **ancillary service agent** who provides **instantaneous reserves** has not submitted a **reserve offer** for a **trading period** in the **trading day** following the next **trading day**.
- (2) An **ancillary service agent** is deemed to have submitted, for that **trading period**, a **reserve offer** that is the same as the **reserve offer** the **ancillary service agent** made for the corresponding **trading period** on the current **trading day**, and clause 13.38(2)(c) applies accordingly.

- (3) A deemed **reserve offer** under subclause (2) applies until the **ancillary service agent** revises the **reserve offer** in accordance with clauses 13.46 to 13.49.

Clause 13.8B: inserted, on 1 November 2012, by clause 4 of the Electricity Industry Participation (Part 13 Minor Amendments) Code Amendment 2012.

Clause 13.8B(3): amended, on 29 June 2017, by clause 11 of the Electricity Industry Participation Code Amendment (Shortened Gate Closure and Revised Bid and Offer Provisions) 2017.

### 13.9 Information that offers must contain

Each **offer** submitted by a **generator** must—

- (a) other than for **intermittent generators**, **type A co-generators**, and **type B co-generators**, contain all information required by Form 1 in Schedule 13.1; and
- (b) *[Revoked]*
- (c) if the **offer** is submitted by an **intermittent generator** for an **intermittent generating station**,—
  - (i) contain the information required by Form 2 in Schedule 13.1; and
  - (ii) have a maximum of 1 price band for each **trading period**; and
  - (iii) specify a price of either \$0.00 (subject to clause 13.116) or \$0.01 for the price band; and
- (d) if the **offer** is submitted by a **type A co-generator** for a **type A industrial co-generating station** or by a **type B co-generator** for a **type B industrial co-generating station**,—
  - (i) contain the information required by Form 3 in Schedule 13.1; and
  - (ii) have a maximum of 2 price bands for each **trading period**; and
  - (iii) specify a price of either \$0.00 (in accordance with clause 13.116) or \$0.01 for the price band.

Compare: Electricity Governance Rules 2003 rule 3.6 section II part G

Clause 13.9(a): amended, on 27 May 2015, by clause 7(1) of the Electricity Industry Participation Code Amendment (Industrial Co-generation Dispatch Arrangements) 2015.

Clause 13.9(b): revoked, on 29 June 2017, by clause 12 of the Electricity Industry Participation Code Amendment (Shortened Gate Closure and Revised Bid and Offer Provisions) 2017.

Clause 13.9(d): amended, on 27 May 2015, by clause 7(2) of the Electricity Industry Participation Code Amendment (Industrial Co-generation Dispatch Arrangements) 2015.

### 13.9A Offer not to exceed capability

The total **MW** specified in each **offer** submitted by a **generator** must, in relation to the **generating plant** that is the subject of the **offer**, not exceed the total **MW** that the **generator** expects to be capable of generating at the relevant **point of connection** to the **grid** for the relevant **trading period**.

Clause 13.9A: inserted, on 29 June 2017, by clause 13 of the Electricity Industry Participation Code Amendment (Shortened Gate Closure and Revised Bid and Offer Provisions) 2017.

### 13.10 Generators must specify units in offers

Each **offer** submitted by a **generator** must—

- (a) be specific to individual **generating units** for **generating plant** in respect of which **electricity** is offered by that **generator** that cannot **synchronise** and come up to minimum load within the duration of a **trading period**; or
- (b) be specific to individual **generating stations** for other **generating plant** in respect of which **electricity** is offered by that **generator**.

Compare: Electricity Governance Rules 2003 rule 3.7 section II part G

### 13.11 Offers may be made by unit or plant

- (1) Despite clause 13.10, a **generator**, other than an **intermittent generator**, may offer **electricity** in respect of any **generating plant** on a unit basis. A **generator** may exercise this option by giving the **system operator** at least 5 **business days'** notice in writing of the exercise of the option. The **system operator** must, during the 5 **business day** period, make any necessary changes to the scheduling **software**.
- (2) If a **generator** has offered **electricity** in respect of any **generating plant** on a unit basis in accordance with subclause (1), it may change to submitting **offers** in accordance with clause 13.10. Such a change may be effected by giving the **system operator** at least 5 **business days'** notice in writing of the change. The **system operator** must, during the 5 **business day** period, make any necessary changes to the scheduling **software**.

Compare: Electricity Governance Rules 2003 rule 3.8 section II part G

### 13.12 Offers may contain up to 5 price bands

Subject to clause 13.9(c) and (d), an **offer** submitted by a **generator** may have a maximum of 5 price bands for each **trading period**. The price offered in each band must increase progressively from band to band as the aggregate quantity increases.

Compare: Electricity Governance Rules 2003 rule 3.9 section II part G

### 13.13 Information to be contained in bids

- (1) A **purchaser** must ensure that each of its **nominated bids**—
  - (a) contains all information required by Form 4 in Schedule 13.1; and
  - (aa) if it is a **nominated bid** for a **dispatch-capable load station**, specifies whether it is—
    - (i) a **nominated dispatch bid**; or
    - (ii) a **nominated non-dispatch bid**.
  - (b) *[Revoked]*
  - (c) if it is a **nominated dispatch bid**, specifies a price for each band that is one of the following:
    - (i) \$15,000/MWh or less; or
    - (ii) if the **Authority** has **published** a price for the purposes of this paragraph, the **published** price; or
    - (iii) if the **Authority** has not **published** a price for the purposes of this paragraph, \$600,000/MWh.
- (1A) The **Authority** may **publish** a price for the purposes of subclause (1)(c) if,—
  - (a) the **system operator** has given to the **Authority** an updated list of values of model parameters in accordance with clause 13.189(2)(a), and the **Authority** has considered any advice it has received from the **system operator** under clause 13.189(2)(b) and (2A); or
  - (b) the **Authority** considers that it is necessary to **publish** a new price.
- (2) A **purchaser** must ensure that each of its **difference bids** contains all information required by Form 4A in Schedule 13.1.

Compare: Electricity Governance Rules 2003 rule 3.10 section II part G

Clause 13.13: substituted, on 28 June 2012, by clause 11 of the Electricity Industry Participation (Demand-side Bidding and Forecasting) Code Amendment 2011.

Clause 13.13(1)(aa): inserted, on 15 May 2014, by clause 13(a) of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

Clause 13.13(1)(b): revoked, on 15 May 2014, by clause 13(b) of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

Clause 13.13(1)(c): inserted, on 3 November 2016, by clause 4(1) of the Electricity Industry Participation Code Amendment (Dispatchable Demand During Tight Market Conditions) 2016.

Clause 13.13(1A): inserted, on 3 November 2016, by clause 4(2) of the Electricity Industry Participation Code Amendment (Dispatchable Demand During Tight Market Conditions) 2016.

Clause 13.13(2): substituted, on 15 May 2014, by clause 13(c) of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

### **13.14 Nominated bids may contain up to 10 price bands**

- (1) A **nominated bid** submitted by a **purchaser** may have a maximum of 10 price bands for each **trading period**.
- (2) The price in each band must decrease progressively from band to band as the aggregate quantity increases.
- (3) The highest price band in each **nominated bid** is deemed to start at a quantity of 0.

Compare: Electricity Governance Rules 2003 rule 3.11 section II part G

Clause 13.14: substituted, on 28 June 2012, by clause 12 of the Electricity Industry Participation (Demand-side Bidding and Forecasting) Code Amendment 2011.

### **13.14A Difference bids may contain up to 10 price bands**

A **difference bid** submitted by a **purchaser** may have a maximum of—

- (a) 5 price bands for each **trading period** representing the **purchaser's** progressive increase in its usual quantity of **electricity** demanded for the **trading period**. The price in bands 2 to 5 must, in each case, be lower than the price in the preceding band; and
- (b) 5 price bands for each **trading period** representing the **purchaser's** progressive decrease in its usual quantity of **electricity** demanded for the **trading period**. The price in bands 2 to 5 must, in each case, be higher than the price in the preceding band.

Clause 13.14A: inserted, on 28 June 2012, by clause 13 of the Electricity Industry Participation (Demand-side Bidding and Forecasting) Code Amendment 2011.

### **13.15 How price is to be specified in bids or offers**

Prices in **bids** or **offers** must be expressed in dollars and whole cents per **MWh** excluding any **GST**. There is no upper limit on the prices that may be specified and the lower limit is \$0.00/**MWh**, subject to clauses 13.9(c) and (d), 13.24, 13.26, and 13.116.  
Compare: Electricity Governance Rules 2003 rule 3.12 section II part G

### **13.16 How quantity is to be specified in bids or offers**

For each price band, a **bid** or **offer** must specify a quantity expressed in **MW** to not more than 3 decimal places. The minimum quantity that may be bid or offered in a price band for a **trading period** is 0.000 **MW**.

Compare: Electricity Governance Rules 2003 rule 3.13 section II part G

Clause 13.16: amended, on 21 September 2012, by clause 18 of the Electricity Industry Participation (Minor Amendments) Code Amendment 2012.

### 13.17 Offers may be revised

- (1) Subject to subclauses (2) to (4), a **generator** may revise an **offer** at any time before the beginning of the **trading period** to which the **offer** relates by submitting a new **offer** to the **system operator**.
- (2) A **generator** must not revise any of its **offer** prices during a **gate closure period**.
- (3) A **generator** must not revise the **MW** specified in any price band in an **offer** during a **gate closure period**, unless clause 13.18(1), 13.18(1A), 13.18A, or 13.19 applies.
- (4) A **generator** must not revise any of the following **offer** parameters during a **gate closure period**, unless clause 13.19 applies:
  - (a) ramp rates;
  - (b) maximum output (including overload).

Compare: Electricity Governance Rules 2003 rule 3.14 section II part G

Clause 13.17 Heading: amended, on 28 June 2012, by clause 14(1) of the Electricity Industry Participation (Demand-side Bidding and Forecasting) Code Amendment 2011.

Clause 13.17(1): amended, on 28 June 2012, by clause 14(2) of the Electricity Industry Participation (Demand-side Bidding and Forecasting) Code Amendment 2011.

Clause 13.17: substituted, on 29 June 2017, by clause 14 of the Electricity Industry Participation Code Amendment (Shortened Gate Closure and Revised Bid and Offer Provisions) 2017.

### 13.18 When revised offer to be submitted

- (1) A **generator** must immediately submit a revised **offer** to the **system operator** if the total **MW** specified in an **offer** exceeds, by more than 5 **MW**, the total **MW** that the **generator** expects to be capable of generating at the relevant **point of connection** to the **grid** for the relevant **trading period**.
- (1A) A **generator** may submit a revised **offer** to the **system operator** if the total **MW** specified in an **offer** exceeds, by 5 **MW** or less, the total **MW** that the **generator** expects to be capable of generating at the relevant **point of connection** to the **grid** for the relevant **trading period**.
- (1B) The submission of a revised **offer** under subclause (1) or subclause (1A) does not relieve the **generator** of liability for breach of any other provision of this Code.
- (2) *[Revoked]*
- (3) Subclause (1) does not apply—
  - (a) in every case, after the beginning of the **trading period** to which an **offer** relates; and
  - (b) in relation to an **intermittent generator**, during the 2 hours immediately preceding the **trading period** to which an **offer** relates.

Compare: Electricity Governance Rules 2003 rules 3.15 and 3.16 section II part G

Clause 13.18 Heading: amended, on 28 June 2012, by clause 15(1) of the Electricity Industry Participation (Demand-side Bidding and Forecasting) Code Amendment 2011.

Clause 13.18 Heading: amended, on 29 June 2017, by clause 15(1) of the Electricity Industry Participation Code Amendment (Shortened Gate Closure and Revised Bid and Offer Provisions) 2017.

Clause 13.18(1): amended, on 28 June 2012, by clause 15(2) of the Electricity Industry Participation (Demand-side Bidding and Forecasting) Code Amendment 2011.

Clause 13.18(1): replaced, on 29 June 2017, by clause 15(2) of the Electricity Industry Participation Code Amendment (Shortened Gate Closure and Revised Bid and Offer Provisions) 2017.

Clause 13.18(1A): inserted, on 28 June 2012, by clause 15(3) of the Electricity Industry Participation (Demand-side Bidding and Forecasting) Code Amendment 2011.

Clause 13.18(1A): replaced, on 29 June 2017, by clause 15(3) of the Electricity Industry Participation Code Amendment (Shortened Gate Closure and Revised Bid and Offer Provisions) 2017.

Clause 13.18(1B): inserted, on 29 June 2017, by clause 15(3) of the Electricity Industry Participation Code Amendment (Shortened Gate Closure and Revised Bid and Offer Provisions) 2017.

Clause 13.18(2): amended, on 28 June 2012, by clause 15(4) of the Electricity Industry Participation (Demand-side Bidding and Forecasting) Code Amendment 2011.

Clause 13.18(2): revoked, on 29 June 2017, by clause 15(4) of the Electricity Industry Participation Code Amendment (Shortened Gate Closure and Revised Bid and Offer Provisions) 2017.

Clause 13.18(3): inserted, on 29 June 2017, by clause 15(5) of the Electricity Industry Participation Code Amendment (Shortened Gate Closure and Revised Bid and Offer Provisions) 2017.

### **13.18A Intermittent generators to submit revised offers**

- (1) During the 2 hours immediately preceding the **trading period** to which an **offer** relates, each **intermittent generator** must submit revised **offers** in respect of **MW** offered to the **system operator** at a frequency of at least 1 revised **offer** per **trading period**.
- (2) A revised **offer** submitted under subclause (1) must be based on a persistence model, unless otherwise agreed with the **Authority**.
- (3) For the purposes of this clause, a persistence model means a method for producing a forecast of the **intermittent generator's** generation, in **MW**, that takes into account only the following factors:
  - (a) if the relevant **intermittent generating station** is generating at the time the revised **offer** is submitted, the actual output from the **intermittent generating station** at that time; and
  - (b) any expected changes in availability and capability of **generating plant** forming all or part of the relevant **intermittent generating station**.

Clause 13.18A: inserted, on 29 June 2017, by clause 16 of the Electricity Industry Participation Code Amendment (Shortened Gate Closure and Revised Bid and Offer Provisions) 2017.

### **13.19 When revised offers may be submitted during gate closure period**

- (1) A **generator** may submit a revised **offer** to the **system operator** during a **gate closure period** if—
  - (a) the revision is necessary due to a **bona fide physical reason**; or
  - (b) the **system operator** issues a **formal notice** under clause 5 of **Technical Code B** of Schedule 8.3; or
  - (c) a **bona fide physical reason** that made a revision necessary under paragraph (a) ceases to exist sooner than was expected at the time it arose, and—
    - (i) the 1st **trading period** after the original **bona fide physical reason** ceases to exist is within 24 hours after the circumstances that constituted the original **bona fide physical reason** arose; and
    - (ii) the total change in **MW** specified in the **offer** that is revised as a result of the **bona fide physical reason** ceasing to exist is the same or less than the total change in **MW** specified in the **offer** that was made as a result of the original **bona fide physical reason**.
- (2) A **generator** that submits a revised **offer** under subclause (1)(c) must do so as soon as possible after the relevant **bona fide physical reason** ceases to exist.

Compare: Electricity Governance Rules 2003 rule 3.17 section II part G

Clause 13.19 Heading: amended, on 28 June 2012, by clause 16(1) of the Electricity Industry Participation (Demand-side Bidding and Forecasting) Code Amendment 2011.

Clause 13.19: amended, on 28 June 2012, by clause 16(2) of the Electricity Industry Participation (Demand-side Bidding and Forecasting) Code Amendment 2011.

Clause 13.19: substituted, on 29 June 2017, by clause 17 of the Electricity Industry Participation Code Amendment (Shortened Gate Closure and Revised Bid and Offer Provisions) 2017.

### 13.19AA Limitations on revised offers

A **generator** that submits a revised **offer** under clauses 13.18(1), 13.18(1A), or 13.19(1) during a **gate closure period** must ensure that—

- (a) the revised **offer** only differs from the original **offer** to the extent necessary to ensure that the **MW** specified in the revised **offer** is the **MW** that the **generator** expects to be capable of generating at the relevant **point of connection** to the **grid** for the relevant **trading period**; and
- (b) the revised **offer** complies with the following:
  - (i) the reduction in **MW** specified in the revised **offer** must be first deducted from the **MW** offered in the highest price band:
  - (ii) if the reduction in **MW** exceeds the **MW** in the highest price band, the remainder must be deducted from the price bands below the highest, in descending order as the **MW** in each price band is reduced to zero, until all of the reduction is reflected in the revised **offer**.

Clause 13.19AA: inserted, on 29 June 2017, by clause 17 of the Electricity Industry Participation Code Amendment (Shortened Gate Closure and Revised Bid and Offer Provisions) 2017.

### 13.19A Bids may be revised

- (1) Each **purchaser** may, at any time before the beginning of a **trading period** in respect of which a **bid** is made,—
  - (a) revise any of its **bid** prices or the **MW** specified in any price band in a **bid** for any **trading period** by submitting a new **bid** to the **system operator**; or
  - (aa) revise a **nominated bid**—
    - (i) from being a **nominated dispatch bid** to being a **nominated non-dispatch bid**; or
    - (ii) from being a **nominated non-dispatch bid** to being a **nominated dispatch bid**.
  - (b) *[Revoked]*
- (1A) Despite subclause (1), a **dispatchable load purchaser** must not do any of the following during a **gate closure period**:
  - (a) revise the price of a **nominated dispatch bid**:
  - (b) revise the **MW** specified in any price band in a **nominated dispatch bid**, unless subclause (1B) or clause 13.19B applies.
- (1B) A **dispatchable load purchaser** may revise the **MW** specified in any price band in a **nominated dispatch bid** during a **gate closure period** if—
  - (a) the revision is necessary due to a **bona fide physical reason**; or
  - (b) the **system operator** issues a **formal notice** under clause 5 of **Technical Code B** of Schedule 8.3; or
  - (c) a **bona fide physical reason** that made a revision necessary under paragraph (a) ceases to exist sooner than was expected at the time it arose, and—
    - (i) the 1st **trading period** after the original **bona fide physical reason** ceases to exist is within 24 hours after the circumstances that constituted the original **bona fide physical reason** arose; and
    - (ii) the total change in **MW** specified in the **nominated dispatch bid** that is revised as a result of the **bona fide physical reason** ceasing to exist is the

same or less than the total change in **MW** specified in the **nominated dispatch bid** that was made as a result of the original **bona fide physical reason**.

- (2) *[Revoked]*
- (3) *[Revoked]*
- (3A) If a **purchaser** revises a **nominated bid** for a **dispatch-capable load station** in the **trading period** that is immediately before the **trading period** to which the **nominated bid** applies, the revised **nominated bid** is a **nominated non-dispatch bid**.
- (3B) Despite subclause (1), a **dispatchable load purchaser** must not, during the 2 **trading periods** immediately preceding the **trading period** to which a **nominated non-dispatch bid** relates, revise the **nominated non-dispatch bid** to being a **nominated dispatch bid**.
- (4) *[Revoked]*
- (5) *[Revoked]*
- (6) If the **system operator** declares a **grid emergency**, a **dispatchable load purchaser** must comply with clause 13.99A.

Clause 13.19A Heading: amended, on 29 June 2017, by clause 18(1) of the Electricity Industry Participation Code Amendment (Shortened Gate Closure and Revised Bid and Offer Provisions) 2017.

Clause 13.19A: inserted, on 28 June 2012, by clause 17 of the Electricity Industry Participation (Demand-side Bidding and Forecasting) Code Amendment 2011.

Clause 13.19A(1): amended, on 29 June 2017, by clause 18(2) of the Electricity Industry Participation Code Amendment (Shortened Gate Closure and Revised Bid and Offer Provisions) 2017.

Clause 13.19A(1)(a): amended, on 29 June 2017, by clause 18(3) of the Electricity Industry Participation Code Amendment (Shortened Gate Closure and Revised Bid and Offer Provisions) 2017.

Clause 13.19A(1)(aa): inserted, on 15 May 2014, by clause 14(1) of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

Clause 13.19A(1)(aa)(ii): amended, on 29 June 2017, by clause 18(4) of the Electricity Industry Participation Code Amendment (Shortened Gate Closure and Revised Bid and Offer Provisions) 2017.

Clause 13.19A(1)(b): revoked, on 29 June 2017, by clause 18(5) of the Electricity Industry Participation Code Amendment (Shortened Gate Closure and Revised Bid and Offer Provisions) 2017.

Clause 13.19A(1A) and (1B): inserted, on 29 June 2017, by clause 18(6) of the Electricity Industry Participation Code Amendment (Shortened Gate Closure and Revised Bid and Offer Provisions) 2017.

Clause 13.19A(2)(ba): inserted, on 15 May 2014, by clause 14(2) of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

Clause 13.19A(3)(a)(ia): inserted, on 15 May 2014, by clause 14(3) of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

Clause 13.19A(3)(b): substituted, on 15 May 2014, by clause 14(4) of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

Clause 13.19A(3)(c): amended, on 15 May 2014, by clause 14(5) of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

Clause 13.19A(2), (3), (4) and (5): revoked, on 29 June 2017, by clause 18(7) of the Electricity Industry Participation Code Amendment (Shortened Gate Closure and Revised Bid and Offer Provisions) 2017.

Clause 13.19A(3A): inserted, on 1 December 2015, by clause 4 of the Electricity Industry Participation Code Amendment (Dispatchable Demand: Late Bid Revisions) 2015.

Clause 13.19A(3B): inserted, on 29 June 2017, by clause 18(8) of the Electricity Industry Participation Code Amendment (Shortened Gate Closure and Revised Bid and Offer Provisions) 2017.

Clause 13.19A(6): inserted, on 29 June 2017, by clause 18(9) of the Electricity Industry Participation Code Amendment (Shortened Gate Closure and Revised Bid and Offer Provisions) 2017.

### 13.19B Bids must be revised

- (1) Before the beginning of the **trading period** to which a **nominated bid** relates, the **purchaser** that submitted the **nominated bid** must immediately submit a revised **nominated bid** in respect of **MW** to the **system operator** if the **purchaser** expects, or ought reasonably to expect, that the **MW** it is likely to purchase at the prices indicated in the **nominated bid** will,—



- (a) if the **nominated bid** is a **nominated non-dispatch bid**, differ from the **MW** specified in the **nominated bid** by more than the lesser of—
    - (i) 20 **MW**; and
    - (ii) 20% of the **nominated bid MW**; or
  - (b) if the **nominated bid** is a **nominated dispatch bid**, differ from the **MW** specified in the **nominated bid** by more than the lesser of—
    - (i) 10 **MW**; and
    - (ii) 10% of the **nominated bid MW**.
- (2) Despite subclause (1), a **purchaser** is not required to submit a revised **nominated bid** in respect of **MW** if the expected change in **MW** is less than 5 **MW**.  
Clause 13.19B: inserted, on 29 June 2017, by clause 19 of the Electricity Industry Participation Code Amendment (Shortened Gate Closure and Revised Bid and Offer Provisions) 2017.

### 13.20 System operator advised of revised nominated bids or offers in certain circumstances

- (1) This clause applies to each **purchaser** or **generator** that submits a revised **nominated bid** or **offer** during the 15 minutes immediately preceding the **trading period** to which the revised **nominated bid** or **offer** relates.
- (2) A **purchaser** or **generator** that submits a revised **nominated bid** or **offer** in the time frame described in subclause (1) must immediately advise the **system operator** of the revision.
- (3) Subclause (2) does not apply to an **intermittent generator** submitting a revised **offer** under clause 13.18A.

Compare: Electricity Governance Rules 2003 rule 3.18 section II part G

Clause 13.20 Heading: amended, on 5 October 2017, by clause 336(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 13.20: substituted, on 28 June 2012, by clause 18 of the Electricity Industry Participation (Demand-side Bidding and Forecasting) Code Amendment 2011.

Clause 13.20: substituted, on 29 June 2017, by clause 20 of the Electricity Industry Participation Code Amendment (Shortened Gate Closure and Revised Bid and Offer Provisions) 2017.

Clause 13.20(1): amended, on 15 May 2014, by clause 15 of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

Clause 13.20(2): amended, on 5 October 2017, by clause 336(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### 13.21 Authority informed of revised nominated dispatch bid or offer during gate closure period

- (1) A **dispatchable load purchaser** or **generator** that submits a revised **nominated dispatch bid** or a revised **offer** to the **system operator** during a **gate closure period** must report each revision to the **Authority** in writing together with an explanation of the reasons for the revision.
- (1A) The **dispatchable load purchaser** or **generator** must report the revision to the **Authority** no later than 1700 hours on the 1st **business day** following the **trading day** on which the revision was made.
- (1B) Subclauses (1) and (1A) do not apply to an **intermittent generator** submitting a revised **offer** under clause 13.18A.
- (2) *[Revoked]*

Compare: Electricity Governance Rules 2003 rules 3.19 and 3.20 section II part G

Clause 13.21 Heading: amended, on 28 June 2012, by clause 19(1) of the Electricity Industry Participation (Demand-side Bidding and Forecasting) Code Amendment 2011.

Clause 13.21 Heading: replaced, on 29 June 2017, by clause 21(1) of the Electricity Industry Participation Code Amendment (Shortened Gate Closure and Revised Bid and Offer Provisions) 2017.

Clause 13.21 Heading: amended, on 5 October 2017, by clause 337 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 13.21(1): amended, on 28 June 2012, by clause 19(2) of the Electricity Industry Participation (Demand-side Bidding and Forecasting) Code Amendment 2011.

Clause 13.21(1): replaced, on 29 June 2017, by clause 21(2) of the Electricity Industry Participation Code Amendment (Shortened Gate Closure and Revised Bid and Offer Provisions) 2017.

Clause 13.21(2): amended, on 28 June 2012, by clause 19(3) of the Electricity Industry Participation (Demand-side Bidding and Forecasting) Code Amendment 2011.

Clause 13.21(1A) and (1B): inserted, on 29 June 2017, by clause 21(2) of the Electricity Industry Participation Code Amendment (Shortened Gate Closure and Revised Bid and Offer Provisions) 2017.

Clause 13.21(2): revoked, on 29 June 2017, by clause 21(3) of the Electricity Industry Participation Code Amendment (Shortened Gate Closure and Revised Bid and Offer Provisions) 2017.

### **13.22 Transmission of information**

- (1) Except where specified otherwise in clauses 13.6 to 13.27, all information that a **purchaser** or **generator** must submit under clauses 13.6 to 13.27 must be submitted to the **system operator** using **WITS**.
- (2) The **system operator** must immediately confirm receipt of any information that the **system operator** receives from a **purchaser** or **generator** under clauses 13.6 to 13.27. Each confirmation must contain a copy of the information received by the **system operator** together with the time of receipt.
- (3) If a **purchaser** or **generator** has not received the confirmation within 10 minutes of submitting the information under clauses 13.6 to 13.27 to the **system operator**, the **purchaser** or **generator** must—
  - (a) check whether the **system operator** has received the information; and
  - (b) if the **system operator** has not received the information, resend the information; and
  - (c) repeat the process set out in this clause until the **system operator** has confirmed receipt of the information from the **purchaser** or **generator**.

Compare: Electricity Governance Rules 2003 rules 3.21 to 3.23 section II part G

Clause 13.22(3): amended, on 28 June 2012, by clause 20 of the Electricity Industry Participation (Demand-side Bidding and Forecasting) Code Amendment 2011.

Clause 13.22: replaced, on 5 October 2017, by clause 338 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### **13.23 Backup procedures if WITS is unavailable**

- (1) If **WITS** is unavailable to receive **bids** or **offers** or to confirm the receipt of **bids** or **offers**, each **purchaser** and **generator** or the **system operator**, as the case may be, must follow the backup procedures specified by the **WITS manager**.
- (2) The backup procedures referred to in subclause (1) must be specified by the **WITS manager** following consultation with the **Authority** and each **purchaser**, **generator** and the **system operator**.

Compare: Electricity Governance Rules 2003 rules 3.24 and 3.25 section II part G

Clause 13.23 Heading: amended, on 5 October 2017, by clause 339(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 13.23: amended, on 5 October 2017, by clause 339(2), (3) and (4) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### 13.24 Plant with special circumstances

Despite clauses 13.9(b) and 13.18(1), a **generator** is not required to submit a revised **offer** in respect of an **automatic control plant** if—

- (a) the **offer** submitted in respect of the **automatic control plant** is based on a profile of the pre-programmed levels of the **automatic control plant**; and
- (b) the **offer** is made at a 0 price and clause 13.116(2) applies to the **generator**; and
- (c) the **offer** is otherwise made in accordance with clauses 13.6 to 13.27; and
- (d) the **system operator** has confirmed in writing to the **generator** that it is satisfied that the **offer** meets the requirements of the **dispatch objective**; and
- (e) the **generator** expects that the ability of the **automatic control plant** to generate the quantity scheduled for a **trading period** at a **grid injection point** will not change by more than 10 MW of the scheduled quantity.

Compare: Electricity Governance Rules 2003 rule 3.26 section II part G

### 13.25 Exception for small generation

- (1) Despite clause 13.6(1), a **generator** is not required to submit an **offer** for a **generating station** that is 10 MW or smaller and any **electricity** sold to the **clearing manager** from the **generating station** is regarded as **unoffered generation** for the purpose of this Code.
- (2) The **system operator** may require the relevant **generator** to provide information in a form reasonably determined by the **system operator** on the expected generation output for any **unoffered generation** from a **generating station** with a **point of connection** to the **grid**.

Compare: Electricity Governance Rules 2003 rule 3.27 section II part G

Clause 13.25(1): amended, on 29 June 2017, by clause 22 of the Electricity Industry Participation Code Amendment (Shortened Gate Closure and Revised Bid and Offer Provisions) 2017.

### 13.26 Exception for embedded generation

An **embedded generator** required to submit an **offer** in accordance with clause 8.25(5) may make an **offer** at a 0 price and clause 13.116(2) applies to the **embedded generator**.

Compare: Electricity Governance Rules 2003 rule 3.28 section II part G

### 13.27 System operator to retain bids and offers

The **system operator** must retain, in a form that it considers appropriate, all **bids** and **offers** for **electricity** submitted by **participants** under this subpart, including all revised **bids** and **offers**.

Compare: Electricity Governance Rules 2003 rule 3.29 section II part G

Clause 13.27: amended, on 29 June 2017, by clause 23 of the Electricity Industry Participation Code Amendment (Shortened Gate Closure and Revised Bid and Offer Provisions) 2017.

#### *Process for determining conforming and non-conforming grid exit points*

Heading: inserted, on 28 March 2012, by clause 21 of the Electricity Industry Participation (Demand-side Bidding and Forecasting) Code Amendment 2011.

### 13.27A Authority determines conforming and non-conforming GXPs on own initiative

The **Authority** may, on its own initiative,—

- (a) determine whether a **GXP**, which is deemed to be a **conforming GXP** under clause 13.27F, is a **conforming GXP** or a **non-conforming GXP**;
- (b) reconsider a previous determination, and as a result may decide to replace the previous determination with a new determination.

Clause 13.27A: inserted, on 28 March 2012, by clause 21 of the Electricity Industry Participation (Demand-side Bidding and Forecasting) Code Amendment 2011.

### **13.27B Authority to determine conforming and non-conforming GXPs if requested**

- (1) Subclause (4) applies if—
  - (a) a **purchaser** or the **system operator** makes a request under clause 13.27H; and
  - (b) the **Authority** decides there are valid grounds to consider the request.
- (2) The **Authority** must decide whether to proceed with the request within a reasonable time after receiving the request.
- (3) If the **Authority** decides there are no valid grounds to consider the request, the **Authority** must give written notice to the requester of—
  - (a) the **Authority's** decision; and
  - (b) the grounds for the **Authority's** decision.
- (4) If subclause (1) applies, the **Authority** must—
  - (a) determine whether a **GXP**, which is deemed to be a **conforming GXP** under clause 13.27F, is a **conforming GXP** or a **non-conforming GXP**;
  - (b) reconsider a previous determination, and as a result may decide to replace the previous determination with a new determination.

Clause 13.27B: inserted, on 28 March 2012, by clause 21 of the Electricity Industry Participation (Demand-side Bidding and Forecasting) Code Amendment 2011.

Clause 13.27B(3): amended, on 5 October 2017, by clause 340 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### **13.27C Process for making determination**

- (1) In making a determination, the **Authority** must—
  - (a) apply the methodology set out in Schedule 13.7; and
  - (b) request and take into account advice from the **system operator**; and
  - (c) take into account any information submitted by a **purchaser** who purchases **electricity** at the **GXP**.
- (2) The **Authority** must make a determination in accordance with the methodology in Schedule 13.7, unless—
  - (a) the **Authority** has applied the methodology; and
  - (b) according to the methodology, the **GXP** is a **conforming GXP**; and
  - (c) the **Authority** considers that the **GXP** should be treated as a **non-conforming GXP**; and
  - (d) the **Authority** has **published** criteria under clause 13.27E; and
  - (e) making a determination that the **GXP** is a **non-conforming GXP** is in accordance with the criteria.
- (3) If paragraphs (a) to (e) in subclause (2) apply, the **Authority** may make a determination in accordance with the criteria **published** under clause 13.27E.
- (4) As soon as practicable after making a determination, the **Authority** must—
  - (a) advise the **WITS manager**, all **purchasers**, and the **system operator**—

- (i) of its determination; and
- (ii) whether, in making the determination, the **Authority** has followed—
  - (A) the methodology set out in Schedule 13.7; or
  - (B) the criteria **published** under clause 13.27E; and
- (b) advise all **purchasers** and the **system operator** of the right to request, under clause 13.27H, a reconsideration of the determination; and
- (c) if the determination was requested under clause 13.27H, provide reasons for its decision to the requester.

Clause 13.27C Heading: amended, on 5 October 2017, by clause 341(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 13.27C: inserted, on 28 March 2012, by clause 21 of the Electricity Industry Participation (Demand-side Bidding and Forecasting) Code Amendment 2011.

Clause 13.27C(2)(d), (3) and (4)(a)(ii)(B): amended, on 5 October 2017, by clause 341(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 13.27C(4): amended, on 27 June 2012, by clause 7 of the Electricity Industry Participation (Demand-side Bidding and Forecasting) Code Amendment 2011, Amendment 2012.

Clause 13.27(4)(a): amended, on 5 October 2017, by clause 341(3) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### **13.27D System operator to provide advice within reasonable time**

The **system operator** must provide the advice requested under clause 13.27C(1)(b) within a reasonable time specified by the **Authority**.

Clause 13.27D: inserted, on 28 March 2012, by clause 21 of the Electricity Industry Participation (Demand-side Bidding and Forecasting) Code Amendment 2011.

### **13.27E Authority may publish criteria for determining GXP to be non-conforming**

- (1) The **Authority** may **publish** criteria that set out the circumstances in which the **Authority** may make a determination that does not follow the methodology set out in Schedule 13.7.
- (2) The **Authority** must consult with **participants** before—
  - (a) **publishing** the criteria under subclause (1);
  - (b) amending the criteria **published** under subclause (1).

Clause 13.27E Heading: amended, on 5 October 2017, by clause 342(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 13.27E: inserted, on 28 March 2012, by clause 21 of the Electricity Industry Participation (Demand-side Bidding and Forecasting) Code Amendment 2011.

Clause 13.27E: amended, on 5 October 2017, by clause 342(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### **13.27F GXP deemed to be conforming GXP before determination is made**

If the **Authority** has not made a determination for a **GXP**, the **GXP** is deemed to be a **conforming GXP** until the **Authority** determines otherwise.

Clause 13.27F: inserted, on 28 March 2012, by clause 21 of the Electricity Industry Participation (Demand-side Bidding and Forecasting) Code Amendment 2011.

### **13.27G Authority must publish and maintain list of non-conforming and conforming GXPs**

The **Authority** must **publish** and maintain a list of all **non-conforming GXPs** and all **conforming GXPs**, including—

- (a) the mean **demand** (in **MW**) for each **GXP** calculated in accordance with clause 1(b) of Schedule 13.7; and
- (b) if the mean **demand** for a **GXP** is 10 **MW** or more, the unpredictability measure for the **GXP** calculated in accordance with clause 1(c) of Schedule 13.7.

Clause 13.27G Heading: amended, on 5 October 2017, by clause 343(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 13.27G: inserted, on 28 March 2012, by clause 21 of the Electricity Industry Participation (Demand-side Bidding and Forecasting) Code Amendment 2011.

Clause 13.27G: amended, on 5 October 2017, by clause 343(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### 13.27H Right to request determination or reconsideration of determination

- (1) A **purchaser** may request that the **Authority**—
  - (a) determine whether a **GXP** is a **conforming GXP** or a **non-conforming GXP**, in respect of a **GXP**—
    - (i) at which the **purchaser** purchases **electricity**; and
    - (ii) which is deemed to be a **conforming GXP** under clause 13.27F;
  - (b) reconsider a determination made under clause 13.27A or clause 13.27B(4) for a **GXP** at which the **purchaser** purchases **electricity**.
- (2) The **system operator** may request that the **Authority**—
  - (a) determine whether a **GXP**, which is deemed to be a **conforming GXP** under clause 13.27F, is a **conforming GXP** or a **non-conforming GXP**;
  - (b) reconsider a determination made under clause 13.27A or clause 13.27B(4).
- (3) The person making the request may provide the **Authority** with information that the person considers relevant to its request.

Clause 13.27H: inserted, on 28 March 2012, by clause 21 of the Electricity Industry Participation (Demand-side Bidding and Forecasting) Code Amendment 2011.

### 13.27I Effect of determination

- (1) When making a determination, the **Authority** must specify a date and a **trading period** from which the determination takes effect.
- (2) The **Authority** must not specify a date that is earlier than 5 **business days** after the date on which the **Authority** makes the determination.

Clause 13.27I: inserted, on 28 March 2012, by clause 21 of the Electricity Industry Participation (Demand-side Bidding and Forecasting) Code Amendment 2011.

### 13.27J New GXPs

At least 1 month before a **grid owner** connects a **GXP** to the **grid** for the first time, the **grid owner** must advise the **Authority** in writing of its intention to connect the **GXP**.

Clause 13.27J: inserted, on 28 March 2012, by clause 21 of the Electricity Industry Participation (Demand-side Bidding and Forecasting) Code Amendment 2011.

Clause 13.27J: amended, on 23 February 2015, by clause 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 13.27J: amended, on 5 October 2017, by clause 344 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### **13.27K Authority to provide information at purchaser's request**

- (1) After the **Authority** has made a determination under clause 13.27A or clause 13.27B(4) for a **GXP**, a **purchaser** who purchases **electricity** at the **GXP** may request from the **Authority** the following information in relation to the **GXP**:
  - (a) reconciled **half hour demand** data (in **MW**), as described in clause 2(1)(a) of Schedule 13.7;
  - (b) information about the way in which **demand** switching information (described in clause 2(1)(b) of Schedule 13.7) has been used to prepare the adjusted reconciled **half hour demand** data described in clause 1(a) of Schedule 13.7;
  - (c) information about the one-off events described in clause 2(1)(c) and clause 2(3) of Schedule 13.7 and the way in which those one-off events have been used to prepare the adjusted reconciled **half hour demand** data described in clause 1(a) of Schedule 13.7;
  - (d) the adjusted reconciled **half hour demand** data (in **MW**), as described in clause 1(a) of Schedule 13.7;
  - (e) the estimates of the adjusted reconciled **half hour demand** produced by the statistical predictive model under clause 3(1)(a) of Schedule 13.7, and the residuals calculated under clause 3(1)(b) of Schedule 13.7.
- (2) If a **purchaser** requests information under subclause (1), the **Authority** must provide the information if the information—
  - (a) is available to the **Authority**; and
  - (b) is not confidential; and
  - (c) is not commercially sensitive.

Clause 13.27K: inserted, on 28 March 2012, by clause 21 of the Electricity Industry Participation (Demand-side Bidding and Forecasting) Code Amendment 2011.

### *Special treatment of some grid exit points*

Heading: inserted, on 28 June 2012, by clause 22 of the Electricity Industry Participation (Demand-side Bidding and Forecasting) Code Amendment 2011.

### **13.28 Special treatment of some grid exit points**

- (1) For the purpose of this subpart and subparts 2 and 4, a **purchaser**, **generator** or **market operation service provider** may apply to the **Authority** to have 2 or more **grid exit points** treated as 1 **grid exit point** for the purposes of determining the status of a **GXP** under clause 13.27A or clause 13.27B(4), submitting **bids**, scheduling, switching, **dispatch**, pricing, clearing and settlement where there are 2 or more **local networks** supplied from the **grid** at the same physical location.
- (2) In determining an application under subclause (1), the **Authority** must consider the following factors:
  - (a) the efficiency or otherwise, of creating a separate price for **grid exit points** that are at the same, or at a geographically similar location;
  - (b) the geographical similarity of the **grid exit points** that are the subject of the application;

- (c) the effect on a **market operation service provider** in terms of added processing time and complexity in treating as separate 2 or more **grid exit points** that are in the same or in a geographically similar location;
  - (d) any submissions received from **participants** under subclause (3);
  - (e) any other matter the **Authority** thinks fit.
- (3) The **Authority** must give written notice to **participants** of an application under subclause (1) within 2 **business days** of the application being received by the **Authority**. Each **participant** has 5 **business days** to make submissions to the **Authority** on the application. The **Authority** must not consider an application until after the period for making submissions on the application has expired.
- (4) If an application under subclause (1) has been approved, the **Authority** must consult with each **market operation service provider** about the time it may take to implement changes that are required to accommodate the decision. The **Authority** must then give written notice to each **participant** of the date from which its decision takes effect.

Compare: Electricity Governance Rules 2003 rule 4 section II part G

Clause 13.28(1): amended, on 28 June 2012, by clause 23 of the Electricity Industry Participation (Demand-side Bidding and Forecasting) Code Amendment 2011.

Clause 13.28(3) and (4): amended, on 5 October 2017, by clause 345 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

#### *Information from grid owners*

### **13.29 Standing data on grid capability to be provided to system operator**

In addition to the **asset owner** obligations to provide information under clauses 2(5) and (6) and 3(1) of **Technical Code A** of Schedule 8.3, each **grid owner** must provide standing data on the capability of the transmission system to the **system operator** that is consistent with the configuration of the transmission system in the algorithms described in Schedule 13.3. The transmission data must include—

- (a) AC system configuration, including the transmission **lines**; and
- (b) AC system capacity including the limits of each transmission line of the transmission system; and
- (c) AC system loss characteristics including transmission loss functions for each transmission line of the transmission system.

Compare: Electricity Governance Rules 2003 rule 5.1 section II part G

Clause 13.29(a): amended, on 1 February 2016, by clause 77 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

### **13.30 Standing data on HVDC capability to be provided to system operator**

- (1) In addition to the **asset owner** obligations to provide information under clauses 2(5) and (6), and 3(1) of **Technical Code A** of Schedule 8.3, the **HVDC owner** must provide standing data on the capability of the **HVDC link** to the **system operator** consistent with the **configuration** of the **HVDC link**.
- (2) The data provided under subclause (1) must include—
  - (a) the HVDC transmission **lines** and system capacity, including reserve capacity; and
  - (b) **HVDC link** capacity, including limits of each HVDC transmission line of the HVDC transmission system; and



- (c) HVDC system loss characteristics including transmission loss functions for each transmission line of the HVDC transmission system; and
- (d) in relation to Pole 2, or Pole 3, or Pole 2 and Pole 3, of the **HVDC link**—
  - (i) if the **HVDC owner** imposes a limit on transfer direction, the direction of that transfer limit (northward or southward); and
  - (ii) if the **HVDC owner** imposes a minimum transfer limit, that minimum transfer limit (in **MW**); and
  - (iii) if the **HVDC owner** imposes a maximum transfer limit, that maximum transfer limit (in **MW**).
- (3) Subclause (2)(d) applies only if—
  - (a) the **HVDC owner** is operating the **HVDC link** in accordance with—
    - (i) a **commissioning** plan agreed with the **system operator** under clause 2(6) to (9) of **Technical Code A** of Schedule 8.3; or
    - (ii) a test plan provided to the **system operator** under clause 2(6) to (9) of **Technical Code A** of Schedule 8.3; and
  - (b) the **configuration** of the **HVDC link** is—
    - (i) Pole 3 and Pole 2 bipole **round power**; or
    - (ii) Pole 3 and Pole 2 bipole not **round power**.

Compare: Electricity Governance Rules 2003 rule 5.2 section II part G

Clause 13.30: substituted, on 1 November 2012, by clause 4 of the Electricity Industry Participation (HVDC Link Pole 3 Standing Data) Code Amendment 2012.

Clause 13.30(2)(a): amended, on 1 February 2016, by clause 78 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

Clause 13.30(2)(d): amended, on 26 September 2013, by clause 5 of the Electricity Industry Participation (HVDC Link Bipole Control System Testing) Code Amendment 2013.

Clause 13.30(3)(a)(i): amended, on 5 October 2017, by clause 346 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### 13.31 Standing data on transformer capability to be provided to system operator

In addition to the **asset owner** obligations to provide information under clauses 2(5) and (6), and 3(1) of **Technical Code A** of Schedule 8.3 each **grid owner** must provide standing data on the capability of transformers to the **system operator** consistent with the configuration of those transformers. The data must include—

- (a) the transformer capacity of each transformer; and
- (b) the transformer loss characteristics, including transformer loss functions, for each transformer.

Compare: Electricity Governance Rules 2003 rule 5.3 section II part G

### 13.32 Transmission grid capability information to be updated

In addition to the **asset owner** obligations to provide information under clauses 2(5) and (6) of **Technical Code A** of Schedule 8.3, and subject to any timetable agreed with the **system operator** under clause 3(1) of **Technical Code A** of Schedule 8.3, each **grid owner** must submit to the **system operator** for each **trading period** of a **schedule period**, or for such longer period of time as agreed between the **system operator** and each **grid owner**, any updates to the information described in clauses 13.29 to 13.31 and 13.33(d).

Compare: Electricity Governance Rules 2003 rule 5.4 section II part G

Clause 13.32: amended, on 28 June 2012, by clause 24 of the Electricity Industry Participation (Demand-side Bidding and Forecasting) Code Amendment 2011.

### 13.33 Grid owners must submit revised information to system operator

Up to 1 hour before the beginning of the relevant **trading period**, but subject to any timetable agreed with the **system operator** under clause 3(1) of **Technical Code A** of Schedule 8.3, each **grid owner** must immediately submit revised information to the **system operator** if there has been or is likely to be—

- (a) a change to the information described in clauses 13.29 or 13.30; or
- (b) a change of 5% or more in the capacity limit of any transmission line of the transmission system, of the **HVDC link**, or of any transformer, represented in the algorithms described in Schedule 13.3; or
- (c) a change to loss characteristics, including loss functions, for any transmission line of the transmission system or of the **HVDC link**, or for any transformer, represented in the algorithms described in Schedule 13.3 that causes any losses or marginal losses to change by 5% or more; or
- (d) a change in the availability of **assets** forming part of the **grid**.

Compare: Electricity Governance Rules 2003 rule 5.5 section II part G

Clause 13.33: amended, on 29 June 2017, by clause 24 of the Electricity Industry Participation Code Amendment (Shortened Gate Closure and Revised Bid and Offer Provisions) 2017.

### 13.34 Changes may be made within 1 hour before trading period

- (1) A **grid owner** may update the information submitted under clause 13.33 later than 1 hour before the relevant **trading period** only if—
  - (a) a **bona fide physical reason** necessitates the change; or
  - (b) the **system operator** issues a **formal notice**; or
  - (c) an unforeseeable change occurs in the availability of a **grid owner's assets**, which were the subject of a planned or unplanned outage in relation to which the **grid owner** gave written notice to the **system operator**.
- (2) If a **grid owner** has sent revised information to the **system operator** under subclause (1) later than 15 minutes before the relevant **trading period**, the **grid owner** must also immediately notify the **system operator** of the revised information by telephone or by such other mechanism as may be agreed from time to time in writing between **grid owners** and the **system operator**.
- (3) *[Revoked]*
- (4) *[Revoked]*

Compare: Electricity Governance Rules 2003 rules 5.6 to 5.9 section II part G

Clause 13.34 Heading: amended, on 29 June 2017, by clause 25(1) of the Electricity Industry Participation Code Amendment (Shortened Gate Closure and Revised Bid and Offer Provisions) 2017.

Clause 13.34(1): amended, on 29 June 2017, by clause 25(2) of the Electricity Industry Participation Code Amendment (Shortened Gate Closure and Revised Bid and Offer Provisions) 2017.

Clause 13.34(1)(c): amended, on 5 October 2017, by clause 347 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 13.34(3) and (4): revoked, on 29 June 2017, by clause 25(3) of the Electricity Industry Participation Code Amendment (Shortened Gate Closure and Revised Bid and Offer Provisions) 2017.

### 13.35 System operator to confirm receipt of grid owner information

- (1) *[Revoked]*

- (2) The **system operator** must immediately confirm to each **grid owner** receipt of all information received from that **grid owner** under clauses 13.29 to 13.36. The confirmation must also contain a record of the time of receipt.
- (3) If a **grid owner** has not received a confirmation that its information has been received by the **system operator** within 10 minutes after that information has been sent, the **grid owner** must telephone the **system operator** to check whether the information has been received. If it has not, the **grid owner** must resend the information. The process set out in this clause must be repeated until the **system operator** confirms receipt of the information.

Compare: Electricity Governance Rules 2003 rules 5.10 to 5.12 section II part G

Clause 13.35 Heading: amended, on 5 October 2017, by clause 348(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 13.35(1): revoked, on 5 October 2017, by clause 348(2)(a) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 13.35(2): amended, on 5 October 2017, by clause 348(2)(b) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### 13.36 *[Revoked]*

Compare: Electricity Governance Rules 2003 rules 5.13 and 5.14 section II part G

Clause 13.36: revoked, on 5 October 2017, by clause 349 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

## *Offering instantaneous reserve*

### 13.37 System operator to approve ancillary service agents wishing to make reserve offers

Before an **ancillary service agent** makes a **reserve offer** under clauses 13.38 to 13.54, the **ancillary service agent** must have a valid and enforceable contract with the **system operator** to provide **reserve offers** in accordance with this Code.

Compare: Electricity Governance Rules 2003 rule 6.1 section II part G

### 13.38 Ancillary service agents to submit reserve offers to system operator

- (1) Each **ancillary service agent** who has a contract described in clause 13.37 may submit **reserve offers** to the **system operator**.
- (1A) An **ancillary service agent** who submits a **reserve offer** must ensure that the **system operator** receives the **reserve offer** at least 71 **trading periods** before the beginning of the **trading period** to which the **reserve offer** applies.
- (2) Each **reserve offer** submitted by an **ancillary service agent** under subclause (1) may be for **fast instantaneous reserve**, **sustained instantaneous reserve** or both and must—
  - (a) contain all the information required by Form 5 in Schedule 13.1 for **partly loaded spinning reserve** or **tail water depressed reserve**; and
  - (b) contain all the information required by Form 6 in Schedule 13.1 for **interruptible load**; and
  - (c) be a reasonable estimate of the quantity of **instantaneous reserve** available from the **ancillary service agent** at that **grid injection point**, **grid exit point** or **interruptible load group GXP**.

- (3) Each **reserve offer** submitted under subclause (1), by an **ancillary service agent** that is a **generator**, must be made by reference to the same **generating unit** or **generating station** that is the subject of an **offer** under clauses 13.10 or 13.11.

Compare: Electricity Governance Rules 2003 rules 6.2 to 6.4 section II part G

Clause 13.38(1): substituted, on 28 June 2012, by clause 25 of the Electricity Industry Participation (Demand-side Bidding and Forecasting) Code Amendment 2011.

Clause 13.38(1A): inserted, on 28 June 2012, by clause 25 of the Electricity Industry Participation (Demand-side Bidding and Forecasting) Code Amendment 2011.

Clause 13.38(1A): amended, on 1 November 2012, by clause 5 of the Electricity Industry Participation (Part 13 Minor Amendments) Code Amendment 2012.

Clause 13.38(3): amended, on 15 May 2014, by clause 38 of the Electricity Industry Participation (Minor Code Amendments) Code Amendment 2014.

### 13.39 Inter-relationship between reserve and energy offers

**Reserve offers** and **offers** made under clauses 13.38(1) and 13.6(1) to (3) respectively, if they are in respect of the same individual **generating unit** or individual **generating station** (as required under clauses 13.10 and 13.11), are inter-related in that the greater the energy **dispatched** the lower the **instantaneous reserve** may be and vice versa. Accordingly, an **ancillary service agent** that is a **generator** does not breach clauses 13.9(b) or 13.38(2)(c) if the **offer** quantity under clauses 13.6 to 13.27 and quantity of **instantaneous reserve** offered under clauses 13.37 to 13.54 are duplicated, and the **ancillary service agent** must not be scheduled by the **system operator** and a **dispatch instruction** from the **system operator** must not be given the effect of which is that the combined dispatch quantity and **instantaneous reserve** exceeds the capacity of the individual **generating unit** or individual **generating station**, as the case may be.

Compare: Electricity Governance Rules 2003 rule 6.5 section II part G

Clause 13.39: amended, on 15 May 2014, by clause 39 of the Electricity Industry Participation (Minor Code Amendments) Code Amendment 2014.

### 13.40 Inter-relationship between reserve offers of interruptible load and bids

**Bids** and **reserve offers** of **interruptible load** are inter-related in that **demand electrically connected** in response to an **under-frequency event** and in accordance with a dispatched **reserve offer** may lower the quantity purchased at that **grid exit point**. Accordingly, a **purchaser** does not breach the reasonable estimate requirement in clauses 13.7(3), 13.7AA(2), and 13.8A(4) if the **purchaser** is acting as an **ancillary service agent** and **electrically disconnects** corresponding **demand** in response to an **under-frequency event** in accordance with a dispatched **reserve offer**.

Compare: Electricity Governance Rules 2003 rule 6.6 section II part G

Clause 13.40 Heading: amended, on 15 May 2014, by clause 16(a) of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

Clause 13.40: amended, on 28 June 2012, by clause 26 of the Electricity Industry Participation (Demand-side Bidding and Forecasting) Code Amendment 2011.

Clause 13.40: amended, on 15 May 2014, by clause 16(b) of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

Clause 13.40: amended, on 5 October 2017, by clause 350 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

#### 13.41 Reserve offers may contain up to 3 price bands

Each **reserve offer** submitted by an **ancillary service agent** may, for each type of **instantaneous reserve**, have a maximum of 3 price bands for each **trading period**. The price offered in each band must increase progressively from band to band as the aggregate quantity increases.

Compare: Electricity Governance Rules 2003 rule 6.7 section II part G

#### 13.42 How price to be specified in reserve offers

When submitting a **reserve offer** under clause 13.38, an **ancillary service agent**—

- (a) must express the price in each band in dollars and whole cents per MW excluding GST; and
- (b) must specify a price that is equal to or greater than \$0.00/MW.

Compare: Electricity Governance Rules 2003 rule 6.8 section II part G

Clause 13.42: substituted, on 1 November 2012, by clause 6 of the Electricity Industry Participation (Part 13 Minor Amendments) Code Amendment 2012.

#### 13.43 *[Revoked]*

Compare: Electricity Governance Rules 2003 rule 6.9 section II part G

Clause 13.43: revoked, on 1 November 2012, by clause 7 of the Electricity Industry Participation (Part 13 Minor Amendments) Code Amendment 2012.

#### 13.44 How quantity is to be specified in reserve offers

For each price band, a **reserve offer** must specify the quantity of **instantaneous reserve** offered to respond as **fast instantaneous reserves** or **sustained instantaneous reserves** as a proportion of **electricity** output or consumption up to a specified maximum quantity or as a quantity available to be interrupted, and must be expressed in MW to not more than 3 decimal places. The minimum quantity that may be offered in a price band for a **trading period** is 0.000 MW.

Compare: Electricity Governance Rules 2003 rule 6.10 section II part G

Clause 13.44: amended, on 15 May 2014, by clause 40 of the Electricity Industry Participation (Minor Code Amendments) Code Amendment 2014.

Clause 13.44: amended, on 29 June 2017, by clause 26 of the Electricity Industry Participation Code Amendment (Shortened Gate Closure and Revised Bid and Offer Provisions) 2017.

#### 13.45 Reserve offers revised if energy offers revised

An **ancillary service agent** that has made a **reserve offer** must revise the **reserve offer** if it has, in accordance with clauses 13.6 to 13.27, revised the **offer** made in respect of the equivalent item of **generating plant**.

Compare: Electricity Governance Rules 2003 rule 6.11 section II part G

Clause 13.45: amended, on 29 June 2017, by clause 27 of the Electricity Industry Participation Code Amendment (Shortened Gate Closure and Revised Bid and Offer Provisions) 2017.

#### 13.46 Reserve offers may be revised

- (1) Subject to subclauses (1A) and (1B), an **ancillary service agent** may revise a **reserve offer** at any time before the beginning of the **trading period** in respect of which the **reserve offer** is made by submitting a new **reserve offer** to the **system operator**.
- (1A) An **ancillary service agent** must not revise its **reserve offer** prices during a **gate closure period**.

- (1B) An **ancillary service agent** must not revise the **MW** specified in any price band in a **reserve offer** during a **gate closure period** unless subclause (3) or clause 13.47 applies.
- (2) An **ancillary service agent** that revises a **reserve offer** for an **embedded generating station** must use reasonable endeavours to submit the **reserve offer** at least 1 hour before the beginning of the **trading period** in respect of which the **reserve offer** is made.
- (3) Before the beginning of the **trading period** to which the **reserve offer** applies, and despite clauses 13.97 to 13.101, an **ancillary service agent** must immediately submit a revised **reserve offer** in respect of **MW** offered to the **system operator** if—
- (a) the **MW** specified in any price band in the **reserve offer** no longer represents a reasonable estimate of the **instantaneous reserve** available from the **ancillary service agent** at the **grid injection point**, **grid exit point** or **interruptible load group GXP**; or
  - (b) the relevant **MW** specified in the **non-response schedule** most recently **published** by the **system operator** is not likely to be achieved by the **ancillary service agent** at the relevant **grid injection point**, **grid exit point** or **interruptible load group GXP**.
- (4) *[Revoked]*

Compare: Electricity Governance Rules 2003 rules 6.12 and 6.13 section II part G  
Clause 13.46 Heading: amended, on 29 June 2017, by clause 28(1) of the Electricity Industry Participation Code Amendment (Shortened Gate Closure and Revised Bid and Offer Provisions) 2017.  
Clause 13.46(1): replaced, on 29 June 2017, by clause 28(2) of the Electricity Industry Participation Code Amendment (Shortened Gate Closure and Revised Bid and Offer Provisions) 2017.  
Clause 13.46(1A) and (1B): inserted, on 29 June 2017, by clause 28(2) of the Electricity Industry Participation Code Amendment (Shortened Gate Closure and Revised Bid and Offer Provisions) 2017.  
Clause 13.46(2): replaced, on 29 June 2017, by clause 28(3) of the Electricity Industry Participation Code Amendment (Shortened Gate Closure and Revised Bid and Offer Provisions) 2017.  
Clause 13.46(3): amended, on 29 June 2017, by clause 28(4)(a) and (b) of the Electricity Industry Participation Code Amendment (Shortened Gate Closure and Revised Bid and Offer Provisions) 2017.  
Clause 13.46(3)(a): amended, on 29 June 2017, by clause 28(4)(c) of the Electricity Industry Participation Code Amendment (Shortened Gate Closure and Revised Bid and Offer Provisions) 2017.  
Clause 13.46(3)(b): amended, on 28 June 2012, by clause 27 of the Electricity Industry Participation (Demand-side Bidding and Forecasting) Code Amendment 2011.  
Clause 13.46(3)(b): amended, on 29 June 2017, by clause 28(4)(d)(i) and (ii) of the Electricity Industry Participation Code Amendment (Shortened Gate Closure and Revised Bid and Offer Provisions) 2017.  
Clause 13.46(4): revoked, on 29 June 2017, by clause 28(5) of the Electricity Industry Participation Code Amendment (Shortened Gate Closure and Revised Bid and Offer Provisions) 2017.

#### 13.47 MW change during gate closure period

- (1) An **ancillary service agent** may revise a **reserve offer** during a **gate closure period** if—
- (a) the revision is necessary due to a **bona fide physical reason**; or
  - (b) the **system operator** issues a **formal notice** under clause 5 of **Technical Code B** of Schedule 8.3; or
  - (c) a **bona fide physical reason** that made a revision necessary under paragraph (a) ceases to exist sooner than was expected at the time it arose, and—
    - (i) the 1st **trading period** after the original **bona fide physical reason** ceases to exist is within 24 hours after the circumstances that constituted the original **bona fide physical reason** arose; and

- (ii) the total change in **MW** specified in the **reserve offer** that is revised as a result of the **bona fide physical reason** ceasing to exist is the same or less than the total change in **MW** specified in the **reserve offer** that was made as a result of the original **bona fide physical reason**.

(2) *[Revoked]*

Compare: Electricity Governance Rules 2003 rule 6.14 section II part G  
Clause 13.47 Heading: replaced, on 29 June 2017, by clause 29(1) of the Electricity Industry Participation Code Amendment (Shortened Gate Closure and Revised Bid and Offer Provisions) 2017.  
Clause 13.47(1): replaced, on 29 June 2017, by clause 29(2) of the Electricity Industry Participation Code Amendment (Shortened Gate Closure and Revised Bid and Offer Provisions) 2017.  
Clause 13.47(2): amended, on 15 May 2014, by clause 41 of the Electricity Industry Participation (Minor Code Amendments) Code Amendment 2014.  
Clause 13.47(2): revoked, on 29 June 2017, by clause 29(3) of the Electricity Industry Participation Code Amendment (Shortened Gate Closure and Revised Bid and Offer Provisions) 2017.

### 13.48 System operator advised of revised reserve offers in certain circumstances

- (1) This clause applies to each **ancillary service agent** that submits a revised **reserve offer** during the 15 minutes immediately preceding the **trading period** to which the revised **reserve offer** relates.
- (2) The **ancillary service agent** must immediately advise the **system operator** of the revision.

Compare: Electricity Governance Rules 2003 rule 6.15 section II part G  
Clause 13.48 Heading: amended, on 5 October 2017, by clause 351(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.  
Clause 13.48: substituted, on 29 June 2017, by clause 30 of the Electricity Industry Participation Code Amendment (Shortened Gate Closure and Revised Bid and Offer Provisions) 2017.  
Clause 13.48(2): amended, on 5 October 2017, by clause 351(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017

### 13.49 Authority advised of revised reserve offer during gate closure period

- (1) An **ancillary service agent** that submits a revised **reserve offer** to the **system operator** during a **gate closure period** must report each revision to the **Authority** in writing together with an explanation of the reason for the revision.
- (2) The **ancillary service agent** must report a revision to the **Authority** no later than 1700 hours on the 1st **business day** following the **trading day** on which it made the revision.

Compare: Electricity Governance Rules 2003 rule 6.16 section II part G  
Clause 13.49 Heading: amended, on 5 October 2017, by clause 352 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.  
Clause 13.49: substituted, on 29 June 2017, by clause 31 of the Electricity Industry Participation Code Amendment (Shortened Gate Closure and Revised Bid and Offer Provisions) 2017.

### 13.50 System operator to advise Authority of revision of reserve offers

- (1) The **system operator** must advise the **Authority** of any revision of the availability of reserves that are provided under **ancillary services** contracts not covered by clauses 13.37 to 13.54.
- (1A) The **system operator** must advise the **Authority** of a revision no later than 1700 hours on the 1st **business day** following the **trading day** on which the revision was made.
- (2) *[Revoked]*

Compare: Electricity Governance Rules 2003 rules 6.17 and 6.18 section II part G  
Clause 13.50 Heading: amended, on 29 June 2017, by clause 32(1) of the Electricity Industry Participation Code Amendment (Shortened Gate Closure and Revised Bid and Offer Provisions) 2017.

Clause 13.50(1): amended, on 29 June 2017, by clause 32(2)(a) and (b) of the Electricity Industry Participation Code Amendment (Shortened Gate Closure and Revised Bid and Offer Provisions) 2017.

Clause 13.50(1A): inserted, on 29 June 2017, by clause 32(3) of the Electricity Industry Participation Code Amendment (Shortened Gate Closure and Revised Bid and Offer Provisions) 2017.

Clause 13.50(2): revoked, on 29 June 2017, by clause 32(4) of the Electricity Industry Participation Code Amendment (Shortened Gate Closure and Revised Bid and Offer Provisions) 2017.

### 13.51 Transmission of reserve offers

- (1) All **reserve offers** or cancellations of **reserve offers** submitted by an **ancillary service agent** under clauses 13.37 to 13.54 must be transmitted to the **system operator** through **WITS**.
- (2) The **system operator** must immediately confirm receipt to the **ancillary service agent** of all **reserve offers** or cancellations of **reserve offers** received from the **ancillary service agent** through **WITS**. Such confirmation must also contain a copy of the **reserve offer** or cancellation of **reserve offer** received by the **system operator**, together with the time of receipt.
- (3) If an **ancillary service agent** has not received confirmation that the **system operator** has received its **reserve offer** or cancellation of a **reserve offer** within 10 minutes after the **ancillary service agent** submitted the **reserve offer** or cancellation of a **reserve offer**, the **ancillary service agent** must check whether the **system operator** has received the **reserve offer** or cancellation of a **reserve offer**. If the **system operator** has not received the **reserve offer** or cancellation of a **reserve offer**, the **ancillary service agent** must resend the **reserve offer** or cancellation of a **reserve offer**. The processes set out in this clause must then be repeated until the **system operator** confirms receipt of the **reserve offer** or cancellation of a **reserve offer** from the **ancillary service agent**.

Compare: Electricity Governance Rules 2003 rules 6.19 to 6.21 section II part G

Clause 13.51 Heading: amended, on 5 October 2017, by clause 353(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 13.51(1) and (2): amended, on 5 October 2017, by clause 353(2)(a) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 13.51(3): replaced, on 5 October 2017, by clause 351(2)(b) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### 13.52 Backup procedures if WITS is unavailable

- (1) If **WITS** is unavailable to receive **reserve offers** or cancellations of **reserve offers** or to confirm the receipt of such **reserve offers** or cancellations, an **ancillary service agent** or the **system operator**, as the case may be, must follow the backup procedures specified by the **WITS manager**.
- (2) The backup procedures referred to in subclause (1) must be specified by the **WITS manager** following consultation with the **Authority**, **ancillary service agents** and the **system operator**.

Compare: Electricity Governance Rules 2003 rules 6.22 and 6.23 section II part G

Clause 13.52 Heading: amended, on 5 October 2017, by clause 354(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 13.52: amended, on 5 October 2017, by clause 354(2), (3) and (4) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.



### 13.53 Additional information to be provided by participants

Despite clauses 13.22, 13.23, 13.51, and 13.52, if an **ancillary service agent** submits a **reserve offer** for **partly loaded spinning reserve** or **tail water depressed reserve** in accordance with clauses 13.37 to 13.54, the **ancillary service agent** must also provide the following information in relation to the capability to provide **partly loaded spinning reserve** or **tail water depressed reserve** to the **system operator** in a manner and at such times as are approved by the **system operator** (such approval not to be unreasonably withheld):

- (a) the maximum quantity of fast response **partly loaded spinning reserve** expressed in **MW** and the maximum quantity of sustained response **partly loaded spinning reserve** expressed in **MW**;
- (b) the maximum quantity of fast response **tail water depressed reserve** expressed in **MW** and the maximum quantity of sustained response **tail water depressed reserve** expressed in **MW**.

Compare: Electricity Governance Rules 2003 rule 6.24 section II part G

Clause 13.53: amended, on 15 May 2014, by clause 42 of the Electricity Industry Participation (Minor Code Amendments) Code Amendment 2014.

### 13.54 System operator to retain reserve offers

The **system operator** must retain, in a form that it considers appropriate, all **reserve offers** submitted by all **ancillary service agents** in accordance with this subpart, including all revised **reserve offers**.

Compare: Electricity Governance Rules 2003 rule 6.25 section II part G

Clause 13.54: amended, on 29 June 2017, by clause 33 of the Electricity Industry Participation Code Amendment (Shortened Gate Closure and Revised Bid and Offer Provisions) 2017.

### 13.55 Availability of bids, offers, and reserve offers

- (1) The **WITS manager** must, within 24 hours of the end of each day, make available on **WITS** and at no cost on a publicly accessible **approved system**, all final **bids**, final **offers** and final **reserve offers** received for the **trading periods** of the previous **trading day**.
- (2) All information made available on **WITS** and on the publicly accessible **approved system** must remain available for inspection for a period of at least 4 weeks—
  - (a) on **WITS**; and
  - (b) at no cost on the publicly accessible **approved system**.
- (3) If **WITS** is unavailable for the purposes of subclause (2)(a), the **WITS manager** must follow the backup procedures specified by the **WITS manager** from time to time.
- (4) The backup procedures referred to in subclause (3) must be put in place by the **WITS manager** in consultation with the **Authority**, **purchasers**, **generators** and **ancillary service agents**.
- (5) If the publicly accessible **approved system** is not available for the purposes of subclause (2)(b), the **WITS manager** is not obliged to follow any backup procedures, but the **WITS manager** must make the information available at no cost as soon as practicable once the publicly accessible **approved system** becomes available.
- (6) *[Revoked]*
- (7) *[Revoked]*

Compare: Electricity Governance Rules 2003 rule 7 section II part G

Clause 13.55 Heading: amended, on 28 June 2012, by clause 28(1) of the Electricity Industry Participation (Demand-side Bidding and Forecasting) Code Amendment 2011.

Clause 13.55(1): amended, on 5 October 2017, by clause 355(1) and (2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 13.55(2): replaced, on 5 October 2017, by clause 355(3) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 13.55(3): amended, on 5 October 2017, by clause 355(1) and (4) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 13.55(4): amended, on 5 October 2017, by clause 355(1) and (5) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 13.55(5): replaced, on 5 October 2017, by clause 355(6) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 13.55(6) and (7): revoked, on 28 June 2012, by clause 28(2) of the Electricity Industry Participation (Demand-side Bidding and Forecasting) Code Amendment 2011.

### 13.55A System operator to make information available

- (1) The **system operator** must retain, for at least 2 years,—
  - (a) information about all **bids**, cancelled **bids**, **offers**, cancelled **offers**, **reserve offers**, and cancelled **reserve offers** submitted by a **purchaser**, **generator**, or **ancillary service agent** for a **trading period**; and
  - (b) each forecast prepared under clause 13.7A(1).
- (2) Any person may request that the **system operator** make available any of the information described in subclause (1) for any **trading period** that occurred at least 1 day before the date of the request.
- (3) The **system operator** must make the requested information available in a manner, and for a fee, that is reasonable having regard to the size and nature of the request.

Clause 13.55A: inserted, on 28 June 2012, by clause 29 of the Electricity Industry Participation (Demand-side Bidding and Forecasting) Code Amendment 2011.

Clause 13.55A(1)(b): amended, on 15 May 2014, by clause 17 of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

## Subpart 2—Scheduling and dispatch

### 13.56 Contents of this subpart

This subpart specifies—

- (a) the **system operator's dispatch objective**; and
- (b) the process for preparing a **price-responsive schedule** and **non-response schedule**, including the contents of and inputs for those schedules; and
- (c) the process by which the **system operator** prepares a **dispatch schedule**; and
- (d) the process by which the **system operator** prepares and issues **dispatch instructions**; and
- (e) the requirement for **generators**, **ancillary service agents**, and **dispatched purchasers** to comply with **dispatch instructions**; and
- (f) the process for preparation and **publication** by the **system operator** of the schedule of **real time prices**; and
- (g) the implications of a **grid emergency** for **bids**, **offers** and **reserve offers**; and
- (h) the **system operator's** reporting obligations; and
- (i) the requirement for the **system operator** to **publish** scheduling information.

Compare: Electricity Governance Rules 2003 rule 1 section III part G

Clause 13.56: substituted, on 28 June 2012, by clause 30 of the Electricity Industry Participation (Demand-side Bidding and Forecasting) Code Amendment 2011.

Clause 13.56(e): amended, on 15 May 2014, by clause 18 of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

### 13.57 The dispatch objective

The **system operator's dispatch objective** is to maximise for each **half hour** the gross economic benefits to all **purchasers of electricity** at the **grid exit points**, less the cost of supplying the **electricity** at the **grid injection points** and the costs of **ancillary services** purchased by the **system operator** under subpart 3 of Part 8, in accordance with the methodology set out in Schedule 13.3, subject to—

- (a) the capability of generation, **dispatch-capable load stations** for which a **nominated dispatch bid** was submitted, and **ancillary services** and the configuration and capacity of the **grid** and information made available by **asset owners**; and
- (b) achieving the **principal performance obligations** and any arrangements of the type described in clause 8.6; and
- (c) meeting the requirements of clause 8.5 in relation to restoration of the power system—

provided that in the case of any conflict between paragraphs (b) and (c), paragraph (c) takes priority.

Compare: Electricity Governance Rules 2003 rule 2 section III part G

Clause 13.57(a): amended, on 15 May 2014, by clause 19 of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

### 13.58 Process for preparing price-responsive schedule and non-response schedule

- (1) The **system operator** must prepare—
  - (a) a **price-responsive schedule**; and
  - (b) a **non-response schedule**.
- (1A) The **system operator** must prepare the schedules listed in subclause (1) in accordance with the timing required under clause 13.62.
- (2) *[Revoked]*
- (3) *[Revoked]*
- (3A) In preparing each **price-responsive schedule**, the **system operator** must—
  - (a) use the most recent information received under subpart 1; and
  - (b) use all other information described in clause 13.58A(1); and
  - (c) act in accordance with Schedule 13.3.
- (3B) In preparing each **non-response schedule**, the **system operator** must—
  - (a) use the most recent information received under subpart 1; and
  - (b) use all other information described in clause 13.58A(2); and
  - (c) act in accordance with Schedule 13.3.
- (4) As soon as practicable after the **system operator** has completed preparing a **price-responsive schedule** and a **non-response schedule**, the **system operator** must make the schedules available to the **clearing manager** using **WITS**.

Compare: Electricity Governance Rules 2003 rules 3.1 to 3.4 section III part G

Clause 13.58(1): substituted, on 28 June 2012, by clause 31 of the Electricity Industry Participation (Demand-side Bidding and Forecasting) Code Amendment 2011.

Clause 13.58(1A): inserted, on 28 June 2012, by clause 31 of the Electricity Industry Participation (Demand-side Bidding and Forecasting) Code Amendment 2011.

Clause 13.58(2) and (3): revoked, on 28 June 2012, by clause 31 of the Electricity Industry Participation (Demand-side Bidding and Forecasting) Code Amendment 2011.

Clause 13.58(3A) and (3B): inserted, on 28 June 2012, by clause 31 of the Electricity Industry Participation (Demand-side Bidding and Forecasting) Code Amendment 2011.

Clause 13.58(4): substituted, on 28 June 2012, by clause 31 of the Electricity Industry Participation (Demand-side Bidding and Forecasting) Code Amendment 2011.

Clause 13.58(4): amended, on 5 October 2017, by clause 356 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### 13.58A Inputs for price-responsive schedule and non-response schedule

- (1) The **system operator** must prepare a **price-responsive schedule** using the following inputs:
  - (a) **offers** and **reserve offers**; and
  - (b) **nominated bids**; and
  - (c) the forecast prepared by the **system operator** under clause 13.7A(1); and
  - (d) **difference bids**; and
  - (e) information provided to the **system operator** by a **grid owner** under clauses 13.29 to 13.34 about—
    - (i) the AC transmission system configuration, capacity, and **losses**; and
    - (ii) the capability of the **HVDC link** including its **configuration**, capacity, **losses**, the direction of any transfer limit, and any minimum or maximum transfer limits; and
    - (iii) transformer configuration, capacity, and **losses**; and
  - (f) the adjustments specified in subclause (2)(e), subject to any exceptions specified in the **policy statement**; and
  - (g) information about **voltage support** from contracts held by the **system operator** under the **procurement plan**; and
  - (h) information from **ancillary service agents** about **instantaneous reserves** procured under the **procurement plan**.
- (2) The **system operator** must prepare a **non-response schedule** using the following inputs:
  - (a) **offers**, **nominated dispatch bids**, and **reserve offers**; and
  - (b) **nominated non-dispatch bid** quantities; and
  - (c) the forecast prepared by the **system operator** under clause 13.7A(1); and
  - (d) information provided to the **system operator** by a **grid owner** under clauses 13.29 to 13.34 referring to—
    - (i) the AC transmission system configuration, capacity, and **losses**; and
    - (ii) the capability of the **HVDC link** including its **configuration**, capacity, **losses**, the direction of any transfer limit, and any minimum or maximum transfer limits; and
    - (iii) transformer configuration, capacity, and **losses**; and
  - (e) adjustments made by the **system operator** under clause 13(1) of Schedule 13.3, in order to meet the **dispatch objective**; and
  - (f) information about **voltage support** from contracts held by the **system operator** under the **procurement plan**; and

- (g) information from **ancillary service agents** about **instantaneous reserves** procured under the **procurement plan**.

Clause 13.58A: inserted, on 28 June 2012, by clause 32 of the Electricity Industry Participation (Demand-side Bidding and Forecasting) Code Amendment 2011.

Clause 13.58A(1)(e)(ii): substituted, on 1 November 2012, by clause 5(1) of the Electricity Industry Participation (HVDC Link Pole 3 Standing Data) Code Amendment 2012.

Clause 13.58A(2)(d)(ii): substituted, on 1 November 2012, by clause 5(2) of the Electricity Industry Participation (HVDC Link Pole 3 Standing Data) Code Amendment 2012.

Clause 13.58A(1)(c): amended, on 15 May 2014, by clause 20 of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

Clause 13.58A(2)(a) – (c): amended, on 15 May 2014, by clause 20 of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

### 13.59 Contents of each price-responsive schedule and non-response schedule

For each **trading period** in the **schedule length period**,—

- (a) each **price-responsive schedule** and each **non-response schedule** prepared by the **system operator** must specify—
- (i) the expected average level of **electricity** output for each **generating plant** or **generating unit**; and
  - (ii) the expected average level of **instantaneous reserve** for each **generating plant** or **generating unit**; and
  - (iii) the expected average level of **interruptible load** for each **ancillary service agent** for each **grid exit point** or **interruptible load group grid exit point**; and
  - (iv) the indicative **frequency keeping units** for each **island**; and
  - (v) the expected average level of **demand** at each **grid exit point**; and
  - (vi) **forecast prices**; and
  - (vii) **forecast reserve prices**; and
  - (viii) **forecast marginal location factors** for each **grid injection point** and each **grid exit point**; and
  - (ix) the expected largest single reserve risk for each **island**; and
  - (x) the expected level of **fast instantaneous reserve** and **sustained instantaneous reserve** required in each **island**; and
  - (xi) a stack of **reserve offers** for each **island** (ranking in price order from lowest to highest), and for each **island** separate stacks must be provided for **fast instantaneous reserve** and **sustained instantaneous reserve**; and
  - (xii) a stack of all **reserve offers** for each **island** (ranking in price order from lowest to highest) adjusted for the expected level of energy output for each **generating plant** or **generating unit**, and for each **island** separate stacks must be provided for **fast instantaneous reserve** and **sustained instantaneous reserve**; and
  - (xiii) the expected **HVDC component flows**; and
  - (xiv) the expected **HVDC risk offsets**; and
  - (xv) the **expected near-constraint arc flows**; and
  - (xvi) the **expected near-group-constraint arc flows**; and
  - (xvii) the **group constraint formulas** relating to the **expected near-group-constraint arc flows**; and

- (xviii) the expected deficit quantities for energy, **fast instantaneous reserve**, and **sustained instantaneous reserve** (if any); and
- (xix) whether the **HVDC link** is out of service; and
- (b) each **price-responsive schedule** prepared by the **system operator** must specify the expected quantities for each **bid**; and
- (c) each **non-response schedule** prepared by the **system operator** must specify the expected—
  - (i) **non-dispatch-capable load** at each **conforming GXP**; and
  - (ii) **demand** for each **nominated bid**.

Compare: Electricity Governance Rules 2003 rule 3.5 section III part G

Clause 13.59: substituted, on 28 June 2012, by clause 33 of the Electricity Industry Participation (Demand-side Bidding and Forecasting) Code Amendment 2011.

Clause 13.59(a)(iv): amended, on 3 October 2013, by clause 5 of the Electricity Industry Participation (Technology Neutral Language in Frequency Keeping) Code Amendment 2013.

Clause 13.59(a)(xviii) and (xix): inserted, on 1 June 2013, by clause 6 of the Electricity Industry Participation (Scarcity Pricing) Code Amendment 2011.

Clause 13.59(c): substituted, on 15 May 2014, by clause 21 of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

### 13.60 Block dispatch may occur

- (1) A **generator** and the **system operator** may agree to treat a group of **generating stations** as a **block dispatch group**.
- (2) If an agreement for block dispatch has been reached, the following procedures apply:
  - (a) the **generator** must give written notice to the **system operator** and the **clearing manager** of the agreement, at least **5 business days** before the agreement takes effect, specifying—
    - (i) the **trading day** and the **trading period** in which the agreement will take effect; and
    - (ii) the **generating stations** that are the subject of the agreement; and
    - (iii) the terms of the agreement; and
  - (b) the **system operator** must identify in each **non-response schedule** the **generating stations** or **generating units** that are part of a **block dispatch group**.
- (3) The **generator** must give written notice to the **system operator** and the **clearing manager** of any change to an agreement for **block dispatch** made under this clause or clause 13.61 at least **5 business days** before the change takes effect.

Compare: Electricity Governance Rules 2003 rules 3.6 to 3.6.2 section III part G

Clause 13.60(2)(a) and (3): amended, on 5 October 2017, by clause 357 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 13.60(2)(b): amended, on 28 June 2012, by clause 34 of the Electricity Industry Participation (Demand-side Bidding and Forecasting) Code Amendment 2011.

Clause 13.60(3): inserted, on 15 May 2014, by clause 43 of the Electricity Industry Participation (Minor Code Amendments) Code Amendment 2014.

### 13.61 System operator to give notice of block security constraints

- (1) The **system operator** must give notice on **WITS** to **generators** of the implication of any **block security constraints** that apply within the **block dispatch group**. The notice must include—
  - (a) the **trading periods** for which the **block security constraint** applies; and

- (b) how the **block security constraint** divides the **generating stations** or **generating units** of a **block dispatch group** into **sub-block dispatch groups**.
- (2) If a notice has been sent in accordance with subclause (1), the notice remains valid until the earliest of—
  - (a) completion of the **trading periods** set out in the notice; or
  - (b) receipt of another notice from the **system operator** in accordance with subclause (1) for the same **block dispatch group** for the same **trading period** or **trading periods**; or
  - (c) receipt of a notice from the **system operator** that the **block security constraint** no longer exists; or
  - (d) receipt of an instruction from the **system operator** in accordance with clause 13.75(f) for the same **block dispatch group** for the applicable **trading period**, and such instruction remains valid for the **trading periods** specified in that instruction.

(3) *[Revoked]*

Compare: Electricity Governance Rules 2003 rules 3.6.3 to 3.6.5 section III part G

Clause 13.61 Heading: amended, on 5 October 2017, by clause 358(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 13.61(1): amended, on 5 October 2017, by clause 358(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 13.61(1)(a) and (b): amended, on 1 February 2016, by clause 79(1) and (2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

Clause 13.61(2)(c): amended, on 1 February 2016, by clause 79(3) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

Clause 13.61(2)(c): amended, on 5 October 2017, by clause 358(3) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 13.61(3): revoked, on 15 May 2014, by clause 44 of the Electricity Industry Participation (Minor Code Amendments) Code Amendment 2014.

### 13.62 Frequency of price-responsive schedules and non-response schedules

- (1) The **system operator** must use reasonable endeavours to commence preparing a **price-responsive schedule** and a **non-response schedule**—
  - (a) once in every 4th **trading period** throughout the **trading day**, for a period covering—
    - (i) the **trading period** in which the **system operator** commences preparing the relevant schedule; and
    - (ii) the following 71 **trading periods**; and
  - (b) once in each **trading period** for a period covering—
    - (i) the **trading period** in which the **system operator** commences preparing the relevant schedule; and
    - (ii) the following 7 **trading periods**.
- (2) The **system operator** must use reasonable endeavours to ensure that—
  - (a) each time it prepares a **price-responsive schedule**, it prepares a **non-response schedule** at the same time; and
  - (b) each time it prepares a **non-response schedule**, it prepares a **price-responsive schedule** at the same time.
- (3) The **system operator** must complete a schedule—

- (a) if it commenced preparing the schedule under subclause (1)(a), by the end of the **trading period** after the **trading period** in which the **system operator** commenced preparing the schedule; and
- (b) if it commenced preparing the schedule under subclause (1)(b), by the end of the **trading period** in which the **system operator** commenced preparing the schedule.

Compare: Electricity Governance Rules 2003 rule 3.7 section III part G  
Clause 13.62: substituted, on 28 June 2012, by clause 35 of the Electricity Industry Participation (Demand-side Bidding and Forecasting) Code Amendment 2011.

### 13.63 Trading period information to be made available to pricing manager and clearing manager

The **system operator** must, by 0730 hours of each **trading day**, make the final information provided to the **system operator** under subpart 1 in relation to each **trading period** of the previous **trading day** available to the **pricing manager** and **clearing manager** on **WITS** or through an **approved system**.

Compare: Electricity Governance Rules 2003 rule 3.8 section III part G  
Clause 13.63 Heading: amended, on 5 October 2017, by clause 359(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.  
Clause 13.63: amended, on 5 October 2017, by clause 359(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### 13.64 Station dispatch may occur

- (1) A **generator** may elect to have its **generating plant dispatched** as a **station dispatch group** by giving the **system operator** at least 15 **business days'** notice in writing in the form set out in Form 8 of Schedule 13.1. The **system operator** must use best endeavours to implement the election within 15 **business days** after receiving the notice.
- (2) The **system operator** must give written notice to the **generator** and the **clearing manager** of the effective date of the election at least 5 **business days** before the date. On and from the effective date, the procedures set out in clauses 13.65 and 13.66 must be followed by the **system operator** and the **generator**.

Compare: Electricity Governance Rules 2003 rule 3.9 section III part G  
Clause 13.64(2): amended, on 5 October 2017, by clause 360 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### 13.65 System operator to give notice of station security constraints

- (1) The **system operator** must give notice on **WITS** to the **generator** of the implication of any **station security constraints** that apply within a **station dispatch group**. The notice must include—
  - (a) the **trading periods** for which the **station security constraint** applies; and
  - (b) how the **station security constraint** divides the **generating units** or **generating stations** of a **station dispatch group** into a **sub-station dispatch group** or limits the generation of a **station dispatch group**.
- (2) If a notice has been sent in accordance with subclause (1), the notice remains valid until the earliest of—
  - (a) completion of the **trading periods** set out in the notice; or



- (b) receipt of another notice from the **system operator** in accordance with subclause (1) for the same **station dispatch group** for the same **trading period** or **trading periods**; or
- (c) receipt of a notice from the **system operator** that the **station security constraint** no longer exists; or
- (d) receipt of an instruction from the **system operator** in accordance with clause 13.75(g) for the same **station dispatch group** for the applicable **trading period**, and the instruction remains valid for the **trading periods** specified in the instruction.

Compare: Electricity Governance Rules 2003 rules 3.9.1 and 3.9.2 section III part G

Clause 13.65 Heading: amended, on 5 October 2017, by clause 361(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 13.65(1): amended, on 5 October 2017, by clause 361(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 13.65(2)(c): amended, on 5 October 2017, by clause 361(3) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### 13.66 Generator gives written notice of change from station to unit dispatch

If a **generator** changes the dispatch of its **generating plant** from a **station dispatch group** basis to a **generating unit** basis, it must give the **system operator** at least 15 **business days**’ notice in writing. The **system operator** must use best endeavours to implement the change within 15 **business days** of receiving a notice. The **system operator** must give written notice to the **generator** and the **clearing manager** of the effective date of the change at least 5 **business days** before the date.

Compare: Electricity Governance Rules 2003 rule 3.9.3 section III part G

Clause 13.66 Heading: amended, on 5 October 2017, by clause 362(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 13.66: amended, on 5 October 2017, by clause 362(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### 13.67 Transmission of information

- (1) *[Revoked]*
- (2) If **WITS** or the publicly accessible **approved system** is unavailable for the purposes of making information available under clauses 13.58 to 13.66, the **system operator** must follow the backup procedures specified by the **WITS manager**.
- (3) The **WITS manager** must specify the backup procedures referred to in subclause (2) following consultation with the **Authority**, the **system operator**, the **clearing manager**, and the **pricing manager**.

Compare: Electricity Governance Rules 2003 rules 3.10 to 3.12 section III part G

Clause 13.67 Heading: amended, on 5 October 2017, by clause 363(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 13.67(1): revoked, on 5 October 2017, by clause 363(2)(a) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 13.67(2) and (3): replaced, on 5 October 2017, by clause 363(2)(b) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### *The dispatch process*

### 13.68 Receipt of new non-response schedule supersedes old schedule *[Revoked]*

Compare: Electricity Governance Rules 2003 rule 4.1 section III part G

Clause 13.68 Heading: amended, on 28 June 2012, by clause 36(1) of the Electricity Industry Participation (Demand-side Bidding and Forecasting) Code Amendment 2011.

Clause 13.68(1): amended, on 28 June 2012, by clause 36(2) of the Electricity Industry Participation (Demand-side Bidding and Forecasting) Code Amendment 2011.

Clause 13.68: revoked, on 15 May 2014, by clause 22 of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

### **13.69 System operator may adjust dispatch schedule *[Revoked]***

Compare: Electricity Governance Rules 2003 rule 4.2 section III part G

Clause 13.69: revoked, on 15 May 2014, by clause 22 of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

### **13.69A System operator to prepare dispatch schedule**

The **system operator** must prepare a **dispatch schedule** in accordance with the methodology set out in Schedule 13.3.

Clause 13.69A: inserted, on 15 May 2014, by clause 23 of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

### **13.70 System operator may depart from dispatch schedule**

The **system operator** may exercise discretion in departing from the **dispatch schedule** only if it is necessary to meet—

- (a) the **dispatch objective**; or
- (b) the requirements of clause 8.5 in relation to restoration of the power system.

Compare: Electricity Governance Rules 2003 rule 4.3 section III part G

### **13.71 System operator to use certain things**

- (1) In determining **dispatch instructions** when implementing a **dispatch schedule** under clause 13.72(1)(a), the **system operator** must use—
  - (a) the price order in the current **dispatch schedule**; and
  - (b) any revised **offer** from a **generator** submitted in accordance with clause 13.19 (except for revised **offers** submitted by an **intermittent generator** under clause 13.19(1)(a)(iii)); and
  - (c) any ramp rates of **generators**. For **intermittent generators**, the ramp rates are those agreed between the **intermittent generator** and the **system operator**; and
  - (d) any revised **nominated bid** quantities from a **purchaser** submitted in accordance with clause 13.19A; and
  - (e) any additional information regarding the future output of an **intermittent generator** submitted by an **intermittent generator** in agreement with the **system operator**; and
  - (f) the actual profile of **demand** during the previous **trading period**; and
  - (g) the expected profile of **demand** within the current **trading period** and the subsequent **trading periods**; and
  - (h) the current output levels of each **generator**; and
  - (i) any revised **reserve offer** from an **ancillary service agent** advised in accordance with clause 13.48; and
  - (j) any revised information received from a **grid owner** under clause 13.34(1); and
  - (k) the order in which reserves may be called as specified by the **system operator** from time to time.
- (2) In determining **dispatch instructions** under clause 13.72(1)(b), the **system operator** must use revised **nominated dispatch bids** submitted under clause 13.19A.

Compare: Electricity Governance Rules 2003 rule 4.4 section III part G

Clause 13.71(d): amended, on 28 June 2012, by clause 37 of the Electricity Industry Participation (Demand-side Bidding and Forecasting) Code Amendment 2011.

Clause 13.71: substituted, on 15 May 2014, by clause 24 of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

Clause 13.71(1)(b), (d) and (i): amended, on 5 October 2017, by clause 364 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### 13.72 System operator to issue dispatch instructions

- (1) The **system operator** must implement—
  - (a) a **dispatch schedule**, and any departure from the **dispatch schedule** under clause 13.70, by issuing **dispatch instructions** to,—
    - (i) **generators**; and
    - (ii) **ancillary service agents**:
  - (b) a **non-response schedule** by issuing **dispatch instructions** to **dispatchable load purchasers** that have submitted **nominated dispatch bids**.
- (2) The **system operator** must issue each **dispatch instruction** in a reasonable and timely manner to enable the **participant** to which the **dispatch instruction** is issued to comply with the **dispatch instruction**.
- (3) Despite subclause (1), the **system operator** is not required to issue a **dispatch instruction** to a **participant** if—
  - (a) the **dispatch instruction** is—
    - (i) to provide a quantity of **active power** under clause 13.73(1)(a); or
    - (ii) to provide a quantity of **instantaneous reserve** under clause 13.73(1)(b); and
  - (b) the **dispatch instruction** would differ from the most recent **dispatch instruction** issued to the **participant** by 1 MW or less.

Compare: Electricity Governance Rules 2003 rule 4.5 section III part G

Clause 13.72: substituted, on 15 May 2014, by clause 25 of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

### 13.73 Content of dispatch instructions to generators, ancillary service agents, and dispatchable load purchasers

- (1) The **system operator** must ensure that each **dispatch instruction** it issues under clause 13.72(1)(a) instructs the **generator** or **ancillary service agent** to carry out 1 of the following in relation to a **generating plant**, a **generating unit**, a **block dispatch group**, a **station dispatch group**, a **frequency keeping unit**, or **interruptible load**:
  - (a) provide a quantity of **active power**:
  - (b) provide a quantity of **instantaneous reserve**:
  - (c) provide a quantity and quality of reserve power or alternative to regulate frequency continuously:
  - (d) provide a quantity of **reactive power**:
  - (e) adjust transformer tap positions to maintain voltage levels:
  - (f) provide a level of voltage:
  - (g) **synchronise** or **de-synchronise generating plant** within the current **trading period** or the next **trading period** either directly or in accordance with any process that may be agreed with the **generator**:
  - (h) switch on or switch off schemes for over frequency tripping where such capability exists in **generating plant** that a **generator** has offered to provide to the **system operator**:

- (i) manage the **generating plant** within a **block dispatch group** or **station dispatch group** so as to ensure the largest single reserve risk within that **block dispatch group** or **station dispatch group** does not exceed the relevant maximum reserve risk advised by the **system operator** for the North Island or the South Island for each **trading period**;
  - (j) manage the total aggregate generation for each **sub-block dispatch group** or **sub-station dispatch group** for that **generator** so as not to exceed the total sum of the **dispatched** quantities for each **generating plant** or **generating unit** comprising that **sub-block dispatch group** or **sub-station dispatch group** for the duration of the notice received under clauses 13.60, 13.61, or 13.64 to 13.66;
  - (k) manage the total aggregate generation for each **block dispatch group** or **station dispatch group** for that **generator** so as to meet the total sum of the **dispatched** quantities for each **generating station** or **generating unit** comprising that **block dispatch group** or **station dispatch group**.
- (2) The **system operator** must ensure that each **dispatch instruction** issued under clause 13.72(1)(b) instructs the **dispatchable load purchaser** to use a specified quantity of **electricity** in relation to a **dispatch-capable load station**.

Compare: Electricity Governance Rules 2003 rule 4.6 section III part G

Clause 13.73 Heading: amended, on 3 October 2013, by clause 6(a) of the Electricity Industry Participation (Technology Neutral Language in Frequency Keeping) Code Amendment 2013.

Clause 13.73: amended, on 3 October 2013, by clause 6(b) and (c) of the Electricity Industry Participation (Technology Neutral Language in Frequency Keeping) Code Amendment 2013.

Clause 13.73(c): amended, on 3 October 2013, by clause 6(d) of the Electricity Industry Participation (Technology Neutral Language in Frequency Keeping) Code Amendment 2013.

Clause 13.73: substituted, on 15 May 2014, by clause 26 of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

Clause 13.73(1)(i): amended, on 5 October 2017, by clause 365 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### 13.74 Content of dispatch instructions to reserve, interruptible load, and frequency keeping suppliers *[Revoked]*

Compare: Electricity Governance Rules 2003 rule 4.7 section III part G

Clause 13.74: substituted, on 3 October 2013, by clause 7 of the Electricity Industry Participation (Technology Neutral Language in Frequency Keeping) Code Amendment 2013.

Clause 13.74: revoked, on 15 May 2014, by clause 27 of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

### 13.75 Form of dispatch instruction

- (1) When issuing a **dispatch instruction** under clause 13.72(1)(a), the **system operator** must specify—
- (a) the **generating plant, generating unit, block dispatch group, station dispatch group, interruptible load, or frequency keeping units** to which the **dispatch instruction** applies; and
  - (b) the desired outcome of the **dispatch instruction**; and
  - (c) if the start time for the **dispatch instruction** differs from the issue time, the start time within the current **trading period** or the next **trading period**; and
  - (d) if specific ramp rates are concerned, a specific target time to reach the desired outcome; and
  - (e) the time at which the **dispatch instruction** was issued; and

- (f) any **block security constraint** that occurs within a **block dispatch group** and how the **block security constraint** divides the **generating stations** or **generating units** of a **block dispatch group** into **sub-block dispatch groups** as part of such a **dispatch instruction**; and
  - (g) any **station security constraint** that occurs within a **station dispatch group** and how the **station security constraint** divides the **generating stations** or **generating units** of a **station dispatch group** into **sub-station dispatch groups**; and
  - (h) if it is a **dispatch instruction** specified in clause 13.73(1)(i), the maximum reserve risk for the relevant **island**.
- (2) When issuing a **dispatch instruction** under clause 13.72(1)(b), the **system operator** must specify—
- (a) the **dispatch-capable load station** to which the **dispatch instruction** applies; and
  - (b) the **trading period** for which the **dispatch instruction** is issued; and
  - (c) the desired outcome of the **dispatch instruction**.

Compare: Electricity Governance Rules 2003 rule 4.8 section III part G

Clause 13.75(a): amended, on 3 October 2013, by clause 8 of the Electricity Industry Participation (Technology Neutral Language in Frequency Keeping) Code Amendment 2013.

Clause 13.75(1): amended, on 15 May 2014, by clause 28(a) & (b) of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

Clause 13.75(1)(f): amended, on 1 February 2016, by clause 80(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

Clause 13.75(1)(g): amended, on 1 February 2016, by clause 80(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

Clause 13.75(1)(h): inserted, on 15 May 2014, by clause 28(c) of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

Clause 13.75(2): inserted, on 15 May 2014, by clause 28(d) of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

### 13.76 System operator to issue and log dispatch instructions

- (1) The **system operator** must issue **dispatch instructions**,—
  - (a) to each **generator**, using an **approved system**; and
  - (b) to each **dispatchable load purchaser** that has submitted a **nominated dispatch bid**, on **WITS**; and
  - (c) to each **ancillary service agent**, verbally or in writing.
- (2) *[Revoked]*.
- (3) The **system operator** must log and record each **dispatch instruction**.
- (4) Each **generator** and each **ancillary service agent** must log each **dispatch instruction** received from the **system operator**.
- (5) The **system operator** must provide a copy of each **dispatch instruction**—
  - (a) to the **clearing manager**, by 1600 hours on the 7<sup>th</sup> **business day** of the **billing period** after the **billing period** in which the **system operator** issues and logs the **dispatch instruction**; and
  - (b) to the **Authority**, by 1600 hours on the first **business day** after the day on which the **system operator** issues and logs the **dispatch instruction**.
- (6) For the purpose of subclause (5), if the **system operator** has issued more than 1 **dispatch instruction** for a **dispatch-capable load station** for the same **trading period**, the **system operator** must provide a copy of the latest **dispatch instruction**.

Compare: Electricity Governance Rules 2003 rule 4.9 section III part G

Clause 13.76 Heading: replaced, on 5 October 2017, by clause 366(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 13.76: substituted, on 15 May 2014, by clause 29 of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

Clause 13.76(1): replaced, on 5 October 2017, by clause 366(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 13.76(2): revoked, on 5 October 2017, by clause 366(3) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 13.76(5): substituted, on 19 May 2016, by clause 31 of the Electricity Industry Participation Code Amendment (System Operator and Alignment with Statutory Objective) 2016.

Clause 13.76(6): amended, on 15 May 2014, by clause 45 of the Electricity Industry Participation (Minor Code Amendments) Code Amendment 2014.

### 13.77 Dispatch instructions to plant required by system operator *[Revoked]*

Compare: Electricity Governance Rules 2003 rule 4.9.1 section III part G

Clause 13.77: revoked, on 15 May 2014, by clause 30 of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

### 13.78 Active power dispatch instructions to clearing manager *[Revoked]*

Compare: Electricity Governance Rules 2003 rule 4.9.2 section III part G

Clause 13.78: revoked, on 15 May 2014, by clause 30 of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

### 13.79 Acknowledgement of dispatch instructions

If the **system operator** has issued a **dispatch instruction** to a **generator** or an **ancillary service agent**, that person must acknowledge to the **system operator** receipt of that **dispatch instruction** within 4 minutes of receiving that **dispatch instruction**, and must use its reasonable endeavours to acknowledge to the **system operator** receipt of the **dispatch instruction** within 3 minutes of receiving the **dispatch instruction**.

Compare: Electricity Governance Rules 2003 rule 4.9.3 section III part G

Clause 13.79: amended, on 21 September 2012, by clause 19 of the Electricity Industry Participation (Minor Amendments) Code Amendment 2012.

### 13.80 Dispatch instructions provided to grid owner

- (1) If the **system operator** has issued a **dispatch instruction** to an **embedded generator** to generate from a **generating plant** required by the **system operator** to be scheduled, the **system operator** must inform the **grid owner** that is connected to the **local network** in which the **embedded generator** is located of the quantity of **active power** that was the subject of such **dispatch instruction** and the **trading periods** for which the **dispatch instruction** was issued.
- (2) The **system operator** must provide the information to the relevant **grid owner** by 0400 hours on the day after the **dispatch instruction** was issued.

Compare: Electricity Governance Rules 2003 rule 4.9.4 section III part G

Clause 13.80(1): amended, on 21 September 2012, by clause 20 of the Electricity Industry Participation (Minor Amendments) Code Amendment 2012.

Clause 13.80(1): amended, on 15 May 2014, by clause 31 of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

Clause 13.80(1): amended, on 15 May 2014, by clause 46 of the Electricity Industry Participation (Minor Code Amendments) Code Amendment 2014.

Clause 13.80(1): amended, on 23 February 2015, by clause 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 13.80(1): amended, on 5 October 2017, by clause 367 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### 13.81 Backup procedures if communication not possible

- (1) The **system operator** must follow the backup procedures specified by it from time to time if—
  - (a) none of the mechanisms described in clause 13.76 are available to issue **dispatch instructions** under clause 13.72(1)(a); or
  - (b) the **system operator** does not receive an acknowledgement from a **generator** or **ancillary service agent** of receipt of a **dispatch instruction** within 10 minutes after issuing the **dispatch instruction**.
- (2) If the **system operator** is not able to issue a **dispatch instruction** on WITS under clause 13.17(1)(b) to a **dispatchable load purchaser** that has submitted a **nominated dispatch bid**, the **dispatchable load purchaser** must follow the backup procedures specified by the **system operator**.

Compare: Electricity Governance Rules 2003 rule 4.10 section III part G

Clause 13.81(1)(a): substituted, on 15 May 2014, by clause 32(a) of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

Clause 13.81(1)(b): amended, on 15 May 2014, by clause 47 of the Electricity Industry Participation (Minor Code Amendments) Code Amendment 2014.

Clause 13.81(2): inserted, on 15 May 2014, by clause 32(b) of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

Clause 13.81(2): amended, on 5 October 2017, by clause 368 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### 13.82 Dispatch instructions to be complied with

- (1) This clause applies to—
  - (a) a **generator**; and
  - (b) an **ancillary service agent**; and
  - (c) a **dispatched purchaser**.
- (2) Each **participant** to which this clause applies must comply with a **dispatch instruction** properly issued by the **system operator** under clause 13.72 unless,—
  - (a) in the **participant's** reasonable opinion,—
    - (i) personnel or plant safety is at risk; or
    - (ii) following the **dispatch instruction** will contravene a law; or
  - (b) the **generating plant** or **dispatch-capable load station** is already responding to an automated signal to activate—
    - (i) **capacity reserve**; or
    - (ii) **instantaneous reserve**; or
    - (iii) **automatic under-frequency load shedding**; or
    - (iv) **over frequency reserve**; or
  - (c) the **participant** is a **generator** or **ancillary service agent** acting in accordance with clause 13.86; or
  - (d) the **participant** is an **intermittent generator** that has complied with clause 13.17 and clause 13.18A, and the **system operator** has not advised that there is—
    - (i) a **grid emergency**; or
    - (ii) a system **constraint** that directly affects the **intermittent generator**; or
  - (e) the **participant**—
    - (i) is a **generator**; and
    - (ii) deviates from a **dispatch instruction** for **active power** to comply with clause 8.17; or
  - (f) the **participant**—

- (i) is a **dispatched purchaser**; and
    - (ii) deviates from the **dispatch instruction**—
      - (A) to comply with a request issued by the **system operator** under clause 5(4) of **Technical Code B** of Schedule 8.3; or
      - (B) to comply with clause 8.18; or
  - (g) the **participant**—
    - (i) is a **dispatched purchaser**; and
    - (ii) cannot comply with the **dispatch instruction** because **demand** has been **electrically disconnected** under clause 7A of **Technical Code B** of Schedule 8.3; or
  - (ga) the **participant**—
    - (i) is a **dispatched purchaser**; and
    - (ii) the **dispatch instruction** is issued for a **trading period** for which the latest **nominated bid** for the relevant **dispatch-capable load station** is a **nominated non-dispatch bid**; or
  - (h) the **participant**—
    - (i) is a **generator** or an **ancillary service agent**; and
    - (ii) deviates from a **dispatch instruction** to comply with clause 9 of **Technical Code B** of Schedule 8.3; or
  - (i) the **participant**—
    - (i) is a **generator** or an **ancillary service agent**; and
    - (ii) is acting in accordance with a **commissioning** plan or test plan that—
      - (A) is required under clause 2(6) of **Technical Code A** of Schedule 8.3; and
      - (B) expressly allows the **generator** or **ancillary service agent** to depart from the **dispatch instruction** for the purpose of the **commissioning** plan or test plan; and
    - (iii) has no reasonable means of complying with the **dispatch instruction** while acting in accordance with the **commissioning** plan or test plan; or
  - (j) the **participant** is a **type B co-generator** and the **system operator** has not advised that there is—
    - (i) a **grid emergency**; or
    - (ii) a system **constraint** that directly affects the **type B co-generator**.
- (3) A **participant** to which the exception in subclause (2)(a) applies must immediately advise the **system operator** of the circumstance in which the exception arises.
- (4) If a **dispatched purchaser** is issued with more than 1 **dispatch instruction** for the same **dispatch-capable load station** for the same **trading period**, the **dispatched purchaser** must comply with the latest **dispatch instruction**.
- (5) To avoid doubt, a **dispatch instruction** listed in clause 13.73(1)(b) to 13.73(1)(f) or 13.73(1)(h) is properly issued only if—
- (a) the **generator** or **ancillary service agent** to which the **dispatch instruction** is given has an enforceable contract with the **system operator** for the provision of services relating to the **dispatch instruction**; or
  - (b) the **dispatch instruction** is consistent with an enforceable contract between the **system operator** and the **generator** or **ancillary service agent** for the provision of services relating to the **dispatch instruction**; or
  - (c) the **dispatch instruction** is given for the purposes of clause 8.5 or 13.70; or
  - (d) the **dispatch instruction** is consistent with—



- (i) the **asset owner performance obligations** under clauses 8.22 to 8.24; or
  - (ii) the **technical codes** concerning voltage; or
  - (iii) a **dispensation**.
- (6) A **dispatched purchaser** issued with a **dispatch instruction** for a **dispatch-capable load station** must not make changes to its other load at the same **GXP** with the intention of offsetting the **dispatch instruction** for the **dispatch-capable load station**.
- Compare: Electricity Governance Rules 2003 rule 4.11 section III part G
- Clause 13.82: substituted, on 15 May 2014, by clause 33 of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.
- Clause 13.82(2)(d): amended, on 29 June 2017, by clause 34 of the Electricity Industry Participation Code Amendment (Shortened Gate Closure and Revised Bid and Offer Provisions) 2017.
- Clause 13.82(2)(d)(ii): amended, on 27 May 2015, by clause 8(1) of the Electricity Industry Participation Code Amendment (Industrial Co-generation Dispatch Arrangements) 2015.
- Clause 13.82(2)(g)(ii): amended, on 7 August 2014, by clause 23 of the Electricity Industry Participation Code Amendment (Extended Reserve) 2014.
- Clause 13.82(2)(ga): inserted, on 1 December 2015, by clause 5 of the Electricity Industry Participation Code Amendment (Dispatchable Demand: Late Bid Revisions) 2015.
- Clause 13.82(2)(h): inserted, on 18 April 2013, by clause 4 of the Electricity Industry Participation (Dispatch Compliance Minor Amendment) Code Amendment 2013.
- Clause 13.82(2)(i)(iii): amended, on 27 May 2015, by clause 8(2) of the Electricity Industry Participation Code Amendment (Industrial Co-generation Dispatch Arrangements) 2015.
- Clause 13.82(2)(j): inserted, on 27 May 2015, by clause 8(3) of the Electricity Industry Participation Code Amendment (Industrial Co-generation Dispatch Arrangements) 2015.
- Clause 13.82(2)(g)(ii) and (2)(i): amended, on 5 October 2017, by clause 369 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### 13.83 Generators to make staff or facilities available to meet dispatch instructions

- (1) Each **generator** must ensure, with respect to each of its **generating plants** that is the subject of an **offer**, that appropriate personnel or facilities are available to receive and comply with any **dispatch instruction** given by the **system operator** to the **generator**.
- (2) Nothing in this clause limits the ability of a **generator** to have a control centre that operates 1 or more items of **generating plant** by remote control.

Compare: Electricity Governance Rules 2003 rule 4.12 section III part G

### 13.83A Dispatchable load purchasers to make staff or facilities available to meet dispatch instructions

- (1) Each **dispatchable load purchaser** that has submitted a **nominated dispatch** bid must ensure that appropriate personnel or facilities are available to receive and comply with each **dispatch instruction** issued to the **dispatchable load purchaser**.
- (2) Nothing in this clause limits the ability of a **dispatchable load purchaser** to have a control centre that operates 1 or more **dispatch-capable load stations** by remote control.

Clause 13.83A: inserted, on 15 May 2014, by clause 34 of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

### 13.84 Ancillary service agents to make staff or facilities available to meet dispatch instructions

Each **ancillary service agent** must ensure, with respect to any **instantaneous reserve** that is the subject of a **reserve offer** for the **trading period**, that appropriate personnel or facilities are available to receive and comply with any **dispatch instruction** given by the **system operator** to that **ancillary service agent**.

Compare: Electricity Governance Rules 2003 rule 4.13 section III part G

### **13.85 Generators have flexibility within block dispatch group or station dispatch group**

Each **generator** may **synchronise, de-synchronise**, or alter the output of any **generating plant** within a **block dispatch group** or **station dispatch group** if it first consults with the **system operator** with regard to such action.

Compare: Electricity Governance Rules 2003 rule 4.15 section III part G

### **13.86 Generators and ancillary service agents not obliged to comply with dispatch instructions below threshold**

For any **generating plant, generating unit, block dispatch group** or **station dispatch group**, a **generator** or **ancillary service agent** is not required to comply with 1 or more **dispatch instructions** given by the **system operator** in accordance with clause 13.72(1)(a) if implementing the **dispatch instruction** or those **dispatch instructions** together would change by less than or equal to—

- (a) for **ancillary service agents**, 1 MW from the last **dispatch instruction** that the **ancillary service agent** complied with; or
- (b) for **generators** other than **type A co-generators**, 1 MW from the last **dispatch instruction** that the **generator** complied with; or
- (c) for **type A co-generators**, 5 MW from the last **dispatch instruction** that the **type A co-generator** complied with.

Compare: Electricity Governance Rules 2003 rule 4.16 section III part G

Clause 13.86: amended, on 15 May 2014, by clause 35 of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

Clause 13.86(b): amended, on 27 May 2015, by clause 9(1) of the Electricity Industry Participation Code Amendment (Industrial Co-generation Dispatch Arrangements) 2015.

Clause 13.86(c): amended, on 27 May 2015, by clause 9(2)(i) and (ii) of the Electricity Industry Participation Code Amendment (Industrial Co-generation Dispatch Arrangements) 2015.

Cross heading: revoked, on 28 June 2012, by clause 38(1) of the Electricity Industry Participation (Demand-side Bidding and Forecasting) Code Amendment 2011.

### **13.87 [Revoked]**

Clause 13.87: revoked, on 28 June 2012, by clause 38(2) of the Electricity Industry Participation (Demand-side Bidding and Forecasting) Code Amendment 2011.

## *Real time prices*

### **13.88 Preparation of schedule of real time prices**

- (1) The purpose of this clause is to require the **system operator** to produce the schedule of **real time prices**.
- (2) Each schedule of **real time prices** prepared by the **system operator** must cover 1 **real time pricing period**.
- (3) In preparing each schedule of **real time prices**, the **system operator** must use the methodology in Schedule 13.3.
- (4) The **system operator** must use its reasonable endeavours to complete a new schedule of **real time prices** for a **real time pricing period** as soon as practicable after the relevant **real time pricing period**, provided that the information required to calculate the

schedule of **real time prices** (as set out in Schedule 13.3) is available to the **system operator**.

Compare: Electricity Governance Rules 2003 rule 6 section III part G

Clause 13.88 Heading: amended, on 28 June 2012, by clause 39(1) of the Electricity Industry Participation (Demand-side Bidding and Forecasting) Code Amendment 2011.

Clause 13.88 (1)-(4): amended, on 28 June 2012, by clause 39(2)-(4) of the Electricity Industry Participation (Demand-side Bidding and Forecasting) Code Amendment 2011.

### 13.89 Publication of schedule of real time prices

The **system operator** must use reasonable endeavours to **publish** each schedule of **real time prices** in accordance with clauses 13.90 to 13.96.

Compare: Electricity Governance Rules 2003 rule 7.1 section III part G

Clause 13.89 Heading: amended, on 28 June 2012, by clause 40(1) of the Electricity Industry Participation (Demand-side Bidding and Forecasting) Code Amendment 2011.

Clause 13.89: amended, on 28 June 2012, by clause 40(2) of the Electricity Industry Participation (Demand-side Bidding and Forecasting) Code Amendment 2011.

### 13.90 Process for making real time prices available

- (1) The **system operator** must use reasonable endeavours to make available on **WITS**, for each **real time pricing period**, as soon as practicable after the **real time pricing period**,—
  - (a) a schedule of **real time prices**; and
  - (b) the following additional information for each schedule of **real time prices**:
    - (i) the number of transmission **lines** or transformers that have a **MW** arc flow equal to the maximum flow limit (in **MW**) on that transmission line or transformer set by the **grid owner** in accordance with clauses 13.29 to 13.32;
    - (ii) the number of groups of transmission **lines** or transformers, or both, that have a total **MW** arc flow equal to the relevant maximum flow limit (in **MW**) as set by the **system operator** in accordance with Schedule 13.3;
    - (iii) the aggregate of the following occurrences:
      - (A) the number of occurrences at which energy (in **MW**) for a **generator** at a set of **grid injection points** is equal to the minimum and/or maximum generation (in **MW**) for that set of **grid injection points** set by the **system operator** in accordance with Schedule 13.3;
      - (B) the number of occurrences at which energy (in **MW**) and reserves (in **MW**) for a **generator** at a set of **grid injection points** is equal to the maximum generation (in **MW**) for that set of **grid injection points** set by the **system operator** in accordance with Schedule 13.3;
      - (C) the number of occurrences at which reserve (in **MW**) for a **participant** at a set of **grid exit points** is equal to the maximum reserve (in **MW**) for that set of **grid exit points** as determined under Schedule 13.3;
    - (iv) the number of occurrences at which the ramp up rate is equal to the maximum ramp up rate specified in the relevant **offer**;
    - (v) the number of occurrences at which the ramp down rate is equal to the maximum ramp down rate as specified in the relevant **offer**;

- (vi) the number of **grid exit points** at which demand was estimated.
- (2) For each **grid injection point** and each **grid exit point**, the **system operator** must use reasonable endeavours to make available on **WITS** a time-weighted average of the **real time prices** for each **trading period**.

Compare: Electricity Governance Rules 2003 rule 7.2 section III part G

Clause 13.90 Heading: replaced, on 5 October 2017, by clause 370(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 13.90(1): amended, on 5 October 2017, by clause 370(2)(a) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 13.90(1): amended, on 28 June 2012, by clause 41 of the Electricity Industry Participation (Demand-side Bidding and Forecasting) Code Amendment 2011.

Clause 13.90(1)(b)(i) and (ii): amended, on 1 February 2016, by clause 81 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

Clause 13.90(1)(b)(ii): substituted, on 15 May 2014, by clause 48 of the Electricity Industry Participation (Minor Code Amendments) Code Amendment 2014.

Clause 13.90(1)(b)(iii): amended, on 15 May 2014, by clause 36 of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

Clause 13.90(1)(b)(iii)(A): amended, on 21 September 2012, by clause 21 of the Electricity Industry Participation (Minor Amendments) Code Amendment 2012.

Clause 13.90(2): replaced, on 5 October 2017, by clause 370(2)(b) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### 13.91 System operator to use backup procedures if WITS unavailable

- (1) *[Revoked]*
- (2) If **WITS** is unavailable for the purposes of making information available under clauses 13.89 to 13.96, the **system operator** must follow the backup procedures specified by the **WITS manager**.
- (3) The **WITS manager** must specify the backup procedures referred to in subclause (2) following consultation with the **Authority, purchasers, generators, and the system operator**.

Compare: Electricity Governance Rules 2003 rules 7.3 to 7.5 section III part G

Clause 13.91 Heading: replaced, on 5 October 2017, by clause 371(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 13.91(1): revoked, on 5 October 2017, by clause 371(2)(a) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 13.91(2) and (3): replaced, on 5 October 2017, by clause 371(2)(b) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### 13.92 Transmission of information through publicly accessible approved system

- (1) The **WITS manager** must make any information it receives from the **system operator** under clause 13.90 available at no cost on a publicly accessible **approved system**.
- (2) If the publicly accessible **approved system** under subclause (1) is unavailable, the **WITS manager** is not required to—
- follow any backup procedures; or
  - make the information available on the publicly accessible **approved system** at a later time.

Compare: Electricity Governance Rules 2003 rules 7.6 and 7.7 section III part G

Clause 13.92: replaced, on 5 October 2017, by clause 372 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### **13.93 Authority to appoint person to monitor and assess demand side participation and real time prices**

- (1) The **Authority** may monitor and assess, or appoint a person at any time to monitor and assess, the **real time prices** made available by the **system operator** under clauses 13.89 to 13.96 in the context of demand side participation.
- (2) The **system operator** must use reasonable endeavours to make available to the **Authority** or the person appointed by the **Authority** under subclause (1), in a manner agreed between the **system operator** and that person,—
  - (a) if that person is not the **Authority**, the information the **system operator** makes available to the **participants** and the **Authority** under clause 13.90; and
  - (b) for each **grid injection point** and each **grid exit point**, a volume weighted average of the **real time prices** for each **trading period**.

Compare: Electricity Governance Rules 2003 rules 7.8 and 7.9 section III part G

Clause 13.93 Heading: amended, on 5 October 2017, by clause 373(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 13.93(1): replaced, on 5 October 2017, by clause 373(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 13.93(2): amended, on 5 October 2017, by clause 373(3) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### **13.94 System operator may suspend publication of real time prices**

Despite anything in this Code, the **system operator** may delay the making available and transmitting of **real time prices** and any other information under clauses 13.89 to 13.96 if the **system operator**—

- (a) issues a **formal notice** in accordance with clause 5 of **Technical Code B** of Schedule 8.3; or
- (b) reasonably believes that its **principal performance obligations** are not being met for the period specified in the **system operator's** instruction.

Compare: Electricity Governance Rules 2003 rule 7.10 section III part G

### **13.95 Real time prices not binding**

The **real time prices published** and made available under clauses 13.89 to 13.96 are indicative only and are not **provisional prices**, **interim prices**, **final prices** or binding in relation to the settlement and clearing processes.

Compare: Electricity Governance Rules 2003 rule 7.11 section III part G

### **13.96 Purchaser to co-operate with system operator to manage response to real time prices**

- (1) This clause applies to a **purchaser** that wishes to increase or decrease its total **demand**, other than **demand** for a **dispatch-capable load station** for which a **nominated dispatch bid** is submitted, across 1 or more of its **grid exit points** in response to **real time prices** by—
  - (a) greater than 50 **MW** in any 15 minute period in the North Island; or
  - (b) greater than 30 **MW** in any 15 minute period in the South Island.
- (2) If this clause applies, the **purchaser** must—
  - (a) advise the **system operator** by telephone of the increase or decrease at least 5 minutes before the change; and

- (b) if instructed by the **system operator** by telephone, manage any such increase or decrease in accordance with the instructions.

Compare: Electricity Governance Rules 2003 rule 7.12 section III part G

Clause 13.96: substituted, on 15 May 2014, by clause 37 of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

### *Grid emergencies*

#### **13.97 Grid emergency situations**

- (1) The **system operator** may, at any time, declare a **grid emergency** in accordance with **Technical Code B** of Schedule 8.3.
- (2) Despite clauses 13.6 to 13.27 and clauses 13.37 to 13.54, if the **system operator** has declared a **grid emergency**,—
  - (a) a **generator**, other than an **intermittent generator**, may not reduce the **MW** specified in any of the **offers** made by the **generator** for the **trading periods** and **grid injection points** affected by the **grid emergency**, unless the **generator** has a **bona fide physical reason** that makes the reduction necessary; and
  - (b) an **ancillary service agent** may not reduce the **instantaneous reserve** specified in any of the **reserve offers** made by the **ancillary service agent** for the **trading periods** and **points of connection** with the **grid** affected by the **grid emergency**, unless the **ancillary service agent** has a **bona fide physical reason** that makes the reduction necessary; and
  - (c) the **system operator** must accept any reduction made under paragraphs (a) or (b).

Compare: Electricity Governance Rules 2003 rules 8.1 and 8.2 section III part G

Clause 13.97(2): amended, on 29 June 2017, by clause 35(1) of the Electricity Industry Participation Code Amendment (Shortened Gate Closure and Revised Bid and Offer Provisions) 2017.

Clause 13.97(2)(a): amended, on 29 June 2017, by clause 35(2)(a) and (b) of the Electricity Industry Participation Code Amendment (Shortened Gate Closure and Revised Bid and Offer Provisions) 2017.

Clause 13.97(2)(b): amended, on 29 June 2017, by clause 35(3)(a) and (b) of the Electricity Industry Participation Code Amendment (Shortened Gate Closure and Revised Bid and Offer Provisions) 2017.

#### **13.98 Generators and ancillary service agents may change other parameters**

Despite clause 13.97(2), during a **grid emergency**,—

- (a) a **generator** may reduce the **MW** specified in any price band offered in respect of certain **generating plant**, if equivalent increased **MW** is, in substitution, offered for other items of **generating plant** owned or operated by that **generator** at **grid injection points** in the electrical or geographical region affected as specified in the **system operator's** notice issued under clause 5(1) of **Technical Code B** of Schedule 8.3; and
- (b) an **ancillary service agent** may reduce the **instantaneous reserves** offered, if equivalent increased **instantaneous reserves** are, in substitution, offered by that **ancillary service agent** at **points of connection** with the **grid** in the electrical or geographical region affected as specified in the **system operator's** notice issued under clause 5(1) of **Technical Code B** of Schedule 8.3; and
- (c) despite clauses 13.6 to 13.27, a **generator** may—
  - (i) submit revised **offers** in respect of **generating plant** already subject to an **offer** before the **grid emergency**, so that the total **MW** offered by the

- generator** from the **generating plant** for that **trading period** is increased; and
- (ii) submit new **offers** in respect of a **generating plant** not subject to an **offer** before the **grid emergency**; and
- (d) despite clause 13.17(2), a **generator** may submit a new price band or bands for new **offers** or revised **offers** in respect of the increased **MW** made under paragraph (c), but may not revise the price band or bands in respect of the **MW** offered before the notice of the **grid emergency**; and
- (e) despite clauses 13.37 to 13.54, an **ancillary service agent** may—
- (i) submit revised **reserve offers** in respect of any **instantaneous reserve** already subject to a **reserve offer** before the **grid emergency** so that the total **instantaneous reserve** offered by the **ancillary service agent** for that **trading period** is increased; and
  - (ii) submit new **reserve offers** in respect of any **instantaneous reserve** not subject to a **reserve offer** before the **grid emergency**; and
- (f) despite clause 13.46(1A), an **ancillary service agent** may submit a new price band or bands for new **reserve offers** or revised **reserve offers** in respect of the increased **instantaneous reserve** made under paragraph (e), but may not revise the type of **instantaneous reserve** or the price band or bands in respect of the **instantaneous reserve** offered before the notice of the **grid emergency**.

Compare: Electricity Governance Rules 2003 rule 8.3 section III part G

Clause 13.98(a): amended, on 29 June 2017, by clause 36(1)(a), (b) and (c) of the Electricity Industry Participation Code Amendment (Shortened Gate Closure and Revised Bid and Offer Provisions) 2017.

Clause 13.98(a) and (b): amended, on 5 October 2017, by clause 374 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 13.98(b): amended, on 29 June 2017, by clause 36(2)(a) and (b) of the Electricity Industry Participation Code Amendment (Shortened Gate Closure and Revised Bid and Offer Provisions) 2017.

Clause 13.98(c)(i): amended, on 29 June 2017, by clause 36(3) of the Electricity Industry Participation Code Amendment (Shortened Gate Closure and Revised Bid and Offer Provisions) 2017.

Clause 13.98(d): amended, on 29 June 2017, by clause 36(4)(a), (b) and (c) of the Electricity Industry Participation Code Amendment (Shortened Gate Closure and Revised Bid and Offer Provisions) 2017.

Clause 13.98(e): amended, on 29 June 2017, by clause 36(5) of the Electricity Industry Participation Code Amendment (Shortened Gate Closure and Revised Bid and Offer Provisions) 2017.

Clause 13.98(f): amended, on 29 June 2017, by clause 36(6)(a), (b) and (c) of the Electricity Industry Participation Code Amendment (Shortened Gate Closure and Revised Bid and Offer Provisions) 2017.

### 13.99 Effect of grid emergency on total quantities bid

Despite clauses 13.19A to 13.27, if the **system operator** has declared a **grid emergency**—

- (a) a **purchaser** may not increase the aggregate quantity of **electricity** specified in all of the **nominated bids** made by the **purchaser** for the **trading periods** and **GXPs** affected by the **grid emergency** unless the **purchaser** has a **bona fide physical reason** that necessitates the increase; and
- (b) the **system operator** must accept any revision made under paragraph (a).

Compare: Electricity Governance Rules 2003 rule 8.4 section III part G

Clause 13.99: amended, on 29 June 2017, by clause 37 of the Electricity Industry Participation Code Amendment (Shortened Gate Closure and Revised Bid and Offer Provisions) 2017.

Clause 13.99(a): amended, on 28 June 2012, by clause 42 of the Electricity Industry Participation (Demand-side Bidding and Forecasting) Code Amendment 2011.

Clause 13.99(a): amended, on 15 May 2014, by clause 38 of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

### 13.99A Effect of grid emergency on nominated dispatch bids

- (1) This clause applies—
  - (a) if the **system operator** has declared a **grid emergency**; and
  - (b) to each **nominated dispatch bid** that is for—
    - (i) a **GXP** that is in the affected electrical or geographical region as specified in the **formal notice** issued by the **system operator**; and
    - (ii) a **trading period** that is specified in the **formal notice** issued by the **system operator**.
- (2) If this clause applies, a **purchaser** must immediately change each **bid** to which this clause applies from a **nominated dispatch bid** to a **nominated non-dispatch bid**.

Clause 13.99A: inserted, on 15 May 2014, by clause 39 of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

### 13.100 Purchasers may change other parameters

Despite clause 13.99, during a **grid emergency**, a **purchaser** may—

- (a) increase a **nominated bid's** quantities, or submit **nominated bids** at **GXP**s that were not subject to **nominated bids** before the **grid emergency**, if equivalent decreased quantities are, in substitution, bid for **GXP**s in the affected electrical or geographical region, as specified in the **formal notice** issued by the **system operator**, which were the subject of **nominated bids** made by the **purchaser**; and
- (b) decrease a **nominated bid's** quantities.

Compare: Electricity Governance Rules 2003 rule 8.5 section III part G

Clause 13.100(a): substituted, on 28 June 2012, by clause 43(1) of the Electricity Industry Participation (Demand-side Bidding and Forecasting) Code Amendment 2011.

Clause 13.100(b): amended, on 28 June 2012, by clause 43(2) of the Electricity Industry Participation (Demand-side Bidding and Forecasting) Code Amendment 2011.

Clause 13.100(a): amended, on 15 May 2014, by clause 40(a) of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

Clause 13.100(b): substituted, on 15 May 2014, by clause 40(b) of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

### 13.101 Reporting requirements in respect of grid emergencies

- (1) If the **system operator** declares a **grid emergency**,—
  - (a) the **system operator** must, within 12 hours of the conclusion of the **grid emergency**, **publish** a written report that describes the basis on which the **system operator** decided to declare the **grid emergency**; and
  - (b) a **generator** that reduced the **MW** specified in any price band in any **offer**, and an **ancillary service agent** that reduced the **instantaneous reserve** specified in any **reserve offer**, made by that person in respect of the **point of connection** with the **grid** and **trading periods** affected by the **grid emergency** must report the reduction to the **Authority** in writing together with details of the **bona fide physical reason** for the reduction claimed by the **generator** or **ancillary service agent**. A reduction must be reported to the **Authority** by 1700 hours on the 1st **business day** after the **trading day** on which the reduction was made.
  - (c) *[Revoked]*
- (2) *[Revoked]*

Compare: Electricity Governance Rules 2003 rules 8.6 and 8.7 section III part G



Clause 13.101(1)(a): substituted, on 1 February 2016, by clause 82 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

Clause 13.101(1)(b): amended, on 28 June 2012, by clause 44(1) of the Electricity Industry Participation (Demand-side Bidding and Forecasting) Code Amendment 2011.

Clause 13.101(1)(b): amended, on 29 June 2017, by clause 38(1)(a), (b) and (c) of the Electricity Industry Participation Code Amendment (Shortened Gate Closure and Revised Bid and Offer Provisions) 2017.

Clause 13.101(1)(c): substituted, on 28 June 2012, by clause 44(2) of the Electricity Industry Participation (Demand-side Bidding and Forecasting) Code Amendment 2011.

Clause 13.101(1)(c): revoked, on 29 June 2017, by clause 38(2) of the Electricity Industry Participation Code Amendment (Shortened Gate Closure and Revised Bid and Offer Provisions) 2017.

Clause 13.101(2): revoked, on 29 June 2017, by clause 38(3) of the Electricity Industry Participation Code Amendment (Shortened Gate Closure and Revised Bid and Offer Provisions) 2017.

### **13.102 Reporting obligations of system operator**

By the 10<sup>th</sup> **business day** of each calendar month, the **system operator** must inform the **Authority** in writing of any discretionary action the **system operator** has taken under clause 13.70, in the previous calendar month, that required departure from the **dispatch schedule**.

Compare: Electricity Governance Rules 2003 rule 9 section III part G.

Clause 13.102(1)(b): amended, on 28 June 2012, by clause 45 of the Electricity Industry Participation (Demand-side Bidding and Forecasting) Code Amendment 2011.

Clause 13.102(1)(d): amended, on 1 February 2016, by clause 83 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

Clause 13.102: substituted, on 19 May 2016, by clause 32 of the Electricity Industry Participation Code Amendment (System Operator and Alignment with Statutory Objective) 2016.

#### *System operator to publish information*

### **13.103 [Revoked]**

Clause 13.103: revoked, on 28 June 2012, by clause 46 of the Electricity Industry Participation (Demand-side Bidding and Forecasting) Code Amendment 2011.

### **13.104 System operator to make information available**

- (1) As soon as practicable after the **system operator** has completed preparing a **price-responsive schedule** and a **non-response schedule**, the **system operator** must make available on **WITS**, for each **trading period** in the **schedule length period**,—
- (a) the following information in respect of both the **price-responsive schedule** and the **non-response schedule**:
- (i) **forecast prices** and **forecast reserve prices**; and
  - (ii) scheduled **non-dispatch-capable load** at each **conforming GXP**; and
  - (iii) the aggregate supply curve at each **reference point** incorporating all **offers** from **generators** with **offer prices** adjusted for **forecast marginal location factors**; and
  - (iv) the **grid injection points** and **grid exit points** that have no load or generation connected to them in the modelling system; and
  - (v) the **grid injection points** and **grid exit points** where an **infeasibility situation** has occurred; and
  - (vi) the scheduled largest single reserve risk for each **island** as described in clause 13.59(ix); and

- (vii) the scheduled levels of **fast instantaneous reserve** and **sustained instantaneous reserve** required in each **island** as described in clause 13.59(x); and
  - (viii) the **reserve offer** stacks for each **island** as described in clause 13.59(xi); and
  - (ix) the adjusted **reserve offer** stacks for each **island** as described in clause 13.59(xii); and
  - (x) *[Revoked]*
  - (xi) the scheduled **HVDC component flows**; and
  - (xii) the scheduled **HVDC risk offsets**; and
  - (xiii) the **expected near-constraint arc flows**; and
  - (xiv) the **expected near-group-constraint arc flows**; and
  - (xv) the **group constraint formulas** relating to the **expected near-group-constraint arc flows**; and
  - (xvi) the expected deficit quantities for energy, **fast instantaneous reserve**, and **sustained instantaneous reserve** (if any); and
  - (xvii) whether the **HVDC link** is out of service; and
  - (b) in relation to the **price-responsive schedule**, the aggregate **demand** curve at each **reference point** incorporating the forecast prepared under clause 13.7A(1), and all **bids** from **purchasers** with **bid** prices adjusted for **forecast marginal location factors**; and
  - (c) in relation to the **non-response schedule**, the scheduled **frequency keeping units** for each **island**.
- (2) Subclause (3) applies to—
- (a) each **price-responsive schedule** prepared under clause 13.62(1)(a);
  - (b) each **non-response schedule** prepared under clause 13.62(1)(a).
- (3) Despite subclause (1), for each schedule to which this subclause applies, the **system operator** is not required to make available on **WITS** the information set out in subclause (1) for the **trading periods** covered by—
- (a) the **price-responsive schedule** prepared under clause 13.62(1)(b);
  - (b) the **non-response schedule** prepared under clause 13.62(1)(b).

Compare: Electricity Governance Rules 2003 rule 10.2 section III part G

Clause 13.104 Heading: replaced, on 5 October 2017, by clause 375(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 13.104: substituted, on 28 June 2012, by clause 47 of the Electricity Industry Participation (Demand-side Bidding and Forecasting) Code Amendment 2011.

Clause 13.104(1) and (1)(a)(iv): amended, on 5 October 2017, by clause 375(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 13.104(1)(a)(x): revoked, on 1 November 2012, by clause 8(1) of the Electricity Industry Participation (Part 13 Minor Amendments) Code Amendment 2012.

Clause 13.104(1)(a)(xvi) and (xvii): inserted, on 1 June 2013, by clause 7 of the Electricity Industry Participation (Scarcity Pricing) Code Amendment 2011.

Clause 13.104(1)(a) & (b): amended, on 15 May 2014, by clause 41 of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

Clause 13.104(1)(c): inserted, on 1 November 2012, by clause 8(2) of the Electricity Industry Participation (Part 13 Minor Amendments) Code Amendment 2012.

Clause 13.104(1)(c): amended, on 3 October 2013, by clause 9 of the Electricity Industry Participation (Technology Neutral Language in Frequency Keeping) Code Amendment 2013.

Clause 13.104(3): amended, on 5 October 2017, by clause 375(3) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### 13.105 *[Revoked]*

Clause 13.105: revoked, on 28 June 2012, by clause 48 of the Electricity Industry Participation (Demand-side Bidding and Forecasting) Code Amendment 2011.

### 13.105A Information to be made available to purchasers, generators, and ancillary service agents

- (1) At the same time as the **system operator** is required to make information available in accordance with clause 13.104, the **system operator** must make available on **WITS**—
  - (aa) for each **dispatchable load purchaser** that has submitted a **nominated dispatch bid**, information from the current **non-response schedule** relating to the scheduling of the **dispatchable load purchaser's nominated dispatch bids** for the **trading periods** covered in the **schedule length period**; and
  - (a) for each **purchaser**, information from the current **price-responsive schedule** relating to the scheduling of the **purchaser's bids** for the **trading periods** covered in the **schedule length period**; and
  - (b) for each **generator**, information from the current **price-responsive schedule** and **non-response schedule** relating to the scheduling of the **generator's offers** for the **trading periods** covered in the **schedule length period**; and
  - (c) for each **ancillary service agent** who has submitted a **reserve offer** for the **scheduling period**, information from the current **price-responsive schedule** and **non-response schedule** relating to the scheduling of the **ancillary service agent's reserve offers** for the **trading periods** covered in the **schedule length period**.
- (2) Subclause (3) applies to—
  - (a) each **price-responsive schedule** prepared under clause 13.62(1)(a);
  - (b) each **non-response schedule** prepared under clause 13.62(1)(a).
- (3) Despite subclause (1), for each schedule to which this subclause applies, the **system operator** is not required to make available on **WITS** the information set out in subclause (1) for the **trading periods** covered by—
  - (a) the **price-responsive schedule** prepared under clause 13.62(1)(b);
  - (b) the **non-response schedule** prepared under clause 13.62(1)(b).

Clause 13.105A Heading: amended, on 5 October 2017, by clause 376(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 13.105A: inserted, on 28 June 2012, by clause 49 of the Electricity Industry Participation (Demand-side Bidding and Forecasting) Code Amendment 2011.

Clause 13.105A(1): amended, on 5 October 2017, by clause 376(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 13.105A(1)(aa): inserted, on 15 May 2014, by clause 42 of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

Clause 13.105A(3): amended, on 5 October 2017, by clause 376(3) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### 13.106 Transmission of information

- (1) *[Revoked]*
- (2) If **WITS** is unavailable for the purposes of making information available under clauses 13.104 to 13.105A, the **system operator** must follow the backup procedures specified by the **WITS manager**.

- (3) The **WITS manager** must specify the backup procedures referred to in subclause (2) following consultation with the **Authority**, the **system operator**, the **pricing manager**, the **clearing manager**, **purchasers**, **generators**, and **ancillary service agents**.

Compare: Electricity Governance Rules 2003 rules 10.5 to 10.7 section III part G

Clause 13.106 Heading: amended, on 5 October 2017, by clause 377(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 13.106(1): amended, on 28 June 2012, by clause 50 of the Electricity Industry Participation (Demand-side Bidding and Forecasting) Code Amendment 2011.

Clause 13.106(1): revoked, on 5 October 2017, by clause 377(2)(a) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 13.106(2) and (3): replaced, on 5 October 2017, by clause 377(2)(b) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### Subpart 3—Must-run dispatch auction

#### 13.107 Contents of this subpart

This subpart provides for must-run dispatch **auctions**.

Compare: Electricity Governance Rules 2003 rule 1 section IV part G

#### 13.108 Clearing manager to hold must-run dispatch auctions

Each day the **clearing manager** must hold an **auction** as set out in clauses 13.117 to 13.130, at which **generators** may bid for **auction rights in time blocks**.

Compare: Electricity Governance Rules 2003 rule 2 section IV part G

#### 13.109 Clearing manager authorises generators

- (1) If a **generator's** bid at an **auction** is successful the **clearing manager** must authorise the **generator** to **offer electricity** at 0 price for the relevant **time block** and **trading period**.
- (2) The **clearing manager** must specify in each authorisation—
- (a) the quantity of **electricity** that the **generator** may offer under the authorisation; and
  - (b) the **trading periods** for which the authorisation is valid; and
  - (c) how much the **generator** must pay the **clearing manager** for the **auction rights**.

Compare: Electricity Governance Rules 2003 rules 2.1 and 2.2 section IV part G

#### 13.110 Clearing manager must calculate amounts owing

- (1) The **clearing manager** must calculate the amount owing by each **generator** for the **auction rights** the **generator** has acquired in the previous **billing period**.
- (2) Any **auction revenue** owing by a **generator** in relation to a **billing period** must be advised to the **generator** by the **clearing manager** under subpart 4 of Part 14.

Compare: Electricity Governance Rules 2003 rules 2.3 and 2.4 section IV part G

Clause 13.110 heading: amended, on 24 March 2015, by clause 9(1) of the Electricity Industry Participation (Settlement and Prudential Security) Code Amendment 2013.

Clause 13.110: amended, on 24 March 2015, by clause 9(2) of the Electricity Industry Participation (Settlement and Prudential Security) Code Amendment 2013.

#### 13.111 Purchasers must receive auction revenue

Each **purchaser** who purchases **electricity** at a **grid exit point** must receive **auction revenue** from **generators** in accordance with clause 13.112(1).

Compare: Electricity Governance Rules 2003 rule 2.5 section IV part G

### 13.112 Clearing manager must calculate amounts receivable

- (1) The **clearing manager** must calculate and credit **purchasers** for **auction revenue** for each **trading period** in accordance with the following formula:

$$AR_p = (TAR_g/APB)*(P_q/TP_q)$$

where

- $AR_p$  is the **auction revenue** receivable by a **purchaser**
- $TAR_g$  is the **total auction revenue** for a **time block** owing by **generators** as calculated by the **clearing manager** in accordance with clause 13.110(1)
- $APB$  is the number of **trading periods** in that **time block**
- $P_q$  is the total **electricity** purchased by that **purchaser** from the **clearing manager** during the **trading period** as shown by the **reconciliation information** calculated by the **reconciliation manager** under clause 15.21 to 15.26
- $TP_q$  is the total **electricity** purchased by all **purchasers** from the **clearing manager** during the **trading period** as shown by **reconciliation information** calculated by the **reconciliation manager** under clause 15.21 to 15.26.

- (2) Any **auction revenue** owing to a **purchaser** in relation to a **billing period** must be advised to the **purchaser** by the **clearing manager** under subpart 4 of Part 14.

Compare: Electricity Governance Rules 2003 rules 2.6 and 2.7 section IV part G

Clause 13.112: amended, on 24 March 2015, by clause 10 of the Electricity Industry Participation (Settlement and Prudential Security) Code Amendment 2013.

### 13.113 Generators choose grid injection points at which they will exercise rights conferred

A **generator** who acquires **auction rights** may exercise them in respect of any **generating plant** it owns and at a **grid injection point** during the relevant **time block**.

Compare: Electricity Governance Rules 2003 rule 2.8 section IV part G

### 13.114 Transmission of auction information

- (1) Except where specified otherwise in this Part, all information in relation to **auctions** must be transmitted using **WITS**.
- (2) If **WITS** is not available to transmit information under this clause, the **clearing manager** must follow the backup procedures specified by the **WITS manager**.
- (3) The **WITS manager** must specify the backup procedures referred to in subclause (2) following consultation with the **Authority**, **generators**, and the **clearing manager**.

Compare: Electricity Governance Rules 2003 rules 2.9 to 2.11 section IV part G

Clause 13.114 Heading: amended, on 1 February 2016, by clause 84(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

Clause 13.114(1): substituted, on 1 February 2016, by clause 84(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

Clause 13.114: replaced, on 5 October 2017, by clause 378 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### 13.115 Trading in auction rights permitted

- (1) A **generator** who has acquired **auction rights** at an **auction** (the "**transferring generator**") may **transfer** all or some of those rights to another **generator**.
- (2) The **generator** who acquires the rights by **transfer** takes them on the same terms that apply to the **transferring generator**.

Compare: Electricity Governance Rules 2003 rule 2.12 section IV part G

### 13.116 Offers at 0

- (1) Subject to subclause (2), a **generator** may offer **electricity** to the **clearing manager** at a 0 price only if the **generator** has an authorisation from an **auction** in accordance with clauses 13.108 to 13.115.
- (2) A **generator** may offer **electricity** to the **clearing manager** at a 0 price without an authorisation from an **auction** only in relation to—
  - (a) generating **plant** that comes within the scope of clauses 13.24 or 13.26; or
  - (b) **offers** submitted before publication of **auction** results, but, if authorisation from an **auction** is not granted, such **offers** are cancelled or revised so that they no longer contain a 0 price before 1300 hours on the day before the **trading day** for which the **offers** apply.

Compare: Electricity Governance Rules 2003 rules 2.13 and 2.14 section IV part G

### *Must-run auction process*

### 13.117 Clearing manager must conduct auctions

- (1) The **clearing manager** must conduct an **auction** every day.
- (2) Each **generator** is eligible to take part in each **auction**.
- (3) The **clearing manager** must specify the format for bidding and must accept **auction bids** only if they are made in that format. Each **auction bid** must be made in positive numbers.

Compare: Electricity Governance Rules 2003 rules 3.1 to 3.3 section IV part G

### 13.118 [Revoked]

Compare: Electricity Governance Rules 2003 rule 3.4 section IV part G

Clause 13.118: revoked, on 1 February 2016, by clause 85 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

### 13.119 Historic load data

- (1) Subject to subclause (3), by 1100 hours on a day that is 2 days before an **auction**, a **grid owner** must advise the **clearing manager** of the information described in subclause (2) by—
  - (a) giving written notice to the **clearing manager**; or
  - (b) using **WITS**.

- (2) The information is the total load that was on the **grid** that is owned or operated by the **grid owner**, on the day that is 363 days before the date of the **auction**.
- (3) If the **trading day** following the **auction** is—
- (a) a **national holiday**, the day referred to in subclause (2) is deemed to be the Sunday before the day preceding the date of the **auction** by 363 days; or
  - (b) a **business day**, but the 363<sup>rd</sup> day before the date of the **auction** is a **national holiday**, the day referred to in subclause (2) is deemed to be the next **business day** after the **national holiday**.

Compare: Electricity Governance Rules 2003 rule 3.5 section IV part G

Clause 13.119: replaced, on 5 October 2017, by clause 379 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### 13.120 Quantity available for auction

The **clearing manager** must calculate the quantity of **auction rights** available in each **time block** at each **auction** as follows:

$$\text{quantity of auction rights available in each time block} = 0.8 \cdot \text{ldf}_{\text{tb}}$$

where

$\text{ldf}_{\text{tb}}$  is the lowest demand forecast for a **time block**, which is the lowest demand in any **trading period** on the day for which load must be advised under clause 13.119 (in an interval that equates to the **time block**)

Compare: Electricity Governance Rules 2003 rule 3.6 section IV part G

Clause 13.120: amended, on 5 October 2017, by clause 380 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### 13.121 Notice of auction and deadline for auction bids

- (1) For each **auction**, by any time up to 1100 hours on the day before the **auction**, the **clearing manager** must give written notice or use **WITS** to advise each **generator** of the quantity of **auction rights** available in each **time block** at the **auction** to be held the following day and must invite **auction bids** for those **auction rights**.
- (2) A **generator** who wishes to bid at an **auction** must submit **auction bids** by 0900 hours on the day that the **auction** is to be held.

Compare: Electricity Governance Rules 2003 rule 3.7 section IV part G

Clause 13.121(1): amended, on 5 October 2017, by clause 381 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### 13.122 Revising, cancelling and extending auction bids

- (1) A **generator** may, by giving written notice or using **WITS**, revise or cancel an **auction bid** up to 0900 hours on the day of the **auction** to which the **auction bid** relates.
- (2) Each **auction bid** is valid for only 1 **auction** unless the **generator** expressly states when it makes the **auction bid** that the **auction bid** is to remain valid until cancelled.

Compare: Electricity Governance Rules 2003 rule 3.8 section IV part G

Clause 13.122(1): amended, on 5 October 2017, by clause 382 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### 13.123 Contents of auction bids

- (1) A **generator** may make up to 5 **auction bids** for each **time block**.

- (2) Each **auction bid** must specify for each **time block** the quantity of **auction rights** sought and the price that the **generator** is prepared to pay if its **auction bid** succeeds.  
Compare: Electricity Governance Rules 2003 rule 3.9 section IV part G

#### 13.124 Ranking of auction bids

- (1) When bidding closes at 0900 hours each day the **clearing manager** must rank the **auction bids** it has received in descending order by price per **MWh**.  
(2) Beside each **auction bid** the **clearing manager** must record the quantity of **auction rights** sought by the relevant **generator**.

Compare: Electricity Governance Rules 2003 rule 3.10 section IV part G

#### 13.125 Matching auction bids to rights

- (1) The **clearing manager** must match the ranked **auction bids** against all the **auction rights** available in each **time block** until the **auction bids** equal the quantity of **auction rights** available.  
(2) The **auction bids** made by a **generator** succeed if the bids are matched (in whole or part) against the **auction rights** available.

Compare: Electricity Governance Rules 2003 rule 3.11 section IV part G

#### 13.126 Similar and identical auction bids

- (1) If the **clearing manager** receives more than 1 **auction bid** at the same price, and there are not enough **auction rights** available to satisfy the **auction bids**, the **clearing manager** must award **auction rights** to each relevant bidder in the order in which the **clearing manager** received the **auction bids** (as evidenced by the time stamp provided by the **clearing manager**'s computer system).  
(2) If the **clearing manager** receives more than 1 **auction bid** at the same price at the same time it will award **auction rights** to each relevant bidder in proportion to the volume of **auction rights** the bidders sought in each of their **auction bids**.

Compare: Electricity Governance Rules 2003 rule 3.12 section IV part G

#### 13.127 Auction payment

The amount owing by a successful bidder in an **auction** is the quantity of **electricity** awarded by the **clearing manager** to that bidder multiplied by the **clearing auction price**.

Compare: Electricity Governance Rules 2003 rule 3.13 section IV part G

Clause 13.127: amended, on 24 March 2015, by clause 11 of the Electricity Industry Participation (Settlement and Prudential Security) Code Amendment 2013.

#### 13.128 Results

By 1100 hours on the day of each **auction** the **clearing manager** must give written notice or use **WITS** to advise—

- (a) each **generator** that has bid at an **auction** of the outcome of the **auction**; and  
(b) all **generators** and **purchasers** of the quantity and price of all successful **auction bids** made at the **auction**.

Compare: Electricity Governance Rules 2003 rule 3.14 section IV part G



Clause 13.128: amended, on 5 October 2017, by clause 383 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### 13.129 Authorisation to successful bidders

The **clearing manager** must give an authorisation, by way of a written notice or using **WITS**, to each **generator** that secures **auction rights** at an **auction**. The authorisation must set out the **auction rights** the **generators** secured at the **auction** and the price payable for them.

Compare: Electricity Governance Rules 2003 rule 3.15 section IV part G

Clause 13.129: amended, on 5 October 2017, by clause 384 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### 13.130 Records

The **clearing manager** must maintain a complete record for 3 years of all quantities of **auction rights** offered, all **auction bids** received, and the prices achieved in each **time block** at each **auction**. A **generator** may require the **clearing manager** to provide, in writing or using **WITS**, information relating to the **generator's auction bids** and **auction** results at any time within that period.

Compare: Electricity Governance Rules 2003 rule 3.16 section IV part G

Clause 13.130: amended, on 5 October 2017, by clause 385 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

## Subpart 4—Pricing

### 13.131 Contents of this subpart

This subpart provides for the processes by which the **pricing manager** receives data and produces **provisional prices**, **provisional reserve prices**, **interim prices**, **interim reserve prices**, **final prices**, and **final reserve prices**.

Compare: Electricity Governance Rules 2003 rule 1 section V part G

### 13.132 Purpose of the pricing process

The purpose of the pricing process is to achieve an appropriate balance between certainty and accuracy of **final prices** and **final reserve prices** for each **trading period**. As part of the process—

- (a) the **system operator**, the **pricing manager**, a **grid owner**, or a **generator** must take certain steps under this subpart if a **provisional price situation** or **shortage situation** exists; and
- (b) after any **provisional pricing situation** is resolved, but before making the **final prices** or **final reserve prices** available on **WITS**, the **pricing manager** must make **interim prices** and **interim reserve prices** available on **WITS**; and (c) if an **error claimant** claims that a **pricing error** has been made, the **pricing manager** must consider the claim and resolve any **pricing error** that has occurred; and
- (d) the **pricing manager** must produce **final prices** and send them to the **clearing manager**, who will then use them in the clearing and settlement processes; and
- (e) the **pricing manager** must produce **final reserve prices**.

Compare: Electricity Governance Rules 2003 rule 2 section V part G

Clause 13.132(a): amended, on 1 June 2013, by clause 8 of the Electricity Industry Participation (Scarcity Pricing) Code Amendment 2011.

Clause 13.132(b): replaced, on 5 October 2017, by clause 386 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### 13.133 Trigger ratio for high spring washer price situation

The value of the **high spring washer price trigger ratio** is 5.

Compare: Electricity Governance Rules 2003 rule 2A section V part G

### 13.134 Methodology to resolve high spring washer price situation

- (1) This clause applies if the **pricing manager**, in relation to a **trading period**,—
  - (a) gives notice in accordance with clauses 13.144(1), 13.156(1)(e), or 13.159(a)(iii) that a **high spring washer price situation** exists; or
  - (b) **publishes provisional prices** and **provisional reserve prices** in accordance with clauses 13.149 or 13.150 because the revised data required by clause 13.146 or the notice required by clause 13.147 in relation to a **high spring washer price situation** have not been given; or
  - (c) **publishes provisional prices** and **provisional reserve prices** in accordance with clause 13.153 because the revised data provided in accordance with clause 13.146 or the notice given in accordance with clause 13.147 have given rise to a **high spring washer price situation**.
- (2) If this clause applies, the **system operator** must—
  - (a) identify each **transmission security constraint** that has **bound** in the relevant **trading period**; and
  - (b) identify the **constraint price** associated with each **transmission security constraint** identified in accordance with paragraph (a); and
  - (c) apply the **high spring washer price relaxation factor**—
    - (i) to the maximum flow limit of the **transmission security constraint** with the highest associated **constraint price**; or
    - (ii) if 2 or more **transmission security constraints** have the equal highest associated **constraint price**, to the maximum flow limit of each of those **transmission security constraints**.
- (2A) *[Revoked]*
- (2B) *[Revoked]*
- (3) *[Revoked]*
- (4) After the **system operator** has applied the **high spring washer price relaxation factor** under subclause (2)(c), the **system operator** must determine whether a **high spring washer price situation** still exists in the **trading period**.
- (5) If the **system operator** determines under subclause (4) that a **high spring washer price situation** still exists in the **trading period**, the **system operator** must reapply the **high spring washer price situation methodology** for that **trading period** unless subclause (6) applies.
- (6) The **system operator** must not reapply the **high spring washer price situation methodology** under subclause (5) if doing so would require the **system operator** to apply the **high spring washer price relaxation factor** to a maximum flow limit to which the **high spring washer price relaxation factor** has already been applied for the **trading period**.

Compare: Electricity Governance Rules 2003 rule 2B section V part G  
Clause 13.134(2): substituted, on 23 December 2011, by clause 4 of the Electricity Industry Participation (High Spring Washer Price Situation) Code Amendment 2011.  
Clause 13.134(2A) and (2B): inserted, on 23 December 2011, by clause 4 of the Electricity Industry Participation (High Spring Washer Price Situation) Code Amendment 2011.  
Clause 13.134(1): amended, on 21 September 2012, by clause 5(1) of the Electricity Industry Participation (High Spring Washer Price Situation) Code Amendment 2012.  
Clause 13.134(2): substituted, on 21 September 2012, by clause 5(2) of the Electricity Industry Participation (High Spring Washer Price Situation) Code Amendment 2012.  
Clause 13.134(2A), (2B) and (3): revoked, on 21 September 2012, by clause 5(2) of the Electricity Industry Participation (High Spring Washer Price Situation) Code Amendment 2012.  
Clause 13.134(4), (5) and (6): inserted, on 21 September 2012, by clause 5(2) of the Electricity Industry Participation (High Spring Washer Price Situation) Code Amendment 2012.

*Rules governing the preparation of provisional, interim, and final prices*

### 13.135 Methodology used to prepare provisional, interim, and final prices

Subject to clause 13.135B, to calculate **provisional prices, provisional reserve prices, interim prices, interim reserve prices, final prices and final reserve prices** the **pricing manager** must use—

- (a) the **input information** in clause 13.141; and
- (b) the methodology in Schedule 13.3.

Compare: Electricity Governance Rules 2003 rule 3.1 section V part G  
Clause 13.135: amended, on 1 June 2013, by clause 9 of the Electricity Industry Participation (Scarcity Pricing) Code Amendment 2011.

#### 13.135A Notice of scarcity pricing situation

- (1) This clause applies if the **pricing manager**, in relation to a **trading period**, gives written notice in accordance with clause 13.144(1) that a **shortage situation** exists.
- (2) If this clause applies, the **pricing manager** must determine whether a **scarcity pricing situation** exists in the relevant **trading period**.
- (2A) The **pricing manager** must determine whether a **scarcity pricing situation** exists in the relevant **trading period** only after the **pricing manager** has—
  - (a) calculated **interim prices** for the 336 **trading periods** before the relevant **trading period**; and
  - (b) if an **infeasibility situation** caused by a shortage of **instantaneous reserve** existed in any of the 336 **trading periods** before the relevant **trading period**, either—
    - (i) recalculated **interim prices** for that **trading period** in accordance with clause 13.166A; or
    - (ii) calculated **interim prices** for that **trading period** in accordance with clause 13.164(b).
- (3) An **island scarcity pricing situation** exists for an **island** if the **pricing manager** gives notice that an **island shortage situation** existed and the **input information** or revised data shows that—
  - (a) for the relevant **trading period**, there is no **binding constraint** in the **island** (excluding the **HVDC link**) in which an **island shortage situation** declaration is made; and
  - (b) for the relevant **trading period**—
    - (i) the **HVDC link** is in service and—

- (A) if the **island** in which the **island shortage situation** declaration is made is the South Island, the price at the Benmore **node** is higher than the price at the Haywards **node**; or
    - (B) if the **island** in which the **island shortage situation** declaration is made is the North Island, the price at the Haywards **node** is higher than the price at the Benmore **node**; or
  - (ii) the **HVDC link** is out of service.
  - (4) A **national scarcity pricing situation** exists if the **pricing manager** gives notice that a **national shortage situation** existed and the **input information** or revised data shows that, for the relevant **trading period**,—
    - (a) there is no **binding constraint** in either **island**; and
    - (b) the **HVDC link** is in service and there is no **binding constraint** on the **HVDC link**.
  - (5) If the **pricing manager** determines that a **scarcity pricing situation** exists, the **pricing manager** must—
    - (a) give written notice of the **scarcity pricing situation** on **WITS** and to the **system operator**, relevant **grid owner**, and any person that has requested notice; and
    - (b) specify in the notice each **trading period** affected by the **scarcity pricing situation**; and
    - (c) in relation to each **trading period** affected by the **scarcity pricing situation**, specify in the notice whether the **scarcity pricing situation** is an **island scarcity pricing situation** or a **national scarcity pricing situation**.
  - (6) If the **pricing manager** determines that a **scarcity pricing situation** does not exist, the **pricing manager** must give written notice of its determination on **WITS** and to the **system operator**, relevant **grid owner**, and any persons that request notice.
- Clause 13.135A: inserted, on 1 June 2013, by clause 10 of the Electricity Industry Participation (Scarcity Pricing) Code Amendment 2011.
- Clause 13.135A(1): amended, on 5 October 2017, by clause 387(a) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.
- Clause 13.135A(2A): inserted, on 19 January 2017, by clause 5(1) of the Electricity Industry Participation Code Amendment (Scarcity Pricing) 2016.
- Clause 13.135A(5)(a): replaced, on 5 October 2017, by clause 387(b) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.
- Clause 13.135A(6): inserted, on 19 January 2017, by clause 5(2) of the Electricity Industry Participation Code Amendment (Scarcity Pricing) 2016.
- Clause 13.135A(6): amended, on 5 October 2017, by clause 387(c) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### **13.135B Methodology to prepare interim prices and interim reserve prices if scarcity pricing situation exists**

- (1) Subject to clause 13.135C, if a **scarcity pricing situation** exists in a **trading period**, the **pricing manager** must—
  - (a) calculate **interim prices** and **interim reserve prices** in the affected **island** or **islands** for that **trading period** in accordance with the methodology set out in Schedule 13.3A; and
  - (b) make **interim prices** and **interim reserve prices** available on **WITS** for the **trading period** by—

- (i) if no notice of a **provisional price situation** is given, 1200 hours in the following **trading day**; or
  - (ii) if notice of a **provisional price situation** is given, 4 hours after the **provisional price situation** is resolved.
- (2) Despite subclause (1), subclause (3) applies if a **scarcity pricing situation** exists in a **trading period**, and there is a change to—
  - (a) **interim prices** or **interim reserve prices** calculated and made available on **WITS** under subclause (1) for the **trading period**; or
  - (b) **interim prices** or **interim reserve prices** made available on **WITS** for any of the **336 trading periods** before the **trading period**.
- (3) If this subclause applies, the **pricing manager** must—
  - (a) recalculate **interim prices** and **interim reserve prices** in the affected **island** or **islands** for the **trading period** in which the **scarcity pricing situation** exists, in accordance with the methodology set out in Schedule 13.3A; and
  - (b) make the recalculated **interim prices** and **interim reserve prices** available on **WITS** no later than 4 hours after the change to **interim prices** or **interim reserve prices**.

Clause 13.135B: inserted, on 1 June 2013, by clause 10 of the Electricity Industry Participation (Scarcity Pricing) Code Amendment 2011.

Clause 13.135B(b)(ii): amended, on 19 January 2017, by clause 6(1) of the Electricity Industry Participation Code Amendment (Scarcity Pricing) 2016.

Clause 13.135B(1)(b): replaced, on 5 October 2017, by clause 388(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 13.135B(2): amended, on 5 October 2017, by clause 388(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 13.135B(2) and (3): inserted, on 19 January 2017, by clause 6(2) of the Electricity Industry Participation Code Amendment (Scarcity Pricing) 2016.

Clause 13.135B(3)(b): amended, on 5 October 2017, by clause 388(3) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### 13.135C Limitation on application of scarcity pricing provisions

Clause 13.135B does not apply—

- (a) in the case of an **island scarcity pricing situation**, if the average **island GWAP** in the previous **336 trading periods** in the **island** affected by the **scarcity pricing situation** exceeds \$1,000 per MWh; or
- (b) in the case of a **national scarcity pricing situation**, if the average **island GWAP** in the previous **336 trading periods** in either **island** exceeds \$1,000 per MWh.

Clause 13.135C: inserted, on 1 June 2013, by clause 10 of the Electricity Industry Participation (Scarcity Pricing) Code Amendment 2011.

#### *Generators to give grid owner half-hour metering information*

Cross heading: amended, on 19 December 2014, by clause 27 of the Electricity Industry Participation Code Amendment (Minor Code Amendments) (No 3) 2014.

### 13.136 Generators to provide half-hour metering information

- (1) Using an **approved system** or by written notice, each **generator** must give the relevant **grid owner half-hour metering information** under clause 13.138 in relation to **generating plant** that is subject to a **dispatch instruction**—
  - (a) that injects **electricity** directly into a **local network** or an **embedded network**; or

- (b) if the **meter** configuration is such that the **electricity** flows into a **local network** without first passing through a **grid injection point** or **grid exit point metering installation**.
- (1A) For the purposes of subclause (1), the relevant **grid owner** is—
  - (a) in relation to a **generator** (other than an **embedded generator**), the **grid owner** of the **grid** to which the **generator's generation** is connected; and
  - (b) in relation to a **generator** that is an **embedded generator**, the **grid owner** of the **grid** to which the **local network** to which the **embedded generator** is directly or indirectly connected, is connected.
- (2) To avoid doubt, subclause (1) does not apply in respect of—
  - (a) any **unoffered generation**; or
  - (b) **electricity** supplied from—
    - (i) an **intermittent generating station**; or
    - (ii) a **type B industrial co-generating station**.

Compare: Electricity Governance Rules 2003 rule 3.2.1 section V part G

Clause 13.136(1): substituted, on 19 December 2014, by clause 28 of the Electricity Industry Participation Code Amendment (Minor Code Amendments) (No 3) 2014.

Clause 13.136(1): amended, on 5 October 2017, by clause 389(a) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017. Clause 13.136(1A): inserted, on 19 December 2014, by clause 28 of the Electricity Industry Participation Code Amendment (Minor Code Amendments) (No 3) 2014.

Clause 13.136(1A): amended, on 23 February 2015, by clause 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 13.136(1A)(a) and (b): amended, on 5 October 2017, by clause 389(b) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 13.136(2): substituted, on 27 May 2015, by clause 10 of the Electricity Industry Participation Code Amendment (Industrial Co-generation Dispatch Arrangements) 2015.

### **13.137 Generators to provide half-hour metering information for unoffered and intermittent generation, and type B industrial co-generation**

- (1) Using an **approved system** or by written notice, each **generator** must give the relevant **grid owner half-hour metering information** for—
  - (a) **unoffered generation** from a **generating station** with a **point of connection** to the **grid**; and
  - (b) **electricity** supplied from an **intermittent generating station** with a **point of connection** to the **grid**; and
  - (c) **electricity** supplied from a **type B industrial co-generating station** with a **point of connection** to the **grid**.
- (2) To avoid doubt, each **generator** must give the relevant **grid owner** the **half-hour metering information** required under this clause in accordance with the requirements of Part 15 for the collection of the **generator's volume information**.
- (3) If the **half-hour metering information** is not available, the **generator** must give the relevant **grid owner** a reasonable estimate of such data using an **approved system** or by written notice.

Compare: Electricity Governance Rules 2003 rule 3.2.2 section V part G

Clause 13.137 Heading: substituted, on 27 May 2015, by clause 11(1) of the Electricity Industry Participation Code Amendment (Industrial Co-generation Dispatch Arrangements) 2015.

Clause 13.137 Heading: amended, on 5 October 2017, by clause 390(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 13.137: amended, on 19 December 2014, by clause 29 of the Electricity Industry Participation Code Amendment (Minor Code Amendments) (No 3) 2014.

Clause 13.137(1)(b): amended, on 27 May 2015, by clause 11(2) of the Electricity Industry Participation Code Amendment (Industrial Co-generation Dispatch Arrangements) 2015.

Clause 13.137(1)(c): inserted, on 27 May 2015, by clause 11(3) of the Electricity Industry Participation Code Amendment (Industrial Co-generation Dispatch Arrangements) 2015.

Clause 13.137 (1) and (3): amended, on 5 October 2017, by clause 390(2)(a) and (b) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### **13.138 Generator's half-hour metering information to be adjusted for losses**

- (1) Each **generator** must provide the information required by clauses 13.136 and 13.137—
  - (a) adjusted for **losses** (if any) relative to the **grid injection point** or, for **embedded generators** the **grid exit point**, at which it offered the **electricity**; and
  - (b) in the manner and form that the relevant **grid owner** stipulates; and
  - (c) by 0500 hours on a **trading day** for each **trading period** of the previous **trading day**.
- (2) To avoid doubt, each **generator** must provide the **half-hour metering information** required under this clause in accordance with the requirements of Part 15 for the collection of that **generator's volume information**.

Compare: Electricity Governance Rules 2003 rule 3.2.3 section V part G

Clause 13.138 Heading: amended, on 15 May 2014, by clause 43 of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

Clause 13.138(1)(b): amended, on 19 December 2014, by clause 30 of the Electricity Industry Participation Code Amendment (Minor Code Amendments) (No 3) 2014.

### **13.138A Dispatchable load purchaser's half-hour metering information to be adjusted for losses**

- (1) Using an **approved system** or by written notice, each **dispatchable load purchaser** must provide **half-hour metering information** to the relevant **grid owner**—
  - (a) for each of its **dispatch-capable load stations**; and
  - (b) in accordance with subclause (2).
- (2) Each **dispatchable load purchaser** must provide the **half-hour metering information**—
  - (a) adjusted for **losses**, if any, relative to the **grid exit point** at which the **dispatchable load purchaser** purchases **electricity** for the **dispatch-capable load station**; and
  - (b) in the manner and form advised by the relevant **grid owner**; and
  - (c) by 0500 hours on a **trading day** for each **trading period** of the previous **trading day**.
- (3) To avoid doubt, each **dispatchable load purchaser** must prepare the **half-hour metering information** required under this clause in accordance with the requirements of Part 15 for the collection of the **dispatchable load purchaser's volume information**.
- (4) If the **Authority** or the **system operator** requests a copy of the information specified in subclause (2) from a **dispatchable load purchaser**, the **dispatchable load purchaser** must comply with the request.

Clause 13.138A: inserted, on 15 May 2014, by clause 44 of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

Clause 13.138A(1): amended, on 19 December 2014, by clause 31(1) of the Electricity Industry Participation Code Amendment (Minor Code Amendments) (No 3) 2014.

Clause 13.138A(1): amended, on 5 October 2017, by clause 391 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 13.138A(2)(b): amended, on 19 December 2014, by clause 31(2) of the Electricity Industry Participation Code Amendment (Minor Code Amendments) (No 3) 2014.

### 13.138B System operator to give list of trading periods

- (1) The **system operator** must give the **pricing manager** and the relevant **grid owner** a list showing, in relation to each **dispatch-capable load station**, each **trading period** in the previous **trading day** for which there is a **nominated dispatch bid**.
- (2) The **system operator** must give the list to the **pricing manager** and the relevant **grid owner**—
  - (a) by 0500 hours on each **trading day**; and
  - (b) in the manner and form agreed by the **pricing manager** and the **system operator**.

Clause 13.138B: inserted, on 15 May 2014, by clause 44 of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

### 13.139 Half-hour metering information part of input information

The adjusted **half-hour metering information** provided under clauses 13.136 to 13.138A forms part of the input information in the formula in clause 13.141(1)(b)(i).

Compare: Electricity Governance Rules 2003 rule 3.2.4 section V part G

Clause 13.139: substituted, on 19 December 2014, by clause 32 of the Electricity Industry Participation Code Amendment (Minor Code Amendments) (No 3) 2014.

### 13.140 Generators and dispatchable load purchasers to advise grid owner of having provided half-hour metering information

- (1) This clause applies to—
  - (a) a **generator**; and
  - (b) a **dispatchable load purchaser**.
- (2) If a **participant** to which this clause applies provides **half-hour metering information** to a **grid owner** under clauses 13.136 to 13.138, or 13.138A, the **participant** must advise the relevant **grid owner** by 0500 hours on the day the **participant** provided the **half-hour metering information** to the relevant **grid owner**.

Compare: Electricity Governance Rules 2003 rule 3.2.5 section V part G

Clause 13.140 Heading: amended, on 5 October 2017, by clause 392 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 13.140: substituted, on 15 May 2014, by clause 45 of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

Clause 13.140(2): substituted, on 19 December 2014, by clause 33 of the Electricity Industry Participation Code Amendment (Minor Code Amendments) (No 3) 2014.

### 13.141 Pricing manager to use certain input information

- (1) The **pricing manager** must use the following **input information**:
  - (a) for existing generation configuration—
    - (i) data specifying the instantaneous **MW injection** at the **grid injection point** at the beginning of each **trading period** for each **generating plant** and each **generating unit** that was the subject of **offers** for that **trading period**; or
    - (ii) if no such data is available, a reasonable estimate of such data:
  - (b) for actual **demand** over the **trading period**,—
    - (i) the **demand half-hour metering information** described as  $L_{MA}$  below must be calculated as follows:



$L_{MA} = G_{EA} + L_{MX} - L_{DCLS}$  (for a **grid exit point**)

$L_{MA} = G_{EA} - L_{MI} - L_{DCLS}$  (for a **grid injection point**)

$L_{MA} = L_{MX} - L_{DCLS} - UIG_{EA}$  (for an **intermittent generating station** with a **point of connection** to the **grid**, and/or **unoffered generation** from a **generating station** with a **point of connection** to the **grid**, and/or a **type B industrial co-generating station** with a **point of connection** to the **grid**)

where

$L_{MA}$  is the adjusted quantity of **electricity** measured in **MWh** by a **metering installation** at a **grid exit point** or **grid injection point**

$L_{MX}$  is the unadjusted **half-hour metering information** for the quantity of **electricity** measured in **MWh** at a **grid exit point**

$L_{MI}$  is the unadjusted **half-hour metering information** for the quantity of **electricity** measured in **MWh** at a **grid injection point**

$L_{DCLS}$  is the adjusted **half-hour metering information** for the quantity of **electricity** measured in **MWh** used by a **dispatch-capable load station** for the **trading periods** that the **system operator** listed under clause 13.138B

$G_{EA}$  is the adjusted **half-hour metering information** given to the relevant **grid owner** under clause 13.136

$UIG_{EA}$  is the information given to the relevant **grid owner** under clause 13.137:

- (ii) if any of the **half-hour metering information** is not available, an **initial estimate** for each **grid exit point** or **grid injection point**:
  - (iii) to avoid doubt, each **grid owner** must, using an **approved system**, provide the **half-hour metering information** to the **pricing manager** required under this clause in accordance with Part 15 for the collection of that **grid owner's volume information**:
- (c) the final **offers** for each **trading period** submitted by **generators** and provided to the **pricing manager** by the **system operator** in accordance with clause 13.63:
  - (ca) the final **nominated dispatch bid** for each **dispatch-capable load station** (other than a **dispatch-capable load station** for which the final **nominated bid** for the **trading period** was a **nominated non-dispatch bid**) dispatched in each **trading period** that was provided to the **pricing manager** by the **system operator** in accordance with clause 13.63:
  - (d) the final **reserve offers** for each such **trading period** as given by **ancillary service agents** in accordance with clauses 13.37 to 13.54:
  - (e) the final information provided to the **system operator** by a **grid owner** under clauses 13.29 to 13.34 for each **trading period** for which the **system operator** makes final information available under clause 13.63.
- (1AA) The **pricing manager** must remove all **offers** from the following **participants** from the information specified in subclause (1)(c) before using it in the pricing process:

- (a) **intermittent generators**; and
  - (b) **type B co-generators**.
- (1A) Each **grid owner** must give the **pricing manager** the information the **pricing manager** is required to use under subclause (1)(a)—
- (a) by 0730 hours on each **trading day**; and
  - (b) for each **trading period** of the previous **trading day**; and
  - (c) in the manner and form agreed by the **pricing manager** and each **grid owner**.
- (2) Each **grid owner** must give the information required by subclause (1)(b) to the **pricing manager** by 0730 hours on a **trading day** for each **trading period** of the previous **trading day**. Each **grid owner** must provide this information in the form specified by the **pricing manager**.
- (3) The **pricing manager** must make the information available on **WITS**, and at no cost on a publicly accessible **approved system**, by 1000 hours on a **trading day** for each **trading period** of the previous **trading day**.
- (4) If the **pricing manager** receives revised demand **half-hour metering information** in accordance with clauses 13.146(1) and 13.154(1A)(b), and if the revised information resolves a **provisional price situation**, the **pricing manager** must make the revised demand **half-hour metering information** available on **WITS**, and at no cost on a publicly accessible **approved system**, no later than the time at which it is required to make **interim prices** and **interim reserve prices** available on **WITS**.
- (5) If the **pricing manager** receives revised information after it has made information available under subclause (3), the **pricing manager** must replace the information previously made available with the revised information.

Compare: Electricity Governance Rules 2003 rule 3.3 section V part G

Clause 13.141(1)(a) & (b): substituted, on 15 May 2014, by clause 46(a) of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

Clause 13.141(1)(b)(i): amended, on 19 December 2014, by clause 34(1) of the Electricity Industry Participation Code Amendment (Minor Code Amendments) (No 3) 2014.

Clause 13.141(1)(b)(i): amended, on 27 May 2015, by clause 12(1) of the Electricity Industry Participation Code Amendment (Industrial Co-generation Dispatch Arrangements) 2015.

Clause 13.141(1)(b)(iii): amended, on 5 October 2017, by clause 393(a) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 13.141(1)(c): amended, on 27 May 2015, by clause 12(2) of the Electricity Industry Participation Code Amendment (Industrial Co-generation Dispatch Arrangements) 2015.

Clause 13.141(1)(ca): inserted, on 15 May 2014, by clause 46(b) of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

Clause 13.141(1)(ca): amended, on 1 December 2015, by clause 6 of the Electricity Industry Participation Code Amendment (Dispatchable Demand: Late Bid Revisions) 2015.

Clause 13.141(1)(e): amended, on 15 May 2014, by clause 46(c) of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

Clause 13.141(1)(e): amended, on 5 October 2017, by clause 393(b) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 13.141(1AA): inserted, on 27 May 2015, by clause 12(3) of the Electricity Industry Participation Code Amendment (Industrial Co-generation Dispatch Arrangements) 2015.

Clause 13.141(1A): inserted, on 15 May 2014, by clause 46(d) of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

Clause 13.141(3): amended, on 5 October 2017, by clause 393(c) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 13.141(4): amended, on 19 December 2014, by clause 34(2) of the Electricity Industry Participation Code Amendment (Minor Code Amendments) (No 3) 2014.

Clause 13.141(4): amended, on 5 October 2017, by clause 393(d) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 13.141(5): amended, on 21 September 2012, by clause 22 of the Electricity Industry Participation (Minor Amendments) Code Amendment 2012.

Clause 13.141(5): amended, on 19 December 2014, by clause 34(3) of the Electricity Industry Participation Code Amendment (Minor Code Amendments) (No 3) 2014.

Clause 13.141(5): replaced, on 5 October 2017, by clause 393(e) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### **13.142 Pricing manager to make interim prices available unless notice is given of provisional price situation or shortage situation**

- (1) The **pricing manager** must implement the process set out in clauses 13.143 to 13.185 and resolve the **provisional price situation** or **shortage situation** if, by 1000 hours on a **trading day**, 1 of the following notices has been given for the previous **trading day**:
  - (a) a written notice given by a **grid owner**, in accordance with clause 13.143, which specifies that a **SCADA situation** exists;
  - (b) a written notice given by the **pricing manager**, in accordance with clause 13.144(1), which specifies that an **infeasibility situation** or a **metering situation** or a **high spring washer price situation** or a **shortage situation** exists.
- (2) However, if by 1000 hours on a **trading day** a notice specified in subclause (1) has not been given for the previous **trading day**, the **pricing manager** must make **interim prices** and **interim reserve prices** for the previous **trading day** available on **WITS** by 1200 hours.

Compare: Electricity Governance Rules 2003 rule 3.4 section V part G

Clause 13.142 Heading: amended, on 1 June 2013, by clause 11(1) of the Electricity Industry Participation (Scarcity Pricing) Code Amendment 2011.

Clause 13.142 Heading: replaced, on 5 October 2017, by clause 394(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 13.142(1): amended, on 1 June 2013, by clause 11(2) of the Electricity Industry Participation (Scarcity Pricing) Code Amendment 2011.

Clause 13.142(1): amended, on 5 October 2017, by clause 394(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 13.142(1)(b): amended, on 1 June 2011, by clause 5 of the Electricity Industry Participation (Minor Amendments) Code Amendment 2011.

Clause 13.142(2): amended, on 5 October 2017, by clause 394(3) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### **13.143 Grid owners to give written notice of SCADA situation**

- (1) If a **grid owner** gives any **input information** in accordance with clause 13.141 to the **pricing manager**, the **grid owner** must—
  - (a) give written notice to the **pricing manager** and the **WITS manager** that the **grid owner** has given the **pricing manager input information**; and
  - (b) specify in the notice whether the **input information** yields a **SCADA situation**, and if so each **trading period** affected; and
  - (c) give details in the notice of the relevant **grid exit points** and **grid injection points** for which the **SCADA situation** exists.
- (2) A **grid owner** must give the notice required by subclause (1)(a) by 0730 hours on the day on which it gives the relevant **input information**.
- (3) Despite subclause (2), the **grid owner** may give further written notices to the **pricing manager** and the **WITS manager** advising that the **grid owner** has found that a **SCADA situation** exists and the **trading periods** that are affected by it.
- (4) A **grid owner** must give each written notice under subclause (3) no later than 0900 hours on the same day that it gave notice under subclause (1)(a).

- (5) As soon as practicable after receiving a written notice from a **grid owner** under this clause, the **WITS manager** must give the notice to any person that has requested it.

Compare: Electricity Governance Rules 2003 rule 3.5 section V part G

Clause 13.143 Heading: amended, on 5 October 2017, by clause 395(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 13.143(1), (3) and (4): amended, on 5 October 2017, by clause 395(2)(a) to (c) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 13.143(5): inserted, on 5 October 2017, by clause 395(2)(d) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### **13.144 Pricing manager to give written notice of infeasibility situation, metering situation, high spring washer price situation, or shortage situation**

- (1) Subject to subclause (2), if the **pricing manager** receives **input information** that yields an **infeasibility situation**, or a **metering situation**, or a **high spring washer price situation**, or receives notice of a **shortage situation** in accordance with clause 5(1A) of **Technical Code B** of Schedule 8.3, the **pricing manager** must—
- (a) give to the **system operator**, relevant **grid owner**, and any persons that request notice, written notice of the **infeasibility situation**, or **metering situation**, or **high spring washer price situation**, or **shortage situation**; and
  - (b) specify in the notice each **trading period** affected by the **infeasibility situation**, or **metering situation**, or **high spring washer price situation**, or **shortage situation**; and
  - (c) in relation to each **trading period** affected by a **high spring washer price situation**, specify in the notice each **transmission security constraint** that has **bound** in the relevant **trading period** or **trading periods**; and
  - (d) in relation to each **trading period** affected by a **shortage situation**, specify in the notice whether the **shortage situation** is an **island shortage situation** or a **national shortage situation**.
- (1A) For the purposes of subclauses (1)(b) and (1)(d), a **trading period** affected by a **shortage situation** is a **trading period** in respect of which a **shortage situation** was in effect at the start of the **trading period**.
- (2) The **pricing manager** must not give written notice of a **high spring washer price situation** or **shortage situation** in accordance with subclause (1) in relation to a **trading period** if an **infeasibility situation**, or a **metering situation**, or a **SCADA situation** exists in that **trading period** and has not been resolved.
- (3) Subject to subclause (4), the **pricing manager** must give written notice of an **infeasibility situation**, **metering situation**, **high spring washer price situation**, or **shortage situation** under subclause (1)(a) no later than 0900 hours on the day that the **pricing manager** receives the relevant **input information** or notice.
- (4) If a **shortage situation** exists at the same time as a **provisional price situation**, the **pricing manager** must give written notice of the **shortage situation** as soon as possible after the **pricing manager** resolves—
- (a) the **provisional price situation**; and
  - (b) any subsequent **provisional price situation** that arises from resolving the **provisional price situation**.
- (5) Despite subclause (4), if the **pricing manager** cannot resolve a **provisional price**

**situation** that exists at the same time as a **shortage situation**, the **pricing manager** must give written notice of the **shortage situation**—

- (a) after the **pricing manager** has given written notice under clause 13.164(a) in relation to the **trading periods** affected by the unresolved **provisional price situation**; but
- (b) before the **pricing manager** makes **interim prices** available under clause 13.164(b) for each **trading period** affected by the unresolved **provisional price situation**.

Compare: Electricity Governance Rules 2003 rules 3.6 and 3.6A section V part G

Clause 13.144 Heading: amended, on 1 June 2013, by clause 12(1) of the Electricity Industry Participation (Scarcity Pricing) Code Amendment 2011.

Clause 13.144 Heading: amended, on 5 October 2017, by clause 396(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 13.144(1): amended, on 1 June 2013, by clause 12(2)(a) and (b) of the Electricity Industry Participation (Scarcity Pricing) Code Amendment 2011.

Clause 13.144(1): amended, on 19 January 2017, by clause 7(1) of the Electricity Industry Participation Code Amendment (Scarcity Pricing) 2016.

Clause 13.144(1)(a): replaced, on 5 October 2017, by clause 396(2)(a) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 13.144(1)(a) and (b): amended, on 1 June 2013, by clause 12(2)(c) of the Electricity Industry Participation (Scarcity Pricing) Code Amendment 2011.

Clause 13.144(1)(c): amended, on 1 June 2013, by clause 12(2)(d) of the Electricity Industry Participation (Scarcity Pricing) Code Amendment 2011.

Clause 13.144(1)(d): inserted, on 1 June 2013, by clause 12(2)(e) of the Electricity Industry Participation (Scarcity Pricing) Code Amendment 2011.

Clause 13.144(1A): inserted, on 19 January 2017, by clause 7(2) of the Electricity Industry Participation Code Amendment (Scarcity Pricing) 2016.

Clause 13.144(2): amended, on 1 June 2013, by clause 12(3) of the Electricity Industry Participation (Scarcity Pricing) Code Amendment 2011.

Clause 13.144(2), (3), (4) and (5): amended, on 5 October 2017, by clause 396(2)(b) and (c) and (3) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 13.144(3), (4) and (5): inserted, on 19 January 2017, by clause 7(3) of the Electricity Industry Participation Code Amendment (Scarcity Pricing) 2016.

### **13.145 Grid owner to give written notice that estimated data given**

- (1) If a **grid owner** gives the **pricing manager** estimated **input information** in accordance with clauses 13.141(1)(a)(ii) or (b)(ii), the **grid owner** must, by 0730 hours on the day the relevant **input information** is required by clause 13.141—
  - (a) give written notice to the **pricing manager** and the **WITS manager** of any **input information** that is estimated; and
  - (b) specify in the notice whether the estimated information relates to **SCADA** or **half-hour metering information**; and
  - (c) give details in the notice of the **grid exit points** and **grid injection points** to which the estimated information relates; and
  - (d) specify in the notice whether the estimated information relates to a **dispatch capable load station** or a **type B industrial co-generating station**; and
  - (e) specify in the notice the **trading periods** for which the input information is estimated for each relevant **grid exit point**, **grid injection point**, and **dispatch capable load station**.

- (2) As soon as practicable after receiving a written notice from a **grid owner** under this clause, the **WITS manager** must give the notice to any person that has requested it.

Compare: Electricity Governance Rules 2003 rule 3.7 section V part G

Clause 13.145 Heading: amended, on 5 October 2017, by clause 397(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 13.145(1)(a): amended, on 5 October 2017, by clause 397(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 13.145(1)(c): amended, on 19 December 2014, by clause 35(1) of the Electricity Industry Participation Code Amendment (Minor Code Amendments) (No 3) 2014.

Clause 13.145(1)(d) and (e): inserted, on 19 December 2014, by clause 35(2) of the Electricity Industry Participation Code Amendment (Minor Code Amendments) (No 3) 2014.

Clause 13.145(1)(d): amended, on 27 May 2015, by clause 13 of the Electricity Industry Participation Code Amendment (Industrial Co-generation Dispatch Arrangements) 2015.

Clause 13.145(2): inserted, on 5 October 2017, by clause 397(2)(b) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### 13.146 Requirements if provisional price situation or shortage situation exists

- (1) If notice is given by—
  - (a) a **grid owner** to the **pricing manager** of a **SCADA situation** in accordance with clause 13.143; or
  - (b) the **pricing manager** of a **metering situation** in accordance with clause 13.144(1); or
  - (c) the **pricing manager** of an **infeasibility situation** in accordance with clause 13.144(1)—  
the relevant **grid owner**, and, in the case of an **infeasibility situation**, the **system operator**, must exercise reasonable endeavours to resolve the **provisional price situation** and to provide revised data to the **pricing manager** using an **approved system**.
- (2) If notice is given of a **high spring washer price situation** in accordance with clause 13.144(1), the **system operator** must apply the **high spring washer price relaxation factor** in accordance with the **high spring washer price situation methodology** and provide revised data to the **pricing manager** using an **approved system**.
- (2A) If the **pricing manager** gives notice of a **shortage situation** in accordance with clause 13.144(1), the **pricing manager** must determine whether a **scarcity pricing situation** exists in accordance with clause 13.135A and, if a **scarcity pricing situation** does exist, calculate **interim prices** and **interim reserve prices** in accordance with clause 13.135B.
- (3) The revised data required by subclauses (1) and (2) must be provided to the **pricing manager**—
  - (a) if the **provisional price situation** arose on a **business day**, by 1000 hours on that day; and
  - (b) if the **provisional price situation** arose on a day other than a **business day**, by 1200 hours on the 2<sup>nd</sup> **business day** after the **provisional price situation** arose.
- (4) If a **generator** or a **dispatchable load purchaser** does not give **half-hour metering information** to a **grid owner** in accordance with clauses 13.136 to 13.140, and the **pricing manager** has given notice of a **metering situation** in accordance with clause 13.144(1), the **generator** or the **dispatchable load purchaser** must use reasonable endeavours to assist the **grid owner** to resolve the **provisional price situation**.

Compare: Electricity Governance Rules 2003 rule 3.8 section V part G

Clause 13.146 Heading: amended, on 1 June 2013, by clause 13(1) of the Electricity Industry Participation (Scarcity Pricing) Code Amendment 2011.

Clause 13.146(1) and (2): amended, on 5 October 2017, by clause 398(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 13.146(2A): inserted, on 1 June 2013, by clause 13(2) of the Electricity Industry Participation (Scarcity Pricing) Code Amendment 2011.

Clause 13.146(4): amended, on 15 May 2014, by clause 47 of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

Clause 13.146(4): amended, on 19 December 2014, by clause 36 of the Electricity Industry Participation Code Amendment (Minor Code Amendments) (No 3) 2014.

Clause 13.146(4): amended, on 5 October 2017, by clause 398(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### 13.147 Revised data to be accompanied by written notice

- (1) Subclauses (2) and (3) apply to—
  - (a) a **grid owner**; and
  - (b) *[Revoked]*
  - (c) the **system operator**.
  - (d) *[Revoked]*
- (2) If a **participant** listed under subclause (1) gives revised data to the **pricing manager** under clause 13.146, the **participant** must—
  - (a) give written notice to the following **participants** that the **participant** has given revised data:
    - (i) if a **grid owner** gave the revised data, the **pricing manager**, **WITS manager**, **system operator**, and any other **grid owners**; or
    - (ii) if the **system operator** gave the revised data, the **pricing manager**, **WITS manager**, and **grid owners**; and
  - (b) specify in the notice the revisions that have been made; and
  - (c) in the case of revised data given in relation to a **SCADA situation**, state in the notice whether a **SCADA situation** continues to exist; and
  - (d) in the case of revised data given in relation to a **high spring washer price situation**, state in the notice whether the **high spring washer price relaxation factor** has been applied.
- (3) A **participant** listed under subclause (1) must comply with subclause (2) within the timeframes specified in clause 13.146(3) as if references to the revised data in clause 13.146(3) are references to a notice under this clause.
- (4) As soon as practicable after receiving a written notice under this clause, the **WITS manager** must give the notice to any person that has requested it.

Compare: Electricity Governance Rules 2003 rule 3.9 section V part G

Clause 13.147 Heading: amended, on 5 October 2017, by clause 399(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 13.147: substituted, on 15 May 2014, by clause 48 of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

Clause 13.147(1), (2) and (3): amended, on 5 October 2017, by clause 399(2)(a) and (b) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 13.147(1)(b) and (d): revoked, on 19 December 2014, by clause 37(1) of the Electricity Industry Participation Code Amendment (Minor Code Amendments) (No 3) 2014.

Clause 13.147(1)(c): amended, on 19 December 2014, by clause 37(2) of the Electricity Industry Participation Code Amendment (Minor Code Amendments) (No 3) 2014.

Clause 13.147(2)(a): replaced, on 5 October 2017, by clause 399(2)(c) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 13.147(4): inserted, on 5 October 2017, by clause 399(2)(d) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### 13.148 Failure to give revised data and notice not breach

A **participant** that is listed in clause 13.147(1) does not breach clauses 13.146(3) or 13.147(3) if the **participant** has,—

- (a) in the case of a **provisional price situation** other than a **high spring washer price situation**, exercised reasonable endeavours to remedy the circumstance giving rise to the **provisional price situation**; and
- (b) in the case of a **high spring washer price situation**, applied the **high spring washer price relaxation factor** in accordance with the **high spring washer price situation methodology**; and
- (c) used reasonable endeavours to provide the notice required by clause 13.147.

Compare: Electricity Governance Rules 2003 rule 3.10 section V part G

Clause 13.148: amended, on 15 May 2014, by clause 49 of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

### 13.149 Pricing manager to make provisional prices and provisional reserve prices available if revised data and notice not given regarding provisional pricing situation arising on business day

- (1) This clause applies if—
  - (a) a notice of a **provisional price situation** is given on a **business day**; and
  - (b) a **participant** that is listed in clause 13.147(1)—
    - (i) does not comply with the timeframes specified in clause 13.146(3); or
    - (ii) does not comply with the timeframes specified in clause 13.147(3).
- (2) If this clause applies, the **pricing manager** must—
  - (a) by 1200 hours on that day, give to the **system operator**, relevant **grid owner**, and any persons that request notice, written notice of the **provisional price situation** and each **trading period** affected; and
  - (b) by 1200 hours on that day, make **provisional prices** and **provisional reserve prices** available on **WITS**; and
  - (c) by 0900 hours on the following day, inform the **Authority** of the **provisional price situation** in the daily report submitted under clause 13.213.

Compare: Electricity Governance Rules 2003 rule 3.11 section V part G

Clause 13.149 Heading: replaced, on 5 October 2017, by clause 400(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 13.149: amended, on 15 May 2014, by clause 50 of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

Clause 13.149(2)(a) and (b): amended, on 5 October 2017, by clause 400(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### 13.150 Pricing manager to make provisional prices and provisional reserve prices available if revised data and notice not given regarding provisional price situation arising on day other than business day

- (1) This clause applies if—
  - (a) a notice of a **provisional price situation** is given on a day other than a **business day**; and
  - (b) a **participant** that is listed in clause 13.147(1),—
    - (i) does not comply with the timeframes in clause 13.146(3); or
    - (ii) does not comply with the timeframes in clause 13.147(3).
- (2) If this clause applies, the **pricing manager** must—



- (a) by 1000 hours on the day that the notice of a **provisional price situation** was given, give to the **system operator**, relevant **grid owner**, and any persons that request notice, written notice of the **provisional price situation** and each **trading period** affected; and
- (b) by 1000 hours on that day make **provisional prices** and **provisional reserve prices** available on **WITS**; and
- (c) by 0900 hours on the following day inform the **Authority** of the **provisional price situation** in the daily report submitted under clause 13.213.

Compare: Electricity Governance Rules 2003 rule 3.12 section V part G

Clause 13.150 Heading: replaced, on 5 October 2017, by clause 401(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 13.150: amended, on 15 May 2014, by clause 51 of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

Clause 13.150(2)(a) and (b): amended, on 5 October 2017, by clause 401(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### **13.151 Data to be used by pricing manager to determine provisional prices and provisional reserve prices**

The **pricing manager** must produce **provisional prices** and **provisional reserve prices**—

- (a) on a **business day**, by using the latest data given to it by 1000 hours on that day; and
- (b) on a day other than a **business day**, by using the data given to it by 0730 hours on that day.

Compare: Electricity Governance Rules 2003 rule 3.13 section V part G

### **13.152 Pricing manager to make interim prices and interim reserve prices available if revised data resolves provisional price situation**

- (1) This clause applies if a **participant** that is listed in clause 13.147(1)—
  - (a) gives revised data in accordance with clause 13.146 (that does not itself give rise to a **provisional price situation**); or
  - (b) gives written notice in accordance with clause 13.147.
- (2) If this clause applies, the **pricing manager** must make **interim prices** and **interim reserve prices** available on **WITS** for each **trading period** of the previous **trading day**.
- (3) The **pricing manager** must make the **interim prices** and **interim reserve prices** available on **WITS** by 1200 hours on the day that the revised data and notice were required to be given.

Compare: Electricity Governance Rules 2003 rule 3.14 section V part G

Clause 13.152 Heading: amended, on 5 October 2017, by clause 402(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 13.152: substituted, on 15 May 2014, by clause 52 of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

Clause 13.152: amended, on 5 October 2017, by clause 402(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### **13.153 Revised data gives rise to provisional price situation**

If revised data provided in accordance with clause 13.146 gives rise to a **provisional price situation**, the **pricing manager** must make **provisional prices** and **provisional**

**reserve prices** available on **WITS** in accordance with clauses 13.149 and 13.150, as if no data had been received.

Compare: Electricity Governance Rules 2003 rule 3.15 section V part G

Clause 13.153: amended, on 5 October 2017, by clause 403 of the Electricity Industry Participation Code

Amendment (Code Review Programme) 2017.

**13.154 Grid owner, generators, dispatchable load purchasers, and system operator to give revised data if provisional prices and provisional reserve prices have been made available**

- (1) This clause applies if the **pricing manager** makes **provisional prices** and **provisional reserve prices** available on **WITS** under clause 13.149 or 13.150.
- (1A) If **provisional prices** and **provisional reserve prices** are made available on **WITS** in relation to—
  - (a) an **infeasibility situation** or a **SCADA situation**, the **grid owner** and, in the case of an **infeasibility situation**, the **system operator**, must use reasonable endeavours to resolve the **provisional price situation** and provide revised data to the **pricing manager** using an **approved system**; or
  - (b) a **metering situation**, the **grid owner** or the **generator** or the **dispatchable load purchaser** (as the case may be) must provide revised **metering information** in accordance with clause 13.166; or
  - (c) a **high spring washer price situation**, the **system operator** must apply the **high spring washer price relaxation factor** in accordance with the **high spring washer price situation methodology** and use reasonable endeavours to provide revised data to the **pricing manager** using an **approved system**.
- (2) The revised data required by subclause (1A) must be provided to the **pricing manager** by 1200 hours on the 2<sup>nd</sup> **business day** after the **pricing manager** makes the **provisional prices** and **provisional reserve prices** available on **WITS**.

Compare: Electricity Governance Rules 2003 rule 3.16 section V part G

Clause 13.154 Heading: amended, on 15 May 2014, by clause 53(a) of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

Clause 13.154 Heading: amended, on 5 October 2017, by clause 404(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 13.154(1): substituted, on 15 May 2014, by clause 53(b) of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

Clause 13.154(1): amended, on 5 October 2017, by clause 404(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 13.154(1A): inserted, on 15 May 2014, by clause 53(b) of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

Clause 13.154(1A): amended, on 5 October 2017, by clause 404(3) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 13.154(2): amended, on 15 May 2014, by clause 53(c) of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

Clause 13.154(2): amended, on 5 October 2017, by clause 404(4) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

**13.155 Revised data to be accompanied by written notice**

- (1) If a **participant** that is listed in clause 13.147(1) gives revised data in accordance with clause 13.154 to the **pricing manager**, the **participant** must, by the time prescribed by that clause for giving revised data,—
  - (a) give written notice to the following **participants** that the **participant** has given revised data:

- (i) if a **grid owner** gave the revised data, the **pricing manager**, **WITS manager**, **system operator**, and any other **grid owners**; or
  - (ii) if the **system operator** gave the revised data, the **pricing manager**, **WITS manager**, and **grid owners**; and
  - (b) specify in the notice the revisions that have been made; and
  - (c) in the case of revised data given in relation to a **metering situation** or a **SCADA situation**, state in the notice whether a **metering situation** or a **SCADA situation** continues to exist; and
  - (d) in the case of revised data given in relation to a **high spring washer price situation**, if the **high spring washer price situation relaxation factor** has been applied, state in the notice that the factor has been applied.
- (2) As soon as practicable after receiving a written notice under subclause (1)(a), the **WITS manager** must give the notice to any person that has requested it.

Compare: Electricity Governance Rules 2003 rule 3.17 section V part G

Clause 13.155 Heading: amended, on 5 October 2017, by clause 405(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 13.155: amended, on 15 May 2014, by clause 54 of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

Clause 13.155(1)(a): replaced, on 5 October 2017, by clause 405(2)(a) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 13.155(2): inserted, on 5 October 2017, by clause 405(2)(b) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### **13.156 Pricing manager to make interim prices available after provisional prices and provisional reserve prices are made available unless further provisional price situation arises**

- (1) Subject to subclause (2), if the **pricing manager**—
- (a) does not receive revised data in accordance with clause 13.154 and notice in accordance with clause 13.155 in relation to a **provisional price situation** (other than a **high spring washer price situation**), the **pricing manager** must make **interim prices** and **interim reserve prices** available on **WITS** for all **trading periods** of the relevant **trading day** in accordance with clauses 13.163 and 13.164; or
  - (b) does not receive revised data in accordance with clause 13.154 and notice in accordance with clause 13.155 in relation to a **high spring washer price situation**, the **pricing manager** must, by 1400 hours on the 2<sup>nd</sup> **business day** after the **provisional prices** and **provisional reserve prices** were made available on **WITS**, make **interim prices** and **interim reserve prices** available on **WITS** for all **trading periods** of the relevant **trading day** as if the **high spring washer price situation** did not exist; or
  - (c) receives revised data in accordance with clause 13.154 (that does not itself give rise to a **provisional price situation**) and notice in accordance with clause 13.155, the **pricing manager** must, by 1400 hours on the 2<sup>nd</sup> **business day** after the **provisional prices** and **provisional reserve prices** were made available on **WITS**, make **interim prices** and **interim reserve prices** available on **WITS** for all **trading periods** of the relevant **trading day**; or

- (d) receives revised data in accordance with clause 13.154 and notice in accordance with clause 13.155 and an **infeasibility situation** arises from that data, the **pricing manager** must, by 1400 hours on the 2<sup>nd</sup> **business day** after the **provisional prices** and **provisional reserve prices** were made available on **WITS**, give to the **system operator**, relevant **grid owner**, and any person that has requested notice, written notice that an **infeasibility situation** exists, specifying in the notice each **trading period** affected by the **infeasibility situation**; or
- (e) receives revised data in accordance with clause 13.154 and notice in accordance with clause 13.155 and a **high spring washer price situation** arises from that data, the **pricing manager** must, by 1400 hours on the 2<sup>nd</sup> **business day** after the **provisional prices** and **provisional reserve prices** were made available on **WITS**, give to the **system operator**, relevant **grid owner**, and any person that has requested notice, written notice that a **high spring washer price situation** exists, specifying in the notice—
  - (i) each **trading period** affected by the **high spring washer price situation**; and
  - (ii) each **transmission security constraint** that has **bound** in the relevant **trading period** or **trading periods**.
- (2) The **pricing manager** must not give written notice of a **high spring washer price situation** in accordance with subclause (1)(e) in relation to a **trading period** if—
  - (a) an **infeasibility situation** exists in that **trading period** and it has not been resolved; or
  - (b) the **pricing manager** has previously given written notice that a **high spring washer price situation** exists in that **trading period**.

Compare: Electricity Governance Rules 2003 rules 3.18 and 3.18A section V part G

Clause 13.156 Heading: replaced, on 5 October 2017, by clause 406(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 13.156(1): amended, on 5 October 2017, by clause 406(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 13.156(2): amended, on 5 October 2017, by clause 406(3) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### **13.157 Requirements if infeasibility situation or high spring washer price situation exists**

- (1) If the **pricing manager** gives notice of an **infeasibility situation** in accordance with clause 13.156(1)(d), the relevant **grid owner** and the **system operator** must, by 1600 hours on the 2<sup>nd</sup> **business day** after the **provisional prices** and **provisional reserve prices** were made available on **WITS**, exercise reasonable endeavours to resolve the **provisional price situation** and provide revised data to the **pricing manager** using an **approved system**.
- (2) If the **pricing manager** gives notice of a **high spring washer price situation** in accordance with clause 13.156(1)(e), the **system operator** must, by 1600 hours on the 2<sup>nd</sup> **business day** after the **provisional prices** and **provisional reserve prices** were made available on **WITS**, apply the **high spring washer price relaxation factor** in accordance with the **high spring washer price situation methodology** and provide revised data to the **pricing manager** using an **approved system**.

Compare: Electricity Governance Rules 2003 rule 3.19 section V part G

Clause 13.157(1) and (2): amended, on 5 October 2017, by clause 407 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### **13.158 Revised data to be accompanied by written notice**

- (1) If a **grid owner** or the **system operator** gives revised data to the **pricing manager** in accordance with clause 13.157, the **grid owner** or **system operator** (as the case may be) must, by the time prescribed by that clause for giving revised data,—
  - (a) give written notice to the following **participants** that it has given revised data:
    - (i) if a **grid owner** gave the revised data, the **pricing manager**, **system operator**, and any other **grid owners**; or
    - (ii) if the **system operator** gave the revised data, the **pricing manager**, and **grid owners**; and
  - (b) specify in the notice the revisions that have been made; and
  - (c) in the case of revised data given in relation to an **infeasibility situation**, state in the notice whether the **infeasibility situation** has been resolved; and
  - (d) in the case of revised data given in relation to a **high spring washer price situation**, if the **high spring washer price situation relaxation factor** has been applied, state in the notice that the factor has been applied.
- (2) As soon as practicable after receiving a written notice under subclause (1)(a), the **WITS manager** must give the notice to any person that has requested it.

Compare: Electricity Governance Rules 2003 rule 3.20 section V part G

Clause 13.158 Heading: amended, on 5 October 2017, by clause 408(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 13.158(1)(a): replaced, on 5 October 2017, by clause 408(2)(a) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 13.158(2): inserted, on 5 October 2017, by clause 408(2)(b) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### **13.159 Pricing manager to make interim prices available or give written notice that high spring washer price situation exists**

Subject to clause 13.160, if the **pricing manager**—

- (a) receives revised data in accordance with clause 13.157 and written notice in accordance with clause 13.158, the **pricing manager** must,—
  - (i) if the revised data does not itself give rise to a **provisional price situation**, by 1800 hours on the 2<sup>nd</sup> **business day** after the **provisional prices** and **provisional reserve prices** were published, make **interim prices** and **interim reserve prices** available on **WITS** for all **trading periods** of the relevant **trading day**; or
  - (ii) if an **infeasibility situation** arises from that data, make **interim prices** and **interim reserve prices** available on **WITS** in accordance with clauses 13.163 and 13.164; or
  - (iii) if a **high spring washer price situation** arises from that data, by 1800 hours on the 2<sup>nd</sup> **business day** after the **provisional prices** and **provisional reserve prices** were made available on **WITS**, give to the **system operator** and any person that has requested notice, written notice that a **high spring washer price situation** exists, specifying in the notice—

- (A) each **trading period** affected by the **high spring washer price situation**; and
  - (B) each **transmission security constraint** that has **bound** in the relevant **trading period** or **trading periods**; and
- (b) does not receive revised data in accordance with clause 13.157 and does not receive a written notice in accordance with clause 13.158,—
  - (i) in relation to an **infeasibility situation**, the **pricing manager** must make **interim prices** and **interim reserve prices** available on **WITS** in accordance with clauses 13.163 and 13.164; or
  - (ii) in relation to a **high spring washer price situation**, the **pricing manager** must make **interim prices** and **interim reserve prices** available on **WITS** by 1800 hours on the 2<sup>nd</sup> **business day** after the **provisional prices** and **provisional reserve prices** were made available on **WITS**, as if the **high spring washer price situation** did not exist.

Compare: Electricity Governance Rules 2003 rule 3.21 section V part G

Clause 13.159 Heading: replaced, on 5 October 2017, by clause 409(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 13.159(a) and (b): amended, on 5 October 2017, by clause 409(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### **13.160 Prohibition on notice of high spring washer price situation**

The **pricing manager** must not give notice of a **high spring washer price situation** in accordance with clause 13.159(a)(iii) in relation to a **trading period** if—

- (a) an **infeasibility situation** exists in that **trading period** and has not been resolved; or
- (b) the **pricing manager** has previously given notice that a **high spring washer price situation** exists in that **trading period**.

Compare: Electricity Governance Rules 2003 rule 3.21A section V part G

### **13.161 System operator to apply high spring washer price relaxation factor and give notice**

- (1) If the **pricing manager** gives written notice of a **high spring washer price situation** in accordance with clause 13.159(a)(iii), the **system operator** must, by 1000 hours on the 3<sup>rd</sup> **business day** after the **provisional prices** and **provisional reserve prices** were made available on **WITS**,—
  - (a) apply the **high spring washer price relaxation factor** in accordance with the **high spring washer price situation methodology**; and
  - (b) exercise reasonable endeavours to provide revised data to the **pricing manager** using an **approved system**.
- (2) If the **system operator** gives revised data to the **pricing manager** in accordance with subclause (1), the **system operator** must, by the time prescribed by that subclause for giving revised data,—
  - (a) give written notice to the **pricing manager** and the **WITS manager** that the **system operator** has given revised data; and
  - (b) specify in the notice the revisions that have been made; and

- (c) if the **high spring washer price relaxation factor** has been applied, state in the notice that the factor has been applied.
- (3) As soon as practicable after receiving a written notice under subclause (2)(a), the **WITS manager** must give the notice to any person that has requested it.
- Compare: Electricity Governance Rules 2003 rule 3.21B section V part G  
Clause 13.161(1): amended, on 5 October 2017, by clause 410(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.  
Clause 13.161(2)(a): replaced, on 5 October 2017, by clause 410(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.  
Clause 13.161(3): inserted, on 5 October 2017, by clause 410(3) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### 13.162 Pricing manager to make interim prices available

If the **pricing manager**—

- (a) receives revised data in accordance with clause 13.161(1) and notice in accordance with clause 13.161(2), the **pricing manager** must, by 1200 hours on the 3<sup>rd</sup> **business day** after the **provisional prices** and **provisional reserve prices** were made available on **WITS**, make **interim prices** and **interim reserve prices** available on **WITS** for all **trading periods** of the relevant **trading day**; or
- (b) does not receive revised data in accordance with clause 13.161(1) and does not receive a notice in accordance with clause 13.161(2), the **pricing manager** must, by 1200 hours on the 3<sup>rd</sup> **business day** after the **provisional** or **provisional reserve price** was made available on **WITS**, make **interim prices** and **interim reserve prices** available on **WITS** for all **trading periods** of the relevant **trading day** as if the **high spring washer price situation** did not exist.

Compare: Electricity Governance Rules 2003 rule 3.21C section V part G  
Clause 13.162 Heading: amended, on 5 October 2017, by clause 411(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.  
Clause 13.162(a) and (b): amended, on 5 October 2017, by clause 411(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### 13.163 Revised data cannot be given or revised data gives rise to provisional price situation (other than high spring washer price situation)

If clause 13.156(1)(a) applies, or the revised data received in accordance with clause 13.157(1) does not resolve an **infeasibility situation** or gives rise to a **provisional price situation** (other than a **high spring washer price situation**), the **pricing manager** must make **interim prices** and **interim reserve prices** available on **WITS** and must give written notice to **generators** and **purchasers**—

- (a) for each **trading period** not affected by a **provisional price situation**; and
- (b) on the basis of the information given to it under clause 13.154; and
- (c) by 1800 hours of the 2<sup>nd</sup> **business day** after it makes **provisional prices** and **provisional reserve prices** available on **WITS**.

Compare: Electricity Governance Rules 2003 rule 3.22 section V part G  
Clause 13.163: amended, on 5 October 2017, by clause 412 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

**13.164 If provisional price situation (other than high spring washer price situation) continues**

If clause 13.156(1)(a) applies, or the revised data received in accordance with clause 13.157(1) does not resolve an **infeasibility situation** or gives rise to a **provisional price situation** (other than a **high spring washer price situation**), the **pricing manager** must, for each affected **trading period**,—

- (a) no later than the time at which the **pricing manager** would be required to make **interim prices** available under clause 13.163, give to the **system operator**, relevant **grid owner**, and any person that has requested notice, written notice that the **pricing manager** cannot calculate **interim prices** and **interim reserve prices**, specifying the **trading periods** affected; and
- (b) on the basis of the information given to the **pricing manager** under clause 13.154, calculate and make **interim prices** available on **WITS** for all **grid injection points** and all **net grid exit points** for each affected **trading period** by—
  - (i) assigning a price to all **net grid injection points** for each affected **trading period** equal to the highest price at the point that the **loss adjusted demand** intersects with the **offer stack**; and
  - (ii) assigning a price to all **net grid exit points** equal to 1.05 times the price calculated for all **grid injection points** under subparagraph (i)—
- (c) calculate and **publish interim reserve prices** by taking the mean of the relevant **final reserve prices** of the corresponding day in each of the 4 previous weeks, by 1800 hours on the 2<sup>nd</sup> **business day** after the **pricing manager** makes **provisional prices** and **provisional reserve prices** available on **WITS**; and
- (d) give to any person that has requested notice, written notice of all **interim prices** and **interim reserve prices** by 1800 hours on the 2<sup>nd</sup> **business day** after the **pricing manager** makes **provisional prices** and **provisional reserve prices** available on **WITS**.

Compare: Electricity Governance Rules 2003 rule 3.23 section V part G

Clause 13.164(a) to (d): amended, on 5 October 2017, by clause 413(a) to (d) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

**13.165 System operator or grid owner to give written notice to Authority if provisional price situation not resolved**

- (1) If a **grid owner** or the **system operator** receives notice of an unresolved **provisional price situation** in accordance with clause 13.164, the **grid owner** or **system operator** (as the case may be) must immediately give written notice to the **Authority** of—
  - (a) how the unresolved **provisional price situation** arose; and
  - (b) the steps taken in attempting to resolve the **provisional price situation**; and
  - (c) the reasons for the inability of the **grid owner** or **system operator** (as the case may be) to resolve the **provisional price situation**.



- (2) As soon as it receives a notice given under subclause (1), the **Authority** must consider the unresolved **provisional price situation** and urgently address the matters raised in the notice.

Compare: Electricity Governance Rules 2003 rules 3.24 and 3.25 section V part G

Clause 13.165 Heading: replaced, on 5 October 2017, by clause 414(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 13.165(1): amended, on 5 October 2017, by clause 414(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### **13.166 Generator, grid owner, or dispatchable load purchaser to give revised metering information following initial estimate**

- (1) If clause 13.154(1A)(b) applies, the **generator, grid owner, or dispatchable load purchaser** who gave the **initial estimate** to the **pricing manager** in accordance with clause 13.141(1)(b)(ii) must give to the **pricing manager**—
- (a) actual **half-hour metering information**; or
  - (b) if actual **half-hour metering information** is not reasonably available, **back-up metering information**; or
  - (c) if **back-up metering information** is not reasonably available, **check metering information** (adjusted by the **relevant registration factor** to achieve accuracy equivalent to actual **half-hour metering information**); or
  - (d) if **check metering information** is not reasonably available, a **final estimate**.
- (2) If a **metering situation** arose, either in whole or in part, from the failure of a **generator** or a **dispatchable load purchaser** to provide **half-hour metering information**, the **generator** or the **dispatchable load purchaser** must use reasonable endeavours to assist the relevant **grid owner** to provide the information required by this clause by the time prescribed in clause 13.154(2).

Compare: Electricity Governance Rules 2003 rule 3.26 section V part G

Clause 13.166 Heading: amended, on 15 May 2014, by clause 55 of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

Clause 13.166 (1) and (2): amended, on 15 May 2014, by clause 55 of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

### **13.166A Pricing manager to recalculate and make interim prices available if infeasibility situation caused by shortage of instantaneous reserve**

- (1) If an **infeasibility situation** that has been resolved under this subpart was caused by a shortage of **instantaneous reserve**, the **pricing manager** must recalculate and make **interim prices** available on **WITS** for the relevant **trading period** by adding a virtual provider of **fast instantaneous reserve** and **sustained instantaneous reserve**, at the price as specified in subclause (2), that provides sufficient **fast instantaneous reserve** and **sustained instantaneous reserve** so that prices for **fast instantaneous reserve** and **sustained instantaneous reserve** do not exceed that price.
- (2) The price referred to in subclause (1) for a **trading period** is the greater of—
- (a) 3 times the highest **offer** scheduled in the relevant **island** during the **trading period** according to the revised data provided to the **pricing manager** under this subpart; and

- (b) the highest **reserve offer** scheduled in the relevant **island** during the **trading period** according to the revised data provided to the **pricing manager** under this subpart as follows:
  - (i) in the case of an **infeasibility situation** caused by a shortage of **fast instantaneous reserve**, the highest **reserve offer** for **fast instantaneous reserve**;
  - (ii) in the case of an **infeasibility situation** caused by a shortage of **sustained instantaneous reserve**, the highest **reserve offer** for **sustained instantaneous reserve**.

Clause 13.166A Heading: amended, on 5 October 2017, by clause 415(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 13.166A: inserted, on 1 June 2013, by clause 14 of the Electricity Industry Participation (Scarcity Pricing) Code Amendment 2011.

Clause 13.166A(1): amended, on 5 October 2017, by clause 415(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

#### *Interim pricing period*

### **13.167 Pricing manager to make interim prices available**

The **pricing manager** must make **interim prices** and **interim reserve prices** available on **WITS**—

- (a) when required to do so by clauses 13.142, 13.152, 13.156(1), 13.159, 13.162, 13.163 or 13.164, by 1200 on each **trading day** for the previous **trading day**; and
- (aa) when required to do so by clause 13.135B; and
- (b) when required to do so by the **Authority** under clause 13.177(1)(c); and
- (c) before making **final prices** or **final reserve prices** available on **WITS**.

Compare: Electricity Governance Rules 2003 rule 3.26A section V part G

Clause 13.167 Heading: amended, on 5 October 2017, by clause 416(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 13.167: amended, on 5 October 2017, by clause 416(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 13.167(aa): inserted, on 1 June 2013, by clause 15 of the Electricity Industry Participation (Scarcity Pricing) Code Amendment 2011.

Clause 13.167(c): amended, on 21 September 2012, by clause 23 of the Electricity Industry Participation (Minor Amendments) Code Amendment 2012.

Clause 13.167(c): amended, on 5 October 2017, by clause 416(3) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### **13.168 When pricing error may be claimed**

Once the **pricing manager** has made **interim prices** and **interim reserve prices** available on **WITS**, an **error claimant** may claim that the prices contain a **pricing error**.

Compare: Electricity Governance Rules 2003 rule 3.26B section V part G

Clause 13.168: amended, on 5 October 2017, by clause 417 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### **13.169 Error claimant materially affected by pricing error**

- (1) Subject to subclause (2), an **error claimant** may only claim that a **pricing error** has occurred if it considers it has been materially affected by the **pricing error**.
- (2) Subclause (1) does not apply to—
  - (a) the **Authority**; or

- (b) any person who is not a **participant**.

Compare: Electricity Governance Rules 2003 rule 3.26C section V part G

### 13.170 Method and timing for claiming pricing error has occurred

To claim that a **pricing error** has occurred, an **error claimant** must—

- (a) complete the form set out in Form 9 of Schedule 13.1; and
- (b) include sufficient information in the form to demonstrate that the **error claimant** (other than an **error claimant** described in clause 13.169(2)) has been materially affected by the **pricing error**; and
- (c) give the completed form to the **pricing manager**; and
- (d) comply with paragraphs (a) to (c) no later than 1200 on the 1st **business day** following the **trading day** on which the **pricing manager** made the **interim price** or **interim reserve price** that contains the **pricing error** available on WITS.

Compare: Electricity Governance Rules 2003 rule 3.26D section V part G

Clause 13.170(b): amended, on 21 September 2012, by clause 24 of the Electricity Industry Participation (Minor Amendments) Code Amendment 2012.

Clause 13.170(c): replaced, on 5 October 2017, by clause 418(a) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 13.170(d): amended, on 5 October 2017, by clause 418(b) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### 13.171 Pricing manager must make final prices available if no pricing error claimed

- (1) Subclause (2) applies if, by 1200 on the 1st **business day** following the **trading day** on which the **pricing manager** made the **interim price** or **interim reserve price** available on WITS, no **pricing error** is claimed in respect of the **interim prices** or **interim reserve prices**.
- (2) The **pricing manager** must make available on WITS the **interim prices** as **final prices**, and **interim reserve prices** as **final reserve prices**, by 1400 hours on the 1st **business day** following the **trading day** on which the **pricing manager** made the **interim prices** or **interim reserve prices** available on WITS.

Compare: Electricity Governance Rules 2003 rule 3.26E section V part G

Clause 13.171: replaced, on 5 October 2017, by clause 419 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### 13.172 Effect of pricing error being claimed

If an **error claimant** claims that a **pricing error** is contained in either **interim prices** or **interim reserve prices**, the **pricing manager** must not make **final prices** or **final reserve prices** available on WITS until the **pricing manager** has implemented the **Authority's** decision in accordance with clause 13.177.

Compare: Electricity Governance Rules 2003 rule 3.26F section V part G

Clause 13.172: amended, on 5 October 2017, by clause 420 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### 13.173 Process when pricing error claimed

If the **pricing manager** receives a claim that an **error claimant** considers that a **pricing error** has occurred, the **pricing manager** must—

- (a) check that sufficient information is included in the form as required under clause 13.170; and
- (b) confirm to the **error claimant** that it has received the **pricing error** claim; and

- (c) by 1400 hours on the 1st **business day** following the **trading day** on which the **pricing manager** made available on **WITS** the **interim prices** or **interim reserve prices** in respect of which the **pricing error** is claimed, give a written notice on **WITS** and to the **error claimant**, the **Authority**, any **participant** to which clause 13.173(d) applies, and any person that has requested notice, advising—
  - (i) that a **pricing error** has been claimed; and
  - (ii) the name of the **error claimant**; and
  - (iii) the reason for the **error claimant** believing that a **pricing error** has occurred; and
  - (iv) the **trading periods** that are claimed to have been affected by the **pricing error**; and
- (d) request that the **error claimant**, a **participant**, or the **Authority**, provide the **pricing manager** with any additional information that the **pricing manager** reasonably requires to determine whether a **pricing error** has occurred; and
- (e) provide the **Authority** with a copy of all information it has received in relation to the **pricing error** that has been claimed; and
- (f) determine whether it agrees that a **pricing error** has occurred.

Compare: Electricity Governance Rules 2003 rule 3.26G section V part G  
Clause 13.173(c): amended, on 5 October 2017, by clause 421 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

#### 13.174 Recommendation to Authority

When the **pricing manager** has determined whether it agrees that a **pricing error** has occurred—

- (a) if it agrees that a **pricing error** has occurred, it must—
  - (i) recommend that the **Authority** uphold the claim; and
  - (ii) set out its reasons for agreeing that a **pricing error** has occurred; and
  - (iii) recommend the actions that the **pricing manager** considers are required to correct the **pricing error**; or
- (b) if it does not agree that a **pricing error** has occurred, it must—
  - (i) recommend that the **Authority** not uphold the claim; and
  - (ii) set out its reasons for not agreeing that a **pricing error** has occurred.

Compare: Electricity Governance Rules 2003 rule 3.26H section V part G

#### 13.175 Authority to accept or reject recommendations

If the **Authority** receives a recommendation and reasons from the **pricing manager** under clause 13.174, it—

- (a) must decide whether to accept the **pricing manager's** recommendations; and
- (b) must immediately give written notice to the **pricing manager** of the **Authority's** decision; and
- (c) may direct the **pricing manager**—
  - (i) to take any specified action to resolve the **pricing error**; or
  - (ii) to direct, on behalf of the **Authority**, another **participant** to take any specified action to resolve the **pricing error**.

Compare: Electricity Governance Rules 2003 rule 3.26I section V part G

Clause 13.175(b): amended, on 5 October 2017, by clause 422 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### 13.176 Pricing manager to give written notice

As soon as practicable after the **Authority** has given written notice to the **pricing manager** of its decision under clause 13.175, the **pricing manager** must give to any person that has requested notice, a written report specifying—

- (a) the name of the **error claimant**; and
- (b) the reason for the **error claimant** claiming that a **pricing error** has occurred; and
- (c) the trading **periods** that are claimed to have been affected by the **pricing error**; and
- (d) the **Authority's** decision made under clause 13.175; and
- (e) the **Authority's** reasons for its decision under clause 13.175; and
- (f) if the **Authority** decided that a **pricing error** had occurred, any actions it has directed be taken to correct the **pricing error**.

Compare: Electricity Governance Rules 2003 rule 3.26J section V part G

Clause 13.176 Heading: amended, on 5 October 2017, by clause 423(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 13.176: amended, on 5 October 2017, by clause 423(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### 13.177 Pricing manager to implement Authority's decision

- (1) If the **Authority** decides that a **pricing error** has occurred, the **pricing manager** must—
  - (a) take any action directed by the **Authority** under clause 13.175(c)(i) to resolve the **pricing error**; and
  - (b) give a written direction to a **participant** to take any action required by the **Authority** under clause 13.175(c)(ii) to resolve the **pricing error**; and
  - (c) once those actions have been completed, make recalculated **interim prices** and **interim reserve prices** available on **WITS**, using any updated **metering information**.
- (2) If the **Authority** decides that a **pricing error** has not occurred, the **pricing manager** must make the **interim prices** and **interim reserve prices** available on **WITS** as **final prices** and **final reserve prices**.

Compare: Electricity Governance Rules 2003 rule 3.26K section V part G

Clause 13.177(1)(a), (c) and (2): amended, on 5 October 2017, by clause 424(a), (c) and (d) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 13.177(1)(b): replaced, on 5 October 2017, by clause 424(b) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### 13.178 Effect of making recalculated interim prices available

If the **pricing manager** is required to make recalculated **interim prices** and **interim reserve prices** available on **WITS** in accordance with clause 13.177(1)(c)—

- (a) the **pricing manager** must do so by following the methodology required under clauses 13.135 to 13.179; and
- (b) a further **pricing error** may be claimed in respect of the recalculated **interim prices** and **interim reserve prices** made available on **WITS**.

Compare: Electricity Governance Rules 2003 rule 3.26L section V part G

Clause 13.178 Heading: replaced, on 5 October 2017, by clause 425(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 13.178: amended, on 5 October 2017, by clause 425(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### 13.179 Timing for resolution of pricing error claim process

The **pricing manager** and the **Authority** must make reasonable endeavours to ensure that, by 1400 hours on the 2<sup>nd</sup> **business day** after the relevant **pricing error** was claimed, but at least 2 hours after the **pricing manager** gives the notice under clause 13.176, the **pricing manager**—

- (a) makes recalculated **interim prices** and **interim reserve prices** available in accordance with clause 13.177(1)(c); or
- (b) makes **final prices** and **final reserve prices** available in accordance with clause 13.177(2).

Compare: Electricity Governance Rules 2003 rule 3.26M section V part G

Clause 13.179: amended, on 21 September 2012, by clause 25 of the Electricity Industry Participation (Minor Amendments) Code Amendment 2012.

Clause 13.179: amended, on 5 October 2017, by clause 426 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### 13.180 Actions Authority may take to resolve pricing error

- (1) To correct a **pricing error**, the actions that the **Authority** may take, or that the **Authority** may direct the **pricing manager** to take, include—
  - (a) delaying when **interim prices**, **interim reserve prices**, **final prices**, and **final reserve prices** are made available under clause 13.184, if the **Authority** considers that is necessary to allow time for the **pricing error** to be investigated or corrected; or
  - (b) giving written directions to any **participant** to act in a manner that will, in the **Authority's** opinion, correct or assist in correcting the **pricing error**.
- (2) However, to avoid any doubt, in resolving a **pricing error**, the **Authority** must not—
  - (a) act inconsistently with this Code, the **Act**, or any other law; or
  - (b) require any other **participant** to act inconsistently with this Code, the **Act**, or any other law.

Compare: Electricity Governance Rules 2003 rule 3.26N section V part G

Clause 13.180(1): amended, on 5 October 2017, by clause 427 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### 13.181 Obligation to comply with pricing manager

- (1) If the **pricing manager** asks a **participant** or the **Authority** to provide information in accordance with clause 13.173(d), the **participant** or the **Authority** must provide the **pricing manager** with the requested information in writing, within the reasonable timeframe advised by the **pricing manager**.
- (2) Each **participant** must comply promptly with any direction given by the **pricing manager** in accordance with clause 13.175(c)(ii).
- (3) To avoid doubt, if an **error claimant** does not provide the **pricing manager** with sufficient information to support its claim that a **pricing error** has occurred, and fails to provide additional information when requested under clause 13.173(d) the **pricing**

**manager** may recommend under clause 13.174(b) that the **Authority** not uphold the claim.

Compare: Electricity Governance Rules 2003 rule 3.26O section V part G

Clause 13.181(1): amended, on 5 October 2017, by clause 428 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### **13.182 No pricing errors may be claimed after final prices calculated**

- (1) An **error claimant** may only claim that a **pricing error** has occurred in respect of **interim prices** or **interim reserve prices**.
- (2) Once the **pricing manager** has made **final prices** or **final reserve prices** available on **WITS**, no further **pricing errors** can be claimed in respect of those prices.

Compare: Electricity Governance Rules 2003 rule 3.26P section V part G

Clause 13.182 Heading: amended, on 5 October 2017, by clause 429(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 13.182(2): amended, on 5 October 2017, by clause 429(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

#### *Making final prices available*

Cross heading: replaced, on 5 October 2017, by clause 430 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### **13.183 Pricing manager must not make recalculated final prices available**

Unless directed to do so by the **Authority** under clause 5.2, the **pricing manager** must not make a recalculated **final price** or **final reserve price** available on **WITS** for any **trading period** despite the fact that the **final price** or **final reserve price** may contain an error.

Compare: Electricity Governance Rules 2003 rule 3.27 section V part G

Clause 13.183 Heading: replaced, on 5 October 2017, by clause 431(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 13.183: amended, on 5 October 2017, by clause 431(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### **13.184 Authority may order delay in making final prices available**

Despite clauses 13.135 to 13.191, the **Authority** may give a written direction to the **pricing manager** to delay making **interim prices**, **interim reserve prices**, **final prices**, or **final reserve prices** available on **WITS**.

Compare: Electricity Governance Rules 2003 rule 3.28 section V part G

Clause 13.184: replaced, on 5 October 2017, by clause 432 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### **13.185 Final prices for more than 1 trading day**

If the **pricing manager** is required to make 1 or more of the following prices available on **WITS** for more than 1 **trading day** at a time, the **pricing manager's** deadline for making the price or prices available on **WITS** is extended by 2 hours for each **trading day**:

- (a) **interim prices**:
- (b) **interim reserve prices**:
- (c) **final prices**:
- (d) **final reserve prices**.

Compare: Electricity Governance Rules 2003 rule 3.29 section V part G

Clause 13.185: substituted, on 21 September 2012, by clause 26 of the Electricity Industry Participation (Minor Amendments) Code Amendment 2012.

Clause 13.185: amended, on 5 October 2017, by clause 433 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

*Miscellaneous requirements relating to calculation of prices*

**13.186 Revised data for more than 1 trading day**

If the **system operator** or a **grid owner** is required to give revised data for more than 1 **trading day** at a time, that **system operator's** or **grid owner's** deadline is extended by 2 hours for each **trading day**.

Compare: Electricity Governance Rules 2003 rule 3.30 section V part G

**13.187 Daylight saving to be observed**

Despite anything in this subpart, if the **grid owner** gives the **pricing manager** data for an **initial estimate** under clause 13.141(1)(b)(ii) or a **final estimate** under clause 13.166(1)(d), the following provisions apply:

- (a) if a **grid owner** gives data for an **initial estimate** or a **final estimate** using an **equivalent day** and the **equivalent day** is the day on which daylight saving begins, the **grid owner** must replicate the actual data from **trading periods 5** and **6** of the **equivalent day** into **trading periods 7** and **8** to produce synthetic data for **48 trading periods**. This is shown below:

Used	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24
Recorded	1	2	3	4	5	6	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22
Used	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48
Recorded	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46

- (b) if a **grid owner** gives data for an **initial estimate** or a **final estimate** for the day on which daylight saving begins, the **grid owner** must discard the actual data for **trading periods 5** and **6** to produce synthetic data for **46 trading periods**. This is shown below:

Used	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24
Recorded	1	2	3	4	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26
Used	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46		
Recorded	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48		

- (c) if a **grid owner** gives data for an **initial estimate** or a **final estimate** for the day on which daylight saving ends, the **grid owner** must replicate the actual data from **trading periods 5** and **6** into **trading periods 7** and **8** to produce synthetic data for **50 trading periods**. This is shown below:



**Electricity Industry Participation Code 2010**  
**Part 13**

Used	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25
Recorded	1	2	3	4	5	6	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23
Used	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50
Recorded	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48

- (d) if a **grid owner** gives data for an **initial estimate** or a **final estimate** using an **equivalent day** and the **equivalent day** is the day on which daylight saving ends, the **grid owner** must discard the actual data from **trading periods 5 and 6** of the **equivalent day** to produce synthetic data for 48 **trading periods**. This is shown below:

Used	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24
Record	1	2	3	4	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26
Used	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48
Record	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50

Compare: Electricity Governance Rules 2003 rule 3.31 section V part G

### **13.188 Reconciliation manager to publish annual consumption list**

- (1) At least once every 6 months, the **reconciliation manager** must give the **Authority** an **annual consumption list**.
- (2) The list must rank in descending order the annual consumption of all **grid exit points** and **grid injection points** with annual consumption greater than 300 GWh for the 12-month period ended 3 months prior to the date on which the list is due.
- (3) The **reconciliation manager** must **publish** the list within 1 **business day** of providing it to the **Authority**.

Compare: Electricity Governance Rules 2003 rule 3.32 section V part G

Clause 13.188 Heading: amended, on 5 October 2017, by clause 434(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 13.188(1) and (3): amended, on 5 October 2017, by clause 434(2) and (3) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### **13.189 System operator to give pricing manager and Authority list of model variable values**

- (1) *[Revoked]*
- (2) If the value of the model parameters listed in Schedule 13.2 are to be changed, the **system operator** must immediately—
  - (a) give the **pricing manager** and the **Authority** an updated list of values in writing; and
  - (b) advise the **Authority**, in relation to the price under clause 13.13(1)(c)(ii), or clause 13.13(c)(iii) if there is no price **published** under clause 13.13(1A), if—
    - (i) the price remains appropriate; or
    - (ii) a new price is appropriate.

- (2A) If the **system operator** advises the **Authority** that a new price is appropriate under subclause (2)(b)(ii), the **system operator** must give to the **Authority** in writing the proposed new price, and an explanation for the proposed new price.
- (3) The **pricing manager** and the **Authority** must acknowledge receipt of the updated list in writing.
- (4) Changes specified in any updated list must become effective from a date specified by the **system operator**, subject to agreement in writing from both the **pricing manager** and the **Authority**.

Compare: Electricity Governance Rules 2003 rule 3.33 section V part G

Clause 13.189 Heading: amended, on 3 November 2016, by clause 5(1) of the Electricity Industry Participation Code Amendment (Dispatchable Demand During Tight Market Conditions) 2016.

Clause 13.189(1): revoked, on 3 November 2016, by clause 5(2) of the Electricity Industry Participation Code Amendment (Dispatchable Demand During Tight Market Conditions) 2016.

Clause 13.189(2): amended, on 3 November 2016, by clauses 5(3) and 5(4) of the Electricity Industry Participation Code Amendment (Dispatchable Demand During Tight Market Conditions) 2016.

Clause 13.189(2A): inserted, on 3 November 2016, by clause 5(5) of the Electricity Industry Participation Code Amendment (Dispatchable Demand During Tight Market Conditions) 2016.

Clause 13.189(3): amended, on 3 November 2016, by clause 5(6) of the Electricity Industry Participation Code Amendment (Dispatchable Demand During Tight Market Conditions) 2016.

Clause 13.189(4): amended, on 3 November 2016, by clause 5(7)(a) and (b) of the Electricity Industry Participation Code Amendment (Dispatchable Demand During Tight Market Conditions) 2016.

#### **13.189A Pricing manager to give clearing manager information about dispatch-capable load station from schedule of final prices**

- (1) The **pricing manager** must give the **clearing manager** information about the quantity of **electricity** scheduled in the schedule of **final prices** for each **dispatch-capable load station** for each **trading period** that is both—
  - (a) a **trading period** for which a **nominated dispatch bid** was submitted for the **dispatch-capable load station**; and
  - (b) a **trading period** in the **billing period** that is immediately before the **billing period** in which the information must be provided under subclause (2).
- (2) The **pricing manager** must provide the information by 1600 hours on the 7<sup>th</sup> **business day** of each **billing period**.

Clause 13.189A: inserted, on 15 May 2014, by clause 56 of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

#### **13.190 All information and notices to be unconditional and final**

- (1) *[Revoked]*
- (2) Except as provided for in this Code, **participants** may treat all information and notices given under clauses 13.135 to 13.191 as final.

Compare: Electricity Governance Rules 2003 rule 3.34 section V part G

Clause 13.190 Heading: replaced, on 5 October 2017, by clause 435(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 13.190(1): revoked, on 5 October 2017, by clause 435(2)(a) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 13.190(2): amended, on 5 October 2017, by clause 435(2)(b) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### 13.191 Backup procedures if WITS or approved system is unavailable

- (1) If **WITS** or the **approved system** is unavailable for the purposes of giving information or making information available under clauses 13.135 to 13.191, each **grid owner** and the **pricing manager** must follow the backup procedures specified by the **WITS manager**.
- (2) The backup procedures referred to in subclause (1) must be specified by the **WITS manager** following consultation with the **Authority, generators, purchasers, ancillary service agents, the grid owners and the pricing manager**.
- (3) *[Revoked]*

Compare: Electricity Governance Rules 2003 rules 3.35 and 3.36 section V part G

Clause 13.191 Heading: amended, on 5 October 2017, by clause 436(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 13.191(1): replaced, on 5 October 2017, by clause 436(2)(a) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 13.191(2): amended, on 5 October 2017, by clause 436(2)(b) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 13.191(3): revoked, on 5 October 2017, by clause 436(2)(c) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### *Calculation of constrained off amounts*

### 13.192 Constrained off situations may occur

A **constrained off situation** occurs when—

- (a) a **generator** is not given a **dispatch instruction**, or is not dispatched by the **system operator** to the level expected based on the **generator's offer** compared to the relevant **final price**, for a **trading period** despite the **generator** having offered **electricity** at a price below the **final price** for that **trading period** at the relevant **grid injection point**; or
- (b) in relation to a **block dispatch group** or **station dispatch group**, a **generator** is not given a **dispatch instruction**, or is not dispatched by the **system operator** to the level expected based on the **generator's offer** compared to the **final price**, for the **trading period**, despite the **generator** having offered **electricity** in the **trading period** at a **grid injection point** within the **block dispatch group** or **station dispatch group** below the **final price** at the relevant **grid injection point** in that **trading period**, and the aggregate quantity of those **offers** is greater than the dispatched quantity calculated in accordance with clause 13.194; or
- (c) in relation to a **dispatch-capable load station** (except when the final **nominated bid** for the **dispatch-capable load station** in a **trading period** is a **nominated non-dispatch bid**), the latest **dispatch instruction** issued by the **system operator** for the **dispatch-capable load station** for a **trading period** is for a **MW** amount that is less than the **MW** amount scheduled for the **dispatch-capable load station** in the schedule of **final prices** for the **trading period**.

Compare: Electricity Governance Rules 2003 rule 4.1 section V part G

Clause 13.192(c): inserted, on 15 May 2014, by clause 57 of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

Clause 13.192(c): amended, on 1 December 2015, by clause 7 of the Electricity Industry Participation Code Amendment (Dispatchable Demand: Late Bid Revisions) 2015.

### 13.193 Determining affected price bands for block dispatch groups and station dispatch groups

If a **constrained off situation** occurs for a **block dispatch group** or **station dispatch group** during any **trading period** during a **billing period**, the **clearing manager** must determine the affected price bands for that **block dispatch group** or **station dispatch group** by—

- (a) taking all the **offers** made by that **block dispatch group** or **station dispatch group** in relation to that **trading period**, calculating the differences between each **offer price** and **final price** for each **grid injection point**, and ranking the differences in ascending order; and
- (b) identifying each price band ranked under paragraph (a) in which the aggregate quantity in all previous price bands plus the quantity for that price band is greater than 0 or the dispatched quantity calculated in accordance with clause 13.194, but is less than the aggregate quantity for all the **generating plant** in that **block dispatch group** or **station dispatch group** calculated by the **clearing manager** using the methodology set out in Schedule 13.3. The **offer** prices corresponding to the ranked price bands identified under this paragraph are the affected price bands for the **block dispatch group** or **station dispatch group** for the purposes of clauses 13.194 to 13.196.

Compare: Electricity Governance Rules 2003 rule 4.2 section V part G

### 13.194 Clearing manager to calculate constrained off amounts

- (1) Despite clause 13.193, if a **constrained off situation** occurs, in relation to a **generator**, during a **trading period**, the **clearing manager** must calculate the **constrained off amounts** for each **generator**, for each affected price band, using the following formula:

$$COF_g = Q_{cof} * (P_f - P_o)$$

where

$COF_g$  is the **constrained off amount** for a **generator**

$Q_{cof}$  is the dispatched quantity in **MWh** (calculated as set out below) from that price band in the **offer** that was constrained off during a **trading period**, or the positive difference between the **reconciliation information** and the **scheduled quantity**, whichever is less

$P_o$  is the price **offered** for that price band by that **generator** for the quantity of **electricity** from the **generating plant** that was constrained off

$P_f$  is the **final price** for that **trading period** at the **grid injection point**.

- (1A) If a **constrained off situation** occurs in relation to a **dispatch-capable load station** during a **trading period**, the **clearing manager** must calculate the **constrained off amounts** for each **dispatch-capable load station**, for each affected **nominated dispatch bid** price band, using the following formula:

$$\text{ConOffAmt}_{\text{disp}} = \text{ConOffQ} * (P_b - P_f)$$

where

$\text{ConOffAmt}_{\text{disp}}$  is the **constrained off amount** for a **dispatch-capable load station** for the **nominated dispatch bid** price band

$\text{ConOffQ}$  is the amount in **MWh** by which  $Q_{\text{fp}}$  exceeds the highest of  $Q_{\text{disp}}$  and  $Q_{\text{rec}}$

where

$Q_{\text{fp}}$  is the quantity, in **MWh**, scheduled for the **nominated dispatch bid** price band in the schedule of **final prices**

$Q_{\text{disp}}$  is the latest quantity, in **MWh**, dispatched for the **nominated dispatch bid** price band in the **trading period**

$Q_{\text{rec}}$  is the **reconciled quantity** provided by the **reconciliation manager** under clause 15.20C allocated by the **clearing manager** to the **nominated dispatch bid** price band in the **trading period**

$P_b$  is the price bid for the **nominated dispatch bid** price band for the **dispatch-capable load station** that was constrained off

$P_f$  is the **final price** for the **trading period** at the **grid exit point**.

- (2) For the purposes of clauses 13.192 to 13.201, dispatched quantity must be calculated taking into account—
- (a) the quantity in **MW** recorded in the log kept by the **system operator** in accordance with clause 13.76 and, if required, the **clearing manager** must aggregate such quantities for—
    - (i) **generating stations** or **generating units** in the relevant **station dispatch group**; or
    - (ii) **generating units**, if the **clearing manager** requires the dispatched quantity to be determined on a **grid injection point** basis; and
  - (b) for an **offer**, the ramp rate applying to that **constrained off situation** that is specified in the **offer** submitted by that **generator**, or—
    - (i) for a **block dispatch group** or a **station dispatch group**; or
    - (ii) for **generating units**, if the **clearing manager** requires the dispatched quantity to be determined on a **grid injection point** basis—  
the fastest of the ramp rates applying to that **constrained off situation** that are specified in the **offers** submitted by the **generator** in that **block dispatch group**, that **station dispatch group** or those **generation units electrically connected** to the relevant **grid injection point** (as the case may be); and
  - (c) plus or minus the **MW bandwidth** applicable for each **generator** affected by a **frequency keeping** requirement as advised by the **system operator** to the **clearing manager**, and, if required, the **clearing manager** must aggregate the **MW bandwidth** applicable to determine the **MW bandwidth** on a **grid injection point** basis.

Compare: Electricity Governance Rules 2003 rule 4.3.1 section V part G  
Clause 13.194(1): amended, on 15 May 2014, by clause 58(1) of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

Clause 13.194(1A): inserted, on 15 May 2014, by clause 58(2) of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

Clause 13.194(2)(b): amended, on 5 October 2017, by clause 437 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 13.194(2)(b) & (c): amended, on 15 May 2014, by clause 58(3) & (4) of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

Clause 13.194(2)(b)(ii): amended, on 21 September 2012, by clause 27 of the Electricity Industry Participation (Minor Amendments) Code Amendment 2012.

Clause 13.194(2)(b): amended, on 23 February 2015, by clause 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 13.194(2)(c): amended, on 15 May 2014, by clause 49 of the Electricity Industry Participation (Minor Code Amendments) Code Amendment 2014.

### 13.195 Constrained off amount for block dispatch groups and station dispatch groups

The **constrained off amounts** for a **block dispatch group** or **station dispatch group** must equal the sum of the amounts calculated in accordance with clause 13.194 for the **generating plant in block dispatch group** or **station dispatch group**.

Compare: Electricity Governance Rules 2003 rule 4.3.2 section V part G

### 13.196 Calculation of constrained off amounts attributable to system operator

If a **constrained off situation** occurs during any **trading period** in the previous **billing period**, and the **clearing manager** receives notice of the **constrained off situation** under clauses 13.76 to 13.80, the **clearing manager** must determine the portion of the **constrained off amounts** calculated under clause 13.194 that is attributable to the **system operator** for each **generator** as follows:

- (a) if the **system operator** has advised the **clearing manager** that a **voltage support** or other **constrained off situation** occurred (including, but not limited to, **over frequency reserve** and **instantaneous reserve**) the **system operator** must be allocated the total **constrained off amount**:
- (b) if the **system operator** has advised the **clearing manager** that a non-security **constrained off situation** occurred, the **system operator** must be allocated a **constrained off amount** calculated in accordance with the following formula:

$$\text{SOCOFNS}_{\text{so}} = \text{TCOFP} * (\text{SOQcoffns} / \text{TQcoff})$$

where

$\text{SOCOFNS}_{\text{so}}$  is the **constrained off amount** attributable to the **system operator** for that non-security **constrained off situation**

$\text{TCOFP}$  is the total constrained off payment for that **trading period**

$\text{SOQcoffns}$  is the non-security quantity that was constrained off and advised to the **clearing manager** by the **system operator** under clauses 13.76 to 13.80 or the total quantity constrained off, whichever is less

$\text{TQcoff}$  is the total quantity constrained off:

- (c) if the **system operator** has advised the **clearing manager** that a **frequency keeping** situation occurred in a **trading period** the **system operator** must be allocated a **constrained off amount** calculated in accordance with the following formula:

$$\text{SOCOFFK}_{\text{so}} = \text{TCOFP} * (\text{SOQcofffk} / \text{TQcoff})$$

where

$\text{SOCOFFK}_{\text{so}}$  is the **constrained off amount** attributable to the **system operator** for that **frequency keeping constrained off situation**

$\text{TCOFP}$  is the total constrained off payment for the **generator** for the **trading period**

$\text{SOQcofffk}$  is the **frequency keeping** quantity advised to the **clearing manager** by the **system operator** under clauses 13.76 to 13.80 or the total quantity constrained off for the **generator**, whichever is the less

$\text{TQcoff}$  is the total quantity constrained off for the **generator**.

Compare: Electricity Governance Rules 2003 rule 4.3.3 section V part G

Clause 13.196 Heading: amended, on 5 October 2017, by clause 438(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 13.196: amended, on 5 October 2017, by clause 438(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 13.196(c): amended, on 15 May 2014, by clause 59 of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

### 13.197 Calculation of constrained off amounts

By 1600 hours on the 8th **business day** of each **billing period** the **clearing manager** must calculate **constrained off amounts** for the previous **billing period** in accordance with clauses 13.194 to 13.196.

Compare: Electricity Governance Rules 2003 rule 4.4 section V part G

Clause 13.197: amended, on 21 September 2012, by clause 28 of the Electricity Industry Participation (Minor Amendments) Code Amendment 2012.

### 13.198 Clearing manager to send constrained off information to system operator

- (1) The **clearing manager** must, at the time specified in clause 13.197, send to the **system operator** the details of **constrained off amounts** that are attributable to the **system operator** (but limited to information about those **constrained off amounts** that is in the possession of the **clearing manager**) and the constrained off quantities (in **MW**) calculated in accordance with clause 13.196 for the previous **billing period**.
- (2) The information must be provided to the **system operator** in the manner and format agreed between the **clearing manager** and the **system operator** from time to time.

Compare: Electricity Governance Rules 2003 rule 4.5 section V part G

Clause 13.198(1): amended, on 15 May 2014, by clause 60 of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

### 13.199 Clearing manager to make details of constrained off amounts available

The **clearing manager** must, at the time specified in clause 13.197, make the details of **constrained off amounts** available on **WITS** for each **generator** and each **dispatched purchaser** for the previous **billing period** as follows:

- (a) the **constrained off amounts** calculated in accordance with clauses 13.194 to 13.196;
- (b) the **generator** or **dispatched purchaser** (as the case may be) that was constrained off;
- (c) the applicable **grid injection point**, or **grid exit point**, or **block dispatch group**, or **station dispatch group**.

Compare: Electricity Governance Rules 2003 rule 4.6 section V part G

Clause 13.199 Heading: amended, on 5 October 2017, by clause 439(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 13.199: amended, on 15 May 2014, by clause 61 of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

Clause 13.199: amended, on 5 October 2017, by clause 439(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### 13.200 Authority, generators and purchasers have rights to constrained off information

- (1) In addition to the information the **clearing manager** makes available under clause 13.199, a **generator** or **purchaser** who reasonably believes it was adversely affected by a **constrained off situation** occurring, or the **Authority**, may request information from the **system operator** about the cause of the **constrained off situation**.
- (2) The **system operator** must comply with any reasonable request made for such information provided that the information does not include any information that is confidential in respect of any other **generator** or **purchaser**.

Compare: Electricity Governance Rules 2003 rule 4.7 section V part G

Clause 13.200(1): amended, on 5 October 2017, by clause 440 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### 13.201 Generators do not get paid constrained off compensation

- (1) A **generator** is not entitled to be paid compensation in respect of any **constrained off situation** except as provided for in an **ancillary service arrangement** entered into by the **system operator** and the **generator**.
- (2) This clause does not affect the rights that a **participant** has under this Code against the **system operator** for a failure by the **system operator** to comply with this Code.

Compare: Electricity Governance Rules 2003 rule 4.8 section V part G

### 13.201A Dispatched purchasers entitled to constrained off compensation and purchasers to pay constrained off compensation

- (1) A **dispatched purchaser** in respect of whose **dispatch-capable load station** there was a **constrained off situation** as described in clause 13.192(c) is owed **constrained off compensation** for the **constrained off amounts** calculated under clause 13.194(1A).
- (2) A **purchaser** that purchases **electricity** at a **grid exit point** incurs an amount owing to the **clearing manager** for **constrained off compensation**, calculated under subclause (6).



- (2A) The **clearing manager** must advise each **purchaser** of the amount owing by the **purchaser** for **constrained off compensation** for a **billing period** when the **clearing manager** advises amounts owing under subpart 4 of Part 14.
- (3) The **clearing manager** owes **constrained off compensation** received under subclause (2), for each **dispatch-capable load station**, to the **dispatched purchaser** that purchased **electricity** for the **dispatch-capable load station**.
- (4) The **clearing manager** must advise each **dispatched purchaser** of the amount owing to the **dispatched purchaser** for **constrained off compensation** for a **billing period** when the **clearing manager** advises amounts owing under subpart 4 of Part 14.
- (5) *[Revoked]*
- (6) The **clearing manager** must calculate **constrained off compensation** owing by a **purchaser** under subclause (2) for each **trading period** using the following formula:

$$\text{ConOffC}_p = \text{ConOffC}_{\text{DLPs}} * (\text{Pur}_i / \text{TotPur})$$

where

$\text{ConOffC}_p$	is the <b>constrained off compensation</b> owing by a <b>purchaser</b>
$\text{ConOffC}_{\text{DLPs}}$	is the sum of <b>constrained off compensation</b> owing to all <b>dispatched purchasers</b> for the <b>trading period</b>
$\text{Pur}_i$	is the total quantity in <b>MWh</b> of all purchases by the <b>purchaser</b> from the <b>clearing manager</b> during the <b>trading period</b> , as shown by <b>reconciliation information</b> calculated by the <b>reconciliation manager</b> under Part 15
$\text{TotPur}$	is the quantity in <b>MWh</b> of all purchases by all <b>purchasers</b> from the <b>clearing manager</b> during the <b>trading period</b> , as shown by <b>reconciliation information</b> calculated by the <b>reconciliation manager</b> under Part 15.

Clause 13.201A: inserted, on 15 May 2014, by clause 62 of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

Clause 13.201A(1): amended, on 24 March 2015, by clause 12(a) of the Electricity Industry Participation (Settlement and Prudential Security) Code Amendment 2013.

Clause 13.201A(2): amended, on 24 March 2015, by clause 12(b) of the Electricity Industry Participation (Settlement and Prudential Security) Code Amendment 2013.

Clause 13.201A(2A): inserted, on 24 March 2015, by clause 12(c) of the Electricity Industry Participation (Settlement and Prudential Security) Code Amendment 2013.

Clause 13.201A(3): substituted, on 24 March 2015, by clause 12(d) of the Electricity Industry Participation (Settlement and Prudential Security) Code Amendment 2013.

Clause 13.201A(4): substituted, on 24 March 2015, by clause 12(e) of the Electricity Industry Participation (Settlement and Prudential Security) Code Amendment 2013.

Clause 13.201A(5): revoked, on 24 March 2015, by clause 12(f) of the Electricity Industry Participation (Settlement and Prudential Security) Code Amendment 2013.

Clause 13.201A(6): amended, on 24 March 2015, by clause 12(g) of the Electricity Industry Participation (Settlement and Prudential Security) Code Amendment 2013.

### *Calculation of constrained on amounts*

#### **13.202 Constrained on situations may occur**

- (1) Subject to subclause (2), a **constrained on situation** occurs when—
- (a) a **generator** is given a **dispatch instruction** by the **system operator** and the price **offered** by the **generator** for that dispatched quantity of **electricity** at the relevant

- grid injection point** and **trading period** is higher than the **final price** at that **grid injection point** in the relevant **trading period**; or
- (b) in relation to a **block dispatch group** or **station dispatch group**, a **generator** is given a **dispatch instruction** by the **system operator** and the price **offered** by the **generator** for that aggregate dispatched quantity of **electricity** from that **block dispatch group** or **station dispatch group** in the relevant **trading period** is higher than the **final price** in the relevant **trading period**; or
  - (c) an **ancillary service agent** is given a **dispatch instruction** by the **system operator** and the price **offered** by the **ancillary service agent** for the dispatched **instantaneous reserve** in the relevant **trading period** is higher than the **final reserve price** of the dispatched **instantaneous reserve** in the relevant **trading period**.
  - (d) in relation to a **dispatch-capable load station** (except when the final **nominated bid** for the **dispatch-capable load station** in a **trading period** is a **nominated non-dispatch bid**), the latest **dispatch instruction** issued by the **system operator** for the **dispatch-capable load station** for a **trading period** is for a **MW** amount that is more than the **MW** amount scheduled for the **dispatch-capable load station** in the schedule of **final prices** for the **trading period**.
- (2) If the **pricing manager** calculates **interim prices** and **interim reserve prices** in accordance with clause 13.135B for a **trading period**, and the scarcity pricing factor in that calculation is determined under clause 1(3)(c) or clause 2(3)(c) of Schedule 13.3A, a **constrained on situation** is deemed not to have occurred in that **trading period** in the **island** or **islands** in which the **scarcity pricing situation** occurred.

Compare: Electricity Governance Rules 2003 rule 5.1 section V part G

Clause 13.202(1): amended, on 1 June 2013, by clause 16(a) of the Electricity Industry Participation (Scarcity Pricing) Code Amendment 2011.

Clause 13.202(1)(d): inserted, on 15 May 2014, by clause 63 of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

Clause 13.202(1)(d): amended, on 1 December 2015, by clause 8 of the Electricity Industry Participation Code Amendment (Dispatchable Demand: Late Bid Revisions) 2015.

Clause 13.202(2): inserted, on 1 June 2013, by clause 16(b) of the Electricity Industry Participation (Scarcity Pricing) Code Amendment 2011.

### 13.203 Determining affected price bands for block dispatch groups or station dispatch groups

If a **constrained on situation** occurred for a **block dispatch group** or **station dispatch group** during any **trading period** during the previous **billing period**, the **clearing manager** must determine the affected price bands for that **block dispatch group** or **station dispatch group** by—

- (a) taking all the **offers** made by that **block dispatch group** or **station dispatch group** in relation to that **trading period**, calculating the differences between each **offer price** and **final price** for each **grid injection point** and ranking the differences in ascending order; and
- (b) identifying each price band ranked under paragraph (a) in which the aggregate quantity for that price band plus all the quantity in all previous price bands exceeds the aggregate quantity for all the **generating plant** in that **block dispatch group** or **station dispatch group** calculated by the **pricing manager** using the

methodology set out in Schedule 13.3. The **offer** prices corresponding to the ranked price bands identified under this paragraph are the affected price bands for that **block dispatch group** or **station dispatch group** for the purposes of clause 13.204.

Compare: Electricity Governance Rules 2003 rule 5.2 section V part G

### 13.204 Calculation of constrained on amounts

(1) If a **constrained on situation** occurs during any **trading period** during a previous **billing period**,—

- (a) the **clearing manager** must calculate the **constrained on amounts** for a **constrained on situation** described in clause 13.202(1)(a) or (b) for each **generator** for each affected price band in accordance with the following formula:

$$\text{COC} = Q_{\text{con}} * (P_o - P_f)$$

where

COC is the **constrained on amount** for a **generator**

$Q_{\text{con}}$  is the dispatched quantity in **MWh** (calculated as set out below) from that price band in the **offer** that was constrained on during a **trading period**, or the positive difference between the **reconciliation information** and the **scheduled quantity**, whichever is less

$P_o$  is the price offered for that price band by the **generator** for the quantity of **electricity** from the **generating plant** which was constrained on

- $P_f$  is the **final price** for that **trading period** at the **grid injection point**; and  
(aa) the **clearing manager** must calculate the **constrained on amounts** for a **constrained on situation** described in clause 13.202(1)(d) for each **dispatch-capable load station** for each affected **nominated dispatch bid** price band, using the following formula:

$$\text{ConOnAmt} = \text{ConOnQ} * (P_f - P_b)$$

where

ConOnAmt is the **constrained on amount** for a **dispatch-capable load station** for the **nominated dispatch bid** price band

ConOnQ is the amount in **MWh** by which the lowest of  $Q_{\text{disp}}$  and  $Q_{\text{rec}}$  exceeds  $Q_{\text{fp}}$

where

$Q_{\text{disp}}$  is the latest quantity in **MWh**, dispatched for the **nominated dispatch bid** price band in the **trading period**

$Q_{\text{rec}}$  is the **reconciled quantity** provided by the **reconciliation manager** under clause 15.20C allocated by the **clearing manager** to the **nominated dispatch bid** price band in the **trading period**

- $Q_{fp}$  is the quantity, in **MWh**, scheduled for the **nominated dispatch bid** price band in the schedule of **final prices**
- $P_f$  is the **final price** for the **trading period** at the **grid exit point**
- $P_b$  is the price bid for the **nominated dispatch bid** price band for the **dispatch-capable load station** that was constrained on; and
- (b) for the purposes of clauses 13.202 to 13.211 dispatched quantity must be calculated taking into account—
- (i) the quantity in **MW** recorded in the log kept by the **system operator** in accordance with clause 13.76; and if required, the **clearing manager** must aggregate such quantities for—
- (A) **generating stations** or **generating units** in the relevant **station dispatch group**; or
- (B) **generating units**, if the **clearing manager** requires a dispatched quantity to be determined on a **grid injection point** basis; and
- (ii) for an **offer**, the ramp rate applying to that **constrained on situation** that is specified in the **offer** submitted by the **generator**, or—
- (A) for a **block dispatch group** or a **station dispatch group**; or
- (B) for **generating units**, if the **clearing manager** requires the dispatched quantity to be determined on a **grid injection point** basis—
- the fastest of the ramp rates applying to that **constrained on situation** that are specified in the **offers** submitted by the **generator** in that **block dispatch group**, that **station dispatch group** or those **generating units electrically connected** to the relevant **grid injection point** (as the case may be); and
- (iii) plus or minus the **MW** bandwidth applicable for each **generator** affected by a **frequency keeping** requirement as advised by the **system operator** to the **clearing manager** under clauses 13.76 to 13.80 and, if required, the **clearing manager** must aggregate the **MW** bandwidth applicable to determine the **MW** bandwidth on a **grid injection point** basis; and
- (c) the **clearing manager** must calculate the **constrained on amounts** for a **constrained on situation** described in clause 13.202(c) for each **ancillary service agent** for each affected price band in accordance with the following formula:

$$COC = Q_{con} * (P_o - P_f)$$

where

$COC$  is the **constrained on amount** for an **ancillary service agent**

$Q_{con}$  is the dispatched quantity of **instantaneous reserve** in **MW** (calculated as set out below) from that price band in the **reserve offer** that was constrained on during a **trading period**

$P_o$  is the price offered for that price band by that **ancillary service agent** for the quantity  $Q_{con}$

$P_f$  is the **final reserve price** for that **trading period** at the **point of connection** on the **grid**; and

- (d) for the purposes of paragraph (c), in determining the dispatched quantity, the **clearing manager** must take into account the quantity in **MW** of **instantaneous reserve** dispatched for the **ancillary service agent** recorded in the log kept by the **system operator** in accordance with clause 13.76; and
  - (e) the **constrained on amounts** for a **block dispatch group** or **station dispatch group** equal the sum of the amounts calculated in accordance with paragraphs (a) and (b) for the **generating plant** in that **block dispatch group** or **station dispatch group** (as the case may be); and
  - (f) in relation to any 2 adjacent **trading periods**, a **generator** is entitled to be paid for the 2<sup>nd</sup> **trading period** at the **final price** for the **grid injection point** if the **generator**—
    - (i) was in a **constrained on situation** in the 1<sup>st</sup> **trading period**; and
    - (ii) continues to generate in the 2<sup>nd</sup> **trading period** as a result of a **dispatch instruction** given for the 1<sup>st</sup> **trading period**; but
    - (iii) has not made an **offer** in the 2<sup>nd</sup> **trading period**.
- (2) To avoid doubt, nothing in this clause entitles the **system operator** to issue any instruction to a **generator** in relation to **unoffered generation**.

Compare: Electricity Governance Rules 2003 rule 5.3 section V part G

Clause 13.204(1)(a): amended, on 5 October 2017, by clause 441 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 13.204(1)(aa): inserted, on 15 May 2014, by clause 64(a) of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

Clause 13.204(1)(b)(ii): amended, on 15 May 2014, by clause 64(b) of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

Clause 13.204(1)(b)(ii): amended, on 23 February 2015, by clause 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 13.204(1)(b)(ii): amended, on 5 October 2017, by clause 441 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 13.204(1)(c): amended, on 21 September 2012, by clause 29 of the Electricity Industry Participation (Minor Amendments) Code Amendment 2012.

### 13.205 Calculation of constrained on amounts attributable to system operator

If a **constrained on situation** occurs during a **trading period** in a previous **billing period**, and the **clearing manager** receives notice of the **constrained on situation** under clauses 13.76 to 13.80, the **clearing manager** must determine the portion of the **constrained on amounts** calculated under clause 13.204 attributable to the **system operator** for each **generator** or each **ancillary service agent** as follows:

- (a) if the **system operator** has advised the **clearing manager** that a **voltage support** or other **constrained on situation** occurred (including but not limited to **over frequency reserve** and **instantaneous reserve**) the **system operator** must be allocated the total **constrained on amount** for that **trading period**:
- (b) if the **system operator** has advised the **clearing manager** that a non-security **constrained on situation** occurred the **system operator** must be allocated a **constrained on amount** calculated in accordance with the following formula:

$$\text{SOCONNS}_{\text{go}} = \text{TCONP} * (\text{SOQconns} / \text{TQcon})$$

where

$\text{SOCONNS}_{\text{go}}$  is the **constrained on amount** attributable to the **system operator** for that non-security **constrained on situation**

$\text{TCONP}$  is the total **constrained on payment** for that **trading period**

$\text{SOQconns}$  is the non-security quantity that was constrained on and advised to the **clearing manager** by the **system operator** under clauses 13.76 to 13.80, or the total quantity constrained on, whichever is less

$\text{TQcon}$  is the total quantity constrained on:

- (c) if the **system operator** has advised the **clearing manager** that a **frequency keeping** situation occurred the **system operator** must be allocated a **constrained on amount** calculated in accordance with the following formula:

$$\text{SOCONFK}_{\text{go}} = \text{TCONP} * (\text{SOQconfk} / \text{TQcon})$$

where

$\text{SOCONFK}_{\text{go}}$  is the **constrained on amount** attributable to the **system operator** for that **frequency keeping constrained on situation**

$\text{TCONP}$  is the total constrained on payment for the **generator** for the **trading period**

$\text{SOQconfk}$  is the **frequency keeping** quantity that was advised to the **clearing manager** by the **system operator** under clause 13.76 to 13.80, or the total quantity constrained on for the **generator**, whichever is less

$\text{TQcon}$  is the total quantity constrained on for the **generator**.

Compare: Electricity Governance Rules 2003 rule 5.4 section V part G

Clause 13.205: amended, on 15 May 2014, by clause 65 of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

Clause 13.205: amended, on 5 October 2017, by clause 442 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### 13.206 Timeframe for calculating constrained on amounts

The **clearing manager** must calculate **constrained on amounts**—

- (a) by 1600 hours on the 8<sup>th</sup> **business day** of each **billing period** for the previous **billing period** in accordance with clauses 13.204 and 13.205; or
- (b) if **final prices** for any **trading period** in the relevant **billing period** are delayed and only made available on **WITS** later than 1600 hours on the 6<sup>th</sup> **business day**

of the month following the relevant **billing period**; 1 **business day** after all **final prices** for the **billing period** are made available on **WITS**.

Compare: Electricity Governance Rules 2003 rule 5.5 section V part G

Clause 13.206 Heading: amended, on 5 October 2017, by clause 443(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 13.206: substituted, on 15 May 2014, by clause 4 of the Electricity Industry Participation (Time Frames for Invoicing) Code Amendment 2014.

Clause 13.206(b): replaced, on 5 October 2017, by clause 443(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### **13.207 Clearing manager to send constrained on information to system operator**

- (1) The **clearing manager** must, at the time specified in clause 13.206, send to the **system operator** the details of **constrained on amounts** that are attributed to the **system operator** (but limited to information about those **constrained on amounts** that is in the possession of the **clearing manager**) and the constrained on quantities (in **MW**) calculated in accordance with clause 13.205 for the previous **billing period**.
- (2) The information must be provided to the **system operator** in the manner and format agreed between the **clearing manager** and the **system operator** from time to time.

Compare: Electricity Governance Rules 2003 rule 5.6 section V part G

### **13.208 Clearing manager to make details of constrained on amounts available**

The **clearing manager** must, at the time specified in clause 13.206, make the details of **constrained on amounts** available on **WITS** in relation to each **generator**, **ancillary service agent**, and **dispatched purchaser** for the previous **billing period** calculated in accordance with clauses 13.204 and 13.205 as follows:

- (a) the aggregate **constrained on amounts** calculated under clauses 13.204 and 13.205:
- (b) the **generator**, **ancillary service agent**, or **dispatched purchaser** (as the case may be) that was constrained on:
- (c) the applicable **grid injection point**, **grid exit point**, **block dispatch group**, or **station dispatch group**.

Compare: Electricity Governance Rules 2003 rule 5.7 section V part G

Clause 13.208 Heading: amended, on 5 October 2017, by clause 444(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 13.208: amended, on 15 May 2014, by clause 66 of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

Clause 13.208: amended, on 5 October 2017, by clause 444(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### **13.209 Authority, generators, ancillary service agents, and purchasers have rights to constrained on information**

- (1) In addition to the information the **clearing manager** makes available under clause 13.208, the **Authority**, or a **generator**, **ancillary service agent**, or **purchaser** who reasonably believes it was adversely affected by a **constrained on situation** occurring, may request information from the **system operator** about the cause of the **constrained on situation**.
- (2) The **system operator** must comply with any reasonable request for such information except that the information must not include any information that is confidential in respect of any other **generator**, **ancillary service agent**, or **purchaser**.

Compare: Electricity Governance Rules 2003 rule 5.8 section V part G  
Clause 13.209(1): amended, on 5 October 2017, by clause 445 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### 13.210 *[Revoked]*

Compare: Electricity Governance Rules 2003 rule 5.9 section V part G  
Clause 13.210: revoked, on 5 October 2017, by clause 446 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### 13.211 Backup procedures if WITS is unavailable

- (1) If **WITS** is unavailable for the purposes of making information available under clauses 13.199 and 13.208, the **clearing manager** must follow the backup procedures specified by the **WITS manager** from time to time.
- (2) The **WITS manager** must specify the backup procedures referred to in subclause (1) following consultation with the **Authority**, **generators**, **ancillary service agents**, **purchasers**, and the **clearing manager**.

Compare: Electricity Governance Rules 2003 rules 5.10 and 5.11 section V part G  
Clause 13.211: replaced, on 5 October 2017, by clause 447 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### 13.212 Payment of constrained on compensation

- (1) For each **trading period**,—
  - (a) a **generator** or **ancillary service agent** is owed **constrained on compensation** for **constrained on amounts** determined under clauses 13.204 and 13.205; and
  - (b) a **dispatched purchaser** is owed **constrained on compensation** for **constrained on amounts** determined under clause 13.204.
- (1A) **Constrained on compensation** for each **dispatch-capable load station** is an amount owing to the **dispatched purchaser** that purchased **electricity** for the **dispatch-capable load station**.
- (2) The **system operator** must pay to a **generator**, or **ancillary service agent** any **constrained on amount** calculated under clause 13.205.
- (3) The **clearing manager** must advise each **generator**, **ancillary service agent**, and **dispatched purchaser** of the amount owing to the **generator**, **ancillary service agent**, or **dispatched purchaser** for **constrained on compensation** for a **billing period** when the **clearing manager** advises amounts owing under subpart 4 of Part 14.
- (4) *[Revoked]*
- (5) Each **purchaser** that purchases **electricity** at a **grid exit point** incurs an amount owing to the **clearing manager** for **constrained on compensation**, calculated under subclause (7).
- (5A) *[Revoked]*
- (6) **Instantaneous reserve constrained on compensation** is an **instantaneous reserve** cost that must be allocated in accordance with clauses 8.59 to 8.66.
- (7) The **clearing manager** must calculate **constrained on compensation** for each **trading period** using the following formula:

$$\text{COC}_p = (\text{COC}_g - \text{COC}_{so}) * (P_q / \text{TP}_q)$$

where



$COC_p$	is the <b>constrained on compensation</b> owing by a <b>purchaser</b>
$COC_g$	is the sum of <b>constrained on compensation</b> owing to all <b>generators</b> and all <b>dispatched purchasers</b> for the <b>trading period</b> calculated in accordance with clause 13.204(1)(a) and 13.204(1)(aa)
$COC_{so}$	is the sum of <b>constrained on compensation</b> for that <b>trading period</b> payable by the <b>system operator</b> to <b>generators</b> under subclause (2)
$P_q$	is the total <b>electricity</b> purchased by that <b>purchaser</b> from the <b>clearing manager</b> during the <b>trading period</b> as shown by the <b>reconciliation information</b> calculated by the <b>reconciliation manager</b> under Part 15
$TP_q$	is the total <b>electricity</b> purchased by all <b>purchasers</b> from the <b>clearing manager</b> during the <b>trading period</b> as shown by <b>reconciliation information</b> calculated by the <b>reconciliation manager</b> under Part 15.

- (8) The **clearing manager** must advise each **purchaser** of the amount owing by the **purchaser** for **constrained on compensation** for a **billing period** when the **clearing manager** advises amounts owing under subpart 4 of Part 14.

Compare: Electricity Governance Rules 2003 rule 6 section V part G

Clause 13.212(1): substituted, on 15 May 2014, by clause 67(a) of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

Clause 13.212(1): amended, on 24 March 2015, by clause 13(a) of the Electricity Industry Participation (Settlement and Prudential Security) Code Amendment 2013.

Clause 13.212(1A): inserted, on 15 May 2014, by clause 67(a) of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

Clause 13.212(1A): amended, on 24 March 2015, by clause 13(b) of the Electricity Industry Participation (Settlement and Prudential Security) Code Amendment 2013.

Clause 13.212(3) & (4): amended, on 15 May 2014, by clause 67(b) & (c) of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

Clause 13.212(3): substituted, on 24 March 2015, by clause 13(c) of the Electricity Industry Participation (Settlement and Prudential Security) Code Amendment 2013.

Clause 13.212(4): revoked, on 24 March 2015, by clause 13(d) of the Electricity Industry Participation (Settlement and Prudential Security) Code Amendment 2013.

Clause 13.212(5): substituted, on 15 May 2014, by clause 67(d) of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

Clause 13.212(5): substituted, on 24 March 2015, by clause 13(e) of the Electricity Industry Participation (Settlement and Prudential Security) Code Amendment 2013.

Clause 13.212(5A): inserted, on 15 May 2014, by clause 67(d) of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

Clause 13.212(5A): revoked, on 24 March 2015, by clause 13(f) of the Electricity Industry Participation (Settlement and Prudential Security) Code Amendment 2013.

Clause 13.212(7): amended, on 15 May 2014, by clause 67(e) of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

Clause 13.212(7): amended, on 24 March 2015, by clause 13(g) of the Electricity Industry Participation (Settlement and Prudential Security) Code Amendment 2013.

Clause 13.212(8): substituted, on 24 March 2015, by clause 13(h) of the Electricity Industry Participation (Settlement and Prudential Security) Code Amendment 2013.

*No payment of constrained on and off compensation for frequency keeping*

Cross heading: inserted, on 1 May 2016, by clause 4 of the Electricity Industry Participation Code Amendment (Removal of In-band Frequency Keeping Compensation) 2015.

**13.212A No payment of constrained on and off compensation for frequency keeping**

- (1) Despite clause 13.192 to clause 13.212, the **system operator** must not pay a **frequency keeping ancillary service agent**—
  - (a) **constrained on compensation** in respect of any **constrained on situation**; or
  - (b) **constrained off compensation** in respect of any **constrained off situation**.
- (2) Subclause (1) applies in respect of any **reconciled quantity** of **electricity** the **frequency keeping ancillary service agent** produces—
  - (a) while providing **frequency keeping**; and
  - (b) between—
    - (i) the level of **active power** (expressed in **MW**) dispatched in a **trading period** to the **ancillary service agent's generating plant**; and
    - (ii) the level of **active power** (expressed in **MW**) generated by the **ancillary service agent's generating plant** in a **trading period**, measured by a **metering installation**.

Clause 13.212A: inserted, on 1 May 2016, by clause 4 of the Electricity Industry Participation Code Amendment (Removal of In-band Frequency Keeping Compensation) 2015.

*Pricing manager's reporting obligations*

**13.213 Daily reports**

- (1) On each **trading day** the **pricing manager** must provide the **Authority** with a written report for the **trading periods** beginning at 0700 hours on the previous **trading day** and ending with the **trading period** beginning at 0630 hours on the **trading day** the report is due to be given, specifying—
  - (a) any **provisional prices** made available on **WITS**; and
  - (b) any **pricing errors** claimed; and
  - (c) any situation where the **pricing manager** believes, on reasonable grounds, that it or another **participant** has breached this Code.
- (2) In relation to each alleged breach the report must give details of—
  - (a) occasions when prices were or will be made available on **WITS** late and whether the delay was caused by the **pricing manager**; and
  - (b) the time at which the alleged breach took place; and
  - (c) the nature of the alleged breach, including details of the person alleged to be in breach and any **generator** or **purchaser** believed to be affected by the alleged breach; and
  - (d) the reason for the alleged breach, if the **pricing manager** is aware of the reason.

Compare: Electricity Governance Rules 2003 rule 7.1 section V part G

Clause 13.213(1) and 2(a): amended, on 5 October 2017, by clause 448 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### 13.214 Authority to publish pricing manager reports

- (1) By the 15th **business day** of each calendar month, the **Authority** must **publish** the sections of the reports of the **pricing manager** given in the previous calendar month under clause 13.213 that relate to any alleged breaches of this Code by the **pricing manager**.
- (2) *[Revoked]*.

Compare: Electricity Governance Rules 2003 rule 7.2 section V part G

Clause 13.214 Heading: amended, on 5 October 2017, by clause 449(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 13.214(1): amended, on 5 October 2017, by clause 449(2)(a) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 13.214(2): revoked, on 5 October 2017, by clause 449(2)(b) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### 13.215 Generators and purchasers have right to information concerning pricing manager's action

- (1) A **generator** or a **purchaser** may, by giving written notice to the **pricing manager**, request further information relating to any situation set out in a **pricing manager's** report **published** under clause 13.214 that has materially affected the **generator** or **purchaser**.
- (2) In such cases, the **pricing manager** must provide the requested information to that **generator** or **purchaser** except that such information must not include any information that is confidential in respect of any other person.

Compare: Electricity Governance Rules 2003 rule 7.3 section V part G

Clause 13.215(1): amended, on 5 October 2017, by clause 450 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### 13.216 Daily situation report

On the day after the **pricing manager** makes **final prices** and **final reserve prices** available on **WITS** in respect of the **trading day** to which the prices relate, the **pricing manager** must give the **Authority** a report containing—

- (a) a statement of whether flows on any **branches** were at their maximum capacity and each **trading period** affected; and
- (b) a statement of whether the status of circulating **HVDC link** and **branch** flows was abnormal and each **trading period** affected.

Compare: Electricity Governance Rules 2003 rule 7.4 section V part G

Clause 13.216: amended, on 5 October 2017, by clause 451 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

## Subpart 5—Hedge arrangement disclosure

### 13.217 Contents of this subpart

This subpart provides for the disclosure of information about **risk management contracts**, which may be **contracts for differences**, **fixed-price physical supply contracts** or **options contracts**, in order to—

- (a) facilitate the ready comparison of **electricity** prices and other key terms of **risk management contracts**; and

- (b) address the lack of information available to persons to formulate their own historic contract curves for **electricity**; and
- (c) provide a more informed basis for persons to assess the competitiveness of the market for **risk management contracts** in respect of **electricity**.

Compare: Electricity Governance Rules 2003 rule 1 section VI part G

### 13.218 Parties required to submit information

The following **parties** to **risk management contracts** are required to submit the information specified in clauses 13.219, 13.222 and 13.223 using an **approved system**:

- (a) the **seller**, if the **seller** is a **participant**; or
- (b) the **buyer**, if the **buyer** is a **participant** and the **seller** is not a **participant**.

Compare: Electricity Governance Rules 2003 rule 2 section VI part G

Clause 13.218: amended, on 5 October 2017, by clause 452 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 13.218(a): amended, on 21 September 2012, by clause 30 of the Electricity Industry Participation (Minor Amendments) Code Amendment 2012.

### 13.219 Information that must be submitted

- (1) The following information must be submitted to the **approved system** in relation to every **options contract**:
  - (a) the **trade date**;
  - (b) the **effective date**;
  - (c) the **end date**;
  - (d) the **quantity**.
- (2) The following information must be submitted to the **approved system** in relation to each **contract for differences** or **fixed-price physical supply contract**:
  - (a) whether the contract is a **contract for differences** or a **fixed-price physical supply contract**;
  - (b) the **trade date**;
  - (c) the **effective date**;
  - (d) the **end date**;
  - (e) the **quantity**;
  - (f) whether or not the contract applies to all **trading periods** within its **term**;
  - (g) whether there is an **adjustment clause**;
  - (h) whether there is a **force majeure clause**;
  - (i) whether there is a **suspension clause**;
  - (j) whether there are any other clauses providing for the pass-through of certain costs, levies or tax or some form of carbon-related cost.
- (3) In addition to the information that must be submitted in accordance with subclause (2), the following information must be submitted to the **approved system** in relation to each **contract for differences**:
  - (a) whether there is a **special credit clause**;
  - (b) whether the volume of **electricity**, in respect of which payments are required to be made by the **floating-price payer**, is flat or varies for different **trading periods**;

- (c) whether the contract has been traded on the EnergyHedge platform. The EnergyHedge platform is a centralised trading platform for standardised derivative contracts on **electricity** prices in New Zealand;
  - (d) whether the contract has been prepared based on the standardised schedule, which can be adopted in conjunction with the International Swaps and Derivatives Association Master Agreement, as may be available on EnergyHedge.
- (4) In addition to the information that must be submitted in accordance with subclauses (2) and (3), the following information must be submitted to the **approved system** in relation to each **contract for differences** that has a **term** of less than 10 years and each **fixed-price physical supply contract** that has a **term** of less than 10 years:
- (a) the **contract price** calculated in accordance with clause 13.220;
  - (b) the **grid zone area** in which the **contract price** is determined or applies.
- (5) The information specified in this clause must be submitted in the form specified by the **Authority** and in accordance with clause 13.225(1).
- (6) If a **seller** and a **buyer** enter into a **contract for differences** or **fixed-price physical supply contract** that includes more than 1 **contract price schedule**, the **party** required to submit information in accordance with clause 13.218 must do so in accordance with 1 of the following methods:
- (a) if the contract includes **contract price schedules** relating to more than 1 **grid zone area**, by combining the information relating to all **contract price schedules** within each **grid zone area** and submitting that combined information to the **approved system** as if there were 1 contract for each **grid zone area**;
  - (b) if the contract includes **contract price schedules** relating to more than 1 **node**, by combining the information relating to all **contract price schedules** at each **node** and submitting the combined information to the **approved system** as if there were 1 contract for each **node**;
  - (c) if the **party** does not wish to combine the information in accordance with paragraphs (a) and (b), by submitting the information for each **contract price schedule** to the **approved system** individually, as though each **contract price schedule** was a separate contract.
- (7) To avoid doubt, if a **contract for differences** or **fixed-priced physical supply contract** includes an **adjustment clause**,—
- (a) the information that must be disclosed in accordance with this clause, in relation to the contract, must only be disclosed once; and
  - (b) the **contract price** to be disclosed in accordance with subclause (4) is that which first applies under the contract.

Compare: Electricity Governance Rules 2003 rule 3 section VI part G  
Clause 13.219(1), (2), (3), (4) and (6): amended, on 5 October 2017, by clause 453 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### 13.220 Calculation of contract price

- (1) The **contract price** to be submitted for the purposes of clause 13.219(4)(a) and (6) is to be calculated in accordance with the following formula:

$$CP = \left( \frac{\sum_{i=1}^n P_i \times TP_i}{\sum_{i=1}^n TP_i} \right) / LF \times LAF$$

where

CP is the **contract price**

n is the number of different prices within the contract

P<sub>i</sub> is the price specified in the contract

TP<sub>i</sub> is the number of **trading periods** during which each price in the contract applies

LF is the **location factor**, for the relevant **node** at which the price is set in the contract, as **published** by the **Authority** in accordance with clause 13.221

LAF means a loss adjustment factor, which is,—

- (a) if the **contract price** for the contract is referenced to a **point of connection** on the **grid**, 1; or
  - (b) for all other contracts, 0.937 (being the difference between 1 and the loss factor of 0.063).
- (2) The **Authority** may issue guidelines on the **approved system** to provide assistance to **sellers** and **buyers** in determining what information must be submitted to the **approved system**, which may include clarification as to how to apply the formula in subclause (1) in the circumstances covered by clause 13.219(6).

Compare: Electricity Governance Rules 2003 rule 4 section VI part G

Clause 13.220(2): amended, on 5 October 2017, by clause 454 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### 13.221 Node and grid zone area information

- (1) The **WITS manager** must **publish** annually,—
- (a) a list of all **nodes** at which the **pricing manager** makes **final prices** available on **WITS**; and
  - (b) a corresponding **location factor** for each such **node**; and
  - (c) a corresponding **grid zone area** for each such **node**; and
  - (d) a list of nominated **zone nodes**, being 1 **node** at which the **pricing manager** makes **final prices** available on **WITS**, within each **grid zone area**.

- (2) For the purposes of subclause (1)(b), the **location factor** for each such **node** must be calculated as follows:

$$LF = A/B$$

where

- A is the average **final price** made available on **WITS** at that **node** over the 12 month period preceding the month before the date on which the **location factors** are **published**
- B is the average **final price** made available on **WITS** at the relevant nominated **zone node**, as **published** in accordance with subclause (1)(d), for the 12 month period preceding the month before the date on which the **location factors** are **published**

LF is the **location factor** to be **published** in accordance with subclause (1)(b).

Compare: Electricity Governance Rules 2003 rule 5 section VI part G  
Clause 13.221(1) and (2): amended, on 5 October 2017, by clause 455 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### 13.222 Other information that must be submitted

- (1) The following information must be submitted to the **approved system** in relation to every **risk management contract**:
- (a) each **party's** legal name:
  - (b) each **party's** email address for notice.
- (2) The information must be submitted in accordance with clause 13.225(1).

Compare: Electricity Governance Rules 2003 rule 6 section VI part G  
Clause 13.222(1): amended, on 5 October 2017, by clause 456 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### 13.223 Modified or amended information

- (1) If a modification or amendment is made to a **risk management contract**, after the information referred to in clauses 13.219 or 13.222 has been submitted to the **approved system**, and the effect of the modification or amendment is that the information submitted to the **approved system** is no longer correct or complete, the modified or amended information must be submitted to the **approved system**.
- (2) The information submitted under subclause (1) must—
- (a) identify in each case the information that has been modified or amended; and
  - (b) be in the form specified by the **Authority**; and
  - (c) be submitted in accordance with clause 13.225(2).

Compare: Electricity Governance Rules 2003 rule 7 section VI part G  
Clause 13.223(1): amended, on 5 October 2017, by clause 457 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

#### 13.224 Correction of information

Except when clause 13.223 applies, if a **party** to a **risk management contract** discovers that information previously submitted to the **approved system** about that **risk management contract** is incorrect or incomplete, that **party** must—

- (a) seek to agree with the **other party** to the **risk management contract** that the information is incorrect or incomplete and how it should be corrected; and
- (b) when both **parties** have agreed that the incorrect or incomplete information should be corrected, submit the corrected information to the **approved system** in accordance with clause 13.225(3).

Compare: Electricity Governance Rules 2003 rule 8 section VI part G  
Clause 13.224: amended, on 5 October 2017, by clause 458 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

#### 13.225 Timeframes for submitting information

- (1) The information specified in clauses 13.219 and 13.222 must be submitted to the **approved system**—
  - (a) in respect of a **contract for differences** or an **options contract**, no later than 5pm, 5 **business days** after the **trade date**; and
  - (b) for any other type of **risk management contract**, no later than 5pm, 10 **business days** after the **trade date**.
- (2) The modified or amended information submitted under clause 13.223(1) must be submitted to the **approved system** no later than 5pm, 5 **business days** after the amendment or modification to the **risk management contract** is made.
- (3) A **participant** that discovers under clause 13.224 that information it submitted to the **approved system** is incorrect or incomplete must submit the corrected information to the **approved system** no later than 5pm, 2 **business days** after both **parties** to the **risk management contract** have agreed how the incorrect or incomplete information should be corrected.
- (4) The corrected information submitted in accordance with clause 13.227(8) must be submitted to the **approved system** no later than 5pm, 2 **business days** after the **parties** to the **risk management contract** have agreed, in accordance with clause 13.227(5)(b), that the information made available under clause 13.226(1) is not correct, and corrected the information accordingly.

Compare: Electricity Governance Rules 2003 rule 9 section VI part G  
Clause 13.225(1) to (4): amended, on 5 October 2017, by clause 459 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

#### 13.226 WITS manager must make certain information available to the public

- (1) The **WITS manager** must, as soon as practicable, make the information submitted under clauses 13.219, 13.223(1), and 13.224 available at no cost on a publicly accessible **approved system**.
- (2) At the same time that it makes the submitted information available in accordance with subclause (1), for all information other than that submitted under clause 13.224, the **WITS manager** must—
  - (a) indicate on the **approved system** that the information is unverified; and



- (b) if the contract is a **contract for differences** or an **options contract**, give a written notice to the **other party** to the contract—
  - (i) (if the **other party** is a **participant**) requiring the **other party** to submit a **verification notice** to the **approved system** within 2 **business days** of receiving the notice confirming whether or not the information is correct; or
  - (ii) (if the **other party** is not a **participant**) giving the **other party** the option to submit a **verification notice** to the **approved system** within 2 **business days** of receiving the notice confirming whether or not the information is correct; or
- (c) if the contract is a **fixed-price physical supply contract**, give a written notice to the **other party** giving the **other party** the option to submit a **verification notice** to the **approved system** within 2 **business days** confirming whether or not the information is correct.
- (3) A **participant** that receives a **verification notice** under subclause (2)(b)(i) must comply with the written notice.

Compare: Electricity Governance Rules 2003 rule 10 section VI part G

Clause 13.226 Heading: replaced, on 5 October 2017, by clause 460(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 13.226(1): replaced, on 5 October 2017, by clause 460(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 13.226(2): amended, on 5 October 2017, by clause 460(3) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 13.226(3): amended, on 5 October 2017, by clause 460(4) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### 13.227 Verification of information

- (1) If the **other party** to a **risk management contract** submits a **verification notice** to the **approved system** within 2 **business days** of receiving notice under clause 13.226(2) confirming that the information made available under clause 13.226(1) is correct, the **WITS manager** must indicate that the information made available under clause 13.226(1) is verified.
- (2) The **WITS manager** must indicate on the **approved system** that the information made available under clause 13.226(1) is not disputed, if—
  - (a) the **other party** to a **contract for differences** or an **options contract** is not a **participant** and does not submit a **verification notice** to the **approved system** within 2 **business days** of receiving notice under clause 13.226(2)(b)(ii); or
  - (b) the **other party** to a **fixed-price physical supply contract** does not submit a **verification notice** to the **approved system** within 2 **business days** of receiving notice under clause 13.226(2)(c).
- (3) If the **other party** to a **risk management contract** submits a **verification notice** to the **WITS manager** within 2 **business days** of receiving notice under clause 13.226(2) advising that the information made available under clause 13.226(1) is not correct, the **approved system** must indicate that the information is disputed.
- (4) If the **other party** to a **contract for differences** or an **options contract** is a **participant** but does not submit a **verification notice** within 2 **business days** of receiving notice in accordance with clause 13.226(2)(b)(i), the **WITS manager** must—

- (a) indicate on the **approved system** that the information made available in accordance with clause 13.226(1) is pending verification; and
  - (b) give the **other party** a written reminder notice requiring the **other party** to submit a **verification notice** as soon as possible.
- (5) If the information made available under clause 13.226(1) is disputed, the **WITS manager** must—
  - (a) indicate on the **approved system** that the information is disputed; and
  - (b) give the **parties** to the relevant **risk management contract** a written notice requiring the **parties** to use all reasonable endeavours to agree on whether the information submitted in accordance with clause 13.225(1) is correct or not within 10 **business days** of receiving the notice.
- (6) The **parties** must comply with any notice given under subclauses (4)(b) or (5)(b).
- (7) If the **parties** to the **risk management contract** agree in accordance with subclause (5)(b) that the information made available in accordance with clause 13.226(1) is correct, the **other party** must submit a **verification notice** to the **approved system** within 1 **business day** confirming that the information is correct.
- (8) If the **parties** to a **risk management contract** agree in accordance with subclause (5)(b) that the information made available in accordance with clause 13.226(1) is not correct, the **party** that submitted that information to the **approved system** must correct that information in accordance with clause 13.225(4).
- (9) If, within 10 **business days** of receiving the notice sent in accordance with subclause (5)(b), the **parties** to the relevant **risk management contract** are not able to agree whether or not the information made available in accordance with clause 13.226(1) is correct, despite using all reasonable endeavours, the **WITS manager** must indicate on the **approved system** that the information is subject to a long term dispute.

Compare: Electricity Governance Rules 2003 rule 11 section VI part G

Clause 13.227(1): amended, on 5 October 2017, by clause 461(1) and (2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 13.227(2): amended, on 5 October 2017, by clause 461(2) and (3) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 13.227(3): amended, on 5 October 2017, by clause 461(2) and (4) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 13.227(4): amended, on 5 October 2017, by clause 461(2), (5) and (6) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 13.227(5): amended, on 5 October 2017, by clause 461(2), (6) and (7) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 13.227(6): amended, on 5 October 2017, by clause 461(8) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 13.227(7): amended, on 5 October 2017, by clause 461(2) and (9) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 13.227(8): amended, on 5 October 2017, by clause 461(2) and (9) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 13.227(9): amended, on 5 October 2017, by clause 461(10) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### 13.228 Confirmation of information submitted through approved system

- (1) The **WITS manager** must, using the **approved system**, confirm receipt of any information received by it under clauses 13.21, or 13.222 to 13.224.

- (2) Each confirmation under subclause (1) must contain a copy of the information received using the **approved system**, together with the date and time of receipt.

Compare: Electricity Governance Rules 2003 rule 12 section VI part G

Clause 13.228 Heading: amended, on 5 October 2017, by clause 462(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 13.228(1): amended, on 5 October 2017, by clause 462(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 13.228(2): amended, on 5 October 2017, by clause 462(3) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### 13.229 Submitting party to check if no confirmation received

- (1) If a **party** that submits information to the **approved system** does not receive confirmation from the **WITS manager** under clause 13.228(1) that the **approved system** has received the **party's** information within 6 hours of submitting the information, that **party** must, within 1 **business day** of that 6 hour period ending, contact the **WITS manager** to check whether the **approved system** has received the information.
- (2) If the **approved system** has not received the information, the **party** must resubmit the information.
- (3) This process must be repeated until the **WITS manager** has confirmed receipt of the information from the **party** in accordance with clause 13.228.

Compare: Electricity Governance Rules 2003 rule 13 section VI part G

Clause 13.229(1): replaced, on 5 October 2017, by clause 463(a) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 13.229(2) and (3): amended, on 5 October 2017, by clause 463(b) and (c) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### 13.230 Certification of information

- (1) Each **participant** that has submitted information in accordance with clause 13.225 in a particular year ending 31 March must, within 3 months of the end of the year ending 31 March, certify to the **Authority** that the information submitted was correct.
- (2) The certification provided under subclause (1) must be—
- (a) *[Revoked]*
  - (b) in the form specified by the **Authority**; and
  - (c) signed and dated by either—
    - (i) a director of the **participant**; or
    - (ii) the **participant's** chief financial officer, or person holding an equivalent position; or
    - (iii) the **participant's** chief executive officer, or person holding an equivalent position.

Compare: Electricity Governance Rules 2003 rule 14 section VI part G

Clause 13.230(1): replaced, on 5 October 2017, by clause 464(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 13.230(2): amended, on 5 October 2017, by clause 464(2)(a) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 13.230(2)(a): revoked, on 5 October 2017, by clause 464(2)(b) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 13.230(2)(c): replaced, on 5 October 2017, by clause 464(2)(c) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### 13.231 Audit of information

- (1) The **Authority** may, in its discretion, carry out an **audit** as to whether a **participant** has complied with this subpart.
- (2) If the **Authority** decides under subclause (1) that a **participant** should be subject to an **audit**, the **Authority** must first give written notice to the **participant** requiring the **participant** to nominate an appropriate **auditor**. The **participant** must provide that nomination in writing to the **Authority** within a reasonable timeframe. The **Authority** must appoint the **auditor** nominated by the **participant**. If the **participant** fails to nominate an appropriate **auditor** within a reasonable timeframe, the **Authority** may appoint an **auditor** of its own choice.
- (3) A **participant** subject to an **audit** under this clause must, on request from the **auditor**, provide the **auditor** with a copy of every **risk management contract** that it has entered into in the previous 12 months or within such other period specified by the **auditor**. The **participant** must provide this **audit** information no later than 20 **business days** after receiving a request from the **auditor** for the information.
- (4) The **participant** must ensure that the **auditor** provides the **Authority** with an **audit** report on the **participant's** compliance with this subpart that has been prepared in accordance with subclauses (4A) and (5).
- (4A) The **audit** report must include any comments from the **participant** on any non-compliance found by the **auditor** if the **participant** provided comments to the **auditor** within a time specified by the **auditor**.
- (5) The **audit** report must not contain any **risk management contract** that the **participant** has provided to the **auditor** in accordance with subclause (3), unless the **Authority** has specifically requested that the **auditor** do so.

Compare: Electricity Governance Rules 2003 rule 15 section VI part G

Clause 13.231(2): amended, on 5 October 2017, by clause 465 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 13.231(4): substituted, on 1 February 2016, by clause 86(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

Clause 13.231(4A): inserted, on 1 February 2016, by clause 86(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

Clause 13.231(5): amended, on 1 February 2016, by clause 86(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

### 13.232 Payment of costs relating to audits

- (1) If an **audit** establishes, to the reasonable satisfaction of the **Authority**, that a **participant** may not have complied with this subpart (whether or not the **Authority** appoints an investigator to investigate the alleged breach), the **participant** must pay for the **audit**.
- (2) If the **Authority** considers that the non-compliance of the **participant** is minor or relates to some (but not all) of the clauses in this subpart, the **Authority** may, in its discretion, make an assessment regarding the proportion of the costs of the **audit** that are to be paid by the **participant**, and those costs must be paid by the **participant**.
- (3) If an **audit** establishes to the reasonable satisfaction of the **Authority** that the **participant** has complied with this subpart, the **participant** is not required to pay any of the **auditor's** costs.

Compare: Electricity Governance Rules 2003 rule 16 section VI part G

### **13.233 WITS manager and Authority must not publish certain information and may use information only under this subpart**

- (1) The **Authority** must keep, and ensure that the **WITS manager** and each **auditor** appointed under clause 13.231(2) keep, information submitted to the **approved system** under clauses 13.219, or 13.222 to 13.224 and copies of any **risk management contract** provided to the **auditor** under clause 13.231 confidential, unless—
  - (a) the information is provided by the **Authority** to subcontractors or **service providers** that the **Authority** appoints to provide services for the purposes of this subpart, and those subcontractors or **service providers** have agreed to keep that information confidential, on the same terms as apply to the **Authority** under this clause; or
  - (b) the information is required to be disclosed by law; or
  - (c) the **party** or **parties** to whom the information relates have provided written consent to the disclosure; or
  - (d) any of the information in a **risk management contract** is made available in accordance with clause 13.226(1).
- (2) The **Authority** may use the information submitted under clause 13.222 and copies of a **risk management contract** provided to the **Authority** by an **auditor** appointed under clause 13.231(2) only for purposes related to this subpart and the enforcement of this subpart.

Compare: Electricity Governance Rules 2003 rule 17 section VI part G

Clause 13.233 Heading: amended, on 5 October 2017, by clause 466(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 13.233(1) and (2): amended, on 5 October 2017, by clause 466(2)(a) and (b) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### **13.234 No misleading information**

A **party** may not submit any information that, at the time the information was submitted, was misleading or deceptive or likely to mislead or deceive.

Compare: Electricity Governance Rules 2003 rule 18 section VI part G

### **13.235 Risk management contracts must be lawful**

A **party** may not submit information if that **party** knows or ought reasonably to know that the **risk management contract** to which that information applies would contravene any law.

Compare: Electricity Governance Rules 2003 rule 19 section VI part G

### **13.236 Availability of information**

The information that is submitted under clauses 13.219, 13.223, or 13.224 may only be removed from the **approved system** after 12 months following the termination of the **risk management contract**.

Compare: Electricity Governance Rules 2003 rule 20 section VI part G

Clause 13.236: amended, on 5 October 2017, by clause 467 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

## Subpart 5A—Spot price risk disclosure

Subpart 5A: inserted on 1 December 2011, by clause 5 of the Electricity Industry Participation Code (Spot Price Risk Disclosure) Amendment 2011.

### 13.236A Disclosing participants must prepare and submit spot price risk disclosure statements

- (1) Each **disclosing participant** must prepare a **spot price risk disclosure statement** for each quarter beginning 1 January, 1 April, 1 July, and 1 October in each year.
- (2) Each **participant** who will be a **disclosing participant** in the next quarter must prepare a **spot price risk disclosure statement** for that quarter in accordance with this subpart.
- (3) The **disclosing participant** must submit the **spot price risk disclosure statement** to the person appointed by the **Authority** to receive **spot price risk disclosure statements** no later than 5 **business days** before the beginning of the quarter to which the statement relates.
- (4) A **participant** is not required to comply with this clause for a quarter if it is a **disclosing participant** in relation to the quarter only because it is subject to a **wash-up** in that quarter.

Clause 13.236A: inserted on 1 December 2011, by clause 5 of the Electricity Industry Participation Code (Spot Price Risk Disclosure) Amendment 2011.

Clause 13.236A(1) and (2): amended, on 5 October 2017, by clause 468 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 13.236A(4): inserted, on 1 February 2016, by clause 87 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

### 13.236B Authority must appoint a person to receive and analyse spot price risk disclosure statements

- (1) The **Authority** must appoint an independent person to receive and analyse **spot price risk disclosure statements**.
- (2) The **Authority** must enter into a contract with the person appointed to receive and analyse **spot price risk disclosure statements**.
- (3) The contract with the person appointed to receive and analyse **spot price risk disclosure statements** must include the following:
  - (a) a requirement that the person does not disclose any **spot price risk disclosure statement** to any other person, including that it does not disclose any **spot price risk disclosure statement** to the **Authority**;
  - (b) a requirement that the person provide information regarding **spot price risk disclosure statements** to the **Authority** in a form that does not identify the **disclosing participant** to which it relates.

Clause 13.236B: inserted on 1 December 2011, by clause 5 of the Electricity Industry Participation Code (Spot Price Risk Disclosure) Amendment 2011.

### 13.236C Authority may approve consolidated spot price risk disclosure statements

On application by 1 or more **disclosing participants**, the **Authority** may approve those **disclosing participants** preparing and submitting a consolidated **spot price risk disclosure statement**.

Clause 13.236C: inserted on 1 December 2011, by clause 5 of the Electricity Industry Participation Code (Spot Price Risk Disclosure) Amendment 2011.

**13.236D Authority must publish base case, stress test, and method for calculating target cover ratio**

- (1) The **Authority** must **publish** a notice setting out the following:
  - (a) a **base case**;
  - (b) 1 or more **stress tests**;
  - (c) 1 or more methods for calculating a **disclosing participant's** target cover ratio.
- (2) If the **Authority** has not **published** a notice under subclause (1) at least 30 **business days** before the start of a quarter in respect of which a **spot price risk disclosure statement** is required to be prepared, a **disclosing participant** is not required to prepare or submit a **spot price risk disclosure statement** for the next quarter.
- (3) If the **Authority publishes** an amendment to a notice, or revokes and replaces a notice, within 30 **business days** before the start of a quarter in respect of which a **spot price risk disclosure statement** is required to be prepared, **disclosing participants** must prepare **spot price risk disclosure statements** for the immediately following quarter in accordance with the notice as in force immediately before the amendment or replacement was made and not in accordance with the notice as amended or replaced.

Clause 13.236D: inserted on 1 December 2011, by clause 5 of the Electricity Industry Participation Code (Spot Price Risk Disclosure) Amendment 2011.

Clause 13.236D Heading: amended, on 5 October 2017, by clause 469(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 13.236D: amended, on 5 October 2017, by clause 469(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

**13.236E Content of spot price risk disclosure statements**

- (1) A **spot price risk disclosure statement** submitted under this subpart must include the following:
  - (a) the **disclosing participant's** annual net cash flow from operating activities as set out in the **disclosing participant's** most recent set of audited annual financial statements;
  - (b) the **disclosing participant's** level of shareholders' equity as set out in the **disclosing participant's** most recent set of audited annual financial statements;
  - (c) the **disclosing participant's** estimate of the value of **electricity** that it expects to sell to the **clearing manager** during the period to which the **stress test** relates when the **stress test** is applied, minus the **disclosing participant's** estimate of the value of that **electricity** under the **base case** for that period;
  - (d) the **disclosing participant's** estimate of the value of **electricity** that it expects to purchase from the **clearing manager** during the period to which the **stress test** relates when the **stress test** is applied, minus the **disclosing participant's** estimate of the value of that **electricity** under the **base case** for that period;
  - (e) the **disclosing participant's** estimate of the projected net cash flows from operating activities of the **disclosing participant** during the period to which the **stress test** relates when the **stress test** is applied, minus the **disclosing participant's** estimate of those cash flows under the **base case** for that period;
  - (f) a statement as to whether the **disclosing participant** has an explicit risk management policy in respect of its exposure to the **wholesale market**:

- (g) if the **disclosing participant** has an explicit risk management policy, the **disclosing participant's** target cover ratio, for each **stress test**, calculated in accordance with the relevant method **published** by the **Authority** under clause 13.236D for the quarter to which the statement relates.
- (1A) Despite subclause (1), a **disclosing participant** is not required to include the information in subclause (1) in its **spot price risk disclosure statement** for a quarter if—
  - (a) the **disclosing participant** expects that a change in spot prices would not affect the **disclosing participant's** cash flow from operating activities in the quarter; and
  - (b) the **disclosing participant's spot price risk disclosure statement** for the quarter includes a statement that the **disclosing participant** expects that a change in spot prices would not affect the **disclosing participant's** cash flow from operating activities in the quarter.
- (2) For the purposes of subclause (1),—
  - (a) **electricity** is deemed to be sold to the **clearing manager** by a **disclosing participant** if it is sold to the **clearing manager** on the **disclosing participant's** behalf; and
  - (b) **electricity** is deemed to be purchased from the **clearing manager** by a **disclosing participant** if it is purchased from the **clearing manager** on the **disclosing participant's** behalf.
- (3) The **disclosing participant** must ensure that a **spot price risk disclosure statement** is signed and dated by a director, or the chief executive officer, or the chief financial officer, or a person holding a position equivalent to one of those positions, of the **disclosing participant** no earlier than 20 **business days** and no later than 5 **business days** before the beginning of the quarter to which the statement relates.
- (4) In preparing a **spot price risk disclosure statement**, a **disclosing participant** must have regard to all relevant factors, including (without limitation)—
  - (a) any financial instruments in which the **disclosing participant** has an interest; and
  - (b) any other measures that the **disclosing participant** has in effect to manage the risk arising from its exposure to the **wholesale market**; and
  - (c) any other arrangements that the **disclosing participant** has in place to manage that risk; and
  - (d) any amounts of **electricity** that the **disclosing participant** expects to buy from, or sell to, the **clearing manager**.

Clause 13.236E: inserted on 1 December 2011, by clause 5 of the Electricity Industry Participation Code (Spot Price Risk Disclosure) Amendment 2011.

Clause 13.236E(1)(g) and (3): amended, on 5 October 2017, by clause 470 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 13.236E(1A): inserted, on 6 November 2017, by clause 4 of the Electricity Industry Participation Code Amendment (Spot Price Risk Disclosure) 2017.

### 13.236F Certification of spot price risk disclosure statement

- (1) A **disclosing participant** who has submitted a **spot price risk disclosure statement** in accordance with this subpart must certify to the **Authority**—
  - (a) that the board of the **disclosing participant** has considered—



- (i) every **spot price risk disclosure statement** submitted under this subpart by the **disclosing participant** in the period to which the certification relates; and
    - (ii) the projected change in net cash flows from operating activities of the **disclosing participant** as a result of applying the **stress test** or **stress tests** that relate to each period to which each **spot price risk disclosure statement** relates; and
  - (b) that the **disclosing participant** has provided to each of the **disclosing participant's** customers who, in the period to which the certification relates, has entered into or renewed a contract with the **disclosing participant** that results in any **electricity** supplied to the customer being determined directly by reference to the **final price** at a **GXP**, information to enable the customer to consider the outcomes of applying the **stress test** or **stress tests** to the customer.
- (2) Each certification must be submitted as follows:
- (a) in the case of the first certification submitted by a **disclosing participant**, no later than the end of the fourth quarter following the quarter in which the first **spot price risk disclosure statement** is submitted by that **disclosing participant** (in which case the certification must relate to every **spot price risk disclosure statement** made by the **disclosing participant** in the preceding quarters);
  - (b) in the case of every subsequent certification, no later than the end of the fifth quarter following the quarter in which the last certification was submitted (in which case the certification must relate to every **spot price risk disclosure statement** made by the **disclosing participant** since the last certification was submitted).
- (3) Each certification submitted under subclause (2) must be—
- (a) in the form specified by the **Authority**; and
  - (b) signed and dated by a director of the **disclosing participant** and either—
    - (i) another director of the **disclosing participant**; or
    - (ii) the **disclosing participant's** chief executive officer, or person holding an equivalent position; or
    - (iii) the **disclosing participant's** chief financial officer, or person holding an equivalent position.

Clause 13.236F: inserted on 1 December 2011, by clause 5 of the Electricity Industry Participation Code (Spot Price Risk Disclosure) Amendment 2011.

Clause 13.236F(1): amended, on 5 October 2017, by clause 471(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 13.236F(2): amended, on 5 October 2017, by clause 471(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 13.236F(3): replaced, on 5 October 2017, by clause 471(3) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### **13.236G Authority may require disclosing participant to submit new spot price risk disclosure statement**

- (1) The **Authority** may, by notice in writing to a **disclosing participant** who submitted a **spot price risk disclosure statement**, require the **disclosing participant** to submit a new **spot price risk disclosure statement**.

- (2) If a **disclosing participant** receives a request from the **Authority** under subclause (1), the **disclosing participant** must submit a new **spot price risk disclosure statement** to the person appointed by the **Authority** to receive **spot price risk disclosure statements** within 10 **business days** after the date on which the **disclosing participant** received the request.
- (3) Clause 13.236E applies to a **spot price risk disclosure statement** submitted under this clause.
- Clause 13.236G: inserted on 1 December 2011, by clause 5 of the Electricity Industry Participation Code (Spot Price Risk Disclosure) Amendment 2011.
- Clause 13.236G(2): amended, on 5 October 2017, by clause 472 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

#### **13.236H Authority may require independent audit of spot price risk disclosure statement or certification**

- (1) The **Authority** may, in its discretion, on the recommendation of the person appointed to receive and analyse **spot price risk disclosure statements** or on its own motion, require an **audit** of 1 or more of the following:
- (a) a **spot price risk disclosure statement**:
  - (b) part of a **spot price risk disclosure statement**:
  - (c) the information set out in the certification given under clause 13.236F.
- (2) If the **Authority** requires an **audit** under subclause (1), the **Authority** must require the relevant **disclosing participant** to nominate an appropriate **auditor**.
- (3) The **disclosing participant** must provide that nomination within a reasonable timeframe.
- (4) The **Authority** may direct the **disclosing participant** to appoint the **auditor** nominated by the **disclosing participant**.
- (5) If the **disclosing participant** fails to nominate an appropriate **auditor** within 5 **business days**, the **Authority** may direct the **disclosing participant** to appoint an **auditor** of the **Authority's** choice.
- (6) The **disclosing participant** must appoint an **auditor** in accordance with a direction made under subsection (4) or subsection (5).
- (7) A **disclosing participant** subject to an **audit** under this clause must, on request from the **auditor**, provide the **auditor** with such information as the **auditor** reasonably requires in order to **audit** the **spot price risk disclosure statement** or the information set out in the certification given under clause 13.236F (as the case may be).
- (8) The **disclosing participant** must provide the information no later than 10 **business days** after receiving a request from the **auditor** for the information.
- (9) The **disclosing participant** must ensure that the **auditor** produces an **audit** report on the **spot price risk disclosure statement** or the information set out in the certification given under clause 13.236F (as the case may be) and submits the **audit** report to the **Authority**.
- (10) Before the **audit** report is submitted to the **Authority**, any failure of the **spot price risk disclosure statement** or the information set out in the certification given under clause 13.236F (as the case may be) to comply with this subpart must be referred back to the **disclosing participant** for comment.

- (11) The comments of the **disclosing participant** must be included in the **audit** report.
- (12) The **disclosing participant** may require that the **auditor** does not provide the **Authority** with a copy of any information that the **disclosing participant** has provided to the **auditor** in accordance with subclause (7).

Clause 13.236H Heading: amended, on 5 October 2017, by clause 473(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 13.236H: inserted on 1 December 2011, by clause 5 of the Electricity Industry Participation Code (Spot Price Risk Disclosure) Amendment 2011.

Clause 13.236H(1), (5), (7), (8), (9) and (10): amended, on 5 October 2017, by clause 473(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### 13.236I Payment of auditor's costs

- (1) If an **audit** establishes, to the **Authority's** reasonable satisfaction, that a **disclosing participant's spot price risk disclosure statement** or the information set out in the certification given under clause 13.236F (as the case may be) has not complied with this subpart (whether or not the **Authority** appoints an investigator to investigate the alleged breach), the **disclosing participant** must pay the **auditor's** costs.
- (2) If the **Authority** considers that the **disclosing participant's** non-compliance is minor, the **Authority** may, in its discretion, determine the proportion of the **auditor's** costs that the **disclosing participant** must pay, and the **disclosing participant** must pay those costs.
- (3) If an **audit** establishes to the **Authority's** reasonable satisfaction that a **disclosing participant's spot price risk disclosure statement** or the information set out in the certification given under clause 13.236F (as the case may be) has complied with this subpart, the **Authority** must pay the **auditor's** costs.

Clause 13.236I: inserted on 1 December 2011, by clause 5 of the Electricity Industry Participation Code (Spot Price Risk Disclosure) Amendment 2011.

Clause 13.236I(1) and (3): amended, on 5 October 2017, by clause 474 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 13.236I(3): amended, on 21 September 2012, by clause 31 of the Electricity Industry Participation (Minor Amendments) Code Amendment 2012.

## Subpart 6—Financial transmission rights

Heading: inserted, on 1 October 2011, by clause 8 of the Electricity Industry Participation (Financial Transmission Rights) Code Amendment 2011.

### 13.237 Contents of this subpart

This subpart provides for the processes by which—

- (a) the **FTR manager** prepares and **publishes** the **FTR allocation plan**; and
- (b) the **Authority** approves the **FTR allocation plan**; and
- (c) the **FTR manager** allocates and creates **FTRs**; and
- (d) the **FTR manager** operates the **FTR register** and collects information from the **grid owner** and **clearing manager**; and
- (e) **FTRs** may be assigned; and
- (f) the **clearing manager** collects and allocates **FTR auction** revenue and collects information from the **FTR manager**; and
- (g) the **Authority** may direct the **FTR manager** to suspend the allocation of **FTRs**.

Clause 13.237: inserted, on 1 October 2011, by clause 8 of the Electricity Industry Participation (Financial Transmission Rights) Code Amendment 2011.

Clause 13.237(c): amended, on 1 November 2014, by clause 5 of the Electricity Industry Participation (FTR Reconfiguration Auctions) Code Amendment 2014.

#### *FTR allocation plan*

Heading: inserted, on 1 October 2011, by clause 8 of the Electricity Industry Participation (Financial Transmission Rights) Code Amendment 2011.

### **13.238 Preparation and publication of FTR allocation plan**

- (1) The **FTR manager** must prepare and **publish** an **FTR allocation plan** that complies with Schedule 13.5.
- (2) The **FTR manager** must keep the **FTR allocation plan published** at all times.
- (3) Subject to subclause (4), if Schedule 13.5 is amended, the **FTR manager** must, no later than 3 months after the date on which the amendment comes into force, submit to the **Authority** for approval under clause 13.241(4), a variation to the **FTR allocation plan** to make the **FTR allocation plan** consistent with Schedule 13.5.
- (4) The **FTR manager** is not required to comply with subclause (3) if no amendment is necessary to make the **FTR allocation plan** consistent with Schedule 13.5.

Clause 13.238: inserted, on 1 October 2011, by clause 8 of the Electricity Industry Participation (Financial Transmission Rights) Code Amendment 2011.

Clause 13.238(2): replaced, on 5 October 2017, by clause 475 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### **13.239 FTR manager gives draft FTR allocation plan to Authority**

- (1) The **FTR manager** must submit to the **Authority** for approval a draft **FTR allocation plan** by the date specified in the **market operation service provider agreement** between the **FTR manager** and the **Authority**.
- (2) In preparing the draft **FTR allocation plan**, the **FTR manager** must—
  - (a) consult with persons that the **FTR manager** thinks are representative of the interests of persons likely to be substantially affected by the plan; and
  - (b) consider submissions made on the plan.
- (3) The **FTR manager** must provide a copy of each submission received under subclause (2) to the **Authority**.

Clause 13.239: inserted, on 1 October 2011, by clause 8 of the Electricity Industry Participation (Financial Transmission Rights) Code Amendment 2011.

### **13.240 Authority approves FTR allocation plan**

- (1) The **Authority** must, as soon as practicable after receiving the draft **FTR allocation plan**, by notice in writing to the **FTR manager**—
  - (a) approve the plan; or
  - (b) decline to approve the plan.
- (2) If the **Authority** declines to approve the draft **FTR allocation plan**, the **Authority** must **publish** the changes that the **Authority** wishes the **FTR manager** to make to the draft plan.
- (3) When the **Authority publishes** the changes that the **Authority** wishes the **FTR manager** to make to the draft **FTR allocation plan** under subclause (2), the **Authority** must give written notice to the **FTR manager** and interested parties of the date by which submissions on the changes must be received by the **Authority**.

- (4) Each submission on the changes to the draft **FTR allocation plan** must be made in writing to the **Authority** and be received on or before the date specified by the **Authority** under subclause (3).
- (5) The **Authority** must—
  - (a) provide a copy of each submission received to the **FTR manager**; and
  - (b) **publish** the submissions.
- (6) The **FTR manager** may make its own submission on the changes to the draft **FTR allocation plan** and the submissions received in relation to the changes. The **Authority** must **publish** the **FTR manager's** submission when it is received.
- (7) The **Authority** must consider the submissions made to it on the changes to the draft **FTR allocation plan**.
- (8) Following the consultation required by subclauses (3) to (7), the **Authority** may approve the **FTR allocation plan** subject to the changes that the **Authority** considers appropriate being made by the **FTR manager**.

Clause 13.240: inserted, on 1 October 2011, by clause 8 of the Electricity Industry Participation (Financial Transmission Rights) Code Amendment 2011.

Clause 13.240(3): amended, on 5 October 2017, by clause 476 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

#### 13.241 Variations to FTR allocation plan

- (1) A **participant** or the **Authority** may submit a proposal for a variation to the **FTR allocation plan** to the **FTR manager**.
- (2) The **FTR manager** must provide a copy of each proposed variation received from a **participant** under subclause (1) to the **Authority**.
- (3) The **FTR manager** must consider a proposed variation to the **FTR allocation plan** submitted under subclause (1).
- (4) The **FTR manager** may submit a request for a variation to the **FTR allocation plan** to the **Authority**.
- (5) The consultation and approval requirements under clause 13.239(2) and (3) and clause 13.240 apply to a request for a variation submitted under subclause (4) as if references to the draft plan were a reference to the requested variation.
- (6) If the **FTR manager** does not submit a request for a variation submitted under subclause (1) to the **Authority** under subclause (4), the **Authority** may consider the proposal and require the **FTR manager** to submit a request for a variation based on the proposal to the **Authority**, and subclause (5) applies accordingly.
- (7) The **Authority** may approve a variation requested under subclause (4) or subclause (6) without complying with the provisions referred to in subclause (5) if—
  - (a) the **Authority** considers that it is necessary or desirable in the public interest that the requested variation be made urgently; and
  - (b) the **Authority publishes** a notice of the variation and a statement of the reasons why the urgent variation is needed.
- (8) Every variation made under subclause (7) expires on the date that is 9 months after the date on which the variation is made.

Clause 13.241: inserted, on 1 October 2011, by clause 8 of the Electricity Industry Participation (Financial Transmission Rights) Code Amendment 2011.

*Allocation, creation and reconfiguration of FTRs*

Heading: inserted, on 1 October 2011, by clause 8 of the Electricity Industry Participation (Financial Transmission Rights) Code Amendment 2011.

Heading: amended, on 1 November 2014, by clause 6 of the Electricity Industry Participation (FTR Reconfiguration Auctions) Code Amendment 2014.

**13.242 FTR manager must allocate and create FTRs**

- (1) The **FTR manager** must conduct an **FTR auction** in accordance with the **FTR allocation plan** approved under clause 13.240 to—
  - (a) allocate **FTRs**; and
  - (b) create **FTRs**; and
  - (c) reconfigure **FTRs**.
- (2) Every **FTR** must relate to—
  - (a) a minimum amount of **electricity** (in **MW**) of 0.1 **MW**; and
  - (b) an amount of **electricity** (in **MW**) that is a multiple of 0.1**MW**.

Clause 13.242: inserted, on 1 October 2011, by clause 8 of the Electricity Industry Participation (Financial Transmission Rights) Code Amendment 2011.

Clause 13.242(2): substituted, on 1 June 2012, by clause 4 of the Electricity Industry Participation (Removal of Quantity Limit for Financial Transmission Rights) Code Amendment 2012.

Clause 13.242 heading: amended, on 1 November 2014, by clause 7(a) of the Electricity Industry Participation (FTR Reconfiguration Auctions) Code Amendment 2014.

Clause 13.242(1): amended, on 1 November 2014, by clause 7(b) of the Electricity Industry Participation (FTR Reconfiguration Auctions) Code Amendment 2014.

**13.242A FTR manager to adjust offered FTR and FTR acquisition cost after FTR reconfiguration auction**

After each **FTR reconfiguration auction**, the **FTR manager** must—

- (a) reduce the amount of **electricity** (in **MW**) to which each **offered FTR** relates by the amount of **electricity** (in **MW**) to which the relevant **reconfigured FTR** relates; and
- (b) adjust the **FTR acquisition cost** of the **offered FTR** by subtracting the **FTR reconfiguration amount** of the relevant **reconfigured FTR** from the **FTR acquisition cost** of the **offered FTR**.

Clause 13.242A: inserted, on 1 November 2014, by clause 8 of the Electricity Industry Participation (FTR Reconfiguration Auctions) Code Amendment 2014.

**13.243 Participation in FTR auction**

The **FTR manager** must not allow a person to participate in an **FTR auction** unless the **FTR manager** is satisfied that the person complies with prudential requirements in Part 14A.

Clause 13.243: inserted, on 1 October 2011, by clause 8 of the Electricity Industry Participation (Financial Transmission Rights) Code Amendment 2011.

Clause 13.243: amended, on 24 March 2015, by clause 14 of the Electricity Industry Participation (Settlement and Prudential Security) Code Amendment 2013.

**13.244 Acceptance of bids and offers in FTR auction**

- (1) The **FTR manager** must not accept a bid or an offer in an **FTR auction** if the **FTR manager** considers that the bid or the offer, if accepted, would cause the person making

the bid or the offer to incur an obligation for which it does not have sufficient acceptable security under Part 14A.

- (2) For the purposes of subclause (1), the **FTR manager** must, based on information received from the **clearing manager**, determine the maximum liability that each person can incur in respect of its bids or offers in the **FTR auction**.

Clause 13.244: inserted, on 1 October 2011, by clause 8 of the Electricity Industry Participation (Financial Transmission Rights) Code Amendment 2011.

Clause 13.244 heading: amended, on 1 November 2014, by clause 9(a) of the Electricity Industry Participation (FTR Reconfiguration Auctions) Code Amendment 2014.

Clause 13.244(1): amended, on 1 November 2014, by clause 9(b) and (c) of the Electricity Industry Participation (FTR Reconfiguration Auctions) Code Amendment 2014.

Clause 13.244(1): amended, on 24 March 2015, by clause 15 of the Electricity Industry Participation (Settlement and Prudential Security) Code Amendment 2013.

Clause 13.244(2): amended, on 1 November 2014, by clause 9(d) of the Electricity Industry Participation (FTR Reconfiguration Auctions) Code Amendment 2014.

#### *Auction revenue and FTR receipts and payments*

Heading: inserted, on 1 October 2011, by clause 8 of the Electricity Industry Participation (Financial Transmission Rights) Code Amendment 2011.

### **13.245 Clearing manager must collect and allocate auction revenue**

The **clearing manager** must collect the **FTR auction** revenue and allocate it in accordance with Part 14.

Clause 13.245: inserted, on 1 October 2011, by clause 8 of the Electricity Industry Participation (Financial Transmission Rights) Code Amendment 2011.

### **13.246 Clearing manager must deal with FTR receipts and payments**

The **clearing manager** must deal with all receipts and payments in respect of **FTRs** in accordance with Part 14.

Clause 13.246: inserted, on 1 October 2011, by clause 8 of the Electricity Industry Participation (Financial Transmission Rights) Code Amendment 2011.

#### *FTR register*

Heading: inserted, on 1 October 2011, by clause 8 of the Electricity Industry Participation (Financial Transmission Rights) Code Amendment 2011.

### **13.247 FTR manager must operate FTR register**

- (1) The **FTR manager** must create and operate an **FTR register** that records—
- (a) the holdings of **FTRs**; and
  - (b) the **FTR acquisition cost** for each **FTR**; and
  - (c) assignments of **FTRs** including any price disclosed under clause 13.249; and
  - (d) the amount of **electricity** (in **MW**) to which each **FTR** relates; and
  - (e) the reconfiguration of each **offered FTR**.
- (2) The **FTR register** must contain an account for each holder of an **FTR**.
- (3) The **FTR manager** must assign a registered number to each **FTR** recorded in the **FTR register**.
- (4) The **FTR manager** must maintain, **publish**, and keep **published** at all times, an up to date copy of the **FTR register**.

Clause 13.247: inserted, on 1 October 2011, by clause 8 of the Electricity Industry Participation (Financial Transmission Rights) Code Amendment 2011.

Clause 13.247(1)(d): inserted, on 1 June 2012, by clause 5 of the Electricity Industry Participation (Removal of Quantity Limit for Financial Transmission Rights) Code Amendment 2012.

Clause 13.247(1)(b): amended, on 1 November 2012, by clause 5 of the Electricity Industry Participation (Financial Transmission Rights) Code Amendment 2012.

Clause 13.247(1)(e): inserted, on 1 November 2014, by clause 10 of the Electricity Industry Participation (FTR Reconfiguration Auctions) Code Amendment 2014.

Clause 13.247(4): replaced, on 5 October 2017, by clause 477 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### *Assignment of FTRs*

Heading: inserted, on 1 October 2011, by clause 8 of the Electricity Industry Participation (Financial Transmission Rights) Code Amendment 2011.

#### **13.248 Assignment of FTRs**

- (1) If a person ("assignor") wishes to assign an **FTR** or part of an **FTR** to another person ("assignee"), the assignor and assignee must complete and sign Form 1 in Schedule 13.6 and provide it to the **FTR manager**.
- (2) The completed form may be provided to the **FTR manager** under subclause (1) in electronic form if—
  - (a) both the assignor and assignee consent to completing and signing the form electronically; and
  - (b) the electronic form contains all of the information required by Form 1 in Schedule 13.6; and
  - (c) the notification of assignment to the **FTR manager** is in a format specified by the **FTR manager**.
- (3) The **FTR manager** must not register an assignment in the **FTR register** unless the **FTR manager** is satisfied that the assignee complies with prudential requirements in Part 14A.
- (4) The **FTR manager**, on being satisfied that all requirements for an assignment are met, must register the assignment on the **FTR register**.
- (4A) If an assignment is made under this clause in respect of part of an **FTR**, the **FTR manager** must register the assignment as follows:
  - (a) create a new record for an **FTR** in respect of the amount of **electricity** (in MW) to which the assignment relates; and
  - (b) amend the record for the **FTR** retained by the assignor by reducing the amount of **electricity** (in MW) to which the **FTR** relates so as to reflect the assignment.
- (5) An assignment of an **FTR** or part of an **FTR** is not effective unless it is registered on the **FTR register** by the **FTR manager**.
- (6) The **FTR manager** must not register an assignment that is expressed to have effect after the end of the **billing period** to which the **FTR** relates.

Clause 13.248: inserted, on 1 October 2011, by clause 8 of the Electricity Industry Participation (Financial Transmission Rights) Code Amendment 2011.

Clause 13.248(1): amended, on 1 June 2012, by clause 6(1) of the Electricity Industry Participation (Removal of Quantity Limit for Financial Transmission Rights) Code Amendment 2012.

Clause 13.248(2): amended, on 5 October 2017, by clause 478 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 13.248(3): amended, on 24 March 2015, by clause 16 of the Electricity Industry Participation (Settlement and Prudential Security) Code Amendment 2013.

Clause 13.248(4A): inserted, on 1 June 2012, by clause 6(2) of the Electricity Industry Participation (Removal of Quantity Limit for Financial Transmission Rights) Code Amendment 2012.



Clause 13.248(5): amended, on 1 June 2012, by clause 6(3) of the Electricity Industry Participation (Removal of Quantity Limit for Financial Transmission Rights) Code Amendment 2012.

### 13.249 Liability for FTR acquisition cost when FTR assigned and price disclosed

- (1) This clause applies if—
  - (a) an **FTR** is assigned under clause 13.248; and
  - (b) the notification of assignment discloses the price (being an amount that may be positive or negative) at which the **FTR** has been assigned.
- (2) The **FTR manager** must provide a copy of the notification of assignment to the **clearing manager**.
- (3) The assignee owes the **clearing manager** the amount disclosed under subclause (1)(b) when it becomes due on settlement of the **FTR**.
- (4) If the price disclosed in the notification is less than the **FTR acquisition cost** in respect of the **FTR** that would, if the assignment had not taken place, become owing on settlement of the **FTR**, the assignor owes the **clearing manager** an amount equal to the difference between the **FTR acquisition cost** and the price at which the **FTR** has been assigned.
- (5) The **clearing manager** must advise the assignor of the amount owing under subclause (4) when the **clearing manager** advises amounts owing under subpart 4 of Part 14 for the **billing period** in which the assignment took place.
- (6) The **clearing manager** must apply any amount owing by a **participant** to the **clearing manager** under this clause to the settlement of **FTRs**, but an amount must not be applied to the settlement of an **FTR** until the **billing period** in which the **FTR** is settled.
- (7) If the price disclosed in the notification is more than the **FTR acquisition cost** in respect of the **FTR** that would, if the assignment had not taken place, become owing on settlement of the **FTR**, the **clearing manager** owes the assignor on settlement of the **FTR** an amount equal to the difference between the price at which the **FTR** has been assigned and the **FTR acquisition cost**.

Clause 13.249: inserted, on 1 October 2011, by clause 8 of the Electricity Industry Participation (Financial Transmission Rights) Code Amendment 2011.

Clause 13.249 Heading: amended, on 1 November 2012, by clause 6(1) of the Electricity Industry Participation (Financial Transmission Rights) Code Amendment 2012.

Clause 13.249(1)(b): amended, on 1 November 2012, by clause 6(2) of the Electricity Industry Participation (Financial Transmission Rights) Code Amendment 2012.

Clause 13.249(3): amended, on 24 March 2015, by clause 17(a) of the Electricity Industry Participation (Settlement and Prudential Security) Code Amendment 2013.

Clause 13.249(4): amended, on 1 November 2012, by clause 6(3) of the Electricity Industry Participation (Financial Transmission Rights) Code Amendment 2012.

Clause 13.249(4): amended, on 24 March 2015, by clause 17(b) of the Electricity Industry Participation (Settlement and Prudential Security) Code Amendment 2013.

Clause 13.249(5): amended, on 24 March 2015, by clause 17(c) of the Electricity Industry Participation (Settlement and Prudential Security) Code Amendment 2013.

Clause 13.249(6): substituted, on 24 March 2015, by clause 17(d) of the Electricity Industry Participation (Settlement and Prudential Security) Code Amendment 2013.

Clause 13.249(7): amended, on 1 November 2012, by clause 6(4) of the Electricity Industry Participation (Financial Transmission Rights) Code Amendment 2012.

Clause 13.249(7): amended, on 24 March 2015, by clause 17(e) of the Electricity Industry Participation (Settlement and Prudential Security) Code Amendment 2013.

### 13.250 Liability for FTR acquisition cost when FTR assigned and price not disclosed

- (1) This clause applies if—

- (a) an **FTR** is assigned under clause 13.248; and
- (b) the notification of assignment does not disclose the price at which the **FTR** has been assigned.
- (2) The **FTR manager** must provide a copy of the notification of assignment to the **clearing manager**.
- (3) The assignee owes the **clearing manager** the **FTR acquisition cost** in respect of the **FTR** that has been assigned when it becomes due on settlement of the **FTR**.  
Clause 13.250: inserted, on 1 October 2011, by clause 8 of the Electricity Industry Participation (Financial Transmission Rights) Code Amendment 2011.  
Clause 13.250 Heading: amended, on 1 November 2012, by clause 7(1) of the Electricity Industry Participation (Financial Transmission Rights) Code Amendment 2012.  
Clause 13.250(3): amended, on 1 November 2012, by clause 7(2) of the Electricity Industry Participation (Financial Transmission Rights) Code Amendment 2012.  
Clause 13.250(3): amended, on 24 March 2015, by clause 18 of the Electricity Industry Participation (Settlement and Prudential Security) Code Amendment 2013.

*Provision of information to the FTR manager and clearing manager*

Heading: inserted, on 1 October 2011, by clause 8 of the Electricity Industry Participation (Financial Transmission Rights) Code Amendment 2011.

**13.251 Information to be provided to FTR manager**

- (1) Each **grid owner** must provide a written forecast of the configuration and capacity of the **grid owner's grid** for the **FTR period** (as advised to each **grid owner** by the **FTR manager**) to the **FTR manager** for use in determining the **FTRs** to be offered in each **FTR auction**.
- (2) The information that each **grid owner** must provide must include relevant planned outages.
- (3) Except as otherwise agreed with the **FTR manager**, each **grid owner** must provide the information to the **FTR manager** no later than 1 month before the date (as advised to each **grid owner** by the **FTR manager**) on which an **FTR auction** is to be held.
- (4) The **clearing manager** must advise the **FTR manager** in writing—
  - (a) whether a person who has applied to participate in an **FTR auction** complies with prudential requirements in Part 14A; and
  - (b) the amount of security that a person who has applied to participate in an **FTR auction** has provided that exceeds that person's other obligations under Parts 14 and 14A.
- (5) Except as otherwise agreed with the **FTR manager**, the **clearing manager** must provide the information to the **FTR manager** no later than 2 **business days** before the date (as advised to the **clearing manager** by the **FTR manager**) on which an **FTR auction** is to be held.
- (6) If the information referred to in subclause (4) changes, the **clearing manager** must, if requested by the person who has applied to participate in an **FTR auction**, provide the updated information in writing to the **FTR manager**.
- (7) The **clearing manager** must inform the **FTR manager** in writing, as soon as practicable after receiving a request from the **FTR manager**, whether an assignee of an **FTR** meets the prudential security requirements in Part 14A.

Clause 13.251: inserted, on 1 October 2011, by clause 8 of the Electricity Industry Participation (Financial Transmission Rights) Code Amendment 2011.

Clause 13.251(1), (4), (6) and (7): amended, on 5 October 2017, by clause 479 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 13.251(4): amended, on 24 March 2015, by clause 19(a) of the Electricity Industry Participation (Settlement and Prudential Security) Code Amendment 2013.

Clause 13.251(7): amended, on 24 March 2015, by clause 19(b) of the Electricity Industry Participation (Settlement and Prudential Security) Code Amendment 2013.

### **13.252 Information to be provided to clearing manager**

(1) The **FTR manager** must provide the following information to the **clearing manager** in writing in relation to each successful bidder in an **FTR auction**:

- (a) the details of each **FTR** allocated under an **FTR auction**, including—
  - (i) the period to which the **FTR** applies; and
  - (ii) whether the **FTR** is an **option FTR** or an **obligation FTR**; and
  - (iii) the formula under which the **FTR hedge value** is to be calculated for the settlement of the **FTR**;
- (b) the **FTR acquisition cost** in respect of each **FTR**.

(2) The **FTR manager** must provide the information specified in subclause (1) to the **clearing manager** as soon as practicable and no later than 1 week after each **FTR auction**.

Clause 13.252: inserted, on 1 October 2011, by clause 8 of the Electricity Industry Participation (Financial Transmission Rights) Code Amendment 2011.

Clause 13.252(1): amended, on 1 November 2012, by clause 8 of the Electricity Industry Participation (Financial Transmission Rights) Code Amendment 2012.

Clause 13.252(1): amended, on 5 October 2017, by clause 480 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### **13.253 [Revoked]**

Clause 13.253: inserted, on 1 October 2011, by clause 8 of the Electricity Industry Participation (Financial Transmission Rights) Code Amendment 2011.

Clause 13.253: revoked, on 5 October 2017, by clause 481 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### **13.254 Publication of results of FTR auctions**

The **FTR manager** must, as soon as practicable after each **FTR auction**, **publish** and keep **published** the results of each **FTR auction** in accordance with the **FTR allocation plan**.

Clause 13.254: inserted, on 1 October 2011, by clause 8 of the Electricity Industry Participation (Financial Transmission Rights) Code Amendment 2011.

Clause 13.254: amended, on 5 October 2017, by clause 482 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

#### *Suspension of FTR allocation*

Heading: inserted, on 1 October 2011, by clause 8 of the Electricity Industry Participation (Financial Transmission Rights) Code Amendment 2011.

### **13.255 Authority may direct FTR manager to suspend allocation of FTRs**

The **Authority** may direct the **FTR manager** to suspend the allocation of **FTRs** if there is any situation that—

- (a) threatens, or may threaten, confidence in, or the integrity of, the allocation or settlement of **FTRs**; and
- (b) in the reasonable opinion of the **Authority**, cannot satisfactorily be resolved by any other mechanism available under this Code.

**Electricity Industry Participation Code 2010**  
**Part 13**

---

Clause 13.255: inserted, on 1 October 2011, by clause 8 of the Electricity Industry Participation (Financial Transmission Rights) Code Amendment 2011.

Clause 13.255: amended, on 18 July 2013, by clause 9(1) of the Electricity Industry Participation (Undesirable Trading Situation) Code Amendment 2013.

Clause 13.255(a): substituted, on 18 July 2013, by clause 9(2) of the Electricity Industry Participation (Undesirable Trading Situation) Code Amendment 2013.

Clause 13.255(b): amended, on 18 July 2013, by clause 9(3) of the Electricity Industry Participation (Undesirable Trading Situation) Code Amendment 2013.

---

**Schedule 13.1**  
**Forms 1 to 9**

cls 13.9, 13.13, 13.38, 13.64, and 13.170

**Form 1**  
**Generator offer**

Date: \_\_\_\_\_

Generator Participant Identifier: \_\_\_\_\_

Generator Name: \_\_\_\_\_

Grid Injection Point: \_\_\_\_\_

Generator Category (clause 13.10 of the Code): ☐ Unit ☐ Station

☐ Generator block (clauses 13.60 and 13.61 of the Code)

Block Name (if applicable): \_\_\_\_\_

Generator Maximum Output (including overload): \_\_\_\_\_ **MW**

Trading Period: \_\_\_\_\_ Starting at \_\_\_\_\_ : \_\_\_\_\_ 0 hours

Maximum Generator Ramp Up Rate: \_\_\_\_\_ **MW/hr**

Maximum Generator Ramp Down Rate: \_\_\_\_\_ **MW/hr**

**Offer to sell electricity**

Band 1: **From 0 MW to** \_\_\_\_\_ **MW @ \$** \_\_\_\_\_ **per MWh**

Band 2: **plus** \_\_\_\_\_ **MW @ \$** \_\_\_\_\_ **per MWh**

Band 3: **plus** \_\_\_\_\_ **MW @ \$** \_\_\_\_\_ **per MWh**

Band 4: **plus** \_\_\_\_\_ **MW @ \$** \_\_\_\_\_ **per MWh**

Band 5: **plus** \_\_\_\_\_ **MW @ \$** \_\_\_\_\_ **per MWh**

Compare: Electricity Governance Rules 2003 form 1 schedule G1 part G  
Schedule 13.1, Form 1: amended, on 27 May 2015, by clause 14 of the Electricity Industry Participation Code Amendment (Industrial Co-generation Dispatch Arrangements) 2015.

**Form 2**  
**Intermittent Generator Offer**

Date: \_\_\_\_\_

Intermittent Generator Participant  
Identifier: \_\_\_\_\_

Intermittent Generator Name: \_\_\_\_\_

Grid Injection Point: \_\_\_\_\_

Generator category (clause 13.10 of the Code): ☐ Station

Generator Installed Capacity: \_\_\_\_\_ **MW**

Trading Period: \_\_\_\_\_ Starting at \_\_\_\_\_ : \_\_\_\_\_ 0 hours

Maximum Generator Ramp Up Rate: \_\_\_\_\_ **MW/hr**

Maximum Generator Ramp Down Rate: \_\_\_\_\_ **MW/hr**

**Offer to sell electricity**

Band 1: **From 0 MW to \_\_\_\_\_ MW @ \$ \_\_\_\_\_ per MWh**

Compare: Electricity Governance Rules 2003 form 2 schedule G1 part G  
Schedule 13.1, Form 2: amended, on 27 May 2015, by clause 15 of the Electricity Industry Participation Code Amendment  
(Industrial Co-generation Dispatch Arrangements) 2015.

---

**Form 3**  
**Type A or Type B Co-generator Offer**

Date: \_\_\_\_\_

Type A/Type B Co-generator  
Participant Identifier: \_\_\_\_\_

Type A/Type B Co-generator  
Name: \_\_\_\_\_

Grid Injection Point: \_\_\_\_\_

Generator Category (clause 13.10 of the Code):      ☐ Unit                      ☐ Station

Type A/Type B Co-generator Maximum Output (including overload):  
\_\_\_\_\_ MW

Trading Period: \_\_\_\_\_ Starting at \_\_\_\_\_ : \_\_\_\_\_ 0 hours

Maximum Generator Ramp Up Rate:  
\_\_\_\_\_ MW/hr

Maximum Generator Ramp Down Rate:  
\_\_\_\_\_ MW/hr

**Offer to sell electricity**

Band 1:              **From 0 MW to \_\_\_\_\_ MW @ \$ \_\_\_\_\_ per MWh**

Band 2:              **plus \_\_\_\_\_ MW @ \$ \_\_\_\_\_ per MWh**

Compare: Electricity Governance Rules 2003 form 2A schedule G1 part G  
Schedule 13.1, Form 3 heading: amended, on 27 May 2015, by clause 16(1) of the Electricity Industry Participation Code Amendment (Industrial Co-generation Dispatch Arrangements) 2015.  
Schedule 13.1, Form 3: amended, on 27 May 2015, by clause 16(2) of the Electricity Industry Participation Code Amendment (Industrial Co-generation Dispatch Arrangements) 2015.

---

**Form 4**

**Purchaser's nominated bid for electricity**

Date: \_\_\_\_\_

Purchaser: \_\_\_\_\_

Grid Exit Point: \_\_\_\_\_

Trading Period: \_\_\_\_\_ starting at \_\_\_\_\_ : \_\_\_\_\_ 0 hours

Type of bid:      Nominated dispatch bid                      ☐

                         Nominated non-dispatch bid                      ☐

Dispatch-capable load station identifier (if applicable): \_\_\_\_\_

**Nominated bid to buy electricity**

Band 1: **From 0 MW to** \_\_\_\_\_ **MW below \$** \_\_\_\_\_ **per MWh**

Band 2: **plus** \_\_\_\_\_ **MW below \$** \_\_\_\_\_ **per MWh**

Band 3: **plus** \_\_\_\_\_ **MW below \$** \_\_\_\_\_ **per MWh**

Band 4: **plus** \_\_\_\_\_ **MW below \$** \_\_\_\_\_ **per MWh**

Band 5: **plus** \_\_\_\_\_ **MW below \$** \_\_\_\_\_ **per MWh**

Band 6: **plus** \_\_\_\_\_ **MW below \$** \_\_\_\_\_ **per MWh**

Band 7: **plus** \_\_\_\_\_ **MW below \$** \_\_\_\_\_ **per MWh**

Band 8: **plus** \_\_\_\_\_ **MW below \$** \_\_\_\_\_ **per MWh**

Band 9: **plus** \_\_\_\_\_ **MW below \$** \_\_\_\_\_ **per MWh**

Band 10: **plus** \_\_\_\_\_ **MW below \$** \_\_\_\_\_ **per MWh**

Compare: Electricity Governance Rules 2003 form 3 schedule G1 part G  
Schedule 13.1 Form 4: amended, on 28 June 2012, by clause 51 of the Electricity Industry Participation (Demand-side Bidding and Forecasting) Code Amendment 2011.  
Schedule 13.1 Form 4: substituted, on 15 May 2014, by clause 68 of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.



---

**Form 4A**  
**Purchaser's difference bid for electricity**

Date:

\_\_\_\_\_

Purchaser:

\_\_\_\_\_

Grid Exit Point:

\_\_\_\_\_

Trading Period: \_\_\_\_\_ starting at \_\_\_\_\_ : \_\_\_\_\_ 0 hours

**Difference bid to increase/ decrease use of electricity**

**Increase electricity**

Band 1: **Increase** \_\_\_\_\_ MW below \$ \_\_\_\_\_ per MWh

Band 2: **plus** \_\_\_\_\_ MW below \$ \_\_\_\_\_ per MWh

Band 3: **plus** \_\_\_\_\_ MW below \$ \_\_\_\_\_ per MWh

Band 4: **plus** \_\_\_\_\_ MW below \$ \_\_\_\_\_ per MWh

Band 5: **plus** \_\_\_\_\_ MW below \$ \_\_\_\_\_ per MWh

**Decrease electricity**

Band 1: **Decrease** \_\_\_\_\_ MW above \$ \_\_\_\_\_ per MWh

Band 2: **plus** \_\_\_\_\_ MW above \$ \_\_\_\_\_ per MWh

Band 3: **plus** \_\_\_\_\_ MW above \$ \_\_\_\_\_ per MWh

Band 4: **plus** \_\_\_\_\_ MW above \$ \_\_\_\_\_ per MWh

Band 5: **plus** \_\_\_\_\_ MW above \$ \_\_\_\_\_ per MWh

Schedule 13.1 Form 4A: inserted, on 28 June 2012, by clause 52 of the Electricity Industry Participation (Demand-side Bidding and Forecasting) Code Amendment 2011.

---

**Form 5**  
**Generation Reserve Offer**

Date: \_\_\_\_\_

Ancillary Service Agent:

\_\_\_\_\_

Generator Name: \_\_\_\_\_

Grid Injection Point: \_\_\_\_\_

Trading Period: \_\_\_\_\_ Starting at \_\_\_\_\_ 0 hours

**Offer to provide reserve**

**1 Partly Loaded Spinning Reserve**

Band 1:

\_\_\_\_\_% of electricity (MW), up to a maximum of \_\_\_\_ MW as Fast Instantaneous  
Reserve @ \$ \_\_\_\_\_ per MW

\_\_\_\_\_% of electricity (MW), up to a maximum of \_\_\_\_ MW as Sustained Instantaneous  
Reserve @ \$ \_\_\_\_\_ per MW

Band 2:

\_\_\_\_\_% of electricity (MW), up to a maximum of \_\_\_\_ MW as Fast Instantaneous  
Reserve @ \$ \_\_\_\_\_ per MW

\_\_\_\_\_% of electricity (MW), up to a maximum of \_\_\_\_ MW as Sustained Instantaneous  
Reserve @ \$ \_\_\_\_\_ per MW

Band 3:

\_\_\_\_\_% of electricity (MW), up to a maximum of \_\_\_\_ MW as Fast Instantaneous  
Reserve @ \$ \_\_\_\_\_ per MW

\_\_\_\_\_% of electricity (MW), up to a maximum of \_\_\_\_ MW as Sustained Instantaneous  
Reserve @ \$ \_\_\_\_\_ per MW

**2 Tail water depressed reserve**

Band 1:

Up to a maximum of \_\_\_\_\_ MW @ \$ \_\_\_\_\_ per MW as Fast Instantaneous Reserve

Up to a maximum of \_\_\_\_\_ MW @ \$ \_\_\_\_\_ per MW as Sustained Instantaneous  
Reserve

**Electricity Industry Participation Code 2010**  
**Schedule 13.1**

---

**Band 2:**

Up to a maximum of \_\_\_\_\_ **MW** @ \$ \_\_\_\_\_ per **MW** as Fast Instantaneous Reserve

Up to a maximum of \_\_\_\_\_ **MW** @ \$ \_\_\_\_\_ per **MW** as Sustained Instantaneous Reserve

**Band 3:**

Up to a maximum of \_\_\_\_\_ **MW** @ \$ \_\_\_\_\_ per **MW** as Fast Instantaneous Reserve

Up to a maximum of \_\_\_\_\_ **MW** @ \$ \_\_\_\_\_ per **MW** as Sustained Instantaneous Reserve

Compare: Electricity Governance Rules 2003 form 4 schedule G1 part G

Schedule 13.1 Form 5: amended, on 15 May 2014, by clause 50 of the Electricity Industry Participation (Minor Code Amendments) Code Amendment 2014.

---

**Form 6**  
**Interruptible Load Offer**

Date: \_\_\_\_\_

Ancillary Service Agent:

\_\_\_\_\_

Grid Exit Point or interruptible load group GXP:

\_\_\_\_\_

***Instantaneous reserve capability***

Holds a Reserve Contract with the System Operator ☐ Yes

Fast Instantaneous Reserve Interruptible Load Available ☐ Yes

Sustained Interruptible Load Available ☐ Yes

Trading Period: \_\_\_\_\_ Starting at \_\_\_\_\_ : \_\_\_\_\_ 0 hours

**Offer to provide reserve**

**1 Interruptible load**

Band 1:

Up to a maximum of \_\_\_\_\_ MW @ \$ \_\_\_\_\_ per MW as Fast Instantaneous Reserve

Up to a maximum of \_\_\_\_\_ MW @ \$ \_\_\_\_\_ per MW as Sustained Instantaneous Reserve

Band 2:

Up to a maximum of \_\_\_\_\_ MW @ \$ \_\_\_\_\_ per MW as Fast Instantaneous Reserve

Up to a maximum of \_\_\_\_\_ MW @ \$ \_\_\_\_\_ per MW as Sustained Instantaneous Reserve

Band 3:

Up to a maximum of \_\_\_\_\_ MW @ \$ \_\_\_\_\_ per MW as Fast Instantaneous Reserve

Up to a maximum of \_\_\_\_\_ MW @ \$ \_\_\_\_\_ per MW as Sustained Instantaneous Reserve

Compare: Electricity Governance Rules 2003 form 5 schedule G1 part G  
Schedule 13.1 Form 6: amended, on 15 May 2014, by clause 51 of the Electricity Industry Participation (Minor Code Amendments) Code Amendment 2014.

---

**Form 7**  
**Instantaneous Reserve Parameters**

Date: \_\_\_\_\_

Trading Period: \_\_\_\_\_ Starting at \_\_\_\_\_ : \_\_\_\_\_ 0 hours

North Island Fast Instantaneous Reserve Adjustment Factor

\_\_\_\_\_

North Island Sustained Instantaneous Reserve Adjustment Factor

\_\_\_\_\_

South Island Fast Instantaneous Reserve Adjustment Factor

\_\_\_\_\_

South Island Sustained Instantaneous Reserve Adjustment Factor

\_\_\_\_\_

**Minimum Risk**

North Island Minimum Risk

\_\_\_\_\_ **MW**

South Island Minimum Risk

\_\_\_\_\_ **MW**

Compare: Electricity Governance Rules 2003 form 6 schedule G1 part G  
Schedule 13.1 Form 7: amended, on 15 May 2014, by clause 52 of the Electricity Industry Participation (Minor Code Amendments) Code Amendment 2014.

---

**Form 8**  
**Notice of Station Dispatch Group**

Date:

Generator:

[*Insert name of generator*] hereby gives the **system operator** notice pursuant to clause 13.64 of the Code that the following group of **generating units** and/or **generating stations** are to be treated as a **station dispatch group**:

Name of Station Dispatch Group:

Station Identifier:

Constituent units:

Grid Injection Point (GIP)	Station/ generating unit name

This notice is to be effective from 0000 hours on [insert date], being at least 15 **business days** after the date of this notice, and remains in force until cancelled in writing by [insert name of generator].

Generator Control centre:

Name: \_\_\_\_\_

Contact Number: Ph: \_\_\_\_\_ Ph: \_\_\_\_\_

Address: \_\_\_\_\_  
\_\_\_\_\_

Yours sincerely

[Name of sender]

[Generator name]

Compare: Electricity Governance Rules 2003 form 7 schedule G1 part G  
Schedule 13.1, Form 8: amended, on 5 October 2017, by clause 483 of the Electricity Industry Participation Code  
Amendment (Code Review Programme) 2017.

**Form 9**  
**Claim of pricing error**

**CLAIM OF PRICING ERROR**

**Please email the completed form to the pricing manager**

**Contact Details (all fields are mandatory)**

Claimant: \_\_\_\_\_

Organisation: \_\_\_\_\_

Role at organisation: \_\_\_\_\_

E-mail: \_\_\_\_\_

Phone: \_\_\_\_\_

Mobile: \_\_\_\_\_

Fax: \_\_\_\_\_

**Pricing Error Summary Details (all fields are mandatory)**

Date: \_\_\_\_\_ Trading period(s) affected: \_\_\_\_\_

Node: \_\_\_\_\_ Energy: Yes/No \_\_\_\_\_ Reserve: Yes/No \_\_\_\_\_

Summary of pricing error: \_\_\_\_\_

**Section 1 - Basis of claim (only question 1 is mandatory)**

1. What is the nature of the pricing error?

2. Has the pricing error been caused by a Code breach? Yes/No

If yes, please specify the clause that has been breached:

**Section 2 – Materiality of pricing error and solution sought by applicant (all questions are mandatory)**

1. Describe the effect of this pricing error for your organisation? (if possible please provide financial information to demonstrate the materiality of the claimed pricing error)

2. Describe how, in your view, the claimed pricing error should be resolved.

Compare: Electricity Governance Rules 2003 form 8 schedule G1 part G  
Schedule 13.1 Form 9: amended, on 15 May 2014, by clause 53 of the Electricity Industry Participation (Minor Code Amendments) Code Amendment 2014.



## Schedule 13.2

### Model parameters

cl 13.189

#### 1 Model parameters

The **system operator** must, in accordance with clause 13.189 of the Code, provide the **pricing manager** with a list specifying the values for the following model parameters:

- (a) deficit bus generation:
- (b) surplus bus generation:
- (c) deficit 6s reserve for a contingent event as defined in clause 12.3 of the Policy Statement:
- (d) deficit 6s reserve for an extended contingent event as defined in clause 12.3 of the Policy Statement:
- (e) deficit 60s reserve for a contingent event as defined in clause 12.3 of the Policy Statement:
- (f) deficit 60s reserve for an extended contingent event as defined in clause 12.3 of the Policy Statement:
- (g) deficit branch group constrained:
- (h) surplus branch group constrained:
- (i) deficit bus group constrained:
- (j) surplus bus group constrained:
- (k) deficit ramp rate:
- (l) surplus ramp rate:
- (m) market node/trader capacity deficit:
- (n) deficit branch flow:
- (o) surplus branch flow:
- (p) deficit M-node constrained:
- (q) surplus M-node constrained.

Compare: Electricity Governance Rules 2003 schedule G2 part G

## Schedule 13.3 The Modelling System

cls 13.29, 13.33, 13.57, 13.58, 13.69, 13.83, 13.87, 13.88, 13.90, 13.135, 13.193, and 13.203

Heading: amended, on 28 June 2012, by clause 53 of the Electricity Industry Participation (Demand-side Bidding and Forecasting) Code Amendment 2011.

Heading: substituted, on 15 May 2014, by clause 54(1) of the Electricity Industry Participation (Minor Code Amendments) Code Amendment 2014.

### *Inputs into the modelling system*

#### 1 Purpose of modelling system

- (1) The purpose of the modelling system is to provide schedules of quantities and prices that maximise the gross **purchaser** benefit from purchases of **electricity** from the **clearing manager** less the total cost of production of **electricity** and **instantaneous reserves** as specified in this Schedule.
- (2) Schedules covering more than 1 **trading period** must be prepared for each **trading period** independently of the previous **trading period** unless otherwise specified in this Schedule.
- (2A) Despite subclause (2), a **price-responsive schedule** and **non-response schedule** must use the scheduled generation at the end of the previous **trading period** as the expected output for the purpose of clause 9A(b).
- (3) The modelling system must provide prices for **electricity** and **instantaneous reserve** that are consistent with the above purpose and the scheduled quantities of **electricity** and **instantaneous reserve**.
- (4) The modelling system must be used, using different inputs, to produce—
  - (a) **price-responsive schedules**; and
  - (b) **non-response schedules**; and
  - (c) **dispatch schedules**; and
  - (d) schedules of **real time prices**; and
  - (e) schedules of **provisional prices**; and
  - (f) schedules of **interim prices**; and
  - (g) schedules of **final prices**.

Compare: Electricity Governance Rules 2003 clause 1.1 schedule G6 part G

Clause 1 Heading: amended, on 15 May 2014, by clause 54(2) of the Electricity Industry Participation (Minor Code Amendments) Code Amendment 2014.

Clause 1(1): amended, on 28 June 2012, by clause 54(1) of the Electricity Industry Participation (Demand-side Bidding and Forecasting) Code Amendment 2011.

Clause 1(1): amended, on 21 September 2012, by clause 32(1) of the Electricity Industry Participation (Minor Amendments) Code Amendment 2012.

Clause 1(2): substituted, on 15 May 2014, by clause 69 of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

Clause 1(2A): inserted, on 15 May 2014, by clause 69 of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

Clause 1(3): amended, on 28 June 2012, by clause 54(2) of the Electricity Industry Participation (Demand-side Bidding and Forecasting) Code Amendment 2011.

Clause 1(4): substituted, on 28 June 2012, by clause 54(3) of the Electricity Industry Participation (Demand-side Bidding and Forecasting) Code Amendment 2011.

#### 2 Contents of each schedule

Each schedule must contain the information specified in—

- (a) clause 13.59, for a **price-responsive schedule** and a **non-response schedule**; and

- (b) *[Revoked]*
- (c) clauses 13.71 to 13.86, for a **dispatch schedule**; and
- (d) clause 13.135, for a schedule of **provisional prices** or a schedule of **interim prices** or a schedule of **final prices**; and
- (e) clause 13.88, for a schedule of **real time prices**.

Compare: Electricity Governance Rules 2003 clause 1.2 schedule G6 part G

Clause 2 Heading: amended, on 28 June 2012, by clause 55(1) of the Electricity Industry Participation (Demand-side Bidding and Forecasting) Code Amendment 2011.

Clause 2(a), (c), (d) and (e): amended, on 28 June 2012, by clause 55(2) of the Electricity Industry Participation (Demand-side Bidding and Forecasting) Code Amendment 2011.

Clause 2(b): revoked, on 28 June 2012, by clause 55(2)(c) of the Electricity Industry Participation (Demand-side Bidding and Forecasting) Code Amendment 2011.

Clause 2(c): amended, on 15 May 2014, by clause 70 of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

### *Inputs used at each stage*

## **3 Specific inputs must be used in schedules**

The schedules must be prepared using the following inputs:

- (a) for each **price-responsive schedule**, the inputs set out in clause 13.58A(1); and
- (b) for each **non-response schedule**, the inputs set out in clause 13.58A(2); and
- (c) for each **dispatch schedule**, the inputs set out in clause 7; and
- (d) for each schedule of **provisional prices**, each schedule of **interim prices** and each schedule of **final prices**, the inputs set out in clause 13.141; and
- (e) for each schedule of **real time prices**, the inputs set out in clause 6.

Compare: Electricity Governance Rules 2003 clause 1.3 schedule G6 part G

Clause 3: substituted, on 28 June 2012, by clause 56 of the Electricity Industry Participation (Demand-side Bidding and Forecasting) Code Amendment 2011.

## **4** *[Revoked]*

Clause 4: revoked, on 28 June 2012, by clause 57 of the Electricity Industry Participation (Demand-side Bidding and Forecasting) Code Amendment 2011.

## **5** *[Revoked]*

Clause 5: revoked, on 28 June 2012, by clause 57 of the Electricity Industry Participation (Demand-side Bidding and Forecasting) Code Amendment 2011.

## **6 Schedule of real time prices**

For a schedule of **real time prices**, the schedule must use—

- (a) the final information for each **real time pricing period** provided to the **system operator** under subpart 1 of Part 13, including—
  - (i) **offers** revised under clause 13.19; and
  - (ii) **nominated dispatch bids** revised under clause 13.19A; and
  - (iii) **reserve offers** revised under clause 13.47; and
  - (iv) information updated under clause 13.34(1); and
- (b) existing generation configuration specifying the instantaneous **MW injection** at each **grid injection point** at the beginning of the relevant **real time pricing period** for **generating plant** or **generating units** that were the subject of **offers**

- for the relevant **trading period**, or, if no such information is available, a reasonable estimate of such data; and
- (c) existing **demand** configuration, specifying the average **MW demand** at each **grid exit point**, excluding the **MW demand** at each **dispatch-capable load station** for which a **nominated dispatch bid** is submitted at the **grid exit point**, during the relevant **real time pricing period**, or if no such information is available, a reasonable estimate of such data.

Compare: Electricity Governance Rules 2003 clause 1.3.3 schedule G6 part G

Clause 6 Heading: amended, on 28 June 2012, by clause 58(1) of the Electricity Industry Participation (Demand-side Bidding and Forecasting) Code Amendment 2011.

Clause 6: amended, on 28 June 2012, by clause 58(2) of the Electricity Industry Participation (Demand-side Bidding and Forecasting) Code Amendment 2011.

Clause 6(a): substituted, on 15 May 2014, by clause 71(1) of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

Clause 6(c): amended, on 15 May 2014, by clause 71(2) of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

Clause 6(c): amended, on 15 May 2014, by clause 54(3) of the Electricity Industry Participation (Minor Code Amendments) Code Amendment 2014.

## 7 Dispatch schedule

For a **dispatch schedule**, the schedule must use—

- (a) **offers** and **reserve offers**, excluding the following:
- (i) **offers** made by an **intermittent generator** under clause 13.6(3);
  - (ii) revised **offers** made by an **intermittent generator** under clause 13.17(3);
  - (iii) **offers** made by a **type B co-generator** under clause 13.6(1) or (2);
  - (iv) revised **offers** made by a **type B co-generator** under clause 13.17(1) or (2);
- and
- (b) the quantities specified in **nominated bids** (clause 13.7 and 13.7AA) and the quantities specified in revised **nominated bids** (clause 13.19A); and
- (c) the expected profile of demand until the next **dispatch schedule** is produced by the **system operator**; and
- (d) the ramp rates agreed for **intermittent generators** under clause 13.71(c); and
- (e) any additional information regarding the future output of an **intermittent generator**, submitted by an **intermittent generator** in agreement with the **system operator** for the period until the next **dispatch schedule** is produced (clause 13.71(e)); and
- (f) the current output levels of each **generator**; and
- (g) information from the **grid owner** (clauses 13.29 to 13.34) and revised information from the **grid owner** (clause 13.33) about—
- (i) the AC transmission system configuration, capacity and losses; and
  - (ii) the capability of the **HVDC link** including its **configuration**, capacity, **losses**, the direction of any transfer limit, and any minimum or maximum transfer limits; and
  - (iii) transformer configuration, capacity and losses; and
- (h) information about **voltage support**; and
- (i) adjustments required to meet the **dispatch objective** must be incorporated in each schedule prepared and this method repeated until the **system operator** is satisfied that the schedule meets the requirements of the **dispatch objective**.

Compare: Electricity Governance Rules 2003 clause 1.3.4 schedule G6 part G

Clause 7 Heading: amended, on 28 June 2012, by clause 59(1) of the Electricity Industry Participation (Demand-side Bidding and Forecasting) Code Amendment 2011.

Clause 7: amended, on 28 June 2012, by clause 59(2) of the Electricity Industry Participation (Demand-side Bidding and Forecasting) Code Amendment 2011.

Clause 7(a): substituted, on 27 May 2015, by clause 17 of the Electricity Industry Participation Code Amendment (Industrial Co-generation Dispatch Arrangements) 2015.

Clause 7(b): substituted, on 28 June 2012, by clause 59(2)(b) of the Electricity Industry Participation (Demand-side Bidding and Forecasting) Code Amendment 2011.

Clause 7(b): substituted, on 15 May 2014, by clause 72(a) of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

Clause 7(g)(ii): substituted, on 1 November 2012, by clause 6(1) of the Electricity Industry Participation (HVDC Link Pole 3 Standing Data) Code Amendment 2012.

Clause 7(i): amended, on 15 May 2014, by clause 72(b) of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

### *The objective function*

## **8 The objective function**

- (1) The objective function of the modelling system is described mathematically as:

$$\begin{array}{c}
 \text{Gross Consumer Benefit} \\
 \hline
 \sum_{i,j} D_{i,j} \times BP_{i,j} \\
 \text{minus} \\
 \text{Cost of Generation} \\
 \hline
 \sum_{i,j} G_{i,j} \times OP_{i,j} \\
 \text{minus} \\
 \text{Cost of Fast Instantaneous Reserves} \\
 \hline
 \sum_{i,j} R_{i,j}^{PLSR,f} \times OP_{i,j}^{PLSR,f} + \sum_{i,j} R_{i,j}^{TWD,f} \times OP_{i,j}^{TWD,f} + \sum_{i,j} R_{i,j}^{IL,f} \times OP_{i,j}^{IL,f} \\
 \text{minus} \\
 \text{Cost of Sustained Instantaneous Reserves} \\
 \hline
 \sum_{i,j} R_{i,j}^{PLSR,s} \times OP_{i,j}^{PLSR,s} + \sum_{i,j} R_{i,j}^{TWD,s} \times OP_{i,j}^{TWD,s} + \sum_{i,j} R_{i,j}^{IL,s} \times OP_{i,j}^{IL,s}
 \end{array}$$

Maximise

where

$i$  is a price band of a **bid / offer** or a **reserve offer**

$j$  is a **generating unit / generating station**, or a **purchaser**

$D_{i,j}$	is the scheduled demand corresponding to price band $i$ of the <b>bid</b> for <b>purchaser</b> $j$ or metered demand, whichever is relevant, and where the relevant <b>bids</b> used here are formed from a combination of the following, as appropriate to the schedule being calculated: (a) nominated bids: (b) the forecast prepared under clause 13.7A(1): (c) difference bids (if difference bids are used, the quantities must be added or subtracted, as appropriate, from the forecast prepared under clause 13.7A(1)): (d) the system operator's expectation of the profile of demand during the relevant period covered by the schedule being calculated: (e) a measure of actual demand during the relevant period
$BP_{i,j}$	is the <b>bid</b> prices corresponding to price band $i$ of the <b>bid</b> for <b>purchaser</b> $j$
$G_{i,j}$	is the scheduled generation corresponding to price band $i$ of the <b>offer</b> for unit / station $j$
$OP_{i,j}$	is the <b>offer</b> price corresponding to price band $i$ of the <b>offer</b> for unit / station $j$
$R_{i,j}^{PLSR,f}$	is the scheduled fast PLSR corresponding to price band $i$ of the fast <b>reserve offer</b> for unit / station $j$
$R_{i,j}^{PLSR,s}$	is the scheduled sustained PLSR corresponding to price band $i$ of the <b>reserve offer</b> for unit / station $j$
$OP_{i,j}^{PLSR,f}$	is the <b>reserve offer</b> price corresponding to price band $i$ of the fast PLSR <b>reserve offer</b> for unit / station $j$
$OP_{i,j}^{PLSR,s}$	is the <b>offer</b> price corresponding to price band $i$ of the sustained PLSR <b>reserve offer</b> for unit / station $j$
$R_{i,j}^{TWD,f}$	is the scheduled fast TWD corresponding to price band $i$ of the <b>reserve offer</b> for unit / station $j$
$R_{i,j}^{TWD,s}$	is the scheduled sustained TWD corresponding to price band $i$ of the <b>reserve offer</b> for unit / station $j$
$OP_{i,j}^{TWD,f}$	is the <b>reserve offer</b> price corresponding to price band $i$ of the fast TWD <b>reserve offer</b> for unit / station $j$
$OP_{i,j}^{TWD,s}$	is the <b>reserve offer</b> price corresponding to price band $i$ of the sustained TWD <b>reserve offer</b> for unit / station $j$
$R_{i,j}^{IL,f}$	is the scheduled fast IL corresponding to price band $i$ of the <b>reserve offer</b> for <b>purchaser</b> $j$

$R_{i,j}^{IL,s}$	is the scheduled sustained IL corresponding to price band $i$ of the <b>reserve offer</b> for purchaser $j$
$OP_{i,j}^{IL,f}$	is the <b>reserve offer</b> price corresponding to price band $i$ of the fast IL <b>reserve offer</b> for purchaser $j$
$OP_{i,j}^{IL,s}$	is the <b>reserve offer</b> price corresponding to price band $i$ of the sustained IL <b>reserve offer</b> for purchaser $j$

and where

PLSR	is <b>partly loaded spinning reserve</b>
TWD	is <b>tail water depressed reserve</b>
IL	is <b>interruptible load</b>
fast	is <b>fast instantaneous reserve</b>
sustained	is <b>sustained instantaneous reserve</b>

- (2) The objective must be maximised to an accuracy specified in the **model formulation**.

Compare: Electricity Governance Rules 2003 clause 2 schedule G6 part G

Clause 8, definition of  $D_{ij}$ : amended, on 28 June 2012, by clause 60 of the Electricity Industry Participation (Demand-side Bidding and Forecasting) Code Amendment 2011.

Clause 8(1) definition of  $D_{ij}$ : amended, on 15 May 2014, by clause 73 of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

## 9 Constraints

In maximising the objective function, the **system operator** or the **pricing manager** (as the case may be) must ensure that the following constraints are met to an accuracy specified in the **model formulation**:

- (a) *[Revoked]*
- (b) each constraint relating to **generation** set out in clause 9A:
- (c) the constraint relating to **demand** set out in clause 10:
- (d) each constraint relating to the transmission system set out in clause 11:
- (e) each constraint relating to **instantaneous reserve** set out in clause 12.

Compare: Electricity Governance Rules 2003 clauses 3 and 3.1 schedule G6 part G

Clause 9: amended, on 28 June 2012, by clause 61 of the Electricity Industry Participation (Demand-side Bidding and Forecasting) Code Amendment 2011.

Clause 9: amended, on 15 May 2014, by clause 74 of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

### 9A Constraints relating to generation

The constraints for the purpose of clause 9(b) are that—

- (a) for each price band, the modelling system does not schedule **electricity** generation that would result in the scheduled quantity of **electricity** to be generated by a **generator** being greater than the quantity offered by the **generator** for the price band; and

- (b) the modelling system schedules **electricity** generation for each **generating unit** or **generating station** in a **trading period** within the offered maximum ramp up and ramp down rates of the **generating unit** or **generating station**, given the expected (or actual) output at the start of the **trading period**.

Clause 9A: inserted, on 15 May 2014, by clause 75 of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

## 10 Constraint relating to demand

The constraint relating to **demand** for the purpose of clause 9(c) is that, for each price band, the modelling system does not schedule **electricity demand** that would result in the scheduled quantity of **demand** being greater than the quantity bid by the **purchaser** for the price band.

Compare: Electricity Governance Rules 2003 clause 3.2 schedule G6 part G

Clause 10: substituted, on 28 June 2012, by clause 62 of the Electricity Industry Participation (Demand-side Bidding and Forecasting) Code Amendment 2011.

Clause 10: substituted, on 15 May 2014, by clause 76 of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

## 11 Constraints relating to transmission system

The final schedule provided by the modelling system must have the following characteristics (all of which must be met to an accuracy to be specified in the **model formulation**):

- (a) the total scheduled flow into and out of a **grid injection point** or **grid exit point** must equal 0 for all **grid injection points** and **grid exit points**:
- (b) the modelling system must calculate **losses** in transmission **lines**, the **HVDC link**, and transformers. Those **losses** must be approximated using the information provided by **grid owners** under clauses 13.29 to 13.31, for transmission **lines**, the **HVDC link** and transformers respectively:
- (c) the modelling system must calculate the **electricity** flows into individual transmission **lines** and flows into the connection points of transformers connected at the same **grid injection point** or **grid exit point** using an established DC power flow technique within the limitations imposed by the technique that—
- (i) correctly adjusts flows for transmission system **losses**; and
- (ii) correctly apportions flows in transmission system loops, whether or not those loops contain transmission **constraints**—
- provided that the capacity of transformers through which **electricity** is supplied to a **grid exit point** is not included in the model unless the transformer may carry flows of **electricity** other than **offtakes** from that **grid exit point**.

Compare: Electricity Governance Rules 2003 clause 3.3 schedule G6 part G

Clause 11 Heading: amended, on 15 May 2014, by clause 77 of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

Clause 11(b) and (c): amended, on 1 February 2016, by clause 88 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

Clause 11(c): amended, on 23 February 2015, by clause 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 11(c): amended, on 5 October 2017, by clause 484 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.



## **12 Constraints relating to instantaneous reserve**

- (1) The modelling system must simultaneously calculate the amount of **fast instantaneous reserve** and **sustained instantaneous reserve** to be provided by each **ancillary service agent** in each **island** to meet the requirements of the **dispatch objective** in each **island**.
- (2) In making the calculation in subclause (1), the modelling system must identify the risk (in **MW**) associated with the largest “Contingent Event” as the largest of—
  - (a) the transfer on a single pole of the **HVDC link**; or
  - (b) the generation from a single **generating unit** (whether or not this is a **generator’s generating unit**); or
  - (c) any other risk specified in the **dispatch objective**.
- (3) The modelling system must calculate the total amount of **fast instantaneous reserve** and **sustained instantaneous reserve** required to meet the requirements of the **dispatch objective**. The amount of **fast instantaneous reserve** and **sustained instantaneous reserve** to be provided by each **ancillary service agent** is this amount less any **instantaneous reserve** being provided by any other person who is not an **ancillary service agent** (as advised by the **system operator**).
- (4) The modelling system must not schedule **instantaneous reserve** at a **generating unit** or **generating station** that would result in the scheduled quantity of **electricity** to be generated plus the scheduled quantity of **instantaneous reserve** to be provided that is greater than the maximum **generator** effective reserve capacity of that **generating unit** or **generating station** as specified in the **reserve offer** for that **generating unit** or **generating station**.

Compare: Electricity Governance Rules 2003 clause 3.4 schedule G6 part G

Clause 12(2)(b): amended, on 21 September 2012, by clause 32(2) of the Electricity Industry Participation (Minor Amendments) Code Amendment 2012.

Clause 12 Heading: amended, on 15 May 2014, by clause 78 of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

Clause 12(3): amended, on 5 October 2017, by clause 485 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

## **13 Adjustments to schedules to meet dispatch objective**

- (1) As soon as practicable after each **non-response schedule** and each **dispatch schedule** has been completed, the **system operator** must give notice on **WITS** to **participants** of any changes required to the **non-response schedule** or **dispatch schedule** (as the case may be) to meet the **dispatch objective**, including adjustments for—
  - (a) **voltage support**; and
  - (b) **frequency keeping** reserves; and
  - (c) over-frequency arming; and
  - (d) additional transmission **constraints**; and
  - (e) **instantaneous reserve**.
- (2) The adjustments identified in subclause (1) must be made by setting 1 or a combination of the following parameters:
  - (a) minimum generation (in **MW**) required at a **grid injection point** or group of **grid exit points**;
  - (b) maximum generation (in **MW**) required at a **grid injection point** or group of **grid exit points**;

- (c) minimum flow limits (in **MW**) on a transmission line or a transformer:
  - (d) maximum flow limits (in **MW**) on a transmission line or a transformer:
  - (e) minimum flow limits (in **MW**) on a group of transmission **lines** or transformers:
  - (f) maximum flow limits (in **MW**) on a group of transmission **lines** or transformers:
  - (g) the reserve modelling parameters as contained in Form 7 in Schedule 13.1.
- (3) For a **non-response schedule** or a **dispatch schedule**, the adjustments must be made by the **system operator**. For a **dispatch schedule**, this method must be repeated to produce a new schedule. This must continue until the **system operator** is satisfied that the requirements of the **dispatch objective** have been met.
- (4) For a schedule of **provisional prices** or a schedule of **interim prices** or a schedule of **final prices**, the adjustments must be made using the adjustments that were used in the **non-response schedule** that applied at the beginning of the **trading period**.

Compare: Electricity Governance Rules 2003 clauses 4.1 and 4.2 schedule G6 part G

Clause 13 Heading: substituted, on 28 June 2012, by clause 63(1) of the Electricity Industry Participation (Demand-side Bidding and Forecasting) Code Amendment 2011.

Clause 13(1): amended, on 5 October 2017, by clause 486 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clauses 13(1), (3) and (4): substituted, on 28 June 2012, by clause 63(2) of the Electricity Industry Participation (Demand-side Bidding and Forecasting) Code Amendment 2011.

Clause 13(2)(e) and (f): amended, on 1 February 2016, by clause 89 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

#### 14 Principles to be followed by system operator

In suggesting changes and making adjustments under clause 13, the **system operator** must have regard to the following principles:

- (a) constraints must be imposed on **generating plant** only if the **system operator** has a specific requirement from the **generating plant** to meet the requirements of the **dispatch objective**:
- (b) constraints must be imposed on a transmission line or transformer only if the **system operator** has a specific requirement from the line or the transformer to meet the requirements of the **dispatch objective**:
- (c) adjustments must be made to **instantaneous reserve** modelling parameters only if the **system operator** has a specific requirement for **instantaneous reserve** to meet the requirements of the **dispatch objective**.

Compare: Electricity Governance Rules 2003 clause 4.3 schedule G6 part G

Clause 14(b): amended, on 28 June 2012, by clause 64 of the Electricity Industry Participation (Demand-side Bidding and Forecasting) Code Amendment 2011.

#### 15 Schedule of prices

A schedule of **provisional prices** or **interim prices** or **final prices** must use —

- (a) the information specified in **generator offers** (clause 13.6(1) to (3)); and
- (aa) the final submitted **nominated dispatch bid** for each **trading period** as specified in clause 13.141(1)(ca); and
- (b) the information specified in **ancillary service agent reserve offers** (clause 13.38(1)); and
- (c) the metered demand within the current **trading period** (clause 13.141(1)(b)), including any adjustments made for an **embedded generator**; and

- (d) the information from the **system operator** and a **grid owner** (clauses 13.29 to 13.34) that was used in the first **dispatch schedule** prepared for that **trading period** about—
  - (i) the AC transmission system configuration, capacity and losses; and
  - (ii) the capability of the **HVDC link** including its **configuration**, capacity, **losses**, the direction of any transfer limit, and any minimum or maximum transfer limits, weighted by time for any changes within the **trading period** (clause 13.30); and
  - (iii) transformer configuration, capacity and losses; and
  - (iv) **voltage support**; and
  - (v) **instantaneous reserves**; and
- (e) adjustments that were made to the **dispatch schedule** and the **non-response schedule**, which were required to meet the **dispatch objective** (clause 13.57).

Compare: Electricity Governance Rules 2003 clause 5 schedule G6 part G

Clause 15: amended, on 28 June 2012, by clause 65 of the Electricity Industry Participation (Demand-side Bidding and Forecasting) Code Amendment 2011.

Clause 15(aa): inserted, on 15 May 2014, by clause 79(a) of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

Clause 15(d)(ii): substituted, on 1 November 2012, by clause 6(2) of the Electricity Industry Participation (HVDC Link Pole 3 Standing Data) Code Amendment 2012.

Clause 15(e): amended, on 15 May 2014, by clause 79(b) of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

## **16 Calculation of prices, marginal location factors and reserve prices**

- (1) The modelling system must calculate the following set of prices:
  - (a) prices for **electricity** at each **grid injection point** and **grid exit point**, and at each **reference point**;
  - (b) **reserve prices** for each **island**;
  - (c) **marginal location factors** for each **grid injection point** and each **grid exit point**. Those factors must be determined by dividing the price at that **grid injection point** or **grid exit point** by the price at the **reference point** relevant to that **grid injection point** or **grid exit point**.
- (2) The modelling system must assign a 0 price for **electricity** at each **grid injection point** and **grid exit point** that has no load or generation connected to it in the modelling system.
- (3) The prices described in subclause (1) must be used—
  - (a) for a **price-responsive schedule** or a **non-response schedule**, as—
    - (i) **forecast prices**; and
    - (ii) **forecast reserve prices**; and
    - (iii) **forecast marginal location factors**;
  - (b) for a schedule of **provisional prices**, or a schedule of **interim prices**, or a schedule of **final prices**, as—
    - (i) **provisional prices**, **interim prices**, or **final prices**, as the case may be; and
    - (ii) **provisional reserve prices**, **interim reserve prices**, or **final reserve prices**, as the case may be; and
    - (iii) **provisional marginal location factors**, **interim marginal location factors**, or **final marginal location factors**, as the case may be;

(c) *[Revoked]*

(d) if this schedule is used as a schedule of **real time prices**, as **real time prices**.

Compare: Electricity Governance Rules 2003 clauses 6 to 6.2 schedule G6 part G

Clause 16(3): amended, on 28 June 2012, by clause 66 of the Electricity Industry Participation (Demand-side Bidding and Forecasting) Code Amendment 2011.

Clause 16(c): revoked, on 28 June 2012, by clause 66(d) of the Electricity Industry Participation (Demand-side Bidding and Forecasting) Code Amendment 2011.

Clause 16(1)(a): amended, on 21 September 2012, by clause 32(3) of the Electricity Industry Participation (Minor Amendments) Code Amendment 2012.

Clause 16(2): amended, on 5 October 2017, by clause 487 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

## 17 What modelling system must take into account when calculating prices

The modelling system must calculate the prices in clause 16 consistent with the objective function, and consistent with the quantities of **electricity** and **instantaneous reserve** scheduled, while meeting all constraints, and in particular—

- (a) prices for **electricity** at each **grid injection point** or **grid exit point** must be consistent with the treatment of transmission system **losses** and the transmission system power flow; and
- (b) subject to the rights of the **system operator** described in clause 13, a **generator** at a **grid injection point** must be scheduled to generate a quantity of **electricity** from a price band if the price determined by the modelling system at the **reference point** multiplied by the marginal **location factor** at that **grid injection point** is greater than or equal to the price offered in that price band; and
- (c) subject to the rights of the **system operator** described in clause 13, a **generator** at a **grid injection point** must not be scheduled to generate a quantity of **electricity** from a price band if the price determined by the modelling system at the **reference point** multiplied by the relevant marginal **location factor** at that **grid injection point** is less than the price offered in that price band; and
- (d) for **nominated bids**, subject to the obligations of the **system operator** described in clause 13, a **purchaser** at a **grid exit point**—
  - (i) must be scheduled to purchase a quantity of **electricity** from a price band if the price determined by the modelling system at the **reference point** multiplied by the relevant marginal location factor at the **grid exit point** is less than the price bid for the price band; and
  - (ii) must not be scheduled to purchase a quantity of **electricity** from a price band if the price determined by the modelling system at the **reference point** multiplied by the relevant marginal location factor at the **grid exit point** is greater than the price bid for the price band; and
- (e) for positive **difference bids**, subject to the obligations of the **system operator** described in clause 13, a **purchaser** at a **grid exit point**—
  - (i) must be scheduled to increase a quantity of **electricity** if the price determined by the modelling system at the **reference point** multiplied by the relevant marginal location factor at the **grid exit point** is less than the price bid for the price band; and
  - (ii) must not be scheduled to increase a quantity of **electricity** if the price determined by the modelling system at the **reference point** multiplied by

- the relevant marginal location factor at the **grid exit point** is greater than the price bid for the price band; and
- (ea) for negative **difference bids**, subject to the obligations of the **system operator** described in clause 13, a **purchaser** at a **grid exit point**—
- (i) must be scheduled to decrease a quantity of **electricity** if the price determined by the modelling system at the **reference point** multiplied by the relevant marginal location factor at that **grid exit point** is greater than the price bid for the price band; and
  - (ii) must not be scheduled to decrease a quantity of **electricity** if the price determined by the modelling system at the **reference point** multiplied by the relevant marginal location factor at that **grid exit point** is less than the price bid for the price band; and
- (f) subject to the rights of the **system operator** described in clause 13, an **ancillary service agent** who has made a **reserve offer** must be scheduled to provide a quantity of **instantaneous reserve** from a reserve price band only if the reserve price determined by the modelling system is greater than or equal to the total price offered for that reserve price band. In the case of a **reserve offer** for a **generating unit**, the total price offered for a price band must be equal to the amount required to ensure that that **ancillary service agent** is indifferent as to whether it generates **electricity** or provides **instantaneous reserve** plus the price **offered** in that reserve price band; and
- (g) subject to the rights of the **system operator** described in clause 13, an **ancillary service agent** who has made a **reserve offer** must not be scheduled to provide a quantity of **instantaneous reserve** from a price band if the reserve price determined by the modelling system is less than the total price offered for that price band. In the case of a **reserve offer** for a **generating unit**, the total price offered for a price band is equal to the amount required to ensure that that **ancillary service agent** is indifferent as to whether it generates **electricity** or provides **instantaneous reserve** plus the price offered in that reserve price band.

Compare: Electricity Governance Rules 2003 clause 6.3 schedule G6 part G  
Clause 17(d) and (e): substituted, on 28 June 2012, by clause 66A(a) and (b) of the Electricity Industry Participation (Demand-side Bidding and Forecasting) Code Amendment 2011.  
Clause 17(ea): inserted, on 28 June 2012, by clause 66A(c) of the Electricity Industry Participation (Demand-side Bidding and Forecasting) Code Amendment 2011.

## Schedule 13.3A

### Calculation of interim prices and interim reserve prices in scarcity pricing situation

cl 13.135B

Schedule 13.3A: inserted, on 1 June 2013, by clause 17 of the Electricity Industry Participation (Scarcity Pricing) Code Amendment 2011.

#### 1 Calculation of interim prices and interim reserve prices in island scarcity pricing situation

- (1) If the **pricing manager** determines under clause 13.135A that an **island scarcity pricing situation** exists in a **trading period**, the **pricing manager** must calculate **interim prices** and **interim reserve prices** in the relevant **island** for that **trading period** in accordance with the following:
- (a) calculate initial **interim prices** and **interim reserve prices** for the relevant **island** for that **trading period** in accordance with clause 13.135:
  - (b) calculate the **island GWAP** in accordance with subclause (2):
  - (c) calculate the scarcity pricing factor in accordance with subclause (3):
  - (d) calculate **interim prices** by multiplying the initial **interim prices** calculated under paragraph (a) by the scarcity pricing factor:
  - (e) calculate **interim reserve prices** by multiplying the initial **interim reserve prices** calculated under paragraph (a) by the scarcity pricing factor.
- (2) The **pricing manager** must calculate the **island GWAP** in accordance with the following formula:

$$\text{GWAP}_{\text{ISL}} = \frac{\sum_{g=1}^n (Q_g * P_g)}{\sum_{g=1}^n Q_g}$$

where

$\text{GWAP}_{\text{ISL}}$  is the **island GWAP**

$Q_g$  is the scheduled quantity of generation for **generator g** in the **island**

$P_g$  is the initial **interim price** at the **node** where **generator g** injects **electricity** in the **island**

- (3) The scarcity pricing factor is determined as follows:
- (a) if the **island GWAP** is greater than or equal to \$10,000/MWh and less than or equal to \$20,000/MWh, the scarcity pricing factor is 1:
  - (b) if the **island GWAP** is less than \$10,000/MWh, the scarcity pricing factor is calculated in accordance with the following formula:

$$X = \frac{\$10,000}{\text{GWAP}_{\text{ISL}}}$$

where

X is the scarcity pricing factor

GWAP<sub>ISL</sub> is the **island GWAP**

- (c) if the **island GWAP** is greater than \$20,000/MWh, the scarcity pricing factor is calculated in accordance with the following formula:

$$X = \frac{\$20,000}{\text{GWAP}_{\text{ISL}}}$$

where

X is the scarcity pricing factor

GWAP<sub>ISL</sub> is the **island GWAP**

Clause 1(2): amended, on 19 January 2017, by clause 8 of the Electricity Industry Participation Code Amendment (Scarcity Pricing) 2016

## 2 Calculation of interim prices in national scarcity pricing situation

- (1) If the **pricing manager** determines under clause 13.135A that a **national scarcity pricing situation** exists in a **trading period**, the **pricing manager** must calculate **interim prices** and **interim reserve prices** for that **trading period** in accordance with the following:
- (a) calculate initial **interim prices** and **interim reserve prices** for that **trading period** in accordance with clause 13.135:
  - (b) calculate the **national GWAP** in accordance with subclause (2):
  - (c) calculate the scarcity pricing factor in accordance with subclause (3):
  - (d) calculate **interim prices** by multiplying the initial **interim prices** calculated under paragraph (a) by the scarcity pricing factor:
  - (e) calculate **interim reserve prices** by multiplying the initial **interim reserve prices** calculated under paragraph (a) by the scarcity pricing factor.
- (2) The **pricing manager** must calculate the **national GWAP** in accordance with the following formula:

$$\text{GWAP}_{\text{NAT}} = \frac{\sum_{g=1}^n (Q_g * P_g)}{\sum_{g=1}^n Q_g}$$

where

$GWAP_{NAT}$  is the **national GWAP**

$Q_g$  is the scheduled quantity of generation for **generator g** in both **islands**

$P_g$  is the initial **interim price** at the **node** where **generator g** injects **electricity in both islands**

- (3) The scarcity pricing factor is determined as follows:
- (a) if the **national GWAP** is greater than or equal to \$10,000/MWh and less than or equal to \$20,000/MWh, the scarcity pricing factor is 1:
  - (b) if the **national GWAP** is less than \$10,000/MWh, the scarcity pricing factor is calculated in accordance with the following formula:

$$X = \frac{\$10,000}{GWAP_{NAT}}$$

where

$X$  is the scarcity pricing factor

$GWAP_{NAT}$  is the **national GWAP**

- (c) if the **national GWAP** is greater than \$20,000/MWh, the scarcity pricing factor is calculated in accordance with the following formula:

$$X = \frac{\$20,000}{GWAP_{NAT}}$$

where

$X$  is the scarcity pricing factor

$GWAP_{NAT}$  is the **national GWAP**

Clause 2(2): amended, on 19 January 2017, by clause 9 of the Electricity Industry Participation Code Amendment (Scarcity Pricing) 2016.



## Schedule 13.4

cl 13.3

### Approval as type A or type B industrial co-generating station

Heading: amended, on 27 May 2015, by clause 18 of the Electricity Industry Participation Code Amendment (Industrial Co-generation Dispatch Arrangements) 2015.

#### 1 Generators to apply to Authority for approval

A **generator** may apply to the **Authority** to have 1 or more **generating units** approved as—

- (a) a **type A industrial co-generating station**; or
- (b) a **type B industrial co-generating station**.

Compare: Electricity Governance Rules 2003 clause 1 schedule G9 part G

Clause 1: substituted, on 27 May 2015, by clause 19 of the Electricity Industry Participation Code Amendment (Industrial Co-generation Dispatch Arrangements) 2015.

#### 2 Application requirements

(1) An application must—

- (a) be in writing; and
- (b) specify each **generating unit** that the applicant wants to have approved; and
- (c) include information related to any seasonal operation of each **generating unit**; and
- (d) specify whether the applicant wants each **generating unit** to be approved as a—
  - (i) **type A industrial co-generating station**; or
  - (ii) **type B industrial co-generating station**.

(2) An applicant may include any supporting information that the applicant considers may assist the **Authority** with the application.

Compare: Electricity Governance Rules 2003 clause 2 schedule G9 part G

Clause 2: substituted, on 27 May 2015, by clause 20 of the Electricity Industry Participation Code Amendment (Industrial Co-generation Dispatch Arrangements) 2015.

#### 3 Authority must publish each application for approval

On receipt of an application, the **Authority** must—

- (a) **publish** the application; and
- (b) provide a copy of the application to the **system operator**.

Compare: Electricity Governance Rules 2003 clause 3 schedule G9 part G

Clause 3 Heading: amended, on 5 October 2017, by clause 488(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 3(a): amended, on 5 October 2017, by clause 488(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

#### 4 Factors that Authority must consider

Before the **Authority** approves an application, it must take into account—

- (a) the **system operator's** views as to the effect an approval would have on the **system operator's** ability to meet the **PPOs**; and
- (b) the cumulative effects, if the approval were granted, of all approvals granted under this Schedule on the **system operator's** ability to meet the **PPOs**; and
- (c) any views that may be made known to the **Authority** within the time specified by the **Authority** when it **published** the application in accordance with clause 3(a); and
- (d) whether each **generating unit** that is the subject of the application is as described

in paragraphs (b) and (c) of the definition of **industrial co-generating station** set out in Part 1; and

- (da) the implications of each **generating unit** that is the subject of the application being approved in accordance with the applicant's preference specified under clause 2(1)(d), having regard to the obligations of **type A co-generators** and **type B co-generators**; and
- (e) section 15 of the **Act**.

Compare: Electricity Governance Rules 2003 clause 4 schedule G9 part G

Clause 4: amended, on 27 May 2015, by clause 21(1) of the Electricity Industry Participation Code Amendment (Industrial Co-generation Dispatch Arrangements) 2015.

Clause 4(c): amended, on 5 October 2017, by clause 489 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 4(d): substituted, on 27 May 2015, by clause 21(2) of the Electricity Industry Participation Code Amendment (Industrial Co-generation Dispatch Arrangements) 2015.

Clause 4(da): inserted, on 27 May 2015, by clause 21(2) of the Electricity Industry Participation Code Amendment (Industrial Co-generation Dispatch Arrangements) 2015.

## 5 **Authority may require extra information**

The **Authority** may require the provision of additional information at any stage during the application process and, if the **Authority's** requirements are reasonable, the applicant must provide that information to the **Authority**.

Compare: Electricity Governance Rules 2003 clause 5 schedule G9 part G

## 6 **Authority may seek independent expert advice**

In considering an application for approval, the **Authority** may seek technical advice from an independent person who is familiar with co-generation.

Compare: Electricity Governance Rules 2003 clause 6 schedule G9 part G

## 7 **Applicant may withdraw or amend application at any time**

- (1) The applicant may, at any time, withdraw or amend an application being considered by the **Authority**.
- (2) An amendment or withdrawal—
  - (a) must be made in writing; and
  - (b) must be submitted to the **Authority**; and
  - (c) takes effect from the date of receipt by the **Authority**.

Compare: Electricity Governance Rules 2003 clause 7 schedule G9 part G

Clause 7(1): amended, on 27 May 2015, by clause 22(1) of the Electricity Industry Participation Code Amendment (Industrial Co-generation Dispatch Arrangements) 2015.

Clause 7(2): inserted, on 27 May 2015, by clause 22(2) of the Electricity Industry Participation Code Amendment (Industrial Co-generation Dispatch Arrangements) 2015.

## 8 **Authority's decision**

- (1) The **Authority** must, no later than 6 months after receiving an application,—
  - (a) approve each **generating unit** that is the subject of the application as either—
    - (i) a **type A industrial co-generating station**; or
    - (ii) a **type B industrial co-generating station**; or
  - (b) decline to approve the application.
- (2) The **Authority** must consult with an applicant before making a decision if the **Authority**—
  - (a) proposes to approve an application for a type of **industrial co-generating station**

- other than the applicant's preference specified under clause 2(1)(d); or
- (b) proposes to decline the application.
- (3) The **Authority** must, as soon as practicable after making a decision,—
- (a) advise the applicant, the **system operator**, the **grid owner**, and the **clearing manager** in writing; and
- (b) **publish** its decision, including—
- (i) the reasons for the decision; and
- (ii) in the case of an application that has been approved, any conditions that have been imposed.

Compare: Electricity Governance Rules 2003 clause 8 schedule G9 part G

Clause 8: substituted, on 27 May 2015, by clause 23 of the Electricity Industry Participation Code Amendment (Industrial Co-generation Dispatch Arrangements) 2015.

Clause 8(3)(b): amended, on 5 October 2017, by clause 490 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

## 9 Decision must be recorded

- (1) The **Authority** must keep a register of all current approvals granted under this Schedule available for public inspection free of charge during normal office hours at the offices of the **Authority** and on the **Authority's** website at all reasonable times.
- (2) The register must state, for each approval on the register,—
- (a) whether the applicant's **generating units** have been approved as a **type A co-generating station** or a **type B co-generating station**; and
- (b) the name of the **type A co-generator** or the **type B co-generator**; and
- (c) the name of the **type A industrial co-generating station** or the **type B industrial co-generating station**; and
- (d) the date of the approval; and
- (e) the duration of the approval; and
- (f) whether the approval includes any conditions and if so, a description of the conditions.

Compare: Electricity Governance Rules 2003 clause 9 schedule G9 part G

Clause 9(2): substituted, on 27 May 2015, by clause 24 of the Electricity Industry Participation Code Amendment (Industrial Co-generation Dispatch Arrangements) 2015.

## 10 Effect of approval

Approval of 1 or more **generating units** as a **type A industrial co-generating station** or a **type B industrial co-generating station** takes effect from the date specified in the approval, which may be no earlier than 10 **business days** after the date of the notice of decision **published** by the **Authority** under clause 8(3).

Compare: Electricity Governance Rules 2003 clause 10 schedule G9 part G

Clause 10: substituted, on 27 May 2015, by clause 25 of the Electricity Industry Participation Code Amendment (Industrial Co-generation Dispatch Arrangements) 2015.

Clause 10: amended, on 5 October 2017, by clause 491 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

## 11 Authority may impose conditions

The **Authority** may impose conditions on any approval it grants. Such conditions may include 1 or more of the following:

- (a) requirements to assist the **system operator** in meeting the **PPOs**;
- (b) requirements as to seasonal co-generation, including limitations on when the approval applies:

- (c) requirements that a **type A co-generator** or **type B co-generator** comply with specific instructions from the **system operator** during a **grid emergency** or during a system **constraint** that directly affects the **type A co-generator** or **type B co-generator**.

Compare: Electricity Governance Rules 2003 clause 11 schedule G9 part G  
Clause 11(b) and (c): substituted, on 27 May 2015, by clause 26 of the Electricity Industry Participation Code Amendment (Industrial Co-generation Dispatch Arrangements) 2015.

## 12 *[Revoked]*

Compare: Electricity Governance Rules 2003 clause 12 schedule G9 part G  
Clause 12: revoked, on 27 May 2015, by clause 27 of the Electricity Industry Participation Code Amendment (Industrial Co-generation Dispatch Arrangements) 2015.

## 13 **Authority may rescind or amend approval**

- (1) If the **Authority** considers a change of circumstance has led to a situation in which the continuation of an approval would significantly adversely impact on the **system operator's** ability to meet the **PPOs**, it may amend or rescind the approval.
- (2) The **Authority** may, at the request of a **type A co-generator** or a **type B co-generator**, amend an approval to change a **type A industrial co-generating station** to a **type B co-generating station**, or vice-versa.
- (3) The **Authority** must consult with the **system operator** before amending an approval under subclause (2).

Compare: Electricity Governance Rules 2003 clause 13 schedule G9 part G  
Clause 13(2) and (3): inserted, on 27 May 2015, by clause 28 of the Electricity Industry Participation Code Amendment (Industrial Co-generation Dispatch Arrangements) 2015.

## 14 **Notice and reasons for rescinding or amending approval**

If the **Authority** amends or rescinds an approval, it must—

- (a) give the **type A co-generator** or **type B co-generator** 3 months' notice before rescinding or amending the approval; and
- (b) advise the **type A co-generator** or **type B co-generator** of the reasons for rescinding or amending the approval.

Compare: Electricity Governance Rules 2003 clause 14 schedule G9 part G  
Clause 14(a) and (b): substituted, on 27 May 2015, by clause 29 of the Electricity Industry Participation Code Amendment (Industrial Co-generation Dispatch Arrangements) 2015.

## Schedule 13.5

cl 13.238

### Requirements for FTR allocation plan

Schedule 13.5: inserted, on 1 October 2011, by clause 9 of the Electricity Industry Participation (Financial Transmission Rights) Code Amendment 2011.

#### 1 Purpose

The purpose of this Schedule is to set out the requirements for the **FTR allocation plan** prepared by the **FTR manager** under subpart 6 of Part 13.

#### 2 Requirements for design of FTRs

- (1) **FTRs** must be allocated by auction.
- (2) At a minimum, the **FTRs** allocated under the **FTR allocation plan** must be **FTRs** between a **hub** in the South Island and a **hub** in the North Island that would provide a reasonable match with the trading points for exchange-traded futures products or the equivalent **electricity** futures products, and which would enable the volumes of **FTRs** available to reflect inter-island **grid** capacity.
- (3) The **FTR manager** must offer **option FTRs** and **obligation FTRs**.
- (4) The **FTRs** offered must include **FTRs** for which the **FTR period** is 1 month.
- (5) Subclause (4) does not prevent the **FTR manager** from offering **FTRs** relating to a shorter **FTR period** in addition to **FTRs** for which the **FTR period** is 1 month.

#### 3 Requirements for FTR auction design

- (1) The number and nature of the **FTRs** allocated under the **FTR allocation plan** and available for auction must be—
  - (a) supported by a reasonable estimate of the capacity of the **grid** for the relevant period; and
  - (b) set so as to achieve a reasonable balance between the following:
    - (i) ensuring that there is revenue available that is sufficient to settle the **FTRs**;
    - (ii) ensuring that sufficient **FTRs** are available so that **participants** who wish to purchase **FTRs** are able to obtain them.
- (2) The **FTR auction** must be designed to—
  - (a) maximise the value of trade in the auction as determined by the bids made in the auction; and
  - (b) maximise competition in the auction; and
  - (c) minimise costs of participation in the auction.
- (3) The **FTR allocation plan** must include **FTR auction** procedures.
- (4) The initial **FTR allocation plan** must specify a plan that seeks to—
  - (a) ensure that, no later than 1 year after the first **FTR auction**, **FTRs** are available in each **FTR auction** relating to an initial month and to at least each of the 11 months following the initial month; and
  - (b) ensure that the availability of **FTRs** is progressively increased so that, no later than 3 years after the first **FTR auction**, **FTRs** are available in each **FTR auction**

relating to an initial month and to at least the 23 months following the initial month.

Clause 3(3): amended, on 5 October 2017, by clause 492 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

#### **4 Requirements for FTR grid design**

The **FTR grid** must—

- (a) be based on each **grid owner's** forecast of the configuration and capacity of its **grid** for the **FTR period**; and
- (b) make allowance for relevant planned and unplanned outages in accordance with reasonable transmission operating practice.

## Schedule 13.6

cl 13.248

Schedule 13.6: inserted, on 1 October 2011, by clause 9 of the Electricity Industry Participation (Financial Transmission Rights) Code Amendment 2011.

Schedule 13.6: amended, on 1 June 2012, by clause 7 of the Electricity Industry Participation (Removal of Quantity Limit for Financial Transmission Rights) Code Amendment 2012.

### Form 1 Assignment of FTR

Date: \_\_\_\_\_

FTR registered number: \_\_\_\_\_

If part of the FTR is to be assigned, specify the amount of electricity (in MW) to which the assigned part of the FTR relates: \_\_\_\_\_

Price\*: \_\_\_\_\_

Assignor: \_\_\_\_\_

Assignee: \_\_\_\_\_

\* Parties are only required to specify the price if they wish clause 13.249 to apply.

## Schedule 13.7

cls 13.27C, 13.27E, 13.27G, and 13.27K

Schedule 13.7: inserted, on 28 March 2012, by clause 67 of the Electricity Industry Participation (Demand-side Bidding and Forecasting) Code Amendment 2011.

### Methodology for Determining Conforming and Non-Conforming GXPs

#### 1 Methodology for determining whether GXP is conforming GXP or non-conforming GXP

In making a determination under clause 13.27A or clause 13.27B(4), the **Authority** must use the following method:

- (a) use the input data described in clause 2 to determine the adjusted reconciled **half hour demand** data (in **MW**) for the **GXP** for each **trading period** during the most recent 12 consecutive months for which data is available; and
- (b) using the results from paragraph (a), determine the mean **demand** (in **MW**) for the **GXP** over the most recent 12 consecutive months for which data is available; and
- (c) determine the unpredictability measure for the **GXP** in accordance with clause 3; and
- (d) apply the results from paragraphs (b) and (c) to the table below, to determine whether the **GXP** is either a **conforming GXP** or a **non-conforming GXP**.

**Table 1: Determining whether GXP is conforming or non conforming**

Category for mean demand (in MW) for a GXP over relevant 12 months (clause 1(b)) (d)	Category for unpredictability measure (clause 1(c)) (p)	Resulting classification of the GXP
Where $d < 10\text{MW}$	For all $p$	<b>Conforming GXP</b>
Where $10\text{MW} \leq d < 20\text{MW}$	For $p < 0.15$	<b>Conforming GXP</b>
	For $p \geq 0.15$	<b>Non-conforming GXP</b>
Where $20\text{MW} \leq d < 250 \text{ MW}$	For $p < 0.10$	<b>Conforming GXP</b>
	For $p \geq 0.10$	<b>Non-conforming GXP</b>
Where $d \geq 250 \text{ MW}$	For all $p$	<b>Non-conforming GXP</b>

#### 2 Input data

- (1) For the purpose of determining the adjusted reconciled **half hour demand** data for a **GXP** under clause 1(a), the **Authority** must use the following data from the most recent 12 consecutive months for which data is available:
  - (a) reconciled **half hour demand** data for the **GXP** representing purchases of **electricity** at the **GXP** aggregated across all **purchasers** at the **GXP**, and with each **half hour** figure in **MWh** converted to an average **demand** in **MW** over that **half hour**; and
  - (b) information about the impact of **demand** switching on the **GXP**; and



- (c) information from **distributors, purchasers** and the **system operator** about any one-off events that have affected **demand** but which would not be expected to affect **demand** in the future.
- (2) If the **Authority** identifies, under subclause (1)(b), that 2 or more adjacent **GXPs** are significantly affected by **demand** switching, the **Authority** must—
  - (a) combine the **GXPs**' reconciled **half hour demand** data as described in subclause (1)(a) and follow the method set out in clause 1 for the combined **GXPs** as if they were a single **GXP**; or
  - (b) follow such other method of addressing the impact of **demand** switching as the **Authority** may determine is appropriate in the circumstances.
- (3) In applying the methodology under clause 1, the **Authority** must remove one-off events identified under this clause from the input data.
- (4) A one-off event includes, but is not limited to, the following:
  - (a) a transmission outage that has caused a **GXP** to be unable to be supplied with **electricity**;
  - (b) a **consumer** ceasing to consume at a **GXP**, if over the proportion of the relevant 12 month period for which the **consumer** was consuming **electricity**, the reconciled **demand** attributed to the **consumer** (in **MW**) was on average at least 40% of the total **demand** (in **MW**) at the **GXP**.

### 3 Calculate unpredictability measures

- (1) For the purpose of determining the unpredictability measure of a **GXP** under clause 1(c), the **Authority** must use the following method:
  - (a) the **Authority** must fit an appropriate statistical predictive model as described in subclause (2), to the adjusted reconciled **half hour demand** data (in **MW**) which is produced in accordance with clause 1(a); and
  - (b) the **Authority** must calculate the residuals (in **MW** for each **half hour**) of the statistical predictive model (representing the simulated predictive errors of such a model); and
  - (c) the **Authority** must calculate the unpredictability measure as the ratio of the standard deviation of the residuals calculated under paragraph (b) to the mean **demand** at the **GXP** (calculated under clause 1(b)).
- (2) The statistical predictive model under subclause (1)(a) must achieve the approximate level of predictive accuracy that should be able to be achieved by the **system operator** when preparing the forecast under clause 13.7A several hours in advance in the absence of forecast information from **purchasers** and **electricity** users.
- (3) To avoid doubt, the statistical predictive model may include a variable representing weather forecast information.

Clause 3(2): amended, on 15 May 2014, by clause 80 of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

### 4 Data for most recent 12 months unavailable

- (1) If the data required under clauses 1 to 3 is not available for the most recent 12 consecutive months, the **Authority** must use reasonable endeavours to make a

determination in accordance with the methodology set out in this Schedule using the data it has available.

- (2) If the available data is insufficient to enable the **Authority** to make a determination in accordance with subclause (1), the **Authority** must make a determination by—
- (a) using all available data; and
  - (b) using its own reasonable expectations of the future activities at the **GXP**; and
  - (c) taking into account, to the extent practicable, the methodology set out in clauses 1 to 3.

## **Schedule 13.8 cl 1.1, 13.3A, 13.3B**

### **Approval of dispatch-capable load station**

Schedule 13.8: inserted, on 15 May 2014, by clause 81 of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

#### **1 Applications for approval**

Each application for approval for a **dispatch-capable load station** must—

- (a) be in writing; and
- (b) list a device or a group of devices that the applicant wishes to have approved as a **dispatch-capable load station**; and
- (c) include information to enable the **system operator** to determine the application.

#### **2 System operator to provide application to Authority and advise others of application**

On receipt of an application, the **system operator** must—

- (a) provide a copy of the application to the **Authority**; and
- (b) advise the following **participants** that it has received the application:
  - (i) the relevant **grid owner**;
  - (ii) each **distributor** that has a **network** from which a device that comprises or forms part of the proposed **dispatch-capable load station** draws **electricity**;
  - (iii) the **pricing manager**;
  - (iv) the **clearing manager**;
  - (v) the **reconciliation manager**;
  - (vi) the **WITS manager**.

Clause 2(b)(ii) substituted, on 1 February 2016, by clause 90 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

Clause 2(b)(vi): amended, on 5 October 2017, by clause 493 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

#### **3 Factors that system operator must consider**

- (1) Before the **system operator** approves a device or a group of devices to be a **dispatch-capable load station**, it must consider—

- (a) the effect an approval would have on the **system operator's** ability to comply with the **PPOs**; and
- (b) whether the applicant—
  - (i) is able to provide real time indications and measurements to the satisfaction of the **system operator**; and
  - (ii) has in place communication systems that meet the **system operator's** requirements; and
  - (iii) is able to receive **dispatch instructions**; and
- (c) whether there is a substantial risk that a **dispatch instruction** that changes the level of load of the device or group of devices that is the subject of the application may be offset by changes in **demand** in the same **trading period** from other load controlled by the applicant; and
- (d) whether the device or group of devices is technically capable of complying with a **dispatch instruction** so that it does not adversely affect the **system operator's** ability to comply with the **PPOs**; and
- (e) any other matter the **system operator** reasonably considers relevant.

- (2) In making a decision under subclause (1), the **system operator** must—
  - (a) ask the **Authority** for the **Authority's** view; and
  - (b) consider the **Authority's** view.

#### **4 System operator may request additional information**

- (1) Subclauses (2) and (3) apply to—
  - (a) a **participant** that has applied to the **system operator** to have a device or a group of devices approved as a **dispatch-capable load station**; and
  - (b) a **purchaser** that has a **dispatch-capable load station** that has been approved.
- (2) The **system operator** may request a **participant** to which this clause applies to provide additional information.
- (3) The **participant** must provide the requested information to the **system operator**.
- (4) As soon as practicable after receiving the requested information, the **system operator** must provide a copy of the information to the **Authority**.

#### **5 Applicant may withdraw or amend application at any time**

- (1) An applicant may, at any time, amend or withdraw an application.
- (2) An applicant must make an amendment or withdrawal—
  - (a) in writing; and
  - (b) by submitting it to the **system operator**.
- (3) An amendment or a withdrawal takes effect from the date of receipt by the **system operator**.
- (4) As soon as practicable after receiving an amendment or a withdrawal, the **system operator** must—
  - (a) provide the amendment or withdrawal to the **Authority**; and
  - (b) advise all **participants** listed in clause 2(b) of the amendment or withdrawal.

#### **6 System operator's decision**

- (1) The **system operator** must decide whether to—
  - (a) approve an application; or
  - (b) decline an application.
- (2) If the **system operator** decides to approve an application, the **system operator** must assign a **dispatch-capable load station identifier** to each approved **dispatch-capable load station**.
- (3) The **system operator** must, as soon as practicable after making a decision, advise the parties listed in subclause (4) in writing of—
  - (a) the decision; and
  - (b) if the decision is to approve the application, any conditions that apply to the approval; and
  - (c) the **system operator's** reasons for the decision.
- (4) For the purpose of subclause (3), the **system operator** must advise the following parties:
  - (a) the applicant;
  - (b) the **Authority**;
  - (c) all **participants** listed in clause 2(b).

**7 System operator may impose conditions**

- (1) The **system operator** may impose conditions on any approval it grants under this Schedule.
- (2) Conditions may include, but are not limited to, 1 or more of the following:
  - (a) a requirement that the applicant has in place real time indications and measurements to the satisfaction of the **system operator**;
  - (b) a requirement that the applicant has in place a system for communicating with the **system operator** to the satisfaction of the **system operator**;
  - (c) a requirement that the applicant performs tests of load controlling systems on a regular basis.

**8 Timeframe for decision**

- (1) The **system operator** must make a decision under clause 6(1)—
  - (a) within 20 **business days** after—
    - (i) the date on which the **system operator** receives the application; or
    - (ii) if the application is amended under clause 5, the date on which the **system operator** receives the amendment; or
  - (b) within any other period of time that has been agreed by the applicant and the **system operator**.
- (2) Despite subclause (1), if the **system operator** requests additional information from the applicant under clause 4, the timeframes in subclause (1) are extended by the number of days the applicant takes to provide the additional information.

**9 Effect of approval**

- (1) When approving an application for a **dispatch-capable load station**, the **system operator** must specify a date from which the approval takes effect.
- (2) The **system operator** must not set a date from which an approval takes effect that is earlier than 10 **business days** after the date on which the approval was granted.
- (3) An approval of a **dispatch-capable load station** takes effect from the date specified in the approval.

**10 System operator may amend, revoke, or suspend approval**

- (1) The **system operator** may, at its own discretion or on the request of the **Authority** or a **dispatchable load purchaser**,—
  - (a) amend an approval; or
  - (b) revoke an approval; or
  - (c) suspend an approval.
- (2) An amendment takes effect from—
  - (a) the date it is made; or
  - (b) a later date specified by the **system operator**.
- (3) A revocation takes effect from—
  - (a) the date it is made; or
  - (b) a later date specified by the **system operator**.
- (4) A suspension—
  - (a) takes effect from—
    - (i) the date it is made; or
    - (ii) a later date specified by the **system operator**; and
  - (b) remains in effect until a date specified by the **system operator**.

**11 System operator to give reasons for amending, revoking, or suspending approval**

As soon as practicable after the **system operator** amends, revokes, or suspends a **dispatchable load purchaser's** approval, the **system operator** must advise the **purchaser**, the **Authority**, and all **participants** listed in clause 2(b) of—

- (a) the revocation, suspension, or amendment; and
- (b) the reasons for the revocation, suspension, or amendment.

**12 Authority to keep register of all current approvals**

- (1) The **Authority** must keep a register of all current approvals—
  - (a) granted under this Schedule; and
  - (b) of which the **system operator** has advised the **Authority**.
- (2) The **Authority** must keep the register available for public inspection free of charge—
  - (a) at its offices, during normal office hours; and
  - (b) on its website, at all reasonable times.
- (3) The register must state, for each approval granted,—
  - (a) the name of the applicant; and
  - (b) the name of the **dispatch-capable load station**; and
  - (c) the **dispatch-capable load station identifier**; and
  - (d) the date from which the approval takes effect; and
  - (e) any conditions.

Clause 12(1)(b): replaced, on 5 October 2017, by clause 494 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

# Electricity Industry Participation Code 2010

## Part 14 Clearing and settlement

Part 14: substituted, on 24 March 2015, by clause 20 of the Electricity Industry Participation (Settlement and Prudential Security) Code Amendment 2013.

### Contents

#### Subpart 1—Sale and purchase of electricity

- 14.1 Contents of this Part
- 14.2 Sale and purchase of electricity
- 14.3 Sale by generators with point of connection to grid
- 14.4 Sale by generators with point of connection to local network or embedded network
- 14.5 On sale by participants
- 14.6 Purchase of offtake through point of connection to grid
- 14.7 Purchase of offtake through local network by embedded generator

#### Subpart 2—Hedge settlement agreements

- 14.8 Hedge settlement agreement lodgement
- 14.9 Cancellation of hedge settlement agreement

#### Subpart 3—Amounts owing

- 14.10 Amounts owing for electricity
- 14.11 Amounts owing for constrained off compensation and constrained on compensation
- 14.12 Amounts owing for washup amounts
- 14.13 Amounts owing for auction revenue
- 14.14 Amounts owing for ancillary services
- 14.14A Amounts owing for extended reserve
- 14.15 Amounts owing for hedge settlement agreements
- 14.16 Calculation of loss and constraint excess
- 14.17 Amounts owing for FTRs

#### Subpart 4—Notification of amounts owing and payable

##### *Information about amounts owing and payable*

- 14.18 Clearing manager to advise participant of amounts owing and payable
- 14.19 Amounts owing by participant to clearing manager
- 14.20 Amounts owing by clearing manager to participant
- 14.21 Methodology for determining settlement retention amount
- 14.22 Calculation of amount payable

##### *Procedure for advising participants of amounts owing and payable*

- 14.23 Procedure for advising participant of amounts owing and payable
- 14.24 Participant to confirm receipt

##### *Disputes about amounts*

- 14.25 Participant may dispute amount

- 14.26 Resolution of dispute about amount
- 14.27 Dispute about amount may be referred to Rulings Panel
- 14.28 Correction of information about amount as result of dispute

Subpart 5—Payments

- 14.29 Payment of amounts payable
- 14.30 Prepayment of amounts payable
- 14.31 Deadlines for payments
- 14.32 Methods of payment
- 14.33 Allocation of payments
- 14.34 Payments by clearing manager
- 14.35 Payment of residual loss and constraint excess

Subpart 6—Washups

- 14.36 Clearing manager to conduct washups
- 14.37 Clearing manager to advise participants of washup amounts
- 14.38 Washup amounts
- 14.39 Washups for grid owners
- 14.40 Payment where no longer participant

Subpart 7—Events of default

*Types of default*

- 14.41 Definition of an event of default

*Procedure for event of default*

- 14.42 Clearing manager to advise Authority of anticipated event of default
- 14.43 Procedure upon event of default

*Remedies and rights of recovery*

- 14.44 Event of default gives clearing manager remedies
- 14.45 Remedies for settlement default
- 14.46 Remedies for other types of default
- 14.47 Application to take possession of FTR
- 14.48 Cancellation of hedge settlement agreement in event of default
- 14.49 Electrical disconnection of direct purchaser
- 14.50 Clearing manager to exercise rights to recover amounts outstanding
- 14.51 Participants assigned or subrogated to all clearing manager's rights of recovery
- 14.52 Rights of participants to exercise rights

*Publication of information about event of default*

- 14.53 Authority may publish information about event of default

Subpart 8—Payments in event of settlement default

- 14.54 Application of this subpart
- 14.55 Allocation of shortfall to settlement of general amounts and FTRs



- 14.56 Calculation of revised amount owing for general amounts
- 14.57 Calculation of revised amount owing for FTR amounts
- 14.58 Calculation of scaled amount payable
- 14.59 Calculation of revised amount payable
- 14.60 Payment of revised amount payable
- 14.61 Payment by participant with negative scaled amount payable
- 14.62 Application of payment by participant with negative scaled amount payable
- 14.63 Further funds paid according to priority
- 14.64 Interest payable to participants
- 14.65 Participant to remain in default

Subpart 9—Administrative obligations of clearing manager

*Clearing manager operating account*

- 14.66 Clearing manager to establish operating account
- 14.67 Payment by clearing manager

*Reporting obligations of the clearing manager*

- 14.68 Monthly divergence reports to be prepared by clearing manager
- 14.69 Authority to publish clearing manager reports
- 14.70 Right to information concerning clearing manager's action
- 14.71 Clearing manager to make block dispatch settlement differences available
- 14.72 Clearing manager to make block dispatch settlement differences available later if WITS unavailable
- 14.73 Clause 14.71 applies to block dispatch groups
- 14.74 No washup calculation under clause 14.71 if revised reconciliation information is received

*Notices*

- 14.75 Notices

**Schedule 14.1**

**Formula for scaling amount owing in respect of FTRs**

**Schedule 14.2**

**Consultation and approval requirements for methodologies**

**Schedule 14.3**

**Calculation of amount of loss and constraint excess to be applied to the settlement of FTRs**

**Schedule 14.4**

**Form of hedge settlement agreement**

---

## 14.1 Contents of this Part

This Part provides for—

- (a) the sale and purchase of **electricity** to and from the **clearing manager**; and
- (b) the calculation and invoicing of amounts owing to and by the **clearing manager** for **electricity**, **ancillary services**, **extended reserve**, **FTRs**, and other payments that may be received or paid by the **clearing manager**; and
- (c) the settlement of amounts payable under this Part; and
- (d) processes and remedies for an **event of default**; and
- (e) obligations of the **clearing manager** in relation to clearing and settlement, including reporting obligations and requirements for the **operating account** that must be established and held by the **clearing manager**.

Clause 14.1(b): amended, on 24 March 2015, by clause 24 of the Electricity Industry Participation Code Amendment (Extended Reserve) 2014.

## Subpart 1—Sale and purchase of electricity

### 14.2 Sale and purchase of electricity

- (1) The **clearing manager** must—
  - (a) purchase **electricity** sold to the **clearing manager** in accordance with clauses 14.3 to 14.5; and
  - (b) sell **electricity** purchased from the **clearing manager** in accordance with clause 14.6.
- (2) Each **generator** must sell **electricity** in accordance with clauses 14.3 and 14.4.
- (3) Each **purchaser** must purchase **electricity** in accordance with clause 14.6.
- (4) Each **participant** that sells or purchases **electricity** through a **local network** or **embedded network** must sell and purchase the **electricity** in accordance with clauses 14.4, 14.5, and 14.7.
- (5) The amount owing for **electricity** purchased under this Part must be determined in accordance with clause 14.10.

Clause 14.2(5): amended, on 24 March 2015, by clause 4 of the Electricity Industry Participation Code Amendment (Late and Revised Data) 2015.

### 14.3 Sale by generators with point of connection to grid

- (1) This clause applies to each **generator** that has a **generating station** or **generating unit** with a **point of connection** to the **grid**.
- (2) Each **generator** to which this clause applies must sell to the **clearing manager** all **electricity** generated by the **generator's generating station** or **generating unit** injected through a **point of connection** to the **grid**.

### 14.4 Sale by generators with point of connection to local network or embedded network

- (1) This clause—
  - (a) applies to each **generator** that has an **embedded generating station**; but
  - (b) does not apply to a **generator** in respect of an **embedded generating station** in relation to a **point of connection** for which a notification under clause 15.14 is in force.
- (2) Each **generator** to which this clause applies must sell all **electricity** generated by the

**embedded generating station** and injected through a **point of connection** with the **local network** or **embedded network** to—

- (a) the **clearing manager**; or
  - (b) a **participant** trading on the **local network** or **embedded network**.
- (3) Despite anything to the contrary in this Code, the relevant **point of connection** to the **grid** is, for the purposes of reconciliation under this Code, deemed to be a **grid injection point**.

#### 14.5 On sale by participants

If an **embedded generator** sells **electricity** to a **participant** under clause 14.4, the **participant** must at the same time on-sell that **electricity** to the **clearing manager**.

#### 14.6 Purchase of offtake through point of connection to grid

Each **purchaser** must purchase from the **clearing manager** the **electricity** allocated to the **purchaser** under Part 15 in respect of a **point of connection** to the **grid**.

#### 14.7 Purchase of offtake through local network by embedded generator

- (1) A **generator** that purchases **electricity** at the same **point of connection** with a **local network** at which it sells **electricity** in accordance with clause 14.4 must purchase the **electricity** from the same **participant** to which it sold its **electricity** under clause 14.4.
- (2) The **participant** from which electricity is purchased under subclause (1) must sell the **electricity** as set out in this Code.

### Subpart 2—Hedge settlement agreements

#### 14.8 Hedge settlement agreement lodgement

- (1) If a **hedge settlement agreement** that is signed by 2 **participants** is submitted to the **clearing manager**, subject to subclauses (2) and (3), it is validly lodged when it is signed by the **clearing manager**.
- (2) A **hedge settlement agreement** must be in 1 of the forms set out in Schedule 14.4, or in an alternative form approved by the **Authority**.
- (3) The **clearing manager** may only sign a **hedge settlement agreement** submitted under subclause (1) if the **clearing manager** is satisfied that, after the **hedge settlement agreement** is lodged, at least 1 **participant** to the **hedge settlement agreement** will have a physical position in **MW** that is 33% or more of its **hedge settlement agreement** position in **MW** in any month calculated under paragraph (b) of subclause (4).
- (4) For the purposes of subclause (3),—
  - (a) a **participant's** physical position in **MW** is the greater of the following:
    - (i) the average of the **participant's** generation in **MW** over the last 12 months based on **reconciled quantities**;
    - (ii) the average of the **participant's** generation in **MW** over the last month based on **reconciled quantities**;
    - (iii) the average of the **participant's** purchases in **MW** over the last 12 months based on **reconciled quantities**;

- (iv) the average of the **participant's** purchases in **MW** over the last month based on **reconciled quantities**; and
  - (b) the sum of the average **MW** of each of the **participant's hedge settlement agreements** for any month to which the **hedge settlement agreement** applies.
- (5) When a **participant** submits a **hedge settlement agreement** to the **clearing manager**, the **participant** must also provide any other information relating to the **hedge settlement agreement** that the **clearing manager** requires.
- (6) A **participant** must provide information under subclause (5) in a form prescribed by the **clearing manager** and notified to **participants**.

#### 14.9 Cancellation of hedge settlement agreement

- (1) A **hedge settlement agreement** may be cancelled only in the following situations:
  - (a) if an **event of default** has occurred and is continuing in relation to a party to the **hedge settlement agreement**, in accordance with clause 14.48;
  - (b) if no **event of default** is continuing in relation to either of the parties to the **hedge settlement agreement**, in accordance with subclause (2).
- (2) A party to a **hedge settlement agreement** may cancel the **hedge settlement agreement** under subclause (1)(b) if both parties to the **hedge settlement agreement** agree in writing to the cancellation and either—
  - (a) the parties give the **clearing manager** at least 90 days' notice of the cancellation; or
  - (b) the parties give the **clearing manager** less than 90 days' notice of the cancellation and the **clearing manager** agrees to the cancellation in accordance with subclause (3).
- (3) The **clearing manager** may agree to the cancellation of a **hedge settlement agreement** under subclause (2)(b) only if the **clearing manager** is satisfied that—
  - (a) immediately following the cancellation of the **hedge settlement agreement**, each party will—
    - (i) continue to meet the requirements in clause 14A.4(1); or
    - (ii) meet the requirements in clause 14A.3; and
  - (b) the cancellation of the **hedge settlement agreement** is not otherwise contrary to the interests of **participants** to which an amount is payable under this Part.
- (4) In deciding whether to agree to the cancellation of a **hedge settlement agreement**, the **clearing manager** may consult with the **Authority**.

### Subpart 3—Amounts owing

#### 14.10 Amounts owing for electricity

- (1) The **clearing manager** must determine the amount owing for **electricity** purchased under clauses 14.2 to 14.7 using the following formula:

$$Q * P_f$$

where

**Q** is the quantity of **electricity** allocated to the **participant** for each **trading period** for each **point of connection** to the **grid** determined in accordance with **reconciliation information** and summarised and loss adjusted **dispatchable load information**

**P<sub>f</sub>** is the **final price** determined by the **pricing manager** for each relevant **point of connection** to the **grid** for each **trading period**

- (2) The **clearing manager** must determine the amount owing for **electricity** sold under clauses 14.2 to 14.7 using the following formula:

$$Q * P_f$$

where

**Q** is the quantity of **electricity** allocated to the **participant** for each **trading period** for each **point of connection** to the **grid** determined in accordance with **reconciliation information**

**P<sub>f</sub>** is the **final price** determined by the **pricing manager** for each relevant **point of connection** to the **grid** for each **trading period**

- (3) The quantity of **electricity** bought by a **purchaser** or sold by a **generator** under subpart 1 must be determined in accordance with clauses 15.20A to 15.26.
- (4) The **final price** of **electricity** bought by a **purchaser** or sold by a **generator** under subpart 1 must be determined in accordance with clauses 13.135 and 13.171 to 13.185.

#### **14.11 Amounts owing for constrained off compensation and constrained on compensation**

The **clearing manager** must determine amounts owing in respect of **constrained off compensation** and **constrained on compensation** in accordance with clauses 13.192 to 13.212.

#### **14.12 Amounts owing for washup amounts**

The **clearing manager** must determine amounts owing in respect of **washup** amounts in accordance with subpart 6.

#### **14.13 Amounts owing for auction revenue**

The **clearing manager** must determine amounts owing in respect of **auction revenue** in accordance with clauses 13.110 to 13.112.

#### **14.14 Amounts owing for ancillary services**

The **clearing manager** must determine amounts owing in respect of **ancillary services** in accordance with clauses 8.6, 8.31, 8.55(1), and 8.68(1).

Clause 14.14: amended, on 24 March 2015, by clause 25 of the Electricity Industry Participation Code Amendment (Extended Reserve) 2014.

#### 14.14A Amounts owing for extended reserve

The **clearing manager** must determine amounts owing in respect of **extended reserve** in accordance with clauses 8.55(2), 8.67A, and 8.68(3) and (4).

Clause 14.14A: inserted, on 24 March 2015, by clause 26 of the Electricity Industry Participation Code Amendment (Extended Reserve) 2014.

#### 14.15 Amounts owing for hedge settlement agreements

The **clearing manager** must calculate amounts owing under a **hedge settlement agreement** in respect of the current **billing period** in accordance with the terms of the **hedge settlement agreement**.

#### 14.16 Calculation of loss and constraint excess

- (1) A **loss and constraint excess** accrues for a **billing period** when the total of the amounts owing by the **clearing manager** to **generators** for that **billing period** for the **electricity** sold and purchased in accordance with clause 14.3 is less than the total amount owing to the **clearing manager** for that **billing period** for the **electricity** sold and purchased in accordance with clause 14.6.
- (2) The **FTR manager** must—
  - (a) determine the amount of **loss and constraint excess** that must be applied to the settlement of **FTRs** in accordance with Schedule 14.3; and
  - (b) advise the **clearing manager** of that amount no later than—
    - (i) 1600 hours on the 7<sup>th</sup> **business day** of the month following the relevant **billing period**; or
    - (ii) if **publication** of **final prices** is delayed for any **trading period** in the relevant **billing period**, so that **final prices** for a **trading period** in the **billing period** are **published** later than 1600 hours on the 6<sup>th</sup> **business day** of the month following the relevant **billing period**, 1 **business day** after all **final prices** for the **billing period** are **published**.
- (3) Each **grid owner** and the **pricing manager** must provide information to the **FTR manager** in accordance with Schedule 14.3.
- (4) Subject to subpart 8, the **clearing manager** must apply the amount advised under subclause (2) to the settlement of **FTRs**.
- (5) Subject to subpart 8, if the amount that the **FTR manager** advises the **clearing manager** under subclause (2) exceeds the amount of the **loss and constraint excess** for the **billing period**, the **clearing manager** must apply all of the **loss and constraint excess** to the settlement of **FTRs**.
- (6) The **Authority** must advise the **clearing manager** of the proportion of the **loss and constraint excess** and **residual loss and constraint excess** owing to each **grid owner**.
- (7) Unless the **Authority** has directed otherwise under this clause, the amount owing to each **grid owner** in the proportions advised under subclause (6) is—
  - (a) the amount of any **loss and constraint excess** less the amount to be applied to the settlement of **FTRs** under subclause (4) or (5); and
  - (b) the amount of any **residual loss and constraint excess**.

Clause 14.16(2)(b): substituted, on 24 March 2015, by clause 10 of the Electricity Industry Participation Code Amendment (Settlement and Prudential Security) 2014.

#### 14.17 Amounts owing for FTRs

- (1) The **clearing manager** must calculate, for each **billing period**, the amount owing—
  - (a) by a **participant** to the **clearing manager** in respect of each **FTR** for which the **participant** is registered as the holder of the **FTR**; and
  - (b) by the **clearing manager** to a **participant** in respect of each **FTR** for which the **participant** is registered as the holder of the **FTR**; and
  - (c) by a **participant** to the **clearing manager** in respect of the assignment of an **FTR** under clause 13.249(4); and
  - (d) by the **clearing manager** to a **participant** in respect of the assignment of an **FTR** under clause 13.249(7).
- (2) The amount owing by a **participant** to the **clearing manager** in respect of an **FTR** is the net amount of the **FTR acquisition cost** for the **FTR** minus the **FTR hedge value** for the **FTR**, if that net amount is positive.
- (3) The amount owing by the **clearing manager** to a **participant** in respect of an **FTR** is the net amount of the **FTR hedge value** for the **FTR** minus the **FTR acquisition cost** for the **FTR**, if that net amount is positive.
- (4) The **clearing manager** must **publish**, for each **billing period**,—
  - (a) the amount owing by a **participant** to the **clearing manager** for each **FTR**; and
  - (b) the amount owing by the **clearing manager** to a **participant** for each **FTR**.
- (5) Subclause (6) applies if, in respect of a **billing period**, the total amount to be advised as owing by the **clearing manager** under paragraphs (b) and (d) of subclause (1) exceeds the sum of the following amounts:
  - (a) the total amount to be advised as owing to the **clearing manager** under subclause (1)(a);
  - (b) any amount available under clause 13.249(6) for the settlement of **FTRs** in the **billing period**;
  - (c) the amount of the **loss and constraint excess** to be applied to the settlement of **FTRs** under clause 14.16(4) or (5).
- (6) The **clearing manager** must, in calculating the amount owing in respect of each **FTR** under paragraph (a) or (b) of subclause (1), use an amended **FTR hedge value** scaled according to the formula specified in Schedule 14.1.

### Subpart 4—Notification of amounts owing and payable

#### *Information about amounts owing and payable*

#### 14.18 Clearing manager to advise participant of amounts owing and payable

- (1) The **clearing manager** must advise each **participant**, for which the **clearing manager** has determined that the **participant** owes or is owed an amount under subpart 3, the following:
  - (a) amounts owing by the **participant** to the **clearing manager** in accordance with clause 14.19;
  - (b) amounts owing by the **clearing manager** to the **participant** in accordance with clause 14.20;

- (c) the amount of the settlement retention amount calculated in accordance with the methodology **published** by the **clearing manager** under clause 14.21:
  - (d) any amount payable by the **participant** to the **clearing manager** and any amount payable by the **clearing manager** to the **participant** under subpart 5 in accordance with clause 14.22.
- (2) The **clearing manager** must advise each **participant** of each amount owing and each amount payable as follows:
- (a) no later than the 9<sup>th</sup> **business day** of the month following the **billing period**; but
  - (b) if the **clearing manager** has not received any information required to determine an amount payable in respect of the prior **billing period** in time to advise each **participant** by that date,—
    - (i) if the **clearing manager** receives the information in time to advise each **participant** of each amount owing and each amount payable 2 **business days** or more before the 20<sup>th</sup> day of the month, the **clearing manager** must advise each **participant** no later than 2 **business days** before the 20<sup>th</sup> day of the month; or
    - (ii) if the **clearing manager** does not receive, or considers that it is not likely to receive, the information in time to advise each **participant** of each amount owing and each amount payable 2 **business days** before the 20<sup>th</sup> day of the month,—
      - (A) the **clearing manager** must refer the matter to the **Authority**; and
      - (B) the **Authority** must direct the **clearing manager** as to the time by which the **clearing manager** must advise each **participant** of each amount owing and each amount payable; and
      - (C) the **clearing manager** must advise each **participant** by the time directed by the **Authority**.
- (3) A **participant** must not issue a **GST** invoice for supplies of **electricity, ancillary services, extended reserve, or ancillary service administrative costs** to the **clearing manager**.

Clause 14.18(2): substituted, on 24 March 2015, by clause 5 of the Electricity Industry Participation Code Amendment (Late and Revised Data) 2015.

Clause 14.18(2)(b)(i) and (ii): amended, on 5 October 2017, by clause 495 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 14.18(3): amended, on 24 March 2015, by clause 27 of the Electricity Industry Participation Code Amendment (Extended Reserve) 2014.

#### **14.19 Amounts owing by participant to clearing manager**

- (1) When advising a **participant** of amounts owing under clause 14.18(1)(a), the **clearing manager** must specify any amount owing by the **participant** to the **clearing manager** for—
- (a) the relevant **billing period**, to the extent that the **clearing manager** has received the necessary information; and
  - (b) any prior **billing period** if the **clearing manager** receives the necessary information for that **billing period** after the date that amounts owing for that **billing period** were required to be advised by the **clearing manager**.
- (2) The **clearing manager** must specify any amount owing by the **participant** to the **clearing manager** in respect of the periods referred to in subclause (1) for the



following:

- (a) **electricity** purchased under clauses 14.2 to 14.7:
  - (b) **constrained off compensation** under clause 13.201A:
  - (c) **constrained on compensation** under clause 13.212:
  - (d) a **washup** amount and any interest on that amount under subpart 6:
  - (e) **auction revenue** under clause 13.110:
  - (f) **ancillary services** under clauses 8.6, 8.31(1)(a), and 8.68(1):
  - (fa) **extended reserve** under clauses 8.67A, and 8.68(3):
  - (g) payment of an amount under any **hedge settlement agreement**:
  - (h) for each **FTR** in respect of which the **participant** is registered as the holder of the **FTR**, the net amount of the **FTR acquisition cost** for the **FTR** minus the **FTR hedge value** for the **FTR**, if that net amount is positive:
  - (i) any amount owing in respect of the assignment of any **FTR** under clause 13.249(4):
  - (j) **GST**.
- (3) The **clearing manager** must specify the sum of the amounts referred to in subclause (2).

Clause 14.19(2)(f): amended, on 24 March 2015, by clause 28(1) of the Electricity Industry Participation Code Amendment (Extended Reserve) 2014.

Clause 14.19(2)(fa): inserted, on 24 March 2015, by clause 28(2) of the Electricity Industry Participation Code Amendment (Extended Reserve) 2014.

#### 14.20 Amounts owing by clearing manager to participant

- (1) When advising a **participant** of amounts owing under clause 14.18(1)(b), the **clearing manager** must specify any amount owing by the **clearing manager** to the **participant** for—
- (a) the relevant **billing period**, to the extent that the **clearing manager** has received the necessary information; and
  - (b) any prior **billing period** if the **clearing manager** receives the necessary information for that **billing period** after the date that amounts owing for that **billing period** were required to be advised by the **clearing manager**.
- (2) The **clearing manager** must specify any amount owing by the **clearing manager** to the **participant** in respect of the periods referred to in subclause (1) for the following:
- (a) **electricity** sold under clauses 14.2 to 14.7:
  - (b) **constrained off compensation** under clause 13.201A:
  - (c) **constrained on compensation** under clause 13.212:
  - (d) a **washup** amount and any interest on that amount under subpart 6:
  - (e) **auction revenue** under clause 13.112:
  - (f) **ancillary services** under clause 8.55(a):
  - (fa) **extended reserve** under clause 8.68(4):
  - (g) payment of an amount under any **hedge settlement agreement**:
  - (h) for each **FTR** in respect of which the **participant** is registered as the holder of the **FTR**, the net amount of the **FTR hedge value** for the **FTR** minus the **FTR acquisition cost** for the **FTR**, if that net amount is positive:
  - (i) any amount owing in respect of the assignment of any **FTR** under clause

13.249(7):

- (j) **GST**:
  - (k) **loss and constraint excess** and **residual loss and constraint excess** under clause 14.16(7).
- (3) The **clearing manager** must specify the sum of the amounts referred to in subclause (2).

Clause 14.20(2)(fa): inserted, on 24 March 2015, by clause 29 of the Electricity Industry Participation Code Amendment (Extended Reserve) 2014.

#### 14.21 Methodology for determining settlement retention amount

- (1) The **clearing manager** must formulate and **publish** a methodology for determining the settlement retention amount to be advised to a **participant** in accordance with clause 14.18(1)(c).
- (2) The methodology formulated by the **clearing manager** under subclause (1) must comply with the principle that the settlement retention amount is set to ensure that the **clearing manager** has sufficient funds to pay each non-defaulting **participant** the amount payable to that **participant** under subpart 5 if both of the following occur:
  - (a) a **settlement default** that results in the largest percentage reduction in payments that would be made in the absence of the settlement retention amount in respect of amounts other than **FTRs**; and
  - (b) a **settlement default** that results in the largest percentage reduction in payments that would be made in the absence of the settlement retention amount in respect of **FTRs** (other than in respect of the **residual loss and constraint excess**).
- (3) For the purposes of subclause (2), multiple **settlement defaults** by parties related in any way specified in the methodology must be treated as 1 **settlement default**.
- (4) The consultation and approval requirements set out in Schedule 14.2 apply to the methodology.

#### 14.22 Calculation of amount payable

- (1) The amount payable by a **participant** to the **clearing manager** under clause 14.31 is determined in accordance with the following formula:

$$AP_P = \text{Max} [0, AO_P - AO_{CM} + SRA]$$

where

$AP_P$  is the amount payable by the **participant** to the **clearing manager**

$AO_P$  is the sum of the amounts owing by the **participant** to the **clearing manager**, calculated under clause 14.19

$AO_{CM}$  is the sum of the amounts owing by the **clearing manager** to the **participant**, calculated under clause 14.20

$SRA$  is the settlement retention amount, calculated in accordance with the methodology **published** by the **clearing manager** under clause 14.21

- (2) Subject to subpart 8, the amount payable by the **clearing manager** to a **participant** in accordance with clause 14.34 is determined in accordance with the following formula:

$$AP_{CM} = AO_{CM} - AO_P + AP_P$$

where

$AP_{CM}$  is the amount payable by the **clearing manager** to the **participant**

$AO_{CM}$  is the sum of the amounts owing by the **clearing manager** to the **participant**, calculated under clause 14.20

$AO_P$  is the sum of the amounts owing by the **participant** to the **clearing manager**, calculated under clause 14.19

$AP_P$  is the amount payable under subclause (1) (if any)

*Procedure for advising participants of amounts owing and payable*

#### 14.23 Procedure for advising participant of amounts owing and payable

- (1) When advising a **participant** of amounts owing and payable under this subpart, the **clearing manager** must—
  - (a) submit the information to each relevant **participant** through **WITS**; and
  - (aa) **publish** the information; and
  - (b) if the **participant** requests, post or hand deliver the information to the **participant**.
- (2) Proof of submitting the information to **WITS** is deemed to be proof of the advice under subclause (1), despite the procedures set out in this clause and in clause 14.24.

Clause 14.23(1)(a): replaced, on 5 October 2017, by clause 496(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 14.23(1)(aa): inserted, on 5 October 2017, by clause 496(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 14.23(2): amended, on 5 October 2017, by clause 496(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

#### 14.24 Participant to confirm receipt

- (1) Each **participant** that receives information from the **clearing manager** under this subpart must immediately confirm, through **WITS**, receipt of the information sent by the **clearing manager** under clause 14.23(1)(a) or (b).
- (2) If, by 1200 hours on the **business day** after submitting the information under clause 14.23(1), the **clearing manager** has not received confirmation from a **participant** that the **participant** has received the information, the **clearing manager** must check whether the **participant** has received the information.
- (3) If the **participant** has not received the information, the **clearing manager** must resubmit the information through **WITS**.
- (4) Delayed confirmation by a **participant** that the information has been received does not extend the payment period set out in clause 14.31.

Clause 14.24(1): amended, on 5 October 2017, by clause 497(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 14.24(2): replaced, on 5 October 2017, by clause 497(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 14.24(3): replaced, on 5 October 2017, by clause 497(3) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

*Disputes about amounts*

**14.25 Participant may dispute amount**

- (1) A **participant** may dispute information about an amount that is provided by the **clearing manager** under this subpart by notice in writing to the **clearing manager**.
- (2) A **participant** may not—
  - (a) dispute the information under subclause (1) after the expiry of 2 years after the date that the information is provided; or
  - (b) commence a dispute under subclause (1) if the **participant** has commenced a dispute in relation to the **volume information** on which the information is based under clause 15.29, and the dispute remains unresolved.
- (3) The **clearing manager** must advise all **participants** materially affected by the dispute and the **Authority** of the dispute no later than 1 **business day** after the dispute is notified to the **clearing manager** under subclause (1).
- (4) On receiving a notification of a dispute that relates to **volume information** under subclause (3), the **Authority** may direct that no further action be taken in respect of the dispute.
- (5) If the **Authority** gives a direction under subclause (4), clauses 14.26 to 14.28 cease to apply to the dispute.
- (6) A direction under subclause (4) does not affect the validity of information provided under clause 14.26(2) or clause 14.37 before the direction was given.

Clause 14.25(2)(b): amended, on 24 March 2015, by clause 6 of the Electricity Industry Participation Code Amendment (Late and Revised Data) 2015.

**14.26 Resolution of dispute about amount**

- (1) The disputing **participant** and the **clearing manager** must attempt to resolve the dispute.
- (2) The **clearing manager** must revise the disputed amount and any other affected amount if, in time for the **clearing manager** to advise each **participant** of each amount owing and each amount payable 2 **business days** or more before the disputed amount is due to be paid or received by the disputing **participant**—
  - (a) the dispute is resolved by the parties advised of the dispute agreeing that information used to determine the amount is incorrect; and
  - (b) *[Revoked]*
  - (c) the **clearing manager** has received all information necessary to revise the amount and any other affected amount (including revised **volume information** if necessary).
- (3) Subject to clause 14.28, if the **participant** and the **clearing manager** do not resolve the dispute by the time referred to in subclause (2), the disputing **participant** must pay or receive the amount in accordance with clauses 14.31 and 14.34.

Clause 14.26(2): amended, on 24 March 2015, by clause 7(1) of the Electricity Industry Participation Code Amendment (Late and Revised Data) 2015.

Clause 14.26(2)(b): revoked, on 24 March 2015, by clause 7(2) of the Electricity Industry Participation Code Amendment (Late and Revised Data) 2015.

Clause 14.26(3): amended, on 24 March 2015, by clause 7(3) of the Electricity Industry Participation Code Amendment (Late and Revised Data) 2015.

#### **14.27 Dispute about amount may be referred to Rulings Panel**

- (1) If the dispute is not resolved within 15 **business days** after the date on which the dispute was notified to the **clearing manager** under clause 14.25(1), the disputing **participant** or the **clearing manager** may refer the dispute to the **Rulings Panel** for resolution.
- (2) The **Rulings Panel** may make such determination as it thinks fit.
- (3) The **Rulings Panel** must give notice of its determination to the parties to the dispute and affected **participants**.

#### **14.28 Correction of information about amount as result of dispute**

- (1) If a dispute (other than a dispute resolved by the time referred to in clause 14.26(2)) is resolved by the parties to the dispute agreeing, or the **Rulings Panel** determining, that information used to determine the amount is incorrect, the **clearing manager** and the **reconciliation manager** must correct the information as follows:
  - (a) if the information to be corrected is **volume information**, the information must be corrected in accordance with subclause (2):
  - (b) if the information to be corrected is not **volume information**—
    - (i) the **clearing manager** must either correct the information, or advise the appropriate **market operation service provider** or the **Authority** so that the information may be corrected; and
    - (ii) if a **market operation service provider** or the **Authority** corrects the information, the **market operation service provider** or the **Authority**, as the case may be, must provide the corrected information to the **clearing manager**.
- (2) The **reconciliation manager** must correct **volume information** as follows:
  - (a) if a revised **seasonal adjustment shape** must be issued in order for the **volume information** to be corrected—
    - (i) the **reconciliation manager** must provide each **reconciliation participant** whose **submission information** is required to be corrected with a revised **seasonal adjustment shape**; and
    - (ii) each **reconciliation participant** must provide corrected **submission information** to the **reconciliation manager** no later than 4 **business days** after being provided with the revised **seasonal adjustment shape**:
  - (b) if a revised **seasonal adjustment shape** is not required to be issued in order for the **volume information** to be corrected, each **reconciliation participant** whose **submission information** or **dispatchable load information** is required to be corrected must provide corrected **submission information** or **dispatchable load information** to the **reconciliation manager** no later than 4 **business days** after being notified of the resolution of the dispute:
  - (c) the **reconciliation manager** must provide the corrected **volume information** to the **clearing manager**.
- (3) If information is corrected under subclause (1) or (2), the **clearing manager** must advise the **Authority** and comply with any direction given by the **Authority** on the matter.

- (4) Without limiting subclause (3), a direction that the **Authority** gives under that subclause may include—
- (a) a direction to advise each **participant** of each amount owing and each amount payable by the **participant** by a date specified by the **Authority**; or
  - (b) a direction to conduct **washups** in accordance with subpart 6.

Clause 14.28(1): amended, on 24 March 2015, by clause 8(1) of the Electricity Industry Participation Code Amendment (Late and Revised Data) 2015.

Clause 14.28(3): amended, on 24 March 2015, by clause 8(2) of the Electricity Industry Participation Code Amendment (Late and Revised Data) 2015.

Clause 14.28(4): inserted, on 24 March 2015, by clause 8(3) of the Electricity Industry Participation Code Amendment (Late and Revised Data) 2015.

## Subpart 5—Payments

### 14.29 Payment of amounts payable

- (1) If the calculation under clause 14.22 provides for a **participant** to pay an amount to the **clearing manager**, the **participant** must pay that amount to the **clearing manager** in accordance with clauses 14.31 and 14.32.
- (2) If the calculation under clause 14.22 provides for the **clearing manager** to pay an amount to a **participant**, the **clearing manager** must pay that amount to the **participant** in accordance with clause 14.34.

### 14.30 Prepayment of amounts payable

- (1) A **participant** may elect to pay an amount to the **clearing manager** before the **participant** incurs the amount owing to the **clearing manager**.
- (2) If a **participant** prepays an amount to the **clearing manager** under subclause (1),—
  - (a) the **participant** must advise the **clearing manager** of 1 or more **billing periods** to which the payment relates; and
  - (b) the **clearing manager** must deduct the amount paid by the **participant** from the amount advised to the **participant** as owing by the **participant** to the **clearing manager** under subpart 4.
- (3) Any amount paid to the **clearing manager** under this clause must not be returned to the **participant**, except as provided in subclause (4).
- (4) If an amount prepaid by a **participant** is more than the actual amount payable by the **participant** to the **clearing manager** for the relevant **billing periods**, the **clearing manager** must—
  - (a) apply the amount to the amount payable in the next **billing period**; or
  - (b) if the **participant** requests the **clearing manager** to pay the residual amount to the **participant** and satisfies the **clearing manager** that it will continue to comply with prudential requirements in Part 14A, pay the residual amount to the **participant** in accordance with clause 14.34.
- (5) The **clearing manager** must credit to a **participant** that has prepaid an amount under this clause all interest received by the **clearing manager** on the prepaid amount, less any applicable deduction for tax purposes.

#### 14.31 Deadlines for payments

- (1) Subject to subclauses (3) and (4), each **participant** must pay the **clearing manager** the amount advised to the **participant** under subpart 4 as payable by the **participant** to the **clearing manager** by—
  - (a) 1300 hours on the 20th day of the month following the **billing period** in respect of which the amount was advised; or
  - (b) if that day is not a **business day**, 1300 hours on the next **business day**.
- (2) If the **clearing manager** does not advise a **participant** of an amount payable by the time specified in clause 14.18(2)(b)(i), payment may, if the **participant** so elects, be delayed for a period corresponding to the period of delay in advising the **participant** of the amount payable.
- (3) In the case of advice of an amount payable being delayed, the **clearing manager** must advise the **participant** of the new payment date.
- (4) If the **clearing manager** revises an amount advised to the **participant** 2 **business days** or more before the amount is due to be paid, the **participant** must pay the amount by the date for payment under subclause (1).

Clause 14.31(1)(a): amended, on 5 October 2017, by clause 498 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 14.31(2): amended, on 24 March 2015, by clause 9 of the Electricity Industry Participation Code Amendment (Late and Revised Data) 2015.

#### 14.32 Methods of payment

- (1) Subject to subclause (2), each **participant** must pay the **clearing manager** in **cleared funds** into the **operating account**.
- (2) A **participant** may instruct the **clearing manager** to pay all or part of an amount payable by the **participant** under clause 14.31 from a **cash deposit** held by the **clearing manager** in respect of the **participant** in accordance with clause 14A.13.
- (3) The **clearing manager** is not required to comply with an instruction given under subclause (2) unless it is received at least 2 **business days** before the **participant** is required under clause 14.31 to pay the **clearing manager** the amount to which the instruction relates.
- (4) However, the **participant** may request that the **clearing manager** comply with an instruction received later than provided for in subclause (3), and the **clearing manager** may agree to comply with such an instruction.

Clause 14.32(3) and (4): inserted, on 24 March 2015, by clause 11 of the Electricity Industry Participation Code Amendment (Settlement and Prudential Security) 2014.

#### 14.33 Allocation of payments

- (1) Subject to subpart 8, the allocation by the **clearing manager** of a payment received from a **participant** under this Part must be dealt with in accordance with this clause.
- (2) The **clearing manager** must hold each amount paid into the **operating account** by or on behalf of a **participant** in payment or part payment of an amount payable under this subpart upon trust for those persons that are entitled to receive payment from the **clearing manager**.
- (3) A **participant** may not direct the **clearing manager** to apply any funds paid under this Part other than in accordance with this clause.

- (4) The **clearing manager** must separately account for any amount received under clause 14.31 in respect of an amount referred to in clause 14.19(2)(h) and (i).

#### 14.34 Payments by clearing manager

- (1) Subject to subparts 7 and 8, the **clearing manager** must pay each **participant** the amount advised to the **participant** under subpart 4 as payable by the **clearing manager** to the **participant** by 1600 hours on the final **business day** for payment under clause 14.31.
- (2) The **clearing manager** must pay each **participant** in **cleared funds**.
- (3) A **participant** may instruct the **clearing manager** to treat all or part of an amount payable to the **participant** under this clause as a **cash deposit** under Part 14A.
- (4) The **clearing manager** is not required to pay a **participant** under this clause if a **settlement default** is continuing in relation to the **participant**.
- (5) The **clearing manager** is not required to comply with an instruction given under subclause (3) unless it is received at least 2 **business days** before the **participant** is required under clause 14.31 to pay the **clearing manager** the amount to which the instruction relates.
- (6) However, the **participant** may request that the **clearing manager** comply with an instruction received later than provided for in subclause (5), and the **clearing manager** may agree to comply with such an instruction.

Clause 14.34(5) and (6): inserted, on 24 March 2015, by clause 12 of the Electricity Industry Participation Code Amendment (Settlement and Prudential Security) 2014.

#### 14.35 Payment of residual loss and constraint excess

Each **grid owner** must treat **residual loss and constraint excess** paid to it under this Part as **loss and constraint excess**.

### Subpart 6—Washups

#### 14.36 Clearing manager to conduct washups

If the **clearing manager** receives corrected information in accordance with clauses 8.68, 8.69, 15.20C(b), 15.26(4), or clause 28 of Schedule 15.4, it must conduct **washups** and advise **participants** of amounts owing in accordance with this subpart.

Clause 14.36: amended, on 24 March 2015, by clause 10 of the Electricity Industry Participation Code Amendment (Late and Revised Data) 2015.

#### 14.37 Clearing manager to advise participants of washup amounts

The **clearing manager** must advise relevant **participants** of amounts owing in respect of **washup** amounts in accordance with subpart 4 and clauses 14.38 to 14.40, except that the **clearing manager** must, if requested by a **participant** affected by the **washup**, issue corrected information covered by the **washup** to the **participant**.

#### 14.38 Washup amounts

- (1) All **washup** amounts and interest accrued in accordance with subclause (2) must be expressed as an amount owing by the **participant** to the **clearing manager** or an amount owing by the **clearing manager** to the **participant** in respect of the current



**billing period.**

- (2) Daily interest (less any deduction for resident withholding tax) on the **washup** amount, calculated at the **bank bill bid rate**, accrues from the date that payment of the amount based on the incorrect information to which the **washup** relates was due as set out in clauses 14.31 and 14.34 (as applicable) until the date of advice of the revised **washup** amount in accordance with clause 14.18, and must be compounded at the end of each calendar month.

**14.39 Washups for grid owners**

If a **washup** has occurred due to incorrect **consumption information** being used to determine amounts owing in accordance with subpart 4 that affects **grid owners**, the **clearing manager** must credit or debit a **washup** amount to or from each **grid owner** as follows:

- (a) if a **grid owner's washup** amount is a credit, the **clearing manager** must add the credit to any amount owing to the **grid owner** in accordance with clause 14.16(7) in respect of the current **billing period**:
- (b) if a **grid owner's washup** amount is a debit, the **clearing manager** must subtract the debit from any amount owing to the **grid owner** in accordance with clause 14.16(7) in respect of the current **billing period**:
- (c) if the **washup** amount is greater than the amount owing, the **clearing manager** must advise the **grid owner** of any amount owing for the **washup** amount concurrently with advising **participants** of any amount owing under clause 14.18, and payment of the **washup** amount must be made by the **grid owner** by the time for payment set out in clause 14.31:
- (d) daily interest (less any deduction for resident withholding tax) on the **washup** amount, calculated at the **bank bill bid rate**, must be debited or credited (as the case may be) to the amount owing to the **grid owner** in accordance with clause 14.16(7), and accrues from the date that payment based on the incorrect information to which the **washup** relates was made until the date of advice in accordance with clause 14.18 resulting in the **grid owner's washup** amount, and must be compounded at the end of each calendar month.

**14.40 Payment where no longer participant**

- (1) Despite clauses 14.38 and 14.39, if a **washup** amount affects a person that is no longer a **participant**, the **clearing manager** must advise the person of the **washup** amount owing and payable in accordance with clauses 14.31 and 14.32.
- (2) The person remains liable for outstanding obligations in accordance with section 30(3) of the **Act**.
- (3) Daily interest (less any deduction for resident withholding tax) on the **washup** amount, calculated at the **bank bill bid rate**, must be added to the **washup** amount and accrues from the date that payment of the amount based on the incorrect information to which the **washup** relates was due as set out in 14.31 and 14.34 (as applicable) until the date of advice of the revised **washup** amount in accordance with clause 14.18, and must be compounded at the end of each calendar month.

## Subpart 7—Events of default

### *Types of default*

#### **14.41 Definition of an event of default**

- (1) Each of the following events constitutes an **event of default**:
- (a) failure of a **participant** to provide security for the minimum amount required in accordance with clause 14A.6:
  - (b) a **settlement default**:
  - (c) any action taken for, or with a view to, the declaration of a **participant** that is required to comply with Part 14A as a corporation at risk under the Corporations (Investigation and Management) Act 1989:
  - (d) appointment of a statutory manager in respect of **participant** that is required to comply with Part 14A under the Corporations (Investigation and Management) Act 1989 (or a recommendation or submission is made by a person to the Financial Markets Authority supporting such an appointment):
  - (e) appointment of a person under section 19 of the Corporations (Investigation and Management) Act 1989 to investigate the affairs or run the **business** of a **participant** that is required to comply with Part 14A:
  - (f) if a **participant** that is required to comply with Part 14A is (or admits that it is or is deemed under any applicable law to be) unable to pay its debts as they fall due or is otherwise insolvent, or stops or suspends, or threatens to stop or suspend, or a moratorium is declared on, payment of its indebtedness generally, or makes or commences negotiations or takes any other steps with a view to making any assignment or composition with, or for the benefit of, its creditors, or any other arrangement for the rescheduling of its indebtedness or otherwise with a view to avoiding, or in expectation of its inability to pay, its debts:
  - (g) a holder of a security interest or other encumbrancer taking possession of, or a receiver, manager, receiver and manager, liquidator, provisional liquidator, trustee, statutory or official manager or inspector, administrator or similar officer being appointed in respect of the whole or any part of the assets of a **participant** that is required to comply with Part 14A or if the **participant** requests that such an appointment be made:
  - (h) termination of a **trader's use-of-system agreement** with a **distributor** because of a **serious financial breach** if—
    - (i) the **trader** continues to have a **customer** or **customers** on the **distributor's local network** or **embedded network**; and
    - (ii) there are no unresolved disputes between the **trader** and the **distributor** in relation to the termination; and
    - (iii) the **distributor** has not been able to remedy the situation in a reasonable time; and
    - (iv) the **distributor** gives notice to the **Authority** that this subclause applies.
- (2) If a **distributor**, having given notice under subclause (1)(h)(iv), considers that an **event of default** no longer exists, the **distributor** must advise the **Authority** that it considers

that the **event of default** has been remedied.

Clause 14.41(h): inserted, on 24 March 2015, by clause 13 of the Electricity Industry Participation Code Amendment (Settlement and Prudential Security) 2014.

Clause 14.41(h): amended, on 24 March 2015, by clause 11 of the Electricity Industry Participation Code Amendment (Late and Revised Data) 2015.

Clause 14.41(h)(i) and (iv): amended, on 1 February 2016, by clause 91(1) and (2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

Clause 14.41(2): inserted, on 1 February 2016, by clause 91(3) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

#### *Procedure for event of default*

#### **14.42 Clearing manager to advise Authority of anticipated event of default**

- (1) If the **clearing manager** believes that an **event of default** is likely to occur, the **clearing manager** must advise the **Authority** so that the **Authority** can consider an appropriate course of action.
- (2) If the **clearing manager**, having advised the **Authority** under subclause (1), no longer believes that an **event of default** is likely to occur, the **clearing manager** must advise the **Authority** that it no longer believes that the **event of default** is likely to occur.

Clause 14.42(2): inserted, on 1 February 2016, by clause 92 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

#### **14.43 Procedure upon event of default**

- (1) If an **event of default** occurs in relation to a **participant**, the **participant** must immediately advise the **clearing manager** and the **Authority** of the **event of default**.
- (2) Despite subclause (1), a **participant** is not required to advise the **clearing manager** or the **Authority** if the **participant** would breach section 36 of the Corporations (Investigation and Management) Act 1989 by advising the **clearing manager** or the **Authority**.
- (3) If subclause (2) applies, the **participant** must seek the consent of the Registrar of Companies or the Financial Markets Authority (as applicable) to disclose the matter to the **clearing manager** and the **Authority**.
- (3A) If a **participant**, having advised of an **event of default** under subclause (1), considers that the **event of default** has been remedied, the **participant** must advise the **clearing manager** that it considers that the **event of default** has been remedied.
- (3B) If the **clearing manager** has been advised under subclause (3A) that the **participant** considers that an **event of default** has been remedied, the **clearing manager** must—
  - (a) decide whether it agrees that the **event of default** has been remedied; and
  - (b) if it agrees, advise the **Authority** that it considers that the **event of default** has been remedied.
- (4) If the **clearing manager** becomes aware that an **event of default** under paragraphs (a) to (g) of clause 14.41 has occurred and is continuing in relation to a **participant**, the **clearing manager** must—
  - (a) advise the **Authority** that the **event of default** has occurred; and
  - (b) if the **participant** has not advised the **clearing manager** of the **event of default**, advise the defaulting **participant** that the **event of default** has occurred.
- (4A) If the **clearing manager**, having advised of an **event of default** under subclause (4), considers that the **event of default** has been remedied, the **clearing manager** must

advise the **Authority** that it considers that the **event of default** has been remedied.

(5) *[Revoked]*

Clause 14.43(3A) and (3B): inserted, on 1 February 2016, by clause 93(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

Clause 14.43(4): substituted, on 24 March 2015, by clause 14(1) of the Electricity Industry Participation Code Amendment (Settlement and Prudential Security) 2014.

Clause 14.43(4A): inserted, on 1 February 2016, by clause 93(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

Clause 14.43(5): revoked, on 24 March 2015, by clause 14(2) of the Electricity Industry Participation Code Amendment (Settlement and Prudential Security) 2014.

*Remedies and rights of recovery*

**14.44 Event of default gives clearing manager remedies**

- (1) If an **event of default** has occurred, the **clearing manager** has the power to exercise, as appropriate, all or any of the following remedies without prejudice to any other remedy it may have at law:
- (a) apply the balance of the **cash deposit** of the defaulting **participant** in accordance with clause 14A.13(a);
  - (b) make a demand under a guarantee, letter of credit, or bond provided under Part 14A in respect of the defaulting **participant**;
  - (c) if the defaulting **participant** has not paid an amount due under this Part by the due date for payment, set-off any amount payable by the **clearing manager** to the defaulting **participant** against the unpaid amount payable by the defaulting **participant** to the **clearing manager**;
  - (d) take possession of any **FTR** held by the defaulting **participant** in accordance with clause 14.47.
- (2) If an **event of default** is continuing at the expiry of the **participant's** post-default exit period registered under clause 14A.22,—
- (a) the **clearing manager** must cancel a **hedge settlement agreement** to which the defaulting **participant** is a party in accordance with clause 14.48;
  - (b) the **Authority** may direct a **grid owner** or **distributor** to exercise any contractual right the **grid owner** or **distributor** has to **electrically disconnect** a defaulting **participant** that is a **direct purchaser** in accordance with clause 14.49.

Clause 14.44(2)(b): amended, on 5 October 2017, by clause 499 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

**14.45 Remedies for settlement default**

If the **clearing manager** elects to exercise any of the remedies specified in clause 14.44 in the event of a **settlement default**, the **clearing manager** must exercise the remedies in the following order:

- (a) set-off the amount payable by the **clearing manager** to the defaulting **participant** against any amount that is payable by the defaulting **participant** to the **clearing manager** in respect of the current **billing period** or any other **billing period**;
- (b) apply the balance of the **cash deposit** of the defaulting **participant**;
- (c) if the amounts set-off or applied under paragraphs (a) and (b) are not sufficient to remedy the default,—
  - (i) make a demand under a guarantee, letter of credit, or bond provided under

Part 14A in respect of the defaulting **participant**:

- (ii) take possession of any **FTR** held by the defaulting **participant** in accordance with clause 14.47.

#### 14.46 Remedies for other types of default

If an **event of default** other than a **settlement default** occurs in relation to a **participant**, the **clearing manager** must exercise all or any of the remedies specified in clause 14.44 to ensure that it has sufficient funds for the next settlement date.

#### 14.47 Application to take possession of FTR

- (1) The **clearing manager** on application to the **FTR manager** is entitled to be registered on the **FTR register** as the holder of any **FTR** that the **clearing manager** takes possession of under clause 14.44(1)(d) without any further authorisation than this subclause.
- (2) If the **FTR hedge values** or estimated **FTR hedge values** of the **FTRs** held by the defaulting **participant** exceed the amount required to remedy the **event of default**, the **clearing manager** may exercise its discretion in deciding which **FTRs** are transferred to the **clearing manager**.
- (3) If the amount received by the **clearing manager** on settlement or sale of an **FTR** taken possession of under clause 14.44(1)(d) exceeds the amount required to remedy the **event of default**, the **clearing manager** must repay the excess amount to the defaulting **participant**.
- (4) If the **clearing manager** holds an **FTR** in respect of which an amount would be owing if the **FTR** was held by another person, no amount is owing by the **clearing manager**.

#### 14.48 Cancellation of hedge settlement agreement in event of default

- (1) If the defaulting **participant** is a party to a **hedge settlement agreement** and the **event of default** is continuing at the expiry of the **participant's** post-default exit period registered under clause 14A.22, the **clearing manager** must cancel the **hedge settlement agreement** on the first **business day** after the expiry of the **participant's** post-default exit period.
- (2) The **clearing manager** must give written notice to the parties to the **hedge settlement agreement** if a **hedge settlement agreement** is cancelled under this clause.

#### 14.49 Electrical disconnection of direct purchaser

- (1) Each **direct purchaser** must at all times ensure that the terms of each of its contracts that provide for the **electrical connection** of the **direct purchaser** to a **network** permit the relevant **grid owner** or **distributor** to **electrically disconnect** the **direct purchaser** on the direction of the **Authority** if an **event of default** occurs in relation to the **direct purchaser** and is continuing at the expiry of its post-default exit period registered under clause 14A.22.
- (2) Each **grid owner** or **distributor** must at all times ensure that the terms of each of its contracts that provide for the **electrical connection** of a **direct purchaser** to a **network** permit the **grid owner** or **distributor** to **electrically disconnect** the **direct purchaser** on the direction of the **Authority** if an **event of default** occurs in relation to the **direct**

**purchaser** and is continuing at the expiry of its post-default exit period registered under clause 14A.22.

- (3) If an **event of default** occurs in relation to a **direct purchaser** and is continuing at the expiry of the **direct purchaser's** post-default exit period registered under clause 14A.22, the **Authority** may direct a **grid owner** or **distributor** to exercise any contractual right the **grid owner** or **distributor** has to **electrically disconnect** the defaulting **direct purchaser**.
- (4) A **grid owner** or **distributor** that receives a direction under subclause (3) must comply with the direction.

Clause 14.49 Heading: amended, on 5 October 2017, by clause 500(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 14.49(1): amended, on 5 October 2017, by clause 500(2) and (3) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 14.49(2): amended, on 5 October 2017, by clause 500(2) and (3) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 14.49(3): amended, on 5 October 2017, by clause 500(3) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

#### **14.50 Clearing manager to exercise rights to recover amounts outstanding**

The **clearing manager** must exercise such rights, including those rights under the **Act** and this Code, as is reasonable to recover any amounts outstanding from a defaulting **participant**.

#### **14.51 Participants assigned or subrogated to all clearing manager's rights of recovery**

- (1) If a **participant's** default means that the **clearing manager** is unable to pay **participants** the full outstanding amount that would otherwise be payable to them so that any amount paid to **participants** is reduced under subpart 8, the **participants** are entitled to be assigned or subrogated to the rights of the **clearing manager** in respect of amounts payable to the **clearing manager** by the relevant defaulting **participant** which, if paid, would have been required to be held on trust by the **clearing manager** for the **participants** in accordance with this Code.
- (2) The **clearing manager** must do all that is reasonably necessary, including the granting of a power of attorney in favour of the **participants**, to assist the **participants** in the exercise of the rights.
- (3) The **participants** may, in the name of the **clearing manager** (if requested),—
- (a) take any step to enforce repayment or exercise any other rights of the **clearing manager** in respect of money for the time being due to the **clearing manager**—
    - (i) from a defaulting **participant**; or
    - (ii) from a guarantor of the defaulting **participant**; or
    - (iii) from any person that has provided a letter of credit or bond in favour of the **clearing manager** in respect of the defaulting **participant**; or
    - (iv) in respect of any other security held by the **clearing manager** in respect of the defaulting **participant**; and
  - (b) directly or indirectly, prove in, claim, share in, or receive the benefit of any distribution, dividend, or payment arising out of—
    - (i) any insolvency of a defaulting **participant**; or
    - (ii) a guarantor of the defaulting **participant**; or

- (iii) any person that has provided a letter of credit or bond in favour of the **clearing manager** in respect of the defaulting **participant**; or
- (iv) any other security held by the **clearing manager** in respect of the defaulting **participant**.

#### 14.52 Rights of participants to exercise rights

- (1) Any 1 or more **participants** is entitled to exercise rights under clause 14.51, if—
  - (a) the **clearing manager** has not, within 3 **business days** of receiving notice of, or otherwise becoming aware of, the occurrence of an **event of default**, taken any action under clauses 14.44 to 14.46; or
  - (b) the **clearing manager** has failed within 2 months of an **event of default** to collect all amounts due from the defaulting **participant**.
- (2) Nothing in subclause (1) or this subpart limits the statutory right of the **clearing manager** to apply to the Court for the appointment of a receiver, interim liquidator, or liquidator.

#### *Publication of information about event of default*

#### 14.53 Authority may publish information about event of default

- (1) The **Authority** may **publish** information about an **event of default** if the **Authority** considers it is appropriate.
- (2) If an **event of default** results in a reduction in payments under subpart 8, the **Authority** must **publish** information about the following:
  - (a) the nature of the **event of default**;
  - (b) the extent of the **event of default**;
  - (c) the identity of the defaulting **participant**.

Clause 14.53 Heading: amended, on 5 October 2017, by clause 501(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 14.53(1) and (2): amended, on 5 October 2017, by clause 501(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### Subpart 8—Payments in event of settlement default

#### 14.54 Application of this subpart

- (1) This subpart applies if—
  - (a) a **participant** commits a **settlement default**; and
  - (b) the amount received from the defaulting **participant** and recovered or set-off under clause 14.44 by 1500 hours on the final day for payment under clause 14.31 is less than the amount payable by the **participant** to the **clearing manager**.
- (2) In this subpart a reference to 1 or more general amounts is a reference to any amount that is not required to be applied to the settlement of **FTRs** or paid to the **grid owner** as **residual loss and constraint excess**.

#### 14.55 Allocation of shortfall to settlement of general amounts and FTRs

- (1) The **clearing manager** must allocate any shortfall as a result of a **settlement default** to adjust the settlement of general amounts and **FTRs** in accordance with this clause.

- (2) The shortfall is—
- (a) the amount payable by the defaulting **participant** to the **clearing manager** under subpart 5; minus
  - (b) any amount received from the defaulting **participant** and recovered or set-off under clause 14.44.
- (3) In respect of each defaulting **participant**, the amount of the shortfall that must be allocated to adjust the settlement of general amounts is the total shortfall, less the amount of the shortfall that must be allocated to adjust the settlement of **FTRs** in accordance with subclause (4).
- (4) In respect of each defaulting **participant**, the amount of the shortfall that must be allocated to adjust the settlement of **FTRs** is determined in accordance with the following formula:

$$X_{\text{FTR}} = X_{\text{TOT}} * (O_{\text{FTR}}/O_{\text{TOT}})$$

where

$X_{\text{FTR}}$  is the amount of the shortfall that must be allocated to adjust the settlement of **FTRs**

$X_{\text{TOT}}$  is the amount of the total shortfall

$O_{\text{FTR}}$  is the total amount owing by the defaulting **participant** to the **clearing manager** in respect of **FTRs** as specified under clause 14.19(2)(h) and (i)

$O_{\text{TOT}}$  is the total amount owing by the defaulting **participant** to the **clearing manager** as specified under clause 14.19(3)

- (5) If the total amount owing by a defaulting **participant** as specified under clause 14.19(3) includes an amount owing in respect of the assignment of any **FTR** under clause 14.19(2)(i) that relates to a future **billing period** or **billing periods**, a portion of the amount of the shortfall that must be allocated to adjust the settlement of **FTRs** under subclause (4) must be allocated to each future **billing period** in accordance with the following formula:

$$F_{\text{FTR}} = X_{\text{FTR}} * (O_{\text{FTR (future)}}/O_{\text{FTR}})$$

where

$F_{\text{FTR}}$  is the amount of the shortfall that must be allocated to adjust the settlement of **FTRs** in the future **billing period**

$X_{\text{FTR}}$  is the amount of the shortfall that must be allocated to adjust the settlement of **FTRs**, calculated under subclause (4)

$O_{\text{FTR (future)}}$  is the amount owing by the defaulting **participant** to the **clearing manager** in respect of the assignment of an **FTR** under clause 14.19(2)(i) that relates to the future **billing period**

$O_{\text{FTR}}$  is the total amount owing by the defaulting **participant** to the **clearing manager** in respect of **FTRs** as specified under clause 14.19(2)(h) and (i)

Clause 14.55(4): amended, on 24 March 2015, by clause 15 of the Electricity Industry Participation Code



Amendment (Settlement and Prudential Security) 2014.

#### 14.56 Calculation of revised amount owing for general amounts

- (1) The **clearing manager** must apply any amount available for the settlement of general amounts in accordance with the following order of priority:
- (a) to satisfy any liability to pay **GST** and other governmental charges or levies, that are payable by the **clearing manager** in respect of the amounts owing and payable under subparts 4 to 6, taking into account any **GST** input tax credits available to the **clearing manager** in respect of payments under paragraphs (b) to (e):
  - (ab) *[Revoked]*
  - (b) to satisfy any amounts owing to the following parties, pro rata according to the amounts owing to them for **ancillary services** or **extended reserve** (as the case may be):
    - (i) the **system operator** for **ancillary services** under clauses 8.6, 8.31(1)(a), and 8.55 to 8.67:
    - (ii) an **extended reserve provider** for **extended reserve** under clauses 8.55(2) and 8.68(4):
  - (c) to satisfy any amount of **loss and constraint excess** to be applied to the settlement of **FTRs** under clause 14.16(4) or (5):
  - (d) to satisfy any amount owing to each **grid owner** for any **loss and constraint excess** in accordance with clause 14.16(7)(a):
  - (e) to satisfy any other general amount owing by the **clearing manager** to a **participant**.
- (2) If there is an insufficient amount available for the settlement of general amounts, the **clearing manager** must calculate the revised amounts owing by the **clearing manager** to **participants** in respect of general amounts as follows:
- (a) first apply the full amount available to satisfy each amount owing in the order of priorities in subclause (1):
  - (b) if there is an insufficient amount to satisfy the full amount owing under any of paragraphs (a) to (e) of subclause (1), calculate the revised amount owing to each **participant** under that paragraph according to the following formula:

$$AO_{CM (revised)} = AO_{CM (general)} \times (A_{general}/R_{general})$$

where

$AO_{CM (revised)}$  is the revised amount owing by the **clearing manager** to the **participant** in respect of the general amounts

$AO_{CM (general)}$  is the amount owing by the **clearing manager** to the **participant** in respect of that **billing period** under the relevant paragraph in subclause (1)

$A_{general}$  is the total amount available for the settlement of amounts owing by the **clearing manager** in the relevant **billing period** under the relevant paragraph in subclause (1)

$R_{\text{general}}$  is the sum of all amounts required to settle those amounts in respect of the **billing period**

Clause 14.56(1)(ab): inserted, on 24 March 2015, by clause 30 of the Electricity Industry Participation Code Amendment (Extended Reserve) 2014.

Clause 14.56(1)(ab): revoked, on 19 January 2017, by clause 15(1) of the Electricity Industry Participation Code Amendment (Extended Reserve) 2016.

Clause 14.56(1)(b): replaced, on 19 January 2017, by clause 15(2) of the Electricity Industry Participation Code Amendment (Extended Reserve) 2016.

#### 14.57 Calculation of revised amount owing for FTR amounts

- (1) The **clearing manager** must apply any amount available for the settlement of **FTRs** in accordance with the following order of priority:
  - (a) to satisfy any amount owing to a **participant** in respect of **FTRs**:
  - (b) to satisfy any amount owing to each **grid owner** for any **residual loss and constraint excess** under clause 14.16(7)(b).
- (2) If there is an insufficient amount available for the settlement of **FTRs**, the **clearing manager** must calculate the revised amount owing in respect of **FTRs** as follows:
  - (a) first apply the amount available for the settlement of **FTRs** in the relevant **billing period** to satisfy each amount owing to a **participant** in respect of an **FTR**:
  - (b) if there is an amount remaining for the settlement of **FTRs** in the relevant **billing period** after the **clearing manager** has satisfied each amount owing to a **participant** in respect of an **FTR**, the **clearing manager** must allocate that amount to each **grid owner** under clause 14.16(7)(b):
  - (c) if there is an insufficient amount to satisfy each amount owing under paragraph (a), the **clearing manager** must adjust each amount owing to a **participant** in respect of an **FTR** according to the following formula:

$$AO_{\text{CM (revised)}} = AO_{\text{CM (FTRs)}} * (C_{\text{FTR}}/\text{FTR}_{\text{required}})$$

where

$AO_{\text{CM (revised)}}$  is the revised amount owing by the **clearing manager** to the **participant** in respect of **FTRs**

$AO_{\text{CM (FTRs)}}$  is the amount advised to the **participant** under clause 14.20 as being owing to the **participant** in respect of that **billing period** in respect of an amount specified in clause 14.20(2)(h) or (i)

$C_{\text{FTR}}$  is the total amount available for the settlement of **FTRs** in the relevant **billing period**

$\text{FTR}_{\text{required}}$  is the sum of all amounts required to settle **FTRs** in respect of the **billing period**

#### 14.58 Calculation of scaled amount payable

The **clearing manager** must calculate the scaled amount payable for each **participant** to which an amount is payable by the **clearing manager** under subpart 5 in accordance with the following formula:

$$AP_{CM \text{ (scaled)}} = AO_{CM \text{ (revised)}} - AO_P + P$$

where

$AP_{CM \text{ (scaled)}}$  is the scaled amount payable by the **clearing manager** to the **participant**

$AO_{CM \text{ (revised)}}$  is the sum of the revised amounts owing by the **clearing manager** to the **participant**, calculated under clauses 14.56 and 14.57

$AO_P$  is the sum of the amounts owing by the **participant** to the **clearing manager**, calculated under clause 14.19

$P$  is any amount payable by the **participant** under clause 14.31 and, in the case of a defaulting **participant**, that amount minus any amount set-off under clause 14.44(1)(c)

Clause 14.58: amended, on 24 March 2015, by clause 16 of the Electricity Industry Participation Code Amendment (Settlement and Prudential Security) 2014.

#### 14.59 Calculation of revised amount payable

- (1) If the application of the formula in clause 14.58 results in a scaled amount payable that is positive or 0 for every **participant** to which an amount is payable by the **clearing manager**, the scaled amount payable by the **clearing manager** to a **participant** is the revised amount payable by the **clearing manager** under clause 14.60.
- (2) *[Revoked]*
- (3) *[Revoked]*
- (4) If the application of the formula in clause 14.58 results in a scaled amount payable that is negative for 1 or more **participants** to which an amount is payable by the **clearing manager**, the **clearing manager** must calculate the revised amount payable by the **clearing manager** under clause 14.60 as follows:
  - (a) for each **participant** for which the scaled amount payable is negative, set the revised amount payable for the **participant** to 0;
  - (b) for each **participant** for which the scaled amount payable is positive, calculate the revised amount payable to the **participant** in accordance with the following formula:

$$AP_{CM \text{ (revised)}} = AP_{CM \text{ (scaled)}} + AP_{\text{negative}} (AO_{CM \text{ (revised)}} / AO_{\text{positive}})$$

where

$AP_{CM \text{ (revised)}}$  is the revised amount payable by the **clearing manager** to the **participant**

$AP_{CM \text{ (scaled)}}$  is the scaled amount payable by the **clearing manager** to the **participant**, calculated under clause 14.58

- $AP_{\text{negative}}$  is the sum of all scaled amounts payable by the **clearing manager** to the **participant** for every **participant** for which the scaled amount payable is negative
- $AO_{\text{CM (revised)}}$  is the sum of the revised amounts owing by the **clearing manager** to the **participant**, calculated under clauses 14.56 and 14.57
- $AO_{\text{positive}}$  is the sum of all revised amounts owing by the **clearing manager** to a **participant** for every **participant** for which the scaled amount payable is positive

- (5) If the application of the formula in subclause (4)(b) results in a **participant** having a revised amount payable that is negative, the **clearing manager** must recalculate the revised amount payable for each **participant** under subclause (4) using the revised amount payable by the **clearing manager** to the **participant** as the scaled amount payable by the **clearing manager** to the **participant**.

Clause 14.59(2): amended, on 24 March 2015, by clause 17(1) of the Electricity Industry Participation Code Amendment (Settlement and Prudential Security) 2014.

Clause 14.59(2) and (3): revoked, on 24 March 2015, by clause 12(1) of the Electricity Industry Participation Code Amendment (Late and Revised Data) 2015.

Clause 14.59(4): amended, on 24 March 2015, by clause 12(2) of the Electricity Industry Participation Code Amendment (Late and Revised Data) 2015.

Clause 14.59(4)(b): amended, on 24 March 2015, by clause 17(2) and (3) of the Electricity Industry Participation Code Amendment (Settlement and Prudential Security) 2014.

#### 14.60 Payment of revised amount payable

The **clearing manager** must pay each **participant** the revised amount payable in accordance with clause 14.34 as if references to the amount payable were references to the revised amount payable.

#### 14.61 Payment by participant with negative scaled amount payable

- (1) If the application of the formula in clause 14.58 results in a scaled amount payable for a **participant** that is negative, the **participant** must pay an amount that is equal to the absolute value of the scaled amount payable in accordance with this clause.
- (2) The **clearing manager** must advise the **participant** of the amount payable.
- (3) The **participant** must pay the amount payable to the **clearing manager** by 1300 hours on the next **business day** after the day on which the **clearing manager** advises the **participant** of the amount.
- (4) Clause 14.32 applies to a payment under this clause.
- (5) If the **clearing manager** receives further funds from the defaulting **participant**, the **clearing manager** may revise or cancel the amount payable under this clause to reflect the need for the amount payable.

#### 14.62 Application of payment by participant with negative scaled amount payable

- (1) The **clearing manager** must allocate the funds received under clause 14.61 to each **participant** for which the scaled amount payable is positive.
- (2) The amount allocated to each **participant** under this clause is the difference between the scaled amount payable and revised amount payable for the **participant**.

- (3) The **clearing manager** must pay each **participant** the amount allocated under this clause by 1600 hours on the day that funds are received under clause 14.61.
- (4) If there are insufficient funds to pay each **participant** the amount allocated under this clause, the **clearing manager** must adjust the amount payable for each **participant** based on the proportion that the amount payable by the **clearing manager** to the **participant** bears to the total amount payable to all **participants** under this clause.

#### 14.63 Further funds paid according to priority

- (1) As further funds are received or recovered from a defaulting **participant** by the **clearing manager**, those funds must be allocated to the settlement of general amounts and **FTRs** and paid in accordance with this subpart as if—
  - (a) the further funds had been paid by the defaulting **participant** on the final day for payment under clause 14.31; but
  - (b) with the amount already paid by the **clearing manager** to a **participant** under this subpart deducted from the amount calculated as payable by the **clearing manager** to the **participant**.
- (2) If funds received or recovered by the **clearing manager** are identifiable as relating to a specific **billing period**, the **clearing manager** must apply those funds in satisfaction or part satisfaction of amounts payable by the **clearing manager** in respect of that **billing period**.
- (3) If it is not clear to which **billing period** the funds relate, the funds must be applied in satisfaction or part satisfaction of amounts payable by the **clearing manager** in respect of the earliest **billing period** in respect of which amounts are outstanding to the extent that full payment has not been received by the relevant **participants** in respect of that **billing period**.

#### 14.64 Interest payable to participants

- (1) If a **participant** does not receive the full amount payable under this Part, the **clearing manager** is liable to pay interest on the unpaid amount.
- (2) The interest must be calculated daily from the date payment would otherwise have been due, at the **default interest rate**, until the date that payment is actually made by the **clearing manager** to the **participant** and compounded at the end of each calendar month.
- (3) If a **participant** has not paid any amount payable under this Part after the due date for payment, the **participant** must pay interest on the unpaid amount.
- (4) The interest must be calculated daily from the date on which the payment was due, at the **default interest rate**, until the date that full payment is received in **cleared funds** and compounded at the end of each calendar month.

#### 14.65 Participant to remain in default

Despite anything else in this Code, the application of money under this Part that does not satisfy the full amount payable by a **participant** does not—

- (a) satisfy the obligation of the **participant** to pay the full amount payable together with the interest due on that amount to the **clearing manager** or to a **participant** acting in accordance with clause 14.51; or

- (b) prejudice any remedy available to the **clearing manager** in an **event of default** or to a **participant** under clause 14.51.

## Subpart 9—Administrative obligations of clearing manager

### *Clearing manager operating account*

#### **14.66 Clearing manager to establish operating account**

- (1) The **clearing manager** must establish, in its name, an **operating account** with a **bank**.
- (2) The **operating account** must—
  - (a) be held by the **clearing manager** as a trust account for the benefit of the persons who are entitled to receive payment from the **clearing manager** under this Part; and
  - (b) be clearly identified as such; and
  - (c) subject to this Code, be entirely separate from the **cash deposit accounts** and any other account of the **clearing manager**.
- (3) The **clearing manager** must obtain an acknowledgement from the **bank** with which the **operating account** is held that—
  - (a) the funds in that account are held on trust for the purposes set out in clause 14.33; and
  - (b) the **bank** has no right of set-off or combination in relation to the funds.

#### **14.67 Payment by clearing manager**

- (1) Each payment required to be made by the **clearing manager** to the person entitled to the payment must be made by direct payment to the **bank** account that the person entitled to the payment may advise the **clearing manager** in writing from time to time.
- (2) Any payment by the **clearing manager** under this Part must be made from the **operating account**.
- (3) Except as expressly permitted by this Code or as required by law, all payments by the **clearing manager** under this Part must be free and clear of any withholding or deduction and without any set-off or counter claim.

### *Reporting obligations of the clearing manager*

#### **14.68 Monthly divergence reports to be prepared by clearing manager**

- (1) The **clearing manager** must report to the **Authority** in writing under this clause.
- (2) The **clearing manager** must give the report to the **Authority**—
  - (a) on the 10th **business day** of each calendar month; or
  - (b) if exceptional circumstances prevent the **clearing manager** from providing the report by that day, as soon as reasonably practicable after that day.
- (3) The report must include—
  - (a) information on any situations where the **clearing manager** believes, on reasonable grounds, that the **clearing manager**, or another **participant**, has breached this Code in the previous calendar month; and

- (b) the date and time at which each alleged breach took place; and
- (c) the nature of each alleged breach, including—
  - (i) details of the person alleged to be in breach; and
  - (ii) any **participants** believed to be affected by the alleged breach; and
  - (iii) in the case of a delay in advising a **participant** of an amount owing under clause 14.18, the part of the process that was delayed; and
- (d) the reason for the alleged breach occurring if the **clearing manager** is aware of the reason; and
- (e) situations in which information about an amount owing was or will be issued late and whether or not the delay was caused by the **clearing manager**.

Clause 14.68(1) and (2): amended, on 5 October 2017, by clause 502 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

#### 14.69 Authority to publish clearing manager reports

- (1) By the 15th **business day** of each calendar month, the **Authority** must **publish** the sections of the report, received in the previous calendar month from the **clearing manager** in accordance with clause 14.68, that relate to any breaches of this Code by the **clearing manager**.
- (2) *[Revoked]*

Clause 14.69 Heading: amended, on 5 October 2017, by clause 503(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 14.69(1): amended, on 5 October 2017, by clause 503(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 14.69(2): revoked, on 5 October 2017, by clause 503(3) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

#### 14.70 Right to information concerning clearing manager's action

- (1) A **participant** may, by notice in writing to the **clearing manager**, request further information related to a situation set out in a **clearing manager's** report **published** under clause 14.69 that has materially affected that person.
- (2) The **clearing manager** must provide the requested information to that person, but the information provided must not include any information that is confidential in respect of any other person.

#### 14.71 Clearing manager to make block dispatch settlement differences available

- (1) By 0900 hours on the 2nd **business day** after the **clearing manager** has advised **participants** of amounts owing under clause 14.18, the **clearing manager** must make the following information available for **participants** on **WITS**:
  - (a) the maximum block dispatch settlement difference for each **block dispatch group** for the previous **billing period** as determined by the following formula:

$$\text{Settlement Difference} = \text{Max} \left\{ \sum_{\text{gip}=1}^{\text{gip}} P_{\text{gip}} \left\{ \text{Gen}_{\text{gip}} - \text{Set}_{\text{gip}} \left\{ \frac{\sum \text{Gen}_{\text{gip}}}{\sum \text{Set}_{\text{gip}}} \right\} \right\} \right\}$$

- (b) the total block dispatch settlement differences for each **block dispatch group** for the previous **billing period** as determined by the following formula:

$$\text{Settlement Difference} = \sum_{i=1}^i \left\{ \sum_{gip=1}^{gip} P_{gip,i} \left\{ \text{Gen}_{gip,i} - \text{Set}_{gip,i} \left\{ \frac{\sum_{gip} \text{Gen}_{gip,i}}{\sum_{gip} \text{Set}_{gip,i}} \right\} \right\} \right\}$$

where

- $P_{gip}$  is the **final price** at the relevant **grid injection point** for the **generating plant** or **generating unit** that forms part of the **block dispatch group** for the relevant **trading period** of the **billing period**
- $\text{Gen}_{gip}$  is the final quantity of **electricity** sold by that **generator** to the **clearing manager** at the relevant **grid injection point** for the **generating plant** or **generating unit** that forms part of the **block dispatch group**, obtained from the **reconciliation information** for the relevant **trading period** of the **billing period**
- $\text{Set}_{gip}$  is the generation quantity at the **relevant grid injection point** for the **generating plant** or **generating unit** that forms part of the **block dispatch group** for the relevant **trading period** of the **billing period**
- $P_{gip,i}$  is the **final price** at the relevant **grid injection point** for the **generating plant** or **generating unit** that forms part of the **block dispatch group** for the relevant **trading period** of the **billing period**
- $\text{Gen}_{gip,i}$  is the final quantity of **electricity** sold by that **generator** to the **clearing manager** at the relevant **grid injection point** for the **generating plant** and **generating units** that form part of the **block dispatch group**, obtained from the **reconciliation information** for the relevant **trading period** of the **billing period**
- $\text{Set}_{gip,i}$  is the generation quantity at the relevant **grid injection point** for the **generating plant** and **generating units** that form part of the **block dispatch group** for the relevant **trading period** of the **billing period**.

- (2) For the purposes of this clause “generation quantity” means the time-weighted average quantity of **electricity** for that **generating plant** or **generating unit** for the relevant **trading period**, taking into account—
- (a) the quantity in **MW** provided to the **clearing manager** by the **system operator** in accordance with clauses 13.76 to 13.80; and
- (b) the ramp rate applying to the relevant **trading period** that is specified in the **offer** submitted by that **generator**.

Clause 14.71 Heading: amended, on 5 October 2017, by clause 504(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 14.71(1): amended, on 5 October 2017, by clause 504(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.



**14.72 Clearing manager to make block dispatch settlement differences available later if WITS unavailable**

- (1) If **WITS** is unavailable to make the information set out in clause 14.71 available, the **clearing manager** is not obliged to follow any backup procedures in respect of making the information available.
- (2) The **clearing manager** must make the information available on **WITS** as soon as reasonably possible after **WITS** becomes available.

Clause 14.72 Heading: replaced, on 5 October 2017, by clause 505(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 14.72(1): amended, on 5 October 2017, by clause 505(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 14.72(2): replaced, on 5 October 2017, by clause 505(3) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

**14.73 Clause 14.71 applies to block dispatch groups only**

The calculation of the block dispatch settlement differences under clause 14.71 must be completed on a **block dispatch group** basis, even if a **block dispatch group** has been divided into **sub-block dispatch groups** during one or more **trading periods** of the relevant **billing period**.

**14.74 No washup calculation under clause 14.71 if revised reconciliation information is received**

Following the calculation and **publication** of the information relating to block dispatch settlement differences in a **billing period** under clause 14.71, the **clearing manager** is not required to recalculate any block dispatch settlement differences as a result of subsequently receiving revised **reconciliation information**.

*Notices*

**14.75 Notices**

- (1) Except as expressly provided in this Code, a notice or demand given or required to be given under this Part may be given by being delivered or transmitted to the intended recipient at its address or electronic address as last advised in writing to the sender and may be posted to such address by prepaid post.
- (2) Subject to subclause (3),—
  - (a) a notice or demand delivered by hand is deemed to be delivered on the date of such delivery; and
  - (b) a notice or demand delivered by post is deemed to be delivered on the 2<sup>nd</sup> **business day** following the date of posting; and
  - (c) a notice or demand transmitted through the **WITS** is deemed to be delivered on the date it was transmitted.
- (3) Any notice or demand delivered, or deemed to be delivered, on a day that is not a **business day**, or after 1600 hours on a **business day**, is deemed to have been delivered on the next **business day**.

Clause 14.75(2)(c): amended, on 5 October 2017, by clause 506 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

## Schedule 14.1

### Formula for scaling amount owing in respect of FTRs

cl 14.17

#### 1 Purpose of this Schedule

The purpose of this Schedule is to set out the formula for scaling the amount owing in respect of **FTRs** if clause 14.17(6) applies.

#### 2 Formula

- (1) The formula for scaling the **FTR hedge value** under clause 14.17(6) is as follows:

$$HV_{\text{Scaled}} = HV \times (C/D)$$

where

$HV_{\text{Scaled}}$  is the scaled **FTR hedge value**

$HV$  is the original **FTR hedge value** that would be owing if this subclause did not apply

$C$  is the amount calculated in accordance with the formula in subclause (2)

$D$  is the amount calculated in accordance with the formula in subclause (3)

- (2) The value for  $C$  in the formula in subclause (1) is as follows:

$$C = LCE_{\text{FTR}} + AC_P + A_P - AC_{\text{CM}} - A_{\text{CM}}$$

where

$LCE_{\text{FTR}}$  is the amount of the **loss and constraint excess** to be applied to the settlement of **FTRs** under clause 14.16(4) or (5)

$AC_P$  is the sum of any **FTR acquisition costs** owing to the **clearing manager**

$A_P$  is the sum of any amounts owing to the **clearing manager** under clause 13.249(4)

$AC_{\text{CM}}$  is the sum of any **FTR acquisition costs** owing by the **clearing manager**

$A_{\text{CM}}$  is the sum of any amounts owing by the **clearing manager** under clause 13.249(7)

- (3) The value for  $D$  in the formula in subclause (1) is as follows:

$$D = HV_{\text{CM}} - HV_P$$

where

$HV_{\text{CM}}$  is the sum of any **FTR hedge values** owing by the **clearing manager**

$HV_P$  is the sum of any **FTR hedge values** owing to the **clearing manager**

## Schedule 14.2 cl 14.21, 14A.5, Schedule 14A.1

### Consultation and approval requirements for methodologies

#### 1 Purpose of this Schedule

This Schedule sets out the consultation and approval requirements that apply to the following methodologies formulated and **published** by the **clearing manager**:

- (a) the methodology for determining the settlement retention amount under clause 14.21;
- (b) the methodology for determining the forward estimate of the minimum amount for which security will be required to be provided by a **participant** under clause 14A.5;
- (c) the methodology for determining the general prudential requirement under clause 8 of Schedule 14A.1;
- (d) the methodology for determining the minimum security required in respect of **FTRs** under clause 12 of Schedule 14A.1.

#### 2 Approval of methodology

- (1) The **clearing manager** must submit to the **Authority** for approval a draft methodology.
- (2) In preparing the draft methodology, the **clearing manager** must—
  - (a) consult with persons that the **clearing manager** thinks are representative of the interests of persons likely to be substantially affected by the methodology; and
  - (b) consider submissions made on the methodology.
- (3) The **clearing manager** must provide a copy of each submission received under subclause (2) to the **Authority**.
- (4) The **Authority** must, as soon as practicable after receiving the draft methodology, by notice in writing to the **clearing manager**—
  - (a) approve the methodology; or
  - (b) decline to approve the methodology.
- (5) If the **Authority** declines to approve the draft methodology, the **Authority** must **publish** the changes that the **Authority** wishes the **clearing manager** to make to the draft methodology.

#### 3 Consultation on proposed changes to methodology

- (1) When the **Authority publishes** the changes that the **Authority** wishes the **clearing manager** to make to the draft methodology under clause 2(5), the **Authority** must **publish** the date by which submissions on the changes must be received by the **Authority**.
- (2) Each submission on the changes to the draft methodology must be made in writing to the **Authority** and be received on or before the date specified by the **Authority** under subclause (1).
- (3) The **Authority** must—
  - (a) provide a copy of each submission received to the **clearing manager**; and
  - (b) **publish** the submissions.

- (4) The **clearing manager** may make its own submission on the changes to the draft methodology and the submissions received in relation to the changes.
- (5) The **Authority** must **publish** the **clearing manager's** submission when it is received.
- (6) The **Authority** must consider the submissions made to it on the changes to the draft methodology.
- (7) Following the consultation required by subclauses (1) to (6), the **Authority** may approve the methodology subject to the changes that the **Authority** considers appropriate being made by the **clearing manager**.

Clause 3(1): amended, on 5 October 2017, by clause 507 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

#### **4 Variations to methodology**

- (1) A **participant** or the **Authority** may submit a proposal for a variation to the methodology.
- (2) The **clearing manager** must provide a copy of each proposed variation received from a **participant** under subclause (1) to the **Authority**.
- (3) The **clearing manager** must consider a proposed variation to the methodology submitted under subclause (1).
- (4) The **clearing manager** may submit a request for a variation to the methodology to the **Authority**.
- (5) The consultation and approval requirements under clauses 2 and 3 apply to a request for a variation submitted under subclause (4) as if references to the draft methodology were a reference to the requested variation.
- (6) If the **clearing manager** does not submit a request for a variation submitted under subclause (1) to the **Authority** under subclause (4), the **Authority** may consider the proposal and require the **clearing manager** to submit a request for a variation based on the proposal to the **Authority**, and subclause (5) applies accordingly.
- (7) The **Authority** may approve a variation requested under subclause (4) or subclause (6) without complying with the provisions referred to in subclause (5) if—
  - (a) the **Authority** considers that it is necessary or desirable in the public interest that the requested variation be made urgently; and
  - (b) the **Authority publishes** a notice of the variation and a statement of the reasons why the urgent variation is needed.
- (8) Every variation made under subclause (7) expires on the date that is 9 months after the date on which the variation is made.

## Schedule 14.3

cl 14.16(2)

### Calculation of amount of loss and constraint excess to be applied to the settlement of FTRs

#### 1 Purpose

The purpose of this Schedule is to set out the formulae and process for the calculation under clause 14.16(2) of the amount of the **loss and constraint excess** to be applied to the settlement of **FTRs**.

#### 2 Interpretation

(1) In this Schedule, unless the context otherwise requires,—

**AC line** means any AC **branch**

**balanced**, in relation to an **FTR injection pattern**, means that the total positive and negative **hub injections** sum to 0. A **balanced FTR injection pattern** is consistent with a **grid** in which **losses** are not modelled

**binding**, in relation to a **constraint**, means that the **constraint** has a non-zero **shadow price**

**branch constraint** means a **constraint** in which all the **LHS** variables are branch flows

**canonical form** means a linear programming problem that is expressed in the following form:

maximise  $c^T x$

subject to  $Ax \leq b$

where

$x$  is the vector of variables to be determined

$c$  and  $b$  are vectors of constants

$A$  is a matrix of coefficients

$c^T x$  is the objective function to be maximised

$Ax \leq b$  is the set of **constraints**, each row of  $Ax$  being the **LHS** of a **constraint** and each element of  $b$  being the corresponding **RHS**

Minimum **constraints** are assumed to have been multiplied through by  $-1$  to form an equivalent maximum **constraint**

Equality **constraints** are assumed to have initially been represented by a pair of minimum and maximum **constraints** with the same **LHS** and **RHS**, and then the resulting minimum **constraint** is assumed to have been multiplied through by  $-1$  to form an equivalent maximum **constraint**

**closed**, in relation to a **branch**, means that the **branch** is **electrically connected** at both ends

**feasible region**, in relation to an n-dimensional linear programming problem, means the n-dimensional solution space filled by the set of all possible feasible solutions

**final pricing schedule** means the schedule that the **pricing manager** uses to produce the **interim prices** on which **final prices** are based

**FTR injection pattern** means the combination of positive or negative net **hub injections** implied by a combination of **FTRs**

**hub injection** means the actual or notional flow of **electricity** into the **grid**, if positive, or out of the **grid**, if negative, at any **hub**

**HVDC link** has the same meaning as in the **model formulation**

**LHS** means the left hand side of a **constraint** expressed in **canonical form**

**mixed constraint** has the same meaning as in the **model formulation**

**open**, in relation to a **branch**, means that the **branch** is **electrically disconnected** at 1 or both ends

**operational system split** means an instance where a **grid owner** chooses to operate with a switch or **branch open** for reasons such as—

- (a) breaking loops that would otherwise constrain flows; or
- (b) reducing the size of the maximum fault duty that switchgear needs to withstand

**RHS** means the right hand side of a **constraint** when expressed in **canonical form**

**scheduled**, in relation to a variable, means the value of the variable in the **final pricing schedule**

**shadow price**, in relation to an **AC line** capacity, **branch constraint** or **mixed constraint**, means the absolute value of the shadow price in \$/MWh for the **AC line** or **constraint** reported in the **final pricing schedule**

**simultaneously feasible**, in relation to an **FTR injection pattern**, means that the implied flows can be carried by the transmission system, subject to the **constraints** as defined by clause 5(2)

- (2) For the purposes of this Schedule, **constraints** that are not expressed in **canonical form** in the **model formulation** must be translated into the equivalent **canonical form**.

Clause 2(1) **closed**: amended, on 5 October 2017, by clause 508(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 2(1) **open**: amended, on 5 October 2017, by clause 508(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### 3 Amount of loss and constraint excess to be applied to settlement of FTRs

The amount of the **loss and constraint excess** that must be applied to the settlement of **FTRs** under clause 14.16(4) is the amount calculated under clause 9(6)(b).

#### **4 Grid owner must determine normal grid configuration**

- (1) Each **grid owner** must determine a normal **grid** configuration for the **grid owner's grid**.
- (2) The normal **grid** configuration determined under subclause (1) must be a **grid** configuration with all existing **branches** and switches **closed** except where the **grid owner** has implemented **operational system splits** and the **grid owner** considers that the normal state of those **operational system splits** is for the relevant **branch** or switch to be **open**.
- (3) Each **grid owner** must provide to the **FTR manager** the information describing the normal **grid** configuration for the **grid owner's grid** determined under subclause (1).
- (4) Each **grid owner** must determine a new normal **grid** configuration for the **grid owner's grid** if the **grid owner** considers it necessary because, for example, any of the following occur:
  - (a) some **grid** equipment is **commissioned** or **decommissioned**;
  - (b) there is a change in the capacity or impedance of some **grid** equipment;
  - (c) the **grid owner** considers that the normal state of any **operational system split** has changed.
- (5) Each **grid owner** must provide new information to the **FTR manager** if the **grid owner** determines a new normal **grid** configuration for the **grid owner's grid** under subclause (4), unless otherwise agreed with the **FTR manager**.

Clause 4(3) and (5): amended, on 24 March 2015, by clause 18 of the Electricity Industry Participation Code Amendment (Settlement and Prudential Security) 2014.

Clause 4(4)(a): amended, on 5 October 2017, by clause 509 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

#### **5 FTR manager must determine FTR injection patterns**

- (1) The **FTR manager** must determine a set of **balanced** extreme **FTR injection patterns**.
- (2) Each **balanced** extreme **FTR injection pattern** determined under subclause (1) must be **simultaneously feasible** assuming—
  - (a) the normal **grid** configuration determined under clause 4; and
  - (b) the absence of all other **grid** flows; and
  - (c) all **AC line** and **HVDC link** capacity limits applied; and
  - (d) all risk and reserve **constraints** disabled; and
  - (e) all **branch** variable **losses** set to 0; and
  - (f) all **branch** fixed **losses** set to 0.
- (3) The set of **balanced** extreme **FTR injection patterns** determined under subclause (1) must, in the reasonable opinion of the **FTR manager**, be the set of **FTR injection patterns** that best represents the extreme limits of the **feasible region** of **FTR injection patterns** as defined by the assumptions listed under subclause (2).
- (4) The **FTR manager** must determine a new set of **balanced** extreme **FTR injection patterns** if—
  - (a) a **grid owner** provides the **FTR manager** with new information under clause 4(5) that results in a change to the **feasible region** of **FTR injection patterns**; or
  - (b) there is a change to the **hubs** or set of **hubs** specified in the **FTR allocation plan**.

Clause 5(4)(a): amended, on 24 March 2015, by clause 19 of the Electricity Industry Participation Code Amendment (Settlement and Prudential Security) 2014.

**6 FTR manager must determine matrix of lossless shift factors**

- (1) For each **trading period** of the relevant **billing period**, following the **publication** of **final prices**, the **FTR manager** must determine a matrix of lossless shift factors referenced to a set of reference **nodes**, from the **input information** or revised data used to produce the **final pricing schedule**, in accordance with the following:
- (a) one reference **node** must be chosen within each electrical island;
  - (b) **nodes** are in the same electrical island if a transmission path exists between them.
- (2) The matrix of lossless shift factors determined under subclause (1) must be calculated in accordance with the following matrix formula:

$$[\text{ShiftFactor}] = [\text{AdmittancePrimitive}] \times [\text{Inc}] \times [\text{Impedance}]$$

where

$[\text{ShiftFactor}]$  is the  $m$  by  $n$  matrix of lossless shift factors, which defines the increment in flow in the conventional forward flow direction on any **branch** in the transmission **network** resulting from an increment in net **injection** at any **node** together with an equal decrement in net **injection** at the reference **node** in the electrical island in which the **node** resides, while neglecting the effect of **losses**

$[\text{AdmittancePrimitive}]$  is the  $m$  by  $m$  diagonal matrix formed from the set of  $m$  **branch** susceptances

$[\text{Inc}]$  is the  $m$  by  $n$  lossless **branch-node** incidence matrix, which denotes the conventional from and to **nodes** for a **branch** by matrix entries of 1 and  $-1$  respectively

$[\text{Impedance}]$  is the  $n$  by  $n$  matrix formed from the inverse of  $[\text{AdmittanceNodal}]$  with the columns and rows



- associated with the  
reference **nodes** reinserted  
and filled with zeroes
- [AdmittanceNodal] is the  $n-r$  by  $n-r$  matrix  
obtained from  
[AdmittanceNodalComplete] by deleting the column  
and row associated with  
each of the reference **nodes**
- [AdmittanceNodalComplete] is the  $n$  by  $n$  matrix =  
[Inc]<sup>T</sup> x  
[AdmittancePrimitive] x  
[Inc]
- [Inc]<sup>T</sup> is the  $n$  by  $m$  matrix  
transpose of [Inc]
- (3) For the purposes of subclauses (1) and (2) —
- (a) the set of inter-island **HVDC links** must be replaced by a single **AC line** with a nominal susceptance value between the Benmore and Haywards HVDC terminal **nodes**, whether or not any **HVDC link** is actually in service during the relevant **trading period**; and
  - (b) the nominal susceptance value determined under paragraph (a) may be any suitable value that will avoid numerical difficulties; and
  - (c) any switches between the Benmore HVDC terminal **node** and other Benmore **nodes** operating at the same nominal voltage that are normally **closed** must be treated as **closed**; and
  - (d) any switches between the Haywards HVDC terminal **node** and other Haywards **nodes** operating at the same nominal voltage that are normally **closed** must be treated as **closed**; and
  - (e) in any **trading period** in which any of the **hubs** reside in different electrical islands (as defined in subclause (1)(b)), the shift factor matrix for the previous **trading period** in which all the **hubs** resided in the same electrical island must be used.
- 7 FTR manager must determine branch participation loading and constraint participation loading**
- (1) For each **trading period** of the relevant **billing period**, the **FTR manager** must determine a **branch** participation loading for each **AC line**  $k$ .
  - (2) Each **branch** participation loading determined under subclause (1) must be calculated—
    - (a) in accordance with the following formula if the **scheduled** flow on the **AC line** is in the conventional forward flow direction:

$$\max \left( \sum_{h \in Hubs} SF_{k,h} \times Inj_{h,p} : p \in 1, \dots, P \right); \text{ and}$$

- (b) in accordance with the following formula if the **scheduled** flow on the **AC line** is in the conventional reverse flow direction:

$$- \min \left( \sum_{h \in Hubs} SF_{k,h} \times Inj_{h,p} : p \in 1, \dots, P \right)$$

where

$SF_{k,h}$  is the shift factor relating flows on **AC line**  $k$  to **injections** at **hub**  $h$ , determined under clause 6(1)

$Inj_{h,p}$  is the positive or negative **hub injection** at **hub**  $h$  in **FTR injection pattern**  $p$  in the set of  $P$  **balanced** extreme **FTR injection patterns** determined under clause 5(1)

- (3) For each **trading period** of the relevant **billing period**, for each **binding branch constraint**  $v$  involving **AC line** flows, the **FTR manager** must determine a **constraint participation loading** in accordance with the following formula:

$$\max \left( \sum_{k \in ACLineGroup_v} \sum_{h \in Hubs} weight_{k,v} \times SF_{k,h} \times Inj_{h,p} : p \in 1, \dots, P \right) \text{ where}$$

$SF_{k,h}$  and  $Inj_{h,p}$  are as defined in subclause (2)

$ACLineGroup_v$  is the set of **AC lines** involved in **branch constraint**  $v$  (any **HVDC link** flow terms in the **constraint** must be excluded from this calculation)

$weight_{k,v}$  is the weight associated with **AC Line**  $k$  in **branch constraint**  $v$  expressed in **canonical form**

- (4) For each **trading period** of the relevant **billing period**, for each **binding mixed constraint**  $v$  (if any) involving **AC line** flow terms or **AC line** variable loss terms, the **FTR manager** must determine a **constraint participation loading** in accordance with the following formula:

$$\max \left( \sum_{k \in ACLineGroup_v} (flowweight_{k,v} \times flow_{k,p} + lossweight_{k,v} \times loss_{k,p}) : p \in 1, \dots, P \right) \text{ where}$$

$ACLineGroup_v$  is the set of **AC lines** whose flows or variable **losses** are involved in **mixed constraint**  $v$  (all other terms in the **mixed constraint** must be excluded

from this calculation)

$flowweight_{k,v}$  is the weight associated with the flow on **AC Line  $k$**  in **mixed constraint  $v$**  expressed in **canonical form**

$lossweight_{k,v}$  is the weight associated with the variable **losses** on **AC Line  $k$**  in **mixed constraint  $v$**  expressed in **canonical form**

$flow_{k,p}$  is the flow on **AC Line  $k$**  due to **FTR injection pattern  $p$** , which equals  $\sum_{h \in Hubs} SF_{k,h} \times Inj_{h,p}$

$loss_{k,p}$  is the variable **losses** on **AC Line  $k$**  due to  $flow_{k,p}$

$SF_{k,h}$  and  $Inj_{h,p}$  are as defined in subclause (2)

- (5) For the purposes of this clause, if **hub  $h$**  is a group of **nodes**, the positive or negative **hub injection** at **hub  $h$**  must be split into its individual nodal components in a manner consistent with the **hub** definition in the **FTR allocation plan**, and each nodal component must be treated as a separate **hub injection**.

## 8 FTR manager must assign portions of capacities

- (1) For each **trading period** of the relevant **billing period**, the **FTR manager** must assign a portion of the capacity of each **AC line**, **AC line loss curve block**, **binding branch constraint RHS** and **binding mixed constraint RHS** (if any) for the purpose of determining amounts to be applied to the settlement of **FTRs** under clause 9(3) to (5).
- (2) The portion of the capacity of each **AC line** to be assigned under subclause (1) must be the minimum of—
  - (a) the line capacity applicable in the **trading period** in the **final pricing schedule**; and
  - (b) the relevant **branch** participation loading determined under clause 7(1).
- (3) The portion of the capacity of each **AC line loss curve block** to be assigned under subclause (1) must be the portion of the loss curve block that would be utilised by a flow at the level of the capacity of the associated **AC line** assigned, as determined under subclause (2), assuming that loss curve blocks are utilised in order from lowest to highest **loss factor**, in the direction of flow.
- (4) Subject to subclause (5), the portion of the capacity of each **binding branch constraint RHS** or **binding mixed constraint RHS** (if any) to be assigned under subclause (1) must be the minimum of—
  - (a) the **constraint RHS** applicable in the **trading period** in the **final pricing schedule**, minus the contribution of any **LHS** terms not involving **AC line** flows

- or **AC line** variable **losses**, calculated assuming the values of the relevant variables applicable in the **trading period** in the **final pricing schedule**; and
- (b) the relevant **constraint** participation loading determined under clause 7(3) or clause 7(4).
- (5) If the capacity determined under subclause (4) for any **constraint** is negative, the capacity to be assigned for that **constraint** must be 0.

**9 FTR manager must calculate amounts to be applied to settlement of FTRs**

- (1) The amounts calculated under this clause must be calculated using the flow quantities, nodal prices and **shadow prices** from the **final pricing schedule**.
- (2) The HVDC **loss and constraint excess** to be applied to the settlement of **FTRs** for each **trading period** of the relevant **billing period** must be calculated in accordance with the following formula:

$$\max \left( 0, \sum_{n(NI)} price_n \times \left( \sum_{l \in R_{HVDC}(n)} (HVDCLinkFlow_l - HVDCLinkLosses_l) - \sum_{l \in S_{HVDC}(n)} HVDCLinkFlow_l \right) \right) + \sum_{n(SI)} price_n \times \left( \sum_{l \in R_{HVDC}(n)} (HVDCLinkFlow_l - HVDCLinkLosses_l) - \sum_{l \in S_{HVDC}(n)} HVDCLinkFlow_l \right) \div 2$$

where

$price_n$  is the energy price at  
AC **node**  $n$

$n(NI)$  is the set of North  
Island AC **nodes** to  
which any **HVDC**  
**links** are connected

$n(SI)$  is the set of South  
Island AC **nodes** to  
which any **HVDC**  
**links** are connected

$HVDCLinkFlow_l$  is the **MW** flow at the  
sending end **scheduled**  
for **HVDC link**  $l$

$HVDCLinkLosses_l$  is the variable **MW**  
**losses** for **HVDC link**  
 $l$

$S_{HVDC}(n)$  is the set of **HVDC**  
**links** for which  $n$  is the  
sending AC **node**

$R_{HVDC}(n)$  is the set of **HVDC links** for which  $n$  is the receiving AC **node**

- (3) The amount of the **loss and constraint excess** generated by each **AC line** that is to be applied to the settlement of **FTRs** must be calculated in accordance with the following formula:

$$AssignedCapacity_k \times ShadowPrice_k \div 2$$

where

$AssignedCapacity_k$  is the portion of the capacity of **AC line  $k$**  assigned under clause 8(1)

$ShadowPrice_k$  is the **shadow price** of the line capacity on **AC line  $k$**

- (4) The amount of the **loss and constraint excess** generated by each **binding branch constraint** and **binding mixed constraint** (if any) involving **AC line** flow terms or **AC line** variable loss terms to be applied to the settlement of **FTRs** must be calculated in accordance with the following formula:

$$AssignedCapacity_v \times ShadowPrice_v \div 2$$

where

$AssignedCapacity_v$  is the portion of the capacity of the **RHS of branch constraint** or **mixed constraint  $v$**  assigned under clause 8(1)

$ShadowPrice_v$  is the **shadow price** of **branch constraint** or **mixed constraint  $v$**

- (5) The amount of the **loss and constraint excess** generated by each **AC line** loss curve block that is to be applied to the settlement of **FTRs** must be calculated in accordance with the following formula:

$$\min(ACLineFlowBlock_{k,j}, AssignedCapacity_{k,j}) \times ReceivingEndPrice_k \\ \times (ACLineLossFactor_{k, \arg} - ACLineLossFactor_{k,j}) \div 2$$

where

$$ACLineLossFactor_{k, \text{margin}} = \min(ACLineLossFactor_{k,j}) \text{ for which } ACLineFlowBlock_{k,j} < ACLineLossMW_{k,j}$$

$ACLineFlowBlock_{k,j}$  is the **MW** flow on the  $j^{th}$  block of the loss curve of **AC line**  $k$  in the direction of **scheduled** positive flow, assuming that loss curve blocks are utilised in order from lowest to highest **loss factor**, in each direction

$AssignedCapacity_{k,j}$  is the portion of the capacity of the  $j^{th}$  block of the loss curve of **AC line**  $k$  assigned under clause 8(1)

$ReceivingEndPrice_k$  is the nodal energy price at the receiving end of the **scheduled** flow on **AC line**  $k$

$ACLineLossFactor_{k,j}$  is the **loss factor** of the  $j^{th}$  block of the loss curve of **AC line**  $k$

$ACLineLossMW_{k,j}$  is the **MW** capacity of the  $j^{th}$  block of the loss curve of **AC line**  $k$

- (6) The **FTR manager** must calculate the amount of the **loss and constraint excess** that must be applied to the settlement of **FTRs** for each **billing period** by—
- (a) determining the sum of the amounts calculated in accordance with subclauses (2) to (5) for each **trading period** of the **billing period**; and
  - (b) determining the sum of the amounts calculated in accordance with paragraph (a) for all **trading periods** of the **billing period**.

## Schedule 14.4

### Forms of hedge settlement agreement

cl 14.8

#### Form 1

Date: [Enter date]

Party A	
Party B	

#### 1 Lodging of hedge settlement agreement

- (1) Party A and Party B (the **parties**) submit this **hedge settlement agreement** to the **clearing manager**, as contemplated by clause 14.8 of the Electricity Industry Participation Code 2010 (the **Code**). Terms that are used in this agreement but not defined bear the meaning given to them in the **Code**.
- (2) By submitting this **hedge settlement agreement** to the **clearing manager** in accordance with clause 14.8 of the **Code**, the **parties** agree to be bound by the terms set out below from the time at which the **clearing manager** counter-signs it.
- (3) If the **clearing manager** counter-signs this document then, from the time it counter-signs, it has obligations relating to it under the **Code**. However, the **parties** acknowledge the **clearing manager** is not bound by this document and that its obligations in relation to it are limited to those set out in the **Code**.

#### 2 Definitions

The following definitions apply in this document:

**aggregate fixed amount** means, in relation to a **billing period**, the sum of the **fixed amounts** for each **calculation period** in that **billing period**

**aggregate floating amount** means, in relation to a **billing period**, the sum of the **floating amounts** for each **calculation period** in that **billing period**

**calculation period** means a **trading period** during the **term**

**commencement date** means the date specified as such in the schedule

**expiry date** means the date specified as such in the schedule

**fixed amount** means, in relation to a **calculation period**, an amount calculated using the following formula:

$$\text{fixed amount} = \text{notional quantity} \times \text{fixed price}$$

**fixed price** means, in relation to a **calculation period**, the amount specified as such for that **calculation period** in the schedule

**fixed price payer** means, in relation to a **hedge settlement agreement**, the party specified as such in the schedule

**floating amount** means, in relation to a **calculation period**, an amount calculated using the following formula:

$$\text{floating amount} = \text{notional quantity} \times \text{floating price}$$

**floating price** means, in relation to a **calculation period**, the **final price** per MWh for that **calculation period** by reference to the **hedge reference point** [rounded to two decimal places]

**floating price payer** means, in relation to a **hedge settlement agreement**, the party specified as such in the schedule

**hedge reference point** means the **grid exit point** specified as such in the schedule

**hedge settlement amount** means, in relation to a **billing period**, the absolute value of the amount calculated by subtracting the **aggregate floating amount** from the **aggregate fixed amount**

**notional quantity** means, in relation to a **calculation period**, the number of MWhs specified as such in the schedule for that **calculation period**

**settlement date** means the date on which payments are due under clause 14.31 of the Code

**term** means the period from 00.00 hours on the **commencement date** until 23.59 hours on the date on which the **hedge settlement agreement** terminates.

### 3 Payment of hedge settlement amounts

In relation to a **billing period**:

- (a) if the **aggregate floating amount** exceeds the **aggregate fixed amount**:
  - (i) the **floating price payer** must pay the **clearing manager** an amount equal to the **hedge settlement amount** in relation to that **billing period**; and
  - (ii) the **clearing manager** must pay the **fixed price payer** an amount equal to the **hedge settlement amount** in relation to that **billing period**, on the relevant **settlement date**; and
- (b) if the **aggregate fixed amount** exceeds the **aggregate floating amount**:
  - (i) the **fixed price payer** must pay the **clearing manager** an amount equal to the **hedge settlement amount** in relation to that **billing period**; and
  - (ii) the **clearing manager** must pay the **floating price payer** an amount equal to the **hedge settlement amount** in relation to that **billing period**, on the relevant **settlement date**.

### 4 Termination

This **hedge settlement agreement** terminates on the earlier of:

- (a) the **expiry date**; and
- (b) the date on which it is cancelled under the **Code**.



**5 Other provisions**

The **fixed price** is inclusive of any additional costs arising due to carbon charges.

**EXECUTION**

[Execution Block Party A]

[Execution Block Party B]

The **clearing manager** accepts the lodgement of this **hedge settlement agreement** by counter-signing it.

[Execution Block Clearing Manager]

**SCHEDULE  
TERMS OF HEDGE SETTLEMENT AGREEMENT**

<b>Hedge settlement agreement terms</b>	
Commencement Date	[Insert date]
Expiry Date	[Insert date]
Fixed Price Payer	[Party A] [Party B]
Floating Price Payer	[Party A] [Party B]
Notional Quantity	[insert number] <b>MWh</b> for each <b>calculation period</b>
Fixed Price	[\$[insert amount] / <b>MWh</b>
Hedge Reference Point	[insert <b>grid exit point</b> ]

Schedule 14.4, Schedule to Form 1: amended, on 24 March 2015, by clause 20 of the Electricity Industry Participation Code Amendment (Settlement and Prudential Security) 2014.

## Form 2: Cap/Floor Calculation Period Price

[Note (not for inclusion in form): This form can be used to achieve both a capped price and a floor price.]

Date: [Enter date]

Party A	
Party B	

### 1 Lodging of hedge settlement agreement

- (1) Party A and Party B (the **parties**) submit this **hedge settlement agreement** to the **clearing manager**, as contemplated by clause 14.8 of the Electricity Industry Participation Code 2010 (the **Code**). Terms that are used in this agreement but not defined bear the meaning given to them in the **Code**.
- (2) By submitting this **hedge settlement agreement** to the **clearing manager** in accordance with clause 14.8 of the **Code**, the **parties** agree to be bound by the terms set out below from the time at which the **clearing manager** counter-signs it.
- (3) If the **clearing manager** counter-signs this document then, from the time it counter-signs, it has obligations relating to it under the **Code**. However, the **parties** acknowledge the **clearing manager** is not bound by this document and that its obligations in relation to it are limited to those set out in the **Code**.

### 2 Definitions

The following definitions apply in this document:

**calculation period** means a **trading period** during the **term**

**calculation period premium** means, in relation to a **calculation period**, the amount specified as such in the schedule for that **calculation period**

**calculation period settlement amount** means, in relation to a **calculation period**, an amount calculated using the following formula:

calculation period settlement amount = **notional quantity** x **strike price differential**

**cash settlement amount** means, in relation to a **billing period**, the sum of the **calculation period settlement amounts** for each **calculation period** in that **billing period**

**commencement date** means the date specified as such in the schedule

**expiry date** means the date specified as such in the schedule

**floating price** means, in relation to a **calculation period**, the **final price** per MWh for that **calculation period** by reference to the **hedge reference point** [rounded to two decimal places]

**hedge reference point** means the **grid exit point** specified as such in the schedule

**notional quantity** means, in relation to a **calculation period**, the number of **MWhs** specified as such in the schedule for that **calculation period**

**option buyer** means, in relation to a **hedge settlement agreement**, the party specified as such in the schedule

**option premium** means, in relation to a **billing period**, the sum of the **calculation period premiums** for each **calculation period** in that **billing period**

**option seller** means, in relation to a **hedge settlement agreement**, the party specified as such in the schedule

**option type** means either a put option or a call option as specified in the schedule

**settlement date** means the date on which payments are due under clause 14.31 of the Code

**strike price** means, in relation to a **calculation period**, the amount specified as such in the schedule

**strike price differential** means, in relation to a **calculation period**, an amount equal to:

- (a) if the **option type** is a put option, the greater of the **strike price** minus the **floating price** and zero;
- (b) if the **option type** is a call option, the greater of the **floating price** minus the **strike price** and zero

**term** means the period from 00.00 hours on the **commencement date** until 23.59 hours on the date on which the **hedge settlement agreement** terminates.

### 3 Payment of hedge settlement amounts

In relation to a **billing period**:

- (a) the **option buyer** must pay the **clearing manager** an amount equal to the **option premium** for that **billing period**; and
- (b) the **clearing manager** must pay the **option seller** an amount equal to the **option premium** for that **billing period**; and
- (c) the **option seller** must pay the **clearing manager** an amount equal to the **cash settlement amount** for that **billing period**; and
- (d) the **clearing manager** must pay the **option buyer** an amount equal to the **cash settlement amount** for that **billing period**, on the relevant **settlement date**.

### 4 Termination

This **hedge settlement agreement** terminates on the earlier of:

- (a) the **expiry date**; and
- (b) the date on which it is cancelled under the **Code**.

## 5 Other provisions

The **strike price** is inclusive of any additional costs arising due to carbon charges.

## EXECUTION

[Execution Block Party A]

[Execution Block Party B]

The **clearing manager** accepts the lodgement of this **hedge settlement agreement** by counter-signing it.

[Execution Block Clearing Manager]

## SCHEDULE TERMS OF HEDGE SETTLEMENT AGREEMENT

Hedge settlement agreement terms	
Commencement Date	[Insert date]
Expiry Date	[Insert date]
Option Buyer	[Party A] [Party B]
Option Seller	[Party A] [Party B]
Option Type	[Call Option] [Put Option]
Notional Quantity	[insert number] <b>MWh</b> for each <b>calculation period</b>
Strike Price	[\$[insert amount] / <b>MWh</b>
Calculation Period Premium	[\$[insert amount] for each <b>calculation period</b>
Hedge Reference Point	[insert <b>grid exit point</b> ]

Schedule 14.4, Schedule to Form 2: amended, on 24 March 2015, by clause 21 of the Electricity Industry Participation Code Amendment (Settlement and Prudential Security) 2014.

### Form 3: Cap/Floor Average Price

[Note (not for inclusion in form): This form can be used to achieve both a capped average price over a defined period and a floor average price over a period.]

Date: [Enter date]

Party A	
Party B	

#### 1 Lodging of hedge settlement agreement

- (1) Party A and Party B (the **parties**) submit this **hedge settlement agreement** to the **clearing manager**, as contemplated by clause 14.8 of the Electricity Industry Participation Code 2010 (the **Code**). Terms that are used in this agreement but not defined bear the meaning given to them in the **Code**.
- (2) By submitting this **hedge settlement agreement** to the **clearing manager** in accordance with clause 14.8 of the **Code**, the **parties** agree to be bound by the terms set out below from the time at which the **clearing manager** counter-signs it.
- (3) If the **clearing manager** counter-signs this document then, from the time it counter-signs, it has obligations relating to it under the **Code**. However, the **parties** acknowledge the **clearing manager** is not bound by this document and that its obligations in relation to it are limited to those set out in the **Code**.

#### 2 Definitions

The following definitions apply in this document:

**average floating price** means, in relation to an **option period**, an amount calculated using the following formula:

$$\text{average floating price} = \frac{\text{option period floating amount}}{\text{option period notional quantity}}$$

**calculation period** means a **trading period** during the **term**

**calculation period floating amount** means, in relation to a **calculation period**, an amount calculated using the following formula:

$$\text{calculation period floating amount} = \text{notional quantity} \times \text{floating price}$$

**calculation period notional quantity** *[Revoked]*

**calculation period premium** means, in relation to a **calculation period**, the amount specified as such in the schedule for that **calculation period**

**cash settlement amount** means, in relation to a **billing period**, the sum of the **option period settlement amounts** for each **option period** in that **billing period**

**commencement date** means the date specified as such in the schedule

**expiry date** means the date specified as such in the schedule

**floating price** means, in relation to a **calculation period**, the **final price** in dollars per MWh for that **calculation period** by reference to the **hedge reference point** [rounded to two decimal places]

**hedge reference point** means the **grid exit point** specified as such in the schedule

**notional quantity** means, in relation to a **calculation period**, the amount of **electricity** (measured in MWh) specified as such in the schedule for that **calculation period**

**option buyer** means, in relation to a **hedge settlement agreement**, the party specified as such in the schedule

**option period** means each period during the **term** specified as such in the schedule

**option period floating amount** means, in relation to an **option period**, an amount equal to the aggregate of the **calculation period floating amounts** for each **calculation period** in that **option period**

**option period notional quantity** means, in relation to an **option period**, the sum of the **notional quantities** for each **calculation period** in the **option period**

**option period premium** means, in relation to an **option period**, the sum of the **calculation period premium** for each **calculation period** in the **option period**

**option period settlement amount** means, in relation to an **option period**, an amount calculated using the following formula:

option period settlement amount = **option period notional quantity** x **strike price differential**

**option premium** means, in relation to a **billing period**, the sum of the **option period premiums** for each **option period** in that **billing period**

**option seller** means, in relation to a **hedge settlement agreement**, the party specified as such in the schedule

**option type** means either a put option or a call option as specified in the schedule

**settlement date** means the date on which payments are due under clause 14.31 of the Code

**strike price** means, in relation to an **option period**, the amount specified as such in the schedule

**strike price differential** means, in relation to an **option period**, an amount equal to:

- (a) if the **option type** is a put option, the greater of the **strike price** minus the **average floating price** and zero;
- (b) if the **option type** is a call option, the greater of the **average floating price** minus the **strike price** and zero

**term** means the period from 00.00 hours on the **commencement date** until 23.59 hours on the date on which the **hedge settlement agreement** terminates.

### 3 Payment of hedge settlement amounts

In relation to a **billing period**:

- (a) the **option buyer** must pay the **clearing manager** an amount equal to the **option premium** for that **billing period**; and
- (b) the **clearing manager** must pay the **option seller** an amount equal to the **option premium** for that **billing period**; and
- (c) the **option seller** must pay the **clearing manager** an amount equal to the **cash settlement amount** for that **billing period**; and
- (d) the **clearing manager** must pay the **option buyer** an amount equal to the **cash settlement amount** for that **billing period**,  
on the relevant **settlement date**.

### 4 Termination

This **hedge settlement agreement** terminates on the earlier of:

- (a) the **expiry date**; and
- (b) the date on which it is cancelled under the **Code**.

### 5 Other provisions

The **strike price** is inclusive of any additional costs arising due to carbon charges.

## EXECUTION

[Execution Block Party A]

[Execution Block Party B]

The **clearing manager** accepts the lodgement of this **hedge settlement agreement** by counter-signing it.

[Execution Block Clearing Manager]

## SCHEDULE TERMS OF HEDGE SETTLEMENT AGREEMENT

Hedge settlement agreement terms	
Commencement Date	[Insert date]
Expiry Date	[Insert date]
Option Buyer	[Party A] [Party B]
Option Seller	[Party A] [Party B]
Option Type	[Call Option] [Put Option]

**Electricity Industry Participation Code 2010**  
**Schedule 14.4**

Option Period	[Each day] [From 00.00 hours until immediately before 00.00 hours on the next day] [first period being nn and last period being mm] [during the <b>term</b> .]
Notional Quantity	[insert number <b>MWh</b> ] [Table of Notional Quantities (in <b>MWh</b> per <b>calculation period</b> ) to be inserted]
Strike Price	[\$[insert amount/ <b>MWh</b> ] – [Table of Strike Prices to be inserted]
Calculation Period Premium	[\$[insert amount] for each <b>calculation period</b> of <b>option period</b> . [Table of Premiums to be inserted]
Hedge Reference Point	[insert <b>grid exit point</b> ]

Schedule 14.4, Form 3, clause 2, formula in the definition of **average floating price**: amended, on 24 March 2015, by clause 22(1)(a) of the Electricity Industry Participation Code Amendment (Settlement and Prudential Security) 2014.

Schedule 14.4, Form 3, clause 2, formula in the definition of **calculation period floating amount**: amended, on 24 March 2015, by clause 22(1)(b) of the Electricity Industry Participation Code Amendment (Settlement and Prudential Security) 2014.

Schedule 14.4, Form 3, clause 2, definition of **calculation period notional quantity**: revoked, on 24 March 2015, by clause 22(1)(c) of the Electricity Industry Participation Code Amendment (Settlement and Prudential Security) 2014.

Schedule 14.4, Form 3, clause 2, definition of **calculation period premium**: inserted, on 24 March 2015, by clause 22(1)(d) of the Electricity Industry Participation Code Amendment (Settlement and Prudential Security) 2014.

Schedule 14.4, Form 3, clause 2, definition of **floating price**: amended, on 24 March 2015, by clause 22(1)(e) of the Electricity Industry Participation Code Amendment (Settlement and Prudential Security) 2014.

Schedule 14.4, Form 3, clause 2, definition of **notional quantity**: substituted, on 24 March 2015, by clause 22(1)(f) of the Electricity Industry Participation Code Amendment (Settlement and Prudential Security) 2014.

Schedule 14.4, Form 3, clause 2, definition of **option period notional quantity**: inserted, on 24 March 2015, by clause 22(1)(g) of the Electricity Industry Participation Code Amendment (Settlement and Prudential Security) 2014.

Schedule 14.4, Form 3, clause 2, definition of **option period premium**: substituted, on 24 March 2015, by clause 22(1)(h) of the Electricity Industry Participation Code Amendment (Settlement and Prudential Security) 2014.

Schedule 14.4, Form 3, clause 2, formula in the definition of **option period settlement amount**: amended, on 24 March 2015, by clause 22(1)(i) of the Electricity Industry Participation Code Amendment (Settlement and Prudential Security) 2014.

Schedule 14.4, Schedule to Form 3: amended, on 24 March 2015, by clause 22(2) of the Electricity Industry Participation Code Amendment (Settlement and Prudential Security) 2014.



# Electricity Industry Participation Code 2010

## Part 14A Prudential requirements

Part 14A: inserted, on 24 March 2015, by clause 20 of the Electricity Industry Participation (Settlement and Prudential Security) Code Amendment 2013.

### Contents

14A.1	Purpose of prudential requirements
14A.2	Participants to comply with prudential requirements
14A.3	Acceptable credit rating
14A.4	Acceptable security
14A.5	Clearing manager to determine estimate of minimum security
14A.6	Participant to provide minimum security required
14A.7	Participant may change form of security
14A.8	Reductions and releases
14A.9	Release of security on ceasing to be participant
14A.10	Clearing manager to release security within 1 business day
	<i>Cash deposits to be held on trust</i>
14A.11	Cash deposit accounts
14A.12	Cash deposits to be paid into cash deposit accounts
14A.13	Cash deposits to be applied subject to conditions
14A.14	Interest on cash deposits
14A.15	Fees and taxes payable by participants
	<i>Information, monitoring and reporting</i>
14A.16	Information required from new purchasers
14A.17	Participants subject to prudential requirements to provide information to clearing manager
14A.18	System operator to provide information
14A.19	Clearing manager to keep information confidential
14A.20	Clearing manager to provide information about cash deposits
14A.21	Clearing manager to provide information about required security
14A.22	Clearing manager to keep register of specified time periods
	<i>Disputes</i>
14A.23	Disputes regarding prudential requirements
	<i>Notices</i>
14A.24	Notices

### Schedule 14A.1 Acceptable security

### Schedule 14A.2 Guarantee

### Schedule 14A.3 Deed of guarantee and indemnity

**Schedule 14A.4**  
**Letter of credit**

**Schedule 14A.5**  
**Surety bond**

---

**14A.1 Purpose of prudential requirements**

The purpose of this Part is to impose prudential requirements on each **participant** that has incurred or will incur financial obligations under this Code to ensure that the **participant** can meet those obligations.

**14A.2 Participants to comply with prudential requirements**

- (1) Before incurring any financial obligations under this Code, a **participant** must comply with prudential requirements in this Part.
- (2) A **participant** complies with prudential requirements in this Part in 1 of the following ways:
  - (a) by maintaining an acceptable credit rating under clause 14A.3:
  - (b) by providing acceptable security that complies with clause 14A.4.

**14A.3 Acceptable credit rating**

- (1) For the purposes of this Part, a person has an acceptable credit rating if—
  - (a) the person has a long-term credit rating no lower than—
    - (i) A3 (Moody's Investor Services Inc.); or
    - (ii) A– (Standard & Poor's Rating Group); or
    - (iii) B+ (AM Best); or
    - (iv) A– (Fitch Ratings); and
  - (b) in the case of a person who has a credit rating at the minimum level required under paragraph (a), the person is not subject to negative credit watch (or any equivalent arrangement) by the agency that gave the credit rating.
- (2) The **clearing manager** may require a **participant** whose compliance with prudential requirements in this Part depends on the credit rating of a person to provide evidence of the person's credit rating.
- (3) The **participant** must provide the evidence required by the **clearing manager**.

**14A.4 Acceptable security**

- (1) A **participant** provides acceptable security by—
  - (a) providing an acceptable form of security in accordance with Part 1 of Schedule 14A.1; and
  - (b) providing security for an amount that is no less than the amount required under clause 14A.6.
- (2) A **participant** that provides acceptable security must do anything the **Authority** requires to ensure that the security is valid, enforceable, and effective.

#### **14A.5 Clearing manager to determine estimate of minimum security**

- (1) At least once in every **business day**, the **clearing manager** must estimate the minimum amount for which security will be required to be provided by a **participant** under this Part on that **business day** and on each of the following 3 **business days** in accordance with Part 2 of Schedule 14A.1.
- (2) The **clearing manager** must formulate and **publish** a methodology for estimating the amounts under subclause (1).
- (3) The consultation and approval requirements set out in Schedule 14.2 apply to the methodology.

#### **14A.6 Participant to provide minimum security required**

- (1) Each **participant** that is required to provide acceptable security under this Part on a **business day** must provide security for an amount that is the lowest of all of the estimates determined by the **clearing manager** for the **participant** for that **business day**.
- (2) The **participant** must provide security for the amount required under subclause (1) no later than 1600 hours on the relevant **business day**.

#### **14A.7 Participant may change form of security**

The **clearing manager** must release a **participant's** existing security when the **participant** provides a different form of security notified under this clause, if—

- (a) the **participant** gives the **clearing manager** notice of its intention to substitute a different form of security for any security provided by it to the **clearing manager**; and
- (b) no **event of default** is continuing in relation to the **participant**; and
- (c) the **participant** satisfies the **clearing manager** that—
  - (i) the proposed new form of security is an acceptable form of security under Part 1 of Schedule 14A.1; and
  - (ii) the security provided by the **participant** will continue to be for an amount that is no less than the amount required under clause 14A.6.

#### **14A.8 Reductions and releases**

The **clearing manager** must reduce or release a **participant's** existing security to the extent requested by the **participant**, if—

- (a) the **participant** gives the **clearing manager** notice that it seeks a partial or complete reduction or release of any security provided by it to the **clearing manager**; and
- (b) no **event of default** is continuing in relation to the **participant**; and
- (c) the **participant** satisfies the **clearing manager** that, following the reduction or release of the security, the **participant** will—
  - (i) continue to meet the requirements in clause 14A.4; or
  - (ii) meet the requirements in clause 14A.3.

#### **14A.9 Release of security on ceasing to be participant**

The **clearing manager** must release a **participant's** existing security if the

**participant**—

- (a) gives the **clearing manager** notice of it ceasing to be a **participant**; and
- (b) ceases to be a **participant** and the **Authority** advises the **clearing manager** that the person has ceased to be a **participant**; and
- (c) has paid all amounts that it owes under this Code (excluding any **washup** amount that has not yet been invoiced).

#### **14A.10 Clearing manager to release security within 1 business day**

- (1) If a **participant** becomes entitled under clause 14A.7 or 14A.8 or 14A.9 or 14A.23 to a reduction or release of any security, the **clearing manager** must reduce or release that security within 1 **business day** of the **participant** becoming entitled to the reduction or release.
- (2) If a **cash deposit** is to be reduced or refunded under subclause (1), the **clearing manager** must pay the amount of the reduction or refund to a **bank** account nominated by the **participant** for that purpose.

*Cash deposits to be held on trust*

#### **14A.11 Cash deposit accounts**

- (1) The **clearing manager** must establish, in the **clearing manager's** name, 2 or more interest bearing **cash deposit accounts**.
- (2) The **cash deposit accounts** must be—
  - (a) held with more than 1 **bank** that each has and maintains an acceptable credit rating in accordance with clause 14A.3(1); and
  - (b) clearly identified as such and be entirely separate from any other **bank** account of the **clearing manager**.
- (3) The **clearing manager** must obtain acknowledgement from each **bank** with which it has a **cash deposit account** that—
  - (a) the **cash deposits** are held on trust in the **cash deposit accounts** for **participants** (including the **clearing manager**) that become entitled to receive money from the **clearing manager** from time to time under clause 14A.13; and
  - (b) the **bank** has no right of set-off or right of combination in relation to the **cash deposits**.

#### **14A.12 Cash deposits to be paid into cash deposit accounts**

- (1) Every **cash deposit** received by the **clearing manager** must be paid by the **clearing manager** immediately into the **cash deposit accounts**.
- (2) Each **cash deposit** must be held between **cash deposit accounts** in approximately equal amounts.
- (3) If a **cash deposit** is debited under this Part, the **clearing manager** must ensure that approximately equal amounts of the **cash deposit** are debited from each **cash deposit account**.

#### **14A.13 Cash deposits to be applied subject to conditions**

The **clearing manager** must hold each **cash deposit** in the **cash deposit accounts** on

trust to be applied, subject to this Code, only in accordance with the following:

- (a) following any **event of default**, the **clearing manager** must use such amount of the defaulting **participant's cash deposit** as is necessary or available in order to satisfy (to the extent possible) any amounts that may be due and owing by the defaulting **participant** to the **clearing manager** under this Code;
- (b) if no **event of default** is continuing in relation to the **participant** that provided the **cash deposit**, the **participant** is entitled to be paid the part of the **cash deposit** that has not been transferred under paragraph (a) in accordance with clause 14A.7 or 14A.8 or 14A.9 or 14A.23;
- (c) to satisfy an amount payable under clause 14.31 if the **participant** satisfies the **clearing manager** that, immediately following the application of the **cash deposit**, it will continue to comply with prudential requirements in this Part;
- (d) the **participant** is not entitled to receive back any part of its **cash deposit**, other than in accordance with this clause, even if the **participant** is in liquidation, receivership, or subject to statutory management or other analogous situation.

#### **14A.14 Interest on cash deposits**

- (1) Subject to clauses 14A.13 and 14A.15, the **clearing manager** must credit to each **participant** on behalf of which the **clearing manager** holds a **cash deposit** all interest received by the **clearing manager** on the **cash deposit**, less any applicable deduction for tax purposes.
- (2) Subject to subclause (3), if a **participant** does not wish the interest to accumulate in the **cash deposit accounts**, the **clearing manager** must, at the request of the **participant**, pay the interest (less any applicable deduction for tax purposes) within 2 **business days** of the end of the month to a **bank** account nominated by the **participant** for this purpose.
- (3) Subclause (2) does not apply if an **event of default** has occurred in relation to the **participant** and is continuing.

#### **14A.15 Fees and taxes payable by participants**

- (1) A **participant** is liable to reimburse the **clearing manager** for all **bank** fees in relation to its **cash deposit** and any taxes that may from time to time be imposed either on its **cash deposit** or on interest earned on such **cash deposit**.
- (2) Such payments must be deducted by the **clearing manager** from any amounts paid to the **participant** under clause 14A.14(2).
- (3) If the amounts are less than the payments owed by the **participant** under this clause, the shortfall must be invoiced separately by the **clearing manager**.

#### *Information, monitoring, and reporting*

#### **14A.16 Information required from new purchasers**

Before a new **purchaser** purchases **electricity**, it must submit to the **clearing manager**—

- (a) historical records of the quantity of **electricity** purchased and sold by that person before that person became a **purchaser**; or

- (b) if the **clearing manager** is not satisfied with records provided under paragraph (a), or if there are no such records, a bona fide **business** plan prepared in good faith to permit a realistic estimate of the **purchaser's** future trading.

#### **14A.17 Participants subject to prudential requirements must provide information to clearing manager**

- (1) The **clearing manager** may require a **participant** that is required to comply with prudential requirements in this Part to provide, by any date specified by the **clearing manager**, any information that the **clearing manager** requires for the purposes of carrying out its functions under this Part.
- (2) A **participant** that is required to provide information to the **clearing manager** under subclause (1) must provide the information to the **clearing manager** by the date specified by the **clearing manager**.
- (3) Each **participant** that is required to comply with prudential requirements under this Part must provide the following information to the **clearing manager** immediately upon the **participant** becoming aware of the situation:
  - (a) if the **participant** is a **purchaser**, any significant change to that **purchaser's** **business**, including a merger or acquisition, loss or gain of a **customer**, or sale or purchase of assets, that could significantly affect the quantity of **electricity** purchased or generated by the **participant** in its capacity as a **purchaser** or **generator**;
  - (b) any change or likely change to the **participant's** credit rating (if the **participant** has a credit rating), regardless of whether or not the **participant** is relying on a credit rating as a prudential requirement in terms of clause 14A.3;
  - (c) if a letter of credit or guarantee or bond is provided in respect of the **participant** in accordance with Part 1 of Schedule 14A.1—
    - (i) any change or likely change to the credit rating of the provider of the guarantee, letter of credit, or bond such that the provider's credit rating would, as a result, not be an acceptable credit rating as defined in clause 14A.3; or
    - (ii) any claim by the provider of the guarantee, letter of credit, or bond that the guarantee, letter of credit, or bond has ceased to be valid and enforceable.
- (4) If, at any time, a **participant** believes that its ability to pay an amount owing to the **clearing manager** under this Code is or is likely to be materially adversely affected, the **participant** must provide the **clearing manager** with details of that fact immediately.

#### **14A.18 System operator to provide information**

The **system operator** must provide the **clearing manager** with the following information immediately upon becoming aware of the information:

- (a) any likely significant change to any amount to be allocated to a **participant** in respect of **ancillary services** or **extended reserve**;
- (b) the amount incurred by a **participant** as a result of the **participant** causing an **under-frequency event**.

Clause 14A.18(a): amended, on 24 March 2015, by clause 31 of the Electricity Industry Participation Code Amendment (Extended Reserve) 2014.

#### 14A.19 Clearing manager to keep information confidential

The **clearing manager** must keep all information received by it under clauses 14A.16 to 14A.18 confidential and must not disclose it to any other person except—

- (a) with the written consent of the person who provided the information; or
- (b) if the information is required to be disclosed to or by the **Rulings Panel** or the **Authority** under this Code, regulations made under section 112 of the **Act**, or any other law.

#### 14A.20 Clearing manager to provide information about cash deposits

Each month the **clearing manager** must provide each **participant** that has provided a **cash deposit** with a statement regarding the balance of the **participant's cash deposit**.

#### 14A.21 Clearing manager to provide information about required security

- (1) The **clearing manager** must provide each **participant** that is required to comply with prudential requirements under this Part with information about the amount for which security is required to be provided by the **participant** under clause 14A.6.
- (2) The **clearing manager** must—
  - (a) provide the information to the **participant** through **WITS**; and
  - (b) **publish** the information.

Clause 14A.21(2): replaced, on 5 October 2017, by clause 510 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

#### 14A.22 Clearing manager to keep register of specified time periods

- (1) The **clearing manager** must keep a register of the following time periods for each **participant** that is required to comply with prudential requirements in this Part (except a **participant** to which subclause (2) applies):
  - (a) a prudential exit period determined in accordance with subclause (3);
  - (b) a post-default exit period determined in accordance with subclause (4).
- (2) The **clearing manager** is not required to keep a register of time periods for a **participant** that is required to comply with prudential requirements in this Part only because the **participant** has an obligation in relation to 1 or more **FTRs**.
- (3) The prudential exit period for a **participant** is the number of **trading days** that elapse over the sum of the following:
  - (a) 1 **trading day**;
  - (b) the post-default exit period for the **participant**.
- (4) The post-default exit period for a **participant** is as follows, unless the **Authority** has approved a shorter period elected by the **participant**:
  - (a) for a **retailer**, 18 **trading days**;
  - (b) for a **direct purchaser**, 7 **trading days**;
  - (c) for a **participant** that is not a **retailer** or a **direct purchaser**, 7 **trading days**.
- (5) The post-default exit period for a **participant** begins from the day on which the **participant** advises the **clearing manager** or the **clearing manager** advises the **participant** under clause 14.43 that an **event of default** has occurred in relation to the **participant**.
- (6) A **participant** that has a shorter post-default exit period approved by the **Authority**

may increase the period to no more than the number of **business days** set out in subclause (4) by giving 20 **business days'** notice to the **clearing manager**.

- (7) A shorter post-default exit period approved by the **Authority** takes effect 20 **business days** after the date of the **Authority's** approval.

### *Disputes*

#### **14A.23 Disputes regarding prudential requirements**

- (1) A **participant** that disputes a decision of the **clearing manager** under this Part may refer the dispute to the **Rulings Panel**.
- (2) Until such time as the **Rulings Panel** makes a decision on the dispute, all **participants** must comply with the relevant decision of the **clearing manager**.
- (3) If a dispute is referred to it under subclause (1), the **Rulings Panel** must, after hearing from the **participant** that disputed the **clearing manager's** decision and from the **clearing manager**, make a decision in accordance with this Part.
- (4) If the **Rulings Panel** overturns or varies a decision by the **clearing manager**, the **clearing manager's** original decision, and the process that led to that decision, is not a breach of this Code by the **clearing manager**, unless the **Rulings Panel** determines that the **clearing manager's** decision was made negligently or in bad faith.

### *Notices*

#### **14A.24 Notices**

- (1) Except as expressly provided in this Code, a notice or demand given or required to be given under this Part may be given by being delivered or transmitted to the intended recipient at its address or electronic address as last advised in writing to the sender and may be posted to such address by prepaid post.
- (2) Subject to subclause (3),—
  - (a) a notice or demand delivered by hand is deemed to be delivered on the date of such delivery; and
  - (b) a notice or demand delivered by post is deemed to be delivered on the 2<sup>nd</sup> **business day** following the date of posting; and
  - (c) a notice or demand transmitted through **WITS** is deemed to be delivered on the date it was transmitted.
- (3) Any notice or demand delivered, or deemed to be delivered, on a day that is not a **business day**, or after 1600 hours on a **business day**, is deemed to have been delivered on the next **business day**.

Clause 14A.24(2)(c): amended, on 5 October 2017, by clause 511 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.



## Schedule 14A.1 Acceptable security

cl 14A.4

### Part 1 Acceptable forms of security

#### 1 Acceptable forms of security

A **participant** may provide acceptable security in any of the following forms:

- (a) a **cash deposit** (see clause 2);
- (b) an unconditional guarantee or letter of credit (see clause 3);
- (c) a security bond (see clause 4);
- (d) another form of security (see clause 5);
- (e) a combination of the forms of security listed in paragraphs (a) to (d) that in aggregate secures the required amount.

#### 2 Cash deposit

- (1) A **participant** must pay a **cash deposit** into the **cash deposit accounts** or to the **clearing manager**.
- (2) The **participant** must provide and maintain an acceptable **participant's** security agreement in respect of the **cash deposit**.
- (3) A **participant's** security agreement must—
  - (a) be a security agreement as defined in section 16(1) of the Personal Property Securities Act 1999; and
  - (b) create a first ranking security interest in respect of the **cash deposit**; and
  - (c) secure the **participant's** payment and performance obligations to the **clearing manager** under this Code; and
  - (d) be in a form approved by the **Authority**.

#### 3 Guarantee or letter of credit

- (1) A guarantee or letter of credit must be given in favour of the **clearing manager**.
- (2) A letter of credit is an acceptable form of security only if it is given by a **bank**.
- (3) A guarantee or letter of credit must be given on terms as follows, or as otherwise approved by the **Authority**:
  - (a) for a guarantee given by a **bank**, the terms in Schedule 14A.2;
  - (b) for a guarantee given by another person, the terms in Schedule 14A.3;
  - (c) for a letter of credit, the terms in Schedule 14A.4.
- (4) A guarantee or letter of credit is an acceptable form of security only while the person giving it has an acceptable credit rating as defined in clause 14A.3.

#### 4 Security bond

- (1) A security bond must be given in favour of the **clearing manager**.
- (2) A security bond must be given on the terms in Schedule 14A.5 or as otherwise approved by the **Authority**.
- (3) A security bond is an acceptable form of security only while the surety has an

acceptable credit rating as defined in clause 14A.3.

## **5 Other security**

- (1) Any other form of security is an acceptable form of security only if it has been approved by the **Authority**.
- (2) The **Authority** may approve another form of security if the **Authority** is satisfied that the form of security ensures that the relevant **participant** can meet its financial obligations under the Code to the same extent as if the **participant** provided a form of security specified in paragraphs (a) to (d) of clause 1.

## **Part 2**

### **Minimum security**

## **6 Determining minimum security**

- (1) The minimum amount for which security is required to be provided by a **participant** under clause 14A.6 is—
  - (a) the sum of the following amounts:
    - (i) the general prudential requirement calculated in accordance with clause 7;
    - (ii) the **FTR** prudential requirement calculated in accordance with clause 11; minus
  - (b) any amount prepaid by the **participant** under clause 14.30 that is specified by the **participant** as being for a **billing period**—
    - (i) that has commenced but remains unsettled on the day for which the minimum security is being determined; or
    - (ii) any part of which falls within the prudential exit period for the **participant** (if any).
- (2) If the sum of the amounts under subclause (1) is negative, the minimum amount for which security is required to be provided is 0.

Clause 6(1)(b): substituted, on 24 March 2015, by clause 23 of the Electricity Industry Participation Code Amendment (Settlement and Prudential Security) 2014.

## **7 General prudential requirement**

The general prudential requirement is the sum of the following amounts calculated in accordance with the methodology approved under clause 8:

- (a) the expected amount of the **clearing manager's** outstanding financial exposure to the **participant**; and
- (b) the exit period prudential margin for the **participant**.

## **8 Methodology for determining general prudential requirement amounts**

- (1) The **clearing manager** must formulate and **publish** a methodology for determining the amounts specified in clause 7.
- (2) The methodology must comply with the requirements specified in clauses 9 and 10.
- (3) The consultation and approval requirements set out in Schedule 14.2 apply to the methodology.

**9 Calculating clearing manager's outstanding financial exposure to participant**

- (1) The expected amount of the **clearing manager's** outstanding financial exposure to a **participant** on any **trading day** is an estimate of all unsettled amounts owing by the **participant** to the **clearing manager** and by the **clearing manager** to the **participant** to the end of the previous **trading day**, including the **clearing manager's** estimate of the following amounts:
- (a) the amount owing to or by the **participant** for purchasing and selling **electricity**;
  - (ab) the amount owing to or by the **participant** in relation to **extended reserve**;
  - (b) the amount owing to or by the **participant** in relation to **ancillary services**;
  - (c) the net amount owing to or by the **participant** in respect of any **hedge settlement agreement** lodged with the **clearing manager** under clause 14.8;
  - (d) the amount of any **GST** payable by the **participant** in respect of the above amounts.
- (2) The **clearing manager** must use **final prices** in calculating amounts under subclause (1) unless—
- (a) **final prices** are not available, in which case the **clearing manager** must use **interim prices**; or
  - (b) neither **final prices** nor **interim prices** are available, or an **undesirable trading situation** has been claimed in respect of a **trading period** or **trading day** that is included in the **clearing manager's** estimate, in which case the **clearing manager** must use the price calculated in accordance with clause 10(2)(c) that is used in the methodology for determining the exit period prudential margin.
- (3) The **clearing manager** must take **washup** amounts that have been advised as owing under Part 14 into account in estimating the amounts described in this clause.

Clause 9(1)(ab): inserted, on 24 March 2015, by clause 32 of the Electricity Industry Participation Code Amendment (Extended Reserve) 2014.

Clause 9(3): amended, on 24 March 2015, by clause 24 of the Electricity Industry Participation Code Amendment (Settlement and Prudential Security) 2014.

**10 Exit period prudential margin**

- (1) The exit period prudential margin for a **participant** is the **clearing manager's** estimate of the amount that the **participant** will incur and earn during the prudential exit period for the **participant** in respect of the following:
- (a) the sale and purchase of **electricity**;
  - (ab) **extended reserve**;
  - (b) **ancillary services**;
  - (c) any **hedge settlement agreement** lodged with the **clearing manager** under clause 14.8;
  - (d) any **GST** payable in respect of the above amounts.
- (2) The estimated amounts to be incurred and earned by the **participant** in respect of the sale and purchase of **electricity** under subclause (1)(a) are based on—
- (a) the number of **trading days** in the prudential exit period for the **participant** determined under clause 14A.22(3); and
  - (b) the expected value of **electricity** to be purchased by the **participant** minus the expected value of **electricity** to be sold by the **participant** during that period

- based on the prices in paragraph (c); and
- (c) the sum of the following amounts:
- (i) the prices of **electricity** expected to apply during the quarter to which the calculation relates in accordance with subclauses (3) and (4);
  - (ii) an amount determined as set out in subclause (5).
- (3) In determining the prices under subclause (2)(c)(i), the **clearing manager** must use prices of **electricity** futures products that are available and that the **clearing manager** considers provide a reasonable estimate of the average price of **electricity** for the relevant quarter.
- (4) The **clearing manager** must determine the prices under subclause (2)(c)(i)—
- (a) for each quarter beginning 1 January, 1 April, 1 July, and 1 October; and
  - (b) no later than 2 months before the beginning of each quarter.
- (5) The amount determined under subclause (2)(c)(ii) must—
- (a) be an amount expressed in \$/MWh of not less than \$0/MWh; and
  - (b) be determined on the basis that the exit period prudential margin for a hypothetical **purchaser** that purchases a constant proportion of total **electricity** purchased from the **clearing manager** for every **trading period** is greater than the general exit period exposure for the **purchaser** on 75% of the days in a modeling period of 3 to 10 years selected by the **clearing manager**.
- (6) The **clearing manager** must determine the amount under subclause (2)(c)(ii)—
- (a) once for each calendar year; and
  - (b) no later than 2 months before the beginning of each calendar year.
- (7) The methodology must specify how the clearing manager will estimate the initial amount of security for **ancillary services** for a new **participant**.
- (8) The expected amounts to be incurred and earned by the **participant** in respect of a **hedge settlement agreement** must be based on the price determined by the **clearing manager** under subclause (2)(c).

Clause 10(1)(ab): inserted, on 24 March 2015, by clause 33 of the Electricity Industry Participation Code Amendment (Extended Reserve) 2014.

Clause 10(5)(b): amended, on 24 March 2015, by clause 25(1) of the Electricity Industry Participation Code Amendment (Settlement and Prudential Security) 2014.

Clause 10(6)(a): amended, on 24 March 2015, by clause 25(2) of the Electricity Industry Participation Code Amendment (Settlement and Prudential Security) 2014.

## 11 FTR prudential requirement

The **FTR** prudential requirement for a **participant** is the sum of the following amounts:

- (a) the **clearing manager's** estimate of an amount to be incurred or earned by the **participant** in respect of any **FTR** in respect of which the **participant** is named in the **FTR register**, calculated in accordance with the methodology approved by the **Authority** under clause 12;
- (b) the amount of any **FTR acquisition cost** in respect of an **FTR** held by the **participant**;
- (c) any amount payable by the **participant** to the **clearing manager** under clause 13.249(4) minus any amount payable by the **clearing manager** to that **participant** under clause 13.249(7).

**12 Methodology for determining minimum security required in respect of FTRs**

- (1) The **clearing manager** must formulate and **publish** a methodology for determining the minimum amount for which security is required to be provided in relation to a matter set out in clause 11(a).
- (2) The methodology formulated by the **clearing manager** under subclause (1) must comply with the principle that the amount taken into account under clause 11(a) is an estimate of the **FTR hedge value** (being an amount that may be positive or negative) of the **FTR** at the time that the estimate is made and the potential for that value to change before the **clearing manager** is able to realise the value of the **FTR** following an **event of default** occurring in relation to the holder of the **FTR**.
- (3) The consultation and approval requirements set out in Schedule 14.2 apply to the methodology.

**13 Information to be considered by clearing manager**

In estimating the amounts described in this Part, the **clearing manager** may take into account a substantial change to a **participant's business**.

## Schedule 14A.2 Guarantee

Schedule 14A.1, cl 3

To: [Clearing manager] [address]

Attention: [name]

Dear Sir/Madam

1. [Bank] (“the Bank”) refers to each and every obligation pursuant to the Electricity Industry Participation Code 2010 (“the Code”) of [Participant] (“the Principal”) to pay amounts the Principal, now or at any time, owes to, and is invoiced by, you (whether as principal or agent) together with default interest, if any, in relation to such amounts (“the Obligations”) pursuant to the Code.
2. The Bank unconditionally guarantees the payment to you on demand of an amount specified in each such demand provided that—

[(a) the aggregate liability of the Bank under this guarantee will not exceed [amount determined from time to time by the clearing manager calculated in accordance with clause 14A.5 of the Code] (the “Maximum Amount”); and]

[Note: Bank to elect either this paragraph or the following paragraph].

[(a) the aggregate liability of the Bank under this guarantee in respect of which this guarantee is in effect will not exceed the Maximum Amount as defined below—

- (i) The sum of the amounts calculated for all trading periods to which this guarantee applies in any period to which a demand under this guarantee relates in accordance with the following formula:

$$A*B$$

where

A is [X] MWh

B is the final price for the trading period at the [specify] [grid injection point/grid exit point/reference point]

- (ii) For the purposes of subparagraph (i) this guarantee applies to every trading period within any period to which a demand under this guarantee relates as follows:

A. From the [“Starting Date” being] the later of—

1. the start of the period; and
2. [DATE]; and

- B. Until the “Final Date” being the earlier of—
1. the end of the period; and
  2. the Final Date as notified to the clearing manager under paragraph 2(a)(iii); and
  3. [DATE];
- (iii) Notwithstanding anything in this guarantee or in the Code, the Bank may give the clearing manager notice of the Final Date for the purposes of paragraph 2(a)(ii)B. The Final Date is the later of the date specified in the notice or 2 business days after the date on which the clearing manager receives the notice; and]
- (b) your demand is made in writing and is purported to be signed by an authorised signatory; and
- (c) a certificate purported to be signed by your authorised signatory and certifying that the Principal has failed, in whole or in part, to fulfil the Obligations accompanies your demand, which certificate will be conclusive proof of such failure.
3. This guarantee will not be affected, discharged, or diminished by any act or omission which would, but for this provision, have exonerated a guarantor but would not have affected or discharged the Bank’s liability had it been a principal debtor.
4. Subject to paragraph 5 below, this guarantee will continue in force until the date at which the Principal has ceased to be bound by the Code and has discharged its obligations to you under the Code at which time you will return this guarantee to the Bank.
- [5. Despite anything else in this guarantee, the Bank may at any time pay you the Maximum Amount less any amount or amounts the Bank may previously have paid under this guarantee or such lesser sum as you may require. Upon payment of that sum, the liability of the Bank under this guarantee will cease and determine].
- [Note: Bank to elect either this paragraph or the following paragraph as a method of cancellation].
- [5. Despite anything else in this guarantee, the Bank may cancel this guarantee as to subsequent liability by giving ninety (90) days’ notice in writing to [clearing manager]; however, the Bank will remain liable with respect to the Obligations that relate to the period prior to the effective date of the ninety (90) days’ notice.]
6. This guarantee may be assigned by you without the Bank’s consent. It will bind the successors and assigns of the Bank, as well as any entity with which the Bank may amalgamate.

7. This guarantee is governed by and interpreted in all respects in accordance with New Zealand law and the parties irrevocably submit to the non-exclusive jurisdiction of the courts of New Zealand.

EXECUTED for and on behalf     )  
of [BANK]                             )  
by its Attorneys                    )  
.....                                 )  
[Print Names]                        )     Signature(s)

.....  
in the presence of:  
.....  
Signature  
.....  
Full Name  
.....  
Address  
.....  
Occupation  
.....  
Signature(s)



## **Schedule 14A.3**

### **Deed of guarantee and indemnity**

Schedule 14A.1, cl 3

DATED

BY

1. [ ] (the “Guarantor”)

IN FAVOUR OF

2. [Clearing manager] (the “Beneficiary”)

#### **1 Guarantee and indemnity**

1. The Guarantor—

- (a) unconditionally and irrevocably guarantees to the Beneficiary the due performance and observance by [Participant] (“the Debtor”) of each and every obligation the Debtor may now or hereafter have to the Beneficiary to pay amounts it owes to, and is invoiced by, the Beneficiary (whether as principal or agent) together with default interest, if any, in relation to such amounts (“the Obligations”) pursuant to the Electricity Industry Participation Code 2010 (“the Code”) and promises to pay to the Beneficiary on demand all amounts now or hereafter owing, due or payable by the Debtor to the Beneficiary in respect of the Obligations; and
- (b) agrees as a primary obligation to indemnify the Beneficiary from time to time on demand from and against any loss incurred by the Beneficiary as a result of any of the Obligations being void, voidable or unenforceable for any reason, whether or not known to the Beneficiary, the amount of such loss being the amount that the Beneficiary would otherwise have been entitled to recover from the Debtor.

- 2. This Deed is to be security in respect of each and every one of the Obligations but, nevertheless, the total amount payable by the Guarantor under this Deed must not exceed the aggregate of [amount determined from time to time by the clearing manager calculated in accordance with clause 14A.5 of the Code] (the “Maximum Amount”) and any sums payable under clauses 1(3) and 9 of this Deed.
- 3. If any moneys payable by the Guarantor under this Deed are not paid on demand, the Guarantor must pay to the Beneficiary interest on such unpaid moneys (both before and after judgement) at the rate determined in accordance with clause 1(4) of this Deed from the date of demand to the date of their actual receipt by the Beneficiary calculated on a daily basis and capitalised as the Beneficiary will determine.
- 4. The rate at which interest must be calculated is the aggregate of 5% per annum plus the then prevailing settlement bid rate for 90 day bills displayed on Reuters Screen BKBM

at 10:45am on the date of demand or, if for any reason that rate is not displayed, the rate determined by the Beneficiary to be the nearest practicable equivalent.

## **2 Preservation of rights**

1. The obligations of the Guarantor under this Deed are in addition to, and not in substitution for, any other security or guarantee that the Beneficiary may at any time hold in respect of the Obligations or any of them and may be enforced without the Beneficiary first having recourse to any such security and without the Beneficiary first taking steps or proceedings against the Debtor.
2. Neither the obligations of the Guarantor under this Deed nor the rights, powers, and remedies conferred in respect of the Guarantor upon the Beneficiary by this Deed or by law may be discharged, impaired, or otherwise affected by anything that might operate to discharge, impair, or otherwise affect the same, including—
  - (a) the insolvency, liquidation, or dissolution of the Debtor or any other person, the appointment of any receiver, manager, receiver and manager, inspector, trustee, statutory manager, or other similar person in respect of the Debtor or any other person, or any change in the Debtor's status, function, control, or ownership; and
  - (b) any of the Obligations, or the obligations of any person under any security or guarantee held in relation to any of the Obligations, being or becoming in whole or in part void, voidable, defective, illegal, invalid, or unenforceable in any respect or ranking after any other security; and
  - (c) any time, credit or other indulgence or other concession being granted or agreed to be granted by the Beneficiary to, or any composition or other arrangement made with or accepted from, the Debtor in respect of any of the Obligations or the obligations of any person under any security or guarantee held in relation to the same; and
  - (d) any variation of the terms of any of the Obligations or of any security or guarantee (including this guarantee) held in relation to the same; and
  - (e) any failure to realise or fully realise the value of, or any release, discharge, exchange, or substitution of, any security or guarantee held in relation to any of the Obligations;
  - (f) any failure (whether intentional or not) to take, fully take or perfect any security now or hereafter agreed to be taken by the Beneficiary in relation to any of the Obligations; and
  - (g) any other act, event or omission that, but for this clause 2(2), would or might operate or discharge, impair, or otherwise affect any of the obligations of the

Guarantor under this Deed or any of the rights, powers, or remedies conferred upon the Beneficiary by the rules or by law.

3. If any payment to the Beneficiary under this Deed is avoided by law, the Guarantor's obligation to have made such payment will be deemed not to have been affected or discharged and the Guarantor must on demand indemnify the Beneficiary against all costs sustained or incurred by the Beneficiary as a result of it being required for any reason to refund all or part of any amount received or recovered by it in respect of such payment and must in any event pay to the Beneficiary on demand the amount so refunded by it. The Beneficiary and the Guarantor will, in any such case, be deemed to be restored to the position in which each would have been and will be entitled to exercise the rights they respectively would have had if that payment had not been made.
4. The Beneficiary is not obliged before exercising any of the rights, powers, or remedies conferred upon it in respect of the Guarantor by law to make any demand on the Debtor, take any action or obtain judgement in any court against the Debtor, make or file any claim or prove in any liquidation of the Debtor, or enforce or seek to enforce any security or guarantee taken in respect of the Obligations.
5. After a demand has been made by the Beneficiary under this Deed, and so long as the Guarantor is under any actual or contingent liability under this Deed, the Guarantor must not—
  - (a) exercise in respect of any amount paid by the Guarantor under this Deed any right of subrogation or any other right or remedy that the Guarantor may have in respect of such amount paid; or
  - (b) except with the Beneficiary's consent in writing, claim or receive payment of any other moneys for the time being due to the Guarantor by the Debtor or exercise any other right or remedy that the Guarantor may have in respect of the same; or
  - (c) unless so required by the Beneficiary, prove in the liquidation of the Debtor in competition with the Beneficiary for any moneys owing to the Guarantor by the Debtor on any account.

Any moneys obtained by the Guarantor from the Debtor with such consent or as so required or in breach of this clause must, in each case, be held by the Guarantor upon trust to pay such moneys to the Beneficiary in or towards discharge of the Guarantor's obligations under this Deed.

6. Any moneys received by the Beneficiary that may be applied in or towards discharge of any of the obligations of the Guarantor under this Deed must be regarded as a payment in gross so that, in the event of the liquidation of the Guarantor, the Beneficiary may prove in the liquidation for the whole of such moneys.

### **3 Representations and warranties**

The Guarantor represents that—

- (a) it is duly incorporated and validly existing under the laws of [New Zealand], capable of suing and being sued and has the power to enter into and perform this Deed, and has taken all necessary corporate action to authorise it to enter into, execute, deliver, and perform its obligations under this Deed; and
- (b) its entry into, execution, delivery, and performance of this Deed will not contravene any law or regulation to which the Guarantor is subject or any provision of its constitutional documents and all things (including the obtaining of consents) requisite for such entry, execution, delivery, and performance have been taken, fulfilled, and done, and are in full force and effect; and
- (c) no obligation of the Guarantor under this Deed is secured by, and the execution, delivery and performance of this Deed will not result in the existence of, or oblige it to create, any mortgage, charge, pledge, lien or other encumbrance over any of its present or future revenues or assets; and
- (d) the execution, delivery of and performance of the Guarantor's obligations under this Deed will not cause the Guarantor to be in breach of or in default under any agreement binding on the Guarantor or any of its assets and no material litigation or administrative proceeding before, by or of any court or governmental authority is pending or (so far as the Guarantor knows) threatened against the Guarantor or any of its assets which, if decided against the Guarantor, would have a material adverse effect on the ability of the Guarantor to meet any or all of the obligations hereunder.

### **4 Payments**

All payments to be made by the Guarantor to the Beneficiary under this Deed must be made without set-off or counterclaim and without any deduction or withholding. If the Guarantor is obliged by law to make any deduction or withholding from any such payment, the amount due from the Guarantor in respect of such payment will be increased to the extent necessary to ensure that, after the making of such deduction or withholding, the Beneficiary receives a net amount equal to the amount the Bank would have received had no such deduction or withholding been required to be made.

### **5 Continuing security**

This Deed will be a continuing security to the Beneficiary in respect of each and every one of the Obligations and must not be (or be construed so as to be) discharged by any intermediate discharge or payment of or on account of the Obligations or any settlement of accounts between the Beneficiary and the Debtor or anyone else.

## **6 Termination**

- [1. Despite anything else in this Deed, the Guarantor may at any time pay to you the Maximum Amount less any amount or amounts the Guarantor may previously have paid under this Deed or such lesser sum as you may require. Upon payment of that sum, the liability of the Guarantor under this Deed will cease and determine.]

[Note: Guarantor to elect either this clause or the following clause as a method of cancellation.]

- [1. Despite anything else in this Deed the Guarantor may cancel this Deed as to subsequent liability by giving ninety (90) days' notice in writing to [Clearing manager]; however, the Guarantor will remain liable with respect to the Obligations that relate to the period prior to the effective date of the ninety (90) days' notice.]

## **7 Assignment**

This Deed may be assigned by the Beneficiary without the Guarantor's consent. It will bind the successors and assigns of the Guarantor, as well as any entity with which the Guarantor may amalgamate.

## **8 Notices**

1. Any demand to be made on the Guarantor by the Beneficiary under this Deed may be made in writing and delivered to the address set out below or to any other address in New Zealand from time to time notified under clause 8(2). The Guarantor's address, as at the date of this Deed is: [address]
2. The Guarantor must immediately notify the Beneficiary of any change in the above address.

## **9 Costs and expenses**

The Guarantor must on demand indemnify and hold harmless the Beneficiary from and against all costs and expenses (including legal fees and any taxes or duties) incurred by the Beneficiary in the enforcement and protection of its rights under this Deed.

## **10 Governing law**

This Deed is governed by, and construed in accordance with New Zealand law, and the Guarantor irrevocably submits to the non-exclusive jurisdiction of the courts of New Zealand.

EXECUTED for and on behalf )  
of [Guarantor] )

**Electricity Industry Participation Code 2010**  
**Schedule 14A.3**

---

in the presence of: )

.....

.....

Director Director/Secretary

.....

Signature

.....

Full Name

.....

Address

.....

Occupation

Note I: If two directors sign, no witness is necessary. If a director and secretary sign, both signatories are to be witnessed. If the director and secretary are not signing together, a separate witness will be necessary for each signature.

Note II: If the Guarantor is incorporated outside of New Zealand, insert an appropriate execution clause for the country of incorporation.

**Schedule 14A.4**  
**Letter of credit**

Schedule 14A.1, cl 3

To: [Clearing manager] [address]

Attention: [name]

Dear Sir/Madam

We, [Bank] (“the Bank”) issue our irrevocable transferable standby letter of credit (“the Letter of Credit”) as follows:

IRREVOCABLE TRANSFERABLE STANDBY LETTER OF CREDIT NO. [number]  
DATED [date]

The Account Party: [Participant] (“the Account Party”)

Beneficiary: [Clearing manager] (“the Beneficiary”)

Issued in Connection With: Each and every obligation (“the Obligations”) of the Account Party to pay the amounts it, now or at any time, owes to, and is invoiced by, the Beneficiary (whether as principal or agent) together with default interest, if any, in relation to such amounts under the Electricity Industry Participation Code 2010 (“the Code”).

Maximum Amount: [insert amount].

Expiry: This Letter of Credit expires on the earliest of—

- (a) the date at which the Account Party has ceased to be bound by the Code and has discharged its obligations to the Beneficiary under the Code; or
- (b) the date of satisfaction of this Letter of Credit in accordance with its terms; or
- [(c) the date on which the Bank makes payment to the Beneficiary of the Maximum Amount either at its sole discretion or following demand by the Beneficiary under this Letter of Credit in accordance with its terms],

[Note: Bank to elect either this clause or the following clause as a method of cancellation.]

- [(c) ninety (90) days after notice in writing of cancellation of this Letter of Credit as to subsequent liability has been given to [Clearing manager]; however, the Bank will remain liable with respect to the Obligations that relate to the period prior to the effective date of the ninety (90) days’ notice.]

(“the Expiry Date”).

Payable at: [Sight or by demand using SWIFT]

Available at: [address]

By Drafts on:     The Bank.

Enfaced:             Drawn under [Bank] Irrevocable Standby Letter of Credit No. [number]  
dated [date].

Returnable to:     The Bank upon expiry.

The proceeds of this Letter of Credit are transferable by the Beneficiary. A claim may be made under this Letter of Credit by delivering to the address at which this Letter of Credit is expressed to be available, by no later than [time] New Zealand time on or before the Expiry Date, draft drawn on the Bank (enfaced as specified above) accompanied by—

- (a)   this Letter of Credit; and
- (b)   a Certificate purported to be signed by an authorised signatory of the Beneficiary in the following form:

To [Bank] [date]

[Clearing manager] of [address] (“the Beneficiary”) hereby makes claim under the [Bank] Irrevocable Standby Letter of Credit No [number] (“the Letter of Credit”). Words and expressions defined in the Letter of Credit will have the same meaning in this Certificate.

[Participant] (“the Account Party”) has failed, in whole or in part, to fulfil the Obligations.

As at the date of this Certificate, the amount owed to the Beneficiary by the Account Party in respect of the Obligations is the sum of [amount outstanding].

Accordingly, the Beneficiary is entitled to claim and requests payment by [date] of the amount of [amount claimed] to be credited to account number [Beneficiary’s trust account number].

The signatory or signatories is/are authorised by the Beneficiary to make the statements in this Certificate on behalf of the Beneficiary.

Signed.....

Authorised Signatory

This Letter of Credit is subject to the Uniform Customs and Practice for Documentary Credits (2007 Revision) International Chamber of Commerce Publication No. 600 [and the Supplement to the Uniform Customs and Practice for Documentary Credits for Electronic Presentation 2007], except as otherwise provided in this Letter of Credit. Subject to that, this Letter of Credit will be governed by, and construed in accordance with, the laws of New Zealand, and the parties irrevocably submit to the non-exclusive jurisdiction of the courts of New Zealand.

The Bank engages with the Beneficiary that drafts drawn under, and in compliance with, this Letter of Credit and, in aggregate, up to the Maximum Amount will be paid on presentation in the manner provided in this Letter of Credit.



**Electricity Industry Participation Code 2010  
Schedule 14A.4**

---

EXECUTED for and on behalf     )  
of [BANK]                             )  
by its Attorneys                    )  
.....                                )  
[Print Names]                        )     Signature(s)

.....  
in the presence of:

.....  
Signature

.....  
Full Name

.....  
Address

.....  
Occupation

---

## Schedule 14A.5 Surety bond

Schedule 14A.1, cl 4

To: [Clearing manager] [address]

Bond Number:

We, [Participant] as Principal, and [name of Surety], as Surety, are held and firmly bound to [Clearing manager], a corporation organised and existing under the laws of New Zealand, its successors and assigns, in the amount of [amount in words] New Zealand dollars (NZ\$ ), lawful money of New Zealand for the payment of which the Principal and Surety, their heirs, executors, administrators, successors and assigns are jointly and severally bound.

### RECITALS

The Principal has obligations (the “Obligations”) pursuant to the Electricity Industry Participation Code 2010 (the “Code”) to pay [Clearing manager] amounts invoiced to it by [Clearing manager].

The Surety agrees to deliver payment to [Clearing manager] of amounts invoiced to the Principal (together with any default interest payable in respect of those invoiced amounts) forthwith upon receipt of written demand for payment issued by a purported authorised representative of [Clearing manager]. Such written demands must be delivered to the Surety at its above address and certify that the Principal has failed, in whole or in part, to fulfil the Obligations.

The Surety is not liable for a larger amount, in the aggregate, than the amount of this Bond.

[The Surety may at any time pay to [Clearing manager] the amount of this Bond less any amount or amounts the Surety may previously have paid under this Bond or such lesser sum as [Clearing manager] may require. Upon payment of that sum, the liability of the Surety under this Bond will cease and determine.]

[Note: Surety to elect either this proviso or the following proviso as a method of cancellation.]

[This Bond may be cancelled by the Surety as to subsequent liability by giving ninety (90) days’ notice in writing to [Clearing manager]. However, the Surety remains liable with respect to the Principal’s Obligations that relate to the period prior to the effective date of the ninety (90) days’ notice.]

This Bond is not affected, discharged, or diminished by any act or omission that would, but for this provision, have exonerated a surety but would not have affected or discharged the Surety’s liability had it been a principal debtor.

This Bond is governed by, and interpreted according to, the laws of New Zealand, and the Principal and the Surety agree to submit to the non-exclusive jurisdiction of the courts of New Zealand.

This Bond may be transferred or assigned by [Clearing manager] without the Surety’s consent. Upon cancellation, the Bond will be returned to the Surety.

## **EXECUTION CLAUSE**

Schedule 14A.5: amended, on 24 March 2015, by clause 26 of the Electricity Industry Participation Code Amendment (Settlement and Prudential Security) 2014.

# Electricity Industry Participation Code 2010

## Part 15 Reconciliation

### Contents

- 15.1 Contents of this Part
- 15.2 Requirement to provide complete and accurate information
- 15.3 Provision of trading information at point of connection to network
  - Provision of information to the reconciliation manager*
- 15.4 Submission information to be delivered for reconciliation
- 15.5 Preparing and submitting submission information
- 15.5A Dispatchable load purchaser must prepare dispatchable load information
- 15.5B Deriving volume information if metering installation is within premises that are connected to a point of connection
- 15.5C Aggregating and rounding dispatchable load information
- 15.5D Dispatchable load information to be delivered to reconciliation manager
  - Additional retailer and direct purchaser information*
- 15.6 Retailer and direct purchaser ICP days information
- 15.7 Retailer electricity supplied information
- 15.8 Retailer and direct purchaser half hourly metered ICPs monthly kWh information
  - NSP information*
- 15.9 Grid owner volume information
- 15.10 Participants to provide NSP submission information
- 15.11 Grid connected generator
- 15.12 Accuracy of submitted information
- 15.13 Notice by embedded generators
- 15.14 Notice of changes to the grid
  - Notice of outage constraints or alternative supply*
- 15.15 Notice of points of connection subject to outages or alternative supply
- 15.16 Balancing area NSP grouping changes
- 15.17 Submission information to be reviewed in the case of an outage constraint
- 15.18 Reconciliation manager may request additional information
- 15.19 Seasonal adjustment and profiling
- 15.20 Calculation and allocation of unaccounted for electricity
  - Reconciliation manager processes dispatchable load information and provides it to the clearing manager*
- 15.20A Reconciliation manager to update revised dispatchable load information
- 15.20B Reconciliation manager loss adjusts and summarises dispatchable load information
- 15.20C Reconciliation manager to provide loss adjusted and summarised dispatchable load information to clearing manager
- 15.20D Reconciliation manager to provide loss adjusted and summarised dispatchable load information to dispatchable load purchasers
  - Reconciliation information produced by reconciliation manager*
- 15.21 Providing information specific to reconciliation participants
- 15.22 Providing information to reconciliation participants
- 15.23 Reconciliation information is not final
- 15.24 Reconciliation information checked

- 15.25 Reconciliation manager must assess information not supplied  
15.26 Reconciliation manager to correct information  
*Revisions*  
15.27 Reconciliation manager must reconcile revised information  
15.28 Transitional provisions concerning revisions  
15.29 Volume information disputes  
*Reporting obligations of the reconciliation manager*  
15.30 Alleged Code breaches reported by the reconciliation manager  
15.31 Right to information concerning reconciliation manager's actions  
15.32 Reconciliation reports  
15.33 The Authority publishes reports  
15.34 Use of agents by reconciliation participants  
15.35 Provision of information  
15.36 New Zealand Daylight Time adjustment techniques  
15.37 *[Revoked]*  
15.37A Reconciliation participants and dispatchable load purchasers to arrange for regular audits  
15.37B Retailers to arrange for audits in respect of distributed unmetered load  
15.37C Authority and participant requested audits  
*Certification*  
15.38 Functions requiring certification  
*Participant identifiers*  
15.39 Participants must use participant identifiers

#### **Schedule 15.1**

#### **Certification process**

#### **Schedule 15.2**

#### **Collection of volume information**

*Meter interrogation for non half hour metering*

*Validation*

#### **Schedule 15.3**

#### **Calculation and provision of submission information**

*Creation of submission information*

#### **Schedule 15.4**

#### **Reconciliation procedures**

*Convert non half hour quantities using profiles*

#### **Schedule 15.5**

#### **Profile administration**

*New NSP derived profiles*

*New statistically sampled/engineered profiles*

*Appendix 1: Profile classes*

*Participants NSP-derived profiles*

*Statistically sampled and engineering profile classes*

*Appendix 2: Determining statistically sampled profiles*

---

### 15.1 Contents of this Part

This Part provides for the following:

- (a) the improvement of information about **electricity** conveyed as more **volume information** becomes available over time;
- (b) the correction of information to remedy errors in information provided;
- (c) how **reconciliation participants** must gather, store and provide information about **electricity** conveyed;
- (d) how **reconciliation participants** must prepare and provide **submission information**;
- (da) how **dispatchable load purchasers** must collect **volume information** in accordance with Schedule 15.2;
- (e) how the **reconciliation manager** must calculate responsibility for **electricity** among **reconciliation participants**;
- (f) how the **reconciliation manager** must pass information to the **clearing manager**, for the calculation of amounts owing under Part 14;
- (g) obligations of the **reconciliation manager** to pass the information to **reconciliation participants**, the **registry manager** and the **Authority**;
- (h) requirements for the creation, approval and maintenance of **profiles**;
- (i) requirements for **audits**, approvals and **certifications**.

Compare: Electricity Governance Rules 2003 rule 1 part J

Clause 15.1(da): inserted, on 15 May 2014, by clause 95 of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

Clause 15.1(f): amended, on 24 March 2015, by clause 21 of the Electricity Industry Participation (Settlement and Prudential Security) Code Amendment 2013.

Clause 15.1(g): amended, on 5 October 2017, by clause 512 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 15.1(i): amended, on 1 June 2017, by clause 23 of the Electricity Industry Participation Code Amendment (Requirements and Processes for Audits) 2016.

### 15.2 Requirement to provide complete and accurate information

- (1) A **participant** must take all practicable steps to ensure that information that the **participant** is required to provide to any person under this Part is—
  - (a) complete and accurate; and
  - (b) not misleading or deceptive; and
  - (c) not likely to mislead or deceive.
- (2) If a **participant** becomes aware that the information the **participant** provided under this Part does not comply with subclause (1)(a) to (c), even if the **participant** has taken all practicable steps to ensure that the information complies, the **participant** must, as soon as practicable, provide such further information as is necessary to ensure that the information complies with subclause (1)(a) to (c).

Compare: Electricity Governance Rules 2003 rule 1A part J

Clause 15.2(2): substituted, on 19 December 2014, by clause 39 of the Electricity Industry Participation Code Amendment (Minor Code Amendments) (No 3) 2014.

### 15.3 Provision of trading information at point of connection to network

- (1) Unless a notice under clause 15.13 is in force, a **trader** must give the **reconciliation manager** a notice that complies with this clause at least **5 business days** before the **trader**—

- (a) commences trading **electricity** at a **point of connection** using a **profile** with a **profile** code other than HHR or RPS or UML or EG1 or PV1; or
- (b) ceases trading **electricity** at a **point of connection** using a **profile** with a **profile** code other than HHR or RPS or UML or EG1 or PV1.
- (2) A person giving a notice must ensure that the notice complies with any procedures or other requirements specified by the **reconciliation manager**.
- (3) The **reconciliation manager** must give a copy of every notice to the **clearing manager** and **system operator** no later than 1 **business day** after receiving the notice.

Compare: Electricity Governance Rules 2003 rule 3 part J

Clause 15.3: amended, on 5 October 2017, by clause 513 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

#### *Provision of information to the reconciliation manager*

### **15.4 Submission information to be delivered for reconciliation**

- (1) Each **reconciliation participant** must, by 1600 hours on the 4th **business day** of each **reconciliation period**, ensure that **submission information** has been delivered to the **reconciliation manager** for all **NSPs** for which the **reconciliation participant** is recorded in the **registry** as having **traded electricity** during the **consumption period** immediately before that **reconciliation period**, in accordance with Schedule 15.3.
- (2) Each **reconciliation participant** must, by 1600 hours on the 13th **business day** of each **reconciliation period**, ensure that **submission information** has been delivered to the **reconciliation manager** for all **points of connection** for which the **reconciliation participant** is recorded in the **registry** as trading **electricity** during any **consumption period** being reconciled in accordance with clauses 15.27 and 15.28, and in respect of which the **reconciliation participant** has obtained revised **submission information**, in accordance with Schedule 15.3.

Compare: Electricity Governance Rules 2003 rules 4.1.1 and 4.1.2 part J

### **15.5 Preparing and submitting submission information**

- (1) In preparing and submitting **submission information**, a **reconciliation participant** must ensure that **volume information** for each **ICP** is allocated to the **NSP** indicated by the data in the **registry** for the relevant **consumption period** at the time the **reconciliation participant** assembles the **submission information**.
- (2) Each **reconciliation participant** must derive **volume information** in accordance with Schedule 15.2.
- (3) If a notice under clause 15.13 is in force for an **embedded generating station** in relation to a **point of connection**, a **reconciliation participant** who trades at the **point of connection** is not required to comply with clause 15.4 or this clause in relation to **electricity** generated by the **embedded generating station** to which the notice relates.

Compare: Electricity Governance Rules 2003 rules 4.1.3 and 4.1.4 part J

Clause 15.5(1) and (3): amended, on 5 October 2017, by clause 514(a) and (b) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 15.5(2): substituted, on 15 May 2014, by clause 96 of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

Clause 15.5(3): amended, on 21 September 2012, by clause 37 of the Electricity Industry Participation (Minor Amendments) Code Amendment 2012.

### 15.5A Dispatchable load purchaser must prepare dispatchable load information

- (1) Each **dispatchable load purchaser** must prepare **dispatchable load information** using **volume information** prepared in accordance with Schedule 15.2.
- (2) If clause 15.5B applies to a **dispatch-capable load station's metering installation**, the **dispatchable load purchaser** responsible for the **dispatch-capable load station** must comply with clause 15.5B in relation to the **dispatch-capable load station**.

Clause 15.5A: inserted, on 15 May 2014, by clause 97 of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

Clause 15.5A(1): amended, on 1 February 2016, by clause 94(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

Clause 15.5A(2): substituted, on 1 February 2016, by clause 94(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

### 15.5B Deriving volume information if metering installation is within premises that are connected to a point of connection

- (1) This clause applies if a **dispatch-capable load station's metering installation** is not at a **point of connection** but is located within premises that are directly connected to a **point of connection**.
- (2) If this clause applies, the **dispatchable load purchaser** responsible for the **dispatch-capable load station** must prepare **dispatchable load information** using **volume information** prepared in accordance with Schedule 15.2 and derived from the **raw meter data**—
  - (a) obtained from the **metering installation**; and
  - (b) that the **dispatchable load purchaser** has adjusted, using an accurate **compensation factor**, to compensate for internal site **losses** between the **metering installation** and—
    - (i) if the premises are directly connected to a **point of connection** to the **grid**, the **point of connection** to the **grid**; or
    - (ii) if the premises are directly connected to a **point of connection** to a **local network**, the **point of connection** to the **local network**; or
    - (iii) if the premises are directly connected to a **point of connection** to an **embedded network**, the **point of connection** to the **embedded network**.
- (3) For the purpose of this clause, a **dispatchable load purchaser** must have a **certified metering installation** for each of its **dispatch-capable load stations**.

Clause 15.5B: inserted, on 15 May 2014, by clause 97 of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

Clause 15.5B: amended, on 23 February 2015, by clause 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 15.5B(1) and (2)(b): amended, on 5 October 2017, by clause 515 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 15.5B(2): amended, on 1 February 2016, by clause 95(a) and (b) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

### 15.5C Aggregating and rounding dispatchable load information

- (1) When preparing **dispatchable load information**, a **dispatchable load purchaser** must—
  - (a) aggregate **volume information** to the following level:
    - (i) **NSP code**;
    - (ii) **dispatch-capable load station identifier**;
    - (iii) **loss category code**;
    - (iv) **trading period**; and
  - (b) round the aggregated **volume information**—



- (i) to 2 decimal places; and
  - (ii) so that if the digit to the right of the second decimal place is—
    - (A) greater than or equal to 5, the second digit is rounded up; or
    - (B) less than 5, the second digit is unchanged.
- (2) When aggregating **volume information** for a **dispatch-capable load station** to the **NSP**, the **dispatchable load purchaser** must use the **NSP** code as shown in the **registry** at the time the **volume information** is derived.

Clause 15.5C: inserted, on 15 May 2014, by clause 97 of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

Clause 15.5C(2): amended, on 5 October 2017, by clause 516 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

#### **15.5D Dispatchable load information to be delivered to reconciliation manager**

- (1) Each **dispatchable load purchaser** must provide to the **reconciliation manager**—
  - (a) **dispatchable load information** for each **GXP** at which the **dispatchable load purchaser** has purchased **electricity** for a **dispatch-capable load station** during the **consumption period** immediately before each **reconciliation period**; and
  - (b) if the **dispatchable load purchaser** knows that **dispatchable load information** previously provided has changed, revised **dispatchable load information** for the **consumption period** for which the **dispatchable load information** was initially provided.
- (2) Each **dispatchable load purchaser** must provide—
  - (a) the information described in subclause (1)(a) by 1600 hours on the 4th **business day** of each **reconciliation period**; and
  - (b) the information described in subclause (1)(b) by 1600 hours on the 13th **business day** of each **reconciliation period**.

Clause 15.5D: inserted, on 15 May 2014, by clause 97 of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

#### *Additional retailer and direct purchaser information*

#### **15.6 Retailer and direct purchaser ICP days information**

- (1) Each **retailer** and **direct purchaser** (excluding **direct consumers**) must deliver a report to the **reconciliation manager** detailing the number of **ICP days** for each **NSP** for each submission file of **submission information** in respect of—
  - (a) **submission information** for the immediately preceding **consumption period**, by 1600 hours on the 4th **business day** of each **reconciliation period**; and
  - (b) revised **submission information** provided in accordance with clause 15.4(2), by 1600 hours on the 13th **business day** of each **reconciliation period**.
- (2) The **retailer** or **direct purchaser** must calculate the **ICP days** information in subclause (1) using the data contained in the **retailer's** or **direct purchaser's** reconciliation system when it aggregates **volume information** for **ICPs** into **submission information**.

Compare: Electricity Governance Rules 2003 rule 4.2.1 part J

#### **15.7 Retailer electricity supplied information**

Each **retailer** must deliver to the **reconciliation manager** the **retailer's** total monthly quantity of **electricity supplied** for each **NSP**, aggregated by invoice month, for which

the **retailer** has provided **submission information** to the **reconciliation manager**, including revised **submission information** for that period as non **loss** adjusted values in respect of—

- (a) **submission information** for the immediately preceding **consumption period**, by 1600 hours on the 4th **business day** of each **reconciliation period**; and
- (b) revised **submission information** provided in accordance with clause 15.4(2), by 1600 hours on the 13th **business day** of each **reconciliation period**.

Compare: Electricity Governance Rules 2003 rule 4.2.2 part J

### 15.8 Retailer and direct purchaser half hourly metered ICPs monthly kWh information

Each **retailer** and **direct purchaser** (excluding **direct consumers**) must deliver to the **reconciliation manager** the **retailer's** or **direct purchaser's** total monthly quantity of **electricity supplied** for each **half hourly** metered **ICP** for which the **retailer** or **direct purchaser** has provided **submission information** to the **reconciliation manager**, including—

- (a) **submission information** for the immediately preceding **consumption period**, by 1600 hours on the 4th **business day** of each **reconciliation period**; and
- (b) revised **submission information** provided in accordance with clause 15.4(2), by 1600 hours on the 13th **business day** of each **reconciliation period**.

Compare: Electricity Governance Rules 2003 rule 4.2.3 part J

### *NSP information*

### 15.9 Grid owner volume information

Each **grid owner** must deliver to the **reconciliation manager**, for each **point of connection** for all of its **GXPs**, the following:

- (a) **submission information** for the immediately preceding **consumption period**, by 1600 hours on the 4th **business day** of each **reconciliation period**;
- (b) revised **submission information** provided in accordance with clause 15.4(2), by 1600 hours on the 13th **business day** of each **reconciliation period**.

Compare: Electricity Governance Rules 2003 rule 4.3.1 part J

### 15.10 Participants to provide NSP submission information

A **participant** must provide the following information to the **reconciliation manager** for each **NSP** for which the **participant** has given a notice under clause 25(1) of Schedule 11.1:

- (a) **submission information** for the immediately preceding **consumption period**, by 1600 hours on the 4th **business day** of each **reconciliation period**; and
- (b) revised **submission information** provided in accordance with clause 15.4(2), by 1600 hours on the 13th **business day** of each **reconciliation period**.

Compare: Electricity Governance Rules 2003 rule 4.3.2 part J

Clause 15.10 heading: substituted, on 19 December 2014, by clause 40 of the Electricity Industry Participation Code Amendment (Minor Code Amendments) (No 3) 2014.

Clause 15.10: amended, on 15 May 2014, by clause 58 of the Electricity Industry Participation (Minor Code Amendments) Code Amendment 2014.

Clause 15.10: amended, on 5 October 2017, by clause 517 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### 15.11 Grid connected generator

Each **generator** who has a **generating station** or **generating unit** with a **point of connection** to the **grid** must deliver to the **reconciliation manager** for each of its **points of connection**—

- (a) **submission information** for the immediately preceding **consumption period**, by 1600 hours on the 4th **business day** of each **reconciliation period**; and
- (b) revised **submission information** provided in accordance with clause 15.4(2), by 1600 hours on the 13th **business day** of each **reconciliation period**.

Compare: Electricity Governance Rules 2003 rule 4.3.3 part J

### 15.12 Accuracy of submitted information

If a **reconciliation participant** submits information in accordance with this Code, and the **reconciliation participant** subsequently obtains more accurate information, the **reconciliation participant** must provide the most accurate information to the **reconciliation manager** or **participant**, as the case may be, at the next available opportunity for submission in accordance with clauses 15.20A, 15.27 and 15.28.

Compare: Electricity Governance Rules 2003 rule 4.4 part J

Clause 15.12: amended, on 15 May 2014, by clause 98 of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

### 15.13 Notice by embedded generators

An **embedded generator** must give a notice to the **reconciliation manager** for an **embedded generating station** in relation to a **point of connection** for the purposes of clauses 15.3 and 15.5(3) if the **embedded generator** will not receive payment from the **clearing manager** or any other person for any **electricity** generated by the relevant **embedded generation station** through the **point of connection** to which the notice relates.

Compare: Electricity Governance Rules 2003 rule 4A part J

Clause 15.13 Heading: amended, on 5 October 2017, by clause 518(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 15.13: amended, on 5 October 2017, by clause 518(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### 15.14 Notice of changes to the grid

- (1) Each **grid owner** must give written notice to the **reconciliation manager**, in accordance with any procedures or other requirements reasonably specified by the **reconciliation manager** from time to time, of any changes that the **grid owner** intends to make to the **grid** that will affect reconciliation.
- (2) The **grid owner** must give the notice at least 1 month before the effective date of the intended change.
- (3) No later than 1 **business day** after receipt of the notice, the **reconciliation manager** must give a copy of the notice to the **extended reserve manager**, the **clearing manager**, and the **Authority**.
- (4) Each **grid owner** must give notice of an intended change to an existing **point of connection** to the **grid** or a new **point of connection** to the **grid** to be **commissioned**.

Compare: Electricity Governance Rules 2003 rule 5 part J

Clause 15.14 Heading: amended, on 5 October 2017, by clause 519(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 15.14: amended, on 5 October 2017, by clause 519(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 15.14(3): amended, on 19 January 2017, by clause 16 of the Electricity Industry Participation Code Amendment (Extended Reserve) 2016.

*Notice of outage constraints or alternative supply*

Cross Heading: amended, on 5 October 2017, by clause 520 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

**15.15 Notice of points of connection subject to outages or alternative supply**

No later than 2 hours after **publication of final prices** for all **trading periods** in a **consumption period**,—

- (a) the **system operator** must give written notice to the **reconciliation manager** of the following:
  - (i) each **point of connection** to the **grid** that had no load or generation connected to it in the modelling system in the **consumption period**;
  - (ii) in relation to each **point of connection** referred to in subparagraph (i), the **trading periods** in the **consumption period** during which the **point of connection** to the **grid** had no load or generation connected to it in the modelling system; and
- (b) each **grid owner** must give written notice to the **reconciliation manager** of the following:
  - (i) each **point of connection** to the **grid** that was supplied from an alternative **point of connection** in the **consumption period**;
  - (ii) in relation to each **point of connection** referred to in subparagraph (i), the **trading periods** in the **consumption period** during which the **point of connection** to the **grid** was supplied from an alternative **point of connection**.

Compare: Electricity Governance Rules 2003 rule 6.1 part J

Clause 15.15 Heading: amended, on 5 October 2017, by clause 521(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 15.15: substituted, on 13 June 2013, by clause 5 of the Electricity Industry Participation (Information Flows) Code Amendment 2013.

Clause 15.15: amended, on 5 October 2017, by clause 521(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

**15.16 Balancing area NSP grouping changes**

If an **NSP** has been affected by an **outage constraint**, and the **reconciliation manager** has determined the notice it receives in accordance with clause 24 of Schedule 11.1 is not compliant with that clause, the **reconciliation manager** must, no later than 10 **business days** after the date on which it determines the notice is not compliant, effect, in consultation with the relevant **distributor**, any changes that are, in the **reconciliation manager's** opinion, necessary to **balancing area NSP** groupings that are to be used during the **outage constraint**.

Compare: Electricity Governance Rules 2003 rule 6.2 part J

Clause 15.16: amended, on 5 October 2017, by clause 522 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### 15.17 Submission information to be reviewed in the case of an outage constraint

In the case of an **outage constraint**, the **reconciliation manager** must—

- (a) review the **submission information** in accordance with a notice received in accordance with clause 15.15 and satisfy itself that the **submission information** is consistent with the occurrence of the stated **outage constraint**; and
- (b) reconcile the **submission information** for the affected **NSP** within the **balancing area** identified in accordance with clause 15.15 for the **trading periods** during which the **outage constraint** applied; and
- (c) as soon as reasonably practicable, but no later than 2 **business days** after **publication of final prices**, give written notice to any **reconciliation participants** who were affected by the **outage constraint** affecting the **NSPs**, of the **trading periods** in the prior **consumption period** during which the **outage constraint** applied, and any changes to **balancing area NSP** groupings made in accordance with clause 15.16; and
- (d) if a **reconciliation participant's submission information** has been affected by an **outage constraint** in a **consumption period**, and the **reconciliation participant** disputes or queries, in accordance with clause 15.24, the change to **balancing area NSP** groupings made in accordance with clause 15.16, the **reconciliation manager** must, no later than 10 **business days** after it determines that the notice it receives in accordance with clause 24 of Schedule 11.1 is not compliant, in consultation with the **distributor, generator or purchaser** concerned, assess whether a different **balancing area NSP** grouping would be more appropriate in the circumstances of the particular **outage constraint**. The **reconciliation manager** may change the alternative **balancing area NSP** grouping for the particular **outage constraint** and, if the alternative **balancing area NSP** grouping is changed, the **reconciliation manager** must update the information changed in accordance with clause 15.16 as necessary.

Compare: Electricity Governance Rules 2003 rule 6.3 part J

Clause 15.17(c): amended, on 13 June 2013, by clause 6 of the Electricity Industry Participation (Information Flows) Code Amendment 2013.

Clause 15.17(c) and (d): amended, on 5 October 2017, by clause 523(a) and (b) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### 15.18 Reconciliation manager may request additional information

For the purpose of carrying out its role in accordance with this Code, the **reconciliation manager** may, in respect of a **consumption period**, give notice to a **reconciliation participant** that it requires such additional information from the **reconciliation participant** as the **reconciliation manager** reasonably requires, and the **reconciliation participant** must, as soon as practicable, provide such information to the **reconciliation manager**.

Compare: Electricity Governance Rules 2003 rule 7 part J

### 15.19 Seasonal adjustment and profiling

- (1) The **reconciliation manager** must process **submission information** derived from non **half hour volume information** using a **profile** to allocate the non **half hour submission information** to **trading periods** in accordance with Schedule 15.4.

- (2) **Profiles** must be established and changed (if necessary) in accordance with Schedule 15.5.
- (3) For each reconciliation revision, the **reconciliation manager** must—
  - (a) subject to paragraph (c), recalculate the **seasonal adjustment shape** for each reconciliation revision cycle; and
  - (b) reconcile **submission information** using the latest **profile** shape published, and the most recently supplied **profile** information; and
  - (c) recalculate the residual **profile** shape and any shapes approved as **NSP** derived **profile** shapes under clauses 19 to 24 of Schedule 15.5 for each reconciliation revision cycle and use the shape to allocate non **half hour** data across the **trading periods**, in accordance with Schedule 15.5; and
  - (d) not recalculate the **seasonal adjustment shape** after the month 7 reconciliation revision.
- (4) Subclause (3)(d) does not prevent the **reconciliation manager** from recalculating the **seasonal adjustment shape** following the month 7 reconciliation revision if necessary to resolve a dispute under clauses 14.25 or 15.29, or to correct information under clauses 15.21 to 15.26.

Compare: Electricity Governance Rules 2003 rule 8 part J

Clause 15.19(4): amended, on 21 September 2012, by clause 38 of the Electricity Industry Participation (Minor Amendments) Code Amendment 2012.

Clause 15.19(4): amended, on 24 March 2015, by clause 22 of the Electricity Industry Participation (Settlement and Prudential Security) Code Amendment 2013.

### 15.20 Calculation and allocation of unaccounted for electricity

The **reconciliation manager** must, in accordance with Schedule 15.4,—

- (a) calculate the **scorecard rating** of each **retailer**; and
- (b) calculate the **unaccounted for electricity**; and
- (c) allocate the **unaccounted for electricity** to, and balance, the total **electricity supplied**, for each **NSP**.

Compare: Electricity Governance Rules 2003 rule 9 part J

*Reconciliation manager processes dispatchable load information and provides it to clearing manager*

Cross Heading: inserted, on 15 May 2014, by clause 99 of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

### 15.20A Reconciliation manager to update revised dispatchable load information

- (1) This clause applies to any revised **dispatchable load information** provided under clause 15.5D(1)(b).
- (2) The **reconciliation manager** must,—
  - (a) if the **dispatchable load information** to which this clause applies relates to 1 or more **consumption periods** being 1, 3, 7, or 14 months before the current **reconciliation period**, conduct a further update for each applicable **consumption period**; or
  - (b) if the **dispatchable load information** to which this clause applies relates to a **consumption period** other than the **consumption periods** set out in paragraph (a),—

- (i) store the **dispatchable load information** until the **consumption period** becomes 1 of the **consumption periods** set out in paragraph (a); and
  - (ii) conduct a further update under paragraph (a).
- (3) The **reconciliation manager** must not update revised **dispatchable load information** for a **consumption period** if 14 months have elapsed since the end of the **consumption period**.
- (4) Subclause (3) does not prevent the correction of information under clauses 14.28, 15.26(2), or 15.29.

Clauses 15.20A: inserted, on 15 May 2014, by clause 99 of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

Clause 15.20A(4): amended, on 24 March 2015, by clause 23 of the Electricity Industry Participation (Settlement and Prudential Security) Code Amendment 2013.

#### **15.20B Reconciliation manager loss adjusts and summarises dispatchable load information**

- (1) The **reconciliation manager** must apply **loss factors** to **dispatchable load information** received under clause 15.5D—
  - (a) for each **trading period**; and
  - (b) using the **loss category** codes advised by the **dispatchable load purchaser** when submitting **dispatchable load information** under clause 15.5D.
- (2) After applying **loss factors** under subclause (1), the **reconciliation manager** must summarise—
  - (a) into 1 file for each **consumption period, dispatchable load information** received under clause 15.5D(1)(a); and
  - (b) into 1 file for each **consumption period, dispatchable load information** received under clause 15.5D(1)(b) and updated under clause 15.20A.
- (3) The **Authority** may direct the **reconciliation manager** to apply specified values for **loss factors** for each **loss category** for a **reconciliation period** for which the **registry manager** does not provide the **reconciliation manager** with the **loss factors** for each **loss category** in accordance with clause 11.26(b).
- (4) If the **Authority** makes a direction under subclause (3), the **reconciliation manager** must apply the values as **loss factors** to the relevant **dispatchable load information** for all **reconciliation periods** during which the direction applies.

Clause 15.20B: inserted, on 15 May 2014, by clause 99 of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

Clause 15.20B(3): amended, on 5 October 2017, by clause 524 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

#### **15.20C Reconciliation manager to provide loss adjusted and summarised dispatchable load information to clearing manager**

The **reconciliation manager** must provide to the **clearing manager**—

- (a) the information described in clause 15.20B(2)(a) by 1600 hours on the 7th **business day** of each **reconciliation period**; and
- (b) the information described in clause 15.20B(2)(b) by 1200 hours on the last **business day** of each **reconciliation period**.

Clause 15.20C: inserted, on 15 May 2014, by clause 99 of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

### **15.20D Reconciliation manager to provide loss adjusted and summarised dispatchable load information to dispatchable load purchasers**

At the same time the **reconciliation manager** provides the information described in clause 15.20C to the **clearing manager**, the **reconciliation manager** must provide each **dispatchable load purchaser** with the part of the information that relates to the **dispatchable load purchaser**.

Clause 15.20D: inserted, on 15 May 2014, by clause 99 of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

*Reconciliation information produced by reconciliation manager*

### **15.21 Providing information specific to reconciliation participants**

The **reconciliation manager** must provide information specific to each **reconciliation participant** and the **clearing manager** in accordance with Schedule 15.4.

Compare: Electricity Governance Rules 2003 rule 10.1 part J

### **15.22 Providing information to reconciliation participants**

The **reconciliation manager** must provide to a **reconciliation participant** the information it has concerning the quantity of **electricity** conveyed at an **NSP** for each **consumption period**, by a time agreed between the **reconciliation participant** and the **reconciliation manager** (or if no such time can be agreed, by such time as determined by the **Authority**), if—

- (a) the **reconciliation participant** has requested the information; and
- (b) the **reconciliation participant** has purchased or sold **electricity** at the **NSP** during the **consumption period** or, in the case of a **network** owner, has a liability as a transporter of **electricity** in relation to the **NSP**; and
- (c) the **reconciliation participant** meets the **reconciliation manager's** reasonable costs of providing the information; and
- (d) the **reconciliation participant** ensures that all information received in accordance with this clause is kept and maintained confidential to the employees of the **reconciliation participant** who are required to have access to the information to enable the **reconciliation participant** to identify errors in the **reconciliation information** produced for the **NSP**; and
- (e) the **reconciliation participant** ensures that all information received in accordance with this clause is not used for any purpose other than enabling the **reconciliation participant** to identify errors in the **submission information** submitted for the **NSP** or, in the case of any **network** owner, other than for a legitimate purpose directly related to the **network** owner's liability as a transporter of **electricity** in relation to that **NSP**; and
- (f) the **reconciliation participant** implements and maintains best practice internal procedures to meet its obligations in accordance with this clause.

Compare: Electricity Governance Rules 2003 rule 10.2 part J

Clause 15.22(e): amended, on 5 October 2017, by clause 525 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.



### 15.23 Reconciliation information is not final

The **reconciliation information** provided in accordance with clauses 15.21 and 15.22 is subject to assessment in accordance with clauses 15.24 to 15.26.

Compare: Electricity Governance Rules 2003 rule 10.3 part J

### 15.24 Reconciliation information checked

- (1) The **reconciliation participant** must check the accuracy of the **reconciliation information** provided by the **reconciliation manager** under clauses 15.21 and 15.22.
- (2) The **reconciliation participant** may dispute the **volume information** on which the **reconciliation information** provided by the **reconciliation manager** under clauses 15.21 and 15.22 is based in accordance with clause 15.29.

Compare: Electricity Governance Rules 2003 rules 10.4 and 10.4A part J

### 15.25 Reconciliation manager must assess information not supplied

- (1) If a **reconciliation participant** fails to provide any information to the **reconciliation manager** that the **reconciliation participant** is required to provide under this Part, the **reconciliation manager** must take all reasonable steps necessary to acquire or estimate the information, and in the case of missing **trader** data the **reconciliation manager** must—
  - (a) estimate a **purchaser's volume information** by applying the **ICP day** scaling factor in accordance with Schedule 15.4; and
  - (b) estimate a **generator's volume information** by using an **estimated reading**.
- (2) Subclause (1) does not apply to information that the **reconciliation manager** is directed by the **Authority** to correct under clause 15.26(2).

Compare: Electricity Governance Rules 2003 rules 10.5 and 10.5A part J

### 15.26 Reconciliation manager to correct information

- (1) If the **reconciliation manager** has, in accordance with clause 15.25(1), acquired or estimated information, or is unable to provide **reconciliation information**, it must, to the extent it is reasonable, attempt to subsequently establish the correct **reconciliation information**, provide the updated **reconciliation information** to the **clearing manager** and distribute the information to the **reconciliation participants** entitled to it in accordance with this Code.
- (2) If the **reconciliation manager** considers that information provided by a **reconciliation participant** or a **service provider** under this Part is incorrect, the **reconciliation manager** must refer the issue to the **Authority**, and, if directed by the **Authority** to do so, take all reasonable steps to correct the information.
- (3) A **reconciliation participant** or **service provider** must provide any information to the **reconciliation manager** that the **reconciliation manager** requires to correct information under subclause (2).
- (4) If the **reconciliation manager** has corrected information under subclause (2), the **reconciliation manager** must provide the corrected information to the **clearing manager** and the **reconciliation participants** who are entitled to the information under this Code.
- (5) The **reconciliation manager** must not correct information later than 24 months after the

date on which information about an amount owing to which the incorrect information relates (if any) has been advised under Part 14.

Compare: Electricity Governance Rules 2003 rules 10.6 to 10.10 part J

Clause 15.26(5): amended, on 24 March 2015, by clause 24 of the Electricity Industry Participation (Settlement and Prudential Security) Code Amendment 2013.

### *Revisions*

#### **15.27 Reconciliation manager must reconcile revised information**

- (1) If the **reconciliation manager** receives revised **NSP** information or **submission information** that has been supplied to it since the previous reconciliation calculation in accordance with clauses 15.4(2) or 15.12, the **reconciliation manager** must reconcile the information in accordance with the following procedure:
  - (a) if the **submission information** received relates to 1 or more **consumption periods** being 1, 3, 7, or 14 months before the current **reconciliation period**, a further reconciliation must be conducted for that **consumption period** or those **consumption periods**:
  - (b) if the **NSP** information or **submission information** relates to any other **consumption period**, the **reconciliation manager** must store the information and wait until the **consumption period** becomes 1 of the **consumption periods** described in paragraph (a) before conducting a further reconciliation.
- (2) The **reconciliation manager** must not reconcile revised **NSP** or **submission information** arising after month 14.
- (3) Subclause (2) does not prevent the correction of information under clauses 14.28, 15.26(2) or 15.29.

Compare: Electricity Governance Rules 2003 rules 11.1 to 11.2A part J

Clause 15.27(3): amended, on 24 March 2015, by clause 25 of the Electricity Industry Participation (Settlement and Prudential Security) Code Amendment 2013.

#### **15.28 Transitional provisions concerning revisions**

- (1) In this clause—
  - (a) “transitional revisions” means any revision carried out by the **reconciliation manager** in accordance with this clause, for **any reconciliation period** that includes a **trading period** that occurred before 1 May 2008; and
  - (b) “incumbent **retailer**” means, for each **balancing area**, the relevant **retailer** to be set out in the list of **NSPs** by **balancing area** and their corresponding **retailers**, **published** from time to time by the **reconciliation manager**, in accordance with subclause (3).
- (2) The intent of this clause is—
  - (a) as far as practicable, to preserve the effect of the reconciliation provisions concerning revisions that were in effect immediately before 1 May 2008, for all transitional revisions; and
  - (b) to clarify that **volume information** and **submission information** for all transitional revisions (except as provided in this clause) must be submitted by **reconciliation participants** in accordance with this Part; and

- (c) to clarify the application of certain clauses concerning disputes that existed before 1 May 2008.
- (3) The **reconciliation manager** must **publish** a list of the incumbent **retailers** finalised under rule 11.4.3.2 of part J of the **rules** until all transitional revisions are completed.
- (4) Despite anything in this Code—
  - (a) to avoid doubt, clause 8 of Schedule 15.3 applies to **submission information** in relation to all transitional revisions; and
  - (b) each **reconciliation participant**, including each incumbent **retailer**, must submit the required **submission information** relating to all transitional revisions in accordance with clause 15.4(2); and
  - (c) if the **submission information** to be **supplied** for a transitional revision is the first such submission after 1 May 2008, the **reconciliation participant** must provide a full data set as if it were an initial submission in accordance with clause 15.4(1); and
  - (d) in recognition of the fact that incumbent **retailers** have not, before 1 May 2008, been required to submit the **submission information** referred to in paragraph (b), the **certification** and **audit** requirements of Schedule 15.1 (required for activities in accordance with clauses 2 to 8 and 11 of Schedule 15.3, and clause 17 of Schedule 15.4), do not apply in relation to the non **half-hour metering information** required to be submitted by incumbent **retailers** to the **reconciliation manager** for transitional revisions.
- (5) Despite anything in this Code, all transitional revisions must be carried out by the **reconciliation manager** in accordance with this Code, subject to the following:
  - (a) for the purposes of clause 7 of Schedule 15.4, the **ICP** scaling factor is 1; and
  - (b) for the purposes of clauses 18(1)(b) and 19 of Schedule 15.4 the **scorecard rating** ( $SC_{ri}$ ) for each **retailer** (other than the incumbent **retailer**) is 1; and
  - (c) for the purposes of clause 19 of Schedule 15.4, at each **NSP** the market share proportion ( $MS_{Ri}$ ) for the incumbent **retailer** is 1, and, for all other **retailers**, is 0.
- (6) Despite anything in this Code, all disputes concerning **metering installations** or **consumption information** in relation to transitional revisions—
  - (a) that existed before 1 May 2008 are not affected by the coming into effect of part J of the **rules** and this Part; and
  - (b) must be commenced no later than 2 years after the date of issue of any invoice to which the disputed information relates.
- (7) Despite anything in this Code—
  - (a) as soon as practicable after 16 October 2008, the **reconciliation manager** must publish 1 **seasonal adjustment shape** for each **balancing area** that existed at the beginning of the 1<sup>st</sup> **trading period** of May 2008; and
  - (b) the **reconciliation manager** must not publish any further **seasonal adjustment shapes** for the **consumption periods** for which transitional revisions are required; and

- (c) no later than 5 **business days** after the date on which those **seasonal adjustment shapes** are published, each **reconciliation participant** must provide **submission information** to the **reconciliation manager** based on those **seasonal adjustment shapes** for the months of February to July 2008; and
- (d) as soon as practicable after the expiry of the time referred to in paragraph (c) the **reconciliation manager** must complete revisions using that **submission information** for the months of February 2008 to July 2008; and
- (e) each **reconciliation participant** must continue to use the **seasonal adjustment shapes** published by the **reconciliation manager** under paragraph (a) for all subsequent transitional revisions for the period for which transitional revisions are required.

Compare: Electricity Governance Rules 2003 rule 11.4 part J

### 15.29 Volume information disputes

- (1) A **reconciliation participant** may commence a dispute relating to **volume information** by notice in writing to the **reconciliation manager**.
- (2) A **reconciliation participant** may not give written notice of a dispute under subclause (1) if information about an amount owing based on the **volume information** has been advised under Part 14.
- (3) The **reconciliation manager** must give written notice to the **Authority** and all **participants** affected by the dispute no later than 1 **business day** after receiving notice of the dispute under subclause (1).
- (4) On receiving a notice of a dispute under subclause (3), the **Authority** may direct that no further action be taken in respect of the dispute.
- (5) If the **Authority** gives a direction under subclause (4), subclauses (6) to (13) cease to apply to the dispute. However, a direction under subclause (4) does not affect the validity of a **washup** conducted under clauses subpart 6 of Part 14 before the direction was given.
- (6) The disputing **reconciliation participant** and the **reconciliation manager** must use reasonable endeavours to resolve the dispute.
- (7) A dispute does not excuse anyone from complying with this Code.
- (8) **Participants** must continue to use disputed **volume information** as if it were not in dispute while the dispute is being resolved.
- (9) If a dispute is not resolved within 15 **business days** after the date on which the **reconciliation manager** received notice of the dispute under subclause (1), the disputing **reconciliation participant** or the **reconciliation manager** may refer the dispute to the **Rulings Panel** for resolution under the **Act**.
- (10) The **Rulings Panel** may make such determination as it thinks fit.
- (11) The **Rulings Panel** must give written notice of its determination to the disputing **reconciliation participant** and affected **participants**.
- (12) If the dispute is resolved by the parties to the dispute agreeing, or the **Rulings Panel** determining, that the **volume information** is incorrect, the **reconciliation manager** must correct the **volume information** as follows:

- (a) if a revised **seasonal adjustment shape** must be issued in order for the **volume information** to be corrected—
    - (i) the **reconciliation manager** must provide each **reconciliation participant** whose **submission information** is required to be corrected with a revised **seasonal adjustment shape**; and
    - (ii) each **reconciliation participant** must provide corrected **submission information** to the **reconciliation manager** no later than 4 **business days** after being provided with the revised **seasonal adjustment shape**;
  - (b) if a revised **seasonal adjustment shape** does not need to be issued in order for the **volume information** to be corrected, each **reconciliation participant** whose **volume information** or **dispatchable load information** is required to be corrected must provide corrected relevant information to the **reconciliation manager** no later than 4 **business days** after receiving notice of the resolution of the dispute.
- (13) The **reconciliation manager** must provide the corrected **volume information** to the **clearing manager**.
- (14) *[Revoked]*
- Compare: Electricity Governance Rules 2003 rule 12 part J  
Clause 15.29(2): amended, on 24 March 2015, by clause 26(a) of the Electricity Industry Participation (Settlement and Prudential Security) Code Amendment 2013.  
Clause 15.29(2): amended, on 5 October 2017, by clause 526(a) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.  
Clause 15.29(3): replaced, on 5 October 2017, by clause 526(b) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.  
Clause 15.29(4): amended, on 5 October 2017, by clause 526(c) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.  
Clause 15.29(5): amended, on 24 March 2015, by clause 26(b) of the Electricity Industry Participation (Settlement and Prudential Security) Code Amendment 2013.  
Clause 15.29(5): amended, on 24 March 2015, by clause 13(1) of the Electricity Industry Participation Code Amendment (Late and Revised Data) 2015.  
Clause 15.29(9): amended, on 5 October 2017, by clause 526(d) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.  
Clause 15.29(11): amended, on 5 October 2017, by clause 526(e) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.  
Clause 15.29(12): amended, on 5 October 2017, by clause 526(f) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.  
Clause 15.29(12)(b): amended, on 15 May 2014, by clause 59 of the Electricity Industry Participation (Minor Code Amendments) Code Amendment 2014.  
Clause 15.29(12)(b): amended, on 19 September 2014, by clause 5 of the Electricity Industry Participation Code Amendment (Minor Code Amendments) (No 2) 2014.  
Clause 15.29(14): amended, on 24 March 2015, by clause 26(c) of the Electricity Industry Participation (Settlement and Prudential Security) Code Amendment 2013.  
Clause 15.29(14): revoked, on 24 March 2015, by clause 13(2) of the Electricity Industry Participation Code Amendment (Late and Revised Data) 2015.

*Reporting obligations of the reconciliation manager*

**15.30 Alleged Code breaches reported by the reconciliation manager**

- (1) As soon as possible and by no later than 1300 hours on the 2<sup>nd</sup> **business day** after the **reconciliation manager** provided **reconciliation information** for a **consumption period** in accordance with clauses 15.21 and 15.22, the **reconciliation manager** must provide a written report to the **Authority** detailing the number and details of any alleged breach of this Code that the **reconciliation manager** is aware of.

- (2) The report must include the matters set out below, and information about any situations when the **reconciliation manager** allegedly breached this Code, or, in the opinion of the **reconciliation manager**, a **reconciliation participant** allegedly breached this Code:
- (a) the time and, if appropriate, the **consumption period**, during which the alleged breach took place:
  - (b) the nature of the alleged breach, including, in the case of late **submission information** or information in a form that compromises the **reconciliation information**, the **reconciliation participant** allegedly responsible for the information:
  - (c) the reason for the alleged breach including, in the case of late **submission information** or information in a form that compromises the **reconciliation information**, the reason for the delay or the inadequate form, if the **reconciliation manager** is aware of the reason.

Compare: Electricity Governance Rules 2003 rule 13.1 part J

### 15.31 Right to information concerning reconciliation manager's actions

- (1) A **reconciliation participant** may, by notice in writing to the **reconciliation manager**, request further information related to any situation set out in the **reconciliation manager's** report provided in accordance with clause 15.30 that has materially affected the **reconciliation participant**.
- (2) The **reconciliation manager** must, no later than 10 **business days** after receiving such a request, provide the requested information to the **reconciliation participant**, provided that the information does not include any information that is confidential in respect of any other person.

Compare: Electricity Governance Rules 2003 rule 13.2 part J

### 15.32 Reconciliation reports

The **reconciliation manager** must report to the **Authority** and each **reconciliation participant**, the information determined during the reconciliation process as described in clauses 24 to 28 of Schedule 15.4.

Compare: Electricity Governance Rules 2003 rule 13.3 part J

### 15.33 The Authority publishes reports

By 1630 hours on the 2<sup>nd</sup> **business day** following the day on which the **Authority** receives the report of the **reconciliation manager** in accordance with clause 15.30, the **Authority** must **publish** the sections of the report that relate to an alleged breach of this Code by the **reconciliation manager** (if any).

Compare: Electricity Governance Rules 2003 rule 14 part J

Clause 15.33: amended, on 15 May 2014, by clause 60 of the Electricity Industry Participation (Minor Code Amendments) Code Amendment 2014.

Clause 15.33: amended, on 1 February 2016, by clause 96 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

### 15.34 Use of agents by reconciliation participants

- (1) A **reconciliation participant** who has obligations under this Part may discharge those obligations by way of an agent.
- (2) A **reconciliation participant** who utilises an agent to discharge an obligation under this Code remains responsible and liable for, and is not in any way released from, that obligation.
- (3) A **reconciliation participant** must not assert, against anyone, that it is not responsible or liable for its obligations because the **reconciliation participant's** agent has done or not done something or has failed to meet a relevant standard.

Compare: Electricity Governance Rules 2003 rule 15 part J

### 15.35 Provision of information

- (1) If an obligation exists to provide information in accordance with this Part, a **participant** must deliver that information to the required person within the timeframe specified in this Code, or, in the absence of any such timeframe, within any timeframe the **Authority** specifies in writing.
- (2) Such information must be delivered in the format determined from time to time by the **Authority**.
- (3) Unless otherwise specified in this Part, information that must be provided under this Part by the **registry manager** or to the **registry manager**, must be provided using the **registry**.

Compare: Electricity Governance Rules 2003 rule 16 part J

Clause 15.35(1): amended, on 5 October 2017, by clause 527(a) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 15.35(3): inserted, on 5 October 2017, by clause 527(b) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### 15.36 New Zealand Daylight Time adjustment techniques

- (1) **Submission information** provided to, and **reconciliation information** provided by, the **reconciliation manager** must, if applicable, be adjusted for **NZDT** using the technique set out in subclause (3) specified by the **Authority**.
- (2) Any information exchanged between **participants** that contains **trading period** specific data must, if applicable, be adjusted for **NZDT** in accordance with subclause (3).
- (3) A daylight savings adjustment must be made by using the “**trading period** run on technique”, which requires that daylight saving adjustment periods are allocated as consecutive **trading periods** within the relevant day, in the sequence that they occur.
- (4) If no adjustment is made in accordance with subclause (3) to information exchanged between **reconciliation participants** that contains **trading period** specific data, the code “**NZST**” must be used within the data transfer file.

Compare: Electricity Governance Rules 2003 rule 17 part J

Clause 15.36(3): substituted, on 1 February 2016, by clause 97 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

### 15.37 *[Revoked]*

Compare: Electricity Governance Rules 2003 rule 18 part J

Clause 15.37(1): substituted, on 1 February 2016, by clause 98(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

Clause 15.37(2): revoked, on 1 February 2016, by clause 98(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

Clause 15.37: revoked, on 1 June 2017, by clause 24 of the Electricity Industry Participation Code Amendment (Requirements and Processes for Audits) 2016.

### **15.37A Reconciliation participants and dispatchable load purchasers to arrange for regular audits**

Each **reconciliation participant** and each **dispatchable load purchaser** must arrange to be **audited** regularly in accordance with Part 16A in respect of the **reconciliation participant's** or **dispatchable load purchaser's** obligations under this Part.

Clause 15.37A: inserted, on 1 June 2017, by clause 25 of the Electricity Industry Participation Code Amendment (Requirements and Processes for Audits) 2016.

### **15.37B Retailers to arrange for audits in respect of distributed unmetered load**

Each **retailer** that is responsible for **distributed unmetered load** must arrange for an **audit** to be carried out in accordance with Part 16A in respect of the **distributed unmetered load** that verifies that—

- (a) the **retailer's distributed unmetered load** database complies with clause 11 of Schedule 15.3; and
- (b) the information recorded in the **retailer's distributed unmetered load** database is complete and accurate; and
- (c) **volume information** for the **distributed unmetered load** is being calculated accurately and **profiles** have been correctly applied.

Clause 15.37B: inserted, on 1 June 2017, by clause 25 of the Electricity Industry Participation Code Amendment (Requirements and Processes for Audits) 2016.

### **15.37C Authority and participant requested audits**

- (1) The **Authority** may at any time carry out, or appoint an **auditor** to carry out, an **audit** of a **participant** in respect of the **participant's** obligations under this Part.
- (2) If a **participant** considers that another **participant** may not have complied with this Part, the **participant** may request that the **Authority** carry out, or appoint an **auditor** to carry out, an **audit** of the other **participant**.
- (3) Part 16A applies to an **audit** carried out under this clause.

Clause 15.37C: inserted, on 1 June 2017, by clause 25 of the Electricity Industry Participation Code Amendment (Requirements and Processes for Audits) 2016.

### *Certification*

Cross heading Certification: inserted, on 15 May 2014, by clause 61 of the Electricity Industry Participation (Minor Code Amendments) Code Amendment 2014.

### **15.38 Functions requiring certification**

- (1) Subject to clauses 2A and 2B of Schedule 15.1, a **reconciliation participant** (except an **embedded generator** selling **electricity** directly to another **reconciliation participant**) must obtain and maintain **certification** in accordance with Schedule 15.1 in order to be permitted to perform, or to have performed by way of an agent or agents, any of the following functions in compliance with this Code:
  - (a) maintaining **registry** information and performing **customer** and **generator** switching (except if the maintenance of **registry** information is carried out by a **distributor** in accordance with Part 11);
  - (b) gathering and storing **raw meter data**;
  - (c) creating and managing (including validating, estimating, storing, correcting and archiving)—



- (i) **half hour volume information**; or
    - (ii) non **half hour volume information**; or
    - (iii) **half hour** and non **half hour volume information**; or
    - (iv) **dispatchable load information**:
  - (d) delivery of:
    - (i) a report under clause 15.6 and the calculation of the number of **ICP days** detailed in the report;
    - (ii) **electricity supplied** information under clause 15.7;
    - (iii) information from **retailer** and **direct purchaser half hourly** metered **ICPs** under clause 15.8;
  - (da) *[Revoked]*
  - (db) *[Revoked]*
  - (e) provision of **submission information** for reconciliation;
  - (f) provision of **metering information** to the **grid owner** in accordance with subpart 4 of Part 13.
- (1A) A **dispatchable load purchaser** must obtain and maintain **certification** in accordance with Schedule 15.1 in order to be permitted to perform, or to have performed by way of an agent or agents, any of the following functions in compliance with this Code:
- (a) gathering and storing **raw meter data**;
  - (b) creating and managing (including validating, estimating, storing, correcting, and archiving)—
    - (i) **half hour volume information**; or
    - (ii) non **half hour volume information**; or
    - (iii) **half hour** and non **half hour volume information**; or
    - (iv) **dispatchable load information**:
  - (c) providing **dispatchable load information**.
- (1B) For the purposes of subclause (1A), each reference to a **reconciliation participant** in Schedule 15.1 is to be read as a reference to a **dispatchable load purchaser**.
- (2) *[Revoked]*

Compare: Electricity Governance Rules 2003 rule 19 part J

Clause 15.38(1): amended, on 1 June 2017, by clause 26(1) of the Electricity Industry Participation Code Amendment (Requirements and Processes for Audits) 2016.

Clause 15.38(1)(a): amended, on 1 February 2016, by clause 99(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

Clause 15.38(1)(c)(iv): inserted, on 15 May 2014, by clause 101(1) of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

Clause 15.38(1)(d): substituted, on 19 December 2014, by clause 41 of the Electricity Industry Participation Code Amendment (Minor Code Amendments) (No 3) 2014.

Clause 15.38(1)(d): substituted, on 1 February 2016, by clause 99(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

Clause 15.38(1)(da) and (db): inserted, on 19 December 2014, by clause 41 of the Electricity Industry Participation Code Amendment (Minor Code Amendments) (No 3) 2014.

Clause 15.38(1)(da) and (db): revoked, on 1 February 2016, by clause 99(3) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

Clause 15.38(1)(f): amended, on 1 February 2016, by clause 99(4) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

Clause 15.38(1A): inserted, on 15 May 2014, by clause 101(2) of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

Clause 15.38(1B): inserted, on 15 May 2014, by clause 62 of the Electricity Industry Participation (Minor Code Amendments) Code Amendment 2014.

Clause 15.38(2): substituted, on 1 February 2016, by clause 99(5) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

Clause 15.38(2): revoked, on 1 June 2017, by clause 26(2) of the Electricity Industry Participation Code Amendment

(Requirements and Processes for Audits) 2016.

*Participant identifiers*

Cross heading Participant identifiers: inserted, on 15 May 2014, by clause 63 of the Electricity Industry Participation (Minor Code Amendments) Code Amendment 2014.

**15.39 Participants must use participant identifiers**

- (1) Each **participant** must use its **participant identifier**, when required, to correctly identify that **participant's** information.
- (2) A **participant** must apply to the **Authority** in the **prescribed form** for a **participant identifier** at least **5 business days** before the **participant identifier** is required.
- (3) The **Authority** may, by giving written notice to any **participant**, change the **participant identifier** for that **participant**. If the **Authority** does this, the new **participant identifier** for that **participant** will become effective from the date specified in the relevant notice.

Compare: Electricity Governance Rules 2003 rule 20 part J

Clause 15.39(3): amended, on 5 October 2017, by clause 528 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

## Schedule 15.1

### Certification processes

cl 15.38

Heading Schedule 15.1: amended, on 1 June 2017, by clause 27 of the Electricity Industry Participation Code Amendment (Requirements and Processes for Audits) 2016.

#### 1 Contents of this Schedule

This Schedule sets out—

- (a) *[Revoked]*
- (b) the requirement for **reconciliation participants** to be **certified** to perform the functions specified in clause 15.38, and the process for obtaining and renewing that **certification**.
- (c) *[Revoked]*

Compare: Electricity Governance Rules 2003 clause 1 schedule J1

Clause 1(a): revoked, on 1 June 2017, by clause 28(1) of the Electricity Industry Participation Code Amendment (Requirements and Processes for Audits) 2016.

Clause 1(b): amended, on 1 June 2017, by clause 28(2) of the Electricity Industry Participation Code Amendment (Requirements and Processes for Audits) 2016.

Clause 1(c): revoked, on 1 June 2017, by clause 28(1) of the Electricity Industry Participation Code Amendment (Requirements and Processes for Audits) 2016.

#### 2 *[Revoked]*

Compare: Electricity Governance Rules 2003 clause 1A schedule J1

Clause 2: revoked, on 1 February 2016, by clause 100 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

#### 2A Requirement for certification

- (1) Despite clause 15.38(1), a **reconciliation participant** that is required to obtain **certification** under clause 15.38 must obtain **certification** no later than,—
  - (a) in the case of a **reconciliation participant** that is recorded in the **registry** as being responsible for fewer than 100 **ICPs** of the kind described in subclause (2), 12 months after the **reconciliation participant** first performs a function specified in clause 15.38(1); or
  - (b) in every other case, the later of—
    - (i) 6 months after the date on which the **reconciliation participant** first performs a function specified in clause 15.38(1); or
    - (ii) the date on which the **reconciliation participant** is recorded in the **registry** as being responsible for 100 or more **ICPs** of the kind described in subclause (2).
- (2) The kind of **ICP** referred to in subclause (1) is an **ICP** at which there is—
  - (a) 1 or more **category 1 metering installations** and no other kind of **metering installation**; and
  - (b) no **unmetered load**.

Clause 2A: inserted, on 1 June 2017, by clause 29 of the Electricity Industry Participation Code Amendment (Requirements and Processes for Audits) 2016.

**2B Reconciliation participants to obtain Authority approval before performing certain functions**

- (1) A **reconciliation participant** that proposes to perform a function listed in clause 15.38(1) without obtaining **certification** (in reliance on clause 2A) must obtain the **Authority's** prior approval.
- (2) The **Authority** must give its approval if it is satisfied, on the basis of information provided to it by the **reconciliation participant**, that the **reconciliation participant** complies with such of the requirements specified in subclause (3) as are relevant to the **reconciliation participant**.
- (3) The requirements are that the **reconciliation participant** must—
  - (a) be capable of producing **submission information** accurately;
  - (b) be capable of performing the functions described in clause 15.38(1)(d);
  - (c) be capable of switching an **ICP** in accordance with Schedule 11.3;
  - (d) be capable of managing an **ICP** in accordance with Schedule 11.1;
  - (e) understand its obligations under this Code.

Clause 2B: inserted, on 1 June 2017, by clause 29 of the Electricity Industry Participation Code Amendment (Requirements and Processes for Audits) 2016.

**3 Performance of reconciliation participant's obligations by agent**

A **reconciliation participant** may perform any obligation under this Schedule by an agent, and for that purpose, every act or omission of a **reconciliation participant's** agent is deemed to be an act or omission of the **reconciliation participant**.

Compare: Electricity Governance Rules 2003 clause 1B schedule J1

**4 Obtaining certification**

- (1) A **reconciliation participant** requiring **certification** to perform the functions specified in clause 15.38 must apply in writing to the **Authority** in the **prescribed form**, at least 2 months before the intended date of **certification**.
- (2) The **reconciliation participant** must promptly provide such other information as the **Authority** may reasonably request.
- (3) The **reconciliation participant** must indicate to the **Authority** the information gathering, processing and management functions it intends to perform and who it intends to use to perform those functions.

Compare: Electricity Governance Rules 2003 clauses 3.1 to 3.1B schedule J1

**5 Granting certification**

- (1) The **Authority** must grant **certification** to a **reconciliation participant** only if—
  - (a) the **Authority** is satisfied, on the basis of an **audit** report provided to the **Authority** under Part 16A, that the **reconciliation participant** meets the requirements relevant to the functions specified in clause 15.38 for which the **reconciliation participant** is seeking **certification**.
  - (b) *[Revoked]*
- (2) A **reconciliation participant** is responsible for appointing an **auditor** to undertake the **audit** required by subclause (1).
- (3) *[Revoked]*

Compare: Electricity Governance Rules 2003 clause 3.2 schedule J1

Clause 5(1)(a): amended, on 1 June 2017, by clause 30(1)(a) and (b) of the Electricity Industry Participation Code Amendment (Requirements and Processes for Audits) 2016.

Clause 5(1)(b): revoked, on 1 June 2017, by clause 30(2) of the Electricity Industry Participation Code Amendment (Requirements and Processes for Audits) 2016.

Clause 5(3): revoked, on 1 June 2017, by clause 30(3) of the Electricity Industry Participation Code Amendment (Requirements and Processes for Audits) 2016.

## 6 Lists of certified reconciliation participants

The **Authority** must **publish**, and keep updated—

- (a) a list of **certified reconciliation participants** that includes, for each **reconciliation participant**, the date on which the **certification** expires.

(b) *[Revoked]*

Compare: Electricity Governance Rules 2003 clause 3A schedule J1

Clause 6 Heading: amended, on 1 February 2016, by clause 101(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

Clause 6: amended, on 1 June 2017, by clause 31 of the Electricity Industry Participation Code Amendment (Requirements and Processes for Audits) 2016.

Clause 6: amended, on 5 October 2017, by clause 529 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 6(a): amended, on 1 February 2016, by clause 101(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

Clause 6(b): revoked, on 1 February 2016, by clause 101(3) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

## 7 Renewal of certification

- (1) **Certification** must not be granted for a term of more than 24 months.
- (2) The **Authority** must renew a **reconciliation participant's certification** for a further term of not more than 24 months if the **Authority** is satisfied on the basis of an **audit** report provided to the **Authority** under Part 16A that the **reconciliation participant** continues to meet the requirements specified in clause 5.

Compare: Electricity Governance Rules 2003 clause 3B schedule J1

Clause 7: amended, on 1 June 2017, by clause 32(1) of the Electricity Industry Participation Code Amendment (Requirements and Processes for Audits) 2016.

Clause 7(2): amended, on 1 June 2017, by clause 32(2) of the Electricity Industry Participation Code Amendment (Requirements and Processes for Audits) 2016.

## 8 Changes that affect certification

(1) *[Revoked]*

- (1A) If there is a material change to a **reconciliation participant's** systems or processes such that an **audit** is required under clause 16A.11, the **Authority** must, on receiving the **audit** report required by that clause, decide whether to continue the **reconciliation participant's certification**.
- (2) The **Authority** must, by notice to the **reconciliation participant**, continue the **reconciliation participant's certification** if the **Authority** is satisfied that the **reconciliation participant** will continue to meet the requirements in clause 5 after the change has come into effect.
- (3) A **reconciliation participant's certification** is revoked if—
  - (a) a **reconciliation participant** fails to provide an **audit** report to the **Authority** in accordance with clause 16A.11; or

- (b) the **Authority** gives written notice to the **reconciliation participant** that the **Authority** is not satisfied that the **reconciliation participant** will continue to meet the requirements in clause 5 after the change has come into effect.

Compare: Electricity Governance Rules 2003 clause 3C schedule J1

Clause 8(1): revoked, on 1 June 2017, by clause 33(1) of the Electricity Industry Participation Code Amendment (Requirements and Processes for Audits) 2016.

Clause 8(1A): inserted, on 1 June 2017, by clause 33(2) of the Electricity Industry Participation Code Amendment (Requirements and Processes for Audits) 2016.

Clause 8(2): amended, on 1 June 2017, by clause 33(3) of the Electricity Industry Participation Code Amendment (Requirements and Processes for Audits) 2016.

Clause 8(3): amended, on 1 June 2017, by clause 33(4)(a) of the Electricity Industry Participation Code Amendment (Requirements and Processes for Audits) 2016.

Clause 8(3)(a): amended, on 1 June 2017, by clause 33(4)(b) of the Electricity Industry Participation Code Amendment (Requirements and Processes for Audits) 2016.

Clause 8(3)(b): amended, on 5 October 2017, by clause 530 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

**8A** *[Revoked]*

Clause 8A: inserted, on 24 May 2013, by clause 5 of the Electricity Industry Participation (Transitional Provisions for New Metering Arrangements) Code Amendment 2013.

Clause 8A(3): amended, on 15 May 2014, by clause 64 of the Electricity Industry Participation (Minor Code Amendments) Code Amendment 2014.

Clause 8A: revoked, on 1 June 2017, by clause 34 of the Electricity Industry Participation Code Amendment (Requirements and Processes for Audits) 2016.

**9** *[Revoked].*

Compare: Electricity Governance Rules 2003 clause 5 Schedule J1

Clause 9(5): amended, on 29 August 2013, by clause 23 of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011.

Clause 9(7): amended, on 21 September 2012, by clause 39 of the Electricity Industry Participation (Minor Amendments) Code Amendment 2012.

Clause 9: revoked, on 1 June 2017, by clause 34 of the Electricity Industry Participation Code Amendment (Requirements and Processes for Audits) 2016.

**10** *[Revoked]*

Compare: Electricity Governance Rules 2003 clause 6 schedule J1

Clause 10: revoked, on 1 June 2017, by clause 34 of the Electricity Industry Participation Code Amendment (Requirements and Processes for Audits) 2016.

**11** *[Revoked]*

Compare: Electricity Governance Rules 2003 clause 6A schedule J1

Clause 11: revoked, on 1 June 2017, by clause 34 of the Electricity Industry Participation Code Amendment (Requirements and Processes for Audits) 2016.

**12** *[Revoked]*

Compare: Electricity Governance Rules 2003 clauses 8.1 and 8.1A schedule J1

Clause 12: revoked, on 1 June 2017, by clause 34 of the Electricity Industry Participation Code Amendment (Requirements and Processes for Audits) 2016.

**13** *[Revoked]*

Compare: Electricity Governance Rules 2003 clause 8.2 schedule J1

Clause 13: revoked, on 1 June 2017, by clause 34 of the Electricity Industry Participation Code Amendment (Requirements and Processes for Audits) 2016.

**14** *[Revoked]*

Compare: Electricity Governance Rules 2003 clause 8.2A schedule J1

Clause 14: revoked, on 1 June 2017, by clause 34 of the Electricity Industry Participation Code Amendment (Requirements and Processes for Audits) 2016.

- 15**    *[Revoked]*  
Compare: Electricity Governance Rules 2003 clause 8.3 schedule J1  
Clause 15: revoked, on 1 June 2017, by clause 34 of the Electricity Industry Participation Code Amendment (Requirements and Processes for Audits) 2016.
- 16**    *[Revoked]*  
Compare: Electricity Governance Rules 2003 clause 8.4 schedule J1  
Clause 16: revoked, on 1 June 2017, by clause 34 of the Electricity Industry Participation Code Amendment (Requirements and Processes for Audits) 2016.
- 17**    *[Revoked]*  
Compare: Electricity Governance Rules 2003 clause 8.5 schedule J1  
Clause 17: revoked, on 1 June 2017, by clause 34 of the Electricity Industry Participation Code Amendment (Requirements and Processes for Audits) 2016.
- 18**    *[Revoked]*  
Compare: Electricity Governance Rules 2003 clause 8.6 schedule J1  
Clause 18: revoked, on 1 June 2017, by clause 34 of the Electricity Industry Participation Code Amendment (Requirements and Processes for Audits) 2016.
- 19**    *[Revoked]*  
Compare: Electricity Governance Rules 2003 clause 8.7 schedule J1  
Clause 19: revoked, on 1 June 2017, by clause 34 of the Electricity Industry Participation Code Amendment (Requirements and Processes for Audits) 2016.

## Schedule 15.2

### Collection of volume information

cl 15.5

#### 1 Contents of this Schedule

This Schedule establishes the required processes, in so far as they relate to the reconciliation process, for—

- (a) collecting **raw meter data**, **interrogating meters**, and deriving **validated meter readings**; and
- (b) creating **estimated readings** and **permanent estimates**; and
- (c) deriving **volume information** from **validated meter readings**, **estimated readings**, and **permanent estimates**; and
- (d) supporting data processing activities.

Compare: Electricity Governance Rules 2003 clause 1 schedule J2

#### 2 Collection of raw meter data by certified reconciliation participant

- (1) This clause applies to each **metering installation** for which a **metering equipment provider** is responsible, except for a **metering installation**—
  - (a) that only the **metering equipment provider** can electronically **interrogate**; or
  - (b) for which the **metering equipment provider** has an arrangement with the **reconciliation participant**, which prevents the **reconciliation participant** from electronically **interrogating** the **metering installation**.
- (2) A **reconciliation participant** must obtain **raw meter data** used to determine **volume information**—
  - (a) from the **services access interface** of the **metering installation**; or
  - (b) if the **raw meter data** can only be obtained from the **metering equipment provider's back office**, from the **metering equipment provider**.
- (3) A **reconciliation participant** must ensure that the **interrogation** cycle for each **metering installation** that it **interrogates** does not exceed the maximum **interrogation** cycle in the **registry**.
- (4) A **reconciliation participant** must **interrogate** a **metering installation** at least once in each maximum **interrogation** cycle for the **metering installation**.
- (5) A **reconciliation participant** must, when electronically **interrogating** a **metering installation**,—
  - (a) ensure that the **interrogation** and processing system electronically monitors and corrects its internal clocks against a time source with a verifiable standard at a frequency sufficient, but no longer than 1 week, to ensure the internal clock is accurate, when carrying out an **interrogation**, to within  $\pm 5$  seconds of—
    - (i) **New Zealand standard time**; or
    - (ii) **New Zealand daylight time**; and
  - (b) compare the time on the internal clock of the **data storage device** with the time on the **interrogation** and processing system clock; and
  - (c) calculate the time error for the **data storage device**; and



- (d) if the time error calculated under paragraph (c) is equal to or less than the applicable time error set out in Table 1, correct the clock of the **data storage device**; and
- (e) if the time error calculated under paragraph (c) is greater than the applicable time error set out in Table 1,—
  - (i) correct the clock of the **data storage device**; and
  - (ii) compare the time of the clock with the time of the **interrogation** and processing system clock; and
  - (iii) correct any affected **raw meter data**; and
- (f) download the **event log**.
- (6) The **reconciliation participant** must record in the **interrogation** and processing system logs, the time, the date, and the extent of any change in the internal clock setting in the **metering installation**.

**Table 1: Maximum permitted time errors**

Metering installation category	Half-hour metering installations (seconds)	Non half-hour metering installations (seconds)
1	±30	±60
2	±10	±60
3	±10	NA
4	±10	NA
5	±5	NA

Compare: Electricity Governance Rules 2003 clause 2 schedule J2  
 Clause 2: substituted, on 29 August 2013, by clause 24 of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011.

### 3 Source of volume information

- (1) A **meter reading** must, in accordance with the relevant **reconciliation participant's certified** processes and procedures, and using its **certified** facilities, be sourced directly from **raw meter data**, and if appropriate, be derived and calculated from financial records.
- (2) A **validated meter reading** must be derived from a **meter reading**. A **meter reading** that is provided by a **consumer** may be used as a **validated meter reading** only if another set of **validated meter readings** that has not been provided by the **consumer** is used during the validation process specified in clauses 16 and 17.
- (3) An **estimated reading** and a **permanent estimate** must be clearly identified as an estimate at source and in an exchange of metering data or **volume information** between **participants** (excluding the **reconciliation manager**).
- (4) **Volume information** must be directly derived, in accordance with this Schedule, from—
  - (a) **validated meter readings**; or
  - (b) **estimated readings**; or
  - (c) **permanent estimates**.

- (5) A **reconciliation participant** must ensure that all **raw meter data** used to derive **volume information** in accordance with this Schedule is not rounded or truncated from the stored data from the **metering installation**.

Compare: Electricity Governance Rules 2003 clause 3 schedule J2

Clause 3(5): inserted, on 1 February 2016, by clause 102 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

#### 4 **Permanence for the purposes of reconciliation**

- (1) Only **volume information** created using **validated meter readings**, or if such values are unavailable, **permanent estimates**, has permanence within the reconciliation processes (unless subsequently found to be in error).
- (2) **Volume information** created using **estimated readings** must be replaced at the earliest opportunity by the relevant **reconciliation participant** with **volume information** that has been created using **validated meter readings** or **permanent estimates** by no later than the month 14 revision cycle.
- (3) A **permanent estimate** may be used in place of a **validated meter reading** only if a **reconciliation participant**, despite having used reasonable endeavours, has been unable to obtain a **validated meter reading**.

Compare: Electricity Governance Rules 2003 clause 4 schedule J2

#### *Meter interrogation for non half hour metering*

#### 5 **Non half-hour metering information**

A **reconciliation participant** must, when manually **interrogating** a **non half-hour metering installation**, if the relevant parts of the **metering installation** are visible and it is safe to do so,—

- (a) obtain the **meter** register value; and
- (b) ensure seals are present and intact; and
- (c) check for phase failure if the **meter** supports it; and
- (d) check for signs of tampering or damage; and
- (e) check for electrically unsafe situations, where “electrically unsafe” has the meaning given to it in the Electricity (Safety) Regulations 2010.

Compare: Electricity Governance Rules 2003 clause 5.1 schedule J2

Clause 5: substituted, on 29 August 2013, by clause 25 of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011.

Clause 5(e): amended, on 5 October 2017, by clause 531 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

#### 6 **When non half hour meter readings apply**

Non **half hour meter readings** are deemed to apply—

- (a) if the non **half hour meter reading** is also a **switch event meter reading**—
  - (i) for the gaining **trader**, from 0000 hours on the day of the relevant **event date**; and
  - (ii) for the losing **trader**, at 2400 hours at the end of the day before the relevant **event date**; or

- (b) in all other cases, from 0000 hours on the day after the last **meter interrogation** up to and including 2400 hours on the day of the **meter interrogation**.

Compare: Electricity Governance Rules 2003 clause 5.2 schedule J2

Clause 6: substituted, on 9 October 2015, by clause 27 of the Electricity Industry Participation Code Amendment (ICP Switching) 2014.

## **7 Non half hour meter reading during period of supply**

- (1) Each **reconciliation participant** must ensure that a **validated meter reading** is obtained in respect of every **meter** register for every non **half hour** metered **ICP** for which it is responsible, at least once during the period of supply to the **ICP** by the **reconciliation participant**, and used to create **volume information**. This may be a **validated meter reading** at the time the **ICP** is switched to, or from, the **reconciliation participant**.
- (2) If **exceptional circumstances** prevent a **reconciliation participant** from obtaining the **validated meter reading** described in subclause (1), the **reconciliation participant** is not required to comply with subclause (1).

Compare: Electricity Governance Rules 2003 clauses 5.3 and 5.3A schedule J2

## **8 Non half hour meter reading on 12 monthly basis**

- (1) Each **reconciliation participant** must ensure that, at least once every 12 months, a **validated meter reading** is obtained for every **meter** register for non **half hour** metered **ICPs** that the **reconciliation participant** trades continuously for each 12 month period. In carrying out this obligation—
- (a) each **reconciliation participant** must report to the **Authority**, in relation to each **NSP**, the percentage of the **ICPs** from which **consumption information** was collected and reported into the reconciliation process in the previous 12 month period. This report must be submitted no later than 20 **business days** after the end of each month; and
- (b) if the percentage reported in accordance with paragraph (a) is less than 100%, the **Authority** may, from time to time, require the **reconciliation participant** to explain why that level was not achieved and to describe the steps that are being taken to achieve a level of performance that, in the **Authority's** assessment, is reasonable.
- (2) If **exceptional circumstances** prevent a **reconciliation participant** from obtaining the **validated meter reading** described in subclause (1), the **reconciliation participant** is not required to comply with subclause (1).

Compare: Electricity Governance Rules 2003 clauses 5.4 and 5.4A schedule J2

Clause 8(1): amended, on 5 October 2017, by clause 532(a) and (b) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

## **9 Non half hour meter reading every 4 months**

- (1) Each **reconciliation participant** must ensure, in relation to each **NSP**, that a **validated meter reading** is obtained, at least once every 4 months, for 90% of the non **half hour** metered **ICPs** at which the **reconciliation participant** trades continuously for each 4 months for which **consumption information** is required to be reported into the reconciliation process. In carrying out this obligation—

- (a) each **reconciliation participant** must report to the **Authority** the percentage, in relation to each **NSP**, of the **ICPs** from which **consumption information** was collected and reported into the reconciliation process in the previous 4 month period. This report must be submitted no later than 20 **business days** after the end of each month; and
- (b) if the percentage reported in accordance with paragraph (a) is less than 90% in relation to any **NSP**, the **Authority** may, from time to time, require the **reconciliation participant** to explain why that level was not achieved and to describe the steps that are being taken to achieve acceptable performance.
- (2) If **exceptional circumstances** prevent a **reconciliation participant** from obtaining the **validated meter reading** described in subclause (1), the **reconciliation participant** is not required to comply with subclause (1).
- (3) The **reconciliation participant** must report to the **Authority** monthly on a rolling 4 month basis the percentage of non **half hour meter interrogations** within that period.

Compare: Electricity Governance Rules 2003 clauses 5.5 and 5.5A schedule J2

Clause 9(1) and (3): amended, on 5 October 2017, by clause 533 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

## 10 Interrogation log

To verify the accuracy of **raw meter data** collected during **interrogation** of non **half hour metering**, a log must be produced consisting of the following as a minimum:

- (a) the means to establish the identity of the individual **meter** reader:
- (b) the **ICP identifier**, and the **meter** and register identification:
- (c) the method being used for this **interrogation** and the device ID of equipment being used for **interrogation** of the **meter**:
- (d) the date and time of the **meter interrogation**.

Compare: Electricity Governance Rules 2003 clause 5.6 schedule J2

## 11 Metering installation that is electronically interrogated

- (1) A **reconciliation participant** must, as required under clause 2(2), obtain **raw meter data** from the **services access interface** for an electronically **interrogated metering installation**. This may be carried out through the use of portable devices or remotely by the use of a recognised communications medium.
- (2) **Raw meter data** obtained by the electronic **interrogation** of a **metering installation** must consist of the following as a minimum:
  - (a) the unique identifier of the **data storage device** in the **metering installation**:
  - (b) the time from the **data storage device** at the commencement of the download, unless the time is within specification and the **interrogation** log automatically records the time of **interrogation**:
  - (c) the **metering information**, which represents the quantity of **electricity** conveyed at the **point of connection**, including the date and time stamp or index marker for each **half hour** period. This may be limited to the **metering information** accumulated since the last **interrogation**:
  - (d) the **event log**, which may be limited to the events information accumulated since the last **interrogation**:

- (e) for all **metering information**, an **interrogation** log generated by the **interrogation software** to record details of all **interrogations**. The **reconciliation participant** responsible for collecting the data must peruse the **interrogation** log and take appropriate action if problems are apparent. Alternatively, this process may be an automated **software** function that flags exceptions.
- (3) For the purposes of subclause (2)(e), the **interrogation** log must form part of the **interrogation** audit trail and must contain the following as a minimum:
  - (a) the date of **interrogation**:
  - (b) the time of commencement of **interrogation**:
  - (c) the operator identification (if available):
  - (d) the unique identifier of the **data storage device**:
  - (e) the time errors outside the range specified in Table 1 of clause 2:
  - (f) the method of **interrogation**:
  - (g) the identifier of the reading device used for **interrogation** (if applicable).

Compare: Electricity Governance Rules 2003 clause 6.1 schedule J2

Clause 11: substituted, on 29 August 2013, by clause 26 of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011.

## 12 *[Revoked]*

Compare: Electricity Governance Rules 2003 clause 6.2 schedule J2

Clause 12 and Table 1: revoked, on 29 August 2013, by clause 27 of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011

## 13 **Trading period**

The **trading period** duration, which is normally 30 minutes, must be within  $\pm 0.1\%$  ( $\pm 2$  seconds).

Compare: Electricity Governance Rules 2003 clause 6.3 schedule J2

## 14 **Quantification error**

*[Revoked]*

Compare: Electricity Governance Rules 2003 clause 6.4 schedule J2

Clause 14: amended, on 21 September 2012, by clause 40 of the Electricity Industry Participation (Minor Amendments) Code Amendment 2012.

Clause 14: amended, on 29 August 2013, by clause 28 of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011.

Clause 14: revoked, on 1 February 2016, by clause 103 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

## 15 **Half hour estimates**

- (1) If a **reconciliation participant** is unable to **interrogate** an electronically **interrogated metering installation** before the deadline for providing **submission information** or **dispatchable load information**, the **reconciliation participant** must submit to the **reconciliation manager** its best estimate of the quantity of **electricity** that was purchased or sold in each **trading period** during any applicable **consumption period** for that **metering installation**.
- (2) The **reconciliation participant** must use reasonable endeavours to ensure that estimated **submission information** is within the percentage specified by the **Authority**.

Compare: Electricity Governance Rules 2003 clause 6.5 schedule J2  
Clause 15(1): amended, on 29 August 2013, by clause 29 of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011.  
Clause 15(1): amended, on 15 May 2014, by clause 102 of the Electricity Industry Participation (Modified Dispatchable Demand) Code Amendment 2013.

*Validation*

**16 Non half-hour meter readings and estimated readings**

- (1) All non **half hour meter readings** and **estimated readings** must be checked for validity by the relevant **reconciliation participant** after each **interrogation**.
- (2) Each validity check of non **half hour meter** readings and **estimated readings** must include the following:
  - (a) confirmation that the **meter reading** or **estimated reading** relates to the correct **ICP, meter**, and register:
  - (b) checks for invalid dates and times:
  - (c) confirmation that the **meter reading** or **estimated reading** lies within an acceptable range compared with the expected pattern, previous pattern or trend:
  - (d) confirmation that there is no corruption of the data, including unexpected 0 values.

Compare: Electricity Governance Rules 2003 clause 7.1 schedule J2

**17 Electronic meter readings and estimated readings**

- (1) All **meter readings** obtained by electronic **interrogation** and **estimated readings** must be checked for validity by the relevant **reconciliation participant**.
- (2) Each validity check of a **meter reading** obtained by electronic **interrogation** and each **estimated reading** must be at a frequency that will allow a further **interrogation** of the **data storage device** before the data is overwritten within the **data storage device** and before the data can be used for any purpose under this Code.
- (3) *[Revoked]*
- (4) Each validity check of a **meter reading** obtained by electronic **interrogation** or an **estimated reading** must include the following:
  - (a) checks for missing data:
  - (b) checks for invalid dates and times;
  - (c) checks of unexpected 0 values:
  - (d) comparison with expected or previous flow patterns:
  - (e) comparison of **meter readings** with data on any **data storage device** registers that are available:
  - (f) a review of **meter** and **data storage device** event log. Any event that could have affected the integrity of **metering data** must be investigated.

Compare: Electricity Governance Rules 2003 clause 7.2 schedule J2  
Clause 17 Heading: amended, on 29 August 2013, by clause 15 of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2013.  
Clause 17(1) and (2): substituted, on 29 August 2013, by clause 30(a) of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011.  
Clause 17(3): revoked, on 29 August 2013, by clause 30(b) of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011.  
Clause 17(4): amended, on 29 August 2013, by clause 30(c) of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011.

Clause 17(4): amended, on 29 August 2013, by clause 9 of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011, Amendment 2013 (No 2)

Clause 17(4)(f): amended, on 15 May 2014, by clause 65 of the Electricity Industry Participation (Minor Code Amendments) Code Amendment 2014.

## **18 Archiving and storing of raw meter data**

- (1) A **reconciliation participant** who is responsible for **interrogating a metering installation** under this Part must archive all **raw meter data** downloaded or collected, and any changes to the **raw meter data**, for not less than 48 months in accordance with clause 8(6) of Schedule 10.6 with all necessary amendments.
- (2) Each **reconciliation participant** must ensure that procedures are in place to ensure that **raw meter data** for which it is responsible cannot be accessed by unauthorised personnel.
- (3) Each **reconciliation participant** must ensure that **meter readings** cannot be modified without an audit trail being created.

Compare: Electricity Governance Rules 2003 clause 8 schedule J2

Clause 18(1): substituted, on 29 August 2013, by clause 31 of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011.

## **19 Correction of meter readings**

- (1) If errors are detected during the validation of non **half hour meter readings**, 1 of the following must be undertaken:
  - (a) confirmation of the original **meter reading** by carrying out another **meter reading**;
  - (b) replacement of the original **meter reading** by another **meter reading** (even if the replacement **meter reading** may be at a different date);
  - (c) if the original **meter reading** cannot be confirmed or replaced by a **meter reading** from another **interrogation**, an **estimated reading** may be substituted if the **estimated reading** is marked as an estimate and it is subsequently replaced in accordance with clause 4(2).
- (2) If errors are detected during the validation of **half-hour meter readings**, the **meter readings** must be corrected as follows:
  - (a) if a check **meter** or **data storage device** is installed at the **metering installation**, data from the check **meter** or **data storage device** may be substituted;
  - (b) in the absence of any check **meter** or **data storage device**, data may be substituted from another period if the total of all substituted intervals matches the total consumption recorded on a **meter**, if available, and the pattern of consumption is considered to be materially similar to the period in error.
- (3) **Error compensation** and **loss compensation** may be carried out as part of the process of determining accurate data. Whatever methodology is used, the compensation process must be documented and must comply with audit trail requirements.

Compare: Electricity Governance Rules 2003 clause 9 schedule J2

Clause 19(2): amended, on 29 August 2013, by clause 32 of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011.

## **20 Data transmission**

Transmissions and transfers of data related to metering between **reconciliation participants** or **reconciliation participant's** agents, for the purposes of this Code, must

be carried out electronically, using systems that ensure the security and integrity of the data transmitted and received.

Compare: Electricity Governance Rules 2003 clause 10 schedule J2

## 21 Audit trails

- (1) Each **reconciliation participant** must ensure that a complete audit trail exists for all data gathering, validation and processing functions of the **reconciliation participant**.
- (2) The audit trail must—
  - (a) include details of information—
    - (i) provided to and received from the **registry manager**;
    - (ii) provided to and received from the **reconciliation manager**; and
    - (iii) provided and received from other **reconciliation participants** and their agents; and
  - (b) cover all **raw meter data** and any changes to the **raw meter data** archived under clause 18.
- (3) Logs of communications and processing activities must form part of the audit trail, including if automated processes are in operation.
- (4) Logs must be printed and filed as hard copy or maintained as data files, in a secure form, along with other archived information, and must include (at a minimum) the following:
  - (a) an activity identifier;
  - (b) the date and time of the activity;
  - (c) the operator identifier.
- (5) A **reconciliation participant** must collect all relevant data used by the **reconciliation participant** to determine **profile** data, including external control equipment operation logs, and archive that data in accordance with clause 18.

Compare: Electricity Governance Rules 2003 clause 11.1 to 11.3 schedule J2

Clause 21(2)(a)(i): amended, on 5 October 2017, by clause 534 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 21(2)(b): substituted, on 29 August 2013, by clause 33(a) of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011.

Clause 21(5): amended, on 29 August 2013, by clause 33(b) of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011.

## 22 Correction of meter readings

- (1) In correcting a **meter reading** in accordance with clause 19, the **raw meter data** must not be overwritten. If the **raw meter data** and the **meter readings** are the same, an automatic secure backup of the affected data must be made and archived by the processing or data correction application.
- (2) If data is corrected or altered, the **reconciliation participant** correcting or altering the data must generate and archive a journal that contains the following information:
  - (a) the date of the correction or alteration;
  - (b) the time of the correction or alteration;
  - (c) the operator identifier of the **reconciliation participant**;
  - (d) the **half-hour meter reading** data or the non **half-hour meter reading** data corrected or altered, and the total difference in volume of such corrected or altered data:



- (e) the technique used to arrive at the corrected data:
- (f) the reason for the correction or alteration.

Compare: Electricity Governance Rules 2003 clause 11.4 schedule J2

## Schedule 15.3

### Calculation and provision of submission information

cl 15.4

#### 1 Contents of this schedule

This Schedule provides for—

- (a) the processing of **raw meter data** and supporting information to create **submission information**; and
- (b) the delivery of **submission information** to the **reconciliation manager**.

Compare: Electricity Governance Rules 2003 clause 1 schedule J3

#### *Creation of submission information*

#### 2 Reconciliation participants to prepare information

- (1) If a **reconciliation participant** is required to prepare **submission information** for an **NSP** for the relevant **consumption period** in accordance with this Code, the **submission information** must comprise the following:
  - (a) **half hour volume information** for each **ICP** provided under clause 11.7(2) for which there is a category 3 or higher **metering installation**;
  - (b) for each **ICP** about which information is provided under clause 11.7(2) for which there is a **category 1 metering installation** or **category 2 metering installation**,—
    - (i) **half hour volume information** for the **ICP**; or
    - (ii) non **half hour volume information** calculated under clauses 4 to 6 (as applicable) for the **ICP**;
  - (c) **unmetered load** quantities for each **ICP** that has **unmetered load** associated with it, which must be derived from the quantity recorded in the **registry** against the relevant **ICP** and the number of days in the period, the **distributed unmetered load** database, or other sources of relevant information.
- (2) To create non **half hour submission information**, a **reconciliation participant** must only use information that is dependent on a **control device** if—
  - (a) the **certification** of the **control device** is recorded in the **registry**; or
  - (b) the **metering installation** in which the **control device** is located is an **interim certified metering installation**.
- (3) A **reconciliation participant** must, to create **submission information** for a **point of connection** for which it is responsible, apply to the **raw meter data** obtained from each **metering installation**—
  - (a) for each **ICP**, the **compensation factor** recorded in the **registry** for the **metering installation**; or
  - (b) for each **NSP**, the **compensation factor** recorded in the **metering installation's** most recent **certification report**.

Compare: Electricity Governance Rules 2003 clause 2.1 schedule J3

Clause 2: substituted, on 29 August 2013, by clause 34 of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011.

Clause 2(1)(c): amended, on 15 May 2014, by clause 66 of the Electricity Industry Participation (Minor Code Amendments) Code Amendment 2014.

### 3 Historical estimates and forward estimates

- (1) Each **reconciliation participant** must, for each **ICP** that has a non **half hour metering installation**, allocate **volume information** derived from **validated meter readings**, **estimated readings** or **permanent estimates**, to **consumption periods** using the techniques described in this clause to create **historical estimates** and **forward estimates**.
- (2) Each estimate that is a **forward estimate** or an **historical estimate**, must be clearly identified as such.
- (3) If a **validated meter reading** is not available for the purpose of clauses 4 and 5, a **permanent estimate** may be used in place of a **validated meter reading**.

Compare: Electricity Governance Rules 2003 clause 2.2 schedule J3

### 4 Historical estimates with seasonal adjustment

The methodology that must be used by each **reconciliation participant** to prepare an **historic estimate** of **volume information** for each **ICP** when the relevant **seasonal adjustment shape** is available, is as follows:

- (a) if the period between any 2 consecutive **validated meter readings** encompasses an entire **consumption period**, an **historical estimate** must be prepared in accordance with the following formula:

$$HE_{ICP} = kWh_p \times A / B$$

where

$HE_{ICP}$  is the quantity of **electricity** allocated to a **consumption period** for an **ICP**

$kWh_p$  is the difference in kWh between the last **validated meter reading** before the **consumption period** and the 1<sup>st</sup> **validated meter reading** after the **consumption period**

A is the sum of the **seasonal adjustment shape** values for the **consumption period**

B is the sum of the **seasonal adjustment shape** values for the same time period as is covered by  $kWh_p$  as published by the **reconciliation manager**:

- (b) if the period between any 2 consecutive **validated meter readings** encompasses the 1<sup>st</sup> part of a **consumption period** and the period between the 2<sup>nd</sup> **validated meter reading** and the subsequent **validated meter reading** encompasses the rest of that **consumption period**, an **historical estimate** must be prepared in accordance with the following formula:

$$HE_{ICP} = kWh_{p1} \times A_1 / B_1 + kWh_{p2} \times A_2 / B_2$$

where

- $HE_{ICP}$  is the quantity of **electricity** allocated to a **consumption period** for an **ICP**
- $kWh_{p1}$  is the difference in kWh between the last **validated meter reading** before the **consumption period** and the **validated meter reading** during the **consumption period**
- $A_1$  is the sum of the **seasonal adjustment shape** values for the relevant days in the 1<sup>st</sup> part of the **consumption period**
- $B_1$  is the sum of the **seasonal adjustment shape** values for the same time period as is covered by  $kWh_{p1}$
- $kWh_{p2}$  is the difference in kWh between the first **validated meter reading** during the **consumption period** and the 1<sup>st</sup> **validated meter reading** after the **consumption period**
- $A_2$  is the sum of the **seasonal adjustment shape** values for the relevant days in the latter part of the **consumption period**
- $B_2$  is the sum of the **seasonal adjustment shape** values for the same time period as is covered by  $kWh_{p2}$ .

Compare: Electricity Governance Rules 2003 clauses 2.2.1 schedule J3

## 5 Historical estimates without seasonal adjustment

If a **seasonal adjustment shape** is not available, either due to timing (for the provision of **submission information** by the 4th **business day** of each **reconciliation period**) or for any other reason, the methodology for preparing an **historical estimate** of **volume information** for each **ICP** must be the same as in clause 4, except that the relevant quantities  $kWh_{Px}$  must be prorated as determined by the **reconciliation participant** using its own methodology or on a flat shape basis using the relevant number of days that are—

- (a) within the **consumption period**; and
- (b) within the period covered by  $kWh_{Px}$ .

Compare: Electricity Governance Rules 2003 clause 2.2.2 schedule J3

## 6 Forward estimates

- (1) A **forward estimate** is an estimation of the total quantity of **electricity** that flowed through an **ICP** during all or part of a **consumption period**.
- (2) A **forward estimate** may be used only for a period for which an **historical estimate** cannot be calculated.
- (3) The methodology used for calculating a **forward estimate** may be determined at the discretion of the **reconciliation participant**, and only if the **reconciliation participant** ensures that the accuracy of its initial **submission information** against each subsequent

revision cycle **submission information** for each **balancing area** is within the percentage of error specified and **published**, from time to time, by the **Authority**.

Compare: Electricity Governance Rules 2003 clause 2.2.3 schedule J3

## **7 Compulsory meter reading after profile change**

- (1) If a **reconciliation participant** changes the **profile** associated with a **meter**, it must, when determining the **volume information** for that **meter** and its respective **ICP**, use a **validated meter reading** or **permanent estimate** on the day on which the **profile** change is to take effect.
- (2) The **reconciliation participant** must use the **volume information** from that **validated meter reading** or **permanent estimate** to calculate the relevant **historical estimates** of each **profile** for that **meter**.

Compare: Electricity Governance Rules 2003 clause 2.2.4 schedule J3

## **8 Provision of submission information to reconciliation manager**

Each **reconciliation participant** must provide **submission information** to the **reconciliation manager** aggregated to the following level:

- (a) **NSP code**:
- (b) **reconciliation type**:
- (c) **profile**:
- (d) **loss category code**:
- (e) **flow direction**:
- (f) **dedicated NSP**:
- (g) **trading period** for **half hour** metered **ICPs** and **consumption period** or day for all other **ICPs**.

Compare: Electricity Governance Rules 2003 clause 3 schedule J3

## **9 Rounding of submission information**

If **submission information** aggregated by a **reconciliation participant** under clause 8 is specified to more than 2 decimal places, the **reconciliation participant** must round the **submission information**—

- (a) to 2 decimal places; and
- (b) so that if the digit to the right of the second decimal place is greater than or equal to 5, the second digit is rounded up, and if the digit to the right of the second decimal place is less than 5, the second digit is unchanged.

Compare: Electricity Governance Rules 2003 clause 3A schedule J3

Clause 9: amended, on 1 February 2016, by clause 104 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2015.

## **10 Reporting requirements**

- (1) By 1600 hours on the 13th **business day** of each **reconciliation period**, each **reconciliation participant** must report to the **reconciliation manager** the proportion of **historical estimates** per **NSP** contained within its non **half hour submission information**.
- (2) By 1200 hours on the last **business day** of each **reconciliation period**, the **reconciliation manager** must provide to the **Authority** a report of the proportion of

**historical estimates** per **NSP**, per **reconciliation participant** being used to create non **half hour consumption information** in respect of each **consumption period** being reconciled, and the **Authority** must publish the information.

- (3) The proportion of **submission information** per **retailer** per **NSP** that is comprised of **historical estimates** must, unless **exceptional circumstances** exist, be—
- (a) at least 80% for revised data provided at the month 3 revision; and
  - (b) at least 90% for revised data provided at the month 7 revision; and
  - (c) 100% for revised data provided at the month 14 revision.

Compare: Electricity Governance Rules 2003 clause 4 schedule J3

## **11 Distributed unmetered load database**

- (1) A **retailer** must ensure that an up-to-date database is maintained for each type of **distributed unmetered load** for which it is responsible. The methodology for deriving **submission information** in the database must comply with Schedule 15.5.
- (2) The database must contain at a minimum—
- (a) each **ICP identifier** for which the **retailer** is responsible, and to which **distributed unmetered load is electrically connected**; and
  - (aa) the item or items of **distributed unmetered load** associated with each **ICP identifier**; and
  - (b) the location of each item; and
  - (c) a description of load type for each item, including any assumptions made in the assessment of its capacity; and
  - (d) the capacity of each item in watts.
- (2A) Each **retailer** must ensure that each item of **distributed unmetered load** for which the **retailer** is responsible is recorded in the database in accordance with this clause.
- (3) The database must track the time of additions and changes in a way that enables the total load in kW to be retrospectively derived for any day.
- (4) The database must incorporate an audit trail of all additions and changes identifying the before and after values for changes, date and time of the change or addition, and the person making the change or addition.
- (5) *[Revoked]*

Compare: Electricity Governance Rules 2003 clause 5 schedule J3

Clause 11(2)(a): amended, on 19 December 2014, by clause 42 of the Electricity Industry Participation Code Amendment (Minor Code Amendments) (No 3) 2014.

Clause 11(2)(a): inserted, on 1 June 2017, by clause 35(1)(a) of the Electricity Industry Participation Code Amendment (Requirements and Processes for Audits) 2016.

Clause 11(2)(a): amended, on 5 October 2017, by clause 535 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 11(2)(b): amended, on 1 June 2017, by clause 35(1)(b) of the Electricity Industry Participation Code Amendment (Requirements and Processes for Audits) 2016.

Clause 11(2)(c): amended, on 1 June 2017, by clause 35(1)(c) of the Electricity Industry Participation Code Amendment (Requirements and Processes for Audits) 2016.

Clause 11(2)(d): amended, on 1 June 2017, by clause 35(1)(d) of the Electricity Industry Participation Code Amendment (Requirements and Processes for Audits) 2016.

Clause 11(2A): inserted, on 1 June 2017, by clause 35(2) of the Electricity Industry Participation Code Amendment (Requirements and Processes for Audits) 2016.

Clause 11(5): revoked, on 1 June 2017, by clause 35(3) of the Electricity Industry Participation Code Amendment (Requirements and Processes for Audits) 2016.

## Schedule 15.4 Reconciliation procedures

cls 15.19, 15.20 and 15.21

### 1 Contents of this Schedule

This Schedule relates to the parts of the reconciliation process performed by the **reconciliation manager** during each **reconciliation period** and for relevant **consumption periods** in accordance with the revision cycle. The following steps comprise the reconciliation process. The requirements of each of these steps are detailed in the remainder of this Schedule. The steps are that the **reconciliation manager** must—

- (a) adjust **submission information** by **ICP days** scaling; and
- (b) apply **loss factors** to **submission information** for **half hour** metered **ICPs** that have been adjusted for **ICP days**; and
- (c) **profile** non **half hour submission information** into **trading periods**; and
- (d) apply **loss factors** to **submission information** for non **half hour** metered **ICPs** that have been adjusted for **ICP days**; and
- (e) calculate **unaccounted for electricity** for each **balancing area**; and
- (f) allocate consumed **electricity** and **unaccounted for electricity** to **purchasers**; and
- (g) allocate generated **electricity** to **generators**; and
- (h) produce reports.

Compare: Electricity Governance Rules 2003 clause 1 schedule J4

### 2 Overview of key reconciliation events

Each **reconciliation participant** must comply with the timing requirements summarised below:

<i>Timing</i>	<i>Reconciliation process</i>	<i>Revisions cycles</i>
Commencement of the 1 <sup>st</sup> day of the <b>reconciliation period</b>	Beginning of <b>reconciliation period</b> .	Beginning of <b>reconciliation period</b> .
By 1600 hours on the 4th <b>business day</b> of the <b>reconciliation period</b>	The <b>registry manager</b> must make available, and the <b>reconciliation manager</b> must procure, <b>ICP days</b> , <b>loss factor</b> and <b>balancing area</b> and <b>half hour ICP identifiers</b> information, in accordance with clauses 11.24 to 11.27. Each <b>reconciliation participant</b> must submit to the <b>reconciliation manager</b> <b>submission information</b> , <b>retailer</b> information and	

Electricity Industry Participation Code 2010  
Schedule 15.4

<i>Timing</i>	<i>Reconciliation process</i>	<i>Revisions cycles</i>
	NSP information, in accordance with clauses 15.4 to 15.12.	
By 1600 hours on the 7th <b>business day</b> of the <b>reconciliation period</b>	The <b>reconciliation manager</b> must complete a reconciliation of the <b>submission information</b> provided by <b>participants</b> and the <b>grid owner</b> in accordance with this Schedule, and must make <b>reconciliation information</b> available to each <b>reconciliation participant</b> who submitted the <b>submission information</b> to which it relates, and the <b>clearing manager</b> for settlement.	
From the 8th <b>business day</b> of the <b>reconciliation period</b>	Each <b>reconciliation participant</b> must seek to resolve all inaccuracies and disputes concerning the <b>reconciliation information</b> .	
By 1600 hours on the 13 <sup>th</sup> <b>business day</b> of the <b>reconciliation period</b>		Each <b>reconciliation participant</b> must submit to the <b>reconciliation manager</b> revised <b>submission information</b> , <b>retailer information</b> and <b>NSP information</b> in accordance with clauses 15.4 to 15.12, 15.27, and 15.28, and clause 10 of Schedule 15.3. The <b>registry manager</b> must make available and the <b>reconciliation manager</b> must procure revised <b>ICP days</b> , <b>loss factor</b> , <b>balancing area</b> and <b>half hour ICP identifiers</b> information, in accordance with clauses 11.24 to 11.27, and clause 10 of Schedule 15.3.



<i>Timing</i>	<i>Reconciliation process</i>	<i>Revisions cycles</i>
By 1200 hours on the last <b>business day</b> of the <b>reconciliation period</b>		The <b>reconciliation manager</b> must distribute revised <b>reconciliation information</b> to the entitled <b>reconciliation participants</b> and the <b>clearing manager</b> , in accordance with clause 28 of this Schedule.

Compare: Electricity Governance Rules 2003 clause 2 schedule J4  
Clause 2 Rows 2 and 5 of Table: amended, on 5 October 2017, by clause 536 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### 3 Calculation by difference for embedded networks

- (1) A **trader** may by written notice to the **reconciliation manager** designate an **ICP** on an **embedded network** for which the **volume information** is to be calculated by difference.
- (2) A **trader** must give notice under subclause (1) at least 5 **business days** before the designation of the **ICP** takes effect.
- (3) Not more than 1 **ICP** on an **embedded network** may be designated at any time.
- (4) The **reconciliation manager** must calculate the **volume information** by **trading period** for an **ICP** to which a designation relates using the following formula:

$$i - x = a$$

where

- i* is the loss adjusted quantity of **electricity** injected into the **embedded network** derived from **NSP** and **submission information**
- x* is the loss adjusted quantity of **electricity** leaving the **embedded network** derived from **NSP** and **submission information**
- a* is the differenced **volume information** for the **ICP** to which the designation relates.
- (5) The **reconciliation manager** must allocate the **volume information** calculated under subclause (4) to the **ICP** to which the designation relates.
  - (6) A **trader** may, by written notice to the **reconciliation manager**, revoke a designation made under subclause (1).

Compare: Electricity Governance Rules 2003 clause 3 schedule J4

### 4 Calculation by difference for local networks

- (1) A **trader** may apply to the **Authority** for the **Authority** to designate part of a **local network** for which the **volume information** is to be calculated by difference.
- (2) A **trader** must give notice under subclause (1) at least 10 **business days** before the date the **trader** intends the designation to take effect.

- (3) The **trader** must comply with any requirements specified by the **reconciliation manager** within 5 **business days** of receiving notice of the requirements.
- (4) If the **Authority** grants a designation, the **reconciliation manager** must calculate the **volume information** by **trading period** for an **ICP** to which the designation relates using the following formula:

$$i - x = a$$

where

- i is the loss adjusted quantity of **electricity** injected into the **local network** derived from **NSP** and **submission information**
  - x is the loss adjusted quantity of **electricity** leaving the **local network** derived from **NSP** and **submission information**
  - a is the differenced **volume information** for the **ICP** to which the designation relates.
- (5) The **reconciliation manager** must allocate the **volume information** calculated under subclause (4) to the **trader** who applied for the designation under subclause (1).
- (6) The **Authority** may revoke the approval of a designation granted under subclause (1).

Compare: Electricity Governance Rules 2003 clause 3A schedule J4  
Clause 4(3): amended, on 5 October 2017, by clause 537 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

## **5 ICP days scaling of submission information excluding embedded generation information**

**ICP** scaling must be used to adjust each **retailer's submission information** (excluding **embedded generator** information) by a factor determined by the number of **ICP days** submitted for reconciliation compared to the number of **ICP days** recorded in the **registry**.

Compare: Electricity Governance Rules 2003 clause 4 schedule J4

## **6 ICP days information**

- (1) Each **retailer** and each **direct purchaser** (excluding **direct consumers**) must deliver to the **reconciliation manager**, in accordance with clause 15.6, the number of **half hour** and non **half hour ICP days** for the **NSPs** that are recorded in the **registry** as consuming **electricity** at any time during the relevant **consumption period**, upon which the **retailer's** or **direct purchaser's submission information** is based.
- (2) The **registry manager** must deliver to the **reconciliation manager**, in accordance with clauses 11.24 to 11.27, the number of **half hour** and non **half hour ICP days** per **NSP** each **retailer** and **direct purchaser** (excluding **direct consumers**) is responsible for during each **consumption period**.

Compare: Electricity Governance Rules 2003 clause 4.1 schedule J4  
Clause 6: amended, on 5 October 2017, by clause 538 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

## 7 ICP scaling factor calculation

- (1) The **reconciliation manager** must, using the **retailer** and **direct purchaser** reported **ICP days** and **registry** reported **ICP days**, calculate **ICP day** scaling factors separately in respect of non **half hour** and **half hour** metered **ICPs** according to the following formula:

$$ICP_{SF} = ICPD_{REG} / ICPD_{RTL R}$$

where

$ICP_{SF}$  is the **ICP** scaling factor

$ICPD_{REG}$  is the number of **ICP days** for that **retailer** per **balancing area** as reported by the **registry manager**

$ICPD_{RTL R}$  is the number of **ICP days** for that **retailer** for that **balancing area** as reported by each **retailer**

provided that if—

- (a) the **ICP** scaling factor is calculated to be less than 1, it must, for the purposes of this clause, be deemed to be 1; and
  - (b) the **ICP** scaling factor is calculated to be greater than 1, it must not exceed a figure nominated and published from time to time by the **Authority**.
- (2) The **ICP days** scaling factor for **direct consumers** must be 1.
- (3) If the **ICP days** value reported by a **retailer** or a **direct purchaser** in respect of a **balancing area** is 0, or if data is not supplied, but in each case the corresponding **ICP days** value from the **registry manager** is not 0, the **reconciliation manager** must add to that **retailer's submission information** for that **consumption period** an amount (designated  $SI_{ICPD-ADD}$ ) that is equal to—
- (a) 25 kWh per **ICP day**, in respect of non **half hour ICPs**; and
  - (b) 40 kWh per **trading period** per **ICP day**, in respect of **half hour ICPs**.
- (4) The relevant number of **ICP days** is the value reported by the **registry manager**.
- (5) The **reconciliation manager** must, when processing 0 **ICP days** information, and if data is not supplied, use default values for **profile**, and **loss category** code, as determined by the **Authority** from time to time.

Compare: Electricity Governance Rules 2003 clause 4.2 schedule J4

Clause 7(1), (3) and (4): amended, on 5 October 2017, by clause 539 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

## 8 ICP days scaling of submission information (excluding embedded generator information)

- (1) The **reconciliation manager** must separately apply the **ICP** scaling factors and any additional amount calculated in clause 7 to the reported **half hour** and non **half hour** **submission information** (excluding **embedded generator** information) of each **retailer** or **direct purchaser** (excluding **direct consumers**) so as to scale up the

**submission information** in proportion to any under submission by the **retailer** or **direct purchaser**.

- (2) The **ICP** scaling factor and any amount calculated in accordance with clause 7 must be applied to the **submission information** according to the following formula:

$$SI_{ICPD-ADJ} = (SI \times ICP_{SF}) + SI_{ICPD-ADD}$$

where

$SI_{ICPD-ADJ}$  is **submission information** adjusted for **ICP days**

$SI$  is the amount of **electricity** reported as part of that **retailer's** or **direct purchaser's submission information**

$ICP_{SF}$  is the **ICP** scaling factor determined in accordance with clause 7

$SI_{ICPD-ADD}$  is the default **ICP** 0 days volume defined under clause 7(3).

Compare: Electricity Governance Rules 2003 clause 4.3 schedule J4

## 9 Calculate residual non half hour profile shape

The **reconciliation manager** must calculate the residual **profile** shape for each **balancing area** in accordance with Schedule 15.5.

Compare: Electricity Governance Rules 2003 clause 5 schedule J4

*Convert non half hour quantities using profiles*

## 10 Allocation by profile

If **submission information** is submitted as non **half hour** quantities to be allocated to **trading periods** by **profile** shape, the **reconciliation manager** must use the appropriate shape for the **profile** code contained in the **submission information**, if—

- (a) the **profile** code has been approved by the **Authority** in accordance with Schedule 15.5; and
- (b) the **profile owner** has given written notice to the **reconciliation manager** of the approved **profile** code; and
- (c) the **profile owner** has authorised the **reconciliation participant** to use the approved **profile** code.

Compare: Electricity Governance Rules 2003 clause 6.1 schedule J4

Clause 10(a) and (b): amended, on 5 October 2017, by clause 540 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

## 11 Profile shapes or operation logs

If an engineered, statistically sampled or recorded **profile** forms part of the **submission information**, the shape file or operation logs associated with the **profile** must be provided to the **reconciliation manager** by the **reconciliation participant** authorised by the **profile owner** to use that **profile** for each relevant **NSP** in respect of the prior **consumption period** in accordance with clauses 15.4 to 15.12.

Compare: Electricity Governance Rules 2003 clause 6.2 schedule J4

## 12 Application of profile shapes

The **reconciliation manager** must calculate the **trading period** information by applying the **profile** shape for the **profile** code specified in the submission file provided by the **reconciliation participant** if—

- (a) the **profile** code has been approved by the **Authority** in accordance with Schedule 15.5; and
- (b) the **profile owner** has given written notice to the **reconciliation manager** of the approved **profile** code, and the **profile owner** has authorised the **reconciliation participant** to use the approved **profile** code; and
- (c) if a **balancing area** shape is required as part of the **profile**, the initial residual or final residual **profile** shape as defined in Schedule 15.5 must be used.

Compare: Electricity Governance Rules 2003 clause 6.3 schedule J4

Clause 12(a) and (b): amended, on 5 October 2017, by clause 541 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

## 13 Balancing area derived profiles approved in accordance with Appendix 1 of Schedule 15.5

The **reconciliation manager** must calculate the **trading period** information by applying the **balancing area** derived **profile** code specified in the submission file provided by the **reconciliation participant**, if—

- (a) the **profile** code has been approved by the **Authority** for use as a **balancing area** derived **profile** in accordance with Schedule 15.5; and
- (b) the **profile owner** has given written notice to the **reconciliation manager** of the approved **profile** code, and that the **profile owner** has authorised the **reconciliation participant** to use the approved **profile** code; and
- (c) if the **Authority** has not approved the **profile** code, or submitted the **profile** to the **reconciliation manager** in accordance with clause 12(1) of Appendix 1 of Schedule 15.5, the **reconciliation manager** must use the final residual **profile** shape as defined in Schedule 15.5.

Compare: Electricity Governance Rules 2003 clause 6.4 schedule J4

Clause 13(a) and (b): amended, on 5 October 2017, by clause 542(a) and (b) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 13(c): replaced, on 5 October 2017, by clause 542(c) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

## 14 Invalid submission information

If invalid **submission information** is submitted, and the **reconciliation manager** cannot obtain corrected information within a reasonable time period from the **reconciliation participant**, the **reconciliation manager** must—

- (a) use the default values specified in this Code (if any); or
- (b) if the default values described in paragraph (a) do not exist, use the default values specified by the **Authority** (if any); or
- (c) if the default values described in paragraph (b) do not exist, temporarily replace the invalid data with an estimate.

Compare: Electricity Governance Rules 2003 clause 6.5 schedule J4

## 15 Loss factors

- (1) The **Authority** may, from time to time, direct the **reconciliation manager** to apply certain values for **loss factors** for each **loss category** for a **reconciliation period** for which the **registry manager** does not, for whatever reason, provide the **reconciliation manager** with the **loss factors** for each **loss category** in accordance with clause 11.26(b).
- (2) If the **Authority** makes such a direction, the **reconciliation manager** must, after adjustment for **ICP days** scaling and the application of **profiles**, apply such **loss factors** to all **submission information** for all **reconciliation periods** during which the **Authority's** direction is current.
- (3) The **reconciliation manager** must apply **loss factors** to **submission information** in respect of each **embedded network** and **interconnection point**, and **submission information** in respect of parent **networks** for the appropriate **reconciliation period**.

Compare: Electricity Governance Rules 2003 clause 7 schedule J4

Clause 15(1): amended, on 5 October 2017, by clause 543 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

## 16 Calculation of unaccounted for electricity

- (1) The **reconciliation manager** must calculate the **unaccounted for electricity** for each **balancing area** for each **trading period** in accordance with the following formula after all relevant quantities have been loss adjusted and scaled for **ICP days**:

$$UFE_{BA} = TOT_{BA} - Q_{BA-EN}$$

where

$UFE_{BA}$  is the **unaccounted for electricity** for each **balancing area** for the relevant **trading period**

$TOT_{BA}$  is the net total of all **electricity** injected into the **balancing area** less all **electricity** leaving the **balancing area** as measured at—  
(a) the **NSPs** in respect of the **balancing area**; and  
(b) the **ICPs** for any **embedded generators electrically connected** to the **balancing area**

$Q_{BA-EN}$  is all **electricity** conveyed to **consumers** connected to the **balancing area**, being the sum of the consumption parts of **submission information**, adjusted for **losses** and **ICP days**.

- (2) The **reconciliation manager** must calculate the **UFE** factor in respect of each **balancing area** for each **trading period** as follows:

$$UFE\ Factor_{BA} = TOT_{BA} / Q_{ICPD-LA}$$

where

$UFE\ Factor_{BA}$  is the **unaccounted for electricity** factor in respect of each **balancing area** for each **trading period**

$Q_{ICPD-LA}$  is all **electricity** conveyed to consumers and **embedded networks** connected to the **balancing area**, being the sum of the consumption parts of **submission information**, adjusted for **losses** and **ICP days**

$TOT_{BA}$  has the meaning given to it in subclause (1).

Compare: Electricity Governance Rules 2003 clause 8 schedule J4

Clause 16(1) definition of  $Q_{BA-EN}$ : amended, on 15 May 2014, by clause 67(a) of the Electricity Industry Participation (Minor Code Amendments) Code Amendment 2014.

Clause 16(2) definition of  $Q_{ICPD-LA}$  : amended, on 15 May 2014, by clause 67(b) of the Electricity Industry Participation (Minor Code Amendments) Code Amendment 2014.

Clause 16(1) and (2): amended, on 23 February 2015, by clause 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 16(1) and (2): amended, on 5 October 2017, by clause 544 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

## 17 Scorecard rating

- (1) The **reconciliation manager** must rate each **retailer** relative to all other **retailers** using a **scorecard rating**. The numerical scores must be determined in accordance with this clause and clause 18 and used to weight the portion of **unaccounted for electricity** to be allocated to each **retailer**.
- (2) Each **retailer** must provide to the **reconciliation manager**, in accordance with clause 15.7, the quantity of **electricity supplied**.
- (3) The **reconciliation manager** must allocate **electricity supplied** quantities, to **reconciliation periods** for reporting and calculation purposes and in the event of unusual circumstances that must have been approved beforehand in writing by the **Authority**, re-allocate quantities on a reasonable basis to reflect the month(s) of actual usage.

Compare: Electricity Governance Rules 2003 clause 9.1 schedule J4

## 18 Calculation of scorecard rating

- (1) The **reconciliation manager** must calculate, **publish** and apply the **scorecard rating** for each **retailer** as follows:
  - (a) the **scorecard rating** for each **retailer** must be calculated and **published** by the **reconciliation manager** in respect of each **reconciliation period** from which the **reconciliation manager** processes **submission information**, but must only be applied in respect of the 7 and 14 month revisions:
  - (b) the **scorecard rating** for each **retailer** for each **balancing area** ( $SC_{Ri}$ ) must, subject to subclause (4), be calculated according to the following formula (provided that if the **scorecard rating** is calculated through the application of the formula to be less than 1, then  $SC_{Ri}$  is set to 1):

$$SC_{Ri} = AES_{Ri} / (ACI_{Ri} \times SC_{Thres})$$

where

- 
- |              |   |
|--------------|---|
| $SC_{Ri}$    | $SC$ is the <b>scorecard rating</b> and the subscript “ $Ri$ ” is a <b>retailer</b> , for each <b>consumption period</b> and each <b>balancing area</b>   |
| $AES_{Ri}$   | is the sum of the <b>electricity</b> supplied quantities for the 12 months up to and including the month of the relevant <b>consumption period</b>  |
| $ACI_{Ri}$   | is the sum of the <b>submission information</b> quantities ( <b>ICP days</b> adjusted but non <b>loss</b> adjusted) for the 12 months up to and including the month before the relevant <b>consumption period</b>                                     |
| $SC_{Thres}$ | is the scorecard threshold (that allows for a degree of expected misalignment between the annualised <b>electricity supplied</b> and <b>submission information</b> quantities) and has the value specified by the <b>Authority</b> from time to time: |
- (c) in all cases, the latest **electricity supplied** and **submission information** quantities submitted to the **reconciliation manager** by the **retailer** must be used.
- (2) The **scorecard rating** for each **retailer** must be set to 1.25 if the **retailer** has not provided the **reconciliation manager** with any of the required information.
- (3) Despite subclauses (1) and (2), the **scorecard rating** for **direct consumers** and **direct purchasers** must be 1.
- (4) Despite anything else in this Code, the **scorecard rating** must be set to 1 until such time as the **Authority** gives written notice to **participants** that the **scorecard rating** will be calculated and applied in accordance with this clause.
- Compare: Electricity Governance Rules 2003 clauses 9.2 and 9.3 schedule J4  
Clause 18(4): amended, on 5 October 2017, by clause 545 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

## 19 Calculation of unaccounted for electricity

The **reconciliation manager** must apportion **unaccounted for electricity** to each **retailer** and **direct purchaser** at each **NSP** and for each **trading period** using the following formulae:

$$UFE_{Ri} = UFE_{BA} \times AF_{Ri}$$

$$AF_{Ri} = \frac{(SC_{Ri} \times MS_{Ri})}{\text{sum}(SC_{R1} \times MS_{R1}, \dots, SC_{Rn} \times MS_{Rn})}$$

$$MS_{Ri} = Q_{ICPD-LA Ri} / \text{sum}(Q_{ICPD-LA 1}, \dots, Q_{ICPD-LA n})$$

where, for each **trading period**

$UFE_{Ri}$  is the quantity of **unaccounted for electricity** to be allocated to each **retailer** or **direct purchaser**

$UFE_{BA}$  is the quantity of **unaccounted for electricity** for each **balancing area** calculated by the **reconciliation manager** in accordance with clause 16(1)



$Q_{ICPD-LA\ Ri}$  is the quantity of **electricity** attributed to each **retailer** or **direct purchaser**, which has been adjusted for **losses** and **ICP days** at each **NSP**, determined by the **reconciliation manager** from that **retailer's** or **direct purchaser's submission information**

$AF_{Ri}$  is the **unaccounted for electricity** allocation factor, expressed as a fractional number (not less than 0 or greater than 1), for each **retailer** or **direct purchaser** at each **NSP**, determined by the **reconciliation manager**

$MS_{Ri}$  is the market share proportion, expressed as a fractional number (not less than 0 or greater than 1), for each **retailer** or **direct purchaser** at each **NSP** to be determined by the **reconciliation manager** from all **submission information** at that **NSP**

and, for each **consumption period**

$SC_{Ri}$  is the **scorecard rating** for each **retailer** or **direct purchaser** for each **balancing area** determined by the **reconciliation manager** in accordance with clauses 17 and 18.

Compare: Electricity Governance Rules 2003 clause 10.1 schedule J4

## 20 Allocation of unaccounted for electricity

The **reconciliation manager** must add each **retailer's** or **direct purchaser's** share of **unaccounted for electricity** to the previously calculated **ICP days** and **loss** adjusted **submission information** at each **NSP** for each **trading period** using the following formula:

$$Q_{ILU\ Ri} = Q_{ICPD-LA\ Ri} + UFE_{Ri}$$

where, for each **trading period**

$Q_{ILU\ Ri}$  is the quantity of **electricity** to be attributed to each **retailer** or **direct purchaser** that has been **ICP days** scaled, and **loss** adjusted and is **UFE** inclusive

$Q_{ICPD-LA\ Ri}$  and  $UFE_{Ri}$  have the meaning given to them in clause 19.

Compare: Electricity Governance Rules 2003 clause 10.2 schedule J4

## 21 Parent network UFE allocated to embedded networks

A portion of the **UFE** from the **balancing area** to which an **embedded network** is connected must be allocated by the **reconciliation manager** to each **reconciliation participant** trading on the **embedded network**. The quantity of **UFE** to be allocated by the **reconciliation manager** to the **embedded network** must be allocated in proportion to the ratio of the **embedded network's**, and upstream **balancing area's**, **submission information** quantities (that have been adjusted for **losses** and **ICP days**).

Compare: Electricity Governance Rules 2003 clause 11 schedule J4

Clause 21: amended, on 23 February 2015, by clause 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 21: amended, on 5 October 2017, by clause 546 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

## 22 Balancing

The **reconciliation manager** must balance the **UFE** inclusive, **ICP days** and loss adjusted **submission information** so that the sum of each **reconciliation participant's** quantities equals each **NSP** metered quantity during each **trading period**. The following process must be used by the **reconciliation manager**:

- (a) for each **retailer** or **direct purchaser**, at each **NSP**, any quantities that have been designated as being attributable to a specific **NSP** within the **balancing area** must be separated off from the remaining non-dedicated quantity and remain allocated to the specific **NSP**. If the sum of each **retailer's** dedicated-**NSP** quantities exceeds the amount of **electricity** conveyed at the **NSP** in any **trading period**, the **NSP** total must be apportioned to the relevant **retailers** or **direct purchasers** in proportion to their dedicated-**NSP** quantities. The net quantities of non-dedicated **electricity** at each **NSP** must be determined by subtracting the dedicated quantities from the **NSP** totals:
- (b) the **NSPs** within a **balancing area** that have been over-allocated **electricity** must be identified by comparing the sum of the non-dedicated quantities for each **retailer** and **direct purchaser** with the net **NSP** quantity. The non-dedicated quantities for each **retailer** and **direct purchaser** at each over-allocated **NSP** must be adjusted in order to achieve balance as follows:

$$Q_{BAL\ NSP_x\ Ri} = \frac{Q_{ILUN\ NSP_x\ Ri} \times TOT_{ND\ NSP_x}}{\text{sum}(Q_{ILUN\ NSP_x\ R1}, \dots, Q_{ILUN\ NSP_x\ Rn})}$$

where

$Q_{BAL\ NSP_x\ Ri}$  is the quantity of fully adjusted, non dedicated **electricity** per **NSP** allocated to each **retailer** and **direct purchaser** after balancing to match the **NSP** total

$Q_{ILUN\ NSP_x\ Ri}$  is the quantity of non-dedicated **electricity** per **NSP** attributed to each **retailer** and **direct purchaser**, which has been adjusted for **losses** and **ICP days**, and is **UFE** inclusive

$TOT_{ND\ NSP_x}$  is the quantity of non-dedicated **electricity** conveyed at the **NSP** (after allowing for relevant **balancing area** injection and extraction quantities):

- (c) the **reconciliation manager** must identify the quantities of **electricity** by which the over-allocated **NSPs** have been reduced, by **retailer** and by **direct purchaser**, and re-allocate to the corresponding under-allocated **NSPs** within the **balancing area** using the following formulae:
  - (i) calculate the previously over-allocated quantity per **retailer** and **direct purchaser** per **balancing area** as follows:

$$Q_{OVER\ Ri} = \text{sum}(Q_{ILUN\ NSP1\ Ri} - Q_{BAL\ NSP1\ Ri}, \dots, Q_{ILUN\ NSPn\ Ri} - Q_{BAL\ NSPn\ Ri})$$

where

$Q_{OVER\ Ri}$  is the sum, over all **NSPs** in the **balancing area** that are over-allocated per **retailer** and **direct purchaser**, of the differences between the pre- and post-adjusted quantities in paragraph (b); and

$Q_{ILUN\ NSP1\ Ri}$  and  $Q_{BAL\ NSP1\ Ri}$  have the meaning given to them in paragraph (b):

- (ii) determine the proportions by which the over-allocated quantity must be allocated to the under-allocated **NSPs**, per **retailer** and **direct purchaser**, in order to ensure that the sum of all **reconciliation participants'** totals balance, after re-allocation, to the **NSP** totals as follows:

$$PR_{NSP\ x} = (\text{TOT}_{ND\ NSP\ x} - \text{sum}(Q_{ILUN\ NSP\ x\ R1} \dots Q_{ILUN\ NSP\ x\ Rn})) / Q_{OVER\ BA}$$

where

$PR_{NSP\ x}$  is the proportion by which the over-allocated quantity must be allocated to the under-allocated **NSPs**, per **retailer** and **direct purchaser**

$Q_{OVER\ BA}$  is the sum of all over-allocated quantities for all **retailers** and **direct purchasers** for all over-allocated **NSPs** in the relevant **balancing area**

$\text{TOT}_{ND\ NSP\ x}$  and  $Q_{ILUN\ NSP\ x\ R1}$  have the meaning given to them in paragraph (b):

- (iii) allocate the over-allocated quantities to each **retailer** and **direct purchaser** at each under-allocated **NSP** as follows:

$$Q_{BAL\ NSP\ x\ Ri} = \frac{Q_{OVER\ Ri} \times PR_{NSP\ Rx}}{+ Q_{ILUN\ NSP\ x\ Ri}}$$

where

$Q_{BAL\ NSP\ x\ Ri}$  is the over-allocated quantities of **electricity** attributed to each **retailer** and **direct purchaser** at each under-allocated **NSP**;

$Q_{OVER\ Ri}$  has the meaning given to it in subparagraph (i)

$Q_{ILUN\ NSP\ x\ Ri}$  has the meaning given to it in paragraph (b); and

$PR_{NSP\ Rx}$  has the meaning given to it in subparagraph (ii).

Compare: Electricity Governance Rules 2003 clause 12 schedule J4

Clause 22: amended, on 15 May 2014, by clause 68 of the Electricity Industry Participation (Minor Code Amendments) Code Amendment 2014.

## 23 Final quantities

The **reconciliation manager** must determine the final quantities of **electricity** to be purchased by each **reconciliation participant** by adding the dedicated and non-dedicated, balanced quantities using the following formula:

$$Q_{TOT Ri} = Q_{BAL NSPx Ri} + Q_{DED Ri}$$

where

$Q_{TOT Ri}$  is the final quantity of **electricity** to be purchased by each **reconciliation participant** determined by adding the dedicated and non-dedicated balanced quantities

$Q_{BAL NSPx Ri}$  has the meaning given to it in clause 22(c)(iii)

$Q_{DED Ri}$  are the quantities of **electricity** to be purchased by each **reconciliation participant** for dedicated quantities.

Compare: Electricity Governance Rules 2003 clause 13 schedule J4

## 24 Reconciliation manager reporting requirements

- (1) The **reconciliation manager** must provide the information specified in clauses 25 to 27 to those **reconciliation participants**, **participants** and the **Authority** listed in those clauses, in respect of the prior **consumption period**, by 1600 hours on the 7th **business day** of each **reconciliation period**, and in respect of revisions in accordance with clauses 15.27 and 15.28 by 1200 hours on the last **business day** of each **reconciliation period**.

Compare: Electricity Governance Rules 2003 clause 14 schedule J4

## 25 Retailer and direct purchaser reports

The **reconciliation manager** must make the following reports available to each relevant **retailer** and **direct purchaser** trading on the **network**:

- (a) the **reconciliation manager** must produce 3 reports of the **UFE** factors for each **NSP** per **retailer** and **direct purchaser**, being—
- (i) 1 report by **trading period**; and
  - (ii) 1 report by **consumption period**; and
  - (iii) 1 report issued monthly in respect of the immediately preceding 12 **consumption periods**:
- (b) the **reconciliation manager** must report to each **retailer** and **direct purchaser** the **retailer's** and **direct purchaser's** own scorecard and market share proportions for each **NSP**:
- (c) the **reconciliation manager** must report the non **half hour** and **half hour ICP days** scaling factor for each **NSP** and each **retailer** and **direct purchaser**:

- (d) the **reconciliation manager** must report to each **retailer** and **direct purchaser** the **retailer's** and **direct purchaser's** monthly totals for **half hour** metered **ICPs** as supplied by that **retailer** and **direct purchaser** in accordance with clause 15.8, for which **submission information** has not been received within the time required by this Code;
- (e) the **reconciliation manager** must report to each **retailer** and **direct purchaser** the **retailer's** and **direct purchaser's** number of **ICP days** for which **submission information** has not been received within the time required by this Code, separately for non **half hour** and **half hour meter** types;
- (f) the **reconciliation manager** must report all **half hourly** metered **ICPs** that have switched **retailer** and **direct purchaser** in the previous 2 months and for which consumption has changed by a percentage determined by the **Authority**.

Compare: Electricity Governance Rules 2003 clause 14.1 schedule J4

## 26 Distributor reports

The **reconciliation manager** must forward a report to each **distributor** that includes the following information:

- (a) **electricity** traded for each **trader** trading on the **distributor's network**;
- (b) **electricity supplied** information for each **trader** trading on the **distributor's network**;
- (c) **submission information** for each **trader** trading on the **distributor's network**.

Compare: Electricity Governance Rules 2003 clause 14.2 schedule J4

## 27 Surveillance reports

The **reconciliation manager** must make the following reports available to the **Authority** and all **participants**:

- (a) reports by **retailers** and **direct purchasers** for the total **unaccounted for electricity** for each **NSP**;
- (b) reports by **retailers** for each **balancing area** of the variation between **electricity supplied** as reported by **retailers** (in accordance with clause 17) and **submission information** submitted for reconciliation by **retailers**;
- (c) summary reports of all **half hour** metered connections for which **submission information** has not been received within the time required by this Code;
- (d) summary reports by **retailers** and **direct purchasers** separately for non **half hour** and **half hour**, of all **ICP days** for which **reconciliation information** has not been received within the time required by this Code;
- (e) reports for each **balancing area** for the difference between the daily average non **half hour** kWh submitted by each **retailer** and **direct purchaser** per **NSP**, and the daily average non **half hour** kWh submitted by all **retailers** and **direct purchasers** per **NSP**;
- (f) separate reports for non **half hour** and **half hour submission information** detailing the difference between the quantity of **electricity** in initial and the quantity of **electricity** in each subsequent **submission information** submission for each **NSP** and each **retailer** and **direct purchaser**.

Compare: Electricity Governance Rules 2003 clause 14.3 schedule J4

Clause 27(c): amended, on 23 February 2015, by clause 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 27(c): amended, on 5 October 2017, by clause 547 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

## **28 Provision of reconciliation information**

The **reconciliation manager** must provide the following information to the **clearing manager** and those **participants** listed below, and in the case of paragraph (f), to the **Authority**, in respect of the prior **consumption period**, by 1600 hours on the 7th **business day** of each **reconciliation period**, and in respect of revisions in accordance with clauses 15.27 and 15.28 by 1200 hours on the last **business day** of each **reconciliation period**. These reports must be in the format, and contain the information determined by the **Authority**. The reports are—

- (a) to each **generator** or **purchaser**, the **reconciliation information** applying to that **generator** or **purchaser**, to enable the **generator** or **purchaser** to verify its **reconciliation information**; and
- (b) to each **grid owner**, such information as is required by that **grid owner** to calculate its charges; and
- (c) to the **clearing manager**, the **reconciliation information** (including all amounts derived by the **reconciliation manager** in accordance with clause 20) applying to each **participant** to enable the **clearing manager** to calculate the amounts owing by the **clearing manager** to each **participant** and by each **participant** to the **clearing manager**; and
- (d) to each **retailer** and **direct purchaser**, the calculated daily **seasonal adjustment shape** related to any **point of connection** for which the **retailer** and **direct purchaser** is trading; and
- (e) to each **retailer**, **generator**, and **direct purchaser**, the **reconciliation manager** must **publish half hour profile** shape data for **profiles**; and
- (f) to the **Authority**, the **reconciliation manager** must provide the report prepared by the **reconciliation manager** referred to in clause 10 of Schedule 15.3; and
- (g) to the **extended reserve manager**, the **reconciliation information** applying to each **participant** to enable the **extended reserve manager** to carry out and manage its procurement process.

Clause 28: amended, on 19 January 2017, by clause 17(1) of the Electricity Industry Participation Code Amendment (Extended Reserve) 2016.

Clause 28(c): amended, on 24 March 2015, by clause 27 of the Electricity Industry Participation (Settlement and Prudential Security) Code Amendment 2013.

Clause 28(f): amended, on 19 January 2017, by clause 17(2) of the Electricity Industry Participation Code Amendment (Extended Reserve) 2016.

Clause 28(g): inserted, on 19 January 2017, by clause 17(3) of the Electricity Industry Participation Code Amendment (Extended Reserve) 2016.

## **29 Extended reserve manager use of reconciliation information**

The **extended reserve manager** must not **publish** or otherwise make available any **reconciliation information** provided to it under clause 28 that identifies any **retailer**, **purchaser**, or **generator**.

Clause 29: inserted, on 19 January 2017, by clause 18 of the Electricity Industry Participation Code Amendment (Extended Reserve) 2016.

## Schedule 15.5 Profile administration

cl 15.19

### 1 Contents of this Schedule

This Schedule (including the appendices) contains the requirements for the production of **profiles** that must be used for **electricity** trading if a **metering installation** or **unmetered load** meets the eligibility criteria described in this Schedule.

Compare: Electricity Governance Rules 2003 clause 1 schedule J5

### 2 Departure from requirements

The **Authority** may approve situations that depart from the requirements of this Schedule if it is satisfied that such departure would have minimal adverse effects on each **participant**.

Compare: Electricity Governance Rules 2003 clause 2 schedule J5

Clause 2: amended, on 5 October 2017, by clause 548 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### 3 Load switching

If load switching information is required from the operation log of an external control system, such as a **SCADA** or ripple injection control system, the relevant **reconciliation participant** must ensure that the information, for the immediately preceding **consumption period**, is available by 1600 hours on the 4<sup>th</sup> **business day** of each month.

Compare: Electricity Governance Rules 2003 clause 3.1 schedule J5

### 4 Non metering information

A **reconciliation participant** using a **profile** must ensure that all non-metering **information**, such as external control equipment operation logs, used in the determination of **profile** data, is archived in accordance with clause 18 of Schedule 15.2.

Compare: Electricity Governance Rules 2003 clause 3.2 schedule J5

Clause 4: amended, on 29 August 2013, by clause 35 of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011.

### 5 Profile population

Each **reconciliation participant** who uses a **profile** must keep a current **profile population** list for each month the **profile** is in use. This will form a part of the audit trail of how **profiles** are applied.

Compare: Electricity Governance Rules 2003 clause 3.3 schedule J5

### 6 Details of profile approved for use

- (1) Each **profile owner** must keep a full copy of all of the details of each **profile** approved for use.

- (2) The details must be kept in accordance with clause 18 of Schedule 15.2 for **audit** purposes.

Compare: Electricity Governance Rules 2003 clause 3.4 schedule J5

Clause 6(2): amended, on 29 August 2013, by clause 36 of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011.

## **7 Multiple meter registers**

If a **metering installation** has multiple **meters** or **meters** with multiple registers, a **reconciliation participant** may choose to have each **meter** or **meter** register treated as 1 of the **profiles** described in Appendix 1.

Compare: Electricity Governance Rules 2003 clause 3.5 schedule J5

## **8 New profiles**

Each new **profile** must be developed in accordance with this Schedule.

Compare: Electricity Governance Rules 2003 clause 3.6 schedule J5

## **9 Accuracy of clocks**

External or internal clocks used for switching of **meter** registers must have a time-keeping accuracy of better than 60 seconds per month. The current time indicated by each clock must be checked for accuracy at least once per year, and corrected as necessary.

Compare: Electricity Governance Rules 2003 clause 3.7 schedule J5

## **10 Subtractive metering**

If a **metering installation** includes subtractive metering, each **participant** must derive the appropriate net consumptions.

Compare: Electricity Governance Rules 2003 clause 3.8 schedule J5

## **11 Change of profile**

- (1) A **profile owner** may apply to the **Authority** to change a **profile**.
- (2) An application must contain—
  - (a) the **profile** code for the **profile** to which the proposed change relates; and
  - (b) details of the proposed change.
- (3) The **Authority** must not approve an application unless the **Authority** is satisfied that the requirements in clause 20 (for **NSP** derived **profiles**), and clauses 25 and 27 (for statistically sampled engineered **profiles**), with all necessary modifications, have been met.
- (4) The **Authority** must advise the **profile applicant** if the application has been approved or rejected, or of additional steps that must be completed before the application can be considered, no later than 15 **business days** after receipt of the application.

Compare: Electricity Governance Rules 2003 clause 3A schedule J5

Clause 11: amended, on 5 October 2017, by clause 549 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

## **12 Approved profile classes**

- (1) Approved **profile classes** are described in Appendix 1.
- (2) Each **reconciliation participant** must, with the exception of **profile classes** 1.4 and 1.5, apply to use specific **profiles** within those **profile classes** in accordance with clauses 19 to 34.

Compare: Electricity Governance Rules 2003 clause 4 schedule J5



### 13 Allocation and storage of profile codes

- (1) The **Authority** must determine the **profile** code for an approved **profile** in accordance with this clause.
- (2) **Profile class** 1.4 and 1.5 each have a single approved **profile** code, being—
  - (a) the **profile** code for the single approved **profile** in **profile class** 1.4 is RPS; and
  - (b) the **profile** code for the single approved **profile** in **profile class** 1.5 is UML.
- (3) **Profile class** 2.5 has 2 approved **profile** codes, being—
  - (a) the **profile** code for the approved **profile** in **profile class** 2.5.1 non **half hour** photovoltaic embedded generation, is PV1; and
  - (b) the **profile** code for the approved **profile** in **profile class** 2.5.2 other non **half hour** embedded generation, is EG1.
- (4) **Profile class** 1.7 has a single approved **profile** being, for differenced load, DFP.
- (5) The **Authority** must **publish** the following information for all approved **profiles** in the following format:

**profile** reference: the unique reference under which the **profile** is allocated and stored

**profile class:** refer to Appendix 1

**characteristics:** type(s) of **meter(s)**: A – None  
B – Single register  
C – Multi-register  
type(s) of load(s) D – Controlled  
E – Uncontrolled

**description:** a brief description of the type of **consumer** or **embedded generator** to whom the **profile** applies.

Compare: Electricity Governance Rules 2003 clause 5 schedule J5

Clause 13(1) and (5): amended, on 5 October 2017, by clause 550 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### 14 Calculate residual non half hour profile shapes

The **reconciliation manager** must calculate, **half hour** by **half hour**, a residual **profile** shape for each **balancing area** that must be used to allocate non **half hour submission information** (after adjustment for **losses** and **ICP days**) to **trading periods** in accordance with clauses 15 to 18.

Compare: Electricity Governance Rules 2003 clause 6 schedule J5

### 15 Determine total balancing area load

- (1) This calculation determines the total **electricity** consumption inside a **balancing area** by summing all of the injection into a **balancing area** and subtracting the extraction out of the **balancing area**. In this case, injection is defined as **electricity** entering ( $E_i$ ) the **balancing area** and includes flows from **embedded generators**, or any other **network** (including **embedded networks** or the **grid**). Similarly, extraction is defined as the flows of **electricity** leaving ( $L_i$ ) the **balancing area**, to other **networks**.
- (2) The process in subclause (1) must be carried out for each **trading period** and for each **balancing area** within which there is non **half hour** metered **electricity** to be reconciled by following the procedure below:

$$TOT_{BA} = \underbrace{(E_{GD} + E_{LN} + E_{EN})}_{\text{Sum of energy flow entering the balancing area}} - \underbrace{(L_{GD} + L_{LN} + L_{EN})}_{\text{Sum of energy flow leaving the balancing area}} + \underbrace{(E_{EG})}_{\text{Sum of generation injection entering the balancing area}}$$

where

$TOT_{BA}$	is the total quantity of <b>electricity</b> consumed within the <b>balancing area</b> , measured as being the sum of flows injected into the <b>balancing area</b> less flows out to any <b>embedded network</b> or to another <b>electrically connected network</b>
$E_{GD}$	is the quantity of <b>electricity</b> entering the <b>balancing area</b> , as measured by the <b>grid NSP metering installation</b> for the <b>balancing area</b>
$E_{LN}$	is the quantity of <b>electricity</b> , entering the <b>balancing area</b> through an <b>interconnection point</b> from another <b>network</b> , as measured by the <b>NSP metering installation</b> (which has been adjusted for losses)
$L_{GD}$	is the quantity of <b>electricity</b> leaving the <b>balancing area</b> , as measured by the <b>grid NSP metering installation</b> for the <b>balancing area</b>
$E_{EN}$	is the quantity of <b>electricity</b> entering the <b>balancing area</b> from an <b>embedded network</b> , as measured by the <b>NSP gateway metering installation</b> for the <b>embedded network</b>
$E_{EG}$	is the quantity of <b>electricity</b> entering the <b>balancing area</b> from an <b>embedded generator electrically connected</b> to the <b>network</b> , (which may either be <b>half hour</b> or non <b>half hour</b> metered), as measured by the <b>NSP metering installation</b>
$L_{LN}$	is the quantity of <b>electricity</b> , leaving the <b>balancing area</b> through an <b>interconnection point</b> to another <b>network</b> , as measured by the <b>NSP metering installation</b> (which has been adjusted for losses)
$L_{EN}$	is the quantity of <b>electricity</b> , leaving the <b>balancing area</b> to an <b>embedded network</b> , as measured by the <b>NSP gateway metering installation</b> for the <b>embedded network</b> .

Compare: Electricity Governance Rules 2003 clause 6.1 schedule J5

Clause 15: amended, on 23 February 2015, by clause 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 15(2): amended, on 5 October 2017, by clause 551 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

## 16 Calculate total non half hour shape

- (1) Using the total **balancing area** quantities determined in accordance with clause 15 and the **reconciliation participants' half hour submission information** (that has been

adjusted for **losses** and **ICP days**), the **reconciliation manager** must calculate, for each **trading period**, a total **profile** shape representing the aggregated consumption of all non **half hour** metered **electricity** for each **balancing area** by following the procedure below:

$$\text{NHH}_{\text{Tot}} = \underbrace{\text{TOT}_{\text{BA}} - \text{HHR}_{\text{M}}}$$

Sum of HHR metered  
consumption internal to  
the network area

where

$\text{NHH}_{\text{Tot}}$  is the total quantity of non **half hour** metered **electricity** consumed in a **balancing area** provided that if the calculated quantity is less than 0, the quantity must, for the purposes of this clause, be deemed to be 0

$\text{TOT}_{\text{BA}}$  is the total quantity of **electricity** consumed within the **balancing area**, determined in accordance with clause 15

$\text{HHR}_{\text{M}}$  is the total quantity of consumed **electricity** which is calculated from all **reconciliation participants' half hour submission information** (which has been adjusted for **losses** and **ICP days**).

- (2) The volumes described in subclause (1) must not be **published** and are a process step only.

Compare: Electricity Governance Rules 2003 clause 6.2 schedule J5

## **17 Calculate initial residual profile shape and seasonal adjustment shape**

- (1) Using the resultant  $\text{NHH}_{\text{Tot}}$  quantities from the calculation in clause 16, the **reconciliation manager** must calculate, for each **trading period**, **half hour** by **half hour**, the initial residual **profile** shape for each **balancing area** by following the procedure below:

$$\text{GXP}_{\text{Init}} = \text{NHH}_{\text{Tot}} - (\text{Pr}_{\text{ENG}} + \text{Pr}_{\text{STAT}})$$

Sum of independently  
shaped, non half hour  
profiled consumption  
internal to the network area

where

$\text{GXP}_{\text{Init}}$  is the Initial Residual **Profile**. This is the remaining total quantity of **electricity** for each **half hour** that represents the shape-dependent balance of the non **half hour** consumption within a **balancing area**. This set of values, calculated for each **trading period**, is the initial residual **profile** for each **NSP** within the **balancing area**

$\text{NHH}_{\text{Tot}}$  is as determined in clause 16

$\text{Pr}_{\text{ENG}}$  is the quantity of consumed **electricity** for each **trading period** that is in accordance with the approved engineered **profile**, calculated from the **reconciliation participant submission information** adjusted for **ICP days** and after application of **loss factors**

$\text{Pr}_{\text{STAT}}$  is the quantity of consumed **electricity** for each **trading period** that is in accordance with the approved statistically sampled **profile**, calculated from the **reconciliation participant submission information** adjusted for **ICP days** and after the application of **loss factors**.

- (2) The  $\text{GXP}_{\text{Init}}$  values must be used by the **reconciliation manager** to allocate non **half hour submission information** to **trading periods** for each **reconciliation participant** that uses a **profile** that specifies the use of the initial residual **profile** shape at the **NSP**.
- (3) The **reconciliation manager** must aggregate those **trading period** volumes into daily totals for each **profile** at the **NSP**, and those daily totals must be **published** by the **reconciliation manager** as the **seasonal adjustment shape**.

Compare: Electricity Governance Rules 2003 clause 6.3 schedule J5

Clause 17(2): amended, on 15 May 2014, by clause 69 of the Electricity Industry Participation (Minor Code Amendments) Code Amendment 2014.

## 18 Calculate final residual profile shape

- (1) Using the resultant  $\text{GXP}_{\text{Init}}$  quantity from the calculation in clause 17, the **reconciliation manager** must calculate, for each **trading period**, the final residual **profile** shape for each **balancing area** by following the procedure below:

$$\text{GXP}_{\text{Res}} = \text{GXP}_{\text{Init}} - (\text{PrSh}_1 + \dots + \text{PrSh}_n)$$

Sum of non half hour  
dependently shaped  
profiles internal to network  
area

where

$\text{GXP}_{\text{Res}}$  is the Final Residual **Profile** (which is given the code “RPS”). This is the remaining quantity of **electricity** for each **trading period** that represents the shape dependent balance of the non **half hour** load within a **balancing area**. The monthly file of this consumption, calculated for each **trading period**, is the final residual **profile** for each **NSP** within the **balancing area**

$\text{GXP}_{\text{Init}}$  is as determined in clause 17

$\text{PrSh}_x$  is the quantity of consumed **electricity** for each **trading period** which is in accordance with the approved shape dependent **profile** calculated from the **reconciliation participant** loss and **ICP days** adjusted **submission information**.

- (2) The  $\text{GXP}_{\text{Res}}$  values in subclause (1) must be used by the **reconciliation manager** to allocate non **half hour submission information** to **trading periods** for each **reconciliation participant** who uses a **profile** that specifies the use of the residual **half hour** shape at the **NSP**, for each **trading period** of the **reconciliation period**.

Compare: Electricity Governance Rules 2003 clause 6.4 schedule J5  
Clause 18(2); amended, on 15 May 2014, by clause 70 of the Electricity Industry Participation (Minor Code Amendments) Code Amendment 2014.

#### *New NSP derived profiles*

### **19 Applications**

- (1) An application to introduce a new **NSP** derived **profile** must be submitted to the **Authority**, who must either advise the **profile applicant** of further actions, or must approve or reject the application no later than 15 **business days** after its receipt.
- (2) Each application must contain the following—
- a **profile** description:
  - a suggested **profile** code:
  - a **profile class** in accordance with Appendix 1:
  - the criteria applied by the **profile applicant** to allocate **ICP identifiers** in the **profile**:
  - a description of the methodology for compiling **submission information** and **profile** shapes:

- (f) details of dynamics derived from sources external to the **metering installation** (including without limitation **SCADA** and ripple control) if appropriate.

Compare: Electricity Governance Rules 2003 clause 7.1 schedule J5

Clause 19(1): amended, on 5 October 2017, by clause 552 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

## 20 Assessment

Before approving a **profile**, the **Authority** must be satisfied that—

- (a) there are clear criteria applied by the **reconciliation participant** to allocate **ICP identifiers** in the **profile**; and
- (b) there are no obvious flaws in the methodology for compiling **submission information** and **profile** shapes; and
- (c) the **reconciliation manager** is able to incorporate the **profile** into the reconciliation process; and
- (d) the proposed **profile** is not at variance with existing **profiles** for like populations.

Compare: Electricity Governance Rules 2003 clause 7.2 schedule J5

Clause 20: amended, on 5 October 2017, by clause 553 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

## 21 Ownership

For the purposes of this Schedule, a **profile applicant** must become the **profile owner** once the application is approved. If the **profile applicant** is not a legal entity, a legal entity must be nominated by the **profile applicant** to be the **profile owner**.

Compare: Electricity Governance Rules 2003 clause 7.3 schedule J5

## 22 Withdrawal of applications

If an application is withdrawn by a **profile applicant** at any time following the **declaration date**, but before approval, the **Authority** must advise all **participants**.

Compare: Electricity Governance Rules 2003 clause 7.4 schedule J5

Clause 22: amended, on 5 October 2017, by clause 554 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

## 23 Rejected applications

If an application is rejected, the **Authority** must provide to the **profile applicant** a detailed explanation of why the application was rejected, together with actions required for a reconsideration of the application.

Compare: Electricity Governance Rules 2003 clause 7.5 schedule J5

Clause 23: amended, on 5 October 2017, by clause 555 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

## 24 Use of approved profiles

- (1) A **profile** must not be used for reconciliation until it is approved by the **Authority** in accordance with clauses 19 and 20. The use of a **profile** must be effective from a date decided by the **Authority**, but not earlier than the 1<sup>st</sup> day of the month following the **declaration date**.
- (2) A **reconciliation participant** who wishes to reconcile its **ICP identifiers** using an existing **profile** must first gain the approval of the **profile owner**.

Compare: Electricity Governance Rules 2003 clause 7.6 schedule J5

Clause 24(1): amended, on 5 October 2017, by clause 556 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

*New statistically sampled/engineered profiles*

## 25 Technical requirements

A new **profile** must be based on a process of statistical sampling carried out in accordance with the guidelines contained in the appendices to this Schedule, or derived using recognised engineering principles, or derived from **NSP profiles**.

Compare: Electricity Governance Rules 2003 clause 8.1 schedule J5

## 26 Applications

- (1) An application to introduce a new **profile** must be submitted to the **Authority**, who must either advise the **profile applicant** of further actions, or approve or reject the application in writing no later than 15 **business days** after its receipt. Each application must contain the following:
- (a) a **profile** description:
  - (b) a suggested **profile** code:
  - (c) a **profile class** in accordance with Appendix 1:
  - (d) the size of the **profile population** and a list that uniquely identifies each member of the **profile population**:
  - (e) the criteria applied by the **reconciliation participant** to allocate **ICP identifiers** to the **profile**:
  - (f) a description of the methodology for compiling **submission information** and **profile shapes**:
  - (g) details of dynamics derived from sources external to the **metering installation** (including without limitation **SCADA** and ripple control) if appropriate:
  - (h) details of any **half-hour metering** as a control or source of input data to the **profile**:
  - (i) statistical or engineering data that supports the proposed **profile** shape.
- (2) The **profile applicant** must supply any analytical information relating to the application in the format required by the **Authority**.

Compare: Electricity Governance Rules 2003 clauses 8.2 and 8.2A schedule J5

Clause 26(1) and (2): amended, on 5 October 2017, by clause 557 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

## 27 Assessment

The **Authority** must be satisfied that—

- (a) there are clear criteria applied by the **reconciliation participant** to allocate **profiles** to **ICP identifiers**; and
- (b) there is an audit trail for the allocation of **profiles** to **ICP identifiers**; and
- (c) there are no obvious flaws in the methodology for allocating **profiles** to **ICP identifiers**; and
- (d) the **reconciliation manager** is able to incorporate the **profile** into the reconciliation process; and
- (e) the proposed **profile** is not at variance with existing **profiles** for like populations.

Compare: Electricity Governance Rules 2003 clause 8.3 schedule J5  
Clause 27: amended, on 5 October 2017, by clause 558 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

## 28 Sampling requirements

- (1) Statistical samples must be drawn using the methodology described in Appendix 2. Sampling information must be taken from **fully certified metering installations**. An **interim certified metering installation** must not be used for this purpose.
- (2) For **profiles** that require statistical sampling, the **Authority** must specify the **preliminary sample size** and draw a **preliminary sample** of **ICP identifiers** from the **profile population** list, or must accept appropriate sampling performed by the **profile applicant**. **Half hour** research **meters** must be, or must have been, installed and operated by the **profile applicant** for this **preliminary sample**. The **Authority** must require a minimum sampling period of 60 days, and not more than 12 months. The **Authority** may withdraw **ICP identifiers** from the **profile population** list if it can be shown by the **profile applicant** that those **ICP identifiers** are in sites that are difficult to meter.
- (3) The average **unit cost** and standard deviation of the **unit cost** must be calculated using the 60 days or more of data obtained as described above. If the sample **co-efficient of variation** is less than or equal to the **profile acceptance limit** specified in Appendix 2, the size of the **profile sample** must be the **profile sample size**. The **Authority** must provide a standard set of synthetic price scenarios to determine the variability of **unit costs**.
- (4) If the sample **co-efficient of variation** is more than the **profile acceptance limit**, the **Authority** can reject the application, or can require the **profile applicant** to supply additional information until the **Authority** is satisfied that there is no clear evidence to suggest the population **co-efficient of variation** exceeds the **profile acceptance limit**.
- (5) If the **preliminary sample size** is less than the **profile sample size**, the **Authority** must draw an additional random sample. The size of the additional random sample must equal the shortfall.
- (6) If the **profile sample size** is less than the **preliminary sample size**, the **preliminary sample** must become the **profile sample**.

Compare: Electricity Governance Rules 2003 clause 8.4 schedule J5  
Clause 28(1): amended, on 29 August 2013, by clause 37 of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011.  
Clause 28: amended, on 5 October 2017, by clause 559 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

## 29 Ownership

For the purposes of this Schedule, a **profile applicant** must become the **profile owner** once the application is approved. If the **profile applicant** is not a legal entity, a legal entity must be nominated to be the **profile owner**.

Compare: Electricity Governance Rules 2003 clause 8.5 schedule J5

## 30 Withdrawal of applications

If an application is withdrawn by a **profile applicant** at any time following the **declaration date**, but before approval, the **Authority** must advise all **participants**.



Compare: Electricity Governance Rules 2003 clause 8.6 schedule J5  
Clause 30: amended, on 5 October 2017, by clause 560 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### 31 Rejected applications

- (1) If an application is rejected, the **Authority** must provide the **profile applicant** with a detailed explanation of why the application was rejected, together with actions required for a reconsideration of the application.
- (2) If an application is rejected because the **coefficient of variation** is found to be too large, the **profile applicant** may resubmit the application with a refined **profile population**.
- (3) The refined **profile population** must be a subset of the original population and must be made up of **ICP identifiers** that are more homogenous in their **unit costs** than those in the original **profile population**.
- (4) Data collected from **half-hour metering** in the original preliminary sample may be re-used to constitute the refined **preliminary sample** as long as the data was collected from **ICP identifiers** that belong to the refined **profile population**.
- (5) The **Authority** must determine if additional **ICP identifiers** are required to make up the refined **preliminary sample**.

Compare: Electricity Governance Rules 2003 clause 8.7 schedule J5  
Clause 31(1) and (5): amended, on 5 October 2017, by clause 561 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### 32 Use of approved profiles

- (1) A **profile** must not be used for reconciliation until the **Authority** approves it. The use of a **profile** must be effective from a date decided by the **Authority**, but not earlier than the 1<sup>st</sup> day of the month following the **declaration date**. If an approved **profile** is used for reconciliation, every **ICP identifier** on the **profile population** list must be reconciled under that **profile**.
- (2) A **reconciliation participant** who wishes to reconcile its eligible **ICP identifiers** using an existing **profile** must first gain the approval of the **profile owner**. **ICP identifiers** not already on the **profile population** list must be added to the list before the **profile** can be applied.

Compare: Electricity Governance Rules 2003 clause 8.8 schedule J5  
Clause 32(1): amended, on 5 October 2017, by clause 562 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### 33 Profile maintenance and changes

- (1) The **profile sample** must be representative of the **profile population**. The **profile owner** must be responsible for maintaining a valid statistical sample which takes into account changes in the **profile population**.
- (2) The **profile owner** must maintain a current **profile population** list. The **profile owner** must inform the **Authority** when an update is necessary (refer subclause (3)). The **profile population** list is subject to random **audit** by the **Authority** or its appointed **audit agent**.
- (3) The **profile sample** must be updated when membership of the **profile population** has changed by more than 20% since the **sample date**. The **profile owner** must, no later than 10 **business days** after the **profile owner** becomes aware of such change in

membership, give written notice to the **Authority** of the changes in the **profile population** list. The **Authority** must determine, and give written notice to the **profile owner** of, any required modifications to the **profile sample**. The **profile owner** has 1 month from the date on which the **profile owner** receives the notice from the **Authority** to ensure that **certified half hour meters** are installed in the **metering installations** of these **ICP identifiers**, and that the **metering installations** are fully **certified**.

- (4) If more than 5% of the **profile sample** has been lost or removed, the **profile owner** must submit to the **Authority** a list of **ICP identifiers** in the current **profile sample** who have been lost or removed from the **profile population** list. The **Authority** must draw **ICP identifiers** from the **profile population** list to replace those who are lost or removed from the **profile sample**. The **profile owner** must ensure that **certified half hour meters** are installed in the **metering installations** of these **ICP identifiers**, and that the **metering installations** are fully **certified**, no later than 1 month after the **Authority** issues its determination of the appropriate replacement **ICP identifiers**.
- (5) The addition or removal of **ICP identifiers** to or from the **profile sample** must follow the procedures in Appendix 2.
- (6) There must be at least 3 months between updates.

Compare: Electricity Governance Rules 2003 clauses 8.9.1 and 8.9.2 schedule J5  
Clause 33(2) to (4): amended, on 5 October 2017, by clause 563 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### 34 Exceptions to sampling methodology

The **Authority** may allow different sampling methodologies that are not described in this Schedule, only if—

- (a) the methodology can, in the **Authority's** assessment, produce sample data that meets the precision standards specified under Appendix 2; and
- (b) the **Authority** or its **audit** agent is satisfied that the methodology can be **audited** to the same degree of rigour as the sampling methodology outlined in Appendix 2; and
- (c) following the **declaration date** but before approval, details of the shape of the proposed **profile** must be provided by the **profile owner** on a monthly basis to all **participants** trading on the affected **NSP(s)**. Use of such **profile** information is subject to clause 32. Following approval, such details must be provided to all **participants** by the **reconciliation manager**.

Compare: Electricity Governance Rules 2003 clause 8.9.3 schedule J5  
Clause 34: amended, on 5 October 2017, by clause 564 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### 35 Audits

- (1) A **participant** may request the selective **audit** of any **participant's** compliance with this Schedule or the **participant's** application and use of any **profile**.
- (2) The **Authority** or its agent must **audit** the application of all **profiles** in a random order at least once every 2 years by applying a selection process that the **Authority** determines.
- (3) As a minimum, a **profile audit** must cover the following:
  - (a) the documents detailing the methodology of the **profile**:

- (b) the application of dynamic and estimated elements of the **profile**;
- (c) the **profile population** list.

Compare: Electricity Governance Rules 2003 clause 9 schedule J5

Clause 35(2): replaced, on 5 October 2017, by clause 565 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### 36 Reviews

- (1) The **Authority** must review the structure of every approved **profile** at least every 3 years.
- (2) Each review must determine whether—
  - (a) the criteria for **profile** definition are still appropriate; and
  - (b) if applicable, the existing sample needs to be redrawn.

Compare: Electricity Governance Rules 2003 clause 10 schedule J5

Clause 36(1): amended, on 5 October 2017, by clause 566 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### 37 Removal of profiles

- (1) The **Authority** must immediately remove a **profile** that fails an **audit** from the list of approved **profiles** held by the **Authority**.
- (2) A **participant** who includes in a **profile** an **ICP identifier** that is not of the classification contained in the **profile** documentation breaches this Code. All alleged breaches must be reported to the **Authority** and resolved in accordance with the **Act**.
- (3) The **Authority** may remove a **profile**—
  - (a) at the request of the **profile owner** that introduced the **profile**; or
  - (b) for such other reasons that the **Authority** decides.
- (4) A **profile owner** that makes a request to the **Authority** under subclause (3)(a) must—
  - (a) make the request in writing; and
  - (b) request the **profile's** removal be effective from the start of the **reconciliation period** immediately following the date on which the **Authority** receives the request.
- (5) If the **Authority** removes a **profile**, the **Authority** must decide on the actions to be taken with respect to the **ICP identifiers** to which the **profile** applied.

Compare: Electricity Governance Rules 2003 clause 11 schedule J5

Clause 37(1): amended, on 5 October 2017, by clause 567(a) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 37(3) to (5): replaced, on 5 October 2017, by clause 567(b) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

## Appendix 1 Profile classes

### 1 Contents of this Appendix

This Appendix contains generic descriptions of **metering installations** to which particular **profile classes** may be assigned.

Compare: Electricity Governance Rules 2003 appendix 1 schedule J5

#### *Participants NSP-derived profiles*

### 2 Profile class 1.1 interval time of use meters

- (1) **Meters** in the **profile class 1.1** – interval time of use meter classification include the following:

- (a) day-night two rate **meters**:
- (b) night only **meters**:
- (c) night only plus afternoon boost **meters**:
- (d) 5 rate time of use **meters**.

- (2) If register-switching is triggered by an external signal, such as a ripple relay, rather than by the **meter's** internal clock, data from the operation log of the equipment controlling the external signal must be used to provide the **profile** time period.

Compare: Electricity Governance Rules 2003 clause 1.1 appendix 1 schedule J5

### 3 Profile class 1.2 separately metered controlled load

- (1) **Meters** in the **profile class 1.2** separately metered controlled load classification include a separate **meter** for a ripple controlled water heater, which may be switched on and off at variable times of the day. The entire load recorded on this register must be available for control.
- (2) Information from the operation logs of equipment controlling the connection of controllable loads must be used to determine the time period relating to them. If the controllable load component is not static, a calculation of the diversity of the load must be documented and applied.
- (3) Other **meters** in the **metering installation** must be applied as per **profile class 1.1** or 1.4, as appropriate.

Compare: Electricity Governance Rules 2003 clause 1.2 appendix 1 schedule J5

Clause 3(2): amended, on 23 February 2015, by clause 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

Clause 3(2): amended, on 5 October 2017, by clause 568 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### 4 Profile class 1.3 non separately metered controlled load

- (1) Installations in the **profile class 1.3** classification non separately metered controlled load include a ripple controlled water heater but with only 1 **meter** measuring the whole installation including the water heater.

- (2) The controlled load may be switched on and off at variable times of the day. In this case a proportion of the **profile** (kWh) must be applied as per **profile class 1.2** with the remaining kWh applied as per **profile class 1.1** or **1.4**, as appropriate.

Compare: Electricity Governance Rules 2003 clause 1.3 appendix 1 schedule J5

## **5 Profile class 1.4 uncontrolled load 24 hour meters**

- (1) The **profile** from **meters** in the **profile class 1.4 uncontrolled load 24 hour meters** must follow the **NSP residual profile**.
- (2) The **NSP residual profile** must be calculated in accordance with clauses 14 to 18 of Schedule 15.5.

Compare: Electricity Governance Rules 2003 clause 1.4 appendix 1 schedule J5

## **6 Profile class 1.5 unmetered loads**

- (1) **Unmetered loads** in the **profile class 1.5** classification include, but are not limited to, under veranda lighting, electric fences, sewer pumps, advertising hoardings, public conveniences, supply to construction sites, electric parking meters, and public water fountains.
- (2) For those types of **unmetered load**, a fixed annual kWh quantity must be assigned to each **ICP** and must be applied according to the 24 hour **NSP final residual profile**.

Compare: Electricity Governance Rules 2003 clause 1.5 appendix 1 schedule J5

## **7 Profile class 1.7 differenced load**

**Profile class 1.7 differenced load** represents the result of subtractive processes performed by the **reconciliation manager** to form differenced load.

Compare: Electricity Governance Rules 2003 clause 1.7 appendix 1 schedule J5

### *Statistically sampled and engineering profile classes*

## **8 Profile class 2.1 unmetered loads**

- (1) **Profiles** may be applied to intended loads with characteristics that are reasonably predictable using time and other observable values.
- (2) The elements making up each load and time period must be documented by the **profile owner**.
- (3) The documentation must include a description of the methodology, formula, and the results of any calculations for any estimated data.

Compare: Electricity Governance Rules 2003 clause 2.1 appendix 1 schedule J5

## **9 Profile class 2.2 half hour data, metering installations with interim certification**

- (1) **Half hour data from interim certified metering installations** may be—
- (a) regarded as a 100% sampled **profile** until the expiry of the interim exemption validity period for those **metering installations** under Part 10. From that date, if the **metering installation** has not been **recertified** as a fully **certified metering installation** under Part 10, the **metering installation** must be assigned to **profile class 1.4**; or

- (b) treated as if it was derived from **fully certified metering installations** until the expiry of the interim exemption validity period for those **metering installations**. To avoid doubt, the **half hour** data must be derived from an **interrogation** of the **metering installation** and must be submitted to the **reconciliation manager** in accordance with Schedule 15.4.
- (2) For a 100% sampled **profile**, a method of calculating **forward estimates** must be adopted in accordance with clauses 2 to 7 of Schedule 15.3. A **profile** shape for the **reconciliation period** must be submitted to the **reconciliation manager** with the estimated data.
- (3) If the gathering, validation and repair of **volume information** from an **interim certified metering installation** is carried out in a manner that is not in accordance with Schedule 15.2, these processes must be fully documented in the quality procedures of the **participant**.

Compare: Electricity Governance Rules 2003 clause 2.2 appendix 1 schedule J5

Clause 9(1): amended, on 29 August 2013, by clause 38(a) of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011.

Clause 9(1)(a): amended, on 29 August 2013, by clause 38(b) and (c) of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011.

Clause 9(1)(b): amended, on 29 August 2013, by clause 38(d), (e) and (f) of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011.

Clause 9(3): amended, on 29 August 2013, by clause 38(g) of the Electricity Industry Participation (Metering Arrangements) Code Amendment 2011.

## **10 Profile class 2.3 unmetered installations that require shape file to be submitted**

- (1) A **profile** may be applied to an intended load with characteristics that are reasonably predictable using time and other observable values.
- (2) For those types of **unmetered load**, the **profile** must include a process for maintaining **unmetered load** quantities that are used in the reconciliation process. The shape file will be produced by the **profile owner** from a **metering installation**.
- (3) The elements making up each load and time period must be documented by the **profile owner**. The documentation must include a description of the methodology, formula, and the results of any calculations for any estimated data.

Compare: Electricity Governance Rules 2003 clause 2.3 appendix 1 schedule J5

## **11 Profile class 2.4 metered installations that require shape file**

- (1) A **profile** may be applied to an intended load with characteristics that are reasonably predictable using time and other observable values.
- (2) For those types of metered load, a **metering installation** must be used to determine the quantity of **electricity** for reconciliation purposes.
- (3) The elements making up each load and time period must be documented by the **profile owner**. The documentation must include a description of the methodology, formula, and the results of any calculations for any estimated data.

Compare: Electricity Governance Rules 2003 clause 2.4 appendix 1 schedule J5

## **12 Profile class 2.5, non half hour embedded generation**

- (1) The **Authority** must—
  - (a) determine how each of the 2 types of non **half hour embedded generator profiles** under subclause (2) applies and operates; and

- (b) having made its determination under paragraph (a), submit each non **half hour embedded generator profile** to the **reconciliation manager**.
- (2) The 2 types of **non half hour embedded generator profiles** are:
  - (a) the photovoltaic is a time limited **profile** and may only be used for photovoltaic generation that injects **electricity** into the **network** during daylight hours; and
  - (b) the other **profile** is a non limited flat load **profile** and must be used for all other embedded generation that does not fit within the **profile** in paragraph (a) or if the **reconciliation participant** has not created an engineered **profile** for the **embedded generator**.

Compare: Electricity Governance Rules 2003 clause 2.5 appendix 1 schedule J5  
Clause 12(1): replaced, on 5 October 2017, by clause 569 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

## Appendix 2

### Determining statistically sampled profiles

#### 1 Basic sampling scheme

The method of simple random sampling without replacement must be used in drawing statistical samples whenever such samples are required for **profiles** under this Code.

Compare: Electricity Governance Rules 2003 clause 1 appendix 3 schedule J5

#### 2 Preliminary sample

- (1) Unless the **profile applicant** has better information available that is acceptable to the **Authority**, the size of the **preliminary sample** must be determined by the following **preliminary sample size** formula:

$$n_1 = (z_{\alpha}^2 \times C_A^2) / r^2$$

- (2) If  $n_1/N$  is greater than 0.1, it must be modified to account for the finite population correction factor and is calculated as—

$$n_1' = n_1 / (1 + n_1/N)$$

- (3) If either  $n_1$  or  $n_1'$  is less than 20, the **preliminary sample size** must be 20.  
(4) In the above formula—

$N$  is the size of the **profile population**

$\alpha$  is the confidence level

$z_{\alpha}$  is the value of the standard normal distribution which gives  $\alpha$  probability outside the tails

$C_A$  is the value of **co-efficient of variation** of the **unit cost**

$r$  is the **relative standard error** of the **unit cost**.

- (5) The following parameter values are to be used:

Value of **co-efficient of variation** ( $C_A$ ): 0.1

**Relative standard error** ( $r$ ): 0.05

Confidence level ( $\alpha$ ): 0.99

- (6) The **profile acceptance limit** must be 0.2.  
(7) These values must be subject to review in accordance with clause 5.  
(8) The **profile applicant** must collect **half hour** data from the **preliminary sample** over a period of at least 60 days. The data, in its processed form, must be submitted to the



**Authority** for consideration. The data processing must include calculations of **unit costs**, and of mean and standard deviation of **unit costs**, over the sample period.

Compare: Electricity Governance Rules 2003 clause 2 appendix 3 schedule J5

Clause 2: amended, on 5 October 2017, by clause 570 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### 3 Profile sample

- (1) The size of the **profile sample** must be determined by the following **profile sample size** formula:

$$n = (S_0^2/Y_0^2) \times (z_\alpha^2/r^2) \times \{1 + 8 \times (r^2/z_\alpha^2) \times [S_0^2/(n_1 \times Y_0^2)] + 2/n_1\}$$

- (2) If  $n/N$  is greater than 0.1, it must be modified to account for the finite **profile population** correction factor and is calculated as—

$$n' = n/(1+n/N)$$

- (3) If either  $n$  or  $n'$  is less than  $n_1$ , the **preliminary sample** must become the **profile sample**.  
(4) In the above formula—

$S_0$  is the estimated standard deviation of **unit costs** from the **preliminary sample**, or from the existing **profile sample** in the case of updates

$Y_0$  is the estimated mean of **unit costs** from the **preliminary sample**, or from the existing **profile sample** in the case of updates

$\alpha$  is the confidence level

$z_\alpha$  is the value of the standard normal distribution which gives  $\alpha$  probability outside the tails

$n_1$  is the size of the **preliminary sample**, or the existing **profile sample** in the case of updates

$r$  is the **relative standard error** of the **unit cost**.

- (5) The **relative standard error** ( $r$ ) and the confidence level ( $\alpha$ ) must be the same as those specified in clause 2.  
(6) If the size of the **profile sample** is larger than the size of the **preliminary sample**, additional **ICP identifiers** from the **profile population** must be drawn to increase the sample size to the required level.  
(7) Data from the **profile sample** must be used to form the basis for future updates.

Compare: Electricity Governance Rules 2003 clause 3 appendix 3 schedule J5

#### 4 Sample updates

- (1) If an update is required because of a change in the **profile population**, the following procedures must be followed:
  - (a) if the size of the updated **profile sample** is larger than the size of the existing **profile sample**, additional **ICP identifiers** must be drawn from new **participants** of the **profile population** to increase the sample size to the required level:
  - (b) if the size of the updated **profile sample** is smaller than the size of the existing **profile sample**, **ICP identifiers** from the existing **profile sample** must be removed to decrease the sample size to the required level, unless the **profile applicant** decides to nominate the existing **profile sample** as the **profile sample**.
- (2) For the purposes of updates, data from the existing **profile sample** must be used (instead of data from the **preliminary sample**) in all **profile sample size** calculations.

Compare: Electricity Governance Rules 2003 clause 4 appendix 3 schedule J5

#### 5 Reviews

- (1) The statistical parameters must be monitored by the **Authority** and reviewed when the **Authority** considers it appropriate. Modifications of those parameters are expected as the industry gains experience in the use of statistical **profiles**. Industry **participants** will be consulted as part of the review process.
- (2) Each year the **Authority** must review data gathered during the year for each **profile sample**, and must re-examine the **co-efficient of variation** and the sample size. A **relative standard error** of 5% and a confidence level of 99% must be applied initially. A figure of 2% for the **relative standard error** is expected to be adopted by the **Authority** following the first 12-monthly review and may thereafter be reviewed from time to time.
- (3) Reviews of existing standards must take place in the 6<sup>th</sup> month and the 12<sup>th</sup> month during the 1<sup>st</sup> year of **profile** introduction.

Compare: Electricity Governance Rules 2003 clause 5 appendix 3 schedule J5

Clause 5(1) and (2): amended, on 5 October 2017, by clause 571 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

# **Electricity Industry Participation Code 2010**

## **Part 16**

### **Special provisions relating to Rio Tinto agreements**

*[Revoked]*

Part 16: revoked, on 16 December 2013, by clause 10 of the Electricity Industry Participation (Revocation of Part 16) Code Amendment 2013

---

# Electricity Industry Participation Code 2010

## Part 16A Audits

### Contents

16A.1	Contents of this Part
16A.2	Purpose of this Part
	Subpart 1—Conduct of audits generally
16A.3	Auditors
16A.4	Participants to give access
16A.5	Approval of auditors by the Authority
16A.6	Expiry and cancellation of approval
16A.7	Requirement to appoint new auditor
16A.8	Combined audits
16A.9	Authority may specify emphasis or scope of audit
16A.10	Agent audits
16A.11	Audit required if participant makes material change
16A.12	Process for completion of audits
16A.13	Participants to give final audit report and compliance plan to the Authority
16A.14	Authority to make determination as to next audit date
16A.15	Authority to publish information
16A.16	Costs of audits
	Subpart 2—Metering equipment provider audits
16A.17	Time frame for metering equipment provider audits
16A.18	Additional requirements for metering equipment provider audits
	Subpart 3—ATH audits
16A.19	Time frame for ATH audits
16A.20	Additional requirements for class B ATH audits
16A.21	Incorporation of NZ/AS ISO 17025 by reference
	Subpart 4—Distributor audits
16A.22	Time frame for distributor audits
16A.23	Additional requirements for distributor audits
	Subpart 5—Reconciliation participant audits
16A.24	Time frame for reconciliation participant audits
	Subpart 6—Dispatchable load purchaser audits
16A.25	Time frame for dispatchable load purchaser audits
	Subpart 7—Distributed unmetered load audits
16A.26	Time frame for distributed unmetered load audits

---

#### 16A.1 Contents of this Part

This Part specifies obligations on participants that perform functions under Parts 10, 11, and 15 in respect of audits required under the following clauses:

- (a) 10.17A (Metering equipment providers and ATHs to arrange for regular audits):
- (b) 10.17B (Authority and participant requested audits):
- (c) 11.8B (Metering equipment providers to arrange for regular audits):

- 
- (d) 11.10 (Distributors to arrange for regular audits):
  - (e) 11.11 (Authority and participant requested audits):
  - (f) 15.37A (Reconciliation participants and dispatchable load purchasers to arrange for regular audits):
  - (g) 15.37B (Retailers to arrange for audits in respect of distributed unmetered load):
  - (h) 15.37C (Authority and participant requested audits).

### 16A.2 Purpose of this Part

The purpose of this Part is to require the performance of **audits** to support the accurate settlement and operation of the wholesale **electricity** market.

## Subpart 1—Conduct of audits generally

### 16A.3 Auditors

- (1) An **audit** must be undertaken by—
  - (a) the **Authority**; or
  - (b) an **auditor** appointed by the **participant** that is the subject of the proposed **audit**, from the list of **auditors** the **Authority publishes** under clause 16A.5(6).
- (2) Despite subclause (1)(b), if an **audit** is carried out under clause 10.17B, 11.11, or 15.37C,—
  - (a) the **Authority** must carry out the **audit** or appoint an **auditor** to carry out the **audit**; and
  - (b) an **auditor** appointed by the **Authority** need not be an **auditor** from the list of **auditors** the **Authority publishes** under clause 16A.5(6).

Clause 16A.3(1)(b) and (2)(b): amended, on 5 October 2017, by clause 572 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### 16A.4 Participants to give access

- (1) A **participant** must give the **Authority** or an **auditor** full access to all information that may be required for the purposes of carrying out an **audit**.
- (2) The **participant** must provide the information—
  - (a) at no charge; and
  - (b) no later than 15 **business days** after receiving a request for the information from the **Authority** or an **auditor**, as the case may be.

### 16A.5 Approval of auditors by the Authority

- (1) The **Authority**—
  - (a) may approve a person to be an **auditor**; and
  - (b) must specify the types of **audits** for which each such person is approved.
- (2) An applicant for approval as an **auditor**, or renewal of an existing approval, must apply to the **Authority** using the **prescribed form**.
- (3) The **Authority** may require an applicant to do any or all of the following:
  - (a) provide additional information or clarify any information provided;
  - (b) attend an interview;
  - (c) undertake an examination.
- (4) The **Authority** must, no later than 2 months after receiving an application and, if applicable, the applicant has complied with subclause (3)—
  - (a) make a decision in relation to the application; and
  - (b) advise the applicant of the decision.

- 
- (5) If the **Authority** approves an application, the **Authority** must specify the date on which the approval expires in its advice to the applicant under subclause (4)(b), which must not be more than 36 months after the date of the approval.
  - (6) The **Authority** must **publish**, and keep updated, a list of the **auditors** that the **Authority** has approved, and the types of **audits** for which each **auditor** is approved.

Clause 16A.5(6): amended, on 5 October 2017, by clause 573 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

#### **16A.6 Expiry and cancellation of approval**

- (1) An **auditor's** approval expires on the date specified for its expiry under clause 16A.5(5).
- (2) The **Authority** may cancel an **auditor's** approval at any time by advising the **auditor** in writing.
- (3) The cancellation or expiry of an **auditor's** approval does not invalidate an **audit** previously completed by the **auditor**, but an **audit** completed after the date on which the **Authority** cancelled the **auditor's** approval, or after the date on which the **auditor's** approval expired, is not a valid **audit** for the purposes of this Code.

#### **16A.7 Requirement to appoint new auditor**

- (1) Unless otherwise agreed with the **Authority**, a **participant** must appoint a new **auditor** to perform a type of **audit** at the later of—
  - (a) 24 months after an **auditor** first performs an **audit** of that type in respect of the **participant**; or
  - (b) after an **auditor** has performed 2 consecutive **audits** of that type in respect of the **participant**.
- (2) A new **auditor** is an **auditor** that did not perform the last **audit** of the relevant type in respect of the **participant**.
- (3) For the purposes of subclause (1),—
  - (a) an **audit** completed under clause 16A.11 must be disregarded in determining the number of **audits** that an **auditor** has performed; and
  - (b) a type of **audit** refers to an **audit** under any 1 of paragraphs (a), (c), (d), (f) or (g) of clause 16A.1.

#### **16A.8 Combined audits**

- (1) A **participant** that is required to carry out an **audit** in accordance with this Part under more than 1 clause of this Code must arrange for a single **audit** report to be completed in respect of all of its obligations that relate to its role as a single type of industry **participant** or industry service provider.
- (2) A **participant** that is required to carry out an **audit** in accordance with this Part in relation to more than 1 of its roles as an industry **participant** or industry service provider must arrange for a separate **audit** report to be completed in respect of its obligations for each of those roles.
- (3) For example, a **participant** that is both a **metering equipment provider** and a **reconciliation participant**—
  - (a) must arrange for a single **audit** report to be completed that relates to all of its obligations as a **metering equipment provider**; and
  - (b) must arrange for a separate **audit** report to be completed that relates to its obligations as a **reconciliation participant**.

- 
- (4) Despite subclauses (1) and (2), a **retailer** that is responsible for **distributed unmetered load** must ensure that a separate **audit** report is completed in respect of the **distributed unmetered load** from any other **audit** report required under this Code.

#### **16A.9 Authority may specify emphasis or scope of audit**

- (1) If the **Authority** advises a **participant** that it requires an **audit** to give emphasis to any aspect of the **participant's** systems or processes, the **participant** must instruct the **auditor** to give emphasis to that aspect in the **audit** report.
- (2) If an **audit** is carried out under clause 10.17B, 11.11, or 15.37C, the **Authority** may specify the scope of the **audit**.
- (3) If the **Authority** advises a **participant** under subclause (1), or specifies the scope of an **audit** under subclause (2), the **Authority** must give the **participant** concerned its reasons for doing so.

#### **16A.10 Agent audits**

If a **participant** appoints an agent to perform any of the **participant's** obligations under this Code in respect of which an **audit** is required under any of the clauses specified in clause 16A.1, the **participant** must ensure that—

- (a) the agent has been **audited** to a standard that would have been required if the **participant** had performed the obligations itself; and
- (b) the information produced as a result of the **audit** of the agent is included in the **auditor's audit** report produced under clause 16A.12.

Clause 16A.10: amended, on 5 October 2017, by clause 574 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

#### **16A.11 Audit required if participant makes material change**

- (1) If there is a material change to any of a **participant's** systems or processes that are the subject of regular **audits** under clause 10.17A, 11.8B, 11.10, 15.37A or 15.37B, the **participant** must arrange for an additional **audit**, which must be completed in accordance with this Part no later than 5 **business days** before the change is implemented.
- (2) For the purposes of subclause (1), a material change to a system or process is a change that is likely to affect the ability of the **participant** to comply with any relevant provision of this Code.

#### **16A.12 Process for completion of audits**

- (1) Subject to subclause (2), a **participant** that is the subject of an **audit** must ensure that the **auditor** carrying out the **audit** complies with the following requirements:
- (a) the **audit** report must be in the **prescribed form**;
- (b) the **auditor** must send a draft of the **audit** report, setting out the provisional findings of the **audit**, to the **participant** that is the subject of the **audit**;
- (c) the **auditor** must consider any comments it receives from the **participant** about the draft **audit** report;
- (d) the **auditor** must produce a final **audit** report and give the report to the **participant** after considering any comments under paragraph (c);
- (e) the final **audit** report must—

- 
- (i) list each agent engaged by the **participant** to perform any of the **participant's** activities under the relevant provisions of this Code, and details of the obligations that the agent performs; and
  - (ii) identify, in relation to the relevant period, the extent to which the **participant** has failed to comply with the provisions of this Code to which the **audit** relates; and
  - (iii) identify any areas for improvement; and
  - (iv) specify any conditions that the **auditor** considers the **participant** must satisfy in order to comply with the provisions of this Code to which the **audit** relates, and any action that the **participant** has taken in respect of those conditions; and
  - (v) include a recommendation as to the date by which the **auditor** considers that the **participant** should complete its next **audit**; and
  - (vi) include any of the **participant's** comments on the draft **audit** report that the **auditor** considers relevant.
- (2) If the **Authority** carries out the **audit**, or appoints an **auditor** to carry out the **audit**, the **Authority** must ensure that the requirements specified in subclause (1) are complied with.

**16A.13 Participants to give final audit report and compliance plan to the Authority**

- (1) A **participant** must give the final **audit** report to the **Authority** no later than the date by which the **audit** is due to be completed.
- (2) Each **participant** must submit a compliance plan to the **Authority** when it gives a final **audit** report to the **Authority** under subclause (1).
- (3) Each compliance plan and **audit** report must be in the **prescribed form**.
- (4) Each compliance plan must specify—
  - (a) the actions that the **participant** intends to take to address any breaches or potential breaches of this Code identified in the **audit** report; and
  - (b) the time frames within which the **participant** intends to complete those actions.
- (5) Subclause (2) does not apply if the relevant **audit** report in relation to a **participant** identifies no breaches or potential breaches of this Code.

**16A.14 Authority to make determination as to next audit date**

- (1) The **Authority** must, after receiving a final **audit** report and compliance plan (if any) from a **participant**, advise the **participant** of the date by which the next **audit** of the **participant** must be completed, which must be—
  - (a) no earlier than 3 months after the date on which the **Authority** advises the **participant** under this subclause; and
  - (b) no later than 36 months after the date of the last **audit**.
- (2) For the purposes of subclause (1) and clauses 16A.17, 16A.19, 16A.22, 16A.24, 16A.25, and 16A.26, an **audit** is complete when the **participant** that is the subject of the **audit** gives the **Authority** the final **audit** report and a compliance plan (if any) under clause 16A.13.
- (3) This clause does not apply to **audits** carried out under clause 10.17B, 11.11, 15.37C, or 16A.11.

**16A.15 Authority to publish information**

- (1) The **Authority** must **publish** the following information:
  - (a) each final **audit** report received under clause 16A.13:
  - (b) the compliance plan (if any) that the relevant **participant** submitted in relation to each final **audit** report:



- 
- (c) the date by which the next **audit** of the **participant** must be completed, as determined under clause 16A.14.
  - (2) The **Authority** must **publish** the information no later than 20 **business days** after advising the relevant **participant** of the date by which the next **audit** of the **participant** must be completed under clause 16A.14.
  - (3) The **Authority** is not required to **publish** the information if doing so—
    - (a) would disclose a trade secret; or
    - (b) would be likely unreasonably to prejudice the commercial position of the person who supplied or is the subject of the information.

Clause 16A.15 Heading: amended, on 5 October 2017, by clause 575(1) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

Clause 16A.15(1), (2) and (3): amended, on 5 October 2017, by clause 575(2) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### 16A.16 Costs of audits

- (1) The cost of an **audit** carried out under clause 10.17A, 11.8B, 11.10, 15.37A, 15.37B, or 16A.11 must be met by the **participant** that is the subject of the **audit**.
- (2) The cost of an **audit** carried out under clause 10.17B, 11.11, or 15.37C must be met in accordance with subclauses (3) to (5).
- (3) If an **audit** establishes that the **participant** that was the subject of the **audit** has breached the relevant provisions of this Code, the cost of the **audit** must be met by,—
  - (a) in respect of an **audit** carried out as a result of the **Authority** initiating the **audit**, the **participant** that was the subject of the **audit** and the **Authority**, in proportions to be determined by the **Authority**;
  - (b) in respect of an **audit** carried out in response to a request to the **Authority** under clause 10.17B(2), 11.11(2), or 15.37C(2), the **participant** that was the subject of the **audit** and the **participant** that requested the **audit**, in proportions to be determined by the **Authority**.
- (4) If the **audit** establishes that the **participant** that was the subject of the **audit** has not breached the relevant provisions of this Code, or if there was a breach but the **Authority** considers it to be minor, the cost of the **audit** must be met by,—
  - (a) in respect of an **audit** carried out as a result of the **Authority** initiating the **audit**, the **Authority**;
  - (b) in respect of an **audit** carried out in response to a request to the **Authority** under clause 10.17B(2), 11.11(2), or 15.37C(2), the **participant** that was the subject of the **audit** and the **participant** that requested the **audit**, in proportions to be determined by the **Authority**.
- (5) The costs under subclauses (3) and (4)(b) must be paid by the **participants** no later than 10 **business days** after being advised of the amount owing.

## Subpart 2—Metering equipment provider audits

### 16A.17 Time frame for metering equipment provider audits

In relation to **audits** required under clauses 10.17A and 11.8B, a **metering equipment provider** must ensure that—

- (a) an initial **audit** is completed no later than 3 months after the date on which the **metering equipment provider's** obligations under Part 10 commence in accordance with clause 10.19; and

- (b) further **audits** are completed as specified by the **Authority** under clause 16A.14.

#### **16A.18 Additional requirements for metering equipment provider audits**

In addition to the requirements specified in clauses 16A.3 to 16A.16, a **metering equipment provider** must ensure that an **auditor** carrying out an **audit** required under clause 10.17A or 11.8B **audits**—

- (a) the management and maintenance of each **metering installation** for which the **metering equipment provider** is responsible, including—
  - (i) maintenance of **metering records**; and
  - (ii) maintenance of **metering components**; and
  - (iii) **certification** of **metering components** and **metering installations**; and
  - (iv) **metering installations** that have been **certified** at a lower category under clause 6 of Schedule 10.7; and
  - (v) inspections of **metering installations** in accordance with this Code; and
  - (vi) investigations under clause 10.43(4); and
- (b) the **metering equipment provider's**—
  - (i) provision of **metering records** to the **registry manager** and the maintenance of that information in the **registry**; and
  - (ii) provision of **metering records** to the **reconciliation manager**; and
- (c) the **metering equipment provider's** provision of access under Part 10 to—
  - (i) **raw meter data**;
  - (ii) **metering records**;
  - (iii) the **metering installation**; and
- (d) the security of—
  - (i) each **metering installation** for which the **metering equipment provider** is responsible; and
  - (ii) if relevant, the **metering equipment provider's back office**; and
  - (iii) if relevant, the **communication** between the **metering equipment provider's back office** and the **metering installation**.

Clause 16A.18(b): replaced, on 5 October 2017, by clause 576 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### **Subpart 3—ATH audits**

#### **16A.19 Time frame for ATH audits**

In relation to **audits** required under clause 10.17A, an **ATH** (or an applicant for approval as an **ATH**) must ensure that—

- (a) an initial **audit** is completed no later than 2 months before the date on which the **ATH** (or the applicant for approval as an **ATH**) intends to be approved as an **ATH** under clause 1 of Schedule 10.3; and
- (b) further **audits** are completed as specified by the **Authority** under clause 16A.14.

#### **16A.20 Additional requirements for class B ATH audits**

In addition to the requirements specified in clauses 16A.3 to 16A.16, a **class B ATH** (or an applicant for approval as a **class B ATH**) must ensure that the **auditor** carrying out an **audit** **audits** the **class B ATH** (or the applicant) in respect of the requirements of NZ/AS ISO 17025

for **calibration** that apply to the performance of the functions for which the **class B ATH** (or the applicant) is being **audited**.

#### **16A.21 Incorporation of NZ/AS ISO 17025 by reference**

- (1) The New Zealand Standard NZ/AS ISO 17025 is incorporated by reference in this Code in accordance with section 32 of the **Act**.
- (2) Subclause (1) is subject to Schedule 1 of the **Act**, which includes a requirement that the **Authority** must give notice in the *Gazette* before an amended or substituted NZ/AS ISO 17025 becomes incorporated by reference in this Code.

### Subpart 4—Distributor audits

#### **16A.22 Time frame for distributor audits**

In relation to **audits** required under clause 11.10, a **distributor** must ensure that—

- (a) an initial **audit** is completed no later than 3 months after the date on which the **distributor** has the first **NSP identifier** or **ICP identifier** recorded in the **registry** as being part of the **distributor's network**; and
- (b) further **audits** are completed as specified by the **Authority** under clause 16A.14.

Clause 16A.22(a): amended, on 5 October 2017, by clause 577 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

#### **16A.23 Additional requirements for distributor audits**

In addition to the requirements specified in clauses 16A.3 to 16A.16, a **distributor** must ensure that the **auditor** carrying out an **audit** audits the **distributor's** processes and procedures in relation to—

- (a) the creation of **ICP identifiers** for **ICPs**; and
- (b) the provision of **ICP** information to the **registry manager** and the maintenance of that information in the **registry**; and
- (c) the creation and maintenance of **loss factors**.

Clause 16A.23(b): amended, on 5 October 2017, by clause 5778(a) and (b) of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### Subpart 5—Reconciliation participant audits

#### **16A.24 Time frame for reconciliation participant audits**

In relation to **audits** required under clause 15.37A, a **reconciliation participant** (or an applicant for **certification** as a **reconciliation participant**) must ensure that—

- (a) an initial **audit** is completed no later than 2 months before the date on which the **reconciliation participant** (or the applicant for **certification** as a **reconciliation participant**) is required to be **certified** as a **reconciliation participant** under clause 2A of Schedule 15.1; and
- (b) further **audits** are completed as specified by the **Authority** under clause 16A.14.

## Subpart 6—Dispatchable load purchaser audits

### 16A.25 Time frame for dispatchable load purchaser audits

In relation to **audits** required under clause 15.37A, a **dispatchable load purchaser** must ensure that—

- (a) an initial **audit** is completed no later than 4 months after the date on which the **system operator** approves the first device or group of devices in respect of the **purchaser** to be a **dispatch-capable load station** under clause 13.3A; and
- (b) further **audits** are completed as specified by the **Authority** under clause 16A.14.

## Subpart 7—Distributed unmetered load audits

### 16A.26 Time frame for distributed unmetered load audits

- (1) In relation to **audits** required under clause 15.37B, a **retailer** that is responsible for **distributed unmetered load** must ensure that—
  - (a) an initial **audit** is carried out in respect of the **distributed unmetered load** no later than 3 months after the date on which information about an **ICP** associated with the **distributed unmetered load** is first provided by the **retailer** to the **reconciliation manager** as **submission information** under clause 15.4; and
  - (b) further **audits** are completed as specified by the **Authority** under clause 16A.14.
- (2) If responsibility for **distributed unmetered load** switches from one **retailer** to another, the **retailer** to which the responsibility switches must ensure that **audits** are completed in respect of the **distributed unmetered load** on the dates that would apply if the switch had not occurred.

Part 16A: inserted, on 1 June 2017 by clause 36 of the Electricity Industry Participation Code Amendment (Requirements and Processes for Audits) 2016.

# Electricity Industry Participation Code 2010

## Part 17 Transitional provisions

### Contents

#### *Transitional provisions relating to Part 1*

- 17.1 Transitional provisions for definitions
- 17.2 Special definition of purchaser and payer

#### *Transitional provisions relating to Part 2*

- 17.3 Requests for rulebook information

#### *Transitional provisions relating to Part 3*

- 17.4 Appointment of market operation service providers
- 17.5 Insurance cover
- 17.6 Notification of a force majeure event by a service provider
- 17.7 Disclosure to the Authority
- 17.8 Performance standards
- 17.9 Market operation service providers must report to Authority
- 17.10 Review of market operation service providers
- 17.11 Software specifications

#### *Transitional provisions relating to Part 4*

- 17.12 Notification of a force majeure event by an ancillary service agent

#### *Transitional provisions relating to Part 5*

- 17.13 Undesirable trading situations

#### *Transitional provisions relating to Part 6*

- 17.14 Approval to connect
- 17.15 Connection of distributed generation outside regulated terms
- 17.16 Connection of distributed generation on regulated terms
- 17.17 Obtaining approval to connect distributed generation under 10kW
- 17.18 Obtaining approval to connect distributed generation over 10kW
- 17.19 Confidentiality of information provided before connection
- 17.20 Annual reporting and record keeping
- 17.21 Confidential information for regulated terms for
- 17.22 Breach of regulated terms
- 17.23 Default dispute resolution process
- 17.23A Delayed application of Electricity Industry Participation Code Amendment (Distributed Generation) 2016 [*Revoked*]

#### *Transitional provisions relating to Part 7*

- 17.24 Security of supply forecasting and information policy
- 17.25 Emergency management policy
- 17.26 Review of system operator
- 17.27 Review of the system operator

#### *Transitional provisions relating to Part 8*

- 17.28 Policy statements
- 17.29 Existing contracts for higher levels of common quality

- 17.30 System security forecast
- 17.31 Load shedding obligations to support voltage
- 17.32 Information provisions
- 17.33 Commissioning plan or testing plan
- 17.34 Equivalence arrangement or dispensation
- 17.35 Excluded generating stations
- 17.36 Procurement plan
- 17.37 Alternative ancillary service arrangement
- 17.38 Allocating ancillary services costs
- 17.39 Requirements for asset capability statement
- 17.40 Connection of local networks in parallel with the grid
- 17.41 Modification and changes to assets
- 17.42 Records, tests and inspections
- 17.43 Information provided
- 17.44 Retention of records
- 17.45 Redistribution of automatic under-frequency load shedding [*Revoked*]
- 17.46 Notice
- 17.47 Specific requirements for document transmission communication
- 17.48 Outage
- 17.48A Transitional provisions for extended reserve [*Revoked*]
- 17.48B Transitional provisions for change to frequency limit in South Island [*Revoked*]

*Transitional provisions relating to Part 9*

- 17.49 System operator rolling outage plan
- 17.50 Participant rolling outage plans
- 17.51 Supply shortage declaration
- 17.52 Security of supply direction
- 17.53 Provision of information

*Transitional provisions relating to Part 10*

- 17.54 Meter installations
- 17.55 Quantification at points of connection
- 17.56 Electricity recorded
- 17.57 Metering installation tests
- 17.58 Approved test house
- 17.59 Certification of metering installations of Practice 10.3.
- 17.60 Inspection requirements
- 17.61 Variation of requirements

*Transitional provisions relating to Part 11*

- 17.62 Requirement to provide complete and accurate information
- 17.63 ICP identifiers for ICPs
- 17.64 Participants may request that distributors create ICP
- 17.65 Provision of ICP information
- 17.66 Provision of and changes to ICP and NSP information
- 17.67 Network owner notifications
- 17.68 Audits
- 17.69 Process for maintaining shared unmetered load
- 17.70 Timeframes and formats of information

- 17.71 Confirmation of receipt of data
- 17.72 Registry must maintain a database of information
- 17.73 Reports from the registry
- 17.74 Registry reports to specific participants
- 17.75 Access to the registry
- 17.76 Registry notifications
- 17.77 Customer and embedded generator queries
- 17.78 Dispensations
- 17.79 Distributors to provide ICP information to registry
- 17.80 Traders to provide ICP information to registry
- 17.81 Correction of errors in the registry
- 17.82 Management of ICP status by distributors and traders
- 17.83 Updating table of loss category codes
- 17.84 Updating loss factors for loss category codes
- 17.85 Updating table of price category codes
- 17.86 Balancing area information
- 17.87 Creation and decommissioning of NSPs and transfer of ICPs
- 17.88 Information to be provided if NSPs are created or ICPs
- 17.89 Information to be provided if ICPs become NSPs
- 17.90 Reconciliation manager to allocate new identifiers
- 17.91 Obligations concerning change in network owner
- 17.92 Reconciliation manager to advise registry
- 17.93 Transfer of ICPs between distributors' networks
- 17.94 Standard switching process for ICPs with non half-hour metering and unmetered ICPs
- 17.95 Switch move process for ICPs with non half-hour metering and unmetered ICPs
- 17.96 Half-hour switching process
- 17.97 Withdrawal of switch requests
- 17.98 Participants to use file formats
- 17.99 Method of exchanging files
- 17.100 Costs of interrogation or estimation
- 17.101 Registry notifications
- 17.101A Switching under Schedule 11.3

*Transitional provisions relating to Part 12*

- 17.102 Discretion to waive requirements
- 17.103 Benchmark agreements to be default transmission agreements
- 17.104 Changes to the connection assets under default transmission agreements
- 17.105 Expiry or termination of transmission agreements
- 17.106 Transmission agreement to be provided and published
- 17.107 Review of Connection Code
- 17.108 Increased services and reliability
- 17.109 Approval of decreased services and reliability
- 17.110 Approval of other variations to terms of benchmark agreement
- 17.111 Customer specific value of unserved energy
- 17.112 Replacement and enhancement of shared connection assets
- 17.113 Resolution of disputes relating to transmission agreements
- 17.114 Review of benchmark agreement

- 17.115 Existing agreements
  - 17.116 Transpower to publish grid reliability report
  - 17.117 Issues paper
  - 17.118 Development of transmission pricing methodology
  - 17.119 Development of transmission prices
  - 17.120 Audit of transmission prices
  - 17.121 Review of approved transmission pricing methodology
  - 17.122 Transpower to identify interconnection branches, and propose service measures and levels
  - 17.123 Transpower to propose reliability investments
  - 17.124 Transpower to propose economic investments
  - 17.125 Information on capacities of individual interconnection assets
  - 17.126 Transpower to provide and publish annual report on interconnection asset capacity and grid configuration
  - 17.127 Transpower to report on availability and reliability
- Transitional provisions relating to Part 13*
- 17.128 Requests for rulebook information
  - 17.129 Approval process for industrial co-generating stations
  - 17.129A Transitional provisions for co-generators
  - 17.130 Offer preparation by generators
  - 17.131 Generators' notice of initial offer
  - 17.132 Bids by purchasers
  - 17.133 Purchasers' notice of initial bids
  - 17.134 Bids and offers are valid until cancelled
  - 17.135 Offers made by unit of plant
  - 17.136 New, revised or cancelled bid or offer inside the 2 hour period
  - 17.137 Backup procedures if the information system is unavailable
  - 17.138 Backup procedures
  - 17.139 Plant with special circumstance
  - 17.140 Retention of bids and offers
  - 17.141 Special treatment of some grid exit points
  - 17.142 Standing data to be provided to the system operator
  - 17.143 Transmission grid capability information to be updated
  - 17.144 Grid owners must submit revised information to the system operator
  - 17.145 Changes may be made within 2 hours prior to the trading period
  - 17.146 System operator to approve ancillary service agents wishing to make reserve offers
  - 17.147 Ancillary service agents to submit reserve offers to the system operator
  - 17.148 Revised reserve offer inside the 2 hour period
  - 17.149 Availability of final bids and final offers
  - 17.150 Process for preparing a pre-dispatch schedule
  - 17.151 Block dispatch may occur
  - 17.152 System operator to notify block security constraints
  - 17.153 Station dispatch may occur
  - 17.154 System operator to notify security constraints
  - 17.155 Generator notifies change from station to unit dispatch
  - 17.156 Dispatch instructions
  - 17.157 Market administrator to appointment person to monitor and assess demands side



- participation
- 17.158 Grid emergency
- 17.159 The effect of a grid emergency in total quantities bid
- 17.160 Reporting requirements in respect of grid emergencies
- 17.161 Reporting obligation of the system operator
- 17.162 System operator to publish information
- 17.163 Run dispatch options
- 17.164 Clearing manager must conduct auctions
- 17.165 Deadline for auction bids
- 17.166 Authorisation to successful bidders
- 17.167 High spring washer price situation
- 17.168 Preparation of provisional and final prices
- 17.169 Half-hour metering information
- 17.170 Input information
- 17.171 Pricing manager to publish interim prices
- 17.172 SCADA situation
- 17.173 Metering situation
- 17.174 High spring washer price situation
- 17.175 Requirements if provisional price situation exists
- 17.176 Provisional prices and provisional reserve prices
- 17.177 Final prices and provisional prices and provisional reserve prices
- 17.178 Publish final prices or notice that a high spring washer price situation exists
- 17.179 System operator to apply high spring washer price relaxation factor and give notice
- 17.180 Revised data
- 17.181 If a provisional price situation (other than a high spring washer price situation) continues
- 17.182 Interim pricing period
- 17.183 Authority may order delay of publication of final prices
- 17.184 System operator to give pricing manager a list of model variable failures
- 17.185 Calculate constrained off amounts
- 17.186 Rights to constrained off information
- 17.187 Constrained on amounts
- 17.188 Payment of constrained on compensation
- 17.189 Market administrator to publish pricing manager reports
- 17.190 Right to information concerning pricing manager's action
- 17.191 Information that must be submitted
- 17.192 Calculation of contract price
- 17.193 Information submitted
- 17.194 Timeframes for submitting that information

*Transitional provisions relating to Part 14*

- 17.195 Acceptable forms of security
- 17.196 Cash deposits
- 17.197 Change in form of security
- 17.198 Reductions and releases
- 17.199 Hedge settlement agreements
- 17.200 Release of security
- 17.201 Level of security

17.202	Information, monitoring and reporting
17.203	Disputes
17.204	Invoices to and payments by payers
17.205	Operating account
17.206	Payments to and from payees
17.207	Defaults
17.208	Disputed invoices
17.209	Washups
17.210	Reporting obligations
17.210A	Acceptable forms of security <i>[Revoked]</i>
17.210B	Cash deposits <i>[Revoked]</i>
17.210C	Change in form of security <i>[Revoked]</i>
17.210D	Reductions and releases <i>[Revoked]</i>
17.210E	Release of security <i>[Revoked]</i>
17.210F	Level of security <i>[Revoked]</i>
17.210G	Information, monitoring, and reporting <i>[Revoked]</i>
17.210H	Disputes <i>[Revoked]</i>
17.210I	Invoices and payments <i>[Revoked]</i>
17.210J	Operating account <i>[Revoked]</i>
17.210K	FTR account <i>[Revoked]</i>
17.210L	Defaults <i>[Revoked]</i>
17.210M	Disputed invoices <i>[Revoked]</i>
17.210N	Washups <i>[Revoked]</i>
17.210O	Reporting obligations <i>[Revoked]</i>

*Transitional provisions relating to Part 15*

17.211	Requirement to provide complete and accurate information
17.212	Provision of trading information at point of connection to network
17.213	Submission information to be delivered for reconciliation
17.214	Retailer and direct purchaser ICP days information
17.215	Retailer electricity supplied information
17.216	Retailer and direct purchaser half-hourly metered ICPs monthly kWh information
17.217	Grid owner volume information
17.218	Local network and embedded network submission information
17.219	Grid connected generator
17.220	Accuracy of submitted information
17.221	Notification by embedded generators
17.222	Notification of changes to the grid
17.223	System operator notifies reconciliation manager of points of connection to the grid subject to outages or alternative supply
17.224	Balancing area NSP grouping changes
17.225	Submission information to be reviewed in the case of an outage constraint
17.226	Reconciliation manager may request additional information
17.227	Providing information specific to reconciliation participants
17.228	Providing information to reconciliation participants
17.229	Reconciliation information checked
17.230	Reconciliation manager must assess information not supplied
17.231	Reconciliation manager to correct information

17.232	Transitional provisions concerning revision
17.233	Volume information disputes
17.234	Alleged breaches reported by the reconciliation manager
17.235	Right to information concerning reconciliation manager's actions
17.236	Reconciliation reports
17.237	The publication of reports
17.238	Provision of information
17.239	New Zealand daylight time adjustment techniques
17.240	Audit
17.241	Functions requiring certification
17.242	Participant must use participant identifiers
17.243	Requirement for certification
17.244	Obtaining certification
17.245	Granting certification
17.246	Lists of certified reconciliation participants and agents
17.247	Renewed certification
17.248	Changes that affect certification
17.249	Auditors
17.250	Audits
17.251	Audit reports
17.252	Participant requested audits
17.253	Scope of audits
17.254	Information requests
17.255	Participants provide access and information
17.256	Production of audit report
17.257	Determination
17.258	Summary of audit report
17.259	Meter interrogation for non half-hour metering
17.260	Non half-hour meter reading every 4 months
17.261	Interrogation logs
17.262	Meter interrogation for half-hour metering
17.263	Audit trails
17.264	Correction of meter readings
17.265	Creation of submission information
17.266	Provision of submission information to reconciliation manager
17.267	Reporting requirements
17.268	Distributed unmetered load database
17.269	Calculation by difference for embedded networks
17.270	Calculation by difference for local networks
17.271	ICP days information
17.272	Calculation of residual non half-hour profile shape
17.273	Convert non half-hour quantities using profiles
17.274	Invalid submission information
17.275	Loss factors
17.276	Scorecard rating
17.277	Calculation of scorecard rating
17.278	Application of scorecard rating

- 17.279 Reconciliation manager reporting requirements
- 17.280 Provision of reconciliation information
- 17.281 Departure from requirements for profile administration
- 17.282 Profile population list
- 17.283 Profiles approved for use
- 17.284 Change of profile
- 17.285 Profile codes
- 17.286 New NSP derived profiles
- 17.287 New statistically sampled/engineered profiles
- 17.288 MARIA profiles
- 17.289 Audits
- 17.290 Removal of profiles
- 17.291 Reviews

*Transitional provisions relating to Part 16 [Revoked]*

- 17.292 Summary of Rio Tinto agreements *[Revoked]*
- 17.293 Variations of Rio Tinto agreements *[Revoked]*
- 17.294 Notifications of Acts and omissions *[Revoked]*
- 17.295 Right of appeal *[Revoked]*

*Transitional provisions relating to Part 16A*

- 17.295A Metering equipment provider audits
- 17.295B ATH audits
- 17.295C Distributor audits
- 17.295D Reconciliation participant audits
- 17.295E Dispatchable load purchaser audits
- 17.295F Distributed unmetered load audits

*Transitional provisions relating to exemptions*

- 17.296 Exemptions
- 

*Transitional provisions relating to Part 1*

**17.1 Transitional provisions for definitions**

- (1) Administrative costs agreed by the Board and the system operator in accordance with the definition of administrative costs in rule 1 of part A of the **rules** that were in force immediately before this Code came into force, are deemed to be **administrative costs** that have been agreed to by the **Authority** and the **system operator** in accordance with the definition of **administrative costs** in clause 1.1(1).
- (2) A declaration date nominated by a profile applicant in accordance with the definition of declaration date in rule 1 of part A of the **rules** that was in force immediately before this Code came into force, is deemed to be a **declaration date** nominated by a **profile applicant** in accordance with the definition of **declaration date** in clause 1.1(1).
- (3) A distributor kvar reference node approved by the system operator in accordance with the definition of distributor kvar reference node in rule 1 of part A of the **rules** that was in force immediately before this Code came into force, is deemed to be a **distributor**

**kvar reference node** approved by the **system operator** in accordance with the definition of **distributor kvar reference node** in clause 1.1(1).

- (4) Expected interruption costs estimated by the Board under the definition of expected interruption costs in rule 1 of part A of the **rules** that were in force immediately before this Code came into force, are deemed to be **expected interruption costs** approved by the **Authority** in accordance with the definition of **expected interruption costs** in clause 1.1(1).
- (5) A grid exit point approved by the system operator under the definition of interruptible load group GXP in rule 1 of part A of the **rules** immediately before this Code came into force, is deemed to be a **grid exit point** approved by the **system operator** in accordance with the definition of **interruptible load group GXP** in clause 1.1(1).
- (6) A system operator register kept, maintained, or made available by the system operator in accordance with the definition of system operator register in rule 1 of part A of the **rules** immediately before this Code came into force, is deemed to be a **system operator register** kept, maintained, or made available, as the case may be, by the **system operator** in accordance with definition of **system operator register** in clause 1.1(1).

## 17.2 Special definition of purchaser and payer

- (1) A notice given under rule 5.2 of part A of the **rules** and in force immediately before this Code came into force, is deemed to be a notice given under clause 1.5(2), and may be—
  - (a) approved by the **Authority** (if it has not been approved by the Board); and
  - (b) revoked by the **participant** named in the notice as participant A or the **participant** in the notice named as participant B.
- (2) A notice published by the Board under rule 5.8 of part A of the **rules** before this Code came into force, is deemed to be a notice published by the **Authority** under clause 1.5(8).

### *Transitional provisions relating to Part 2*

## 17.3 Requests for rulebook information

- (1) A request for rulebook information received by the Commission under regulation 15 of the Electricity Governance Regulations 2003 that had not been responded to immediately before this Code came into force, is deemed to be a request for **Code information** received by the **Authority** under clause 2.1.
- (2) A request for rulebook information received by the Commission under regulation 17 of the Electricity Governance Regulations 2003 that had not been responded to immediately before this Code came into force, is deemed to be a request for **Code information** received by the **Authority** under clause 2.3.
- (3) A request for rulebook information received by a participant under regulation 19 of the Electricity Governance Regulations 2003 that had not been responded to immediately before this Code came into force, is deemed to be a request for **Code information** received by a **participant** under clause 2.5.
- (4) A notice transferring a request for rulebook information under regulation 22 of the Electricity Governance Regulations 2003 that had not been responded to immediately

before this Code came into force, is deemed to be a notice transferring a request for **Code information** under clause 2.8.

- (5) A charge payable by a participant under regulation 26 of the Electricity Governance Regulations 2003 immediately before this Code came into force, is deemed to be a charge payable by a **requesting participant** under clause 2.12.

*Transitional provisions relating to Part 3*

**17.4 Appointment of market operation service providers**

- (1) A person or persons appointed as a registry by the Commission under regulation 30 of the Electricity Governance Regulations 2003, and whose appointment was in force immediately before this Code came into force, is deemed to have been appointed by the **Authority** as a **registry manager** under clause 3.1.
- (2) A person or persons appointed as a reconciliation manager by the Commission under regulation 30 of the Electricity Governance Regulations 2003, and whose appointment was in force immediately before this Code came into force, is deemed to have been appointed by the **Authority** as a **reconciliation manager** under clause 3.1.
- (3) A person or persons appointed as a pricing manager by the Commission under regulation 30 of the Electricity Governance Regulations 2003, and whose appointment was in force immediately before this Code came into force, is deemed to have been appointed by the **Authority** as a **pricing manager** under clause 3.1.
- (4) A person or persons appointed as a clearing manager by the Commission under regulation 30 of the Electricity Governance Regulations 2003, and whose appointment was in force immediately before this Code came into force, is deemed to have been appointed by the **Authority** as a **clearing manager** under clause 3.1.
- (5) A person or persons appointed as a market administrator by the Commission under regulation 30 of the Electricity Governance Regulations 2003, whose appointment was in force immediately before this Code came into force, is deemed to have been appointed by the **Authority** as a **market administrator** under clause 3.1.
- (6) A service provider's term of appointment and the date on which that term begins agreed under regulation 32 of the Electricity Governance Regulations 2003, and in force immediately before this Code came into force, is deemed to be the relevant **market operation service provider's** term of appointment for the purposes of clause 3.3 and the date on which the term begins, as the case may be.
- (7) The remuneration and other terms and conditions of appointment of a service provider agreed under regulation 33 of the Electricity Governance Regulations 2003, and in force immediately before this Code came into force, are deemed to be the remuneration and terms and conditions of appointment of the relevant **market operation service provider**, as the case may be, for the purposes of clause 3.4.
- (8) A service provider agreement published by the Commission under regulation 34 of the Electricity Governance Regulations 2003 and in force immediately before this Code came into force, is deemed to be a **market operation service provider agreement** published by the **Authority** under clause 3.5.

### **17.5 Insurance cover**

- (1) A requirement by the Commission that a service provider maintain insurance cover under regulation 36 of the Electricity Governance Regulations 2003 that was in force immediately before this Code came into force, is deemed to be a requirement by the **Authority** under clause 3.6.
- (2) An insurer approved by the Commission under regulation 36 of the Electricity Governance Regulations 2003 immediately before this Code came into force, is deemed to be approved by the **Authority** under clause 3.6 on the same terms and in respect of the same risks.

### **17.6 Notification of a force majeure event by a service provider**

A notification to the Commission of a force majeure event under regulation 38 of the Electricity Governance Regulations 2003 that was in force immediately before this Code came into force, is deemed to be a notification to the **Authority** of a **force majeure event** under clause 3.7.

### **17.7 Disclosure to the Authority**

Information received by a service provider to which regulation 42 of the Electricity Governance Regulations 2003 applied immediately before this Code came into force, is deemed to be information received by the relevant **market operation service provider** on the day on which this Code came into force for the purposes of clause 3.11.

### **17.8 Performance standards**

Performance standards agreed between the Commission and a service provider for the 2010/2011 financial year under regulation 43 of the Electricity Governance Regulations 2003 that were in force immediately before this Code came into force, are deemed to be the performance standards agreed between the **Authority** and the relevant **market operation service provider** under clause 3.12 for that financial year.

### **17.9 Market operation service providers must report to Authority**

- (1) Despite the revocation of the **rules**, a person who was a service provider immediately before this Code came into force must conduct a self-review of its performance as if regulations 44 and 45 of the Electricity Governance Regulations 2003 had not been revoked, and must provide the report required under regulation 45 of the Electricity Governance Regulations 2003 to the **Authority**.
- (2) A report provided to the **Authority** under subclause (1) is deemed to be a report given under clause 3.14.

### **17.10 Review of market operation service providers**

- (1) If the **Authority** reviews a **market operation service provider** for the 2010/2011 financial year under clause 3.15, the **Authority** must report on the matters specified in regulation 46 of the Electricity Governance Regulations 2003 for the period up to the date on which this Code came into force, as well as matters specified in clause 3.15 for

the remainder of the period.

- (2) Each report to which subclause (1) applies must consolidate all of the information required to be included so as to report on the period to which it relates as a whole.

#### **17.11 Software specifications**

- (1) An agreement between the Commission and a service provider under regulation 51 of the Electricity Governance Regulations 2003 in force immediately before this Code came into force, is deemed to be an agreement between the **Authority** and the **market operation service provider** in force under clause 3.16.
- (2) An agreement between the Commission and a service provider under regulation 52 of the Electricity Governance Regulations 2003 in force immediately before this Code came into force, is deemed to be an agreement between the **Authority** and the **market operation service provider** in force under clause 3.17.
- (3) An audit report provided to the Commission under regulation 52 of the Electricity Governance Regulations 2003 before this Code came into force, is deemed to be an audit report provided to the **Authority** under clause 3.17.

#### *Transitional provisions relating to Part 4*

#### **17.12 Notification of a force majeure event by an ancillary service agent**

A notification to the system operator and the Commission of a force majeure event under regulation 53B of the Electricity Governance Regulations 2003 immediately before this Code came into force, is deemed to be a notification to the **Authority** of a **force majeure event** under clause 4.1.

#### *Transitional provisions relating to Part 5*

#### **17.13 Undesirable trading situations**

- (1) An investigation of an undesirable trading situation initiated by the Commission under regulation 54 of the Electricity Governance Regulations 2003, and not completed immediately before this Code came into force, is deemed to be an investigation of an **undesirable trading situation** initiated by the **Authority** under clause 5.1.
- (2) An action taken by the Commission to correct an undesirable trading situation under regulation 56 of the Electricity Governance Regulations 2003 before this Code came into force, is deemed to be an action taken by the **Authority** under clause 5.2.
- (3) Consultation undertaken by the Commission with the system operator to correct an undesirable trading situation under regulation 58 of the Electricity Governance Regulations 2003 before this Code came into force, is deemed to be consultation undertaken by the **Authority** in respect of action taken under clause 5.2 to correct an **undesirable trading situation** under clause 5.3.
- (4) Consultation undertaken by the Commission with participants under regulation 59 of the Electricity Governance Regulations 2003 before this Code came into force, is deemed to be consultation undertaken by the **Authority** with **participants** under clause 5.4.



*Transitional provisions relating to Part 6*

**17.14 Approval to connect**

An approval granted by a distributor to a generator to connect distributed generation under regulation 7 of the Electricity Governance (Connection of Distributed Generation) Regulations 2007 that was in force immediately before this Code came into force, is deemed to be an approval granted to **connect distributed generation** under clause 6.4.

**17.15 Connection of distributed generation outside regulated terms**

A connection contract entered into by a distributor and a generator outside the regulated terms under regulation 8 of the Electricity Governance (Connection of Distributed Generation) Regulations 2007 that was in force immediately before this Code came into force, is deemed to be a **connection** contract outside the **regulated terms** under clause 6.5.

Clause 17.15: amended, on 23 February 2015, by clause 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

**17.16 Connection of distributed generation on regulated terms**

- (1) If distributed electricity was connected on regulated terms under regulation 9 of the Electricity Governance (Connection of Distributed Generation) Regulations 2007 immediately before this Code came into force, it is deemed to be **connected on regulated terms** under clause 6.6.
- (2) If a period for negotiating a connection contract under clause 9 or clause 24 of Schedule 1 of the Electricity Governance (Connection of Distributed Generation) Regulations 2007 had commenced but had not expired immediately before this Code came into force, the period expires for the purposes of clause 6.6 on the date on which it would have expired if the Electricity Governance (Connection of Distributed Generation) Regulations 2007 were not revoked.

Clause 17.16(1): amended, on 23 February 2015, by clause 75 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2014.

**17.17 Obtaining approval to connect distributed generation under 10kW**

- (1) An application by a generator to a distributor to connect distributed generation only capable of generating electricity at a rate of 10kW under clause 2 of Schedule 1 of the Electricity Governance (Connection of Distributed Generation) Regulations 2007, and on which a distributor had not made a decision immediately before this Code came into force, is deemed to be an application under clause 2 of Schedule 6.1.
- (2) A generator approved to connect distributed generation under clause 3 of Schedule 1 of the Electricity Governance (Connection of Distributed Generation) Regulations 2007 immediately before this Code came into force, is deemed to have been approved to **connect distributed generation** under clause 3 of Schedule 6.1.
- (3) A notice of intention to proceed given by a generator under clause 5 of Schedule 1 of the Electricity Governance (Connection of Distributed Generation) Regulations 2007 that was in force immediately before this Code came into force, is deemed to be a notice

of intention to proceed under clause 5 of Schedule 6.1.

#### **17.18 Obtaining approval to connect distributed generation over 10kW**

- (1) An initial application made by a generator to a distributor to connect distributed generation capable of generating electricity above 10kW under clause 11 of Schedule 1 of the Electricity Governance (Connection of Distributed Generation) Regulations 2007, for which the generator had not made a final application in respect of the generation immediately before this Code came into force, is deemed to be an **initial application** under clause 11 of Schedule 6.1.
- (2) Information provided under clauses 12 and 13 of Schedule 1 of the Electricity Governance (Connection of Distributed Generation) Regulations 2007 before this Code came into force, is deemed to be information provided under clauses 12 and 13 of Schedule 6.1.
- (3) A final application made under clause 15 of Schedule 1 of the Electricity Governance (Connection of Distributed Generation) Regulations 2007, on which a distributor had not made a decision immediately before this Code came into force, is deemed to be a **final application** made under clause 15 of Schedule 6.1.
- (4) A generator approved to connect distributed generation under clause 18 of Schedule 1 of the Electricity Governance (Connection of Distributed Generation) Regulations 2007 immediately before this Code came into force, is deemed to have been approved to **connect distributed generation** under clause 18 of Schedule 6.1.
- (5) Any conditions specified by a distributor in its decision on an application under clause 18 of Schedule 1 of the Electricity Governance (Connection of Distributed Generation) Regulations 2007 immediately before this Code came into force, are deemed to be conditions specified by the **distributor** under clause 18 of Schedule 6.1.
- (6) A notice of an intention to proceed made by a generator under clause 20 of the Electricity Governance (Connection of Distributed Generation) Regulations 2007 that was in force immediately before this Code came into force, is deemed to be a notice under clause 20 of Schedule 6.1.

#### **17.19 Confidentiality of information provided before connection**

Information provided with an application made under Schedule 1 of the Electricity Governance (Connection of Distributed Generation) Regulations 2007 before this Code came into force, is subject to the confidentiality provisions in clause 25 of Schedule 6.1.

#### **17.20 Annual reporting and record keeping**

- (1) An annual report given by a distributor under clause 26 of Schedule 6.1 for the year 1 January 2010 to 1 January 2011 must report on the matters contained in clause 26 of Schedule 1 of the Electricity Governance (Connection of Distributed Generation) Regulations 2007 for the period 1 January 2010 to the date on which this Code came into force, as well as matters contained in clause 26 of Schedule 6.1, for the remainder of the period.
- (2) Each report to which subclause (1) applies must consolidate all of the information

- required to be included so as to report on the period to which it relates as a whole.
- (3) Records to which clause 28 of Schedule 1 of the Electricity Governance (Connection of Distributed Generation) Regulations 2007 applied immediately before this Code came into force, are deemed to be records to which clause 28 of Schedule 6.1 applies, and must be maintained accordingly.

#### **17.21 Confidential information for regulated terms for connection of distributed generation**

- (1) Conditions specified under clause 18 of Schedule 2 of the Electricity Governance (Connection of Distributed Generation) Regulations 2007 apply as if they were specified under clause 17 of Schedule 6.2.
- (2) Information that came within the definition of confidential information under clause 16 of Schedule 2 of the Electricity Governance (Connection of Distributed Generation) Regulations 2007, is deemed to be **confidential information** as defined in clause 1.1(1).

#### **17.22 Breach of regulated terms**

A regulated terms breach under clause 21 of Schedule 2 of the Electricity Governance (Connection of Distributed Generation) Regulations 2007 that was not resolved immediately before this Code came into force, is deemed to be a **regulated terms** breach under clause 20 of Schedule 6.2.

#### **17.23 Default dispute resolution process**

- (1) A dispute to which clause 1 of Schedule 3 of the Electricity Governance (Connection of Distributed Generation) Regulations 2007 applies that was not resolved immediately before this Code came into force, is deemed to be a dispute to which clause 1 of Schedule 6.3 applies.
- (2) A notice of dispute given under clause 2 of Schedule 3 of Electricity Governance (Connection of Distributed Generation) Regulations 2007, for a dispute that was not resolved immediately before this Code came into force, is deemed to be a notice given under clause 2 of Schedule 6.3.

#### **17.23A [Revoked]**

Clause 17.23A: inserted, on 9 January 2017, by clause 6 of the Electricity Industry Participation Code Amendment (Distributed Generation) 2016.

Clause 17.23A: revoked, on 5 October 2017, by clause 579 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

#### *Transitional provisions relating to Part 7*

#### **17.24 Security of supply forecasting and information policy**

A security of supply forecasting and information policy issued by the Commission and in force immediately before this Code came into force, is deemed to be the **security of supply forecasting and information policy** prepared and published under clause 7.3, and may be substituted by the **system operator** accordingly.

### 17.25 Emergency management policy

An emergency management policy issued by the Commission and in force immediately before this Code came into force, is deemed to be the **emergency management policy** prepared and published under clause 7.3, and may be substituted by the **system operator** accordingly.

### 17.26 Review of system operator

- (1) The review of the performance of the **system operator** by the **Authority** for the 2010/2011 financial year required under clause 7.8 must report on the matters specified in regulations 47 and 48 of the Electricity Governance Regulations 2003 for the period up to the date on which this Code came into force, as well as the matters specified in clauses 7.8 and 7.9 for the remainder of the period.
- (2) Each report to which subclause (1) applies must consolidate the information required to be included so as to report on the period to which it relates as a whole.

### 17.27 Review of the system operator

An assessment of the system operator's performance submitted to the Commission under rule 14 of section II of part C of the **rules** for the period ending 31 August 2010, is deemed to have been submitted to the **Authority** under clause 7.11.

### *Transitional provisions relating to Part 8*

### 17.28 Policy statements

- (1) The policy statement set out in schedule C4 of part C of the **rules** immediately before this Code came into force, continues in force and is deemed to be the **policy statement** that applies under clause 8.9, with the following amendments:
  - (a) every reference to the Board must be read as a reference to the **Authority**;
  - (b) every reference to the **rules** must be read as a reference to the Code;
  - (c) every reference to the regulations must be read as a reference to the Code;
  - (d) every reference to a provision of the **rules** or the regulations must be read as a reference to the corresponding provision of the Code.
- (2) The **Authority** must, as soon as practicable after this Code came into force, publish a version of the **policy statement** in which the provisions of this Code that correspond to the provisions of the **rules** or regulations referred to in the **policy statement** are shown.

### 17.29 Existing contracts for higher levels of common quality

- (1) This clause applies if—
  - (a) **Transpower** and any person have a contract or an arrangement to maintain voltage at a **point of connection** that—
    - (i) was in force immediately before the **rules** came into force; and
    - (ii) remained in force after this Code came into force; and
  - (b) the effect of the contract or arrangement may cause the **system operator** to operate the **grid** voltage within a lesser range than the range set out in the

**AOPOs**; and

- (c) **Transpower** and the **system operator** have a matching contract or arrangement in that respect under clause 8.6.
- (2) When this clause applies, any incremental cost arising from the **system operator** operating within a lesser range under a contract or arrangement to which subclause (1)(c) applies—
  - (a) must not be allocated according to clause 8.6; but instead
  - (b) is an **allocable cost** and must be paid as set out in clauses 8.55 and 8.67.
- (3) Subclause (2) applies to the costs arising from a contract or arrangement to which subclause (1)(c) applies until the earlier of the following:
  - (a) the expiry date of the contract or arrangement;
  - (b) termination of the contract or arrangement;
  - (c) the end of the life of the **assets** employed in providing the voltage service provided for in the contract or arrangement.

### **17.30 System security forecast**

- (1) A review of the system security forecast prepared in accordance with rule 15.1 of section II of part C of the **rules** for the 6 month period immediately before this Code came into force, is deemed to be a review of the **system security forecast** under clause 8.15.
- (2) The system security forecast last provided to the Commission under rule 15 of section II of part C of the **rules** immediately before this Code came into force, is deemed to have been prepared, published and provided to the **Authority** under clause 8.15.

### **17.31 Load shedding obligations to support voltage**

A requirement expressed by the system operator under rule 3.3 of section III of part C of the **rules** that was in force immediately before this Code came into force, is deemed to be a requirement expressed by the **system operator** under clause 8.24.

### **17.32 Information provisions**

- (1) A notice given by the system operator to an embedded generator under rule 4.5 of section III of part C of the **rules** that was in force immediately before this Code came into force, is deemed to be a notice issued by the **system operator** to an **embedded generator** under clause 8.25(5)(b).
- (2) An application to the Commission under rule 4.6 of section III of part C of the **rules** on which the Commission had not made a decision immediately before this Code came into force, is deemed to be an application to the **Authority** under clause 8.25(6).
- (3) An approval given by the Commission under rule 4.6 of section III of part C of the **rules** immediately before this Code came into force, is deemed to be an approval given by the **Authority** under clause 8.25(6).

### **17.33 Commissioning plan or testing plan**

A commissioning plan or testing plan agreed between the asset owner and the system

operator under rule 6 of section III of part C of the **rules** and in force immediately before this Code came into force, is deemed to be a commissioning plan or testing plan agreed between the **asset owner** and the **system operator** under clause 8.28(3)(b).

#### 17.34 Equivalence arrangement or dispensation

- (1) An approval of an equivalence arrangement under rule 7.2 of section III of part C of the **rules**, unless cancelled under rule 8.2 of section III of part C or revoked under rule 8.3 of section III of part C, that was in force immediately before this Code came into force, is deemed to be an approval of an **equivalence arrangement** under clause 8.30 and clause 8 of Schedule 8.1, as modified in accordance with rule 8.1 of section III of part C of the **rules**.
- (2) A grant of a dispensation under rule 7.3 of section III of part C of the **rules**, unless cancelled under rule 8.2 of section III of part C, or revoked or varied under rule 8.3 of section III of part C, that was in force immediately before this Code came into force, is deemed to be a grant of a **dispensation** under clause 8.31 and clause 8 of Schedule 8.1 as modified in accordance with rule 8.1 of section III of part C of the **rules**.
- (3) An application for an equivalence arrangement made under clause 2 of schedule C1 of part C of the **rules**, on which the system operator had not yet advised its decision immediately before this Code came into force, is deemed to be an application for an **equivalence arrangement** under clause 2 of Schedule 8.1.
- (4) An application for a dispensation made under clause 2 of schedule C1 of part C of the **rules**, on which the system operator had not yet advised its decision immediately before this Code came into force, is deemed to be an application for a **dispensation** under clause 2 of Schedule 8.1.
- (5) An agreement relating to the processing costs for the approval of an equivalence arrangement or the grant of a dispensation under clause 5 of schedule C1 of part C of the **rules** that was in force immediately before this Code came into force, is deemed to be an agreement under clause 5 of Schedule 8.1.
- (6) A draft decision issued and published by the system operator on the grant of a dispensation under clause 6 of schedule C1 of part C of the **rules**, on which the system operator had not advised its decision immediately before this Code came into force, is deemed to be a draft decision issued and published by the **system operator** on the grant of a **dispensation** under clause 6 of Schedule 8.1.

#### 17.35 Excluded generating stations

A directive issued by the Commission under rule 10 of section III of part C of the **rules** that was in force immediately before this Code came into force, is deemed to be a directive issued by the **Authority** under clause 8.38(2).

#### 17.36 Procurement plan

- (1) *[Expired]*
- (2) *[Expired]*
- (3) Subclauses (1) and (2) expire at the close of 30 November 2010.

- (4) The **procurement plan** notified in the *Gazette* dated 15 July 2010 is deemed to be the **procurement plan** made under clause 8.41.
- (5) Subclause (4) came into force on 1 December 2010.
- (6) A draft procurement plan submitted to the Commission under rule 4 of section IV of part C of the **rules** on which the review process in rule 5 of section IV of part C had not been completed immediately before this Code came into force, is deemed to be a **draft procurement plan** submitted to the **Authority** under clause 8.43.
- (7) A draft procurement plan published by the Commission under rule 5 of section IV of part C of the **rules** on which the review process in that rule had not been completed immediately before this Code came into force, is deemed to be a **draft procurement plan** published by the **Authority** under clause 8.44.
- (8) A submission received on a draft procurement plan under rule 5 of section IV of part C of the **rules** on which the review process in that rule had not been completed immediately before this Code came into force, is deemed to be submission received on a **draft procurement plan** under clause 8.44.
- (9) A request for variation to a current procurement plan by a participant that the Commission had determined to hold over until the next draft procurement plan process under rule 7.2.2 of section IV of part C of the **rules** immediately before this Code came into force, is deemed to be a request for variation to a current **procurement plan** that has been held over by the **Authority** until the next **draft procurement plan** process under clause 8.46(3).
- (10) A report provided to the Board by the system operator under rule 8.2 of section IV of part C of the **rules** before this Code came into force, is deemed to be a report provided to the **Authority** under clause 8.47(2).

Clause 17.36(1) and (2): expired, on 30 November 2012 by clause 17.36(3).

### 17.37 Alternative ancillary service arrangement

- (1) An alternative ancillary service arrangement authorised under rules 9.1 to 9.3 of section IV of part C of the **rules**, unless cancelled under rule 9.6 of section IV of part C or revoked under rule 9.7 of section IV of part C, immediately before this Code came into force, is deemed to be an authorised **alternative ancillary service arrangement** under clause 8.48, with any modifications to the arrangement made by rules 9.4 and 9.5 of section IV of part C of the **rules**.
- (2) An application for an authorisation of an alternative ancillary service arrangement made under rules 9.1 to 9.3 of section IV of part C of the **rules**, not determined immediately before this Code came into force, is deemed to be is an application for authorisation of an alternative **ancillary service arrangement** made under clause 8.48 and clause 1 of Schedule 8.2.
- (3) A notification given under rule 10 of section IV of part C of the **rules** that was in force immediately before this Code came into force, is deemed to be a notification under clause 8.54.

### 17.38 Allocating ancillary services costs

- (1) Amounts payable pursuant to contracts under rule 11.1.1 of section IV of part C of the **rules**, not paid immediately before this Code came into force, are deemed to be amounts payable under clause 8.55(a).
- (2) Actual administrative costs approved by the Commission under rule 11.1.2 of section IV of part C of the **rules** and in force immediately before this Code came into force, are deemed to be actual **administrative costs** under clause 8.55(b).
- (3) Costs or charges payable under rule 11.5.1 of section IV of part C of the **rules**, not paid immediately before this Code came into force, are deemed to be costs or charges payable under clause 8.59.
- (4) A notice given by the system operator to a participant under rule 11.5.1A of section IV of part C of the **rules**, for which the required information had not been provided immediately before this Code came into force, is deemed to be a notice given under clause 8.60.
- (5) A draft determination published by the system operator under rule 11.5.1B of section IV of part C of the **rules** before this Code came into force, is deemed to be a draft determination **published** under clause 8.61.
- (6) A submission received on a draft determination published by the system operator under rule 11.5.1B of section IV of part C of the **rules** before this Code came into force, is deemed to be a submission received under clause 8.61.
- (7) A notice given to the Rulings Panel under rule 11.5.1C of section IV of part C of the **rules** that was in force immediately before this Code came into force, is deemed to be a notice given under clause 8.62.
- (8) A decision made by the Rulings Panel under rule 11.5.1D of section IV of part C of the **rules** before this Code came into force, is deemed to be a decision made by the **Rulings Panel** under clause 8.63.
- (9) A determination referred back to the system operator under rule 11.5.1D of section IV of part C of the **rules** that had not been resolved immediately before this Code came into force, is deemed to have been referred back to the **system operator** under clause 8.63.
- (10) Costs or charges payable under rule 11.5.2 of section IV of part C of the **rules**, not paid immediately before this Code came into force, are deemed to be costs or charges payable under clause 8.64.
- (11) An event charge that had been paid but not rebated under rule 11.5.3 of part IV of part C of the **rules** immediately before this Code came into force, must be rebated under clause 8.65.
- (12) Costs or charges payable under rule 11.6 of section IV of part C of the **rules**, not paid immediately before this Code came into force, are deemed to be costs or charges payable under clause 8.67.
- (13) Amounts payable under rule 11.7 of section IV of part C of the **rules**, not paid immediately before this Code came into force, are deemed to be amounts payable under clause 8.68.
- (14) Amounts payable under rule 11.8 of section IV of part C of the **rules**, not paid



immediately before this Code came into force, are deemed to be amounts payable under clause 8.69.

#### **17.39 Requirements for asset capability statement**

An asset capability statement provided to the system operator by an asset owner under clause 2.5 of technical code A of schedule C3 of part C of the **rules** before this Code came into force, is deemed to be an **asset capability statement** provided under clause 2(5) of **Technical Code A** of Schedule 8.3.

#### **17.40 Connection of local networks in parallel with the grid**

An agreement under clause 6 of technical code A of schedule C3 of part C of the **rules** that was in force immediately before this Code came into force, is deemed to be an agreement under clause 6 of **Technical Code A** of Schedule 8.3.

#### **17.41 Modification and changes to assets**

A notification given by an asset owner to the system operator under clause 7.2 of schedule C3 of part C of the **rules** that was in force immediately before this Code came into force, is deemed to be a notification given under clause 7(2) of Schedule 8.3.

#### **17.42 Records, tests and inspections**

A written request made by the system operator to an asset owner under clause 8.3 of schedule C3 of part C of the **rules** that the asset owner had not responded to immediately before this Code came into force, is deemed to be a written request made under clause 8(3) of **Technical Code A** of Schedule 8.3.

#### **17.43 Information provided**

- (1) Information provided by a North Island distributor under clause 6 of appendix B of technical code A of schedule C3 of part C of the **rules** before this Code came into force, is deemed to be information provided by a North Island **distributor** under clause 6 of Appendix B of **Technical Code A** of Schedule 8.3.
- (2) Information provided by a South Island distributor under clause 7 of appendix B of technical code A of schedule C3 of part C of the **rules** before this Code came into force, is deemed to be information provided by a South Island **distributor** under clause 7 of Appendix B of **Technical Code A** of Schedule 8.3.

#### **17.44 Retention of records**

The **system operator** and each **participant** must retain records of formal notices issued under clause 4 of technical code B of schedule C3 of part C of the **rules**.

#### **17.45 Redistribution of automatic under-frequency load shedding *[Revoked]***

Clause 17.45: revoked, on 7 August 2014, by clause 34 of the Electricity Industry Participation Code Amendment (Extended Reserve) 2014.

#### 17.46 Notice

A notice in relation to a participant under clause 6.5A.2 of technical code B of schedule C3 of part C of the **rules** that was in force immediately before this Code came into force, is deemed to be a notice in relation to a **participant** under clause 7(11) of **Technical Code B** of Schedule 8.3.

#### 17.47 Specific requirements for document transmission communication

- (1) A request made by an asset owner to the system operator under clause 4.1.2 of technical code C of schedule C3 of part C of the **rules** that had not been dealt with by the system operator immediately before this Code came into force, is deemed to be a request made under clause 5(2) of **Technical Code C** of Schedule 8.3.
- (2) An approval of primary or backup means of document transmission communication under clauses 4.1 or 4.2 of technical code C of schedule C3 of part C of the **rules** that was in force immediately before this Code came into force, is deemed to be an approval under clause 5(2) or (3), as the case may be, of **Technical Code C** of Schedule 8.3.

#### 17.48 Outage

- (1) A notification of a planned outage under clause 2 of technical code D of schedule C3 of part C of the **rules** that was in force immediately before this Code came into force, is deemed to be a notification under clause 2 of **Technical Code D** of Schedule 8.3.
- (2) Any asset outage programme published under clause 6 of technical code D of schedule C3 of part C of the **rules** that was in force immediately before this Code came into force, is deemed to be a **asset** outage programme published under clause 6 of **Technical Code D** of Schedule 8.3.

#### 17.48A [Revoked]

Clause 17.48A: inserted, on 7 August 2014, by clause 35 of the Electricity Industry Participation Code Amendment (Extended Reserve) 2014.

Clause 17.48A(3): amended, on 19 December 2014, by clause 43 of the Electricity Industry Participation Code Amendment (Minor Code Amendments) (No 3) 2014.

Clause 17.48A: revoked, on 5 October 2017, by clause 580 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

#### 17.48B [Revoked]

Clause 17.48B: inserted, on 7 August 2014, by clause 35 of the Electricity Industry Participation Code Amendment (Extended Reserve) 2014.

Clause 17.48B: revoked, on 5 October 2017, by clause 581 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### *Transitional provisions relating to Part 9*

#### 17.49 System operator rolling outage plan

A system operator rolling outage plan issued by the Commission immediately before this Code came into force, is deemed to be the **system operator rolling outage plan** prepared and published under clause 9.2, and may be substituted by the **system operator** accordingly.

### 17.50 Participant rolling outage plans

- (1) A notice given by the Commission to a specified participant under regulation 8A(2) of the Electricity Governance (Security of Supply) Regulations 2008 that was in force immediately before this Code came into force, is deemed to be a notice given by the **system operator** under clause 9.6(2).
- (2) A participant outage plan submitted to the Commission for approval under regulation 8B(2) of the Electricity Governance (Security of Supply) Regulations 2008, that had not been approved by the Commission immediately before this Code came into force, is deemed to be a **participant rolling outage plan** submitted to the **system operator** for approval under clause 9.7(2).
- (3) A participant outage plan approved by the Commission under regulation 8D of the Electricity Governance (Security of Supply) Regulations 2008 that was in force immediately before this Code came into force, is deemed to be a **participant rolling outage plan** approved by the **system operator** under clause 9.9.
- (4) A revised participant outage plan submitted to the Commission for approval under regulation 8E(b) of the Electricity Governance (Security of Supply) Regulations 2008 that had not been approved by the Commission immediately before this Code came into force, is deemed to be a **participant rolling outage plan** submitted to the **system operator** for approval under clause 9.10(b).
- (5) A participant outage plan approved by the Commission under regulation 8F of the Electricity Governance (Security of Supply) Regulations 2008 immediately before this Code came into force, is deemed to be a **participant rolling outage plan** approved by the **system operator** under clause 9.11.
- (6) A participant outage plan published under regulation 8G of the Electricity Governance (Security of Supply) Regulations 2008 that was in force immediately before this Code came into force, is deemed to be a **participant rolling outage plan** published under clause 9.12.
- (7) Every reference to the Commission in a participant outage plan published under regulation 8G of the Electricity Governance (Security of Supply) Regulations 2008 that was in force immediately before this Code came into force, is deemed to be a reference to the **system operator**.
- (8) Every reference to the Security of Supply Outage Plan in a participant outage plan published under regulation 8G of the Electricity Governance (Security of Supply) Regulations 2008 that was in force immediately before this Code came into force, is deemed to be a reference to the **System Operator Rolling Outage Plan**.
- (9) Every reference to a provision of the Electricity Governance (Security of Supply) Regulations 2008 in a participant outage plan published under regulation 8G of the Electricity Governance (Security of Supply) Regulations 2008 that was in force immediately before this Code came into force, is deemed to be a reference to the corresponding provision of the Code.
- (10) A participant outage plan submitted to the Commission for approval under regulation 8H of the Electricity Governance (Security of Supply) Regulations 2008 that had not

been approved by the Commission immediately before this Code came into force, is deemed to be a **participant rolling outage plan** submitted to the **system operator** for approval under clause 9.13.

- (11) A participant outage plan submitted to the Commission under regulations 8B(2), 8E(b), or 8H of the Electricity Governance (Security of Supply) Regulations 2008 and held by the Commission immediately before this Code came into force, must be made available by the **Authority** to the **system operator** on request by the **system operator**.

#### 17.51 Supply shortage declaration

A supply shortage declaration in force under regulation 9 of the Electricity Governance (Security of Supply) Regulations 2008 immediately before this Code came into force, is deemed to be a **supply shortage declaration** in force under clause 9.14.

#### 17.52 Security of supply direction

A direction in force under regulation 10 of the Electricity Governance (Security of Supply) Regulations 2008 immediately before this Code came into force, is deemed to be a direction in force under clause 9.15.

#### 17.53 Provision of information

- (1) A written notice for information received by a participant under regulation 14 of the Electricity Governance (Security of Supply) Regulations 2008 that had not been responded to immediately before this Code came into force, is deemed to be a written notice for information given by the **system operator** under clause 9.18.
- (2) Any information provided to the Commission under regulation 14 of the Electricity Governance (Security of Supply) Regulations 2008 and held by the Commission immediately before this Code came into force, must be made available by the **Authority** to the **system operator** on request by the **system operator**.

#### *Transitional provisions relating to Part 10*

#### 17.54 Meter installations

- (1) Consultation undertaken by the Commission in respect of a new point of connection under rule 2 of part D of the **rules**, for which the responsibility had not been determined immediately before this Code came into force, is deemed to be consultation by the **Authority** under clause 10.2.
- (2) Advice of an assignment of responsibility for provision of a metering installation made under rule 2 of part D of the **rules** immediately before this Code came into force, is deemed to be advice of an assignment of responsibility for provision of a **metering installation** to the **Authority** made under clause 10.2(2).
- (3) The **Authority** is not required to advise **registered participants** of an assignment under clause 10.2(3) if the Commission advised registered participants of the assignment under rule 2 of part D of the **rules**.

### 17.55 Quantification at points of connection

A method of calculation approved by the Board under rule 3.1.2 of part D of the **rules** in force immediately before this Code came into force, is deemed to be a method of calculation approved by the **Authority** under clause 10.3(a)(ii).

### 17.56 Electricity recorded

- (1) Electricity recorded in accordance with rule 3 of part D of the **rules** immediately before this Code came into force, is deemed to be **electricity** recorded under clause 10.3.
- (2) Electricity recorded in accordance with rule 3.1 of part D of the **rules** immediately before this Code came into force, is deemed to be **electricity** recorded under clause 10.3(a).
- (3) Electricity recorded in accordance with rule 3.3 of part D of the **rules** immediately before this Code came into force, is deemed to be **electricity** recorded under clause 10.3(c).
- (4) Electricity recorded in accordance with rule 3.4 of part D of the **rules** immediately before this Code came into force, is deemed to be **electricity** recorded under clause 10.3(d).

### 17.57 Metering installation tests

- (1) A notice requesting a test of a metering installation given under rule 9 of part D of the **rules**, for which a test had not been carried out immediately before this Code came into force, is deemed to be a notice under clause 10.9(1).
- (2) Any cost of a test payable under rule 9 of part D of the **rules**, if not paid immediately before this Code came into force, is deemed to be a cost payable under clause 10.9(2).
- (3) A direction by the reconciliation manager as to the adjustment, repair or replacement of a metering installation given under rule 11 of part D of the **rules** that had not been complied with immediately before this Code came into force, is deemed to be a direction of the **reconciliation manager** under clause 10.11.

### 17.58 Approved test house

- (1) A person approved as an approved test house by the market administrator under clauses 7.1 to 7.4 of code of practice D2 of part D of the **rules**, whose approval had not been cancelled under rule 7.7 of code of practice D2 of part D of the **rules**, immediately before this Code came into force, is deemed to be an **approved test house** under clause 7(2) of **Code of Practice** 10.2 for the purposes of **Code of Practice** 10.2.
- (2) An application for the renewal of an approval as an approved test house under clauses 7.1 to 7.4 of code of practice D2 of part D of the **rules** that was not determined immediately before this Code came into force, is deemed to be an application for renewal under clause 7(9) of **Code of Practice** 10.2.
- (3) An audit carried out under clause 7.5 of code of practice D2 of part D of the **rules** before this Code came into force, is deemed to be an **audit** carried out under clause 8 of **Code of Practice** 10.2.
- (4) A data logger certified under clause 3.4 of code of practice D3 of part D of the **rules**

immediately before this Code came into force, is deemed to be a **data logger** certified under clause 3.4 of **Code of Practice** 10.3.

- (5) A report of defects, tampering and incidents under clause 10 of code of practice D3 of part D of the **rules** made before this Code came into force, is deemed to be a report under clause 12 of **Code of Practice** 10.3.

#### **17.59 Certification of metering installations**

- (1) A metering installation certified, or deemed by rule 6 of section III of part I of the **rules** to be certified, under clause 4 of code of practice D3 of part D of the **rules** immediately before this Code came into force, is deemed to be a **metering installation certified** under clause 4 of **Code of Practice** 10.3.
- (2) A metering installation that had, or was deemed by rule 5 of section III of part I of the **rules** to have, interim certification under clause 4 of code of practice D3 of part D of the **rules** immediately before this Code came into force, is deemed to be a **metering installation** that has interim **certification** under clause 4 of **Code of Practice** 10.3.
- (3) A metering installation recertified under clause 5.4.2 of code of practice D3 of part D of the **rules** immediately before this Code came into force, is deemed to be a **metering installation recertified** under clause 7 of **Code of Practice** 10.3.

#### **17.60 Inspection requirements**

A variation approved by the market administrator under clause 3 of code of practice D5 of part D of the **rules** that had not expired immediately before this Code came into force, is deemed to be a variation approved by the **market administrator** under clause 3 of **Code of Practice** 10.5.

#### **17.61 Variation of requirements**

A variation granted under code of practice D5 of part D of the **rules** that had not expired immediately before this Code came into force, is deemed to be a variation granted under **Code of Practice** 10.5.

#### *Transitional provisions relating to Part 11*

#### **17.62 Requirement to provide complete and accurate information**

For the purposes of clause 11.2(2), information provided by a participant under part E of the **rules** before this Code came into force, is deemed to be information provided under Part 11.

#### **17.63 ICP identifiers for ICPs**

An ICP identifier that applied to an ICP immediately before this Code came into force, is deemed to be an **ICP identifier** for that **ICP** created under this Code.

#### **17.64 Participants may request that distributors create ICP identifiers for ICPs**

A request by a participant that a distributor create an ICP identifier for an ICP made under rule 4 of part E of the **rules**, on which the distributor had not made a decision

immediately before this Code came into force, is deemed to be a request made under clause 11.5(1).

#### **17.65 Provision of ICP information**

Information provided by a distributor or a trader under rule 6 of part E of the **rules** before this Code came into force, is deemed to be information provided by a **distributor** or a **trader**, as the case may be, under clause 11.7.

#### **17.66 Provision of and changes to ICP and NSP information**

A notification given by a participant under rule 8.2 of part E of the **rules** that had not been processed immediately before this Code came into force, is deemed to be a notification given under clause 11.8(2).

#### **17.67 Network owner notifications**

A notification given by a network owner under rule 8.5 of part E of the **rules** that had not been processed immediately before this Code came into force, is deemed to be a notification given under clause 11.8(5).

#### **17.68 Audits**

- (1) An initial audit completed in accordance with rule 10.1.1 of part E of the **rules** before this Code came into force, is deemed to be an initial **audit** completed in accordance with clause 11.10(1)(a).
- (2) A further audit completed under rules 10.1.2 and 10.1.3 of part E of the **rules** before this Code came into force, is deemed to be a **audit** completed under clauses 11.10(1)(b) or (c), as the case may be.
- (3) An audit carried out by the Board in accordance with rule 10A of part E of the **rules** before this Code came into force, is deemed to be an **audit** carried out by the **Authority** in accordance with clause 11.11.
- (4) An audit report prepared in accordance with rule 10B of part E of the **rules** before this Code came into force, is deemed to be an **audit** report prepared in accordance with clause 11.12.
- (5) Comments on a draft audit report provided by a distributor to an auditor under rules 10B.3 and 10B.4 of part E of the **rules**, in respect of an audit report that had not been finalised immediately before this Code came into force, are deemed to be comments provided by that **distributor** in accordance with clauses 11.12(c) and (d).
- (6) A final audit report provided to a distributor by an auditor under clause 10B.6 of part E of the **rules** before this Code came into force, is deemed to be a final **audit** report provided under clause 11.12(f).
- (7) Any conditions specified in a final audit report provided under clause 10B.6 of part E of the **rules** that were in force immediately before this Code came into force, are deemed to be conditions specified under clause 11.12(f).
- (8) A summary published by the Board under rule 10C.2 of part E of the **rules** before this Code came into force, is deemed to be a summary published by the **Authority** under

clause 11.13(2).

#### **17.69 Process for maintaining shared unmetered load**

- (1) A notification provided by a distributor to the registry under rule 14.2 of part E of the **rules** that had not been processed immediately before this Code came into force, is deemed to be a notification provided under clause 11.14(2).
- (2) A notification provided by a trader to a distributor under rule 14.2A of part E of the **rules** that had not been processed immediately before this Code came into force, is deemed to be a notification provided under clause 11.14(3).
- (3) A notification provided by a distributor to the registry and each trader under rule 14.2B of part E of the **rules** that had not been processed immediately before this Code came into force, is deemed to be a notification provided under clause 11.14(4).
- (4) A notification provided by a distributor to all traders under rule 14.3 of part E of the **rules** that was in force immediately before this Code came into force, is deemed to be a notification provided under clause 11.14(5).

#### **17.70 Timeframes and formats of information**

Any requirements as to timeframes and formats of information specified by the Board in accordance with rule 20 of part E of the **rules** that were in force immediately before this Code came into force, are deemed to be requirements specified by the **Authority** under clause 11.19(2).

#### **17.71 Confirmation of receipt of data**

Confirmation provided by the registry to a participant under rule 22.2 of part E of the **rules** before this Code came into force, is deemed to be confirmation provided under clause 11.21(4).

#### **17.72 Registry must maintain a database of information**

A register of information and audit trail maintained by the registry under rule 22.3 of part E of the **rules** immediately before this Code came into force, is deemed to be a register of information and complete **audit** trail maintained in accordance with clause 11.22.

#### **17.73 Reports from the registry**

- (1) A report published by the registry under rule 23 of part E of the **rules** immediately before this Code came into force, is deemed to be a report published by the **registry** under clause 11.23.
- (2) An agreement between the Board and the registry as to other information that must be included in a report published under rule 23.3 of part E of the **rules** that was in force immediately before this Code came into force, is deemed to be an agreement made under clause 11.23(c).



#### **17.74 Registry reports to specific participants**

- (1) A report delivered by the registry under rule 24.1A of part E of the **rules** before this Code came into force, is deemed to be a report delivered by the **registry** under clause 11.24.
- (2) A request made by the system operator in accordance with rule 24.1.2 of part E of the **rules** that had not been processed immediately before this Code came into force, is deemed to be a request made by the **system operator** under clause 11.25(2).
- (3) A variation requested under rule 24.1.5 of part E of the **rules** that had not been processed immediately before this Code came into force, is deemed to be a variation requested under clause 11.25(5).

#### **17.75 Access to the registry**

- (1) An application made by a participant under rule 25.1 of part E of the **rules** that had not been processed immediately before this Code came into force, is deemed to be an application made under clause 11.28(1).
- (2) Terms and conditions specified by the Board under rule 25.2 of part E of the **rules** that were in force immediately before this Code came into force, are deemed to be terms and conditions specified under clause 11.28(2).
- (3) A report requested by a participant under rule 25.4 of part E of the **rules** that had not been provided immediately before this Code came into force, is deemed to be a report requested by a **participant** under clause 11.28(4).

#### **17.76 Registry notifications**

A notification provided by the registry to affected participants under rule 26 of part E of the **rules** that was in force immediately before this Code came into force, is deemed to be a notification provided under clause 11.29.

#### **17.77 Customer and embedded generator queries**

A request received by a trader or a distributor under rule 28 of part E of the **rules** that the trader or distributor had not responded to immediately before this Code came into force, is deemed to be a request received in accordance with clause 11.31.

#### **17.78 Dispensations**

A dispensation granted by the Board under clause 1.4 of schedule E1 of part E of the **rules** that was in force immediately before this Code came into force, is deemed to be a dispensation granted by the **Authority** under clause 4 of Schedule 11.1.

#### **17.79 Distributors to provide ICP information to registry**

Information provided by a distributor to the registry under clause 2 of schedule E1 of part E of the **rules** that had not been changed by the distributor under clause 2A of schedule E1 of part E of the **rules** immediately before this Code came into force, is deemed to be information provided to the registry under clause 7 of Schedule 11.1.

#### **17.80 Traders to provide ICP information to registry**

Information provided by a trader to the registry under clause 2 of schedule E1 of part E of the **rules** that had not been changed by the trader under clause 2A of schedule E1 of part E of the **rules** immediately before this Code came into force, is deemed to be information provided to the registry under clause 7 of Schedule 11.1.

#### **17.81 Correction of errors in the registry**

A list of ICPs and other information provided by the registry to each participant under clause 3B of schedule E1 of part E of the **rules** that was in force immediately before this Code came into force, is deemed to be a list of **ICPs** and other information provided by the **registry** to **participants** under clause 11 of Schedule 11.1.

#### **17.82 Management of ICP status by distributors and traders**

- (1) The status of an ICP recorded on the registry and managed in accordance with clause 4 of schedule E1 of part E of the **rules** immediately before this Code came into force, is deemed to be the status of the **ICP** recorded on the **registry** and managed by **distributors** or **traders**, as the case may be, in accordance with clauses 12 to 20 of Schedule 11.1, as the case may be.
- (2) A request made by a distributor to a trader under clause 4.3A.1 of schedule E1 of part E of the **rules** that the trader had not responded to immediately before this Code came into force, is deemed to be a request made under clause 15(a) of Schedule 11.1.
- (3) A method of calculation approved by the Board under clause 4.6.2 of schedule E1 of part E of the **rules** that was in force immediately before this Code came into force, is deemed to be a method of calculation approved by the **Authority** under clause 17(2)(b) of Schedule 11.1.
- (4) Advice given by a distributor under clause 4.6A of part E of the **rules** before this Code came into force, is deemed to be advice given by a **distributor** under clause 18 of Schedule 11.1.

#### **17.83 Updating table of loss category codes**

A loss category code entered in the table in the registry under clause 5 of schedule E1 of part E of the **rules** and in force immediately before this Code came into force, is deemed to be a **loss category** code entered in accordance with clause 21 of Schedule 11.1.

#### **17.84 Updating loss factors for loss category codes**

A loss factor entered in the table in the registry under clause 5A of schedule E1 of part E of the **rules** that is in force immediately before this Code came into force, is deemed to be a **loss factor** entered in accordance with clause 22 of Schedule 11.1.

#### **17.85 Updating table of price category codes**

A price category code entered in the table in the registry under clause 6 of schedule E1 of part E of the **rules** that is in force immediately before this Code came into force, is

deemed to be a **price category** code entered in accordance with clause 23 of Schedule 11.1.

#### **17.86 Balancing area information**

- (1) A notification given to the reconciliation manager under clause 7.1 of schedule E1 of part E of the **rules** that was in force immediately before this Code came into force, is deemed to be a notification given under clause 24(1) of Schedule 11.1.
- (2) A notification of a change of information given to the reconciliation manager under clause 7.1A of schedule E1 of part E of the **rules** that was in force immediately before this Code came into force, is deemed to a notification given under clause 24(2) of Schedule 11.1.
- (3) A notification given by the reconciliation manager to the registry of changes to balancing areas under clause 7.2 of schedule E1 of part E of the **rules** that was in force immediately before this Code came into force, is deemed to be a notification given under clause 24(4) of Schedule 11.1.
- (4) A schedule published by the registry under clause 7.3 of schedule E1 of part E of the **rules** that was in force immediately before this Code came into force, is deemed to be a schedule published under clause 24(5) of Schedule 11.1.

#### **17.87 Creation and decommissioning of NSPs and transfer of ICPs**

- (1) A notification given by a participant to the reconciliation manager under clause 8.1.1 of schedule E1 of part E of the **rules** that was in force immediately before this Code came into force, is deemed to be a notification given under clause 25(1)(a) of Schedule 11.1.
- (2) A notification given by the reconciliation manager to the market administrator and affected reconciliation participants under clause 8.1.2 of Schedule E1 of part E of the **rules** that was in force immediately before this Code came into force, is deemed to be a notification given under clause 25(1)(b) of Schedule 11.1.
- (3) A notification given by a distributor under clause 8.1A of schedule E1 of part E of the **rules** that was in force immediately before this Code came into force, is deemed to be a notification given under clause 25(2) of Schedule 11.1.

#### **17.88 Information to be provided if NSPs are created or ICPs are transferred**

- (1) A request made by a participant to the reconciliation manager under clause 9.1 of schedule E1 of part E of the **rules** that had not been responded to and resolved immediately before this Code came into force, is deemed to be a request made under clause 26(1) of Schedule 11.1.
- (2) Information provided by a distributor to the reconciliation manager under clause 9.3 of schedule E1 of part E of the **rules** before this Code came into force, is deemed to be information provided under clause 26(3) of Schedule 11.1.
- (3) A notification given by a distributor to the reconciliation manager under clause 9.4 of schedule E1 of part E of the **rules** that was in force immediately before this Code came into force, is deemed to be a notification given under clause 26(4) of Schedule 11.1.

#### **17.89 Information to be provided if ICPs become NSPs**

A notification given by a distributor to traders under clause 10 of schedule E1 of part E of the **rules** that was in force immediately before this Code came into force, is deemed to be a notification given under clause 27 of Schedule 11.1.

#### **17.90 Reconciliation manager to allocate new identifiers**

An NSP identifier allocated by the reconciliation manager under clause 11 of schedule E1 of part E of the **rules** and in force immediately before this Code came into force, is deemed to be an NSP identifier allocated under clause 28 of Schedule 11.1.

#### **17.91 Obligations concerning change in network owner**

A notification given by a network owner under clause 12 of schedule E1 of part E of the **rules** that was in force immediately before this Code came into force, is deemed to be a notification given under clause 29 of Schedule 11.1.

#### **17.92 Reconciliation manager to advise registry**

- (1) Advice given by the reconciliation manager to the registry under clause 13.1 of schedule E1 of part E of the **rules** before this Code came into force, is deemed to be advice given under clause 30(1) of Schedule 11.1.
- (2) A schedule published by the registry under clause 13.2 of schedule E1 of part E of the **rules** that was in force immediately before this Code came into force, is deemed to be a schedule published by the **registry** under clause 30(2) of Schedule 11.1.

#### **17.93 Transfer of ICPs between distributors' networks**

- (1) A notification given by a distributor to the market administrator under clause 2 of schedule E1A of part E of the **rules** that was in force immediately before this Code came into force, is deemed to be a notification given under clause 2 of Schedule 11.2.
- (2) Confirmation given by a distributor to the market administrator under clause 5 of schedule E1A of part E of the **rules** before this Code came into force, is deemed to be confirmation given under clause 5 of Schedule 11.2.
- (3) A validated meter reading or permanent estimate taken by a reconciliation participant under clause 11 of schedule E1A of part E of the **rules** before this Code came into force, is deemed to be a validated meter reading or permanent estimate taken under clause 11 of Schedule 11.2.
- (4) An authorisation given by the Board to the reconciliation manager under clause 12 of schedule E1A of part E of the **rules** and in force immediately before this Code came into force, is deemed to be an authorisation given by the **Authority** under clause 12 of Schedule 11.2.

#### **17.94 Standard switching process for ICPs with non half-hour metering and unmetered ICPs**

- (1) A period identified by a gaining trader under clause 1.1B.1 of schedule E2 of part E of the **rules** before this Code came into force, is deemed to be a period identified under clause 1(2)(a) of Schedule 11.3.
- (2) An arrangement deemed to come into effect under clause 1.1B.2 of schedule E2 of part E of the **rules** before this Code came into force, is deemed to be an arrangement deemed to come into effect under clause 1(2)(b) of Schedule 11.3.
- (3) Advice given to the registry under clause 1.1 of schedule E2 of part E of the **rules** before this Code came into force, is deemed to be advice given under clause 2 of Schedule 11.3.
- (4) An event date established by a losing trader under clause 1.2 of schedule E2 of part E of the **rules** before this Code came into force, is deemed to be an event date established under clause 3 of Schedule 11.3.
- (5) Acknowledgment of a switch request, final information, or a request for withdrawal of a switch provided by a losing trader under clause 1.2 of schedule E2 of part E of the **rules** before this Code came into force, is deemed to be an acknowledgement, final information, or request for withdrawal of a switch, as the case may be, provided under clause 3 of Schedule 11.3.
- (6) Information provided by a losing trader under clause 1.3 of schedule E2 of part E of the **rules** before this Code came into force, is deemed to be information provided by a losing trader under clause 5 of Schedule 11.3.
- (7) A dispute of a validated meter reading or permanent estimate raised under clause 1.4.2 of schedule E2 of part E of the **rules** that had not been resolved immediately before this Code came into force, is deemed to be a dispute under clause 6(b) of Schedule 11.3.
- (8) A changed validated meter reading or permanent estimate provided under clause 1.4.2 of schedule E2 of part E of the **rules** before this Code came into force, is deemed to be a changed validated meter reading or permanent estimate provided under clause 6(b) of Schedule 11.3.
- (9) A notice given by a losing trader under clause 1.4.2.1 or 1.4.2.2 of schedule E2 of part E of the **rules** that was in force immediately before this Code came into force, is deemed to be a notice given under clause 6(b)(i) or (ii) of Schedule 11.3.
- (10) A dispute notified under clause 1.5 of schedule E2 of part E of the **rules** that had not been resolved immediately before this Code came into force, is deemed to be a dispute under clause 7 of Schedule 11.3.

#### **17.95 Switch move process for ICPs with non half-hour metering and unmetered ICPs**

- (1) A period identified by a gaining trader under clause 2.1B.1 of schedule E2 of part E of the **rules** before this Code came into force, is deemed to be a period identified under clause 8(2)(a) of Schedule 11.3.
- (2) An arrangement deemed to come into effect under clause 2.1B.2 of schedule E2 of part E of the **rules** before this Code came into force, is deemed to be an arrangement deemed to come into effect under clause 8(2)(b) of Schedule 11.3.

- (3) Advice given to the registry under clause 2.1 of schedule E2 of part E of the **rules** before this Code came into force, is deemed to be advice given under clause 9 of Schedule 11.3.
- (4) A proposed event date confirmed or set by a losing trader under clause 2.2 of schedule E2 of part E of the **rules** before this Code came into force, is deemed to be an event date confirmed or set under clause 10 of Schedule 11.3.
- (5) Acknowledgment of a switch move, final information, or a request for withdrawal of a switch provided by a losing trader under clause 2.2 of schedule E2 of part E of the **rules** before this Code came into force, is deemed to be an acknowledgement, final information, or request for a switch move, as the case may be, provided under clause 10 of Schedule 11.3.
- (6) Information provided by a losing trading trader under clause 2.3 of schedule E2 of part E of the **rules** before this Code came into force, is deemed to be information provided by a losing trader under clause 11 of Schedule 11.3.
- (7) A dispute of a validated meter reading or permanent estimate raised under clause 2.4.2 of schedule E2 of part E of the **rules** that had not been resolved immediately before this Code came into force, is deemed to be a dispute under clause 12(2)(b) of Schedule 11.3.
- (8) A changed validated meter reading or permanent estimate provided under clause 2.4.2 of schedule E2 of part E of the **rules** before this Code came into force, is deemed to be a changed validated meter reading or permanent estimate provided under clause 12(3) of Schedule 11.3.
- (9) A notice given by a losing trader under clause 2.4.2 of schedule E2 of part E of the **rules** that was in force immediately before this Code came into force, is deemed to be a notice given under clause 12(3) of Schedule 11.3.
- (10) A dispute notified under clause 2.4.2.1 of schedule E2 of part E of the **rules** that had not been resolved immediately before this Code came into force, is deemed to be a dispute under clause 12(3)(i) of Schedule 11.3.

#### **17.96 Half-hour switching process**

- (1) A period identified by a gaining trader under clause 3.1A.1 of schedule E2 of part E of the **rules** before this Code came into force, is deemed to be a period identified under clause 13(2)(a) of Schedule 11.3.
- (2) An arrangement deemed to come into effect under clause 3.1A.2 of schedule E2 of part E of the **rules** before this Code came into force, is deemed to be an arrangement deemed to come into effect under clause 13(2)(b) of Schedule 11.3.
- (3) Advice given to the registry under clause 3.2 of schedule E2 of part E of the **rules** before this Code came into force, is deemed to be advice given under clause 14 of Schedule 11.3.
- (4) Information provided by a losing trader under clause 3.3 of schedule E2 of part E of the **rules** before this Code came into force, is deemed to be information provided by a losing trader under clause 15 of Schedule 11.3.

- (5) A notice given to the registry under clause 3.4 of schedule E2 of part E of the **rules** that was in force immediately before this Code came into force, is deemed to be a notice given under clause 16 of Schedule 11.3.

#### **17.97 Withdrawal of switch requests**

- (1) Codes for withdrawing a switch request determined and published by the Board under clause 4.1 of schedule E2 of part E of the **rules** before this Code came into force, are deemed to be codes determined and published by the **Authority** under clause 18(b) of Schedule 11.3.
- (2) Information provided to the registry under clause 4.2 of schedule E2 of part E of the **rules** immediately before this Code came into force, is deemed to be information provided under clause 18(c) of Schedule 11.3.
- (3) A notification given by a trader under clause 4.3 of schedule E2 of part E of the **rules** that was in force immediately before this Code came into force, is deemed to be a notification given under clause 18(d) of Schedule 11.3.
- (4) A rejection notification given by the registry under clause 4.3 of schedule E2 of part E of the **rules** for a switch withdrawal request that had not been resolved immediately before this Code came into force, is deemed to be a rejection notification given under clause 18(d) of Schedule 11.3.
- (5) A switch withdrawal request resubmitted by a trader under clause 4.4 of schedule E of part E of the **rules** that had not been resolved immediately before this Code came into force, is deemed to be a switch withdrawal request resubmitted under clause 18(e) of Schedule 11.3.
- (6) A request that a switch request be withdrawn made under clause 4.5 of schedule E2 of part E of the **rules** that had not been resolved immediately before this Code came into force, is deemed to be a request made under clause 18(f) of Schedule 11.3.

#### **17.98 Participants to use file formats**

- (1) File formats determined and published by the Board under clause 5.1 of schedule E2 of part E of the **rules** that were in force immediately before this Code came into force, are deemed to be file formats determined and published by the **Authority** under clause 19 of Schedule 11.3.

#### **17.99 Method of exchanging files**

- (1) Consultation carried out under clause 5.2 of schedule E2 of part E of the **rules** before this Code came into force, is deemed to be consultation carried out under clause 20(1) of Schedule 11.3.
- (2) A method by which participants must exchange information in file formats determined and published by the Board under clause 5.2 of schedule E2 of part E of the **rules** that were in force immediately before this Code came into force, are deemed to be methods and file formats determined and published by the **Authority** under clause 20 of Schedule 11.3.

### **17.100 Costs of interrogation or estimation**

The costs of an interrogation or validated meter reading or permanent estimate carried out in accordance with clause 1.3.2 or clause 2.2.2 of schedule E2 of part E of the **rules** before this Code came into force, are deemed to be costs for the purposes of clause 21 of Schedule 11.3.

### **17.101 Registry notifications**

A notification provided by the registry to participants under clause 5.4 of schedule E2 of part E of the **rules** that was in force immediately before this Code came into force, is deemed to be a notice provided by the registry to participants under clause 22 of Schedule 11.3.

### **17.101A Switching under Schedule 11.3**

- (1) This clause applies to an arrangement between a **trader** and a **customer** or **embedded generator** to carry out a switch in relation to an **ICP** under Schedule 11.3.
- (2) If the arrangement came into effect before 9 October 2015 and the relevant switch had not been completed by that date, the switch must be completed in accordance with Schedule 11.3 as amended by the Electricity Industry Participation Code Amendment (ICP Switching) 2014 and the Electricity Industry Participation Code Amendment (ICP Switching) 2015.

Clause 17.101A: inserted, on 9 October 2015, by clause 28 of the Electricity Industry Participation Code Amendment (ICP Switching) 2014. Clause 17.101A(2): amended, on 9 October 2015, by clause 17 of the Electricity Industry Participation Code Amendment (ICP Switching) 2015.

## *Transitional provisions relating to Part 12*

### **17.102 Discretion to waive requirements**

An agreement by the Board to waive rule requirements under rule 2.1 of section I of part F of the **rules** that was in force immediately before this Code came into force, is deemed to be an agreement by the **Authority** to waive Code requirements under clause 12.2.

### **17.103 Benchmark agreements to be default transmission agreements**

A process commenced but not completed under rule 3.1.3 of section II of part F of the **rules** immediately before this Code came into force, must be continued and completed under clause 12.10 and any action taken, information provided, or advice given under that rule is deemed to be an action taken, information provided, or advice given, as the case may be, under clause 12.10.

### **17.104 Changes to the connection assets under default transmission agreements**

A process commenced but not completed under rule 3.1.5 of section II of part F of the **rules** immediately before this Code came into force, must be continued and completed under clause 12.12, and any action taken, information provided, or advice given under



that rule is deemed to be an action taken, information provided, or advice given, as the case may be, under clause 12.12.

#### **17.105 Expiry or termination of transmission agreements**

A process commenced but not completed under rule 3.1.6 of section II of part F of the **rules** immediately before this Code came into force, must be continued and completed under clause 12.13, and any action taken, information provided, or advice given under that rule is deemed to be an action taken, information provided, or advice given, as the case may be, under clause 12.13.

#### **17.106 Transmission agreement to be provided and published**

- (1) A transmission agreement provided by Transpower to the Board under rule 3.2.2.1 of section II of part F of the **rules** immediately before this Code came into force, is deemed to be a **transmission agreement** provided by **Transpower** to the **Authority** under clause 12.15(1).
- (2) A transmission agreement published under rule 3.2.2.3 of section II of part F of the **rules** immediately before this Code came into force, is deemed to be a **transmission agreement** published under clause 12.15(3).

#### **17.107 Review of Connection Code**

A review initiated by the Board under rule 3.3.10 of section II of part F of the **rules** but not completed immediately before this Code came into force, is deemed to be a review initiated by the **Authority** under clause 12.18.

#### **17.108 Increased services and reliability**

A certification given under rule 5.1 of section II of part F of the **rules** immediately before this Code came into force, is deemed to be a certification given under clause 12.35.

#### **17.109 Approval of decreased services and reliability**

An approval given under rule 5.2 of section II of part F of the **rules** that was in force immediately before this Code came into force, is deemed to be an approval given under clause 12.36.

#### **17.110 Approval of other variations to terms of benchmark agreement**

An approval given under rule 5.4 of section II of part F of the **rules** that was in force immediately before this Code came into force, is deemed to be an approval given under clause 12.38.

#### **17.111 Customer specific value of unserved energy**

- (1) An application made but not approved or declined under rule 5.5.1 of section II of part F of the **rules** immediately before this Code came into force, is deemed to be an application made under clause 12.39(2).

- (2) A provisional approval of a value of unserved energy given under rule 5.5.3 of section II of part F of the **rules** that was in force immediately before this Code came into force, is deemed to be a provisional approval given under clause 12.39(4).
- (3) An approval given under rule 5.5.4.1 of section II of part F of the **rules** that was in force immediately before this Code came into force, is deemed to be an approval given under clause 12.39(5)(a).

#### **17.112 Replacement and enhancement of shared connection assets**

A process commenced but not completed under rule 5.6 of section II of part F of the **rules** immediately before this Code came into force, must be continued and completed under clause 12.37, and any notification, proposal, or attempt to reach agreement made under that rule is deemed to be a notification, proposal, or attempt to reach an agreement, as the case may be, under clause 12.40.

#### **17.113 Resolution of disputes relating to transmission agreements**

- (1) A dispute process commenced but not determined under rule 6 of section II of part F of the **rules** immediately before this Code came into force, is deemed to be a dispute process commenced under clause 12.45.
- (2) A determination made by the Rulings Panel under rule 6.3 of section II of part F of the **rules** before this Code came into force, is deemed to be a determination made by the **Rulings Panel** under clause 12.47.

#### **17.114 Review of benchmark agreement**

A review initiated by the Board under rule 7 of section II of part F of the **rules** but not completed immediately before this Code came into force, is deemed to be a review initiated by the **Authority** under clause 12.28.

#### **17.115 Existing agreements**

A request made by the Board under rule 8.2.1 of section II of part F of the **rules** that had not been complied with immediately before this Code came into force, is deemed to be a request made by the **Authority** under clause 12.50.

#### **17.116 Transpower to publish grid reliability report**

The grid reliability report last published by Transpower under rule 12A.1 of section III of part F of the **rules** immediately before this Code came into force, is deemed to be the **grid reliability report** published by **Transpower** under clause 12.76(1).

#### **17.117 Issues paper**

- (1) An issues paper prepared under rule 4 of section IV of part F of the **rules** and in force immediately before this Code came into force, is deemed to be an issues paper prepared under clause 12.81.
- (2) A date notified under rule 5.1 of section IV of part F of the **rules** before this Code came into force, is deemed to be a date notified under clause 12.82(1).

- (3) A submission received on an issues paper under rule 5.2 of section IV of part F of the **rules** that had not been considered immediately before this Code came into force, is deemed to be a submission received under clause 12.82(2).

#### **17.118 Development of transmission pricing methodology**

The process and guidelines for the development of the transmission pricing methodology last published by the Board under rule 6 of section IV of part F of the **rules** immediately before this Code came into force, are deemed to be the process and guidelines for the development of **transmission pricing methodology** published by the **Authority** under clause 12.83.

#### **17.119 Development of transmission prices**

The transmission prices last developed and published by Transpower under rule 9.2 of section IV of part F immediately before this Code came into force, are deemed to be the transmission prices developed and published under clause 12.96.

#### **17.120 Audit of transmission prices**

- (1) An auditor appointed under rule 9.3.1 of section IV of part F of the **rules** who had not yet completed their review immediately before this Code came into force, is deemed to have been appointed under clause 12.97(1).
- (2) If Transpower had received an auditor's report but had not yet responded to the report under rule 9.4 of section IV of part F of the **rules** immediately before this Code came into force, **Transpower** must be provided with the opportunity to respond to the **auditor's** report in accordance with clause 12.98.
- (3) If an auditor had received a response from Transpower but had not yet provided certification under rule 9.5 of section IV of part F of the **rules** immediately before this Code came into force, the **auditor** must provide certification to the **Authority** in accordance with clause 12.99(1).

#### **17.121 Review of approved transmission pricing methodology**

A proposed variation to a transmission pricing methodology submitted under rule 11.1 of section IV of part F of the **rules** but not reviewed immediately before this Code came into force, is deemed to be a proposed variation submitted under clause 12.85.

#### **17.122 Transpower to identify interconnection branches, and propose service measures and levels**

- (1) Information provided under rule 2 of section VI of part F of the **rules** immediately before this Code came into force, is deemed to be information provided under clause 12.107.
- (2) A request made under rule 2.6 of section IV of part F of the **rules** that had not been complied with immediately before this Code came into force, is deemed to be a request made under clause 12.107(6).

- (3) Information and diagrams that had been published under rule 2.7 of section VI of part F of the **rules** and that had not been consulted on immediately before this Code came into force, is deemed to be the interconnection asset capacity and grid configuration published for consultation under clause 12.108.

**17.123 Transpower to propose reliability investments**

A process commenced but not completed under rule 6.1 of section VI of part F of the **rules** immediately before this Code came into force, is deemed to be a process commenced under clause 12.114.

**17.124 Transpower to propose economic investments**

The grid economic investment report last published under rule 6.2 of section VI of part F of the **rules** immediately before this Code came into force, is deemed to be the previous **grid economic investment report** for the purposes of clause 12.115(2).

**17.125 Information on capacities of individual interconnection assets**

The information last published under rule 7 of section VI of part F of the **rules** immediately before this Code came into force, is deemed to be the information published under clause 12.116.

**17.126 Transpower to provide and publish annual report on interconnection asset capacity and grid configuration**

The annual report last provided to the Board and published under rule 9 of section VI of part F of the **rules** immediately before this Code came into force, is deemed to have been provided to the **Authority** and published under clause 12.118.

**17.127 Transpower to report on availability and reliability**

The information most recently published and provided to the Board under rule 10.8 of section VI of part F of the **rules** immediately before this Code came into force, is deemed to be information published and provided to the **Authority** under clause 12.127.

*Transitional provisions relating to Part 13*

**17.128 Requests for rulebook information**

A **participant** who discovers, that any information disclosed by it to any person under part G of the **rules** before this Code came into force was misleading, deceptive, or incorrect, must immediately disclose the corrected information to the person who originally received the misleading, deceptive, or incorrect information.

**17.129 Approval process for industrial co-generating stations**

- (1) An application to the Board to be an industrial co-generating station in accordance with rule 3 of section I of part G of the **rules** that was not approved, declined, or rescinded immediately before this Code came into force, is deemed to be an application to the

**Authority** to be an **industrial co-generating station** under clause 13.3 and must be continued and completed.

- (2) A generator approved as an industrial co-generating station by the Board under rule 3 of section I or schedule G9 of part G of the **rules**, whose approval had not been rescinded immediately before this Code came into force, is deemed to be a **generator** approved by the **Authority** as an **industrial co-generating station** under clause 13.3 and Schedule 13.4.
- (3) A notice issued by the Board of an amendment or rescission of an approval under rule 3 of section I or clause 14 of schedule G9 of part G of the **rules** immediately before this Code came into force, where the amendment or rescission is to take effect after this Code came into force, is deemed to be a notice issued by the **Authority** under clause 13.3 and clause 14 of Schedule 13.4.

#### **17.129A Transitional provisions for co-generators**

An approval granted by the **Authority** or deemed to have been granted under Schedule 13.4 and in effect immediately before 27 May 2015 is deemed to be an approval granted by the **Authority** under clause 8(1)(a)(i) of Schedule 13.4 of 1 or more **generating units** as a **type A industrial co-generating station**.

Clause 17.129A: inserted, on 27 May 2015, by clause 30 of the Electricity Industry Participation Code Amendment (Industrial Co-generation Dispatch Arrangements) 2015.

#### **17.130 Offer preparation by generators**

- (1) An offer submitted by a generator under rule 3.1 of section II of part G of the **rules** on the day immediately before the day on which this Code came into force for the **trading day** on which this Code came into force, made in accordance with section II of part G of the **rules**, is deemed to be an **offer** by a **generator** under clause 13.6, subject to any revision of that **offer** made in accordance with part G of the **rules** or Part 13 of this Code, as applicable.
- (2) An offer submitted by an embedded generator under rule 3.2 of section II of part G of the **rules** on the day immediately before the day on which this Code came into force for the **trading day** on which this Code came into force, made in accordance with section II of part G of the **rules**, is deemed to be an **offer** by an **embedded generator** under clause 13.6, subject to any revision of that **offer** made in accordance with part G of the **rules** or Part 13 of this Code, as applicable.
- (3) An offer submitted by an intermittent generator under rule 3.13 of section II of part G of the **rules** on the day immediately before the day on which this Code came into force for the **trading day** on which this Code came into force, made in accordance with section II of part G of the **rules**, is deemed to be an **offer** by an **intermittent generator** under clause 13.6, subject to any revision of that **offer** made in accordance with section II of part G of the **rules** or Part 13 of this Code as the case may be.

#### **17.131 Generators' notice of initial offer**

Notice of an initial offer in respect of a generating plant given under rule 3.2 of the section II of part G of the **rules** and in force immediately before this Code came into

force, is deemed to be notice of an initial **offer** under clause 13.6(4).

#### **17.132 Bids by purchasers**

A bid submitted by a purchaser under rule 3.3 of section II of part G of the **rules** on the day immediately before the day on which this Code came into force for the **trading day** on which this Code came into force, made in accordance with section II of part G of the **rules**, is deemed to be a **bid** by a **purchaser** under clause 13.7, subject to any revision of that **bid** made in accordance with part G of the **rules** or Part 13 of this Code, as applicable.

#### **17.133 Purchasers' notice of initial bids**

Notice of an initial bid in respect of a generating plant given under rule 3.4.1 of the section II of part G of the **rules** and in force immediately before this Code came into force, is deemed to be notice of an initial **bid** under clause 13.7.

#### **17.134 Bids and offers are valid until cancelled**

A purchaser or generator who failed to make a bid or offer under rules 3.1 to 3.4 of section II of part G of the **rules** by 1300 hours on the day immediately before the day on which this Code came into force for the **trading day** on which this Code came into force, is deemed to have made the same **bid** or **offer** for the **trading day** on which this Code came into force as that made in respect of the same **trading period** of the **trading day** immediately before the day on which this Code came into force, until that **bid** or **offer** is cancelled or revised by the **purchaser** or **generator** in accordance with rules 3.14 to 3.20 of section II of part G of the **rules** or clauses 13.17 to 13.21 of this Code as the case may be.

#### **17.135 Offers made by unit of plant**

Notice given under rule 3.8 of section II of part G of the **rules**, that was in force immediately before this Code came into force, is deemed to be notice given under clause 13.11.

#### **17.136 New, revised or cancelled bid or offer inside the 2 hour period**

- (1) A report of a new, revised, or cancelled bid made to the Board under rule 3.19 of section II of part G of the **rules** before this Code came into force, for any **trading period** on the **trading days** immediately before and on which this Code came into force, is deemed to be a report made to the **Authority** under clause 13.21.
- (2) A report of a revised or cancelled bid made to the Board under rule 3.19 of section II of part G of the **rules** that had not been determined by the Board under rule 3.20 of section II of part G of the **rules** immediately before this Code came into force, is deemed to be a report to the **Authority** under clause 13.21.

#### **17.137 Backup procedures if the information system is unavailable**

Backup procedures specified by the market administrator under rules 3.25, 5.14, 6.23,

or 7.3 to 7.5 of section II, 3.10 to 3.12 of section III, or 3.36 of section V of part G of the **rules** immediately before this Code came into force, are deemed to be backup procedures specified by the **market administrator** for the purposes of clauses 13.23, 13.36, 13.52, 13.55 and 13.67 and 13.191.

#### **17.138 Backup procedures**

Backup procedures specified by the market administrator under rule 5.11 of section V of part G of the **rules** immediately before this Code came into force, are deemed to be backup procedures specified by the **market administrator** under clause 13.211.

#### **17.139 Plant with special circumstance**

An offer submitted in respect of an automatic control plant under rule 3.26 of section II of part G of the **rules** immediately before this Code came into force, is deemed to be an **offer** submitted under clause 13.24.

#### **17.140 Retention of bids and offers**

The **system operator** must retain records of all bids and offers for electricity submitted by participants and all reserve offers submitted by ancillary service agents under section II of part G of the **rules**, including all revised bids and offers and revised reserve offers, all cancelled bids and offers and all cancelled reserve offers.

#### **17.141 Special treatment of some grid exit points**

- (1) An application to the Board under rule 4 of section II of part G of the **rules** that was not determined by the Board immediately before this Code came into force, is deemed to be an application to the **Authority** under clause 13.28.
- (2) 2 or more grid exit points approved to be, or deemed to be approved to be, treated as 1 grid exit point under rule 4 of section II of part G of the **rules** immediately before this Code came into force, are deemed to be approved to be treated as 1 **grid exit point** under clause 13.28.

#### **17.142 Standing data to be provided to the system operator**

Standing data provided to the system operator under rules 5.1 to 5.3 of section II of part G of the **rules** before this Code came into force, is deemed to be standing data provided under clauses 13.29 to 13.31, as the case may be.

#### **17.143 Transmission grid capability information to be updated**

The period of time agreed between the system operator and each grid owner for updates to information described in rules 5.1 to 5.3 and rule 5.5 of section II of part G of the **rules** immediately before this Code came into force for the purposes of rule 5.4 of section II of part G of the **rules**, is deemed to be the period of time agreed between the **system operator** and each **grid owner** for updates to information described in clauses 13.29 to 13.31 and 13.33 as the case may be, for the purpose of clause 13.32.

**17.144 Grid owners must submit revised information to the system operator**

Any revised information submitted to the system operator in accordance with rule 5.5 of section II of part G of the **rules** immediately before this Code came into force for any **trading period** immediately after this Code came into force, is deemed to be revised information submitted under clause 13.33, and may be varied in accordance with rules 5.6 to 5.9 of section II of the part G of the **rules** or clause 13.34, as the case may be.

**17.145 Changes may be made within 2 hours prior to the trading period**

A report made to the Board under rule 5.8 of section II of part G of the **rules** immediately before this Code came into force for any **trading period** on the **trading day** immediately before or on which this Code came into force, is deemed to be a report to the **Authority** under clause 13.34(3).

**17.146 System operator to approve ancillary service agents wishing to make reserve offers**

A contract between an ancillary service agent and the system operator to provide reserve offers entered into in accordance with rule 6.1 of section II of part G of the **rules** that was in force immediately before this Code came into force, is deemed to be a contract entered into in accordance with clause 13.37.

**17.147 Ancillary service agents to submit reserve offers to the system operator**

- (1) A reserve offer submitted by an ancillary service agent under rules 6.2 to 6.4 of section II of part G of the **rules** immediately before this Code came into force, for the **trading day** on which this Code came into force, made in accordance with part G of the **rules**, is deemed to be a **reserve offer** by an **ancillary service agent** under clause 13.38, subject to any revision or cancellation of that **reserve offer** made in accordance with part G of the **rules** or Part 13 of this Code, as applicable.
- (2) A report made to the Board under rule 5.8 of section II of part G of the **rules**, not determined by the Board immediately before this Code came into force, is deemed to be a report to the **Authority** under clause 13.34(3).

**17.148 Revised reserve offer inside the 2 hour period**

- (1) A report of a new, revised, or cancelled reserve offer to the Board under rule 6.16 of section II of part G of the **rules** before this Code came into force, for any **trading period** on the **trading days** immediately before or on which this Code came into force, is deemed to be a report to the **Authority** under clause 13.49.
- (2) A report of a new, revised or cancelled bid under rule 6.18 of section II of part G not determined by the Board immediately before this Code came into force, is deemed to be a report under clause 13.50.

**17.149 Availability of final bids and final offers**

All information made available under rule 7 of section II of part G of the **rules** immediately before this Code came into force, is deemed to be information made



available under clause 13.55.

#### **17.150 Process for preparing a pre-dispatch schedule**

- (1) A pre-dispatch schedule for any schedule period for the **trading day** on which this Code came into force prepared in accordance with rules 3.1 to 3.5 of section III of part G of the **rules** immediately before this Code came into force, is a **pre-dispatch schedule** under clause 13.58.
- (2) In preparing **pre-dispatch schedules** for the **trading day** on which this Code came into force, the **system operator** may use the most recent information received under section II and schedule G6 of part G of the **rules** before this Code came into force, and any information received under Part 13 or Schedule 13.3 of this Code, as applicable.

#### **17.151 Block dispatch may occur**

- (1) A notification provided to the system operator under rules 3.6 to 3.62 of section III of part G of the **rules** immediately before this Code came into force, in respect of **trading periods** that occur after this Code came into force, is deemed to be a notification under clause 13.60 in respect of those **trading periods**.
- (2) An agreement or deemed agreement to treat a group of generating stations as a block dispatch group under rule 3.6 of section III of part G of the **rules** that was in force immediately before this Code came into force, is deemed to be an agreement under clause 13.60.

#### **17.152 System operator to notify block security constraints**

A notification of block security constraints under rule 3.6.5 of section III of part G of the **rules** immediately before this Code came into force, which applies to **trading periods** after this Code came into force, is deemed to be a notification of **block security constraints** under clause 13.61(1).

#### **17.153 Station dispatch may occur**

- (1) A notification given, or deemed by rule 4.2 of section IV of part I of the **rules** to be given, by a generator to the system operator in accordance with rule 3.9 of section III of part G of the **rules** before this Code came into force, which applies to a period after this Code came into force, is deemed to be a notification given under clause 13.64.
- (2) An election notified, or deemed by rule 4.2 of section IV of part I of the **rules** to be notified, by the system operator to a generator and the clearing manager in accordance with rule 3.9 of section III of part G of the **rules** before this Code came into force, which applies to a period after this Code came into force, is deemed to be an election notified under clause 13.64.

#### **17.154 System operator to notify security constraints**

A notification of a dispatch made in accordance with rules 3.91 and 3.92 of section III of part G of the **rules** that was in force immediately before this Code came into force, which applies to a period after this Code came into force, is deemed to be a notice under

clause 13.65.

**17.155 Generator notifies change from station to unit dispatch**

A notification of a change from a station dispatch group to a generating unit under rule 3.9.3 of section III of part G of the **rules** that was in force immediately before this Code came into force, which applies to a period after this Code came into force, is deemed to be a notification under clause 13.66.

**17.156 Dispatch instructions**

- (1) Dispatch instructions issued to a generator under rule 4.6 of section III of part G of the **rules** immediately before this Code came into force, which apply to a period after this Code came into force, are deemed to be **dispatch instructions** issued under clause 13.73.
- (2) Dispatch instructions issued to an ancillary service agent under rule 4.7 of section III of part G of the **rules** immediately before this Code came into force, which apply to a period after this Code came into force, are deemed to be **dispatch instructions** issued under clause 13.74.

**17.157 Market administrator to appointment person to monitor and assess demands side participation**

A person appointed by a market administrator to monitor and access real time prices under rules 7.8 and 7.9 of section III of part G of the **rules** immediately before this Code came into force, is deemed to be a person appointed to monitor and assess **real time prices** under clause 13.93.

**17.158 Grid emergency**

A grid emergency declared under rules 8.1 and 8.2 of section III of part G of the **rules** immediately before this Code came into force, which applies to a period after this Code came into force, is deemed to be a **grid emergency** declared under clause 13.97.

**17.159 The effect of a grid emergency in total quantities bid**

A revision made under rule 8.4 of section III of part G of the **rules** that was in force immediately before this Code came into force, is deemed to be a revision made under clause 13.99.

**17.160 Reporting requirements in respect of grid emergencies**

A report made to the Board under rules 8.6 and 8.7 of section III of part G of the **rules** and not resolved by the Board immediately before this Code came into force, is deemed to be a report made to the **Authority** under clause 13.101.

**17.161 Reporting obligation of the system operator**

A report by the system operator under rule 9 of section II of part G of the **rules** that was in force immediately before this Code came into force, is deemed to be a report under

clause 13.102.

#### **17.162 System operator to publish information**

Information that a system operator is responsible for publishing under rules 10.1 to 10.7 of section III of part G of the **rules** that had not been published immediately before this Code came into force, is deemed to be information the **system operator** is responsible for publishing under clauses 13.103 to 13.106.

#### **17.163 Run dispatch options**

- (1) An authorisation by the clearing manager of a generator's bid under rule 2.1 and 2.2 of section IV of part G of the **rules** before this Code came into force, for a period after this Code came into force, is deemed to be an authorisation under clause 3.109.
- (2) A calculation of auction revenue payable by a generator under rules 2.3 and 2.4 of section IV of part G of the **rules** but not paid immediately before this Code came into force, is deemed to be an amount payable by a **generator** under clause 13.110.
- (3) Auction revenue payable to a purchaser under rules 2.6 and 2.7 of section IV of part G of the **rules** but not paid immediately before this Code came into force, is deemed to be **auction revenue** payable under clause 13.112.
- (4) Auction rights acquired under rule 2.8 of section IV of part G of the **rules** immediately before this Code came into force, which relate to a **time block** after this Code came into force, are deemed to be **auction rights** acquired under clause 13.115 and those rights may be exercised in accordance with clause 13.113.

#### **17.164 Clearing manager must conduct auctions**

The format specified by the clearing manager for bidding under rule 3.3 of section IV of part G of the **rules** that was in force immediately before this Code came into force, is deemed to be the format for bidding under clause 13.117(3), until further amended.

#### **17.165 Deadline for auction bids**

An auction bid submitted under rule 3.7 of section IV of part G of the **rules** immediately before this Code came into force for any period after this Code came into force, is deemed to be an **auction bid** submitted under clause 13.121, unless revised or cancelled in accordance with rule 3.8 of section IV of part G of the **rules** or clause 13.122 of this Code, as the case may be.

#### **17.166 Authorisation to successful bidders**

An authorisation issued by the clearing manager under rule 3.15 of section IV of part G of the **rules** immediately before this Code came into force, is deemed to be an authorisation issued by the **clearing manager** under clause 13.129.

#### **17.167 High spring washer price situation**

- (1) Notice of a high spring washer price situation given in accordance with rules 3.6, 3.18, or 3.21 of section V of part G of the **rules** and in force, immediately before this Code

came into force, is deemed to be a notice in accordance with clause 13.144(1), 13.156(1)(e), or 13.159(a)(iii) respectively, and is subject to clause 13.134, unless resolved.

- (2) Provisional prices published under rule 3.11 of section V of part G of the **rules** immediately before this Code came into force, are deemed to be published in accordance with clause 13.149 for the purposes of clause 13.134, unless resolved.
- (3) Provisional reserve prices in accordance with rule 3.12 of section V of part G of the **rules** immediately before this Code came into force, are deemed to be published in accordance with clause 13.150, for the purpose of clause 13.134, unless resolved.
- (4) If revised data had not been provided as required by rule 3.8 of section V of part G of the **rules** immediately before this Code came into force, it is deemed that the revised data has not been provided as required by clause 13.146, for the purpose of clause 13.134.
- (5) If notice required by rule 3.9 of section V of part G of the **rules** had not been given immediately before this Code came into force, it is deemed that no notice has been provided as required by clause 13.147, for the purposes of clause 13.134.

#### **17.168 Preparation of provisional and final prices**

- (1) To calculate **provisional prices, provisional reserve prices, interim prices, interim reserve prices, final prices and final reserve prices** under clause 13.135, the **pricing manager** may use input information provided under rule 3.3 of section V of part G of the **rules** immediately before this Code came into force, as well as the **input information** in clause 13.141, as appropriate.
- (2) To calculate **provisional prices, provisional reserve prices, final prices and final reserve prices** under clause 13.135, the **pricing manager** may use the methodology in schedule G6 of part G of the **rules** as well as methodology in Schedule 13.3, as appropriate.

#### **17.169 Half-hour metering information**

- (1) The manner and form of half-hour metering information stipulated by the pricing manager under rule 3.2.3 of section V of part G of the **rules** immediately before this Code came into force, is deemed to be the manner and form for **half-hour metering information** stipulated by the **pricing manager** under clause 13.138.
- (2) Half-hour metering information provided under rule 3.2.3 of section V of part G of the **rules** that was in force before this Code came into force, is deemed to be **half-hour metering information** provided under clause 13.138.

#### **17.170 Input information**

Input information estimated in accordance with rule 3.3 of section V of part G of the **rules** before this Code came into force, for any period after this Code came into force, is deemed to be estimated **input information** in accordance with clause 13.141.

#### **17.171 Pricing manager to publish interim prices**

A notice published under rule 3.4.1 of section V of part G of the **rules** and in force immediately before this Code came into force, is deemed to be a notice published under clause 13.142(1).

#### **17.172 SCADA situation**

Notice by a grid owner of a SCADA situation under rule 3.5 of section V of part G of the **rules** that was in force immediately before this Code came into force, relating to a period 2 days before this Code came into force or a period after this Code came into force, is deemed to be a notice of a **SCADA situation** in accordance with clause 13.143.

#### **17.173 Metering situation**

Notice by a pricing manager of a metering situation under rules 3.6 and 3.6A of section V of part G of the **rules** that was in force immediately before this Code came into force, relating to a period 2 days before this Code came into force or a period after this Code came into force, is deemed to be notice of a **metering situation** in accordance with clause 13.144(1).

#### **17.174 High spring washer price situation**

Notice by the pricing manager of a high spring washer price situation in accordance with rules 3.6 and 3.6A of section V of part G of the **rules** that was in force immediately before this Code came into force, relating to a period 2 days before this Code came into force or a period after this Code came into force, is deemed to be notice of a **high spring washer price situation** in accordance with clause 13.144(1).

#### **17.175 Requirements if provisional price situation exists**

Revised data given to the pricing manager in accordance with rule 3.8 of section V of part G of the **rules** immediately before this Code came into force, relating to a period 2 days before this Code came into force or any period after this Code came into force, is deemed to be revised data given under clause 13.146.

#### **17.176 Provisional prices and provisional reserve prices**

If notice of a provisional price situation is given immediately before this Code came into force under rules 3.6 to 3.6A of section V of part G of the **rules**, and no revised data is provided in accordance with rule 3.8 of section V of part G and no notice is provided in accordance with rule 3.9 of section V of part G of the **rules** immediately before this Code came into force, no notice is deemed to be given under clauses 13.146 and 13.147 and accordingly clauses 13.149 and 13.150 apply as appropriate.

#### **17.177 Interim prices and provisional prices and provisional reserve prices**

- (1) Interim prices and interim reserve prices in relation to a provisional price situation (other than a high spring washer price situation) published under rule 3.18 of section V

- of part G of the **rules** immediately before this Code came into force, are deemed to be **interim prices** and **interim reserve prices** published under clause 13.156(1)(a).
- (2) Interim prices and interim reserve prices in relation to a high spring washer price situation published under rule 3.18 of section V of part G of the **rules** immediately before this Code came into force, are deemed to be **interim prices** and **interim reserve prices** published under clause 13.156(1)(a).
  - (3) Interim prices and interim reserve prices that do not give rise to a **provisional price situation** published under rule 3.18 of section V of part G of the **rules** immediately before this Code came into force, are deemed to be **interim prices** and **interim reserve prices** published under clause 13.156(1)(b).
  - (4) If an infeasibility situation arises after interim prices and interim reserve prices are published under rule 3.18 of section V of part G of the **rules** before this Code came into force, an **infeasibility situation** is deemed to have arisen under clause 13.156(1)(a).
  - (5) Notice of a high spring washer price situation issued under rule 3.18 of section V of part G of the **rules** and in force immediately before this Code came into force, is deemed to be notice of a **high spring washer price situation** issued under clause 13.156(1)(a).

Clause 17.177(4): amended, on 21 September 2012, by clause 41(1) of the Electricity Industry Participation (Minor Amendments) Code Amendment 2012.

Clause 17.177(5): amended, on 21 September 2012, by clause 41(2) of the Electricity Industry Participation (Minor Amendments) Code Amendment 2012.

#### **17.178 Publish final prices or notice that a high spring washer price situation exists**

- (1) Notice that a high spring washer price situation exists under rule 3.21 of section V of part G of the **rules**, relating to the 2 day period before this Code came into force or any period after this Code came into force, is deemed to be notice that a **high spring washer price situation** exists under clause 13.159.
- (2) Interim prices and interim reserve prices published in accordance with rule 3.21 of section V of part G of the **rules** immediately before this Code came into force, which relate to a 2 day period before this Code came into force or a period after this Code came into force, are deemed to be **interim prices** and **interim reserve prices** published under clause 13.159.

#### **17.179 System operator to apply high spring washer price relaxation factor and give notice**

Notice published under rule 3.21B of section V of part G of the **rules** immediately before this Code came into force, which relates to a period 2 days before this Code came into force or a period after this Code came into force, is deemed to be a notice published under clause 13.161.

#### **17.180 Revised data**

Notice given under rule 3.22 of section V of part G of the **rules** and in force immediately before this Code came into force, is deemed to be notice given under clause 13.163.

**17.181 If a provisional price situation (other than a high spring washer price situation) continues**

- (1) Notice given under rule 3.23 of section V of part G of the **rules** and in force immediately before this Code came into force, is deemed to be notice given under clause 13.164.
- (2) Notice given to the Board under rules 3.24 and 3.25 of section V of part G of the **rules** that was unresolved immediately before this Code came into force, is deemed to be notice to the **Authority** under clause 13.165.

**17.182 Interim pricing period**

- (1) A form received by the pricing manger under rule 3.26D.3 of section V of part G of the **rules** before this Code came into force, is deemed to be a form received by the **pricing manager** under clause 13.170(c).
- (2) Prices published by the pricing manger under rule 3.26E.2 of section V of part G of the **rules** immediately before this Code came into force, are deemed to be prices published under clause 13.171(2).
- (3) A process commenced under rule 3.26G of section V of part G of the **rules** but not completed immediately before this Code came into force, is deemed to be a process commenced under clause 13.173.
- (4) A determination made by the pricing manger that had not been recommended to the Board under rule 3.26H of section V of part G of the **rules** immediately before this Code came into force, is deemed to be a determination to which clause 13.174 applies.
- (5) A recommendation received by the Board under rule 3.26I of section V of part G of the **rules** that had not been accepted or rejected immediately before this Code came into force, is deemed to be a recommendation received by the **Authority** under clause 13.175.
- (6) A notice published under rule 3.26J of section V of part G of the **rules** immediately before this Code came into force, is deemed to be a notice **published** under clause 13.176.
- (7) An action taken by the Board under rule 3.26N of section V of part G of the **rules** immediately before this Code came into force, is deemed to be an action taken by the **Authority** under clause 13.180.
- (8) A request under rule 3.26O of section V of part G of the **rules** that had not been complied with immediately before this Code came into force, is deemed to be a request under clause 13.181.

**17.183 Authority may order delay of publication of final prices**

An order by the Board to delay publication under rule 3.28 of section V of part G of the **rules** that was in force immediately before this Code came into force, is deemed to be an order to delay **publication** under clause 13.184.

**17.184 System operator to give pricing manager a list of model variable failures**

A list of values provided that was in force under rule 3.33 of section V of part G of the

**rules** immediately before this Code came into force, is deemed to be a list of values provided under clause 13.189, effective as at the date set under the **rules**.

**17.185 Calculate constrained off amounts**

Calculation of constrained off amounts under rule 4.3.1 of section V of part G of the **rules** for the billing period immediately before this Code came into force, is deemed to be calculation of **constrained off amounts** under clause 13.194.

**17.186 Rights to constrained off information**

A request for information under rule 4.7 of section V of part G of the **rules** not resolved immediately before this Code came into force, is deemed to be a request for information under clause 13.200.

**17.187 Constrained on amounts**

Calculation of constrained on amounts under rule 5.4 of section V of part G of the **rules** for the **billing period** immediately before this Code came into force, is deemed to be calculation of **constrained on amounts** under clause 13.205.

**17.188 Payment of constrained on compensation**

- (1) For the purposes of clause 13.212(1) compensation for constrained on amounts determined under rules 5.3 and 5.4 of section V of part G of the **rules** before this Code came into force, is deemed to be compensation payable.
- (2) For the purposes of clause 13.212(2), a constrained on amount compensation calculated under rule 5.4 of section V of part G of the **rules** immediately before this Code came into force, is deemed to be a **constrained on compensation** amount payable.
- (3) The above entitlements are subject to clauses 13.212(3) to (8), as if the compensation were payable under clause 13.212, with any necessary modifications.

**17.189 Market administrator to publish pricing manager reports**

Daily reports provided under rule 7.1 of section V of part G of the **rules** that were in force immediately before this Code came into force relating to the calendar month immediately before this Code came into force, are deemed to be daily reports for the purposes of clause 13.213.

**17.190 Right to information concerning pricing manager's action**

- (1) A request for further information under rule 7.3 of section V of part G of the **rules** that had not been resolved immediately before this Code came into force, is deemed to be a request for information under clause 13.215.
- (2) Information specified in rules 3 to 7 of section VI of part G of the **rules** and not submitted immediately before this Code came into force, is deemed to be information specified in clauses 13.219 and 13.221 to 13.223, for the purposes of clause 13.218.



#### **17.191 Information that must be submitted**

The form specified by the Board for submission of information under rule 3 of section VI of part G of the **rules** immediately before this Code came into force, is deemed to be the form specified by the **Authority** under clause 13.219.

#### **17.192 Calculation of contract price**

Guidelines issued by the Board under rule 4 of section VI of part G of the **rules** and in force immediately before this Code came into force, are deemed to be guidelines issued by the **Authority** under clause 13.220.

#### **17.193 Information submitted**

Information submitted under rules 3, 7 and 8 of section VI of part G of the **rules** immediately before this Code came into force, is deemed to be information submitted under clauses 13.219, 13.223, and 13.224 respectively.

#### **17.194 Timeframes for submitting that information**

Information submitted in accordance with rule 9 of section VI of part G of the **rules** immediately before this Code came into force, is deemed to be information submitted under clause 13.225.

### *Transitional provisions relating to Part 14*

#### **17.195 Acceptable forms of security**

- (1) A cash deposit paid under rule 2.4.1 of part H of the **rules** before this Code came into force, is deemed to be a **cash deposit** paid under clause 14.5(a).
- (2) A security agreement provided and maintained under rule 2.4.1 of part H of the **rules** immediately before this Code came into force, is deemed to be a security agreement provided and maintained under clause 14.5(a).
- (3) An unconditional guarantee or letter of credit provided and maintained under rule 2.4.2 of part H of the **rules** immediately before this Code came into force, is deemed to be an unconditional guarantee or letter of credit provided and maintained under clause 14.5(b).
- (4) An unconditional third party guarantee provided and maintained under rule 2.4.3 of part H of the **rules** immediately before this Code came into force, is deemed to be an unconditional third party guarantee provided and maintained under clause 14.5(c).
- (5) A security bond provided and maintained under rule 2.4.4 of part H of the **rules** immediately before this Code came into force, is deemed to be a security bond provided and maintained under clause 14.5(d).
- (6) A hedge settlement agreement lodged under rule 2.4.5 of part H of the **rules** immediately before this Code came into force, is deemed to be a **hedge settlement agreement** lodged under clause 14.5(e).
- (7) If the terms of a security were approved by the Commission under rule 2.4 of part H of the **rules** immediately before this Code came into force, those terms are deemed to be approved by the **Authority** under clause 14.5.

#### **17.196 Cash deposits**

- (1) A cash deposit account established under rule 2.6.1 of part H of the **rules** immediately before this Code came into force, is deemed to be a **cash deposit account** established under clause 14.7(1).
- (2) An acknowledgment obtained under rule 2.6.3 of part H of the **rules** immediately before this Code came into force, is deemed to be an acknowledgment obtained under clause 14.7(3).
- (3) A cash deposit received under rule 2.6.4 of part H of the **rules** immediately before this Code came into force, is deemed to be a **cash deposit** received under clause 14.8, and must be paid accordingly.
- (4) Bank fees that were owed in relation to a cash deposit under rule 2.6.8 of part H of the **rules** immediately before this Code came into force, are deemed to be bank fees owed under clause 14.11.
- (5) A statement issued under rule 2.6.9 of part H of the **rules** immediately before this Code came into force, is deemed to be a statement issued under clause 14.12.

#### **17.197 Change in form of security**

A notice given under rule 2.7 of part H of the **rules** that was in force immediately before this Code came into force, is deemed to be a notice given under clause 14.13.

#### **17.198 Reductions and releases**

A notice given under rule 2.8 of part H of the **rules** that was in force immediately before this Code came into force, is deemed to be a notice given under clause 14.14.

#### **17.199 Hedge settlement agreements**

A notice given under rule 2.9 of part H of the **rules** that was in force immediately before this Code came into force, is deemed to be a notice given under clause 14.15.

#### **17.200 Release of security**

A notice given under rule 2.10 of part H of the **rules** that was in force immediately before this Code came into force, is deemed to be a notice given under clause 14.16.

#### **17.201 Level of security**

- (1) A determination made under rules 3.1.1 or 3.1.2 of part H of the **rules** that was in force immediately before this Code came into force, is deemed to be a determination made under clause 14.18(1) or (2), as the case may be.
- (2) A notice of a call given under rule 3.1.3 of part H of the **rules** that was in force immediately before this Code came into force, is deemed to be a notice of a **call** given under clause 14.18(3).
- (3) A determination made under rule 3.2 of part H of the **rules** that was in force immediately before this Code came into force, is deemed to be a determination made under clause 14.19.

#### **17.202 Information, monitoring and reporting**

- (1) Historical records or a business plan submitted under rule 4.1 of part H of the **rules** that were in force immediately before this Code came into force, are deemed to be historical records or a **business** plan, as the case may be, submitted under clause 14.23.
- (2) Information provided under rule 4.2 of part H of the **rules** before this Code came into force, is deemed to be information provided under clause 14.24.
- (3) Information provided under rule 4.3 of part H of the **rules** before this Code came into force, is deemed to be information provided under clause 14.25.
- (4) Information provided under rule 4.4 of part H of the **rules** before this Code came into force, is deemed to be information provided under clause 14.26.
- (5) If a person had consented to the disclosure of information provided by them under rule 4.5 of part H of the **rules** before this Code came into force, they are deemed to have consented to the disclosure of that information under clause 14.27.
- (6) A report provided under rule 4.6 of part H of the **rules** that was in force immediately before this Code came into force, is deemed to be a report provided under clause 14.28.

#### **17.203 Disputes**

A matter that was referred to the Rulings Panel under rule 5.1 of part H of the **rules** but which remain unresolved immediately before this Code came into force, is deemed to be a matter referred to the **Rulings Panel** under clause 14.29(1).

#### **17.204 Invoices to and payments by payers**

- (1) Reconciliation information received under rule 7.1 of part H of the **rules** for which no invoice had been issued immediately before this Code came into force, is deemed to be **reconciliation information** received under clause 14.36, and is deemed to have been received on the date on which the **reconciliation information** was received under that rule.
- (2) An invoice issued under rule 7.1 of part H of the **rules** that remained unpaid immediately before this Code came into force, is deemed to be an invoice issued under clause 14.36.
- (3) An invoice sent using one of the methods in rule 7.7 of part H of the **rules** before this Code came into force, is deemed to have been sent using that method under clause 14.41.

#### **17.205 Operating account**

- (1) An operating account established under rule 7.11 of part H of the **rules** immediately before this Code came into force, is deemed to be an **operating account** established under clause 14.43(1).
- (2) An acknowledgment obtained under rule 7.12 of part H of the **rules** immediately before this Code came into force, is deemed to be an acknowledgment obtained under clause 14.43(2).

#### **17.206 Payments to and from payees**

- (1) A pro forma invoice issued under rule 8.1 of part H of the **rules** immediately before this Code came into force, is deemed to be a pro forma invoice issued under clause 14.44.
- (2) Any interest that was owed under rules 8.7 or 8.8 of part H of the **rules** before this Code came into force, is deemed to be interest owed under clause 14.50 and continues to accrue accordingly.

#### **17.207 Defaults**

- (1) An event of default under rule 9.1 of part H of the **rules** that occurred before this Code came into force, is deemed to be an **event of default** under clause 14.55.
- (2) A matter referred to the Commission under rule 9.2 of part H of the **rules** and not resolved immediately before this Code came into force, that remains unresolved is deemed to be a matter referred to the **Authority** under clause 14.56.

#### **17.208 Disputed invoices**

A dispute notified under rule 10 of part H of the **rules** that was not resolved immediately before this Code came into force, is deemed to be a dispute notified under clause 14.64.

#### **17.209 Washups**

- (1) Corrected information received under rule 11.1 of part H of the **rules** before this Code came into force, is deemed to be corrected information received under clause 14.65.
- (2) An invoice issued under rule 11.7 of part H of the **rules** before this Code came into force, is deemed to be an invoice issued under clause 14.72.

#### **17.210 Reporting obligations**

- (1) A report made under rule 13.1 of part H of the **rules** that was not resolved immediately before this Code came into force, is deemed to be a report made under clause 14.74 and may be published accordingly.
- (2) A request made under rule 13.3 of part H of the **rules** immediately before this Code came into force, is deemed to be a request made under clause 14.76.

#### **17.210A [Revoked]**

Clause 17.210A: inserted, on 24 March 2015, by clause 28 of the Electricity Industry Participation (Settlement and Prudential Security) Code Amendment 2013.

Clause 17.210A: revoked, on 5 October 2017, by clause 582 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

#### **17.210B [Revoked]**

Clause 17.210B: inserted, on 24 March 2015, by clause 28 of the Electricity Industry Participation (Settlement and Prudential Security) Code Amendment 2013.

Clause 17.210B: revoked, on 5 October 2017, by clause 582 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

#### **17.210C [Revoked]**

Clause 17.210C: inserted, on 24 March 2015, by clause 28 of the Electricity Industry Participation (Settlement and

Prudential Security) Code Amendment 2013.

Clause 17.210C: revoked, on 5 October 2017, by clause 582 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

#### **17.210D [Revoked]**

Clause 17.210D: inserted, on 24 March 2015, by clause 28 of the Electricity Industry Participation (Settlement and Prudential Security) Code Amendment 2013.

Clause 17.210D: revoked, on 5 October 2017, by clause 582 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

#### **17.210E [Revoked]**

Clause 17.210E: inserted, on 24 March 2015, by clause 28 of the Electricity Industry Participation (Settlement and Prudential Security) Code Amendment 2013.

Clause 17.210E: revoked, on 5 October 2017, by clause 582 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

#### **17.210F [Revoked]**

Clause 17.210F: inserted, on 24 March 2015, by clause 28 of the Electricity Industry Participation (Settlement and Prudential Security) Code Amendment 2013.

Clause 17.210F: revoked, on 5 October 2017, by clause 582 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

#### **17.210G [Revoked]**

Clause 17.210G: inserted, on 24 March 2015, by clause 28 of the Electricity Industry Participation (Settlement and Prudential Security) Code Amendment 2013.

Clause 17.210G: revoked, on 5 October 2017, by clause 582 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

#### **17.210H [Revoked]**

Clause 17.210H: inserted, on 24 March 2015, by clause 28 of the Electricity Industry Participation (Settlement and Prudential Security) Code Amendment 2013.

Clause 17.210H: revoked, on 5 October 2017, by clause 582 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

#### **17.210I [Revoked]**

Clause 17.210I: inserted, on 24 March 2015, by clause 28 of the Electricity Industry Participation (Settlement and Prudential Security) Code Amendment 2013.

Clause 17.210I: revoked, on 5 October 2017, by clause 582 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

#### **17.210J [Revoked]**

Clause 17.210J: inserted, on 24 March 2015, by clause 28 of the Electricity Industry Participation (Settlement and Prudential Security) Code Amendment 2013.

Clause 17.210J: revoked, on 5 October 2017, by clause 582 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

#### **17.210K [Revoked]**

Clause 17.210K: inserted, on 24 March 2015, by clause 28 of the Electricity Industry Participation (Settlement and Prudential Security) Code Amendment 2013.

Clause 17.210K: revoked, on 5 October 2017, by clause 582 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### **17.210L [Revoked]**

Clause 17.210L: inserted, on 24 March 2015, by clause 28 of the Electricity Industry Participation (Settlement and Prudential Security) Code Amendment 2013.

Clause 17.210L(2) and (3): inserted, on 24 March 2015, by clause 27 of the Electricity Industry Participation Code Amendment (Settlement and Prudential Security) 2014.

Clause 17.210L: revoked, on 5 October 2017, by clause 582 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### **17.210M [Revoked]**

Clause 17.210M: inserted, on 24 March 2015, by clause 28 of the Electricity Industry Participation (Settlement and Prudential Security) Code Amendment 2013.

Clause 17.210M: revoked, on 5 October 2017, by clause 582 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### **17.210N [Revoked]**

Clause 17.210N: inserted, on 24 March 2015, by clause 28 of the Electricity Industry Participation (Settlement and Prudential Security) Code Amendment 2013.

Clause 17.210N: revoked, on 5 October 2017, by clause 582 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

### **17.210O [Revoked]**

Clause 17.210O: inserted, on 24 March 2015, by clause 28 of the Electricity Industry Participation (Settlement and Prudential Security) Code Amendment 2013.

Clause 17.210O: revoked, on 5 October 2017, by clause 582 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

## *Transitional provisions relating to Part 15*

### **17.211 Requirement to provide complete and accurate information**

For the purposes of clause 15.2, information provided by a participant under part J of the **rules** before this Code came into force, is deemed to be information provided by that **participant** under Part 15.

### **17.212 Provision of trading information at point of connection to network**

- (1) A notification given by a trader under rule 3.1 of part J of the **rules** that was in force immediately before this Code came into force, is deemed to be a notification given under clause 15.3(1).
- (2) Procedures or requirements specified by the reconciliation manager under rule 3.2 of part J of the **rules** that were in force immediately before this Code came into force, are deemed to be procedures or other requirements, as the case may be, specified by the **reconciliation manager** under clause 15.3(2).

### **17.213 Submission information to be delivered for reconciliation**

Submission information delivered or revised by a reconciliation participant under rule 4.1 of part J of the **rules** before this Code came into force, is deemed to be submission information delivered or revised, as the case may be, by that **reconciliation participant** under clause 15.4.

**17.214 Retailer and direct purchaser ICP days information**

A report delivered to the reconciliation manager under rule 4.2.1 of part J of the **rules** before this Code came into force, is deemed to be a report delivered under clause 15.6(1).

**17.215 Retailer electricity supplied information**

Information delivered by a retailer to the reconciliation manager under rule 4.2.2 of part J of the **rules** before this Code came into force, is deemed to be information delivered to the **reconciliation manager** under clause 15.7.

**17.216 Retailer and direct purchaser half-hourly metered ICPs monthly kWh information**

Information delivered by a retailer or direct purchaser to the reconciliation manager under rule 4.2.3 of part J of the **rules** before this Code came into force, is deemed to be information delivered to the **reconciliation manager** under clause 15.8.

**17.217 Grid owner volume information**

Information delivered by a grid owner to the reconciliation manager under rule 4.3.1 of part J of the **rules** before this Code came into force, is deemed to be information delivered to the **reconciliation manager** under clause 15.9.

**17.218 Local network and embedded network submission information**

Information provided by a participant to the reconciliation manager under rule 4.3.2 of part J of the **rules** before this Code came into force, is deemed to be information provided to the **reconciliation manager** under clause 15.10.

**17.219 Grid connected generator**

Information delivered by a generator to the reconciliation manager under rule 4.3.3 of part J of the **rules** before this Code came into force, is deemed to be information delivered to the **reconciliation manager** under clause 15.11.

**17.220 Accuracy of submitted information**

For the purposes of clause 15.12, information submitted by a participant under the **rules** before this Code came into force, is deemed to be information submitted by that **participant** in accordance with this Code.

**17.221 Notification by embedded generators**

A notification given by an embedded generator to the reconciliation manager under rule 4A of part J of the **rules** that was in force immediately before this Code came into force, is deemed to be a notification given under clause 15.13.

**17.222 Notification of changes to the grid**

- (1) A notification given by a grid owner to the reconciliation manager under rule 5 of part J

- of the **rules** that was in force immediately before this Code came into force, is deemed to be a notification given under clause 15.14(1).
- (2) Procedures or other requirements specified by the reconciliation manager under rule 5 of part J of the **rules** that were in force immediately before this Code came into force, are deemed to be procedures or other requirements, as the case may be, specified under clause 15.14(1).
  - (3) A copy of a notice given by the reconciliation manager to the clearing manager and the Board under rule 5 of part J of the **rules** before this Code came into force, is deemed to be given under clause 15.14(3).
  - (4) A notice given by a grid owner of an intended change to an existing point of connection to the grid or a new point of connection to the grid to be commissioned under rule 5 of part J of the **rules** that was in force immediately before this Code came into force, is deemed to be a notice given under clause 15.14(4).

**17.223 System operator notifies reconciliation manager of points of connection to the grid subject to outages or alternative supply**

A notification given by the system operator to the reconciliation manager under rule 6.1 of part J of the **rules** that was in force immediately before this Code came into force, is deemed to be a notification given under clause 15.15.

**17.224 Balancing area NSP grouping changes**

- (1) A determination made by the reconciliation manager under rule 6.2 of part J of the **rules** before this Code came into force, is deemed to be a determination made under clause 15.16.
- (2) A change effected by the reconciliation manager under rule 6.2 of part J of the **rules** that was in force immediately before this Code came into force, is deemed to be a change effected under clause 15.16.

**17.225 Submission information to be reviewed in the case of an outage constraint**

- (1) A review of submission information undertaken by the reconciliation manager in accordance with rule 6.3.1 of part J of the **rules** before this Code came into force, is deemed to be a review undertaken under clause 15.17(a).
- (2) Submission information reconciled under rule 6.3.2 of part J of the **rules** immediately before this Code came into force, is deemed to be **submission information** reconciled under clause 15.17(b).
- (3) A notification given by the reconciliation manager under rule 6.3.3 of part J of the **rules** that was in force immediately before this Code came into force, is deemed to be a notification given under clause 15.17(c).
- (4) A consultation or assessment carried out by the reconciliation manager in accordance with rule 6.3.4 of part J of the **rules** before this Code came into force, is deemed to be a consultation or assessment, as the case may be, carried out in accordance with clause 15.17(d).
- (5) A change to an alternative balancing area NSP grouping or update to information



carried out in accordance with rule 6.3.4 of part J of the **rules** before this Code came into force, is deemed to be a change or update, as the case may be, carried out in accordance with clause 15.17(d).

#### **17.226 Reconciliation manager may request additional information**

- (1) Notice given by the reconciliation manager under rule 7 of part J of the **rules** before this Code came into force, is deemed to be a notice given under clause 15.18.
- (2) Information provided by a reconciliation participant under rule 7 of part J of the **rules** before this Code came into force, is deemed to be information provided under clause 15.18.

#### **17.227 Providing information specific to reconciliation participants**

Information provided by the reconciliation manager under rule 10.1 of part J of the **rules** before this Code came into force, is deemed to be information provided under clause 15.21.

#### **17.228 Providing information to reconciliation participants**

- (1) Information provided by the reconciliation manager to a reconciliation participant under rule 10.2 of part J of the **rules** before this Code came into force, is deemed to be information provided under clause 15.22.
- (2) A time agreed between a reconciliation participant and the reconciliation manager or determined by the Board under rule 10.2 of part J of the **rules** before this Code came into force, is deemed to be a time agreed between the **reconciliation participant** and the **reconciliation manager** or determined by the **Authority**, as the case may be, under clause 15.22.
- (3) A request made by a reconciliation participant under rule 10.2.1 of part J of the **rules** that had not been responded to immediately before this Code came into force, is deemed to be a request made under clause 15.22(a).
- (4) For the purposes of clause 15.23, information provided by a participant under rule 10 of part J of the **rules** before this Code came into force, is deemed to be information provided by that **participant** in accordance with clauses 15.21 to 15.26.

#### **17.229 Reconciliation information checked**

- (1) Reconciliation information provided by the reconciliation manager under rule 10 of part J of the **rules** that had not been checked by the relevant reconciliation participant immediately before this Code came into force, is deemed to be **reconciliation information** provided under clauses 15.21 to 15.26.
- (2) A dispute commenced under rule 10.4A of part J of the **rules** that had not been resolved immediately before this Code came into force, is deemed to be a dispute commenced under clause 15.24(2).

#### **17.230 Reconciliation manager must assess information not supplied**

- (1) For the purposes of clause 15.25(1), information that is required to be provided under

part E of the **rules** before this Code came into force, is deemed to be information required to be provided under Part 11.

- (2) Information acquired or estimated by the reconciliation manager under rule 10.5 of part J of the **rules** before this Code came into force, is deemed to be information acquired or estimated, as the case may be, under clause 15.25(1).
- (3) A direction by the Board under rule 10.5A of part J of the **rules** given before this Code came into force, is deemed to be a direction given under clause 15.25(2).

#### **17.231 Reconciliation manager to correct information**

- (1) An issue referred to the Board under clause 10.7 of part J of the **rules** that had not been resolved immediately before this Code came into force, is deemed to be an issue referred to the **Authority** under clause 15.26(2).
- (2) A direction given by the Board to the reconciliation manager under rule 10.7 of part J of the **rules** immediately before this Code came into force, is deemed to be a direction given by the **Authority** under clause 15.26(2).
- (3) For the purposes of clause 15.26, information corrected by the reconciliation manager under rule 10.7 of part J of the **rules** immediately before this Code came into force, is deemed to be information corrected under clause 15.26.
- (4) Corrected information provided to the clearing manager and reconciliation participants under rule 10.9 of part J of the **rules** immediately before this Code came into force, is deemed to be information provided under clause 15.26(4).

#### **17.232 Transitional provisions concerning revision**

A list of incumbent retailers published by the **reconciliation manager** under rule 11.4.3.4 of part J of the **rules** that was in force immediately before this Code came into force, is deemed to be a list published under clause 15.28(3).

#### **17.233 Volume information disputes**

- (1) A dispute commenced by a reconciliation participant under rule 12.1 of part J of the **rules** that had not been resolved immediately before this Code came into force, is deemed to be a dispute commenced under clause 15.29(1).
- (2) A notification given by the reconciliation manager under rule 12.3 of part J of the **rules** that was in force immediately before this Code came into force, is deemed to be a notification given under clause 15.29(3).
- (3) A direction given by the Board under rule 12.4 of part J of the **rules** that was in force immediately before this Code came into force, is deemed to be a direction given by the **Authority** under clause 15.29(4).
- (4) A dispute referred to the Rulings Panel under rule 12.9 of part J of the **rules** that had not been resolved immediately before this Code came into force, is deemed to be a dispute referred to the **Rulings Panel** under clause 15.29(9).
- (5) A determination made by the Rulings Panel under rule 12.10 of part J of the **rules** before this Code came into force, is deemed to be a determination made by the **Rulings Panel** under clause 15.29(10).

- (6) Notice given by the Rulings Panel under rule 12.11 of part J of the **rules** before this Code came into force, is deemed to be notice given under clause 15.29(11).
- (7) A revised seasonal adjustment shape issued under rule 12.12 of part J of the **rules** before this Code came into force, is deemed to be a revised **seasonal adjustment shape** issued under clause 15.29(12).
- (8) An agreement by parties to a dispute to resolve the dispute made under rule 12 of part J of the **rules** that was in force immediately before this Code came into force, is deemed to be an agreement made under clause 15.29(12).
- (9) Corrected submission information provided by a reconciliation participant under rule 12.12 of part J of the **rules** before this Code came into force, is deemed to be corrected **submission information** provided under clause 15.29(12).
- (10) Corrected volume information provided to the clearing manager under rule 12.13 of part J of the **rules** before this Code came into force, is deemed to be corrected **volume information** provided under clause 15.29(13).

#### **17.234 Alleged breaches reported by the reconciliation manager**

A report provided by the reconciliation manager to the Board under rule 13.1 of part J of the **rules** before this Code came into force, is deemed to be a report provided to the **Authority** under clause 15.30.

#### **17.235 Right to information concerning reconciliation manager's actions**

Notice given by a reconciliation participant under rule 13.2 of part J of the **rules** that was in force immediately before this Code came into force, is deemed to be a notice given under clause 15.31(1).

#### **17.236 Reconciliation reports**

A report given by the reconciliation manager to the Board under rule 13.3 of part J of the **rules** before this Code came into force, is deemed to be a report given to the **Authority** under clause 15.32.

#### **17.237 The publication of reports**

Sections of a report published by the Board under rule 14 of part J of the **rules** that were in force immediately before this Code came into force, are deemed to be published under clause 15.33.

#### **17.238 Provision of information**

Timeframes notified by the Board or formats determined by the Board under rule 16 of part J of the **rules** that were in force immediately before this Code came into force, are deemed to be timeframes notified by or formats determined by the **Authority**, as the case may be, under clause 15.35.

#### **17.239 New Zealand daylight time adjustment techniques**

Techniques specified by the Board under rule 17 of part J of the **rules** that were in force

immediately before this Code came into force, are deemed to be techniques specified by the **Authority** under clause 15.36.

#### **17.240 Audit**

A requirement issued by the Board that a participant have an audit undertaken under rule 18 of part J of the **rules** that was in force immediately before this Code came into force, is deemed to be a requirement issued by the **Authority** under clause 15.37.

#### **17.241 Functions requiring certification**

Certification to carry out functions under the Code obtained and maintained by a reconciliation participant under rule 19 of part J of the **rules** that by that **reconciliation participant** was in force immediately before this Code came into force, is deemed to be certification obtained and maintained under clause 15.38.

#### **17.242 Participant must use participant identifiers**

- (1) For the purpose of clause 15.39, a participant identifier obtained by a participant under the **rules** before this Code came into force, is deemed to be the **participant identifier** for that **participant** under this Code.
- (2) An application made by a participant under rule 20.2 of part J of the **rules** before this Code came into force, is deemed to be an application made under clause 15.39(2).
- (3) A notification given by the Board under rule 20.3 of part J of the **rules** before this Code came into force, is deemed to be a notification given by the **Authority** under clause 15.39(3).

#### **17.243 Requirement for certification**

A reconciliation participant required to obtain certification in accordance with clause 1A of schedule J1 of the **rules** immediately before this Code came into force, is required to obtain certification in accordance with clause 2 of Schedule 15.1 of this Code, but must do so no later than the expiry of the remainder of the 3 calendar month period specified in clause 1A of schedule J1 of part J of the **rules** as at the date on which this Code came into force.

#### **17.244 Obtaining certification**

- (1) An application made by a reconciliation participant under clause 3.1 of schedule J1 of the **rules** before this Code came into force, is deemed to be an application made under clause 4(1) of Schedule 15.1.
- (2) A request by the Board for information under clause 3.1A of schedule J1 of part J of the **rules** made before this Code came into force, is deemed to be a request made by the **Authority** under clause 4(2) of schedule 15.1.
- (3) Information provided by a reconciliation participant under clause 3.1A of schedule J1 of part J of the **rules** before this Code came into force, is deemed to be information provided under clause 4(2) of Schedule 15.1.

#### 17.245 Granting certification

A quality certification deemed by the Board to be equivalent to AS/NZS ISO 9001:2000 or AS/NZS ISO 9001:2008 before this Code came into force, is deemed to be a quality certification deemed by the **Authority** to be equivalent to AS/NZS ISO 9001:2000 or AS/NZS ISO 9001:2008, as the case may be, under clause 5(1)(b)(iii) of Schedule 15.1.

#### 17.246 Lists of certified reconciliation participants and agents

A list of certified reconciliation participants and agents used by certified reconciliation participants published and updated by the Board in accordance with clause 3A of schedule J1 of part J of the **rules** that was in force immediately before this Code came into force, is deemed to be a list of certified reconciliation participants or agents used by certified reconciliation participants, as the case may be, under clause 6 of Schedule 15.1.

#### 17.247 Renewed certification

A certification renewed by the Board under clause 3B of schedule J1 of part J of the **rules** before this Code came into force, is deemed to be a certification renewed by the **Authority** under clause 7(2) of Schedule 15.1.

#### 17.248 Changes that affect certification

- (1) A notification and an audit report provided by a reconciliation participant to the Board under clause 3C.1 of schedule J1 of part J of the **rules** before this Code came into force, is deemed to be a notification or an audit report, as the case may be, provided to the **Authority** under clause 8(1) of Schedule 15.1.
- (2) Notice given by the Board under clause 3C.2 of schedule J1 of part J of the **rules** before this Code came into force, is deemed to be notice given by the **Authority** under clause 8(2) of Schedule 15.1.
- (3) A notice given by the Board to a reconciliation participant under rule 3C.3.2 of schedule J1 of part J of the **rules** before this Code came into force, is deemed to be a notice given by the **Authority** under clause 8(3)(b) of Schedule 15.1.

#### 17.249 Auditors

- (1) An auditor approved by the Board under clause 5.1A of schedule J1 of part J of the **rules** who had not had its approval withdrawn by the Board immediately before this Code came into force, is deemed to be an **auditor** approved by the **Authority** under clause 9(1) of Schedule 15.1.
- (2) An application by a person to be an auditor or for the renewal of an existing approval made under clause 5.1A of schedule J1 of part J of the **rules** that had not been processed by the Board immediately before this Code came into force, is deemed to be an application made under clause 9(4) of Schedule 15.1.
- (3) A request for clarification, further data, or information made by the Board under clause 5.1A.3 of schedule J1 of part J of the **rules** before this Code came into force, is deemed to be a request for clarification, further data, or information, as the case may be,

requested by the **Authority** under clause 9(4) of Schedule 15.1.

- (4) A list of auditors published by the Board under clause 5.1B of schedule J1 of part J of the **rules** that was in force immediately before this Code came into force, is deemed to be a list published by the **Authority** under clause 9(7) of Schedule 15.1.

#### **17.250 Audits**

- (1) The prescribed form for an audit report prescribed by the Board under clause 6.1 of schedule J1 of part J of the **rules** before this Code came into force, is deemed to be the **prescribed form** for an **audit** report prescribed by the **Authority** under clause 10 of Schedule 15.1.
- (2) An audit report provided by an auditor to a reconciliation participant under clause 6 of schedule J1 of part J of the **rules** before this Code came into force, is deemed to be an **audit** report provided under clause 10(a) of Schedule 15.1.
- (3) Comments received by an auditor from a reconciliation participant under clause 6.3 of schedule J1 of part J of the **rules** in respect of an audit report that had not been finalised immediately before this Code came into force, are deemed to be comments received under clause 10(d) of Schedule 15.1.
- (4) Any conditions specified in a final audit report provided under clause 6.5 of Schedule J1 of part J of the **rules** that were in force immediately before this Code came into force, are deemed to be conditions specified under clause 10(f) of Schedule 15.1.

#### **17.251 Audit reports**

- (1) A final audit report provided to the Board under clause 6A of schedule J1 of part J of the **rules** before this Code came into force, is deemed to be a final **audit** report provided to the **Authority** under clause 11(1) of Schedule 15.1.
- (2) A summary published by the Board under clause 6A.2 of schedule J1 of part J of the **rules** before this Code came into force, is deemed to be a summary published by the **Authority** under clause 11(2) of Schedule 15.1.
- (3) An agreement between a reconciliation participant and the Board made under clause 6A.3 of schedule J1 of part J of the **rules** that was in force immediately before this Code came into force, is deemed to be an agreement made under clause 11(3) of Schedule 15.1.

#### **17.252 Participant requested audits**

A request made by a participant under clause 8.1A of schedule J1 of part J of the **rules** before this Code came into force, is deemed to be a request made under clause 12(2) of Schedule 15.1.

#### **17.253 Scope of audits**

A requirement of the Board issued for the purposes of clause 8.2 of schedule J1 of part J of the **rules** that was in force immediately before this Code came into force, is deemed to be a requirement of the **Authority** issued under clause 13 of Schedule 15.1.

#### **17.254 Information requests**

A request by the Board or its auditor under clause 8.2A of schedule J1 of part J of the **rules** made before this Code came into force, is deemed to be a request made by the **Authority** or its auditor, as the case may be, under clause 14 of Schedule 15.1.

#### **17.255 Participants provide access and information**

Additional information that the Board or its auditor reasonably considers is necessary under clause 8.3 of schedule J1 of the **rules** and requested before this Code came into force, is deemed to be additional information that the **Authority** or its auditor, as the case may be, reasonably considers is necessary under clause 15 of Schedule 15.1.

#### **17.256 Production of audit report**

An audit report produced under clause 8.4 of schedule J1 of part J of the **rules** before this Code came into force, is deemed to be an **audit** report produced under clause 16 of Schedule 15.1.

#### **17.257 Determination**

- (1) A determination by the Board of an instance of non-compliance made under clause 8.5 of schedule J1 of part J of the **rules** that was in force immediately before this Code came into force, is deemed to be a determination made by the **Authority** under clause 17(1) of Schedule 15.1.
- (2) Details submitted by a participant under clause 8.5 of schedule J1 of part J of the **rules** before this Code came into force, are deemed to be details submitted under clause 17(2) of Schedule 15.1.

#### **17.258 Summary of audit report**

A summary of an audit report published by the Board under clause 8.6 of schedule J1 of part J of the **rules** before this Code came into force, is deemed to be a summary published by the **Authority** under clause 18 of Schedule 15.1.

#### **17.259 Meter interrogation for non half-hour metering**

- (1) A report given by a reconciliation participant under clause 5.4.1 of schedule J2 of part J of the **rules** before this Code came into force, is deemed to be a report given under clause 8(1) of Schedule 15.2.
- (2) A requirement that a reconciliation participant explain why a level was not achieved and describe steps taken issued under clause 5.4.2 of schedule J2 of part J of the **rules** that was in force immediately before this Code came into force, is deemed to be a requirement issued under clause 8(1) of Schedule 15.2.

#### **17.260 Non half-hour meter reading every 4 months**

- (1) A report given by a reconciliation participant to the market administrator under clause 5.5.1 of schedule J2 of part J of the **rules** before this Code came into force, is deemed to be a report given under clause 9(1) of Schedule 15.2.

- (2) A requirement issued by the market administrator that a reconciliation participant explain why a level was not achieved and describe the steps that are being taken to achieve a level issued under clause 5.5.2 of schedule J2 of part J of the **rules** that was in force immediately before this Code came into force, is deemed to be a requirement issued under clause 9(1)(b) of Schedule 15.2.

#### **17.261 Interrogation logs**

An interrogation log produced under clause 5.6 of schedule J2 of part J of the **rules** before this Code came into force, is deemed to be an **interrogation** log produced under clause 10 of Schedule 15.2.

#### **17.262 Meter interrogation for half-hour metering**

- (1) An estimate submitted to the reconciliation manager by a reconciliation participant under clause 6.5 of schedule J2 of part J of the **rules** before this Code came into force, is deemed to be an estimate submitted under clause 15(1) of Schedule 15.2.
- (2) A percentage specified by the Board under clause 6.5 of schedule J2 of part J of the **rules** that was in force immediately before this Code came into force, is deemed to be a percentage specified by the **Authority** under clause 15(2) of Schedule 15.2.

#### **17.263 Audit trails**

Information provided to and received from the registry, provided to and received from the **reconciliation manager**, or provided to and received from other reconciliation participants and their agents under clause 11.1 of schedule J2 of part J of the **rules** immediately before this Code came into force, is deemed to be information provided to and received from the **registry**, provided to and received from the **reconciliation manager**, or provided and received from other **reconciliation participants** and their agents, as the case may be, under clause 21(2).

#### **17.264 Correction of meter readings**

A journal generated and archived by a reconciliation participant under clause 11.4.2 of schedule J2 of part J of the **rules** before this Code came into force, is deemed to be a journal generated and archived under clause 22(2) of Schedule 15.2.

#### **17.265 Creation of submission information**

- (1) The time period covered by kWh<sub>p</sub> published by the reconciliation manager under clause 2.2.1.1 of schedule J3 of part J of the **rules** before this Code came into force, is deemed to be published by the **reconciliation manager** under clause 4(a) of Schedule 15.3.
- (2) A percentage specified and published by the Board under clause 2.2.3 of schedule J3 of part J of the **rules** that was in force immediately before this Code came into force, is deemed to be a percentage specified and published, as the case may be, by the **Authority** under clause 6(3) of Schedule 15.3.



#### **17.266 Provision of submission information to reconciliation manager**

Submission information provided by a reconciliation participant to the reconciliation manager under clause 3 of schedule J3 of part J of the **rules** before this Code came into force, is deemed to be **submission information** provided under clause 8 of Schedule 15.3.

#### **17.267 Reporting requirements**

- (1) A report provided by a reconciliation participant to the reconciliation manager under clause 4 of schedule J3 of part J of the **rules** before this Code came into force, is deemed to be a report provided under clause 10(1) of Schedule 15.3.
- (2) A report provided by the reconciliation manager to the Board under clause 4 of schedule J3 of part J of the **rules** before this Code came into force, is deemed to be a report provided to the **Authority** under clause 10(2) of Schedule 15.3.
- (3) Information published by the Board under clause 4 of schedule J3 of part J of the **rules** immediately before this Code came into force, is deemed to be information published by the **Authority** under clause 10(2) of Schedule 15.3.

#### **17.268 Distributed unmetered load database**

A database maintained by a retailer in accordance with clause 5 of schedule J3 of part J of the **rules** before this Code came into force, is deemed to be a database maintained by that **retailer** under clause 11 of Schedule 15.3.

#### **17.269 Calculation by difference for embedded networks**

A notice given by a trader to the reconciliation manager designating an ICP under clause 3 of schedule J4 of part J of the **rules** that had not been revoked immediately before this Code came into force, is deemed to be a notice given under clause 3 of Schedule 15.4.

#### **17.270 Calculation by difference for local networks**

- (1) An application made by a trader to the Board under clause 3A of schedule J4 of part J of the **rules** before this Code came into force, is deemed to be an application made under clause 4(1) of Schedule 15.4.
- (2) A designation granted by the Board under clause 3A of schedule J4 of part J of the **rules** that had not been revoked by the Board immediately before this Code came into force, is deemed to be a designation granted by the **Authority** under clause 4 of Schedule 15.4.

#### **17.271 ICP days information**

The default values for profiles and loss category codes determined by the Board under clause 4.2.2 of schedule J4 of part J of the **rules** that were in force immediately before this Code came into force, are deemed to be default values for **profiles** and **loss category** codes, as the case may be, determined by the **Authority** under clause 7(5) of Schedule 15.4.

#### **17.272 Calculation of residual non half-hour profile shape**

A residual profile shape for a balancing area calculated by the reconciliation manager under clause 5 of schedule J4 of part J of the **rules** before this Code came into force, is deemed to be a residual **profile** shape for a **balancing area** calculated by the **reconciliation manager** under clause 9 of Schedule 15.4.

#### **17.273 Convert non half-hour quantities using profiles**

- (1) A notification given by a profile owner to the reconciliation manager under clause 6.1.2 of schedule J4 of part J of the **rules** that was in force immediately before this Code came into force, is deemed to be a notification given under clause 10(b) of Schedule 15.4.
- (2) A authorisation given by a profile owner to a reconciliation participant under clause 6.1.3 of part J of the **rules** that was in force immediately before this Code came into force, is deemed to be an authorisation given under clause 10(c) of Schedule 15.4.

#### **17.274 Invalid submission information**

Default values specified by the Board under clause 6.5.2 of schedule J4 of part J of the **rules** that were in force immediately before this Code came into force, are deemed to be default values specified by the **Authority** under clause 14(b) of Schedule 15.4.

#### **17.275 Loss factors**

A direction given by the Board under clause 7 of schedule J4 of part J of the **rules** that was current immediately before this Code came into force, is deemed to be a direction given by the **Authority** under clause 15(1) of Schedule 15.4.

#### **17.276 Scorecard rating**

- (1) A scorecard rating given to a retailer by the reconciliation manager under clause 9 of schedule J4 of part J of the **rules** that was in force immediately before this Code came into force, is deemed to be the **scorecard rating** of the **retailer** under clause 17 of Schedule 15.4.
- (2) Information about the quantity of electricity supplied to the reconciliation manager under clause 9 of schedule J4 of part J of the **rules** before this Code came into force, is deemed to be information provided under clause 17(2) of Schedule 15.4.
- (3) An unusual circumstance approved by the Board under clause 9.1 of schedule J4 of part J of the **rules** that was in force immediately before this Code came into force, is deemed to be an unusual circumstance approved by the **Authority** under clause 17(3) of Schedule 15.4.

#### **17.277 Calculation of scorecard rating**

- (1) A scorecard rating for a retailer that was calculated, published, or applied under clause 9.2 of schedule J4 of part J of the **rules** before this Code came into force, is deemed to be a **scorecard rating** calculated, **published**, or applied, as the case may be,

under clause 18 of Schedule 15.4.

- (2) A value specified by the Board under clause 9.2.2 of schedule J4 of part J of the **rules** that was in force immediately before this Code came into force, is deemed to be a value specified by the **Authority** under clause 18(1)(b) of Schedule 15.4.

#### **17.278 Application of scorecard rating**

A scorecard rating notified by the Board under clause 9.3 of schedule J4 of part J of the **rules** that was in force immediately before this Code came into force, is deemed to be a **scorecard rating** notified by the **Authority** under clause 18(4) of Schedule 15.4.

#### **17.279 Reconciliation manager reporting requirements**

- (1) Information provided by the reconciliation manager under clause 14 of schedule J4 of part J of the **rules** before this Code came into force, is deemed to be information provided by the **reconciliation manager** under clauses 24 to 27, as the case may be, of Schedule 15.4.
- (2) A percentage determined by the Board under clause 14.1.6 of schedule J4 of part J of the **rules** that was in force immediately before this Code came into force, is deemed to be a percentage determined by the **Authority** under clause 25(f) of Schedule 15.4.

#### **17.280 Provision of reconciliation information**

- (1) Information provided by the reconciliation manager under clause 15 of schedule J4 of part J of the **rules** before this Code came into force, is deemed to be information provided under clause 28 of Schedule 15.4.
- (2) A format or information requirement determined by the Board under clause 15 of schedule J4 of part J of the **rules** that was in force before this Code came into force, is deemed to be a format or information requirement, as the case may be, determined by the **Authority** under clause 28 of Schedule 15.4.

#### **17.281 Departure from requirements for profile administration**

An approval given by the market administrator under clause 2 of schedule J5 of part J of the **rules** that was in force immediately before this Code came into force, is deemed to be an approval given under clause 2 of Schedule 15.5.

#### **17.282 Profile population list**

A profile population list kept by a reconciliation participant under clause 3.3 of schedule J5 of part J of the **rules** immediately before this Code came into force, is deemed to be a **profile population** list kept under clause 5 under Schedule 15.5.

#### **17.283 Profiles approved for use**

Details kept by a profile owner under clause 3.4 of schedule J5 of part J of the **rules** immediately before this Code came into force, are deemed to be details kept under clause 6 of Schedule 15.5.

#### 17.284 Change of profile

- (1) An application made under clause 3A of schedule J5 of part J of the **rules** that had not been approved or rejected immediately before this Code came into force, is deemed to be an application made under clause 11 of Schedule 15.5.
- (2) Advice given by the market administrator under clause 3A.4 of schedule J5 of part J of the **rules** that was in force immediately before this Code came into force, is deemed to be advice given under clause 11(4) of Schedule 15.5.

#### 17.285 Profile codes

- (1) A profile code determined by the market administrator under clause 5 of schedule J5 of part J of the **rules** that was in force immediately before this Code came into force, is deemed to be a **profile code** determined under clause 13 of Schedule 15.5.
- (2) Information published by the market administrator under clause 5.2 of schedule J5 of part J of the **rules** that was in force immediately before this Code came into force, is deemed to be information **published** under clause 13(5) of Schedule 15.5.

#### 17.286 New NSP derived profiles

- (1) An application made under clause 7.1 of schedule J5 of part J of the **rules** that had not been approved, withdrawn, or rejected immediately before this Code came into force, is deemed to be an application made under clause 19 of Schedule 15.5.
- (2) Advice given by the market administrator to a profile applicant under clause 7.1 of schedule J5 of part J of the **rules** that was in force immediately before this Code came into force, is deemed to be advice given under clause 19(1) of Schedule 15.5.
- (3) A legal entity nominated by a profile applicant under clause 7.3 of schedule J5 of part J of the **rules** immediately before this Code came into force, is deemed to be a legal entity nominated under clause 21 of Schedule 15.5.
- (4) An explanation provided by the market administrator under clause 7.5 of schedule J5 of part J of the **rules** that was in force immediately before this Code came into force, is deemed to be an explanation provided under clause 23 of Schedule 15.5.
- (5) A profile approved by the market administrator under clause 7 of schedule J5 of part J of the **rules** that was in force immediately before this Code came into force, is deemed to be a **profile** approved by the **market administrator** under clauses 19 to 24, as the case may be, of Schedule 15.5.
- (6) An approval given by a profile owner to a reconciliation participant under clause 7.6 of schedule J5 of part J of the **rules** that was in force immediately before this Code came into force, is deemed to be an approval given under clause 24(2) of Schedule 15.5.

#### 17.287 New statistically sampled/engineered profiles

- (1) An application to introduce a new profile submitted under clause 8.2 of schedule J5 of part J of the **rules** on which a decision had not been made immediately before this Code came into force, is deemed to be an application submitted under clause 26 of Schedule 15.5.
- (2) Advice given by the market administrator under clause 8.2 of schedule J5 of part J of

- the **rules** that was in force immediately before this Code came into force, is deemed to be advice given under clause 26(1) of Schedule 15.5.
- (3) A format for the supply of analytical information required by the market administrator under clause 8.2A of schedule J5 of part J of the **rules** that was in force immediately before this Code came into force, is deemed to be a format required under clause 26(2) of Schedule 15.5.
  - (4) A legal entity nominated to be the profile owner under clause 8.5 of schedule J5 of part J of the **rules** immediately before this Code came into force, is deemed to be a legal entity nominated under clause 29 of Schedule 15.5.
  - (5) Advice given by the market administrator to participants under clause 8.6 of schedule J5 of part J of the **rules** immediately before this Code came into force, is deemed to be advice given under clause 30 of Schedule 15.5.
  - (6) An explanation provided by the market administrator under clause 8.7 of schedule J5 of part J of the **rules** immediately before this Code came into force, is deemed to be an explanation provided under clause 31 of Schedule 15.5.
  - (7) A date decided by the market administrator under clause 8.8 of schedule J5 of part J of the **rules** immediately before this Code came into force, is deemed to be a date decided under clause 32(1) of Schedule 15.5.
  - (8) An approval given by a profile owner to a reconciliation participant under clause 8.8 of schedule J5 of part J of the **rules** that was in force immediately before this Code came into force, is deemed to be an approval given under clause 32(2) of Schedule 15.5.
  - (9) A profile population list maintained by a profile owner under clause 8.9 of schedule J5 of part J of the **rules** immediately before this Code came into force, is deemed to be a **profile population** list maintained under clause 33 of Schedule 15.5.
  - (10) A notification given by the market administrator to a profile owner under clause 8.9.2 of schedule J5 of part J of the **rules** that was in force immediately before this Code came into force, is deemed to be a notification given under clause 33(3) of Schedule 15.5.
  - (11) A list of ICP identifiers submitted under clause 8.9.2 of schedule J5 of part J of the **rules** that was in force immediately before this Code came into force, is deemed to be a list of **ICP identifiers** submitted under clause 33(4) of Schedule 15.5.
  - (12) A determination of appropriate replacement ICP identifiers issued by the market administrator under clause 8.9.2 of schedule J5 of part J of the **rules** that was in force immediately before this Code came into force, is deemed to be a determination under clause 33(4).

#### **17.288 MARIA profiles**

A profile deemed, in accordance with rule 4 of section III of part I of the **rules** to be a profile determined under rules 6.1 and 7.2 of code of practice G2 of schedule G8 of part G of the **rules**, is deemed to be a **profile** approved in accordance with clauses 19 to 34, as the case may be, of Schedule 15.5.

#### **17.289 Audits**

- (1) A request for an audit made under clause 9 of schedule J5 of part J of the **rules** before

this Code came into force, is deemed to be a request made under clause 35 of Schedule 15.5.

- (2) An audit conducted under clause 9.2 of schedule J5 of part J of the **rules** before this Code came into force, is deemed to be an **audit** conducted under clause 35(2) of Schedule 15.5.
- (3) A selection process maintained by the market administrator and monitored by the Board under clause 9.2 of schedule J5 of part J of the **rules** that was in force immediately before this Code came into force, is deemed to be a selection process maintained by the **market administrator** and monitored by the **Authority** under clause 35(2) of Schedule 15.5.

#### **17.290 Removal of profiles**

- (1) A breach reported to the Board under clause 11.1 of schedule J5 of part J of the **rules** that was not resolved immediately before this Code came into force, is deemed to be a breach reported to the **Authority** under clause 37(2) of Schedule 15.1.
- (2) A request that a profile be removed made under clause 11.2 of schedule J5 of part J of the **rules** immediately before this Code came into force, is deemed to be a request made under clause 37(3) and (4) of Schedule 15.5.

#### **17.291 Reviews**

A review undertaken under clause 5 of Appendix 3 of schedule J5 of part J of the **rules** before this Code came into force, is deemed to be a review undertaken under clause 5 of Appendix 2 of Schedule 15.5.

Transitional provisions relating to Part 16 cross-heading: revoked on 16 December 2013, by clause 11(1) of the Electricity Industry Participation (Revocation of Part 16) Code Amendment 2013.

#### **17.292 [Revoked]**

Clause 17.292: revoked on 16 December 2013, by clause 11(2) of the Electricity Industry Participation (Revocation of Part 16) Code Amendment 2013.

#### **17.293 [Revoked]**

Clause 17.293: revoked on 16 December 2013, by clause 11(3) of the Electricity Industry Participation (Revocation of Part 16) Code Amendment 2013.

#### **17.294 [Revoked]**

Clause 17.294: revoked on 16 December 2013, by clause 11(2) of the Electricity Industry Participation (Revocation of Part 16) Code Amendment 2013.

#### **17.295 [Revoked]**

Clause 17.295: revoked on 16 December 2013, by clause 11(2) of the Electricity Industry Participation (Revocation of Part 16) Code Amendment 2013.

#### *Transitional provisions relating to Part 16A*

Cross Heading: inserted on 1 June 2017, by clause 37 of the Electricity Industry Participation Code Amendment (Requirements and Processes for Audits) 2016.

### 17.295A Metering equipment provider audits

- (1) If, on the date that the Electricity Industry Participation Code Amendment (Requirements and Processes for Audits) 2016 comes into force, the **Authority** has specified a date under clause 1(1)(b) of Schedule 10.5 by which a **metering equipment provider** must ensure that an **audit** is carried out, the **metering equipment provider** must ensure that an **audit** is completed in accordance with Part 16A by the later of—
  - (a) the date that the **Authority** has specified; or
  - (b) the date that is 1 month after the date that the Electricity Industry Participation Code Amendment (Requirements and Processes for Audits) 2016 comes into force.
- (2) If, on the date that the Electricity Industry Participation Code Amendment (Requirements and Processes for Audits) 2016 comes into force, the **Authority** has not specified a date under clause 1(1)(b) of Schedule 10.5 by which a **metering equipment provider** must ensure that an **audit** is carried out,—
  - (a) the **Authority** must, no later than 1 month after the date that the Electricity Industry Participation Code Amendment (Requirements and Processes for Audits) 2016 comes into force, specify a date by which the **metering equipment provider** must ensure that an **audit** is carried out in accordance with Part 16A; and
  - (b) the **metering equipment provider** must comply with that requirement.
- (3) Clause 16A.17 applies to a **metering equipment provider** to which subclauses (1) or (2) apply as if the **audit** completed under those subclauses were the initial **audit** required under clause 16A.17(a).

Clause 17.295A: inserted on 1 June 2017, by clause 37 of the Electricity Industry Participation Code Amendment (Requirements and Processes for Audits) 2016.

### 17.295B ATH audits

- (1) If, on the date that the Electricity Industry Participation Code Amendment (Requirements and Processes for Audits) 2016 comes into force, the **Authority** has specified a date under clause 1(4)(c) of Schedule 10.3 by which an **ATH** must ensure that an **audit** is carried out, the **ATH** must ensure that an **audit** is completed in accordance with Part 16A by the later of—
  - (a) the date that the **Authority** has specified; or
  - (b) the date that is 1 month after the date that the Electricity Industry Participation Code Amendment (Requirements and Processes for Audits) 2016 comes into force.
- (2) If, on the date that the Electricity Industry Participation Code Amendment (Requirements and Processes for Audits) 2016 comes into force, the **Authority** has not specified a date under clause 1(4)(c) of Schedule 10.3 by which an **ATH** must ensure that an **audit** is carried out,—
  - (a) the **Authority** must, no later than 1 month after the date that the Electricity Industry Participation Code Amendment (Requirements and Processes for Audits) 2016 comes into force, specify a date by which the **ATH** must ensure that an **audit** is carried out in accordance with Part 16A; and
  - (b) the **ATH** must comply with that requirement.
- (3) Clause 16A.19 applies to an **ATH** to which subclauses (1) or (2) apply as if the **audit** completed under those subclauses were the initial **audit** required under clause 16A.19(a).

Clause 17.295B: inserted on 1 June 2017, by clause 37 of the Electricity Industry Participation Code Amendment (Requirements and Processes for Audits) 2016.

#### 17.295C Distributor audits

- (1) If, immediately before the Electricity Industry Participation Code Amendment (Requirements and Processes for Audits) 2016 comes into force, a **distributor** was required to arrange for an **audit** to be completed by a date determined in accordance with clause 11.10(1)(b), the **distributor** must ensure that an **audit** is completed in accordance with Part 16A by the later of—
    - (a) the date determined in accordance with clause 11.10(1)(b); or
    - (b) the date that is 1 month after the date that the Electricity Industry Participation Code Amendment (Requirements and Processes for Audits) 2016 comes into force.
  - (2) Clause 16A.22 applies to a **distributor** to which subclause (1) applies as if the **audit** completed under that subclause were the initial **audit** required under clause 16A.22(a).
- Clause 17.295C: inserted on 1 June 2017, by clause 37 of the Electricity Industry Participation Code Amendment (Requirements and Processes for Audits) 2016.

#### 17.295D Reconciliation participant audits

- (1) If, immediately before the Electricity Industry Participation Code Amendment (Requirements and Processes for Audits) 2016 comes into force, a **reconciliation participant** was required to provide a final **audit** report to the **Authority** by a date determined in accordance with clause 11(1) of Schedule 15.1, the **reconciliation participant** must ensure that an **audit** is completed in accordance with Part 16A by the later of—
    - (a) the date determined in accordance with clause 11(1) of Schedule 15.1; or
    - (b) the date that is 1 month after the date that the Electricity Industry Participation Code Amendment (Requirements and Processes for Audits) 2016 comes into force.
  - (2) Clause 16A.24 applies to a **reconciliation participant** to which subclause (1) applies as if the **audit** completed under that subclause were the initial **audit** required under clause 16A.24(a).
- Clause 17.295D: inserted on 1 June 2017, by clause 37 of the Electricity Industry Participation Code Amendment (Requirements and Processes for Audits) 2016.

#### 17.295E Dispatchable load purchaser audits

- (1) If, immediately before the Electricity Industry Participation Code Amendment (Requirements and Processes for Audits) 2016 comes into force, a **dispatchable load purchaser** was required to provide a final **audit** report to the **Authority** by a date determined in accordance with clause 11(1) of Schedule 15.1, the **dispatchable load purchaser** must ensure that an **audit** is completed in accordance with Part 16A by the later of—
  - (a) the date determined in accordance with clause 11(1) of Schedule 15.1; or
  - (b) the date that is 1 month after the date that the Electricity Industry Participation Code Amendment (Requirements and Processes for Audits) 2016 comes into force.
- (2) Clause 16A.25 applies to a **dispatchable load purchaser** to which subclause (1) applies as if the **audit** completed under that subclause were the initial **audit** required under clause 16A.25(a).



Clause 17.295E: inserted on 1 June 2017, by clause 37 of the Electricity Industry Participation Code Amendment (Requirements and Processes for Audits) 2016.

#### **17.295F Distributed unmetered load audits**

- (1) A retailer that is responsible for **distributed unmetered load** on the date that the Electricity Industry Participation Code Amendment (Requirements and Processes for Audits) 2016 comes into force must ensure that an **audit** is completed in accordance with Part 16A no later than 12 months after that date.
- (2) Clause 16A.26(1) applies to a **retailer** to which subclause (1) applies as if the **audit** completed under that subclause were the initial **audit** required under clause 16A.26(1)(a).

Clause 17.295F: inserted on 1 June 2017, by clause 37 of the Electricity Industry Participation Code Amendment (Requirements and Processes for Audits) 2016.

Clause 17.295F(1): amended, on 5 October 2017, by clause 583 of the Electricity Industry Participation Code Amendment (Code Review Programme) 2017.

#### *Transitional provisions relating to exemptions*

#### **17.296 Exemptions**

- (1) An exemption in force under regulations 194 to 197 of the Electricity Governance Regulations 2003 immediately before this Code came into force, in relation to a rule, continues in force and is deemed to be an exemption from the obligation to comply with the corresponding provision of this Code and may be amended and revoked accordingly.
- (2) A proposed exemption being considered by the Commission under regulation 194 of the Electricity Governance Regulations 2003 immediately before this Code came into force must be treated by the **Authority** as a proposed exemption under section 11 of the **Act**.
- (3) An application for a variation or revocation of an exemption under regulation 196 of the Electricity Governance Regulations 2003 that was in force immediately before this Code came into force must be dealt with by the **Authority** under section 11 of the **Act**.